

This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`



TAYLOR'S PRINCIPLES AND PRACTICE

OF

MEDICAL JURISPRUDENCE

EDITED BY

THOMAS STEVENSON, M.D.

ALSO BY DR. A. S. TAYLOR, F.R.S.

A MANUAL OF MEDICAL JURISPRUDENCE. Ninth Edition, with 55 Engravings. Crown 8vo, 14s.

ON POISONS IN RELATION TO MEDICAL JURISPRUDENCE AND MEDICINE. Third Edition, with 104 Engravings. Crown 8vo, 16s.

THE

PRINCIPLES AND PRACTICE

OF

MEDICAL JURISPRUDENCE

BY THE LATE

ALFRED SWAINE TAYLOR, M.D., F.R.S.

FELLOW OF THE ROYAL COLLEGE OF PHYSICIANS OF LONDON

THIRD EDITION

EDITED BY

THOMAS STEVENSON, M.D. LOND.

FELLOW OF THE ROYAL COLLEGE OF PHYSICIANS OF LONDON, LECTURER ON MEDICAL JURISPRUDENCE AND ON CHEMISTRY AT GUY'S HOSPITAL, OFFICIAL ANALYST TO THE HOME OFFICE

VOL. I.



LONDON

J. & A. CHURCHILL

NEW BURLINGTON STREET

1883

151 a 13


BODLEIAN LIBRARY
1 JUN 83
OXFORD.

EDITOR'S PREFACE.

THE task of preparing for the press a Third Edition of "THE PRINCIPLES AND PRACTICE OF MEDICAL JURISPRUDENCE" has been with me a labour of love. For fourteen years I was the colleague of the late Dr. A. S. Taylor, at Guy's Hospital; and as such I had ample opportunities of observing his enormous grasp of all matters connected with the subject of which these volumes treat.

For the revision of the present edition I alone am responsible, though I gratefully acknowledge the valuable assistance afforded me by a few of my professional friends. A superficial glance might perhaps lead the reader to suppose that the present is a mere reproduction, with a few additions, of the second edition. A more careful examination will show, however, that this is by no means the case; for, whilst I have not felt it right to depart from the method of treatment adopted by the author, I have endeavoured to introduce a large mass of new matter, without increasing the bulk of the volumes. This has been done by carefully condensing the sometimes diffuse language in which cases were described, without, I trust, marring the clearness of the author's diction. It will be found that the present, though scarcely so bulky as the second edition, contains a large mass of new matter.

The chapters on POISONING have been in some parts entirely rewritten. This has been necessitated by the recent advances made in this department of forensic medicine; and many illustrative cases have been added. I may mention the case of *Reg.* v. *Lamson*, as an example.

In many other departments also new and illustrative cases have been added, without burthening the text. I may refer to the recent

trial of the brothers *Peltzer* for the murder of *M. Bernays*, as an example. Indeed, I believe that the work will be found to be still worthy of its place as the leading British work on Medical Jurisprudence.

In one respect I have thought it right to tone down, and curtail materially, Dr. Taylor's language. I refer to that portion of the work dealing with the relations of medical witnesses to the bar. However truthfully the author's lively descriptions may have represented scenes in Court between witnesses and barristers, as they appeared to his mind, I felt that they were no longer applicable at the present day. It is rare indeed, nowadays, that a medical witness, when honestly endeavouring to state the truth, receives anything but courteous treatment at the hands of counsel.

T. S.

SANDHURST LODGE, GRESHAM ROAD, LONDON, S.W.,
March, 1883.

AUTHOR'S PREFACE TO THE SECOND EDITION.

In preparing this work for a Second Edition, it has been found necessary to divide it into two volumes. Every page has undergone revision, and such alterations and additions have been made as the progress of time had rendered necessary. A slight change has been made in the arrangement of the subjects, and this has been accompanied by an increase in the number of the chapters from eighty-seven to one hundred. Some cases of old date have been omitted, and replaced by others of more recent occurrence and of more immediate interest.

The subject of MEDICAL EVIDENCE has been enlarged, and incorporated in two chapters with the text of the work. In the section on POISONING, in addition to recent cases and improved processes of analysis, notices of several new Poisons have been introduced. In the section on WOUNDS and PERSONAL INJURIES, many new cases of medico-legal importance will be found, and there have been considerable additions to the chapters on Wounds of the Throat and Chest, on Blood-stains, and the new methods of research proposed for the detection of blood, including Spectral analysis and the Guaiacum process. The subject of Cicatrices and other marks indicative of personal identity has acquired great medico-legal interest in reference to the *Tichborne Case*. The evidence derivable from these marks will be found in the chapter appropriated to this subject; but as the case is still pending, it is impossible to give a summary of the medical evidence or to make any comments upon it. Additions of facts and new cases have been made to the chapters on death from ASPHYXIA, on death from STARVATION, including the case of the *Welsh Fasting Girl*, also to the chapters on CRIMINAL ABORTION, INFANTICIDE, INSANITY, and LIFE INSURANCE. From the large number of medico-legal cases published yearly in British and

foreign journals, it has been found impossible to refer to more than a selection of them, and to condense the details as much as possible. In spite of the increased dimensions of the work and its publication in two volumes, it has been considered advisable to confine it within certain limits, and to insert notices of those cases only which appeared to have some immediate and practical interest for medical men and lawyers. When it has been found impossible for want of space to quote a case fully, numerous references have been inserted, showing where additional information may be obtained. Some new engravings from photographs and original drawings have been introduced into these volumes.

I have in conclusion to express my obligations to many known as well as unknown correspondents in the professions of Law and Medicine, for the reports of numerous cases not before published, which I have been able to introduce into this edition. I have also to thank others for their friendly criticism on some parts of the first edition. It will be seen that I have taken advantage of their suggestions.

A. S. T.

15, St. James's Terrace, Regent's Park,
August, 1873.

CONTENTS

OF

THE FIRST VOLUME.

MEDICAL EVIDENCE.

CHAPTER 1.

The practice of Medical Jurisprudence—Medical and medico-legal duties contrasted—Medical reports—Coroners' inquests—Concealed murders—Inspections of the dead—Trial at the assizes—Subpœnas—Duties and privileges of medical witnesses . . . . . PAGES 1—19

CHAPTER 2.

Compulsory attendance in Court—License of counsel—Examination in chief—Cross-examination and Re-examination—Quotations from books—Presence of medical witnesses in Court—Rules for the delivery of medical evidence—Technical terms—Medical experts—Medical counsel—Conflicting medical testimony—Fees . . . . . PAGES 19—41

QUESTIONS CONNECTED WITH THE DEAD BODY.

CHAPTER 3.

Questions connected with the dead body—Signs of death—Cessation of respiration and circulation—Apparent death—Trance—Coldness of the body—Post-mortem heat—Rigor mortis—Cadaveric rigidity—Circumstances which influence its commencement and duration—Other indications of death . . . . . PAGES 42—63

CHAPTER 4.

Cadaveric spasm—Evidence of murder, suicide, or accident furnished by the position of a dead body—Weapons found in the hands—Muscular irritability—Tests of its presence—Post-mortem contractility—Alleged premature interments—Proofs of the reality of death—Death-trance—Apparent death in the drowned and in new-born children . . . . . PAGES 63—81

CHAPTER 5.

Inference of the time of death from the state of the body before putrefaction—Priority of death—Presumptions of suicide or murder—Of survivorship—Stages of change after death—Cadaveric lividity—Sugillation—Ecchymosis . . . PAGES 81—91

CHAPTER 6.

Putrefaction—Its nature and progress—Production of gases—Post-mortem hæmorrhage—Pressure on the viscera—Nature of the gases of putrefaction—Changes in the colour of the skin and other organs—Putrefaction in air—Conditions for the process—Circumstances which modify it—Influence of disease and certain poisons—Putrefaction in bodies buried in graves—Production of adipocere—Its chemical nature . . . . . PAGES 91—108

CHAPTER 7.

Inference of the period of death in a body after putrefaction—Instances of rapid decomposition of the body—Probable causes—Determination of the time of death—Putrefaction suspended—Case of Desha—Putrefaction accelerated—Cases of Mrs. Byrne and Joseph Mahaig—Marks on the skin—Protrusion of the eye and tongue as a result of putrefaction or strangulation—Putrefaction in water—Period of immersion in water . . . . . PAGES 109—129

CHAPTER 8.

Identity of mutilated remains—Cases—Exhumation of skeletons—Human and animal bones—Determination of sex, age, and personal peculiarities—Determination of age by the teeth—Questions of personal identity—Evidence from fractures, disease, and deformity . . . . . PAGES 129—163

CHAPTER 9.

Causes of death—Sudden death—Syncope—Asphyxia—Coma—Presumption of death—Medical evidence of priority of death in cases of several persons perishing from a common cause—Presumption of survivorship . . . . PAGES 163—179

POISONING.

CHAPTER 10.

Definition of the term poison—Deadly poisons—Mechanical irritants—Influence of habit and idiosyncrasy—Classification—Special characters of Irritant, Corrosive, and Neurotic poisons . . . . . PAGES 180—188

CHAPTER 11.

Evidence of poisoning in the living subject—Action of poisons increased or diminished by disease—Symptoms connected with food or medicine—Several persons attacked simultaneously—Evidence from the detection of poison in the food PAGES 188—193

CHAPTER 12.

On the evidence of poisoning in the dead body—Period at which poisons prove fatal—Chronic poisoning—Appearances produced by the different classes of poisons—Redness of the mucous membrane mistaken for inflammation—Ulceration and corrosion—Softening—Perforation of the stomach from poison and disease . PAGES 194—202

CHAPTER 13.

Rules to be observed in investigating a case of poisoning—The inspection of the body—The exhumation of bodies—Identity of substances—Preservation of articles for analysis—Use of notes—Medico-legal reports . . . PAGES 203—210

IRRITANT POISONS.

CHAPTER 14.

Sulphuric acid or oil of vitriol—Symptoms—Appearances after death—Fatal dose—Period at which death takes place—Mode of detecting the poison in the pure state and in mixture with liquids—On articles of clothing—Sulphate of indigo PAGES 211—218

CHAPTER 15.

Nitric acid or aqua fortis—Symptoms—Appearances after death—Fatal dose—Processes for detecting the poison in liquids containing organic matter—Hydrochloric acid, or spirit of salt . . . . . PAGES 219—225

CHAPTER 16.

Poisoning by vegetable acids. Oxalic acid—Symptoms and effects—Appearances after death—Fatal dose and fatal period—Chemical analysis—Acid potassium oxalate, or salt of sorrel—Tartaric acid—Acetic acid—Vinegar . PAGES 225—233

CHAPTER 17.

Poisoning by the alkalies: potash, soda, and their carbonates—Symptoms—Fatal effects of the Carbonate of potash—Appearances after death—Ammonia and its carbonate (Sal Volatile)—Chemical analysis . . . PAGES 233—240

CHAPTER 18.

Poisoning by Nitre, Sulphate of potash, and Potassium iodide—Chlorate of potash—Barium chloride—Barium carbonate . . . . PAGES 240—246

CHAPTER 19.

Phosphorus—Symptoms and appearances—Chronic poisoning by the vapour—Fatal dose—Chemical analysis—Phosphorus-paste—Red or allotropic phosphorus—Iodine . . . . . PAGES 246—255

CHAPTER 20.

Metallic irritants—Arsenic—Arsenious acid—Symptoms—Chronic poisoning—Appearances after death—*Fatal dose—Chemical* analysis—Arsenites—Arsenic acid—*Orpiment and other arsenical compounds* . . . . PAGES 256—285

CHAPTER 21.

Poisoning by mercury—Corrosive sublimate—Symptoms—Chronic poisoning—Fatal dose—Appearances after death—Period at which death takes place—Chemical analysis—Processes for mercury in organic liquids—White and red precipitates—Other compounds . . . . . PAGES 285—300

CHAPTER 22.

Poisoning by lead—Sugar of lead—Symptoms—Appearances after death—Chemical analysis—Lead in organic mixtures—Carbonate or white lead—Chronic poisoning. Poisoning by copper—Blue vitriol—Symptoms—Appearances after death. Poisoning by other compounds of copper—Chemical analysis—Copper in organic liquids—In articles of food . . . . . PAGES 300—315

CHAPTER 23.

Tartar emetic—Symptoms—Appearances—Chronic poisoning—Chemical analysis—Chloride or butter of antimony—Poisoning by Sulphate and Chloride of zinc—Preparations of Tin—Silver—Gold—Iron—Bismuth and Chromium—Potassium bichromate—Osmic acid—Thallium . . . . . PAGES 315—334

CHAPTER 24.

Vegetable irritants—Aloes—Colocynth—Gamboge—Jalap—Scammony—Savin—Capsicum—Croton oil—Castor seeds—Physic nut—Colchicum—Hellebore—Yellow jasmine (*Gelsemium sempervirens*)—Oil of Turpentine—Camphene—Oil of Tar—Creasote—Carbolic acid or phenol—Resorcin or resorcinol . PAGES 335—348

CHAPTER 25.

Animal irritants—Cantharides or Spanish flies—Symptoms and effects—Analysis—Poisonous animal food—Fish—Mussels—Cheese—Sausages—Diseased flesh of animals—Trichinosis . . . . . PAGES 348—361

NEUROTIC POISONS.

CHAPTER 26.

Opium—Symptoms—Appearances—Its action on infants—Poisoning by poppies—By opiate compounds—Morphia and its salts—Process for detecting opium and its principal constituents in organic mixtures—Lactucarium . PAGES 362—376

CHAPTER 27.

Prussic acid—Symptoms and appearances—Fatal dose—Tests for the acid—Process for organic mixtures. Cyanide of potassium. Silver cyanide. Essential Oil of Bitter Almonds . . . . . PAGES 376—387

CHAPTER 28.

Narcotic liquids and vapours—Carbon disulphide—Coal-naphtha—Wood-naphtha—Amylene—Fusel-oil. Amylic alcohol—Benzol—Nitrobenzol—Aniline—Oil of wormwood—Absinthe—Nitroglycerin or glonoin—Alcohol—Ether—Chloral Hydrate—Chloroform—Bichloride of methylene—Iodoform . . . PAGES 388—407

CHAPTER 29.

Camphor—Tobacco—Nicotine—Cocculus indicus—Picrotoxin—Darnel seeds—Calabar bean—Fungi—Henbane—Solanum—Deadly nightshade, or Atropa Belladonna—Atropine—Datura stramonium, or Thornapple . . . PAGES 408—429

CHAPTER 30.

Nux vomica—Strychnine—Symptoms and appearances—Time of occurrence of symptoms—Fatal dose—Period of death—Chemical and microscopical analysis of nux vomica and strychnine—Tests—Process for organic mixtures—Detection of strychnine in the tissues—Brucine . . . . . PAGES 430—444

CHAPTER 31.

Conium maculatum. Hemlock—Conia—Cicuta virosa—Œnanthe crocata—Water-parsnip—Æthusa cynapium—Lobelia—Foxglove—Digitalin. Aconite, or Monks-hood. Aconitine . . . . . PAGES 444—466

CHAPTER 32.

Laburnum—Taxus baccata, or yew—Ligustrum, or privet—Ilex aquifolium, or holly—Viburnum opulus, or Guelder rose . . . . . PAGES 466—472

CHAPTER 33.

The Cadaveric alkaloids, or ptomaines . . . . . PAGES 472—476

WOUNDS AND PERSONAL INJURIES.

CHAPTER 34.

Surgical definitions of a wound—Injury to the skin—Legal definition—Implies immediate and not remote injury to the skin—Is a dislocation or fracture a wound?—Wounds dangerous to life—The danger imminent—Dying declarations—Wounds producing grievous bodily harm . . . . . PAGES 477—485

CHAPTER 35.

Examination of wounds in the dead body—All the cavities should be inspected—Acquittals from the neglect of this rule—Characters of a wound inflicted during life—Of a wound made after death—Experiments on amputated limbs—Caution in medical opinions—Wounds or injuries unattended with bleeding—Ecchymosis from violence—Evidence from ecchymosis—Ecchymosis from natural causes—Is ecchymosis a necessary result of violence? . . . . . PAGES 485—498

CHAPTER 36.

Evidence of the use of a weapon—Characters of wounds caused by weapons—Incised, punctured, lacerated, and contused wounds—Stabs and cuts—What are weapons?—Examination of the dress—Wounds produced through the dress PAGES 498—509

CHAPTER 37.

Wounds indicative of homicide, suicide, or accident—Evidence from the situation of a wound—Suicidal wounds in unusual situations—Evidence from nature and extent—Shape—Evidence from the direction of a wound—Suicidal and accidental wounds—Wounds inflicted by the right or left hand—Accidental and homicidal stabs—Evidence from the presence of several wounds—The use of several weapons—Two or more mortal wounds—Wounds produced simultaneously or at different times PAGES 509—531

CHAPTER 38.

Evidence from circumstances—Medical questions—Value of circumstantial evidence—The position of the body—Of the weapon—The weapon or other articles found in the hand of the deceased—Evidence from blood, hair, and other substances on weapons—Human and animal hair—Marks of blood on clothing and furniture—No blood on the assailant—Evidence from wadding and projectiles—Examination of fire-arms—Blood on the deceased—Blood on the assailant—Evidence from the form and direction of spots of blood . . . . . PAGES 532—554

CHAPTER 39.

Examination of blood-stains—Chemical, optical, and microscopical evidence—Stains of blood on linen and other stuffs—Age or date of the stains—Insoluble stains resembling blood—Stains of fruits, flowers, roots, and extracts—Stains of blood on weapons—Stains from iron-rust—Arterial and venous blood—The Guaiacum process—Spectral analysis—Varieties of blood—Blood of man and animals—Blood-crystals . . . . . PAGES 555—578

CHAPTER 40.

Imputed or self-inflicted wounds—Motives for their production—Medico-legal investigation of these cases . . . . . 578—582

CHAPTER 41.

The cause of death in wounds—Caution on assigning too many causes—Wounds directly or indirectly fatal—Death from hæmorrhage—Loss of blood required to prove fatal—Modified by age and other circumstances—Fatal wounds of small arteries—Internal hæmorrhage—Death from mechanical injury to a vital organ—Death from shock—Blows on the abdomen—Flagellation—Death from numerous injuries without any mortal wound . . . . . PAGES 582—588

CHAPTER 42.

Death of wounded persons from natural causes—Distinction between real and apparent cause—Death from wounds or latent disease—Accelerating causes—Which of two wounds caused death?—Death following slight personal injuries . PAGES 589—593

CHAPTER 43.

Wounds indirectly fatal—Death from wounds after long periods—Secondary causes of death—The cause is unavoidable—The cause avoidable by good medical treatment—Comparative skill in treatment—Cause avoidable but for imprudence on the part of the wounded person—Abnormal or unhealthy state of the body—Acceleration of death . . . . . PAGES 594—603

discovered—Deflection of balls—Accidental, suicidal, and homicidal wounds—Position of the wounded person when shot—Wounds from small-shot—Wounds from wadding and gunpowder—Identity from the flash of powder—Examination of the weapon . . . . . PAGES 683—704

CHAPTER 51.

Death from burns and scalds—Symptoms—Stupor—Cause of death—Post-mortem appearances—Burns on the dead body—Accident, homicide, or suicide—Wounds caused by fire—Scalding—Burns by corrosive liquids . . PAGES 705—718

CHAPTER 52

Spontaneous combustion—Alleged occurrence of cases in human beings—In the dead body—Accidents by fire . . . . . PAGES 718—727

ILLUSTRATIONS

IN

THE FIRST VOLUME.

FIG.		PAGE
1.	Skeleton of Dr. Parkman, restored	131
2.	The Waterloo Bridge case, the remains restored	132
3.	Front and back view of the skeleton	132
4.	Beaker and tube for the dialysis of poisons	216
5.	Crystals of nitre, magnified	222
6.	Crystals of oxalic acid, magnified	229
7.	Crystals of calcium oxalate, by dialysis	230
8.	Crystals of acid potassium oxalate	232
9.	Crystals of sodium nitrate	235
10.	Crystals of barium chloride	246
11.	Berzelius's reduction-tube for arsenic	264
12.	Reduction-tube with sublimate of metallic arsenic	264
13.	Reduction-tube with octahedral crystals of arsenic	264
14.	The same, highly magnified	264
15.	Crystals of arsenic by sublimation	265
16.	Crystals of arsenic from a solution in water	265
17.	Deposits of arsenic (Marsh's process)	267
18.	Apparatus for separating arsenic from organic substances	270
19.	Apparatus for testing chloride of arsenic obtained by distillation	272
20.	Portion of tube with metallic deposit	272
21.	Tube apparatus for testing chloride of arsenic	273
22.	Flask and funnel employed in testing substances by Reinsch's process	274
23.	Crystals of corrosive sublimate, obtained by sublimation	290
24.	Crystals of the same from a solution in water	291
25.	Crystals of the same from a solution in alcohol	291
26.	Metallic mercury sublimed in globules from corrosive sublimate	291
27.	The same, highly magnified	291
28.	Galvanic pile of gold and zinc for separating mercury	292
29.	Magnified sublimate of mercury	293
30.	Mixed sublimates of mercury and arsenious acid	294
31.	Crystals of sugar of lead from water	303
32.	The same, magnified	303

FIG.		PAGE
33.	Crystals of tartar emetic	321
34.	Crystals of potassium bichromate, magnified	332
35.	Leaves of savin	336
36.	Croton seeds	337
37.	Castor seeds	340
38.	Colchicum seeds	340
39.	Crystals of cantharidin from chloroform	351
40.	The same from ether	351
41.	Trichina spiralis in capsule	357
42.	The same, with the worm coiled	357
43.	Capsule of trichina	357
44.	Trichinæ in human flesh, natural size	357
45.	Trichina removed and magnified	359
46.	Section of trichina in capsule, in flesh	359
47.	Trichinæ in human muscle, magnified	360
48.	Crystals of morphia from the hydrochlorate	373
49.	Crystals of silver cyanide from the vapour of prussic acid	381
50.	Apparatus for detecting chloroform-vapour	406
51.	Berry and kernel of cocculus indicus	412
52.	Crystals of picrotoxin, magnified	413
53.	Bearded darnel (*Lolium temulentum*)	414
54.	Calabar bean	414
55.	Leaf of henbane	420
56.	Seeds of henbane	420
57.	Leaf of belladonna	422
58.	Seeds of belladonna	423
59.	Crystals of sulphate of atropine	425
60.	Seeds of datura stramonium	429
61.	Seeds of datura alba	429
62.	Leaf of stramonium	429
63.	Crystals of daturine	429
64.	Seed of nux vomica, convex surface	437
65.	The same, concave surface	437
66.	Section of seed with hairs, magnified	437
67.	Hairs of nux vomica, magnified	437
68.	Crystals of strychnine from alcohol	438
69.	Crystals of sulphate of strychnine	438
70.	Crystals of sulphocyanate of strychnine	439
71.	Crystals of chromate of strychnine	439
72.	Crystals of salicin	439
73.	Crystals of santonin	439
74.	Crystals of sulphate of brucine	444
75.	Seeds of hemlock (*Conium maculatum*)	446
76.	Leaves of hemlock	446
77.	Leaves of parsley	447
78.	Seeds of parsley	447
79.	Seed of water-hemlock (*Cicuta virosa*)	448

FIG.		PAGE
80.	Leaf of Œnanthe crocata	450
81.	Seeds of the same	450
82.	Leaf of fool's parsley (*Æthusa cynapium*)	451
83.	Seeds of Æthusa cynapium	451
84.	Seeds of Indian tobacco (*Lobelia Inflata*)	453
85.	Leaves of foxglove (*Digitalis purpurea*)	454
86.	Seeds of the same	454
87.	Root of aconite	462
88.	Root of horseradish	462
89.	Leaf of aconite	462
90.	Seeds of the same	462
91.	Seeds of laburnum	468
92.	Leaf of laburnum	468
93.	Leaves of yew	470
94.	View of the blood-vessels of the neck	516
95.	Position of the body of Mrs. Gardner	519
96.	The hands of Mrs. Gardner, showing the cuts across them	520
97.	Side view of the chest. Case of Mr. Moon	525
98.	Fibres of cotton, magnified	538
99.	Fibres of linen	538
100.	Fibres of silk	538
101.	Fibres of woollen	539
102.	Fibres of ancient woollen	539
103.	Fibres of ancient linen	539
104.	Human hair and hair of the eyebrow	539
105.	Human hair with tubular sheath	540
106.	Hairs of the dog, rabbit, hare, horse, goat, fox, cow, and fallow-deer	540
107.	Rabbit's fur and flakes of resin. Case of Raynor	542
108.	Stains of blood on the flap of a table—from photograph	555
109.	Spots of arterial blood on a brick	565
110.	Spectra of blood	568
111.	Blood-corpuscle, magnified	571
112.	Blood-corpuscle seen sideways	571
113.	Corpuscles of blood in linen fibre	572
114.	Human blood-corpuscles, magnified	572
115.	The same from a dried specimen (bloodstain)	572
116.	Human corpuscles as seen in water	573
117.	The same in a solution of sodium sulphate	573
118.	Blood-corpuscles of the dog, mouse, rabbit, and ass	575
119.	Blood-corpuscles of the cow, ox, pig, and cat	575
120.	Blood-corpuscles of the horse, sheep, common fowl, and salamander	576
121.	Blood-crystals from the blood of man, the cat, guinea-pig, and squirrel	576
122.	Blood-crystals of human blood and the blood of the fish	577
123.	Crystals from a dried clot of human blood	577
124.	Hæmin-crystals from the blood of man, the sheep, and bullock	577
125.	Hæmin-crystals (Neumann)	578
126.	Section of the bones of the skull and the membranes of the brain	650

FIG.		PAGE
127.	Section of the brain, showing the ventricles or cavities	650
128.	Lateral view of the brain, showing the cerebellum and spinal marrow	651
129.	Right side of the heart, with its cavities laid open	658
130.	Front view of the viscera of the chest	660
131.	The diaphragm. Under or abdominal surface	663
132.	View of the under surface of the liver	670
133.	Section of the stomach and duodenum	673
134.	The stomach in connection with the small and large intestines	674
135.	The liver, stomach, duodenum, and pancreas, in position	674

ERRATA.

Vol. I. at page 503, 3rd and 4th lines from bottom, for 'Gould' read 'Gold.'

" " 718, omit latter part of heading of chapter from 'spontaneous combustion of mineral and organic substances' to end.

THE

PRINCIPLES AND PRACTICE

OF

MEDICAL JURISPRUDENCE.

MEDICAL EVIDENCE.

CHAPTER 1.

THE PRACTICE OF MEDICAL JURISPRUDENCE—MEDICAL AND MEDICO-LEGAL DUTIES CONTRASTED—MEDICAL REPORTS—CORONERS' INQUESTS—CONCEALED MURDERS—INSPECTIONS OF THE DEAD—TRIAL AT THE ASSIZES—SUBPŒNAS—DUTIES AND PRIVILEGES OF MEDICAL WITNESSES.

MEDICAL JURISPRUDENCE—or, as it is more commonly called, FORENSIC, or LEGAL MEDICINE—is a branch of MEDICINE, and may be defined to be that science which teaches the application of every branch of medical knowledge to the purposes of the law; hence its limits are, on the one hand, the requirements of the law, and on the other, the whole range of medicine. Anatomy, physiology, medicine, surgery, chemistry, physics, and botany, lend their aid as necessity arises; and in some cases all these branches of science are required to enable a Court of Law to arrive at a proper conclusion on a contested question affecting life or property.

Medical jurists are by no means agreed upon the exact boundaries of their science. Some authorities include forgery and coining, and all offences requiring purely chemical evidence; others include feigned diseases, nuisances, and subjects connected with public health or sanitary legislation; while one German writer introduces the government and regulation of Temperance Societies. Those who thus propose to enlarge the science forget the maxim, '*Ars longa, vita brevis;*' and they also forget that, by demanding too much of a medical practitioner, they may deter him from undertaking the study of that portion which may really prove serviceable to him in the practice of his profession. STATE MEDICINE includes both Medical Jurisprudence and Hygiène.

The purpose of this work is to bring as far as possible within a reasonable compass those subjects which especially demand inquiry, and which more particularly concern the duties of the educated physician and surgeon in his relation to the law. The definition above given necessarily implies that a medical jurist should have a theoretical and practical knowledge of all branches of the profession, a large range of experience, and the rare power

of adapting his knowledge and experience to emergencies. He should b able to elucidate any difficult medico-legal question which may arise, an be prepared at all times to make a cautious selection of such medical fact and a proper application of such medical principles, as may be necessar to enable a judge to place the subject in an intelligible light before th jury, and to enable a jury to arrive at a just conclusion.

Medico-legal knowledge does not consist so much in the acquisition c facts as in the power of arranging them, and in applying the conclusions t which they lead to the purposes of the law. A man may be a most skilfu surgeon, or a most experienced physician; his mind may be well store with professional information; yet if he is unable by the use of simpl language to make his ideas known to others, his knowledge will be of n avail. One far below him in professional standing and experience ma make a better medical witness.

The variety of subjects in which a medical jurist is required to hav knowledge and experience may alarm a student of medicine, and lead hir to suppose that, as he cannot make himself perfectly acquainted with al he may well forego the labour of preparing himself in any. But thi would be taking an erroneous view of his position. This description c the qualifications necessary to constitute a normal witness in a Court c Law must not deter him from entering on the study. It is assuredl beyond the mental power of any individual that he should be at the sam time profoundly versed in all the principles of medicine and jurisprudenc and that he should be able to answer all possible questions, and encounte and remove all medical difficulties that may occur during the trial of civil or criminal case. All that the law expects from a medical man is fair average knowledge not merely of his profession, but of that which fall more peculiarly under the province of a medical witness. There can b no doubt that the more perfectly a man has made himself master of hi profession, the better will he be fitted to follow the principles and appl himself to the practice of medical jurisprudence; but he must divest himsel of the notion that these principles can be spontaneously acquired, or tha they are necessarily derived from the study of those isolated branches o medicine upon which medical jurisprudence is based. The materials fo the medical jurist undoubtedly exist in these collateral sciences: but the require to be assorted, selected, and moulded into shape, before they can b applied to any useful purpose. A man may be well qualified to practise a a physician or surgeon, and yet find himself deficient when called upo to act as a medical witness. There was no doubt that John Hunter stoo in his time at the very head of his profession, and that none could hav profited more by industry and experience. If sound professional know ledge could have qualified any man to act as a medical witness, we shoul assuredly be justified in pointing to him as an example; and yet this grea man, when summoned to give evidence on a memorable trial for poisoning which occurred in 1781, was obliged to confess that he was unable to giv a satisfactory answer to the important question put to him. Hunter wa the only professional witness called on the part of the prisoner to rebu the charge of poisoning the deceased by laurel-water. His cross-examina tion, however, rather strengthened the case for the prosecution; and th final question put by the Court was: 'Give your opinion, in the bes manner you can, one way or the other, whether, upon the whole of th symptoms described, the death proceeded from the medicine (laurel-water) or any other causes?' *A.* 'I do not mean to equivocate; but when I tel the sentiments of my own mind, what I feel at the time, I can give nothing decisive.' With that candour which exists in all great minds, Hunte admitted his deficiencies; and he regretted to the latest period of his lif

that he had not directed more attention to subjects of this nature. It is clear from his answer that he should not have appeared in the case at all. In Hunter's time medical jurisprudence was unknown in this country; but the want of it was clearly perceived. It was made apparent from the events of this remarkable trial (*Rex* v. *Donellan*, Warwick Lent Ass., 1781), that a peculiar kind of experience was required to fit a medical man to act as a witness in a Court of Law—that many loose principles existed in medicine, surgery, and chemistry, the fallacies of which were quite unimportant so far as they related to medical practice, but which required to be closely sifted and thoroughly examined before they could be received as evidence in law. Medical men were then, as now, apt to confound what is mere matter of belief with proof. In a Court of Law, however, the difference is soon made apparent. From the occurrence of this and similar cases, there was an obvious necessity for the creation of a distinct branch of science in which all medical facts and principles capable of serving as evidence should be arranged, developed, and explained.

The duties of a medical jurist are distinct from those of a practising physician or surgeon: the latter looks only to the treatment of disease or accident, and the saving of life; but the object of the former, in a large proportion of cases, is, whether in reference to the living or the dead, to aid the law in fixing on the perpetrator of a crime, or to rescue an innocent person from a falsely imputed crime. Thus he may be required to determine whether, in a particular case, the cause of death is natural or violent; and for this purpose it will be necessary for him to make an entirely new application of his professional knowledge. He has now the difficult task of making a selection from those parts of the medical sciences which bear upon the legal proof and development of crime.

Some members of the medical profession have been inclined to look upon medico-legal practice as an unnecessary addition to their ordinary duties; but there are few who have been long engaged in the practice of the profession who have not found themselves occasionally placed in situations of difficulty from the accidental occurrence of cases demanding medico-legal investigation. A medical man is summoned to attend a person labouring under the effects of poison criminally administered, but at the time he may have no knowledge or even suspicion that poison is the cause of the symptoms. In spite of the best treatment, death ensues: here the functions of the medical man end, and those of a medical witness begin. It is impossible that he can now avoid giving evidence, or shift the responsibility to another—the law will insist upon his appearance, first in the Court of the coroner, and afterwards at the Assizes. It will be assumed that, as a registered member of the profession, he is fully competent to answer every question put to him by judge and counsel relative to the general effects of poison; the quantity of each required to destroy life; and the time within which a poison may prove fatal. It may be objected to his evidence, that the deceased had died from the effects of disease and not from poison; in which case the examination will lead to a searching inquiry into all those diseases which resemble poisoning in their symptoms and post-mortem appearances, as well as the means of making a certain distinction between them, and the fallacies to which the chemical processes for the detection of poison are liable. On another occasion, a medical man may be called to render assistance to one who has been stabbed in a quarrel, and who speedily dies from the wound. The office of the surgeon here ceases, while that of the medical jurist commences. He must now be prepared to answer numerous questions, all bearing upon the legal proof of crime—all necessary in law, although apparently superfluous in surgery. Thus he may be asked to state the precise characters of a wound inflicted

upon the body of a man soon after death, and by what means a particula wound was inflicted. Was it homicidal or accidental? The amount o blood lost? Whether the person could have moved or performed any ac after receiving it? Are certain stains found upon his clothes, or upon knife belonging to him, owing to effused blood or other causes? Whethe any and what statements were made by the dying man, and what were th precise circumstances under which they were made? It need hardly b observed that questions of this nature are rarely noticed, except in a cursor manner, by professors of chemistry and surgery, and a medical man is no likely to acquire the means of answering them by intuition. On the othe hand, regarding ourselves as living in a civilized state, in which the detec tion and punishment of crimes against life and property are indispensabl to the security to all, it is impossible to overrate their importance. Unles a witness is able to return answers to these questions when a publi necessity occurs, a guilty man may escape punishment or an innocent ma may be condemned. He may thus most seriously injure his own reputa tion; for it is certain that his qualifications as a physician, surgeon, o general practitioner, however great, will not shield him from the reproach of having caused a failure of justice.

Thus, then, it is obvious that the duties of a medical jurist are of a highly responsible nature and of great importance to society, while the cases which call them into exercise are of purely accidental occurrence. A medical practitioner who thinks himself secure in the most retired corner of the kingdom, is liable to find himself suddenly summoned as a witness on a trial, to answer questions which perhaps during a long period of practice he had been led to regard as trifling and unimportant. Under the circumstances it is scarcely possible that he can avoid exposing his deficiencies, and the final question will be, *Have you ever attended to or thought of these subjects before?* A negative answer to this question, while it commonly brings with it public censure, will in most instances lead to the acquittal of the accused in spite of strong presumptions of guilt.

The truth of this picture will be felt and acknowledged by those who have been a few years engaged in practice. The records of our law-courts contain many unfortunate exposures, which might have been easily avoided had the witnesses only availed themselves of the opportunities afforded to them of acquiring a knowledge of the subject; but they had unreflectingly acted on the principle that medical jurisprudence was a dry, dull, and useless study, and that the practice of it was remote and speculative. This feeling is, however, fast disappearing. Those who have been compelled by circumstances to give their attention to it have in subsequent cases taken care to prepare themselves for the ordeal through which every medical witness must pass.

Some medical men who have treated legal medicine with indifference have occasionally ventured to act as witnesses, thinking that the subjects on which they were likely to be examined were so little known to judge and counsel that even hazardous or rash statements would escape observation: such witnesses, however, have often found to their cost that they were labouring under a great delusion. Various circumstances have led, in recent times, to the acquisition of much medico-legal knowledge by lawyers, especially in relation to questions connected with wounds, child-murder, and poisoning; and they are not slow in detecting and exposing a mere pretender who attempts to shelter himself by vague or evasive statements and technical language. There are few counsel engaged in any civil or criminal case of importance who do not take care to fortify themselves, under medical advice, with a full knowledge of the views of standard medical writers on the subject in dispute; and with these works before them, and with their pro-

verbial acuteness, he must indeed be a clever witness who can succeed in passing off an erroneous or evasive answer to a medico-legal question.

It is a frequent charge against members of the medical profession, that in a Court of Law they are the worst witnesses on matters of fact and opinion. This is an unmerited censure. Those who are ready to make this charge overlook the complexity and difficulty of the questions which are put to medical men compared with those put to other witnesses. They also forget that medical men are much more frequently summoned as witnesses than the members of the two other learned professions. Their evidence obtains greater publicity, and is necessarily exposed to greater criticism. The author was, on one occasion, present at a trial before Lord Truro, in which the action was between two members of the legal profession, and the witnesses on both sides were chiefly barristers, solicitors, or solicitors' clerks. The questions put to the witnesses were so cleverly met and so technically evaded, that it was scarcely possible to obtain a plain statement or a consistent history of the most simple facts of the case. A direct answer could not be procured on any question, and the mode in which the witnesses gave their testimony elicited on several occasions rebukes from the judge. The fact is, that good and bad witnesses are to be met with in every profession; under equal conditions there is no reason to suppose that one would furnish a greater number of incompetent witnesses than another. It is certainly the fault of medical men that they are not generally prepared for the questions which are likely to arise in a case on which they know they will be required to give evidence. This want of preparation frequently applies to facts as well as to opinions. Thus, in reference to a case on which a charge of murder or manslaughter may be ultimately founded, a medical man who is called in, frequently omits to observe many circumstances because they appear to him to be irrelevant or to have little importance, although at the subsequent trial he may find, to his dismay, that they actually become the turning-points of innocence or guilt. Medical observation as a result of professional habits is, on these occasions, in general confined to only one set of circumstances —the recognition and treatment of disease or personal injury; but medico-legal observation should take a much wider range than this, and should be directed to all the surrounding facts and incidents of a case. The essential difference in the two kinds of practice is, that circumstances which are of no interest in a medical or surgical point of view are often of the greatest value and importance in legal medicine. It is obvious that if they are not observed by a medical witness when he is first summoned to the injured person, whether dying or dead, it will be out of his power to meet many of the questions which must arise in the progress of the case. The non-observance of these facts is a serious evil, and often carries with it, although unjustly, an imputation of professional ignorance.

The first duty, therefore, of a medical jurist is to cultivate a faculty of minute observation of medical and moral circumstances. This, when combined with a general knowledge of what the law requires as evidence, will enable him to meet in a satisfactory manner all the scientific questions that may be necessary for the elucidation of a case. The exercise of this faculty is by no means inconsistent with the performance of his duties as a physician or surgeon. Some eminent professional men have been known to possess this power as a natural gift. Sir Astley Cooper was called to see a man who, while sitting in his chair in a private room, had been mortally wounded by a pistol-shot from the hands of an unseen person. Sir Astley having done what was necessary respecting the wound, compared closely the direction from which the pistol was fired with the position of the wounded man, and he came to the conclusion that the pistol must have

been fired by a left-handed man. The only left-handed man known to be on the premises at the time was an intimate friend of the deceased, against whom there was no suspicion; but this acute observation led to his arrest and trial, and he was subsequently convicted of this act of murder.

The condition and position of the body of a person dead from wounds, the position of a weapon, and the state of the dress and weapon, as well as the form and direction of the wound itself, are not always noticed with sufficient accuracy. It is, however, only right to say that many medical men in the present day show great acumen in their examination of these cases. The author was present at a trial for murder in which the evidence showed that a man had been stabbed in the chest, and he died almost instantly from a wound in the heart. The act had been perpetrated by some one in a crowd in the dusk of the evening, but no one was seen to strike the blow, and no weapon was found near the spot. The surgeon observed that the wound in the chest was sharp at one angle and rounded at the other, and he gave his opinion that the wound had been inflicted with a knife having one sharp edge, and not with a dagger or double-edged knife. Within a few hours after the occurrence, a man was arrested on suspicion and a knife which he attempted to conceal was taken from him. It was in a sheath and had at this time *wet* blood upon it, showing a recent use of the weapon. It was a pointed knife, with a broad blade, and one sharp edge only—such a weapon as, in the opinion of the surgeon, would have produced the stab in the chest. The man was tried and convicted, the observation of the surgeon respecting the state of the wound and the weapon furnishing important evidence of his guilt. On the other hand, want of observation may lead to the discharge of guilty persons. A woman was found dead in her bed, with some lacerated wounds of the scalp: there was strong reason to believe that these had been produced by criminal violence, but it was suggested for the defence that as there were projecting nails at the head of the bed, these lacerations might have arisen from accident—a suggestion supported to some extent by the medical evidence. An experienced witness, however, stated that from his examination he did not believe that the nails, even if they were in the bedstead at the time of the occurrence, could have produced the wounds. He also said that as blood had issued from the wounds, and there was no blood about the nails or this part of the bed around them, he did not believe that the head had at any time come in contact with the nails. Those who were first called to the dead body had omitted to notice whether there was anything on or near to the bed to account for the wounds on the scalp, and they were quite unable to say whether there were or were not any projecting nails at the head of the bed when they first examined the body. The prisoner was discharged on the Scotch verdict of 'Not proven;' and there was some reason to believe that he escaped through manufactured evidence, *i.e.* that the nails had been driven into the head of the bed subsequently to the death of the woman. At any rate, it seems perfectly clear from a general view of the medical evidence that the wounds could not have been produced by the nails in the manner suggested, and that the wounded portion of the scalp had not at any time been in contact with them. As they were lacerated wounds, and so might have been produced by nails, the accused had the benefit of the doubt which was thus raised in the minds of the jury.

The judge who tried this case remarked that '*a medical man, when he sees a dead body, should notice everything.*' Undoubtedly he should observe everything which could throw a light upon the production of wounds or other injuries found upon it. It should not be left to policemen to say whether there were any marks of blood on the dress or on the hands of the deceased, or on the furniture in the room. The dress of the

deceased as well as the body should be always closely examined at once on the spot by a medical man. The importance of this precaution is well illustrated by a case related in another page, in which a man just escaped committal on what would have proved a false charge of murder, by reason of the examination of an article of dress accidentally produced at the adjourned inquest.

There is another point which is frequently omitted on these occasions, and the omission may give rise to great inconvenience if not to a failure of justice. Thus, in reference to a dead body, no observation is made at the time of the visit whether it or any part of it is cold or warm; whether the limbs are cold and rigid, or cold and pliant. In a medical and surgical view these conditions of the body are of no importance, but medico-legally, if the facts are observed, they may enable a witness to speak with greater or less probability as to the time of death: this may make all the difference between the acquittal and conviction of a person charged with murder. The case of *Gardner*, elsewhere related, will show the importance of observations of this kind. The circumstances which chiefly require notice on these occasions have been fully described in the section on Wounds. In reference to supposed death from poison, other matters will also require special attention. These will be found in detail in the chapters on Poisoning.

It may stimulate the attention of a medical practitioner in reference to these inquiries, if he is informed that it is a great art of counsel who defend persons charged with murder or manslaughter to endeavour to discover what he omitted to do. Although sometimes the omission may be really of no medical importance whatever, yet it may be placed before the jury in such a strong light that the accused obtains the benefit of a doubt. The omission may be attributed to professional ignorance, or, what is worse to professional bias—a determination to find proofs of guilt against the 'unhappy prisoner at the bar'—when the facts might be innocently explained by a want of experience on the part of the witness in dealing with cases of this nature.

Medical Reports for Inquests.—If we except medical experts, who are selected according to their experience in different branches of the profession, medical men have no option respecting medico-legal practice, for the cases which give rise to medico-legal questions are always more or less connected with the general practice of medicine and surgery. The initiation of criminal proceedings in England and Ireland is generally in the court of the Coroner. Unless the medical man is supposed to be implicated by maltreatment or otherwise in the death of a person, an order is issued to him to make an inspection of the body and report the results. In reference to cases of poisoning, wounds, and alleged child-murder, the points to which he should especially direct his attention will be found fully described in the chapters on those subjects. At the time of the inspection and analysis he should make notes of all that he observes and does; and upon this he may base a report, which should be a summary of the medical facts, and of the conclusions based upon them expressed as much as possible in untechnical language. In another part of the work the reader will find a description of the course to be pursued on such occasions, as well as of the circumstances under which notes are permitted to be referred to by a medical witness; and the rules for drawing up medico-legal reports are also fully explained.

There are frequently defects in these reports which it is desirable to point out. The statements are sometimes drawn up in exaggerated language: at others they are overloaded with technical and unintelligible terms, and the

writer is seldom sufficiently careful to keep his facts distinct from his comments. The former may be useful as evidence; the latter are inadmissible.

With respect to the first of these defects, it is very much the practice of medical men, in drawing up reports of medical cases for professional purposes, to use, unthinkingly, exaggerated language. Thus it may be observed in the drawing up of an ordinary post-mortem examination, the lining-membrane of the stomach is described as being 'intensely' inflamed or some part is 'considerably' injected, or a cavity is 'enormously' distended. Expressions thus loosely employed convey to the legal mind a widely-different meaning from that intended by the reporter. They create also great difficulty in evidence if withdrawn or modified—a change which other circumstances may show to be necessary, and at the same time they place the witness in an undesirable position before the Court. On the other hand, if retained, they may render the facts unsusceptible of explanation upon any theory of natural disease. Such descriptions obviously imply a comparison with similar conditions in numerous other dead bodies; but what is the standard by which they are really measured, and what opportunity has the witness had of creating such a standard in his own mind? In general, it will be found that such expressions have been used without proper consideration, from a habit acquired by the writer in reporting cases for the information of medical men only. Let him who is inclined to use them bear in mind that barristers look much more closely to the strict signification of words than medical men, and that they are always disposed to distrust the judgment of one who cannot speak or write without resorting to the use of the superlative degree.

The free use of *technical terms* in drawing up reports may be attributed to a similar practice in the profession. Putting aside those cases in which a medical man thinks he is displaying his erudition by the selection and use of such terms, there can be no doubt that great numbers of medical practitioners fall into this practice from mere habit. They think they are addressing the report to a medical society, instead of a coroner and jury who have never in their reading or experience met with such terms, and to whom therefore they are unintelligible. In a report on the appearances in the body of a man who had suffered from chronic insanity, the following passage occurred:—'The only morbid appearance in the brain was an atheromatous deposit in the Pons Varolii, near the situation of the locus niger.' In another document, the reporter stated, for the information of a coroner's jury, that the 'integuments of the cranium were reflected, and the calvarium was exposed.' If a reporter will use such terms as these or others of a similar kind, such as 'parietes of the abdomen,' 'epigastrium,' 'hypertrophy of the liver,' when it would require no more trouble to put what he means in plain English, he must be prepared to have his meaning perverted or wholly misunderstood. Setting aside the men who act as jurors, it may be observed that educated persons, such as coroners and magistrates, do not commonly include professional terms within the range of their studies. There are but few of them who understand the difference between perineum and peritoneum, or the meaning of the words hemispheres of the brain, pia mater, puncta cruenta, corpora quadrigemina centrum ovale, &c. They are not likely to know the difference between the cardia and pylorus, nor the nature or situation of the duodenum, jejunum, ileum or cæcum, and are as ready to consider them to be parts of the liver or urinary bladder as of the intestines. On one occasion, a learned judge asked for an explanation of the meaning of the term 'alimentary canal.' A slight consideration will show to any medical practitioner that refined professional language is wholly misplaced in a report which is intended to inform and convince the minds of ordinary men upon plain matters of fact

The last point which calls for comment in reference to medical reports is the loose manner in which facts and comments upon facts, as well as hearsay statements and arguments, are sometimes found blended. If a reporter takes care to eliminate facts from comment, his report is admissible, and may be read at the inquest or trial as evidence. The facts are for the jury—the comments upon the facts, introduced by the reporter, may or may not be just, and are therefore not evidence. Their correctness or relevancy to the case will be elicited in the cross-examination. As a rule, nothing should be entered in a report which is not connected with the subject of inquiry, and which has not actually fallen under the observation of the reporter. The introduction of hearsay statements—*i.e.* statements made by others, or of circumstances which have come to his knowledge through public rumour—should be carefully avoided.

In the case of *M'Lachlan*, who was tried for the murder of Jessie M'Pherson (Glasgow Aut. Circ., 1862), some discussion arose upon what should and what should not find a place in a medical report. A report was put in at the trial, in which the surgeon of police, who had been authorized to make a post-mortem examination of the body of deceased, stated, in commencing his report, that the body had been found '*under circumstances of great suspicion*,' in a front room, &c. The judge remarked that this was matter which was not suitable to a medical report. So again, in reference to the conclusions drawn, the first and third were as follows:—

1. 'That this woman (the deceased) was *murdered*, and that with extreme ferocity.'

3. '*That a severe struggle had taken place before death.*'

The suggestion of murder was an anticipation of the verdict of the jury. As a general rule, conclusions are limited to the *cause of death*, and no reference is made to ferocity.

The difficulties arose from the introduction of comments into the report. There was no evidence of conflict or struggle, as far as the examination went. The facts upon which the witness relied as evidence of a struggle were equally consistent with the dragging of the body after death.

In a medical report of an analysis in a case of suspected poisoning, it is not necessary that all the details of an analysis should be entered. A general statement of the results, to the effect that certain tests and processes had been used, will be sufficient. In the various analyses connected with the case of Cook and Ann Palmer (*Reg.* v. *Palmer*, C.C.C., May, 1856), an application was made to Dr. Rees and the author to give to the prisoner's attorney, before the trial, a statement of the whole of the details of their analysis of antimony and strychnine. They declined to do this without authority. The Queen's Bench was appealed to, and Lord Campbell decided that there was no legal ground on which such a demand could be enforced. Considering that the medical evidence against the prisoner was clear and conclusive, the counsel for the Crown advised that they should concede the point, although admitted to be neither in accordance with law nor custom. Upon this advice they acted, but it is not a course to be recommended to any scientific witness to follow in a future case. The result was that, before the trial, these memoranda were placed in the hands of some chemists retained for the defence, with a view to hostile criticism. Portions of them appeared in a garbled, fragmentary, and incorrect form in some journals and newspapers, with comments attacking the processes and conclusions before their evidence had been given. It was well known that, under the circumstances, the witnesses for the Crown were precluded from making any reply or giving any explanation. No medical man is called upon to lay himself open to attacks of this nature, or to

furnish materials for a cross-examination to 'medical counsel' acting in the interests of a prisoner. In regard to the chemical research for poisons, chemists generally differ about the process which it may be desirable to pursue in a given case; and although the same result may be reached by various methods, it is by no means difficult to find one who will assert that his is the only correct process, and that all others are fallacious, or to raise by such counter-statements that kind of doubt in the minds of a jury which may lead to the discrediting of a witness's results.

Upon a medical report, and such evidence as may be required to explain it, an accused person may be committed for trial at the Assizes, either by a coroner or magistrate. In the first stage of proceedings under these circumstances, the medical witness goes before the Grand Jury, and there after the administration of an oath, he is required to make a general statement of what he knows of the matter. Such questions are put as may be necessary to elucidate the cause of death; and on the finding of a true bill for murder or manslaughter, the accused is placed upon his trial before one of the judges of assize. According to the variable circumstances attending such cases, the medical evidence is called for at an early or late stage of the proceedings. When it is at all doubtful whether the cause of death was owing to any criminal act, it is called for at the commencement of the case, in order to lay a distinct foundation for further inquiry.

It is necessary that a medical witness should remember that copies of his report and depositions, either before a coroner or magistrate, are usually placed in the hands of counsel as well as of the judge, and that his evidence as it is given at the trial, is compared word for word with that which has been already put on record. There is reason to believe that this is not generally known to members of the medical profession, and thus it happens that either from failure of memory, want of accurate observation, or carelessness in giving evidence at coroners' inquests, medical witnesses lay themselves open to severe censure, either by stating matters differently at the trial, or by giving a very different complexion to the facts. Any serious deviations from what is on record will of course tell unfavourably for the witness, supply materials for a severe cross-examination, and form an excellent ground of defence for the prisoner. The witness's weakness is the prisoner's opportunity, and of course his counsel will not lose the occasion of impressing upon the jury that a man who can on oath give two different accounts of the same transaction is not to be believed on either.

Coroners' Inquests.—The proceedings at Coroners' inquests are treated too lightly by medical men. The ignorant and uneducated class of persons who often constitute the jury, as well as the circumstances under which the inquiry usually takes place, are not calculated to inspire great respect for these initiatory proceedings; but still by law and custom coroners' inquisitions are, and have been for ages in this country, the primary tribunals for inquiring into and determining the cause of death in cases of suspected violence; and they are therefore deserving of more attention than is usually shown to them by medical witnesses. The observations elsewhere made in reference to inquests in alleged child murder apply to all other cases demanding medical evidence. As a rule, in all inquests which are likely to end in a committal of the accused person, a medical man who is giving his evidence before a coroner, usually in the room of a small inn, is virtually delivering it before a judge of assize; and this fact alone, if not a respect for the Court, should induce him to give the evidence guardedly, and with a due consideration of the serious results to which exaggerations or mis statements may ultimately lead. The deposition should be always read by or to the witness, before he signs it. It is therefore easy for him to correc

any error which may have crept into the document by reason of the ignorance or neglect of the coroner's or magistrate's clerk.

Coroners' inquisitions are so intimately associated with the practice of medical jurisprudence in reference to criminal cases, that it is impossible to pass over this subject without pointing out what must be regarded as the defects of this method of inquiry. The 4th Edward I., stat. 2, on which coroners profess to act, directs that, 'upon information,' they shall 'go to the place where any be slain or suddenly dead,' and make due inquiry as to the cause, &c., before a jury selected from persons living in the neighbourhood. The information upon which a coroner generally acts is,—1. Notice from a beadle, or other officer of the parish (whose zeal is sometimes stimulated by a fee or salary) of any death from sudden or supposed unusual causes. 2. Notice from a medical man who may have attended the deceased, and who communicates his suspicion that the cause of death is not natural. 3. Notice from a registrar of deaths that no cause has been assigned in a particular case, or that there has been a rapid death after a short illness.

The conclusion to which experience leads in reference to these inquiries is, that the system affords no certainty for the detection of crime; that it affords no protection to those who are wrongly charged with crime; and lastly, that in some cases it screens a criminal by a verdict based upon an imperfect inquiry, in which the important medical facts are either not understood or are misinterpreted by the jury. A remarkable illustration of this statement has been furnished, in reference to an inquest held in Suffolk, in Sept., 1867. A druggist applied to the ulcerated breast of a woman suffering from cancer, *thirty grains* of morphia in powder. The woman was soon afterwards seized with the symptoms of poisoning by morphia in a severe form, and she died in ten hours. The druggist, when examined at the inquest, admitted that he had applied this large quantity of a powerful poison, and in his judgment it was a right and proper application. There was medical evidence that the woman had died from poisoning with morphia by absorption, on which fact there could not indeed be two opinions. The coroner summed up the case, and the jury returned a verdict of 'death from natural causes.'

Admitting that some crimes (which might have remained concealed) have been brought to light by this system, as the inquiry is now conducted, it fails to exercise any deterring influence on criminals. In a large proportion of cases there is no inspection of a dead body. This is probably in order to avoid delay or the expenses of a post-mortem examination. It would be easy to point to cases in which death by poison has been thus concealed, and the fact has only come to light by accident some years afterwards. With rare exceptions, indeed, is it justifiable on the part of a coroner to hold an inquiry on a dead body without a strict external and internal examination of the body. Either the inquiry is necessary, or it is not. If not necessary, the coroner is to blame in holding it; if necessary, an inspection of the body is the very essence of the inquiry, where it refers to one who 'has been slain or is suddenly dead.'

The author was once an attendant at a funeral; it was delayed, and the cause of the delay was this:—An inquest had been held on the body (a case of very sudden death in a state of health), and a verdict of 'Death from disease of the heart' had been returned. There had been no inspection of the body. When the grave-clothes were removed, and the body was examined, it was found to be covered with bruises, and some of the muscles of the thigh were found reduced to a jelly by blows. Death had been clearly caused by violence. But an inquiry before a coroner for two days had, with all the usual formalities of medical evidence, &c., resulted in a verdict of

'Death from disease of the heart.' Within two hours only of the body being put into the ground, it was clearly proved to be an act of murder or manslaughter. The guilty party was tried, convicted, and punished. (*Reg.* v. *Hopley*, *Lewes Aut. Ass.* 1860.) This case, with several others of a similar kind, establishes two propositions. The coroner's inquest affords no certainty for the detection of crime. It, in some cases, tends to screen a criminal.

The secrets of the grave are only known to those who practice medical jurisprudence. In the course of thirty years' practice, at least fifteen cases of the exhumation of dead bodies were referred to the author. On some of these inquests had been held, but no inspections were made. Verdicts of death from cholera or natural causes had been returned, and, at intervals of from one month to twenty-two months, the bodies have been disinterred, and it was then proved that the deceased persons had died from poison. In some of these cases the deaths were sudden, and in others slow; in the latter the symptoms during life were mistaken for those of disease, medical certificates of the cause of death were given without sufficient inquiry: thus it is that crime passes undetected, and several lives may be destroyed in succession before a criminal is arrested in his career. There is a popular notion in accordance with the ancient statute, that *sudden* deaths only require an investigation by the coroner; but this is an error. A large proportion of sudden deaths take place from well-known natural causes, easily elicited by a proper medical inquiry, and they strictly demand no judicial proceedings. On the other hand, in all cases of slow or chronic poisoning, the person has lingered on with intermitting symptoms, and death has taken place only after an illness of some days' or weeks' duration. There is no provision for the detection of such cases. Their discovery appears to be a matter of accident.

As a rule, it may be said that all inquests in which there has been no medical inspection of the body are a vain mockery, and the sooner the public mind is imbued with this proposition the better for society. It is not implied that an inquest should be held on the bodies of all persons who die suddenly. If circumstances of a suspicious kind justify an inquest, *ipso facto* there should be an inspection. If an inspection is not required, an inquest is not required. Such cases as inquiries into deaths from machinery, railway accidents, &c., where the physical injury is obviously sufficient to account for death without further inspection, are excepted from this remark. The verdicts of coroners' juries are sometimes quite erroneous, and contrary to the medical evidence. Great injury is thus done occasionally to innocent persons. At the Assizes the bill may be thrown out by the Grand Jury; but the person inculpated by the verdict may always have a stigma attached to his character, as a result of mistake or misapprehension of medical evidence, or, sometimes, of local prejudice.

Many persons who occupy the office of coroner are neither medically nor judicially qualified for the proper performance of the duties of the office. The system of electing a man to hold such an office as this (one demanding special *medical* knowledge of the causes of death, and good *legal* knowledge of the law of evidence) by freeholders of the lowest degree, is so intrinsically absurd, that it is wonderful how, with improved knowledge and the advance of civilization, it has maintained its ground in such a country as England. The election of a Lord Chancellor, of the judges of our Courts of Law, or of County Court judges, might be with equal reason left in the hands of voters of this class—men who have no knowledge of the duties of the office, or of the skill and learning required in one who is really competent to fill it. The election of a good and capable person as coroner is, therefore, a matter of pure accident. No preliminary test of ability or capacity is required.

The time is not far distant when an effort will be made to alter the law relating to coroners' inquests, and to redeem from popular and professional contempt that which is too often a farce—'crowner's quest law.' Few are prepared to leave the duties and positions of coroners as they at present exist untouched; and on all hands the necessity of some change is admitted.

In Scotland, the office of coroner does not exist; but in place of this there is an officer named Procurator Fiscal, generally a skilled solicitor, nominated by competent authority, and not elected by scot and lot voters. The general order issued to these officers by the Lord Advocate enjoins that in cases where a dead body is discovered, the Procurator Fiscal shall obtain a medical report of the cause of death; and in cases of persons found dead, the body is generally inspected for this purpose. This, however, is at the option of the appointed officer, the instruction being in these words: 'Wherever in his opinion a written medical report is necessary for the due consideration of the case, he, the Procurator, shall obtain such a report from a duly-qualified medical practitioner.' The usual practice in England is to select the *nearest* medical practitioner, whether he has had any experience or not, and often to trust an important chemical inquiry in the hands of one who probably has never before made an inspection or an analysis for poison.

In France, the officer corresponding most nearly to our coroner is the *procureur*, or Attorney of the Republic, who is also a kind of local public prosecutor, and is a lawyer. On receiving information, he makes the necessary investigations, and draws up a report. He is assisted by a medical officer or officers, chosen for superior medical and surgical knowledge; and he may also call in the aid of experts. The system is said to be effective; for whilst the presiding officer is a lawyer, he has a medical assessor, medical testimony is obligatory, and the interests of the public and of the medical profession are guarded.

In Germany, an inquest is solely an affair of the police, and there is neither coroner nor analogous officer. There are, however, distinct judicial medical officers, regularly appointed and selected for their special training and fitness for forensic duty. On the summons of the district attorney they examine dead bodies, make post-mortem examinations, and report on the medical examination.

A very satisfactory system of holding inquests has been adopted by the State of Massachusetts, and is said to work well. Coroners and juries are wholly dispensed with on the preliminary examination. A competent medical man is duly appointed, in consequence of his fitness, to the post of district medical officer. He inspects the corpse; and if, on such examination, he thinks further examination necessary, he is required by the district attorney to make a post-mortem examination in the presence of two witnesses, and makes his report. If it is to the effect that death resulted from violence, the case is then investigated by the local public prosecutor. The medical officer is empowered to call in the aid of the chemist. To guard against negligence and fraud, if the examiner report that the death was not caused by violence, and the legal authorities be of a contrary opinion, they cause an inquest to be held in a prescribed manner.

The steps necessary for the proper identity and preservation of viscera, or other articles for analysis, are often neglected. The stomach is cut open, and the contents lost. The stomach containing poison is thrown into the same vessel with other viscera, and thus all are impregnated with poison. Evidence of absorption and diffusion of poison through the body during life is thereby entirely destroyed. Stomachs have been sent for analysis wrapped

only in brown paper. On one occasion, two stomachs (of children poisoned) were sent in bladders, unlabelled. The identity of these at the subsequent trial for murder could only be made out by the different colour of the string with which one bladder was tied. On another occasion, in a newly-papered room in which a body was examined, the stomach was wrapped in a portion of the paper-hangings lying about: these, as it happened, were coloured with an arsenical pigment, and the poison was thus transferred from the paper to the stomach.

The selection of the nearest medical man, or of any gentleman who will make an inspection and analysis for the statutory fee of two guineas, in a case of murder by poison, generally leads to a large expenditure subsequently for a further analysis before the trial, when the parts in which the poison would be most probably found have been destroyed. On such occasions it is the custom to condemn severely the medical and chemical gentlemen, who have probably, for the first time in their lives, undertaken a case of this serious nature upon the express order of a coroner, with insufficient remuneration for its performance. This is manifest injustice. The fault is in the system, and not in the men, who do their utmost to perform a difficult duty, for the first time, as well as they can.

If a coroner places the inspection of a body in the hands of one who is not well skilled in the appearances produced by poison or disease, it is obvious that a serious mistake may be committed, which may implicate an innocent person. If he places a stomach for analysis in the hand of an inexperienced analyst, it is not the fault of the analyst (whose living depends on his practice) if he undertakes it, and falls into some grievous act of omission or commission. The error is rather with the system; and the sooner it is abolished, and a more reasonable mode of proceeding substituted, the better.

There is for these defects a simple remedy, which is often now resorted to by coroners in cases demanding great medical and scientific skill—in other words, the evidence of *experts*. The necessity of employing experts, more especially in supposed cases of poisoning, is now generally admitted. A coroner has only to make a representation to the Home Secretary, giving satisfactory reasons why an analysis is needed, and an expert is appointed at no cost to the coroner. Some coroners, though aware of this privilege, are, nevertheless, unwilling to avail themselves of it; and instances are known of a coroner insisting on an analysis being made by a local practitioner, spite of his declared inability to make an analysis. After a coroner's inquiry, the whole of the proceedings are sometimes directed to be re-heard before a magistrate or magistrates, who can analyse and sift evidence, and can bring the minds of educated men and trained lawyers to bear upon the facts. A proper analysis and inspection are then made, and the case in this complete form goes before an Assize court for trial. If this is done occasionally in cases of importance, why not in all cases that are now properly the subjects of a coroner's inquiry? Let a well-trained gentleman be appointed as a stipendiary judge in every county or borough; let him, upon the same sources of information as are now open to the coroner, hold inquiries or not, according to his judgment. There are many coroners who are quite competent to fill such an office. In each county, or district, there should be appointed a surgeon—skilled in the inspection of the dead body, and in a knowledge of the causes of death; and a chemist, skilled in the processes for the detection of poisons. To these three officers, and, if necessary, to assistants appointed by and under them, all inquiries into crimes connected with the death of persons should be exclusively remitted. Proper salaries for skilled surgeons and analysts would secure competent men, and probably turn out in the end to be less costly than the present system.

The duties of sanitary officers might perhaps be shared by the medical and chemical officers appointed to these offices.

Some such regulations as these must sooner or later be made if the public desire to have the duties of an important office properly performed. The value of life is said to be greater in England than in any other country; but this remark applies only to cases of crime which are actually detected, and to the prosecution and punishment of criminals. We are greatly inferior to France and Germany in our means for the scientific detection of crime and murder by secret poisoning. In the case of Palmer (1856), there was evidence to show that his wife, his wife's mother, two of his children, his brother and one of his personal friends, had all died from poison under his roof, within two or three years before the death of Cook—for the murder of whom Palmer was tried and convicted. His wife had been poisoned by tartar emetic, and his brother by prussic acid. The deaths of at least two others in his house were probably violent. Where was the coroner's inquest for the protection of life? The initiation of proceedings is often placed in the hands of a police constable or a coroner's beadle, instead of being directed by the public prosecutor.

Inspections.—The necessity for appointing a skilled independent inspector of bodies in all suspected cases demanding inquiry, will be apparent from other considerations. Under the present system, a person who has destroyed the life of another by poison may be present at the post-mortem inspection of the body of his victim, and may use his efforts to defeat the objects of the inquiry. Palmer, a medical man, was thus allowed to be present at the inspection of the body of Cook. He nominated the persons, one of them an inexperienced young man who had never before inspected a body in a case of death from poison, and he stood over them while they were engaged in the office. The stomach of the deceased when received for analysis was cut open throughout its length. The injury to this organ, by which at least a portion of the contents was lost, occurred during the inspection, and is said to have arisen from Palmer having accidentally (as it was alleged) pushed against the youth who was making the inspection. After the viscera had been placed in a jar and secured with a bladder, Palmer found an opportunity of cutting the bladder with a knife and inverting the jar, and this probably led to a further loss of the contents. In another case of exhumation, the viscera had been carefully removed and placed (as it was supposed) in separate jars, which were properly secured and labelled. When the jar labelled 'Stomach and Contents' was opened by the analyst to whom it had been sent, it was found empty. From inquiries subsequently made, there was but little doubt that a person who was interested in preventing an analysis was permitted to be present at the inspection, and that he had taken the opportunity, when the inspectors were otherwise occupied, of removing the stomach from the jar and again secretly returning it into the abdomen before the body was sewn up, or otherwise disposing of it. Acts of this kind should be impossible in the present day, and the best security against their occurrence would be the appointment of a skilled inspector in a district, to conduct all post-mortem examinations for coroners' inquests.

A charge of malapraxis is sometimes raised against a medical man in consequence of the death of a patient. The examination of the body may, by order of a coroner, be unknowingly placed in the hands either of a professional rival, or of a friend of the person inculpated. This is not just either to the practitioner or the public. There is nothing more easy, medically speaking, than to exaggerate appearances in a body, or to assign to the action of medicines, or to the use of surgical instruments, post-mortem conditions to which an independent and experienced anatomical inspector

would probably attach no importance. Supposing the question to be that a patient has died from an overdose of opium, said to have been found in the stomach—if the analysis has been intrusted by a coroner to any professional rival, or to an incompetent analyst selected by him, the injury done may be irreparable. Such cases have occurred and must occur until special inspectors are appointed in place of men who are now taken by chance, by the fact of their living in the vicinity, or of their being called to see the person while dying.

If a person has had poison administered to him feloniously and he recovers, the facts of the case are duly investigated by a magistrate, the evidence is carefully sifted, analyses are properly made when required, and the depositions are so drawn up as to form a correct basis of proceedings for the trial of the accused. If, however, the person dies from the poison, the case then goes before a coroner and a coroner's jury; and although the medical and other questions which arise are usually of greater importance, they are now dealt with by men frequently incompetent to understand them, and who are not always qualified to elicit the facts or put them into a proper shape for trial. Hence it is that, unless a true bill has been found by a Grand Jury at the Assizes, or the alleged criminal has been committed by a magistrate, no prosecution is commonly instituted. The proceedings taken before a coroner are in this case disregarded.

There is no doubt that a large number of these officers might be retained with benefit to the public, but the system of nomination by election should be altered. Tried and competent men only should be appointed, and in place of a jury they should have the assistance of persons skilled in a knowledge of the causes of death and in conducting post-mortem examinations and analyses. Under the present system coroners are empowered by the Medical Witnesses' Act (6 and 7 William IV. c. 89) to issue an order for the attendance of any legally-qualified practitioner: a fee of two guineas is the maximum allowed for making a post-mortem examination, giving evidence, and, if considered necessary by the jury, a chemical analysis of the stomach and intestines, except the Home Secretary orders an analysis by an expert. A penalty of five pounds is attached to disobedience of this order, except for reasonable cause. Rumsey has correctly represented the unsatisfactory position in which medical men are placed by such an arrangement. He observes: 'It is no discredit to a practitioner engaged in the toilsome routine of ordinary medical duties, if he should feel himself at a loss when called upon for a decisive opinion in some obscure case of poisoning or infanticide. His scanty opportunities for the study of these subjects and for making post-mortem examinations cannot suffice to qualify him for answering the delicate and important questions which he must answer before a jury can find a proper verdict.' . . . 'The custom of indiscriminately summoning medical practitioners of all sorts, and of all degrees of pathological knowledge and forensic skill, has sadly depreciated the value of medical evidence in courts of justice. Public confidence in the profession has been shaken, and the appearance of a "doctor" in the witness-box is but too often a signal for sport among gentlemen of the long robe.' ('Essays on State Medicine,' p. 356.) There appears to be no fee for attendance at an adjourned inquest.

No man can be compelled to undertake that which he feels incompetent to perform, and medical practitioners who have felt this want of experience usually decline to make chemical analyses involving so serious a responsibility. It is thus that, in many cases of importance, analyses for coroners' inquests are now referred to chemical experts, and the practitioner discharges himself of that responsibility which the Medical Witnesses' Act imposes upon him without any adequate remuneration.

Medical men are too ready to give their opinions of the cause of death for a coroner's inquest without making an inspection of the body. No man is compellable to give an opinion upon insufficient data, and if by the institution of a judicial inquiry there are grounds for believing that a death has not been natural, no medical opinion of the cause should be given in the absence of an inspection. Such an opinion must always be conjectural, and may involve a medical man in an unpleasant responsibility.

Trial at the Assizes.—The next stage of the proceedings in a criminal case brings a medical witness before a Superior Court. For this purpose a *subpœna* is issued. It need hardly be observed that every witness is bound to obey a subpœna, when with it his reasonable expenses for journey, &c., are tendered to him, but he is not bound to attend at the trial except upon a subpœna. There are some questions connected with this subject which it will be proper to consider in this place. *If a subpœna is served on an ordinary or skilled medical witness, is he bound to obey it?* In *Betts* v. *Clifford* (Warwick Lent Ass., 1858) Lord Campbell stated, in answer to a question, that a *scientific witness* was not bound to attend upon being served with a subpœna, and that he ought not to be subpœnaed. If the witness knew any question of *fact* he might be compelled to attend, but he could not be compelled to give his attendance to speak to matters of *opinion*.

In *Rich* v. *Pierpoint*, an action for malapraxis, Dr. Lee was summoned against his will to give evidence on the part of the plaintiff. He stated that on the evening before the trial a solicitor called on him and left a subpœna with him. Lee would not hear any account of the case which the solicitor proposed to give, and expressed his resolution to have nothing to do with the trial. The solicitor informed him that he would be required to pay the usual penalty if he did not attend. He went down to Kingston, and was warned not to leave the Court until the trial was over. He heard the evidence on the part of the plaintiff, and upon this and the medical evidence he gave his opinion—not much in favour of the party who summoned him, and not much against him. Dr. Lee considered that he could not avoid attending the trial under these circumstances. ('Med. Times and Gaz.,' 1862, I. p. 389.)

In the case of *Webb* v. *Page* ('Carrington and Kirwan's Rep.,' p. 23) Maule, J., ruled as follows:—'There is a distinction between the case of a man who sees a fact and is called to prove it in a Court of Law, and that of a man who is selected by a party to give his opinion on a matter on which he is peculiarly conversant from the nature of his employment in life. The former is bound, as a matter of public duty, to speak to *a fact* which happens to have fallen within his own knowledge—without such testimony the course of justice must be stopped. *The latter is under no such obligation;* there is no such necessity for his evidence, and the party who selects him must pay him.' In the case referred to a skilled witness had been subpœnaed, but refused to give evidence unless first paid for his services and loss of time ('Med. Times and Gaz.,' 1862, I. p. 432). A barrister, who quotes this ruling, goes on to say: 'There is one reason why I should not advise any person in the position of a skilled witness totally to disregard a subpœna. It is quite clear that should such a person fail to attend a trial no attachment could issue, even if he were called as is usual upon the subpœna, because the party subpœnaing him could not make the requisite affidavits that he was damnified by the witness's absence and in what respect. But such party might bring an action for damages; and although he would recover none, he might not only worry, but might even put the defendant to a considerable expense, as taxed costs by no means include the entire costs in such cases. Although, therefore, I could not

advise a total neglect of the subpœna, the safest course would be to obey it, and demand expenses before giving evidence. Such expenses would be only those allowed for a professional witness (not special fees); but if the person so subpœnaed were willing to run the risk of an action, he might safely absent himself without any fear of an attachment from the Court for contempt.' With regard to the question whether a skilled witness would be permitted to demand a high fee for his attendance under such circumstances, the writer adds: 'To permit him legally to demand a high fee would perhaps look somewhat like legally countenancing a bribe.' At all events there is no such legal recognition. A witness subpœnaed to depose as to facts cannot refuse to give his experience as to these or any other facts of the case.

In the case of *Maxsted* v. *Morris* (Court of Exch., May, 1868), a witness wilfully disobeyed a subpœna. In consequence of this the trial was postponed, and the parties were put to great expense. An arrangement was made by which the witness bound himself to pay a part of the expenses. The Chief Baron said: 'It must be distinctly understood that in all cases where it appeared to the Court that there had been a wilful disobedience of a subpœna after proper service, such a contempt of Court would be visited with the punishment it deserved.' Martin, B.: 'It was not to be tolerated that a man should exercise any discretion as to whether he would or would not attend a Court in pursuance of a subpœna. Enormous costs were incurred in preparing a case and in bringing it down to trial, the whole of which were to be thrown away and wasted because a man refused to obey a lawful summons to attend as a witness.' Pigott, B.: 'A subpœna was not to be treated as mere waste paper. Public justice required that persons wilfully committing contempt of Court should be dealt with in such a manner as to teach them that they could not commit a contempt of Court with impunity.'

The question may not be one of fees, but of obedience to a simple order to attend and give evidence on matters of *opinion* irrespective of scientific facts. In a case before Vice-Chanc. Wood (*Simpson* v. *Halliday*, 1864) the author was required to attend on a subpœna as a skilled witness, to give evidence of *opinion* in reference to the alleged infringement of a patent. The defendant, who summoned him, did not make it in any way a question of fees; but being wholly unacquainted with the facts of the case, he did not feel in a position at a short notice to appear as a witness for parties of whom he knew nothing. The author obeyed the subpœna, as the disobedience of it might have been, in the uncertain state of the law, a contempt of Court; and after giving evidence, requested his Honour to state for future guidance whether a skilled witness was compelled to attend under such circumstances as those in which he had attended; and referred him at the same time to the decision of Lord Campbell in *Betts* v. *Clifford*. The Vice-Chanc. said that a Court of Law never gave an opinion on a speculative question, and there the matter ended.

It would seem therefore that a skilled witness, who is not acquainted with *any of the facts* of a case, may be compelled by a subpœna to attend and give evidence on a matter involving scientific opinion alone. Some months before this occurrence the author had given evidence in a similar case, and the defendant Halliday, seeing that his opinion in that case was favourable to his views, exercised a right to impound his services. When some portions of the public press undertake to censure experts for acting as hired witnesses, it may be as well to remember that they may be sometimes unwillingly forced into Court by subpœnas which they dare not disobey.

Lord Campbell's dictum in reference to the distinction between fact and

opinion confers no practical benefit on witnesses. It is at all times difficult in science, and in the medical sciences particularly, to separate them; and if a man appears to testify to a medical or scientific fact, he cannot avoid giving an opinion arising out of the fact. In an action against a druggist for a mistake in compounding medicine an attempt was made to procure the author's *opinion* as a skilled witness at the trial by reason of *facts* obtained from the report of a chemical analysis, the object of which was at the time entirely concealed from him. The suit was compromised, and his attendance was not necessary; but such a case should convey a caution to chemical experts. They may be employed secretly and under untrue statements to make analyses; these become *facts* on which they may be summoned like ordinary witnesses to give *opinions* as skilled witnesses, while the payment of the usual fee for a skilled witness is evaded.

A medical man may be placed in the disagreeable position of receiving separate subpœnas, to attend trials at different Assizes which are held at or about the same time. An obedience to both of them is clearly impossible—one at least must be sacrificed to the other. On one occasion the author was called from a civil trial which had commenced in the Assize Court at Durham to a criminal trial which was fixed to take place on the same day at Lincoln. The civil case was postponed, and he had so far the benefit of the opinion of one of the most learned judges on the Bench, that in all cases in which there were served separate subpœnas fixing trials for the same time, the civil should give way to the criminal case. The former can be postponed, the latter cannot. But if the subpœnas are for two criminal cases, the course of a witness should be to attend to that in which the subpœna was first served upon him.

CHAPTER 2.

COMPULSORY ATTENDANCE IN COURT—LICENSE OF COUNSEL—EXAMINATION IN CHIEF—CROSS-EXAMINATION AND RE-EXAMINATION—QUOTATIONS FROM BOOKS—PRESENCE OF MEDICAL WITNESSES IN COURT—RULES FOR THE DELIVERY OF MEDICAL EVIDENCE—TECHNICAL TERMS—MEDICAL EXPERTS—MEDICAL COUNSEL—CONFLICTING MEDICAL TESTIMONY.

Assuming that the medical man has obeyed the subpœna, he will now be required to attend before the Court, and to state, in the face of adverse counsel, the opinions which he has formed from the medical facts of the case, as well as the grounds for these opinions. He will then undergo the ordeal of a public examination.

Before being sworn to deliver his evidence, a medical or scientific witness may, in a civil cause, claim the payment of his customary fees, unless an arrangement has already been made between him and the solicitors who have sent him a subpœna. These fees are generally made a matter of private arrangement between the witness and the solicitor. Unless there is such an arrangement, or some written document to show an agreement as to the amount, the witness will be paid according to a tariff which will not even suffice to indemnify him for the expenses necessarily incurred by a journey to or residence in an assize town; not to mention the loss occasioned in his practice during this forced absence from it. This is necessarily a source of dissatisfaction among members of the medical profession. The country impounds their services for the administration of justice without

making a proper remuneration to them. In some exceptional cases a special application made to the Court may have the effect of rectifying this matter.

A solicitor who serves a subpœna is not liable for the fees. In a case in which an action was brought against a solicitor for the amount of the fees Bramwell, B., said: 'As a rule, an attorney was merely the agent of another person, and if he simply subpœnaed a man, he was not liable, the witness's action for expenses being against the principal.' This shows the necessity for a special agreement.

Some medico-legal writers have considered it necessary to lay down rules respecting the manner in which a medical witness should give his evidence; how he is to act on cross-examination, and in what way he is to recover himself on re-examination. Any advice upon this head appears to be superfluous; since experience shows that these rules, like those given to prevent drowning, are invariably forgotten at the very moment when the individual is in the situation in which he most requires them. A man who goes to testify to the truth to the best of his ability should bear in mind two points. 1. That he should be well prepared on all parts of the subject on which he is about to give evidence. Let him remember on these occasions the advice contained in the Latin motto, *ne tentes aut perfice.* 2. That his demeanour should be that of an educated man, and suited to the serious occasion on which he appears, even although he may feel himself provoked or irritated by the course of examination adopted. A medical witness must not show a testy disposition in having his professional qualifications, his experience, his means of knowledge, or the grounds for his opinions very closely investigated: he should rather prepare himself to meet with good humour the attempts of an adverse counsel to involve him in contradiction, and show by his answers that he has only a desire to state the truth. Law and custom have long established that a barrister, in defending a prisoner charged with murder, has a right to make use of all fair and even what may appear at the time to the witness unfair means for the defence. Nothing can tend more to lower a witness in the opinion of the Court and jury, or diminish the value of his evidence, than the manifestation of a disposition to deal with his examiner as if he were a personal enemy, to evade the questions put, or to answer them with flippancy or anger. All such exhibitions invariably end in the discomfiture of the witness. It has been suggested that medical men on these occasions might take a lesson from lawyers, and observe how little they allow forensic differences, which they put on with their professional costume, to influence them in their intercourse with each other, or with an adverse judge or jury.

License of Counsel.—Medical men have complained, and on many occasions justly, of the license of counsel. On this subject it may be well to consider what has been said by one of the highest authorities on the Bench, Erle, C.J.:—'The law trusts the advocate with a privilege in respect to the liberty of speech which is in practice bounded only by his own sense of duty; and he may have to speak upon subjects concerning the deepest interests of social life and the innermost feelings of the soul. The law also trusts him with a power of insisting upon answers to the most painful questioning, and this power again is in practice only controlled by his own view of the interests of truth.' (Judgment in *Kennedy* v. *Brown*, 1862.) Thus it will be seen that almost unlimited powers of interrogation are entrusted to counsel by the law, and it is a question whether the unrestricted use (which it has been justly remarked means only the frequent abuse) of these enormous powers is necessary or even favourable to the administration of justice. One of the most severe reprimands on this abuse came from the same judge in a case which was before him in 1857, and was to this effect:—A question had been put throwing on the witness

an imputation for which there was really no foundation. The judge then said: 'The freedom of question allowed to the bar was a public nuisance, and the barrister who made such an imputation ought to be prosecuted. If a question had relation to the truth, he was most anxious it should be put; but to cast haphazard imputations at the suggestion of a person (an attorney) who might have no scruples as to what he did, was a degree of mischief that made him wish that a party should be prosecuted. He begged leave to say that in his experience he had seen counsel so abuse their privilege that he had cordially wished a power could be instituted that they might be prosecuted for a misdemeanour.' It is the general practice to say that the obnoxious questions are in the instructions, but a barrister can always exercise a power of putting or not putting a question which may be found there. Mellor, J., observed on one occasion that 'he did not approve of counsel throwing everything upon the attorney. The counsel who put an improper question ought not to be shielded merely because he had been instructed by an attorney. Counsel should always exercise caution in putting a question.' By putting it he clearly adopts it, and frequently to the great damage of his own case. This is at present the only check upon the practice, for judges seldom interfere unless directly appealed to by the witness.

Some medical men have claimed a privilege not to answer certain questions which are put to them, on the ground that the matters have come to their knowledge through private and confidential communications with their patients. The law concedes no such special privilege of this nature to members of the medical profession. No man is bound to reply to any question if the answer would tend in any way to incriminate himself—for no man is compellable to be a witness against himself. With this exception all questions must be answered, provided they are relevant to the case, and their relevancy is a matter for the consideration of the presiding judge. Sometimes a witness makes a frivolous objection—the refusal to answer an ordinary question—bringing only ridicule upon himself. A skilled expert, at an important trial, was asked his age. Instead of answering so simple a question at once he angrily appealed to the judge to know whether he was bound to give an answer on a matter which, as he said, could have nothing to do with the case. The judge informed him that unless he had some very strong reasons for concealing it he had better state it. At a trial for murder by poison, in the course of a cross-examination counsel for the prisoner asked the medical witness what remedy or antidote he had employed when he was first called to attend the deceased. He appealed to the judge to know whether he was bound to answer such a question as that. *Judge:* 'Yes, unless you have reason to believe that your antidote killed the deceased. In that case you are not bound to answer it.' The question was immediately answered.

As there is no special privilege granted to members of the profession, a witness must remember that there are *no medical secrets*. In the case of the *Duchess of Kingston* this privilege of withholding statements was claimed by a medical witness but denied. In a case in which a female was indicted for the murder of her infant a surgeon was called to prove certain confessions made to him by the woman during his attendance. He objected, on the ground that he was then attending her as a private patient. Park, J., said this was not a sufficient reason to prevent a disclosure for the purposes of justice, and he was ordered to answer the questions. (Beck's 'Med. Jurisp.') At the meeting of the British Med. Assoc. at Leeds (Aug., 1869) Mr. Bateman said, 'There are many cases in which a doctor cannot discharge his duty to a sick person without putting questions the replies to which may criminate the patient, or seriously affect his interests, and these

replies the doctor is now called upon to communicate, either in a civil or a criminal Court.' A case was mentioned in which two sisters were servants to an old lady. One of them became pregnant, miscarried, and was attended by a surgeon. The mistress, who knew all about the matter, retained the girl in her service, and left her a legacy at her death. The will was disputed by the heir-at-law on the ground of undue influence, and at the trial, in order to injure the girl's character, the surgeon was called, and asked for what illness he had attended her some years before. Believing that he had a privilege, he refused to answer, but it was decided by Kindersley, V.C., that he had no privilege, but was bound to tell all he knew, and this decision put him to an expense of 30*l.* for costs. In cases of a criminal kind the same point has several times arisen; and it has even happened that the reply made by the accused to a doctor's professional question has been the sole evidence on which a conviction could be based. It will be perceived, therefore, that any statements which are made to physicians or surgeons while attending persons in a private capacity, although they are not to be volunteered in evidence, must be given in answer to questions whatever consequences may ensue. Cases of poisoning and wounding, duelling, as well as cases which involve questions of divorce, or the legitimacy of offspring, may be materially affected by the answers of a medical man on matters which have been the subject of private communications. The difference between the English and the French practice will be seen by reference to a paper by Hemar, 'Ann. d'Hyg.,' 1869, vol. i. p. 187.

Examination-in-chief.—The ordinary course of proceeding in a criminal case is thus concisely stated by Stephen ('Criminal Law of England,' pp. 168, 282). After opening the case the counsel for the Crown calls the witnesses, and examines them according to the rules of evidence—that is, he brings out by questions *which do not suggest their answers*, the facts relevant to the issue to be tried which are within his personal knowledge. Those questions which suggest the answers are called "leading" questions. With one exception it is not the practice to allow these to be put in this part of the examination. The exception according to Stephen is: 'When the judge is satisfied, either by a witness's demeanour or by contradictions between the evidence and the depositions, that he is trying to keep back the truth and favour the prisoner, he may in his discretion allow the counsel for the Crown to ask leading questions and, as the phrase is, to treat the witness as hostile.' When the examination-in-chief has been given, the next step is the cross-examination.

Cross-examination.—In this, the second stage, the counsel for the prisoner extracts from the medical witness, by questions *which may suggest the answer in the strongest form*, any facts that may appear to be favourable to his client, and which he believes to be within the witness's knowledge. Leading questions are not only allowable in this part of the examination, but, according to good authority, a counsel for the defence can hardly lead too much. The theory of the law is that the witness is unfavourable to the prisoner and has come to bear evidence against him. The more he has shown himself, by conduct or conversation, a partisan in the case, the more severely will he be treated. Anything which he may have said in the hearing of others, or published in journals, or even written in private letters (if the contents transpire), in reference to the case or the guilt of the prisoner, is now brought to light, although he may have supposed that what he did say was in perfect confidence. It is at this stage of the case that any exaggerations which may have been most favourably received by the counsel for

he prosecution are reduced to their true proportions. Any bias by which he mind of a witness may have been influenced, or any imperfection or onfusion of memory as to facts, is here brought out. (Stephen, p. 177.) t is in this part of his examination that the witness will be closely questioned as to his qualifications, the time during which he has been engaged n practice, the accuracy of his judgment, his general professional knowledge, and his special experience in reference to the matter in issue, the number of cases he has seen, &c. Straightforward answers should be given to all these questions. No harm can be done to the witness by the answers unless they are given evasively, since it is not to be supposed that the witness wishes to represent himself differently from what he is. If he does make the attempt, he will assuredly fail. The most striking distinction between the examination-in-chief and cross-examination is in reference to leading questions. It rests upon the assumption that there is a danger that a witness will say whatever is suggested to him by the one side, and conceal everything that is not extorted from him on the other. It need scarcely be observed that witnesses whose evidence is of little importance in the case are rarely cross-examined. This, however, is reserved in its most stringent form for those whose knowledge of facts and whose opinions are likely to influence the fate of a prisoner in a criminal trial.

In dealing with a skilled witness whose evidence may be of importance, the questions in cross-examination are usually put by the counsel for the prisoner with great caution, or the answers brought out may be more adverse to his own case than those elicited in the examination-in-chief.

Re-examination.—The cross-examination is usually followed by a re-examination on the part of the counsel for the Crown, or of the counsel by whom the witness has been called. The object of this is to clear up or explain any portion of the evidence which may have been rendered obscure or doubtful by the cross-examination. It is sometimes unnecessary to put a question, and if the witness has given his evidence consistently and fairly no questions may be asked. As a rule the re-examination must be confined to those matters which have arisen out of the cross-examination. Any questions upon new subjects may render a further cross-examination on them necessary. In reference to *facts*, a medical witness must bear in mind that he should not allow his testimony to be influenced by the consequences which may follow from his statement of them, or their probable effect on any case which is under trial. In reference to *opinions*, their possible influence on the fate of a prisoner should inspire caution in forming them; but when once formed they should be honestly and candidly stated without reference to consequences. It will be well to remember, in regard to each stage of the examination, what a great medical authority has said:—'To make a show and appear learned and ingenious in natural knowledge may flatter vanity. To know facts, to separate them from supposition, to arrange and connect them, to make them plain to ordinary capacities, and above all to point out their useful applications, should be the chief object of ambition.' (William Hunter.)

Quotations from Books.—It is not unfrequent custom with counsel to refer to medical works during the examination of a witness. He is expected to have a fair knowledge of the writings of professional men in reference to the subject of inquiry. The authority is mentioned, the passage is quoted, and the witness may be then asked whether he agrees with the views of the author or whether he differs, and if so, his reasons. In cases connected with medical treatment, the views of the profession are and have been so various, that a barrister would have no great difficulty in finding some book to oppose to the opinions of the witness. Standard

works of recent date are so well known to the profession that there are few medical men engaged in practice who are not acquainted with and able to explain the views of the writers and how far they agree or conflict with his own. The witness must be on his guard that the quotation is properly taken with the context, or he may unexpectedly find himself involved in a difficulty. On one occasion the author found that a learned gentleman stopped in his quotation at a comma, and on another occasion a quotation ended at a colon—the remainder of the sentence in each case materially weakening the inference which it was intended to draw with the apparent sanction of the witness.

When a quotation from a standard work is thus opposed to the evidence of a medical witness, he should take care by reference to the work itself to see that the passage is correctly quoted. An instance of the importance of this caution occurred at the Swansea Lent Ass., 1869, when an action was brought against a railway company for compensation for personal injury. Plaintiff was proved to have had pneumonia shortly after the accident, and the counsel for the company wished to show that the pneumonia had not arisen from any physical injury, but from shock; and the author's work on 'Medical Jurisprudence' was quoted as referring to a case of pneumonia caused by shock. It was subsequently discovered, on referring to the work, that the case in question was one in which the lung had been wounded by a fractured rib. The cause of the pneumonia was thus sufficiently explained; it was proved to have been a result of physical injury and not of shock. A reference at the time to the work which is quoted is always necessary if any use is to be made of a quotation. Without suggesting that there is intentional misrepresentation to bear out a particular view of the case, a barrister, in dealing with the medical facts, may wholly misunderstand the author's views and statements, and in some instances wrongly assign to the author himself, opinions which he has merely quoted from other authorities for comment or illustration.

Presence in Court.—In England medical and scientific witnesses, except under special circumstances, are allowed to be present in Court and hear the whole of the evidence in the case. This is in some instances absolutely necessary if the Court requires medical opinions, for unless the witnesses are fully acquainted with the facts they can give no opinions, and they can only become fully acquainted with the facts by being allowed to be present and hearing the evidence in Court. If excluded, the judge or counsel will be compelled to read to the witness notes of the evidence before an opinion can be given, and it may then appear that some small point which counsel did not think of importance is omitted: this if known to the witness might, however, materially affect his opinion. A failure of justice is likely to occur when medical witnesses are excluded, and it is generally where there is no defence or a false defence that the right of excluding them is exercised. The rule in Scotland is different; medical witnesses are there rigorously excluded from Court until after they have delivered their evidence.

The examination of the witnesses for the Crown is followed by the defence of the prisoner, either in person or by his counsel, who acts throughout the part of an advocate, simply securing for his client every advantage the facts or the law may afford him. In other words, he sees that his client is strictly tried according to law, and not condemned contrary to law.

A key to some of the difficulties which medical witnesses must be prepared to encounter will be found in the exposition given by Stephen of the tacit rules which regulate the duties of counsel for the prosecution and defence:—'In practice it is universally admitted that the counsel for the prosecution is morally and professionally bound always to keep in sight

e ultimate object—namely, the discovery of truth; whereas no such ligation is laid upon the prisoner and those who represent him, because is too much to expect of human nature that they should discharge it, and is better not to impose an obligation which is sure to be systematically olated. Both sides, on the other hand, are bound in the strongest way *t to do anything to propagate falsehood.* The counsel for the Crown is ound not to suppress any fact within his knowledge favourable to the isoner; and, on the other hand, the counsel for the prisoner is bound bring to light facts within his knowledge unfavourable to the prisoner. he counsel for the Crown may not use arguments to prove the guilt of e prisoner which he does not himself believe to be just, and he is bound warn the jury of objections which may diminish the weight of his arguents: in short, as far as regards the evidence which he brings forward, s speech should as much as possible resemble the summing-up of the dge. He should contend not for the success of his cause at all events, it for the full recognition by the judge and jury of that side of the truth hich makes in favour of it. On the other hand, the counsel for the prisoner ay use arguments which he *does not believe to be just.* It is the business the jury, after hearing the judge, to say whether they are or are not st.' (Op. cit. pp. 160 and 168.) The last remark shows what appears be a serious defect in the administration of the criminal law. While in case of misdemeanour a prisoner may be tried by a special jury, in a case felony, involving an analysis of important questions of medical science reference to murder or manslaughter, the trial takes place before a ommon and comparatively ignorant jury. Such a jury is hardly in a osition to cope with an ingenious counsel, who has it in his power to isrepresent and distort medical facts and opinions in any manner that he leases. The chapters on Infanticide will furnish numerous illustrations of he measure which counsel take of the intellectual capacity of common uries. The defences made are frequently such as no counsel would venture o place before a jury of educated men. These 'sensational or powerful" ddresses, as they are termed by the press, full of burning eloquence and mpassioned logic, have frequently withdrawn the attention of the jury rom the real facts, and have procured verdicts of acquittal contrary to the vidence and all the medical circumstances of the case.

Another observation made by Stephen more nearly concerns the nedical witness:—'There are many obligations which affect each side qually. Neither is at liberty to attempt to browbeat, intimidate, or conuse a witness, although they may expose any real confusion which exists n his mind, or test, by the strictest cross-examination, the accuracy of his tatements. Neither is at liberty wilfully to misunderstand a witness, or o *misstate, in his address to the jury*, the effect of what he has said, either y distortion or suppression. The neglect or observation of these and ther rules of the same kind practically establishes a wide distinction, and ne which is easily recognized, between those who exercise a noble profession nd those who disgrace it.' (Op. cit. p. 168.)

Assuming that the witness is properly prepared for the discharge of is duties, and that the questions put to him are answered fairly and truly, ccording to his knowledge and experience, without exaggeration or concalment, he has no reason to fear any attempt at intimidation. Barristers, or the most part, know that by this line of conduct they lose more, even ith a common jury, than they gain by the attempt to confuse the witness; nd as their ultimate object is a favourable verdict, they will generally oid conduct which must necessarily place this verdict in jeopardy.

The normal barrister, as depicted by Stephen, is not at liberty, in his ddress to the jury, to misrepresent, either by distortion or suppression,

the medical facts or opinions given in a case. According to the author's experience, however, misrepresentation is a not unfrequent practice, and one of which medical witnesses have very strong reason to complain. Whether such misstatements are in some cases wilful or not it may be difficult to determine, but their effect on the jury is well known to those who employ them, and they frequently escape the observation of counsel on the other side, and even of the judge, unless he happens to be well versed in medical subjects.

Intimidation is sometimes carried too far. On a trial for murder by poisoning, a respectable country practitioner, who had given his evidence for the Crown in a fair and proper manner, was thus addressed in cross-examination by counsel:—'On your solemn oath, Sir, and in the face of the whole profession, will you venture to persist in that statement?' Again, the intimidating modes of address—'Do you mean to swear?' 'Will you pledge your professional character?' &c., intermingled with the admonitions, 'Pray be careful,' 'Be cautious,' &c., may suggest to the witness that his examiner already regards him as perjured, and that however truly he may state the facts within his knowledge, he will not be believed.

A public writer, in commenting on this subject, says, 'But the hardest and most unfair part of the system (of cross-examination) is when witnesses have to bear a loud and insulting tone or gesture without remonstrance or retaliation.' At the trial of Kelly for the murder of Police Constable Talbot (*Reg.* v. *Kelly*, Dublin Commis. Court, Nov., 1871), Tuffnell, a surgeon of repute, and formerly Professor of Surgery, was summoned as a witness for the prosecution. Having deposed to the nature of the wounds, and that the deceased died from the effects, he was subjected to the usual ordeal of a cross-examination, but in a somewhat unusual form. Counsel for prisoner having begun by addressing him in a loud and offensive tone, he turned to the Chief Baron, and said, 'My lord, I am very excitable, and if this gentleman has a right to roar at me, I consider that I have a right to roar too.' The Court expressed a hope that it would not be necessary for him to roar, and intimated, after a short trial of vocal strength between the two opponents, that counsel's manner to the witness was not what it ought to be. Counsel disclaimed any intention of being offensive, but claimed the liberty which is usually conceded in cases of importance. Whatever may be the importance of a case to a prisoner, nothing can justify the putting of questions in a loud and insulting tone to a skilled professional witness.

I agree with a writer whose opinion has been already quoted, that 'Every contemptuous and even uncourteous expression, every query leading nowhere, except to the end of confusing the mind or irritating the temper of a witness, ought surely to be reckoned as overpassing the legitimate limits of the counsel's office, and as such be regarded with universal disapprobation.' That the administration of justice should be aided by this mode of dealing with medical witnesses is impossible. It may be that criminal cases fall more into the hands of the second class of barristers to whom Stephen alludes—namely, those who disgrace a noble profession. But it is a widely spread opinion in the medical profession, that this style of examining educated men, who are perhaps compelled most unwillingly to appear on a subpœna to testify to facts, is certainly not adapted to elicit the truth, but rather to favour the escape of criminals and give impunity to crime.

It may be fairly admitted that a man who puts himself forward as a witness, and attempts to elucidate what he only succeeds in rendering more obscure, should receive no favour at the hands of the bar. Elwell, a member of the legal as well as of the medical profession, observes that—

No witness is ever compelled to appear and testify to what *he does not know.* He may be compelled to attend in Court in obedience to a subpœna; but he attempts to testify upon a subject requiring *opinions* upon which he has no well-settled or well-defined ideas, it is his own fault, and he alone is to blame; for no one but himself can know so well as he, until he has exposed himself, how unfit he is for the occasion.' (Medico-legal Treat. on 'Malpractice and Med. Evid.,' by J. J. Elwell, New York, 1863, p. 302.) But let us take the case of a practitioner who, in a country district, has gone through twenty years of practice with honour and credit in his neighbourhood, and who is suddenly called to a case in which a man is found dead from a wound in his throat. Under the Medical Witnesses' Act he is compelled to make an examination of the body for a Coroner's inquest. At a great loss of time, and for no adequate remuneration, he attends the inquest and gives his evidence; he is bound over, *nolens volens*, to appear for the first time as a witness at a criminal trial, and to testify, 1st, to the throat being cut, and 2ndly, to give his opinion to the Court on the cause of death, and whether the wound was inflicted by the deceased on himself, or by another person. A medical man who limited himself to the statement of the bare fact that the deceased's throat was cut need not appear at all, for this evidence might be supplied by a constable or policeman; but the law presumes from his profession, that the medical man made a proper examination of the wound, with a view to determine, to the best of his ability, whether it was the cause of death, and whether it was or was not self-inflicted. It is difficult to understand how a medical man, although before this occurrence he may never have seen a case of cut-throat, could excuse himself from giving answers to these questions, both of which involve purely matters of *opinion*. If he excused himself altogether from giving answers, there would be a failure of justice, and no conviction for such a common form of murder could ever take place. If, on the other hand, he answers these questions to the best of his ability, he may reasonably complain that while thus compelled to appear as a witness to testify to what he knows, his evidence should, by rules of law, be made the subject of abuse and ridicule before his neighbours, when he expresses his *opinion* from the facts; and that the counsel who examines him possesses an unlimited power of misrepresenting his views. A medical man is certainly not benefited in public opinion by being described as an ignoramus or a blunderer in his profession, whom no one ought to trust. The truth is, in medical evidence, facts and opinions cannot be entirely separated; and if medical practitioners were restricted in their evidence only to those facts which they observed in a case in which no other professional man saw the person living or dead, it is difficult to understand how crime could be detected and punished. These remarks of course do not apply to cases in which the opinions of medical experts can be taken. Here it would be desirable that one who has not had experience on the subject should avoid giving any opinion; he might simply state the facts, and decline for want of experience to give an opinion on the conclusions to which they lead. In pursuing any other course, he will find that the whole weight of the cross-examination will fall upon him.

There are other remarks on this subject made by Elwell, which those who are compelled to attend as witnesses in a Court of Law will do well to bear in mind:—'However anxious an incompetent witness may be to appear learned, and however hard he may labour to show it, he will ever find it a difficult business to make the Court and counsel believe that he is really so. To appear really learned, he must be able to make the subject on which he gives an opinion *clear*, and to give *satisfactory reasons* for this

opinion. He must be not only a thinker, but must satisfy others that he is master of the subject. Take almost any one of the important scientific questions upon which a professional witness is called to pass an opinion, and unless he has *looked at the subject before with a purpose to understand it*—comprehending its extent, weight, and relations—he will find it to have suddenly assumed an importance he had not suspected, just at the time when the discovery will add to his confusion. It is better to make this discovery in the quiet stillness and security of solitude, than under the eye of a judge and the severe scrutiny of counsel. A man, whether learned or not—whether in Court or out of Court—will talk clearly upon a subject he well understands, whether it is scientific or otherwise; but *unless it is clear in his own mind his account of it will be confused and unsatisfactory.*' (Op. cit. p. 303). This is undoubtedly the test to which every man should rigorously submit himself before entering the witness-box. The case should be viewed in all possible aspects, and if an opinion has been formed, it should be dealt with and criticised as if it were that of an adversary. As in controversy, a disputant should put himself as much as possible into the position of his antagonist, and see the question from his point of view. In this kind of self-examination it may be well to remember two points—1st, that there is no opinion so certain as that the human mind, if left to itself, will not raise a difference of opinion upon it; and 2ndly, that a man is never so near an error as when he claims a complete immunity from error.

Rules for the delivery of Evidence.—There are a few rules bearing upon medical evidence which, if observed, may save the witness from interruption or reproof and place him in a favourable position with the Court:—

1. The questions put on either side should receive *direct* answers, and the manner of the witness should not be perceptibly different whether he is replying to a question put by the counsel for the prosecution or for the defence.

Most of the questions put by counsel in cross-examination will admit of an answer 'yes' or 'no.' If, from the ingenious or casuistical mode in which the question is framed the witness should feel that the simple affirmative or negative might mislead the Court, then, after giving the answer, he can appeal to the judge to allow him to qualify it, or add to it any matter within *his own knowledge* and which is at the same time relevant to the case. The witness must remember that he takes an oath to state the truth, *the whole truth*, and nothing but the truth. On the other hand, while the counsel for the defence is bound not to introduce falsehood, his object is *not* the discovery or development of truth. Unless the witness is on his guard, he may find that his affirmatives and negatives may be worked into a shape representing the reverse of what he intended, when the learned counsel who has cross-examined him addresses the jury.

Some counsel adopt the ingenious plan of compressing two or three questions into one. A witness unthinkingly answers the last, or that which most fixes his attention. The same answer may not be strictly applicable to all, but the witness may find, when too late, that it is made so in the defence. In this case he should ask for a severance of the questions and give separate replies.

Direct answers are necessary, because it is only by them that the case can be brought clearly before the Court and jury in all its details. Medical witnesses sometimes forget this, and fall into answers to questions floating in their own minds, or which they think are likely to be put to them. They are also sometimes disposed to anticipate many questions by one general answer. This simply creates confusion, and the witness will be told by

to keep to the question, and that he is coming to the other matters
y.

case involving a question of compensation for personal injury as a
f a railway accident, medical witnesses were called on both sides.
orter of the trial observes, in reference to the evidence of one of
lical witnesses for the plaintiff: 'In the course of a long cross-
tion, this witness appeared to avoid giving "direct" answers to the
s put to him, and to affect to misunderstand them, to such an
s to draw from his lordship the remark, "Do pray, Dr. ——, be a
re candid."' From some judges a witness thus acting would have
h a much more severe rebuke. A witness should remember, at all
hat he takes an oath to state the *whole* truth.

should be taken by the medical witnesses not to argue with
. Argument is not evidence, and the entering into it disturbs the
the proceedings. Arguments between counsel and witnesses, and
tween medical witnesses themselves, are freely allowed in the French
but in England such a practice is not recognized. The mode in
questions are put by counsel in cross-examination sometimes tends
ntroduction of argument, but the witness should avoid the tempta-
nter into it. What he says under such circumstances is not evidence,
in the form of answers to questions, and he is there only for the
of stating what is relevant to the case.

re is a difference between evidence and testimony. A medical
sometimes gives much in the form of testimony which amounts
little as evidence. When he does not attend to the questions, he
to a variety of subjects which have no bearing on the case, and do
stitute evidence. The decision on what is and what is not evidence
h the judge.

he replies should be concise, distinct, and audible; and, except where
tion may be necessary, they should be confined strictly to the terms
question. An experienced barrister on one occasion felt it necessary
this advice to a witness: 'Reflect before you answer, and answer
you may be heard.' A judge generally takes full notes of the
evidence: he has first to hear, secondly to understand, and thirdly
down, the replies of the witness.

ne witnesses have a habit of not answering the question which
d, but one which is not asked. In reference to this practice, which
ly arises from a want of proper attention to the question, a judge
he following remarks: 'When a witness does not answer a question,
swers something else, it leads persons accustomed to Courts of
to believe that he prefers not to answer the question, but to put a
t point upon the counsel.' Again, we meet with witnesses who
o answer before the question is completed. Some are concise from a
f saying too much, while the answers of others are given in such
le form, in the shape of a small speech or lecture, that there is great
y in reducing them to their proper proportions. A witness who
ofuse of information generally supplies abundant matter for a long
ublesome cross-examination.

as been a question whether a witness should volunteer evidence
g that the examination-in-chief and cross-examination have not
t out all that he knows of the case. If that which he has to state is
atter of fact within his own knowledge, or an opinion based on facts
his knowledge, he will be allowed, on application to the judge, to make
ement in spite of the efforts of counsel on either side to shut it out.
language in which the answers are returned should be plain and

Counsel who are unacquainted with medical terms frequently

misapply them, or use them in a wrong sense. There are few barriste who are aware that the term 'symptom' is confined to the living body, a 'appearance' to the dead; and the witness may thus find himself questione on the 'appearances' when he first saw the patient, or the 'symptom which he observed on the post-mortem examination of the stomach a bowels. On a trial for murder, in which one of the questions at iss was whether dysentery or poison was the cause of death, counsel puzzl one of the medical witnesses by asking him whether during his attendan he found any traces of '*dysuria*' in the fæces. There is no doubt he i tended to refer to the state of the fæces like that met with in dysente but the professional term employed by him signified a 'difficulty in passi urine.' A judicious witness will avoid anything like a triumph over h examiner under such circumstances, and simply put him right.

3. Answers to questions should be neither ambiguous, undecided, n evasive. An ambiguous answer necessarily leaves the witness's meanin doubtful, and calls for an explanation. An undecided answer—indicate by the words 'I believe,' 'I think,' 'It might be,' or 'My impressio is'—is not sufficient for evidence. Did the wound cause death? W death caused by loss of blood or poison? If, by a proper consideration all the medical facts, the witness has come to a conclusion on the subjec his answer should be expressed in plain and decided language, either in t affirmative or negative. A man who has formed no conclusion is not in position to give evidence. No opinion should be given for which the witne is not prepared to assign reasons; and, except by permission of the Cour no medical opinion should be expressed on facts or circumstances observe by others. A hesitating witness will be met with the question,—Have yo any doubt about it? or,—Was it so or not?—to which a reply in the affirm tive or negative must be given. If the witness fairly entertains doub about the matter at issue, it is his duty to express them at once, and n allow them to be extorted from him piecemeal by a series of questions.

Chemical witnesses have occasionally certified to the discovery of 'impe ceptible,' 'unmistakable,' or 'undoubted' traces of poison in the liver, & Such terms naturally convey to the shrewd mind of the examiner that th witness has some lurking doubt or suspicion of mistake in his mind, f that of which we are sure requires no such terms to express our meanin If poison has been discovered, the statement of the fact is sufficient.

4. The replies should be made in language free from technicality an exaggeration. Some remarks have been elsewhere made in reference t the use of technical terms in drawing up medico-legal reports. If medic men could be made aware of the ridicule which they thus bring on the evidence, otherwise good, they would at once strive to dispense with suc language. A witness is perhaps unconsciously led to speak as if he wer addressing a medical assembly, instead of plain men like the members o a common jury who are wholly ignorant of the meaning of medical term and barristers who are but imperfectly acquainted with them. Thus medical man will speak of an 'exacerbation' instead of 'increase' o symptoms, of the 'integuments of the cranium' instead of the 'skin o the head,' while a common cut is described as an 'incision,' and a blac eye as 'a tumefaction of the orbit.' On a trial for an assault whic took place at Assizes some years since, a medical witness informed th Court that on examining the prosecutor, he found him suffering from severe contusion of the integuments under the left orbit, with great extra vasation of blood and ecchymosis in the surrounding cellular tissue, whic was in a tumefied state. There was also considerable abrasion of th cuticle.' *Judge:* 'You mean, I suppose, that the man had a bad blac eye?' *Witness:* 'Yes.' *Judge:* 'Then why not say so at once?' Thi

t erudite description of the injury was at once resolved by the judge
two plain Saxon words, the meaning of which every one in Court
ld understand. In a case of child-murder, a medical witness who was
ed to state simply the cause of death, said that it was owing to
electasis, and general engorgement of the pulmonary tissue.' This is
science, but pedantry; and if such language is employed by a witness
h a view of impressing the Court with some idea of his learning, it
olly fails of its effect. Barristers and reporters put down their pens
despair, and the time of the Court is wasted until the witness has con-
cended to translate his ideas into ordinary language. Lord Hatherley
ll observed that 'a scientific witness in giving his evidence should avoid
much as possible the use of technical scientific language, especially if
case is before a jury. This is especially desirable when the evidence is
dical, for really many technical words in medicine seem to be invented
cover ignorance. But be this as it may, a witness is always suspected of
ectation, and the Court and jury are but little instructed when a vast
ount of learned phraseology is poured forth instead of a clear statement
the witness's opinion.'

5. In giving evidence of *opinion* a medical witness must take care not base it on any statements made by others, or on circumstances which y have come to his knowledge by public rumour. Again, his evidence uld be confined only to subjects properly within the range of medical ence, and on which, as a professional man, he is competent to speak. In rial for murder by wounding, in which the identity of the prisoner was question, a medical man stated that he compared certain footmarks with e boots taken from the prisoner, and he found that they corresponded. comparison had also been made, but not at the same time, by a police- icer, more accustomed to matters of this kind. On cross-examination, ere was such a want of agreement between the surgeon and the constable specting the number of nails in the boots and the number indicated by e footprints, that no reliance could be placed on this portion of the idence. In reference to this discrepancy, the judge remarked that a edical man should confine himself to matters belonging to his own pro- sion, and not take upon himself the duties of a police constable. There e some points in reference to gunshot wounds which can be better plained by a gun or shot-manufacturer than by a medical witness—*cuique rtè arte credendum.*

Exaggerated language should be avoided. There is a tendency mong some medical witnesses to express their views in a superlative gree. If a part is simply inflamed, it is frequently described as 'in- nsely' inflamed. One witness may speak of patches of ulceration in the testines, another will describe the same condition as 'extensive ulceration.' n a trial for murder by poisoning, a witness when asked by the Court as his experience of the effects of the poison on man and animals, said that had seen 'some dozens of cases.' These 'dozens' on cross-examination to time, place, and circumstances, were reduced to the modest propor- on of about six to eight cases. This use of exaggerated language often ads to apparent conflict in medical testimony. It is not creditable to e witness, and throws a doubt upon the whole of his evidence.

The use of Notes in Evidence.—This subject will be more fully con- dered in another part of the work.

Medical Experts.—In cases of a complicated nature and involving im- rtant interests, it is customary to call in medical or scientific experts, who, reason of their special experience in certain branches of the profession,

are presumed to be able to guide the Court to a proper understanding of the facts of the case. In questions of legitimacy or divorce, obstetricians of high standing are consulted on both sides; in questions affecting the sanity of persons, those who have acquired a reputation in the treatment or observation of the insane are selected; in the various obscure injuries resulting from railway accidents, surgeons of repute,—and in questions of life-insurance, physicians of high standing are summoned as experts to give the results of their experience. There are many of these cases, including some in criminal law, which could not possibly be settled without this collateral aid—the questions at issue not being based on matters of fact occurring within the ordinary range of practice, so much as on an enlarged experience of a particular department. There is, however, a strong public feeling against the admission of the testimony of experts. One able writer remarks:—'It is impossible to shut out such evidence altogether, but there is nothing which brings more discredit upon the administration of justice. There is one consequence of its admission which is common to all cases in which it occurs: it is, that no difficulty has ever been found in obtaining any amount of evidence of this description, on either side of any point at issue. There is a contest as to whether a vitriol or a gas manufactory is a nuisance. Twenty chemists of fair character and scientific acquirements come forward to swear that the effluvia evolved by these processes are producing the most deadly fevers, and twenty others, equally eminent, will give just as positive testimony that the gases are absolutely wholesome, and rather fattening than otherwise. These things are of everyday experience.' There is here some use of exaggerated language.

It will frequently be the duty of a medical expert, in civil as well as in criminal cases, and in all actions for malapraxis, to pass an opinion on the practice of another professional man. On such occasions, while there should be no suppression of the truth, a witness is bound, in answering questions put to him by counsel, to state his opinion and the grounds on which it is based clearly and distinctly. It may be hard to condemn a brother-practitioner, but it would be still harder to ignore the public interest, and condemn ourselves and our profession by concealing that which we know to be true, or by suppressing what we honestly believe. There is no etiquette in the profession which demands such a sacrifice of principle as this conduct involves. A medical witness is not bound to be forward in pointing out and suggesting defects, or in endeavouring to lower another practitioner in the opinion of the public; but nothing should be concealed which is relevant to the elucidation of the case in issue. The golden rule, 'Do unto others as you would that they should do unto you,' should be strictly observed on these occasions.

Certain lunacy cases, and cases of compensation for bodily injury by railway accidents, have drawn particular attention to the testimony of experts. Lord Westbury in referring to experts in lunacy in the *Windham* case, remarked that they came forward to swear away the sanity of persons, and when their reasons were examined it was found that persons asserted to be insane, could not answer questions which some of the witnesses themselves were also unable to answer. 'The absence of explicit statement,' said Lord Westbury, 'was abundantly made up by the flow of hard names, which no doubt had great weight with the jury.' 'I should call unsoundness of mind a mixture of chronic mania and *dementia*,' said one doctor; 'speaking in popular language, I should call it a mixture of mania and fatuity occurring in a person once having a sane understanding.' Another learned physician examined the same lady, no doubt with great cleverness, and thought he would try her knowledge of law. He therefore asked her several questions about the Constitution,

but when similar questions were addressed to him by counsel he himself betrayed considerable uncertainty and hesitation. In the examination of an alleged lunatic in another of these cases, she was asked how much 100*l.* a-year would give per week; and she was not able to tell, and this was relied on as a proof of her insanity; but upon cross-examination of the medical man who was giving evidence of her lunacy, he was asked whether he himself could tell how much per week 100*l.* a-year would give: he hesitated. He was then asked whether he did not know or declined to tell; his reply was that he declined to tell.'

It cannot be denied that experts have frequently introduced into their evidence speculative fancies and theories, not warranted by a proper induction from the facts; but it is clear that in all trials requiring special knowledge, if justice is to be administered, a Court of Law must be assisted by those who possess that knowledge. The author has elsewhere suggested the cause of the evil, and what would prove a remedy. The cause of the evil is that the solicitors on each side are allowed to search the whole profession, until they can find one or more persons ready to adopt their respective views; when once in Court, provided a man can call himself a 'doctor,' his qualifications and experience sometimes escape a rigid scrutiny. Persons have thrust themselves, or have been thrust into cases as experts, without any pretensions to such a title, either by their profcssional standing or experience. A man who may have been engaged for a few years only in the ordinary routine of medical practice, and who may have had no special experience on the subject on which an opinion is required, will be described by his counsel as 'a most learned and eminent member of the profession, on whose opinion the jury are as much entitled to rely as on that of the "highly respectable gentleman" called on the other side,' &c.

Cockburn, C.J., in commenting upon evidence so obtained, observed, 'that it was in the nature of things, that those who gave scientific evidence should lean slightly to the side upon which they were giving their testimony, not from any dishonest intention, but from a perfectly natural and human failing, as in such cases a man was apt to look with a keener eye on those things favourable to his own side, than on those which were unfavourable.'

Bovill, C.J., in making some remarks on medical evidence, says: 'The great misfortune or defect in medical testimony hitherto has been that medical men, like many other professional men, have been too much in the habit of making themselves partisans in endeavouring to support the particular views of the parties on whose behalf they have been called, and this has led to conflicts of opinion which have sometimes appeared not very creditable to the profession.' Lord Hatherley thus expressed his views on the subject: 'A witness to facts knows that it would be base beyond measure to bend his evidence so as to suit the case of him on whose behalf he is called, and that his only duty is to state plainly without colour or fencing what he knows as a *fact*. But the witness who gives an *opinion* is selected by the litigant, often communicating with many of the same profession as the witness, and when so selected he is expected to express a particular opinion. He may honestly entertain it when first selected, but then it is like the case of a counsel's opinion: the counsel gives his opinion on the statement of facts submitted to him, but perhaps after hearing the other side he would find the case wholly altered, and would say so. The scientific witness called into Court by the plaintiff is generally expected to support his case in cross-examination, when many views may be suggested that may really modify the witness's judgment; but even after facts have been proved that ought to modify it, the witness frequently holds to his original opinion. Every witness should eschew altogether the notion of

partisanship. He should be ready to give his opinion frankly and unreservedly, regardless how it may tell. He is there not as an advocate, but in order to inform the Court and jury to the best of his judgment. In fact, I think a judge ought to call in scientific evidence as in lunacy cases, and I doubt whether any *opinion* on oath should ever be given. The jury would then see that it was opinion only—the witness would with more decorum modify his opinion, and would acquire the habit of believing himself to be, not a partisan but an expert, thus rendering assistance of greater value.'

Men of acknowledged skill and good professional experience sometimes quite forget their proper duties as experts, and lay themselves open to censure. An expert is usually called to give an opinion on certain facts laid before the Court in the evidence of other witnesses: thus certain appearances may be described as having been seen in the stomach or brain, and he may be asked to state the conclusions to which such appearances lead. A medical practitioner may describe accurately what he sees, but may not have sufficient experience to draw a correct conclusion. In this case an expert may differ from him and totally alter the bearing of the case. So a man may describe certain symptoms which an expert may say are or are not consistent with poisoning, but he must take care that he does not alter or distort the facts deposed to by other witnesses, in order to fit into the case his own theories or opinions. The alteration of facts to suit special views is by no means unfrequent, and an expert who thus deliberately mangles the evidence of others cannot escape the charge of being a partisan or an advocate in the case—a character wholly inconsistent with that of a witness, who should aim to be in all things impartial. A glaring instance of this kind occurred (Guildford Sum. Ass., 1862,) in an action against a railway company for damages for personal injury. The condition of the plaintiff was accurately described by his medical attendant. Some eminent surgeons who had examined him were called as experts to depose to his present and probably future condition. Other equally eminent surgeons were called as experts on the part of the company, and they differed (as well they might) on the speculative question when the man was likely to recover entirely from the effects of the accident. One of the most distinguished surgical experts for the defence, however, began by saying that plaintiff had only sustained a 'considerable shake'; but shakes are not commonly recognized as surgical accidents, and the surgeon on the other side had described this 'shake,' from actual examination, as a 'concussion of the spine.' But the witness continued—'And as to what was said of congestion of the fibrous tissue, it was mere phraseology not indicating actual facts.' The judge who tried the case observed that he could hardly take that as evidence. 'The *witness must state facts, or his opinion from facts.*' The witness then *disputed the facts*, but the learned judge told him that he had no right to do so, and that he must *give his opinion on the facts as proved.* In these few words are defined the whole of the duties of an expert who presents himself as a witness. The above example shows clearly what ought to be avoided, and it corroborates an observation elsewhere made that the greatest professional knowledge and skill may co-exist with an entire ignorance of the proper methods of employing this knowledge to aid the administration of the law.

The subject of experts, and the mode in which their evidence should be received, has been ably handled, in a legal point of view, by Stephen ('Criminal Law,' p. 209). He objects to the proposition of referring scientific questions to them, even when nominated by the Court, and he considers a common jury better qualified than experts to deal with and decide on all points of scientific evidence. One of the reasons which he assigns for his objection will probably surprise the medical reader: it is,

hat experts so nominated and employed, *i.e.* as assessors to the judge and n the absence of a jury, would *only direct their minds to the truth.* 'A uror,' he observes, 'is not a scientific inquirer, but a judge bound by oath o say whether or not certain evidence satisfies his mind; a scientific nquirer is not bound by anything of the kind.' He considers the sug- estion to be based on a misapprehension of the result to be reached and he mode of reaching it: 'It assumes that the object of the inquiry is the ttainment of the truth simply, and that scientific men are more likely to ttain it than others. To this it may be replied, that the result to be eached is not truth simply, but such an approach to truth as the average an of men are capable of making, and that the result is more likely to be ound in the opinions of common than scientific jurors.' (loc. cit.) On is it may be observed, that while experts have the same power of dealing ith common things as common jurors, they have an additional special ower of making that approach to truth on scientific subjects, which ommon jurors certainly do not possess. It would also appear from this easoning, that in a judicial inquiry affecting a person charged with murder, omething less than truth is more satisfactory for the purposes of justice an truth itself.

But the question regarding this employment of experts as assessors, and he avoidance of the imputation of their appearing as hired retainers in a ase, is practically answered in the Admiralty Courts. Four Masters of the Trinity House, experienced in all the rules of navigation, give their opinions on questions submitted to them, as nautical experts, by the Court; and without creating any charge of injustice in the decisions of he Court, they constantly guide these decisions by answering certain ifficult nautical questions. In a case in which two ships come into ollision, both parties contend they are right, or the case would not be itigated. The question turns upon the respective positions of the ships, he setting of certain sails, the direction of winds, tide and currents, and whether the helm should have been ported or starboarded before the collision. These nautical experts acquit themselves with satisfaction; but if uch a trial took place before a jury, and each captain was allowed to elect his own experts as witnesses, there would probably be the same lissatisfaction as that which now exists in reference to trials involving ther branches of scientific evidence. On this subject a writer justly emarks:—'It is true that in all trials requiring special knowledge the Court must be assisted by those who have that knowledge. But it would contribute very much to the morality of science and to the due dministration of justice if this assistance were not allowed to be given by witnesses hired and brought forward by the parties. The inconvenience as been provided against in some cases with admirable effect. In the Lunacy Commission the visits are made throughout the kingdom by baristers and physicians associated in pairs, the one educated to the investigation of law and facts, the other to the diagnosis of diseases. This has worked admirably. So in shipping cases, where it is necessary that the Court should be assisted by nautical knowledge, the Elder Brethren of the Trinity House are not put into the witness-box by the parties to the suit, but are placed on the Bench, and act with judicial responsibility. In all ases we think that the light which science can throw upon the question hould come not from a witness who is paid to refract it, and who, if his udgment or his conscience will not allow him to make it tell for his client, s not called, but from a man who has no bias, who is chosen either by oth parties or by the Court, and who is rather an assessor than a witness. n lunacy cases the presence of one or more of the physicians of the unacy Commission, sitting with the judge, and aiding the jury in their

examination, would be of more value than the evidence of a hundred madhouse-keepers.' Some sensible remarks on this subject, made by a Medical Committee of the American Academy, will be found in the 'Med. Times and Gaz.,' 1870, 1, p. 370.

There can be no doubt that the present system discourages some eminent and upright men, who could by their special knowledge solve many important questions, from appearing as witnesses. Several have uniformly refused on this ground to attend as experts in a Court of Law. A distinguished chemist, a gentleman of strict honour and integrity, was once asked by counsel—in the first question put to him in cross-examination—'When and by whom were *you* first *retained* in this case?' Without directly imputing bribery and perjury to the witness, the innuendo to the Court and jury was to the effect that this gentleman had received his fee to maintain a client's cause, wholly irrespective of the oath which he had taken. As counsel on both sides look on the experts opposed to them in the light of hired advocates, it is obvious that so long as this system lasts, it must have a deterring effect on the higher and better class of witnesses, who, whenever they have the option, will avoid placing themselves in such a position as to have imputations of venality and untruthfulness thrown out against them in a public Court. In a correspondence with the late Dr. Andrew Combe of Edinburgh, many years since, he informed the author that he had been consulted in a case in which a gentleman was considered to be incompetent to manage his affairs. He says in his letter: 'I was required to go and examine him on twenty-four hours' notice, but I insisted first on receiving some account of him, and being allowed to form an unbiassed opinion of the results of the examination. With some difficulty I obtained his history, and on perusing it saw a strong probability that my opinion would be adverse to those who consulted me. They of course professed pure impartiality, but it was manifest that my opinion was expected to confirm theirs. Had I been called by the sheriff, for example, I might have given impartial evidence.' Baly, Munro, Wood, and the author were required to give their opinions in a similar case. They insisted upon being allowed to make a full examination of the alleged lunatic, and the result was that their opinions were completely adverse to those who consulted them, much to their disappointment. They declined to give evidence in the case. It is a fact worthy of note, that in criminal trials, where life is concerned, no provision is made by the English law for enabling a judge to take the opinions of one or more medical or scientific experts, not connected with the case, although such a practice would be attended with great public benefit. If there is conflicting medical evidence he can only direct an acquittal. In reference to actions for railway accidents the law has interposed. By an act passed in 1868 (31 and 32 Victoria, cap. 119, sec. 26) it is enacted that, 'whenever any person injured by an accident on a railway claims compensation on account of the injury, any judge of the Court in which proceedings to recover such compensation are taken, or any person, who by the consent of the parties or otherwise, has power to fix the amount of compensation, may order that the person injured be examined by some duly qualified medical practitioner named in the order, not being a witness on either side, and may make such order with respect to the costs of such examination as he may think fit.' This power was exercised by Kelly, C.B., in a railway case (Exch., Dec., 1871.). Three physicians were examined and gave their opinions on the degree of injury sustained. An eminent surgeon, who had not been consulted in the case, was required under the judge's order to draw up a special report from the facts proved in evidence. This report was given in evidence, and confirmed the state-

ments of the witnesses for the plaintiff; a verdict was given accordingly Such a principle should be extended to all cases involving criminal charges and requiring medical or scientific evidence for their elucidation.

Medical Counsel.—Some barristers, who feel themselves unable to discuss the medical bearings of a question, are in the habit of employing medical men to instruct them on the best mode of endeavouring to cross-examine medical witnesses, so as if possible to place the case in another light before a jury. It is obvious that even if interference were prudent under the present system of summoning medical witnesses, the law could not interfere to check a practice which is certainly liable to lead to evil results; for the parties who give the suggestions which may suit the purpose of an advocate do not always act as witnesses, and therefore cannot have their own means of knowledge or sources of experience fairly tested, while the *selected* medical facts or opinions which they may communicate to the advocate may have the effect of confusing the minds of the jury. Under these circumstances, the result must depend on the acumen and medical knowledge possessed by the judge who tries the case.

The question has been frequently asked, May not a medical witness honestly take up the defence of a prisoner? Is it always certain that the case for the prosecution is indisputably correct? The latter question admits of a simple answer, which will show the course that may be fairly pursued. The evidence for a prosecution may involve a serious medical error, as well as the evidence for a defence. Assuming, from his knowledge of the ascertained facts of the case, a witness believes *bonâ fide* that the medical opinions for the prosecution are incorrect or contrary to his own experience, he has a right to interfere and point out what he considers to be an error of fact or opinion. What he has to state, however, in this behalf should be publicly stated on oath, so that his experience, motives, and honesty of purpose may be fairly and openly tested by a cross-examination. He should remember that his interposition is only justifiable in the interests of justice as well as of the *public*, and not simply in the personal interest of the accused. If he is retained and paid by the prisoner's legal advisers to defend the prisoner's interest, wholly irrespective of the public interests, he is simply a medical counsel or advocate. It is this kind of interference, on the part of some medical and scientific witnesses, which has laid the whole profession under a general censure. When, as in certain criminal trials, men thus hire themselves for the purpose of a defence, *i.e.* to rescue an accused person from the penalty due to a crime which there may be strong reason to believe he has committed, they may justly be called, in the language of a great lawyer, traffickers in evidence. In one important case (*Reg.* v. *Tawell*, Aylesbury Ass., 1845), a woman died from the effects of prussic acid, and a fatal quantity of that poison, amounting to one grain, was clearly discovered in the stomach of deceased by an experienced chemist. As, from the moral and circumstantial evidence, the guilt of the man could scarcely be disputed, an attempt was made to destroy the effect of the chemical evidence, and to impose on the common sense of the jury, by the statement that the deceased had eaten some apples, that the pips of apples contained the principles for producing prussic acid in the human stomach, and that the poison found in this case had resulted wholly or in part from the apple-pips. This monstrous chemical proposition met with no acceptance from the jury; they preferred the doctrines of common sense to this pseudo-scientific theory. The interference in this case for the defence, could not have been based on any *bonâ-fide* belief that the chemical evidence for the prosecution, on which the conviction of the prisoner chiefly turned, was untrustworty.

In cases in which medical men summoned as witnesses lend themselves as advocates to the party consulting them, for the purpose of weakening or overthrowing the scientific evidence on the other side, in spite of its consistency and accordance with sound medical doctrines, they lose sight of their true position, and justly expose themselves to severe censure. If, on hearing the evidence to facts on the side of the party consulting them they find the complexion of the case altered, and that they cannot support it as they believed they were in a position to do, it is their duty to themselves and their profession as well as to the public interests—which are always superior to private interests—to withdraw from the case. No man should ever appear to support that which he does not believe to be true.

In civil cases it is not always easy to say, until the evidence has been heard in Court, whether scientific opinions should be in favour of plaintiff or defendant; and herein lies the great advantage arising from the opinions of scientific experts employed as assessors. There may be on each side a portion of truth which will meet with its medical supporters, without any imputation upon their motives, any more than upon the motives of the members of a special jury, who, in spite of perfect absence of bias, cannot always agree. Nevertheless there are some plain matters of fact in which it is discreditable to the profession to find disagreement. If medical science is of any value for the guidance of a country, it should be able to determine whether a man is or is not labouring under paralysis as the result of accidental injury. In the following case (*Sherwin* v. *N. E. Ry. Co.* Leeds, Lent Ass., 1872) an equal number of medical witnesses supported opposite views. In this case the plaintiff claimed damages for personal injuries. He was described as a strong healthy man up to the time of the accident. The negligence was admitted, and the plaintiff was examined by three medical gentlemen on each side. The three witnesses for the plaintiff stated that he had paralysis of the legs, which was extending upwards, and was of a permanent character, so that he would not be able to walk again. The three medical gentleman called on the part of the defendants deposed that the plaintiff was not suffering from paralysis at all. The jury found a verdict for the plaintiff.

Actions for compensation in railway accidents have brought to light some practices among certain members of the profession which have repeatedly called forth the censure of the Bench. These persons have allowed themselves to be retained by the Company as surgeons to attend on these who have suffered injury; they have then been employed to suggest terms for compensation, so as to avoid litigation, and if possible to keep the case out of Court. So far no public injury may possibly accrue, although the financial part of the transaction is in the province of an attorney, and not of a surgeon; but when the case comes to trial, the matter assumes an entirely different aspect. The medical attendant of the Company, who has seen the injured plaintiff, but in the interest of the Company, and can probably give the best evidence of the injuries which he has sustained, is so situated, that anything which he may say will necessarily have the taint of bias and self-interest. Medical men have thus been strongly condemned by judges for degrading their profession by lending themselves as money agents for the defendants. A case of this kind (*Lee* v. *Yorks. Rail. Company*) led to some severe but just remarks on this medical trafficking in accidents in the Court of Malins, V.C. ('Med. Times and Gaz.,' 1870, 1, p. 733).

Other practices, too, of a more remarkable nature have come to light. In a reported trial of this kind, which took place during the Summer Assizes of 1865, there was a conflict of medical evidence respecting the condition of the plaintiff, the witnesses on one side taking the view that

had sustained serious injury, and those on the other that he was either mming or greatly exaggerating his symptoms. One medical witness, adopted the shamming theory, and who appeared on the part of the npany, had attended the plaintiff and prescribed for him, as an experi- nt, syrup and water, under which it was stated he improved. This sfied him that the man was shamming. It appeared, however, in cross- mination, that although the witness was paid for his services by the npany, he knew that the plaintiff believed at this time that he was acting is own medical attendant. This mode of getting up scientific evidence the Company was justly and severely condemned by the learned judge tried the case. A medical man's own judgment should suffice to pre- t him from falling into errors like these; he thereby not only damages self, but the profession of which he is a member. Men who adopt e practices should know that they are not in a position to give un- sed evidence, and therefore should decline to appear as witnesses.

Medical counsel and medical witnesses are differently placed in relation case under investigation. While he who acts solely as medical counsel have undue weight given to his suggestions, in their being put boldly rard by the barrister who retains him, in forcible and impressive lan- ge, as ascertained medical truths, he entirely escapes that searching nination into his competency which is infallibly the lot of a medical ness; and again, while the latter is bound by his oath, without reference he prosecution or defence, to state the *whole* truth, the former is only ged to give so much of the truth as may suit the case of the party for m he appears. In short, like a barrister, he may be not an advocate of abstract principle of justice, but of the cause of his client. How far a ical man has a moral right to make use of his professional knowledge rder to embarrass the testimony of those of his professional brethren are compelled by law to appear and give evidence to the best of their ity, is an ethical question which it is here unnecessary to consider; but e can be no doubt, that while in some instances the practice may work , by preventing convictions from taking place upon erroneous opinions, liable to be perverted to the worst purposes. An unscrupulous man, chose to make himself thoroughly acquainted with scientific subjects, ht in this way so pervert the medical facts of a case, and lead to the usion of witnesses who are not able to cope with him, as to procure an ittal in face of the most convincing proofs of guilt. The remedy for evil is in some measure with the medical witness himself. By having mind fully prepared on the subject before entering the witness-box, he have no occasion to fear an encounter with members of his own pro- ion, thus working against him. A plain statement of the whole truth, the fact that he shows by his evidence that he has no end to serve but public good, will enable him to put down the sophistry, medical or l, that may be thus arrayed against him.

It has been stated that no man acting as medical counsel or adviser uld on any occasion be allowed to act in the capacity of a witness. doubtedly a man who takes up a case with a view of dressing up facts for one side only, and collecting evidence for defeating by mystifi- on the case on the other side, is not in a position to act as a witness h any credit to himself, to his profession, or to those who summon him. object is neither truth nor an approach to it, but rather the gaining of ctory *per fas aut nefas*. There is no law by which such persons can be vented from acting as witnesses: but, as a rule, their evidence is either cted or received with great distrust. In some cases the cross-examination uch persons would be a benefit, since it might have the effect of showing t many of the questions which they had suggested in the case were

based upon erroneous views, on ignorance of the real facts, or on actua want of experience. A medical witness may, however, without any im putation upon his *bonâ fides*, explain medical points to counsel, and correc him on medical subjects when wrong in his views or statements.

Conflicting Medical Testimony.—The conflict of opinion among medica witnesses and medical experts is a favourite theme of comment with portion of the public. The reader will find some remarks on this subjec in reference to Commissions of Lunacy. There is little to add to them, fo similar remarks apply to all medico-legal cases which come before a Cour of Law. That men should be found who can traffic in evidence is certainl a misfortune for the profession to which they belong, but differences o opinion on the same state of facts may fairly exist in the medical as wel as in any other profession. If such differences come more before th public on medical or scientific questions, it arises from the fact that th cases demanding such evidence are far more numerous than those whic affect the two other learned professions. In suits which involve the right and duties of the clergy, there is seldom agreement among those who hav to decide upon them as ecclesiastical authorities. So among members o the legal profession, and in the administration of justice generally, whil barristers notoriously differ and give conflicting written opinions upon th same state of facts, special jurors, consisting of highly-educated men, ar unable to agree in opinion, and are often discharged without a verdict, t the great injury of litigants. If in an important patent case, after a serie of appeals, judges themselves differ *toto cœlo* in the construction of the law and are obliged to read conflicting written judgments *seriatim*, it may b surely permitted to scientific men also to differ conscientiously from eac other without any imputation of interested motives. The fact that th venal evidence of 'hired' experts or witnesses occasionally finds its wa into a case, does not justify the sweeping denunciation of medical o scientific witnesses as a body. As Stephen remarks of the Law, so i may be said of medicine—no system of rules can fully embody that line o conduct by the observance of which those who exercise a noble professio with honour and credit are distinguished from those who disgrace it. It i purely a matter of sentiment and good feeling; and it is truly a sad da for science, as one judge remarked, when the conflict of opinion ma be traced to the ignoble motives of a desire of gain or of notoriety, o of anything but a desire for truth. From these remarks, a medical witnes will learn not only what he ought to do, but what he ought not to do, i taking up the defence of a person who is charged with crime.

Fees.—The following information as to fees payable to medical witnesse may be useful to the medical practitioner:—

In the Supreme Court of Judicature, and in the Court of Appeal, 1*l.* 1 a day, if resident in the city where the case is tried; and 2*l.* 2*s.* to 3*l.* 3*s.* day, if resident at a distance from the place of trial, inclusive of all exce travelling expenses. For travelling expenses a sum not exceeding 3*d.* p mile each way if there be a railway, and 6*d.* per mile each way if there no railway. It is customary to pay return first-class, or sometimes secon class, railway fare only. In the Divorce Court, 1*l.* 1*s.* a day, if reside within five miles of the General Post Office. Higher charges are allow for experts, but not exceeding 5*l.* 5*s.* a day, including all except travelli expenses. Sundays are never counted. In the County Court 10*s.* to 1*l.* a day is allowed. At Assizes, medical men attending to give professio evidence are allowed 1*l.* 1*s.* a day, 2*s.* for every night they are away fr home, and second-class travelling expenses by rail, or a sum not exceedi 3*d.* a mile each way when there is no railway.

registered medical practitioner is entitled if formally summoned, of 1*l.* 1*s.* for attending to give evidence at a coroner's inquest o *post-mortem* examination is ordered, and to an additional fee .—2*l* 2*s.* in all—when an examination is ordered. The fee for a *tem* examination will not be paid if the examination has not been in writing. These fees are to be paid by the coroner immediately close of the inquest. There is no provision for a second attendance journed inquest, nor for making a second *post-mortem* examination. roners are in the habit of paying 1*l.* 1*s.* for every day's attendance; ay 1*l.* 1*s.* only for all the attendances however many.

nregistered medical practitioner, whatever his diplomas may be, n fees for giving medical evidence. In all cases where attendance red in a civil court to give expert evidence, a special agreement e made in writing, binding the solicitor who requires the attend- himself pay the fees, as these are only recoverable from principals, here is a special agreement to the contrary.

QUESTIONS CONNECTED WITH THE DEAD BODY.

CHAPTER 3.

QUESTIONS CONNECTED WITH THE DEAD BODY—SIGNS OF DEATH—CESSATION OF RESPIRATION AND CIRCULATION—APPARENT DEATH—TRANCE—COLDNESS OF THE BODY—POST-MORTEM HEAT—RIGOR MORTIS—CADAVERIC RIGIDITY—CIRCUMSTANCES WHICH INFLUENCE ITS COMMENCEMENT AND DURATION—OTHER INDICATIONS OF DEATH.

Among the subjects which sometimes claim the attention of a medical jurist, in reference to the bodies of persons found dead, are the conditions known as real and apparent death, the proofs of death, and the priority of death. A knowledge of the changes which take place in the dead body at a recent, as well as at a remote period, may be usefully applied to the determination either of the reality of death, a problem seldom involving difficulty, or of the period at which death took place, a question of considerable importance, and upon which the guilt or innocence of an accused person may frequently depend. Medical jurists have enumerated certain external signs or indications of death. It will be necessary to consider these in the order in which they commonly present themselves to the observer.

1. Cessation of Circulation and Respiration.—The cessation of these two important functions is regarded as in itself sufficient to determine the reality of death. But persons have been resuscitated from a state of asphyxia; and, others again have recovered from a state of lethargy or catalepsy, when, to all appearance, the respiratory and circulating processes had been completely arrested. Life is not incompatible with a temporary apparent suspension of these two important functions; but, in making this admission, it is undeniable that the processes must be speedily re-established, or death will assuredly follow. One remarkable case illustrative of the maintenance of life under a partial suspension of the action of the heart and lungs, is recorded by Cheyne. It is that of Colonel Townshend, who appears to have possessed the power of voluntarily dying:—*i.e.*, of so suspending the heart's action, that no pulsation could be felt. After lying in this state of lifelessness for a short period, active life became slowly re-established, but without any volition or consciousness on his part. The longest period during which he remained in this inanimate state, was about *half an hour*. It is probable, however, that the heart's action was not entirely suspended during the whole of this time, but that respiration and circulation were feebly continued at intervals; so slightly as to be imperceptible to the examiners, or to be indicated by a pulsation of the radial artery. The stethoscope had not been then invented, and the method of detecting the sounds of the heart by auscultation was unknown. A hybernating animal would appear to be dead under similar circumstances, but it is known that circulation and respiration still continue in a sufficient degree to maintain life. Bouchut has proved that during hybernation, an animal is simply in a state of apparent death. The vital functions are not arrested, but are reduced to their lowest ebb. Thus he found, in his experiments on the marmot, or mountain rat, that when the animal was in an active state, the pulsations of the heart were 90 while in the torpid state they were reduced to 8 or 10 in a minute ('Ann. d'Hyg.,' 1848, 2, 96.) In the case of Colonel Townshend, it i

obvious that the action of the heart may have continued, although the pulse at the wrist and other parts of the body failed to indicate it. It appears that the Colonel really died nine hours after the performance of the experiment above mentioned. His body was carefully examined, but nothing could be detected to account for the extraordinary power which he possessed over the action of the heart. This case, which rests upon good authority, must be regarded as altogether exceptional. It may, however, serve to throw some light upon the possible survivorship of persons, who have been exposed to death by drowning, and whose bodies may have been immersed in water for an unusual period of time.

In some works on the subjects of apparent death and asphyxia, cases are recorded which are intended to show that respiration and circulation may be suspended for many hours, and yet the person be living. It is impossible to place any credit on narratives of this description, which generally rest upon hearsay or conjectural evidence. To suppose that the two important functions of respiration and circulation can be wholly suspended for even an hour, in a human being, without destroying life, is to set at defiance all physiological experience. Admitting the possibility of such a case occurring, it would require the best and most unequivocal evidence to support it. The phenomena of hybernation in many animals can have no reference to this condition: for in these, a purpose is answered by the feeble state of existence into which they are thrown. While it is natural for such animals to remain torpid during the winter season, or to exist under a feeble exercise of the functions of respiration and circulation, it would be an unnatural condition for a human being, and inconsistent with the maintenance of life.

There are some forms of disease affecting the nervous system, as, for example, hysterical tetanus, coma, and catalepsy, the symptoms of which are occasionally such, as closely to simulate death. Respiration and circulation appear either to cease entirely, or to be carried on so feebly, that, to uninformed observers, the persons affected may seem to be really dead. Catalepsy, or, as it is vulgarly called, *trance*, in which the person lies in an unconscious state, may thus assume the appearance of death; but the warmth of the body is retained, the limbs are flexible, and the heart and lungs continue to act, although less vigorously than natural. (For a remarkable case of this kind, see 'Med. Times and Gaz.,' 1870, I. p. 495.) Cases of prolonged and profound sleep of a natural kind, which have also been described as cases of trance, cannot be mistaken for death. Cousins met with an instance which may be taken as the type of others. A man of healthy habits, forty-three years of age, was at intervals subject to attacks of long and persistent sleep. He would retire to bed at his usual hour, and, without any warning symptoms, suddenly and almost immediately fall into a profound sleep, from which all the usual means would fail to rouse him. In this state, his face and ears were pale; the skin was pale and generally warm, but his feet were cold and livid, and the limbs quite relaxed. His pulse was soft, slow, and feeble; his respirations almost imperceptible, amounting to about eight or nine in a minute. He appeared like a person in a refreshing, tranquil slumber. There was no stertor or snoring. The longest period he ever passed in profound sleep, was five days and five nights. He frequently slept three days and occasionally four days without waking, but his average period was two days. His secretions were suppressed, and no food was required. He commonly awoke suddenly, and had no consciousness of the lapse of time, and retained a good remembrance of the last occurrences before he fell into this state. He had no dreams. ('Med. Times and Gaz.,' 1863, I. p. 396.)

A married woman, thirty-six years of age, became subject to attacks of

prolonged sleep or trances, lasting from two to seven days, but usually about five days. They occurred suddenly, without warning, sometimes during the night, and sometimes during the day. After twenty-four hours she was half roused, and her lips moistened with liquids which she swallowed insensibly, again falling asleep immediately afterwards. These trances generally occurred at intervals of from two to twenty days, during which she had no regular sleep, or, if any, it was short and disturbed. The evacuations were suspended during this state. It was found impossible to rouse her; but she awoke spontaneously, feeling much fatigued and not refreshed by this unnatural sleep. When an eyelid was lifted, the eye was found to be fixed upwards; light did not cause her pupils to contract. The respiration, circulation, and temperature of the body were in their original state, during and after these trances. ('Gaz. Méd.,' Jan. 1845; and 'Edin. Month. Jour.,' Ap., 1845, p. 307.)

It has been demonstrated by Durham, that in ordinary sleep, there is a withdrawal of a due supply of blood from the capillary vessels of the brain. The remarkable fact is, that the proper supply of this fluid to the brain, should be so long withdrawn or suspended, without producing serious injury to the nervous system. This condition appears to be a kind of human hybernation. It could not be mistaken for death, even by the most ignorant observer, considering that respiration and circulation are still carried on, and the warmth of the body is retained.

Certain tests have been proposed for the purpose of ascertaining whether these processes have ceased or not. It is unnecessary to allude to them, because they appear to be wholly inadequate to the purpose intended; but in the absence of all appearance of movement in the chest and abdomen, a medical man may readily satisfy himself of the fact of respiration and circulation continuing or not, by the occasional application of a stethoscope, or of the ear itself, to different parts of the chest—especially to the region of the heart. The auscultatory test, applied at intervals during half an hour, cannot fail to lead to a satisfactory conclusion. This test, first proposed by Bouchut, and rewarded by the French Academy with a prize, as being the most certain method of proving death before putrefaction, has been objected to by Dowler,—1, because the heart itself may, like other muscles, be in a state of apparent, and not real death; and 2, because the pulsations and sounds of this organ may not always be appreciable to the ear, even when aided by the stethoscope. In support of these objections, it is stated that Brachet has repeatedly restored the vitality of new-born children, in whom no pulsation whatever could be discovered for a period of fifteen to thirty minutes after birth. In one instance a child was revived, after *twenty minutes* of apparent death, by insufflation of the lungs, although during that time no pulsation could be heard or felt. Another case was that of a man, æt. thirty-three, whose heart presented no contraction that could be detected during at least eight minutes, although the ear was applied again and again. *Twenty minutes* after the suspension of its action, a slight contraction was perceived in the heart, its pulsations then became regular, and the patient opened his eyes. ('Philadel. Med. Exam.,' Oct., 1850, p. 599.) To these may be added the case of Colonel Townshend, which carries the supposed period of the entire suspension of the heart's action to half an hour. Such cases however do not show that a person can live while the heart's action is thus continuously suspended, but that the means employed for testing the state of this organ have been insufficient.

In awarding the Manni prize, founded for the discovery of a certain sign of death, the French Commissioners, Dunéril, Andral, Magendie Serres and Rayer, very properly dwelt upon the state of the heart as for

ing the most unequivocal proof of death before the occurrence of veric rigidity and putrefaction. Bouchut, to whom the prize was ded in 1846, found, in an extensive series of researches experimentally rmed by the Commissioners themselves, that in all cases of apparent ı, whether arising from asphyxia or syncope, there is one common ıcter by which they may be distinguished from real death, and that is, ıtinuance of the pulsations of the heart. He established the fact, that e most perfect state of syncope, attended with entire loss of motion ıensation, as well as cooling of the body, the contractions of the heart not really at any time suspended, but simply reduced in force and ency. In syncope from hæmorrhage, carried to the fullest extent, and ses in which respiration was either imperceptible or carried on at long rals, the body at the same time having the aspect of a corpse, he was ed by auscultation to detect the pulsations of the heart, and thus to ıguish apparent from real death. In children born in a state of apparent , and in cases of asphyxia from any cause, in narcotic poisoning, in rical and epileptic coma, and in all diseases which have been stated to ıble apparent death, the living has been easily distinguished from the body by the continuance of the heart's action—this was feeble and place at intervals, but it was always sufficiently marked to enable a ssional man to distinguish a living from a dead body.

was considered important, if possible, to define the periods at which, the entire cessation of the heart's action, a person might be pro- ed dead. Assuming that the last audible expiration has been made, he motions of the chest have apparently ceased, and that no pulsation e felt in any of the arteries of the neck or limbs, the longest interval elapsed between the pulsations of the heart was about six seconds. r, one of the Commissioners, from his own observations on the , assigned as a maximum, an interval of seven seconds between the ulsations of this organ. If, therefore, no motion of the heart is per- l during an interval of *five minutes*, a period which is fifty times as as that which observation warrants, death may be regarded as certain. the cessation of the pulsations of the heart, the usual cardiac sounds ease. At the same time their cessation furnishes a proof that respira- has ceased, and that the functions of the nervous system are not y suspended, but destroyed. ('Ann. d'Hyg.,' 1848, 2, 78.)

ı reference to *respiration*, the alternate motions of the chest and nen, serve better as a means of diagnosis, and are more readily ved, than the motions of the chest alone. In the absence of a stetho- , an opinion may be formed from an external view of the body by the ring arrangement. An even piece of looking-glass, plate glass, or a of water or of mercury, may be placed upon the front of the chest, he image of some object allowed to be reflected from the window, or strong source of light. The slightest motion in the reflecting surface e indicated by an alteration in the image of the object reflected. A nformed practitioner can, however, generally determine the question ut resorting to experiments of this description.

ıe entire cessation of breathing, in the opinion of Brodie, should be ied alone, as a decisive test of the extinction of life. The move- ı of respiration cannot be overlooked by any person who exercises due and the heart never continues to act for more than four or five es after respiration has ceased. This organ has been properly des- l to be the *primum vivens* and the *ultimum moriens*, the first to live and st to die. The proofs of its continued action, however, are less obvious unskilled observer than the movements of the chest; hence the visible ion of these movements for a period of five minutes furnishes a certain

proof that the person is really dead. But the skilled observer would apply the test of auscultation, and before giving an opinion would satisfy himself of the permanent cessation of the heart's action. It is impossible to admit that the heart can remain for even half an hour in a state of inaction in a human being, and then spontaneously recover its activity.

2. Coldness of the Body.—One of the most striking characteristics of life, is the power which the body has of retaining a temperature far above that of the medium in which it is ordinarily placed. Notwithstanding that the body is constantly subjected to the same laws of cooling as all other heated solids, *i.e.* by radiation, conduction, and convection, the supply of heat internally, is so constant and uniform, as to counterbalance exactly the loss which is experienced. Most physiologists consider that animal heat depends entirely on the chemical changes produced by respiration. When, therefore, life is extinguished, the body will gradually lose the heat which it possessed at the moment of death, just like so much inert organic matter artificially raised to the same temperature.

The normal temperature of the interior of the body in health is about 98·4° F. It is liable to be increased in some diseases and to be diminished in others. In one case of typhoid fever, Piorry states that he found the blood to have a temperature of 113° F.; and the temperature of the uterus during parturition is said to have been found still higher. In strychnine poisoning it is very high.

The time usually assigned for the cooling of the dead human body to the temperature of the air is from twelve to twenty-four hours, but it varies according to the condition of the body at the time of death, the mode of death, and the circumstances under which it has been placed. From Jan. to June, 1863, Dr. Wilks and the author collected observations on the cooling of the dead body in one hundred cases, at Guy's Hospital. The age, the cause of death, and the circumstances under which the bodies were exposed, were at the same time noted. The reader will find the details of these cases in a table published in the "Guy's Hosp. Rep." 1863, p. 184. A summary of the observations of temperature recorded in this table leads to the following conclusions. If the periods of time be divided, first, into those which are included between two and three hours; secondly, between four and five hours; thirdly, between six and eight hours; and fourthly, twelve hours, including one or two cases extending to fourteen hours, the results were as follows:—

	First period, 2 to 3 hours.	Second period, 4 to 6 hours.	Third period, 6 to 8 hours.	Fourth period, 12 hours.
Number of observations .	76	49	29	35
Maximum temperature of the body . . .	94° F.	86° F.	80° F.	79° F.
Minimum temperature of the body . . .	60° „	62° „	60° „	56° „
Average temperature .	77° „	74° „	70° „	69° „

The temperature was tested by simply placing the exposed bulb of a thermometer on the skin of the abdomen. It should be remarked, however, that as the observations could not be commenced until the bodies were brought to the dead-house, and a variable interval elapsed, during which they remained in the wards, these temperatures are lower than they would be at the respective periods, after death; as the body would neces-

cool to some extent before the first observation could be made. ıevertheless, show that a dead body cools slowly and progressively, ıt the trunk generally retains a well-marked warmth for ten or twelve ıfter death.

:he circumstances under which a body is exposed are favourable to ı of heat, it may be found cold in eight or nine hours after death. case of *Millie*, for the manslaughter of whom a man named *Bolam* ed and convicted some years since, the body, although clothed, is d to have been found cold about nine hours after death. Casper ight to twelve hours as the usual period of cooling.

may be accepted as a general fact that the body is not cooled to imately the temperature of the surrounding medium, air, in less venty-four hours. Many writers on forensic medicine assume that ly cools at the rate of 1° F. per hour. But the rate of cooling is proportional to the difference of temperature between the body and rounding medium; so that the rate of cooling becomes slower as its ature approximates to that of the surrounding air. Soon after death may lose temperature at the rate of 4° or 5° F. per hour; and after se of twenty hours may not lose so much as 1° F. of temperature ır.

is customary to judge of the degree of coldness by the sense of but the dead human skin is a good conductor of heat, and thus the ı may appear cold to a moderately warm hand. The condition of nd itself may lead to an erroneous impression. If the two hands are ıerent temperatures, a recently dead body may appear cold to one and to the other. Another fact should also be borne in mind, that in the and abdomen, the viscera may retain a well-marked warmth when rface of the skin is actually cool or cold. Among the cases observed y's Hospital in 1863, (*ante*, p. 46) it was remarked that in several a emperature was retained by the viscera for a long period after death. ɔ instances a thermometer indicated in the viscera a temperature F., in one instance seventeen, and in the other eighteen hours after —the temperature of the air being comparatively low (49° F.), and rface of the body cool. In a third instance, ten hours after death, the surface of the abdomen had a temperature of 65° F., the interior 5° F. ('Guy's Hosp. Rep.,' 1863, p. 193). In all observations on mperature of the dead body, a thermometer should, if possible, be yed. This may be applied for the exterior, either to the skin of the ıen or to the armpits; and for determining the temperature of the ır, the bulb may be introduced into the mouth, throat, or rectum.

hen death has taken place suddenly, from accident, apoplexy, or acute a, a body has been observed to retain its heat for a long period. It ted, by Nysten, that the bodies of persons who have died from ria, by hanging, or suffocation, or from the inhalation of carbonic as, do not cool, *cæteris paribus*, until from twenty-four to forty-eight after death; and that sometimes even *three days* have elapsed before dy has become completely cold. Too much importance must not be ed to this statement, since in some cases of fatal asphyxia, the body en observed to cool just as rapidly as in death from other causes.

cording to Richardson, a loss of blood, as in cases of death from rrhage, whether the blood is effused externally or internally, or even rarily withdrawn from the heart, as in syncope, is a cause of the cooling of the body. He states that 'the decline of the tempera- ı these cases is so great, that the external surface of the body may ly run down to that of the air without death.' ('Med. Critic,' Jan. p. 31.) The sudden cold of collapse observed on the surface of a

living body, is here confounded with the slow and progressive cooling of a dead body. The cases which have been adduced in support of this view are exceptional instances of disease, and have no practical bearing on the question at issue—namely, the cooling of the body after the sudden death of healthy persons from wounds. Hence the conclusion drawn from them, 'if the body is left dead from direct and absolute loss of blood, cooling to the temperature of the surrounding medium is completed, in regard to the external surface, in two hours,' may lead to a serious error, and implicate an innocent person in a charge of murder.

An opportunity of testing the accuracy of this statement presented itself at Guy's Hospital in Feb., 1863. A healthy man, æt. forty-seven, died suddenly from hæmorrhage. A ligature had been placed on the axillary artery in consequence of an accident: this gave way, and about four pounds of blood were lost. Four hours after death the shoulders, chest, and abdomen of the deceased were quite warm. The skin of the abdomen had a temperature of 84° F.; eight hours after death the temperature was 80° F., and the arms and legs were not rigid. The conditions under which this body was exposed, were favourable to rapid cooling: it was placed in a shell with a shirt loosely over it, and the temperature of the dead-house was 38° F. The alleged effect of loss of blood in accelerating the cooling of the human body when death has occurred suddenly from hæmorrhage, has therefore no foundation in fact. The only physical difference which it would be likely to create, would be by simply reducing the amount of fluids in the body to undergo the cooling process. In the above well-marked case, the loss of four pounds made no appreciable difference in the rate of cooling.

It has been suggested that coldness of the body as a result of disease, whether arising from malignant cholera, phthisis, or other chronic disease, or from death during the stage of collapse in poisoning, might create difficulty in reference to an opinion respecting the date of death. It is stated that the bodies of persons who have died of these diseases, have been found quite cold on the surface within *four* or *five* hours; at least, as cold as the bodies of healthy persons after the lapse of fifteen or twenty hours. In such cases, coldness of the body is commonly manifested before dissolution, in those parts which are the most exposed, as in the extremities of the hands and feet, the nose and ears. Like all other diagnostic signs, when taken alone, coldness of the surface is open to this objection; but the obvious cause of death, and the emaciated state of the body, as well as the facts connected with the occurrence and disappearance of rigidity, even supposing that no history of the case could be obtained, would be sufficient to remove any doubt. The objection is of a speculative kind, and no instance has been adduced in which these morbid states have led to an erroneous medical opinion.

The physical circumstances which influence the cooling of a dead body are precisely those which influence the cooling of all heated inert substances. 1. The medium in which it is immersed. A body will cool more rapidly in water than in air—a fact which may be important in a question of survivorship in drowning; and it will cool more rapidly in the open air than in a dwelling—on the floor than in bed, or under exposure to a current of air than in a warm, tranquil atmosphere. It will cool more rapidly in a large apartment than in one which is small. The dead human body cools, first, by radiation; secondly, by conduction; thirdly, if naked and exposed, by convection: consequently, its own mass, as well as the nature of the materials with which it is in contact, must modify the results. The body of an adult, *cæteris paribus*, cools more slowly than that of a child, or of an old person; and that of a fat or corpulent person cools

h less rapidity than one which is lean and emaciated. Again, when dead human body is placed on good conducting substances, or is osed to the open air in a naked state, the cooling process will be tened. If, on the contrary, it is much covered with badly conducting erials, as cloth, flannel, or cotton, and is allowed to remain on a bed, it require more than the usual period of time to become cold.

The dead body, like so much inert matter, continues to cool until it hes the temperature of the medium (air or water) to which it is osed. As the soft solids are not good conductors of heat, the inner s of the body are much longer than the surface in acquiring the perature of the surrounding air; and, for the same reason, when once ed, it is long before they reach the temperature of the air, supposing to have risen. Thus, if a dead body is cooled to 60° F., and the air in room suddenly increases in temperature to 80° F., the viscera may be ıd to remain for some time at 60° F. The dead body is not, therefore, a minimum thermometer in marking a low temperature, but like all l flesh, its temperature rises and falls with the thermometer, although e slowly than other solids possessing better conducting powers.

Mere coldness of the body is not incompatible with a continuance of ; for many morbid causes may modify, or even altogether suspend the luction of heat in the living subject. Thus, in syncope or in hysteria, it ot unusual to meet with extreme coldness of the skin; but this differs n the coldness of death, in taking place over the whole body *suddenly*, in even preceding the state of apparent lifelessness. It does not depend ely, as in death, on the slow and gradual loss of heat, because it is per- ible even when the body is placed in conditions under which a heated stance would not become cold. Besides, the interior of the body at the um or throat will be found to have a higher temperature than the skin he chest or abdomen. Let us take the opposite condition—Can the mth of the human body be retained in its normal state for any length ime after death? We might suppose, *à priori*, that this question should at once answered in the negative; but there are numerous authentic ervations which show that heat may be sometimes long retained by the l body, both on the surface as well as in the cavities; and it has been ced, in certain fatal diseases, that the temperature has actually risen he body after death. This exceptional retention of heat has given to the erroneous suspicion that the person was still living, as in the wing case, a report of which appeared in the 'Lancet' some years e:—

A servant girl, who had retired to bed in apparently perfect health, found on the following morning, as it was supposed, dead. A surgeon was called in pronounced her to be certainly dead, and stated that she probably been dead for some hours. A coroner's inquest was appointed four o'clock of the same day, to inquire into the cause of death; directions were given that a post-mortem inspection of the body should ade in the mean time. The reporter of the case was requested to give assistance. Accompanied by the surgeon who had been consulted, he t to the house about two o'clock, for the purpose of making an in- tion. The deceased was found lying on the bed, in an easy posture, ier left side, her body forming somewhat of a semicircle. The counte- ce was pallid, but so perfectly placid and composed, as to give to her the earance of being in a deep sleep. The temperature of the body, although must have been dead eight or ten hours, was not in the least diminished. room was carefully searched, but nothing in the shape of poison, nor other means of self-destruction, could be discovered: every article of rel lay around, as it might be supposed to have been left, by a person

going to bed in perfect health as usual. The warmth of the body not diminishing, a vein was opened, and various stimuli applied, but without producing any sign of resuscitation. Respiration and circulation had ceased; no artery could be felt pulsating in any part. Two hours had now elapsed since their arrival, and the parties still hesitated to perform the inspection, when a message was sent to them, stating that the jury were waiting for their evidence. The inspection was then commenced; but in moving the body for the purpose, the warmth and pliancy of the limbs were such as to suggest to the examiners that they were inspecting a living subject. The internal cavities were so warm that a copious stream issued from them when they were laid open. All the viscera were healthy, there were no signs of disease;—nothing appeared to account for death, and from what they saw, the inspectors regretted that they had not postponed the examination until the signs of death had been more completely manifested. For obvious reasons, the name of the place where this extraordinary case occurred, and the name of the reporter, were suppressed. It is probable that a high temperature was retained by this body for a much longer period than usual after death. There were, however, two physical causes in operation, the influence of which does not seem to have been sufficiently appreciated. The girl died suddenly while in a state of perfect health and vigour; and until the time of inspection, the body appears to have remained in bed closely covered by badly-conducting materials; *i.e.* the bed-clothes. The temperature of the room in which the body was found, is not stated; but as the month was October, it was probably not low. The temperature of the surface or of the internal organs, was not determined by a thermometer. Although there can be no doubt that this girl was really dead, yet, as a rule, no medical man is justified in making an inspection of a body until after the signs of death (coldness and rigidity) have been clearly manifested. Respiration and circulation had ceased, and no pulsation could be felt in the heart or arteries; the body had been in this state for at least eight hours; hence it is evident that this was not a case of apparent death. The examiners were simply deceived by an unusual retention of heat in the viscera. Doubts were entertained for several days respecting the death of the well-known Prof. Dieffenbach. The unusual retention of heat, and the delay of the putrefactive process, led to the supposition that he was only in a state of apparent death.

It can scarcely be imagined that the production of heat should continue in a really dead body; and yet certain facts connected with the malignant cholera, yellow fever, and other diseases, appear to establish the possibility of this. In some cases of death from malignant cholera, when epidemic in this country, in 1832–3, the body, which had become moderately cold, was observed suddenly to resume its warmth so that the temperature is stated to have risen some time after death as high as 87° F., although circulation and respiration had entirely ceased. In another instance the temperature was observed to rise from 79° to 92° F. after death. This singular phenomenon, like numerous others connected with that disease, has received no adequate explanation. According to Valentin the occurrence of post-mortem heat is common to all dead bodies, the difference being only in degree. It is said to be most rapidly developed after death from injuries to the nervous centres, especially the brain. In cerebro-spinal meningitis the temperature has risen after death from 104° to 111° F., and in a fatal case of small-pox, attended with much delirium, Simon observed that the thermometer rose at death from 104° to 113° F. ('Lancet,' 1870, 1, p. 21.) This production of heat after the cessation of breathing must be taken as evidence of some chemical action; for in real death, the animal body, when it has once become cold, is no more

pable of spontaneously generating heat within itself than any of the ert and lifeless solids by which it is surrounded.

In a case of death from Asiatic cholera Rumsey observed that half ı hour after the complete cessation of respiration and circulation, the uscles of the arms underwent spontaneously various motions of contrac-ɔn and relaxation, continuing for upwards of an hour, and that although eviously cold, they then became evidently warmer. The facts connected th the production of heat in the dead body have not received much tention from physiologists.

John Davy met with some very high temperatures in the *dead* body. a case of rheumatism, after the viscera had been exposed for nearly ten nutes, the mercury of a thermometer, placed under the left ventricle, rose 113° F., and when in contact with the lobulus Spigelii of the liver to 2° F. In a second subject, examined *six hours* after death, the thermo-ter under the left ventricle indicated a temperature of 108° F., and when contact with the lobulus Spigelii 107° F. In these cases the patients re ill but a short time, and died suddenly; and the temperature of the artment in which the observations were made was 86° F. This increase temperature after death has been referred to putrefaction; but Dowler ı shown that it takes place soon after death, and before rigidity sets in. me of the cases reported by Wilks and the author also show that it y take place independently of putrefaction. ('Guy's Hosp. Rep.,' 3, cases 4, 26, 30, p. 184.) Dowler has called this condition post-rtem caloricity; he has noticed it as a common occurrence, in a warm mate, in the bodies of persons who have died from yellow fever. The at of the body, according to him, continues to increase for several hours er death; and in one case, after six hours, he found the arm-pit to re a temperature of 100° F., and the abdomen of 103° F. In another, ɔ temperature of the arm-pit during life being 100° F., it was found that three hours after death the temperature of this part had risen to 104° F.; a third case, a similar increase was observed in thirty minutes. The ghest post-mortem temperatures were observed in the thighs. Thus in ase in which the arm-pit had, during life, a temperature of 104° F., in ı minutes after death it indicated a temperature of 109° F., and in fifteen nutes after death the thigh gave a temperature of 113° F. When the ximum, which is variable in different bodies, has been attained the body adually undergoes the cooling process observed after death, and accord-ɜ to Dowler, this generally commences with the head. ('Phil. Med. am.,' Oct. and Nov., 1845, pp. 625 and 359.) In death from malignant olera he found that the dead body reached its maximum temperature of 9° F. in about an hour and a half. Hensley published, in the same journal, series of cases in old and young persons who had died from different uses; these do not show a similar increase of temperature, but they prove at after thirty hours a dead body may retain a temperature two or three grees above that of the room (Ibid., March, 1846, p. 151). These obser-tions may serve to explain facts similar to those observed in the case of pposed premature inspection just now related, for they show that in some ceptional instances a really dead body may retain for many hours a tem-rature as high, or higher, than that which is usually found in the living.

Dowler considers that the gradual loss of heat in the *interior* of the dy, as determined by a thermometer, furnishes the best test to establish ɔ reality of death. The living body maintains a uniform temperature, lependently of that of the surrounding medium; but a dead body, like ıer inert matter, is governed in its temperature by purely physical con-ions. ('Phil. Med. Exam.,' Oct., 1850, p. 606.) It may be observed, wever, that in temperate climates the signs of death are sufficiently well

marked by the progressive cooling and rigidity of the body, before the application of the thermometrical test to the interior could be made; hence, although it would furnish information that death had certainly taken place, a medical examiner could come to a safe conclusion without it. The occasional existence of post-mortem high temperature offers no objection to this conclusion, since cooling sooner or later follows this condition as a result of ordinary physical causes. The coldness of the living body in cholera, congelation, hysteria, etc., is a physiological condition, and not the result of physical cooling. If death takes place the coldness may continue, or the body may again become warm. In either case it passes ultimately, by physical cooling, to the temperature of the surrounding medium.

3. Cadaveric Rigidity. Rigor Mortis.—The first effect of death from any cause is in most cases a general relaxation of the whole of the muscular system. The lower jaw drops, the eyelids lose their tension, the limbs are soft and flabby, and the joints are quite flexible. In from five to six hours after death, and generally while the body is in the act of cooling, the muscles of the limbs are observed to become hard and contracted, the joints stiff, and the body firm and unyielding. This peculiar condition is known under the name of cadaveric rigidity or *rigor mortis*. The muscular tissue may be considered as passing through three stages in a dead body. 1. It is, as above mentioned, flaccid but contractile, although, as it will be seen hereafter, muscles contracted by living force in the act of dying do not necessarily become relaxed in death; 2. It becomes rigid and incapable of contraction; and 3. It is once more relaxed, and does not regain its power of contractility. The body now passes into the incipient stage of putrefaction. The first stage defines the duration of muscular irritability, the second stage that of cadaveric rigidity, and the third that of the commencement of chemical change or putrefaction.

Experiment shows that the seat of this phenomenon is in the muscular system, for the rigidity disappears immediately on the removal or division of the muscles. According to the experiments of Béclard and others, the rigid condition of the muscles is wholly independent of the integrity of the nervous system; for a division of the nerves leading to the particular muscles, or even the entire removal of the brain, has not been found to prevent, or to retard its occurrence. It has also been observed that when death has taken place from paralysis, hemiplegia, or apoplexy, the rigidity has been as strongly manifested in the muscles of the paralytic or hemiplegic as by those on the healthy side, provided they are well nourished and retain some irritability. The muscles of shattered limbs in death from comminuted fractures do not take on this condition. According to Küssmaul the living metamorphosis of the muscle has ceased; the muscle becoming rigid is a dying—the perfectly rigid, is a dead muscle. Rigidity is in general observed to take place simultaneously with the coagulation of the blood throughout the body. Some have considered it to depend upon this; but not to mention that the alleged cause appears to be wholly inadequate to the effect produced, the rigidity sometimes occurs while the body is warm and the blood fluid, therefore this cannot be the true explanation; moreover it closely resembles the rigidity of syncope and asphyxia, which can have no reference to the coagulation of the blood.

Brown Séquard found by experiments on rabbits that if a current of arterial blood is re-established through muscles in which cadaveric rigidity has already begun to show itself they cease to be rigid, and recover their irritability. He even succeeded in removing the cadaveric rigidity from the muscles of the decapitated body of a criminal, thirteen hours after execution and two hours after the supervention of rigidity, by the injection

of defibrinated human blood. The muscles lost their rigidity, and continued to contract on irritation for several hours. ('Gaz. Méd. de Paris,' Nos. 24 and 27; and 'Amer. Journ. Med. Sci.,' Jan., 1852, p. 221.) These facts appear to show that the muscles, on becoming rigid, still possess vitality. Rigidity is undoubtedly referable to the spontaneous contraction or rather stiffening of the muscles; until it appears these organs are susceptible of galvanic and mechanical stimuli, but after it has ceased this irritability of the muscular fibre is entirely lost. The power with which these organs contract in a state of rigidity is far less than that observed when they are subjected to the influence of volition in the living body. The contractile force is not so great as to induce any apparent alteration in the position of the parts to which the tendinous extremities of the muscles are attached; so that there is no displacement, nor is any force of counterbalancing nature manifested between flexors and extensors. It is asserted that the flexor muscles are usually more contracted than the extensors, so that the limbs and trunk, as well as the fingers, if left undisturbed in the dead body, have a tendency to assume a state of flexion. As a general rule, however, the position in which the muscles may be, at the time of death, is that which they retain during the state of rigidity, whether the body be lying, sitting, or standing, and whether the limbs be in a state of flexion or extension. When the rigid state is strongly manifested the muscles assume a prominence, as under violent contraction in the living body.

When a muscle enters into the condition of *rigor mortis* it loses its transparency and becomes opaque. It has lost much of its former softness, and has become firmer and more resistent. Previously amphichroitic, *i.e.* capable of turning red litmus blue and blue litmus red, the muscle is found to have become distinctly acid—more acid than during the state of contraction in life. At the onset of *rigor mortis* the muscle undergoes a distinct rise of temperature. The peculiar feature of *rigor mortis* is, however, the coagulation of some portion of the fibre: no coagulable muscle-plasma is obtainable from the rigid muscle. The rigid muscle indeed contains ready formed myosin, the result of a coagulation of the muscle-plasma coincident with, and constituting an important part of the phenomena of *rigor mortis*.

The *time* at which rigidity occurs after death, as well as its duration, is affected by various circumstances. It generally commences within *five* or six hours, and lasts from sixteen to twenty-four hours. Sommer assigns the time at which it occurs, after the cessation of respiration, as not later than seven hours. Nysten, who closely investigated this subject, considered that rigidity never made its appearance in the muscles, until the body had entirely lost its animal heat; but some of his own observations tend to show that this statement is not correct. Cases every now and then present themselves in which, after death, the limbs become rigid while they are yet warm; and it is the same with the trunk.

Ollivier observed, in cases of death from malignant cholera, that cadaveric rigidity occurred while the body was yet warm. He also saw a rigid condition of the muscles in well-developed bodies, which were inspected in from six to eight hours after death. ('Ann. d'Hyg.' 1833, 1, 233.) Brown Séquard mentions the case of a man who died in one of the Parisian hospitals in 1849, in whose body cadaveric rigidity appeared three minutes after he had ceased to breathe, and while the heart was still beating twenty times in a minute, while the man was still alive, if life is considered to persist so long as the heart beats. These beatings ceased only three minutes and a half after cadaveric rigidity had shown itself everywhere. A quarter of an hour afterwards, there was no trace of cada-

veric rigidity, and in less than an hour after death, signs of putrefacti had appeared in the limbs. This man died of exhaustion after prolong typhoid fever. ('Savory on Life and Death,' p. 196.) According Küssmaul, when the muscular system is powerfully developed and death sudden, rigidity may not occur for sixteen or seventeen hours, and t shortest period within which it may occur and pass off in such cases, about ten hours after death; but under certain circumstances it may co tinue for fourteen days or even longer. In a case in which the author w consulted, a stout muscular man died suddenly from an attack of apople His body was exhumed and examined three weeks after death in the mor of January. It was in a good state of preservation, and the limbs were rigid that it required a great degree of force to bend them. No doubt this case cold favoured the continuance of rigidity.

The following case related by Chowne, shows the rapid access cadaveric rigidity in a new-born child, as well as its occurrence in a de body before the entire loss of animal heat. He was called to a labo and when he arrived, the child had been born about three quarters an hour, and the midwife was then engaged in dressing it. One a was a little raised and the hands were partly closed—these circumstan giving it the appearance of being a living child. He found, howev that it had actually been still-born, and that it had been part of the ti in a warm bath. The other limbs were also stiff in about the sa degree. The stiffness was unequivocal, there was no elasticity, as if was the result of spasmodic muscular contraction:—a joint being flex it remained flexed. The midwife particularly observed the stiffness wh the child was in the warm bath. The mother said the child moved, ve perceptibly to herself, not long before its birth. Whether the skin was wa or cold is not stated, but the body of a child cools very quickly. It is p bable, from the midwife's statement, that the rigidity came on immediat or very soon after death. Sommer placed the bodies of two infants, whi had died asphyxiated, in tepid baths at from 90° to 99° F. immediately aft birth, and left them there. In between three and four hours rigidity w developed, and had attained its height in six hours. In eleven hours t rigidity of the lower jaw had disappeared. The presence of *rigor mortis* a new-born child may show that it has been recently living, but it will n show that it was born alive. In a case of alleged child murder, tried the Dorchester Assizes, the rigidity of the body of the infant was wrong assumed to indicate that the child had been born alive, and had had independent existence. In 1871 Parkinson delivered a woman of a ch which died during labour. On the next day the fingers of the dead ch were tightly clenched, the fore-arms rigidly bent on the arms and the le on the thighs. In another case he was compelled to perform craniotomy a dead child to effect its delivery. On the following day there was stro *rigor mortis*.

The author observed in a cat which had died from disease, that the bo and limbs became perfectly rigid about an hour after death, while warm was still very great throughout. The bodies of birds generally become rig before they cool. He has also remarked, in animals poisoned by prus acid, where convulsions ensued, that they died in violent muscular spas with the limbs and tail perfectly rigid while the body was warm. This l condition, however, corresponds rather to what has been called cadave spasm than cadaveric rigidity. The difference between these two stat will be a subject for after-consideration.

Brown Séquard has demonstrated the relations between muscular irri bility, cadaveric rigidity and putrefaction ('Pr. Roy. Soc.,' 1861, p. 20 and maintains that the greater the degree of muscular irritability at t

ime of death, the later the cadaveric rigidity sets in and the longer it asts; and that the later putrefaction appears, the slower it progresses.

Cæteris paribus, rigidity is always more strongly manifested and continues for a longer period, in those bodies in which the muscular system is ealthy and fully developed. It has been observed, that the time at which t appears after death in muscular subjects, is longer than in other cases, so hat it may not supervene for twelve or fourteen hours, and it may last for wenty-four or thirty-six hours. Rigidity is said to be slow in manifesting self in death from hæmorrhage, irritant poisoning, apoplexy, wounds of he heart, decapitation, as also in all cases of asphyxia, especially in death rom hanging, or from the action of carbonic acid. In a case of suicide rom a fatal wound in the throat, observed by Handyside, the rigidity of he muscular system commenced while the body was yet warm, and was omplete in *one hour and a half* after death. This early occurrence of igidity cannot be referred to any influence produced on the muscular ystem by loss of blood. In a case of death from hæmorrhage, in which our pounds of blood were suddenly lost from the axillary artery, it was bserved that eight hours after death, the arms and legs were pliant; nd it was not until twelve hours after death, when the body was becoming old, that rigidity manifested itself. Death by hæmorrhage, therefore, does ot accelerate this condition; it appears to have no more influence upon the eriod of its occurrence, than it has upon the cooling of the body. So with gard to irritant poisoning in an acute form; no difference was observed in ference to the rate of cooling or the commencement of rigidity in a well-arked case of death from arsenic in eleven hours. In a case of suffocation y charcoal vapour, Nysten observed that rigidity did not make its appear-ace until *sixteen* hours after death, and it is stated to have lasted for the ng period of *seven* days. In other instances of suffocation, this protraction f cadaveric rigidity has not been noticed.

In these cases, the slow access of this state depends less on the mode of eath than on the irritability of the muscles at the time of death. This is lways great when the nutrition of the muscles is perfect, a condition which ists in cases of violent death, as from decapitation, sudden hæmorrhage, r some form of asphyxia. Symonds saw a body in a state of rigidity ight days after death by hanging. Nysten found that there was muscular rritability in the body of a decapitated man, twenty-six hours after the ead had been severed from the body; and Brown Séquard states as the eneral result of his experience, that in the bodies of healthy persons ecapitated or asphyxiated, cadaveric rigidity did not appear sooner than en or twelve hours after death, and that it lasted more than a week even hen the weather was warm. He has found in the muscles of the limbs f two decapitated men, some degree of irritability thirteen and fourteen ours after death.

Atmospheric changes appear to modify considerably the duration of this tate. Dry and cold air will cause it to persist for a long time; and thus it s, that during the winter season, especially in a frost, it is slow in disap-pearing;—its mean duration being then from twenty-four to thirty-six ours. If the air is warm and saturated with humidity, it soon ceases. Temperature appears therefore chiefly to affect its duration and intensity. Sommer found that, other things being equal, bodies became rigid as quickly in an atmosphere of from 59° to 63° F. as in one from 77° to 81° F.; but that the bodies of strong persons continued rigid for eight or ten days at a temperature of from 36° to 45° F., while it totally disappeared in from four to six days when they were exposed to a temperature of from 65° to 86° F. Bodies sunk in cold water soon pass into this state, and retain their rigidity for a long time. Water is a better conductor of heat than air, and

tends to retard putrefaction. The contracted state of the skin known as *cutis anserina* is sometimes observed in a recently-drowned body.

According to Nysten cadaveric rigidity first appears in the muscles of the trunk and neck; it then takes place in the muscles of the upper extremities, and lastly in those of the lower. In regard to its disappearance, the muscles of the lower extremities will often be found rigid, while those of the trunk and upper extremities are again in a state of relaxation. It appears later and lasts longer in the lower extremities, than in other parts of the body. If Nysten's theory were true, that rigidity depended exclusively on the mere loss of heat, it should appear first in the lower extremities, and last in the trunk. His own observations, therefore, respecting the order of its disappearance are against his theory. Later observers have to some extent corroborated Nysten's statements regarding the commencement and diffusion of rigidity. Thus it begins almost always in the neck and lower jaw. Sommer found only one exception to this rule in examining two hundred dead bodies. From the neck it passes in two directions: upwards to the muscles of the face, and downwards to the muscles of the upper extremities and trunk—then attacking those of the lower extremities. In the particular limbs, it commonly proceeds from above downwards, and it generally passes off in the same order. It always sets in, increases, and decreases imperceptibly and gradually, in which respect it differs strikingly from the rigidity of muscles as a result of disease. ('Küssmaul, Vierteljahrsschr. f. prakt. Heilk., 1856,' B. 2, s. 67. See also a trans. by Moore, 'Dublin Quar. Jour. Med. Sci.' 1856, vol. 22, p. 490.) A more recent observer, Larcher, who states that he has examined more than six hundred dead human bodies, as well as the bodies of a great number of animals, assigns the following course unless convulsions may have been present at the time of death. Rigidity commences in the lower jaw—affects the lower limbs—and afterwards the neck and the upper limbs. Those muscles which are the first to become rigid are the longest to retain rigidity. ('Ann. d'Hyg.' 1869, 1, 469.)

It will now be necessary to consider whether a living body ever assumes a condition analogous to that of cadaveric rigidity. Tetanus, apoplexy, catalepsy, hysteria, syncope, and asphyxia, have been stated to present symptoms which might lead to doubt respecting the reality of death from this sign. There are, however, these striking differences. In rigidity from any of these diseases, the warmth of the body is commonly in great part preserved, if not on the surface, in the rectum and flexures of the joints. The rigidity of disease takes place simultaneously with the apparent suspension of life from the attack; and lastly, the whole of the body becomes equally rigid at the same moment, owing to the existence of a general muscular spasm. In order to distinguish this state of spasm in a really living member from the rigidity of death, it has been recommended to bend it forcibly; if it be in a state of spasm from disease (tetanus), it will return to its original position so soon as the bending force is removed; if it be in a state of cadaveric rigidity, the limb will not return to its position, but may be afterwards moved in any direction. If rigidity was at the time fully developed, the muscle will not again become rigid; if, however, rigidity was only commencing, then the limb will again resume its rigid condition, but slowly. (Sommer.) This is the main distinction between rigidity in a living and in a dead body. In real death, however, other unequivocal signs will be present. Rigidity takes place in the muscles of the countenance as well as in those of the body. It is important to bear this in mind, since identity may be mistaken when a corpse is seen about this period. The expression of the countenance, as of anger, pain, or terror, at the moment of death, depends on the contraction of the facial muscles.

er death these, like other voluntary muscles, undergo relaxation, and the e assumes a placid appearance; but as rigidity manifests itself, there is ietimes a remarkable change of expression. The face is pale or sallow, jaws are fixed, the corners of the mouth are drawn downwards, the ples sunk, and the brow contracted. Even those who may have wn a person well during life, would scarcely recognize him at this time, e they to see the body in a strange locality. Snow was once called to a young woman after she had been dead three days, whose face had denly become so suffused and red, that her friends doubted the reality ier death. After a time, however, the colour abated, and the com- cement of putrefaction clearly proved that she was dead. ('Med. ic,' Jan., 1863, p. 26.) The author has witnessed a similar appearance in rpse; the cheeks acquired a florid red colour between the third and th day after death, when rigidity had ceased. It is supposed that this ur is due to the action of the oxygen of the air on the blood forced into apillaries by incipient decomposition. It is hardly necessary to observe this appearance, coupled, as it is stated to have been in some cases, with ght degree of warmth, could not give rise to any mistake about the date eath, since the rest of the body would be cold, and in death which is y recent the face becomes cold before the skin of the chest and abdomen. According to Symonds, the kind of death has a great influence on expression of the countenance. On fields of battle, the corpses of e who have died of stabs are said to be easily distinguished by the tenance from those who have fallen by gunshot. In the former, an emely painful impression must have been transmitted to the brain, h produced the usual change in the nerves and muscles of expression; ie latter, concussion was given to the whole system, paralysing, without intermediate sensation, so that no expression remained more than that e repose of the muscles. ('Cyc. Anat. and Physiol.,' art. Death.)

The involuntary muscles are subject to cadaveric rigidity as well as the ntary, and by reason of the more speedy loss of muscular irritability, pears in them more rapidly. The ventricles of the heart commonly their irritability within an hour after death. They become rigid, and in in that state for ten or twelve hours, sometimes for twenty-four irty-six hours, then again becoming relaxed or flaccid (Carpenter). I saw the heart of a criminal a quarter of an hour after decapitation, ng with great distinctness. The left auricle in particular exhibited g and regular action, forty-four times in a minute, and continued to for an hour. ('Prov. Med. Journ.,' Sept., 1851.) At a certain period death, the heart becomes rigid and firmly contracted. If examined at time, it may appear to be in a state of spasm and to have its walls ened, while the cavity of the left ventricle may be described as being h smaller than in the normal state. Paget has pointed out that this ral condition of the heart after death has led to pathological mistakes, walls being described as thickened and the cavities being diminished ze, and the heart itself as being in a state of concentric hypertrophy disease. On the other hand, the perfect relaxation of the heart which ws at a later period after death, has been mistaken for and described morbid flabbiness and flaccidity. Spasm and paralysis cannot be in- d to have existed when we discover these conditions of the heart in dead body.

The observations of Brown Séquard have already been quoted (*ante*, p. as furnishing an explanation of many of the difficulties connected with occurrence, duration, and disappearance of cadaveric rigidity. This iologist agrees with Nysten and others that the greater the degree uscular irritability at the time of death, the later cadaveric rigidity

sets in, and the longer it lasts; and the later also putrefaction appears, the more slowly it progresses. Müller and Gierlichs had already shown that rigidity does not occur until the muscles have lost their irritability, or their power of contracting on the application of ordinary stimuli; that in frogs, in which, as in other reptiles, muscular irritability is very persistent, rigidity is often not established until three or four days after death; that in birds, on the other hand, in which muscular irritability remains but a short time after death, rigidity ensues quickly. Further, all circumstances which cause a speedy exhaustion of muscular irritability during life, induce an early occurrence of cadaveric rigidity, while those conditions by which the appearance of irritability is delayed, retard its access. ('Baly and Kirke's Physiol.') Brown Séquard observed as a result of his experiments on animals, that when the temperature of the muscles was diminished before death, their irritability lasted long after death; cadaveric rigidity set in late, and lasted long; and putrefaction appeared late and proceeded slowly. Whatever exhausts muscular irritability, such as violent exercise or exertion, accelerates rigidity in the dead, and, in an equal degree, putrefaction: this applies to observations on man, as well as on animals. Rigidity takes place rapidly in the dead bodies of cattle that have been overdriven, or of animals that have been hunted to death. Mackintosh has communicated some facts which he collected respecting the bodies of hares run down by coursing. Cadaveric rigidity generally appeared in from one hour to one hour and a half—but the longer and the more severe the course, the sooner it appeared—thus bearing out the views of Brown Séquard respecting the exhaustion of muscular force. In three of these experiments, the throats of the animals were cut when they were run down. One lost two ounces of blood, a second lost very little, and a third none. Yet in each of these instances cadaveric rigidity began one hour and twenty minutes after death. The bodies of soldiers killed in the early part of a battle become rigid slowly, while the bodies of those who are killed at the close, after many hours of violent muscular exertion, become rigid almost immediately. This may explain the singular fact recorded by military men, that the dead bodies are sometimes found on the field of battle stiffened in the attitude of kneeling or sitting with their weapons clenched firmly in their hands. There has been no relaxation in death, but the muscles appear to have at once passed from a living contraction into a rigid condition. This also throws light upon a fact to be presently noticed, that suicides are sometimes found with weapons grasped in their hands, and their bodies stiffened in the attitudes in which they have died. It may be inferred in these cases that from some cause operating during life, the muscular irritability was exhausted at the time of death. Hence the greatest differences are observed to exist in regard to the commencement of cadaveric rigidity and putrefaction, in consequence of the variable degree of muscular irritability at the time of death. Brinton has recorded his experience on this curious subject during the American war. In many who had died instantaneously from brain- and heart-wounds, the body was rigid throughout, and the position was that of the last moment of life. He has called this *instantaneous rigor*. After the battle of Antietam, in 1862, he counted within a small space, forty dead bodies, mostly with chest wounds. There were some with their arms raised rigidly in the air, and others with their legs drawn up and fixed. In not a few the body was curved forwards and fixed. These attitudes were not those of the relaxation of death, but were rather of a seemingly active character, the muscles remaining rigid and inflexible as the result of spasmodic muscular action in the last moment of life. ('Amer. Jour. Med. Sci.,' Jan. 1870, p. 87. Also 'Lancet,' 1870, 1 p. 276.)

The effects of strychnine and other poisons which produce convulsions may be explained by reference to their action on the muscles. Rigidity has been observed to set in with great rapidity in animals destroyed by strychnine or veratrine. Küssmaul made a similar observation in reference to the action of coal-gas on the system. Brown Séquard noticed that when death was produced almost at once by these poisons, or by others having a similar mode of action, *e.g.* atropine, morphia, oxalic acid, and mercuric cyanide, there was hardly any effect observed on the time of access and duration of rigidity and putrefaction; but when convulsions had existed for a long time before death, the influence was most remarkable. He poisoned three healthy dogs, as much alike as possible, with acetate of strychnine. One of them had a dose of two grains, another of half a grain, and the third of one-fourth of a grain. The first dog died at once; the second after twelve minutes, during seven of which it had convulsions; and the third after twenty-one minutes, during eleven of which it suffered from convulsions. The following are the tabulated results in reference to the duration of muscular irritability and of cadaveric rigidity, as well as of the occurrence of putrefaction:—

	Durat. of musc. irrit.	Durat. of cad. rigid.	Putrefaction.
1st dog	8 hours	19 or 20 days	slow
2nd dog	2½ „	5 days	rapid
3rd dog	½ „	less than a day	very rapid

In other animals which were killed by poisons causing convulsions, the more violent and frequent the convulsions were, the sooner cadaveric rigidity set in after death; and the shorter the time that it lasted, the sooner also did putrefaction appear, and the more rapid its progress. In reference to the author's own experiments, a rabbit died from the effects of half a grain of strychnine in twenty-three minutes; during the last eleven minutes it had several fits of convulsions, and died in one of these. In ten minutes after death, rigidity showed itself in the hind legs, and rapidly spread throughout the body. The rigidity had decreased in two days, and had nearly disappeared in four days. ('Guy's Hosp. Rep.,' 1856, p. 112.) Clegg has communicated the case of a woman who died in Sept., 1864, from the effects of a large dose of strychnine, whose body passed rapidly into a rigid state. The strychnine, mixed with laudanum, was taken about 8.30 a.m., and she was found dead in a field, with the limbs rigid and the body quite cold, at 11 a.m. There was slight warmth in the arm-pits. The deceased was fully dressed, and the weather was warm for the time of year. In the body of a strongly built woman, who died of hydrophobia after violent convulsions, Brown Séquard found that cadaveric rigidity had set in within the first hour after death, and that it had ceased before the end of the tenth hour.

Although, according to Nysten and Brown Séquard, the later the time at which rigidity commences the longer it lasts, yet it does not necessarily follow that when it speedily supervenes after death, it will rapidly disappear. There are many facts which show that when the muscles are strongly contracted at the time of death, they become rigid in this contracted state, and remain rigid for many hours, and even days.

The rigidity produced as a result of poisoning by strychnine may sometimes continue for a very long period. Thus, in the case of *Cook* (*Reg.* v. *Palmer*, C. C. C., May, 1856), the body when examined on the sixth day after death, was in a state of rigid spasm, and the members were found in a similar state on the exhumation of the body two months afterwards. It is worthy of remark that Cook lived only twenty minutes after the symptoms first appeared. He suffered from a few convulsive fits, but not sufficient to exhaust the irritability of the muscular system.

These facts have an important bearing on cases of poisoning by strychnine and other spinal poisons. The state of the dead body will vary according to the rapidity of death, and the degree of exhaustion of muscular irritability at the time of death, as a result of the fits of convulsion produced by the poison. They also show that when, from whatever cause, muscular irritability at the time of death is slight, either in consequence of a bad state of nutrition or of exhaustion from over-exertion, or from convulsions caused by disease or poison, cadaveric rigidity sets in and ceases soon, and putrefaction appears and progresses quickly. (Brown Séquard, 'Proc. Roy. Soc.,' 1861, p. 204.) For a similar reason it takes place at an earlier period in the very young and the old, than in an adult at the prime of life.

It has been long observed that the bodies of those who are emaciated, or who die from debilitating diseases, such as phthisis, typhus or typhoid fever, and malignant cholera, pass rapidly into a state of rigidity, which is commonly of short duration. Hence, owing to want of correct observation, it has been erroneously stated that cadaveric rigidity did not occur in such cases. In reference to deaths from malignant cholera, Brown Séquard observed, that cadaveric rigidity appeared late and lasted long in those patients who died quickly, that is, before a prolonged alteration of nutrition, and that those muscles which had been attacked with violent and frequent cramps, became rigid very soon after death, and remained so only for a short time. Olliver found that the bodies of cholera patients were frequently rigid in from six to eight hours after death, while the muscles which were the seat of this rigidity were still warm, and on making an incision into them, the blood readily flowed out. A similar error has arisen respecting the bodies of persons killed by lightning. John Hunter thought that cadaveric rigidity did not occur in this mode of violent death; but Brodie found that the body of an animal killed by electricity became, as usual, rigid after death. In an accident which occurred in France, in Aug., 1846, a group of labourers was struck by lightning: four were killed on the spot, and five or six severely wounded. It was remarked that the person whose body bore the most extensive marks of injury had worn a goat-skin. There were several lacerations about this body, and in three hours after death it became perfectly rigid. ('Med. Gaz.,' vol. 38, p. 351.) In another case of death from lightning, rigidity was strongly marked in the limbs about twenty-eight hours after death. ('Med. Gaz.,' vol. 47, p. 844.) In May, 1854, during a storm, a man was struck by lightning. He made a short exclamation, and immediately expired. It was observed in this case that the body became rigid after death.

Facts are now sufficiently numerous to enable us to say that the old opinion of the non-occurrence of rigidity in the bodies of persons killed by lightning is unfounded. Bagot met with it in a case which he examined in the summer of 1855, in which the body of a man, æt. 28, who had been killed by lightning, was as rigid twenty-eight hours after death as if death had taken place from any other cause. The researches of Brown Séquard afford a satisfactory explanation of the differences among physiologists upon this question. In some instances, no doubt, cadaveric rigidity has set in, and has been of such short duration, that it has not been possible to ascertain its existence. Death by lightning may be the result, 1st, of syncope by fright, or in consequence of a direct or reflex influence of lightning on the par vagum; 2nd, of hæmorrhage or bleeding in or around the brain, the lungs, or pericardium; and 3rd, of concussion, or some other change produced by the electricity on the brain and nervous system. When death by lightning is due to any one of these causes, cadaveric rigidity may appear and run through its course rapidly, as it

some other cases of sudden death. But lightning may destroy life like a powerful electric shock, by producing such a violent convulsion of every muscle in the body that muscular irritability ceases almost at once. The rigidity in this case may be of such short duration as entirely to escape notice. Lightning may indeed reduce the duration of muscular irritability to the fraction of a second, and that of cadaveric rigidity in a corresponding degree, so that no trace of it may remain even a few minutes after death (op. cit. p. 209). Ranke has made the curious observation, that there is a difference in the conducting power of living and dead muscle, in reference to electricity. Contrary to that which might have been anticipated, he found that dead muscle was a much better conductor than living muscle; and he traced this increase in conducting power to the presence of certain products of decomposition which do not appear until after death.

It has been observed, as a general rule, that cadaveric rigidity does not affect the relative position of the parts to which the muscles are attached; but a peculiar condition of the *hands* of the dead, observed by Villermè, would tend to show that in dying, the fingers assume a certain position by virtue of the contraction of the flexor muscles connected with them; although it is not quite established, whether this contracted state of the fingers takes place at the same moment with the commencing rigidity of the body, or whether it is not an immediate consequence of dissolution. Villermè has remarked, that in a dead body, the thumbs are always bent inwards towards the palms of the hands, the apex of the thumb being opposite the base of the little finger; and the thumb itself being covered by the four fingers of the hand. Villermè found this condition in many dead bodies which had not been disturbed. Devergie supposes that this position of the thumbs depends on a convulsive action of the fingers at the last moment of life; and as death may take place without any convulsive action, the appearance may be in some instances wanting. This sign of death, if it can be so called, is of but little importance; it will, however, be found in a large number of cases where there has been no interference with the hands. ('Ann. d'Hyg.' 1830, 2, 420.)

There is another condition of the *hand* in the dead which calls for notice. If the hand of a living person is held before a strong light, it will be found to be translucent, and of a deep red colour from the transparency of the fluid blood circulating through it. The hand of a really dead person thus examined is stated to be in all cases opaque owing to the opacity of the coagulated blood. In applying this as a test, we must remember that a horny or hardened state of the cuticle, or a diseased condition of parts, may interfere with this translucency in the living subject: it is always better seen in the young and in those whose hands are thin. In these cases the fingers appear to be formed of a mass of blood; they have a deep red tint, except about the joints, where the colour appears lighter.

The Eyes.—Shortly after death, the cornea becomes dull, its brightness and prominence disappear, the globe becomes collapsed, and, after a time, the surface of the membrane is wrinkled. Louis long since observed, that the eyes of the dead became flaccid and soft in a very few hours after dissolution, and that a film was formed over them; this condition he considered to be characteristic of death. It is necessary to observe, however, that while this appearance is not always met with in the dead body, it is sometimes found in the living. In those who have died from apoplexy, or from the inhalation of carbonic acid gas, the eyes have often preserved their brilliancy and prominence for a length of time. This has also been observed in those who have been poisoned by prussic acid, potassium cyanide, or the essential oil of bitter almonds. Incipient putrefactive changes may, by

forcing the blood towards the head, cause a prominence and brilliancy of these organs, in those bodies in which they were dull and collapsed soon after death. On the other hand the film over the eye and the collapse of the globe have been observed in cases of malignant cholera several hours before death, and while the heart was still beating. ('Ann. d'Hyg.' 1848, 1, 104.) Larcher has pointed out a sign which he calls cadaveric imbibition of the globe of the eye. This appears in the shape of a blackish stain on the sclerotic coat on the outer side. This is at first slight, but becomes gradually deeper. It is followed by a similar patch or spot on the sclerotic in the inner side. They extend towards the centre of the eye, approaching each other, and forming the segment of an ellipse. This appearance is probably due to the sclerotic becoming thinner in these parts by evaporation and the dark pigment showing itself through it. Larcher describes this mark as the forerunner of putrefaction, following rigidity but preceding even the green tint which is seen in the skin of the abdomen at the commencement of this process. ('Ann. d'Hyg.' 1869, 1, 468.) Kussmaul states, that no conclusion can be drawn, from the width of the pupils in death, as to the diameter which they presented at the latest period of life. This statement is of some practical importance in reference to post-mortem appearances in cases of alleged narcotic poisoning. Ripault noticed that in real death, the iris is perfectly flaccid. This is seen when the globe is compressed in two opposite directions at the same time. If the person is living, the pupil retains its circular form, notwithstanding the compression. If dead, the circular form is lost, and the aperture becomes irregular. Fleming has noticed that a solution of atropine, which by causing dilatation of the pupil would in a few minutes reduce the living iris to a mere line, has no action on the iris of the dead eye; but this result probably depends on the time after death at which the liquid is applied. Jobst and Hesse found that two drops of an aqueous solution of physostigmine (the poisonous alkaloid of the Calabar bean) applied to the eye of a rabbit an hour after death from natural causes, caused the pupil to contract to one-fourth, compared with the other eye, and it remained in this condition. ('Chem. News,' March 5, 1864, p. 109.) In cases of catalepsy, or trance simulating death, the pupil retains its contractile power. It contracts under a strong light and dilates when the light is withdrawn. In real death the pupil is not affected by light.

The Skin.—After dissolution, the skin is observed to become extremely pallid and waxy-looking, owing to the absence of all circulation. In some parts as the body cools it becomes covered by livid discolorations (cadaveric ecchymosis); this is especially the case in those instances where death has taken place by sudden violence. One of the most striking changes in the skin is its entire loss of elasticity. In the living body, if any part of the surface be compressed, the skin will readily return to its original form on removing the pressure. Thus, in a doubtful case, a flatness of those parts which have been allowed to lie upon an even surface may be regarded as a sign of real death, provided the other concomitant changes are observed. It is almost unnecessary to remark, that if certain diseases have the power of depriving the skin of its elasticity, the history of these cases, or a superficial inspection of the body, will suffice to show to what cause the want of elasticity is to be attributed.

Among the signs of death has been enumerated *coagulation of the blood.* Donné suggested that, in order to determine the reality of death before the access of putrefaction, a small portion of blood should be drawn from a vessel, and it should then be observed whether it coagulated or not. If instead of a red homogeneous *coagulable* liquid we obtain only a reddish coloured uncoagulable serum, from which the particles speedily subside as

a red sediment, we shall be justified in inferring that life has ceased—a conclusion at which we could not arrive if even the smallest portion of coagulum should be formed. This appears to be a fair physiological test, and easy of application. When the blood has once coagulated, there must be an arrest of circulation; and although it might become again fluid, this would be only under the influence of putrefaction, and it would not thereby recover a coagulating power. One of the great characters of blood effused from a *living* body is, that it coagulates speedily after its effusion. Thus, drops from an artery thrown on furniture or a wall speedily consolidate, assuming an oval or long elliptical form, the narrow point downwards, and at this part will be found the coagulum of fibrin locking up the red colouring matter. Blood sprinkled from a dead body is more liquid; it forms a long irregular drop or streak, and only dries up by evaporation.

The blood coagulates in most cases after death, but at a variable time after the cessation of the heart's action. When blood is removed from the living body, coagulation commences in from five to ten minutes. In the dead body, it probably does not commence until it begins to cool. Hence the fact of coagulation does not prove that the person is living. Wilks has observed that when a body is examined eight or ten hours after death it is not unusual to find the blood which may have flowed from it as a liquid, forming a firm clot; and that which is effused into the chest during the examination often forms after some time a very firm coagulum. ('Guy's Hosp. Rep.,' 1863, p. 183.) It has been stated that the blood of persons killed by lightning does not coagulate, but this statement is erroneous. Certain diseases appear to influence the coagulation of the blood. Savory has observed that coagulation has been partial or imperfect in cases of death from delirium tremens; and it is well known that in rapid death from certain vegetable poisons the blood is found fluid and of a darker colour than natural, even when the examination is made soon after death.

CHAPTER 4.

CADAVERIC SPASM—EVIDENCE OF MURDER, SUICIDE, OR ACCIDENT FURNISHED BY THE POSITION OF A DEAD BODY—WEAPONS FOUND IN THE HANDS—MUSCULAR IRRITABILITY — TESTS OF ITS PRESENCE — POST-MORTEM CONTRACTILITY — ALLEGED PREMATURE INTERMENTS — PROOFS OF THE REALITY OF DEATH — DEATH-TRANCE — APPARENT DEATH IN THE DROWNED AND IN NEW-BORN CHILDREN.

In reference to persons found dead, the position or attitude of the body, if undisturbed, may often throw an important light on the mode of death, and on the question whether the deceased had died by his own act or by the act of another.

Cadaveric Spasm.—It has been already stated that, as a general rule, the muscular system passes into a state of relaxation at the moment of death. This is observed in cases of tetanus of a severe form, whether produced by disease or by poison. Half a grain of strychnine was given to a rabbit. After several fits of convulsions the animal died; respiration ceased in twenty-three minutes. At this time there was perfect flaccidity of the body, limbs and joints; but this condition lasted but for a very short period. The animal was placed on its back, and the legs raised, for the purpose of making an examination of the chest. In ten minutes the body became, while still warm, perfectly rigid in the attitude in which it was held—the fore-legs remaining stretched upwards and wide apart. If an animal dies

in a convulsion, and the body is not disturbed, the tetanic spasm may pass rapidly into cadaveric rigidity. This has been called tetanic rigidity, but it is in fact cadaveric rigidity, or muscular spasm, showing itself in a persistent form after death. When the rigid state is destroyed by forcibly bending a joint, the limb will not return to its position like one which is contracted by a tetanic convulsion. Engel has seen this transition from spasm to rigidity; and in experiments on animals, a rigid condition assumed is noticed after death without any apparent relaxation of the muscles. Sommer and Clemens have observed, in fatal cases of rheumatic tetanus, that the spasms of the muscles of the jaw, neck, and back, passed immediately into cadaveric rigidity. (Küssmaul, loc. cit. 490.)

That spasmodic condition of the muscles which passes into rigidity in death from tetanus, may also show itself in other cases of strong muscular contraction at the moment of death. Thus a body may stiffen or become rigid in an attitude of attack or resistance; the members may retain in a rigid state the position which the last act of volition imparted to them. The term cadaveric spasm has been applied to this condition of the muscles; it is nothing more than muscular rigidity or violent muscular contraction so rapidly followed by the rigidity of death that the muscles have not relaxed on the cessation of life.

Marc first directed the attention of medical jurists to this subject in reference to a case which will be hereafter related. He considered that this form of rigidity might occur as a result of sudden death from apoplexy, and he quotes the following case as an illustration:—An aged man, while at the theatre with his family, rested his forehead upon his hands, which were crossed in front of him, while with his elbows he leaned on the front of the box. It was thought that he had gone to sleep in this attitude, and he was not disturbed; but after the performance was over and the persons were about to leave the theatre, it was found that he was quite dead. ('Ann. d'Hyg.' 1832, 1, 602.) A lady who had retired to her bed-room in perfect health was found dead the following morning. The editor has seen a similar case. She was kneeling at a chair in the attitude of prayer, and her body had become rigid in this position. This was also a case of sudden death from apoplexy. In some instances in which chloroform vapour has caused accidental death, the hand firmly grasping the handkerchief has been found applied to the mouth and nostrils, as if the deceased were still breathing the vapour.

From what has been elsewhere stated (p. 58) this singular condition of the body is more likely to present itself in those cases in which there has been great muscular exertion, and when muscular irritability is nearly exhausted at the moment of death. Corpses have thus been seen stiffened on the battle-field in the last attitude of life. Russell thus describes what he saw after the battle of the Alma in the Crimean war:—'The attitudes of some of the dead were awful. One man might be seen resting on one knee, with the arms extended in the form of taking aim, the brow compressed, the lips clenched, the very expression of firing at an enemy stamped on the face, and fixed there by death: a ball had struck this man in the neck. Another was lying on his back, with the same expression, and his arms raised in a similar attitude, the Minié musket still grasped in his hands, undischarged. Another lay in a perfect arch, his head resting on one part of the ground and his feet on the other, but the back raised high above it.' Cases of a similar kind were noticed in the Italian war after the battle of Solferino, and in some of the battles in North America between the Federal and Confederate States. See p. 57; also 'Savory on Life and Death,' p. 192.

The case of the ill-fated Captain Nolan, who fell at the battle of

is of historic interest, and is thus described by Mr. Kinglake.
of a shell ' met Nolan full on the chest, and tore a way into
The sword dropt from his hand; but the arm with which he
it the moment before still remained high uplifted in the air, and
he practised horseman remaining as yet unrelaxed still held him
addle. Missing the perfect hand of his master, and finding the
governance now succeeded by dangling the reins, the horse all at
l about, and began to gallop back upon the front of the advancing
hen from what had been Nolan—and his form was still erect
e, his sword-arm still high in the air—there burst forth a cry
and appalling, that the hearer who rode the nearest to him
called it "unearthly." And in truth, I imagine the sound
n no human will, but rather from those spasmodic forces which
on the bodily frame when life, as a power, has ceased. The
rider, with arm uplifted and stiff, could hardly be ranked with
. . This dead horseman rode on till he had passed through
of the 13th Light Dragoons. Then at last he dropped out of
('Invasion of the Crimea,' 6th ed. vol. v. p. 222.)

of sudden and violent death, it is by no means unusual to find
one or more of the limbs, rigid and fixed in a state of spas-
action. This is sometimes witnessed in cases in which persons
full and robust health. The body of a suicide may be dis-
tched on the floor of an apartment, with the suicidal weapon
ed in his hand. Razors and pistols are thus frequently found
s of suicides, whether recently dead, or whether they have been
time before they were discovered: and these instruments may
or held under circumstances which would appear impossible,
veight, were it not well ascertained that the spasm which often
e moment of death may be retained for a considerable period.
gentleman was found dead in a chair in his bed-room; he had
f some hours before his body was discovered. A discharged
till held firmly in his right hand, and there was also a loaded
ed in his left. Instances are frequently occurring, in which
nives require to be removed even with some force, from the
ose who have destroyed themselves. In such cases, the con-
ver, impressed by the last fatal act of volition, persists until
gidity has supervened.

e observes, that, although in many cases the arms, at the
death, fall in a collapsed state by the sides of the body, there
as others in which their situation may throw some light on the
death. In one case of suicide by a pistol-shot, he found on
e apartment, the right arm and hand of the deceased turned
e side of the head, against which the pistol had been fired. A
ad died from the effects of carbonic acid gas given out by a lime-
und with the left arm raised and supporting his head, the right
n the abdomen; the whole figure being that of a person quietly
ese facts deserve to be borne in mind, for questions relating to
inexpectedly on trials for murder. Although apparently trivial,
n some instances become the turning-points of the guilt or
f a person charged with murder.

ase of *Lord William Russell*, who was murdered by Courvoisier
was observed that one hand of the deceased firmly grasped the
e bed, as if in a struggle against an assassin. The force here
e muscles during life had persisted after death: it had passed
has been termed, for want of a better designation, 'cadaveric
l in this state the contracted hand had become rigid. This

position of the hand of deceased furnished, among other circumstances, some evidence against the presumption of suicide. In drowning, it is by no means unusual to find, when the dead bodies are taken from water soon after the accident, that pieces of rope, an oar, grass similar to that growing on the banks, or weeds like those growing at the bottom of a canal or river, are firmly grasped in the hands. This is one of the strongest proofs which we have that the individual has gone into the water living. Part of a dress may be thus found grasped in the hand, and serve to identify a person accused of murder.

In general, when the dead bodies of the recently drowned are taken from water, the limbs are found relaxed; but this depends on the time at which they are removed. Convulsions sometimes precede death by asphyxia, but the effects of these on the body are generally lost when the person dies. Rigidity of the muscles takes place after death in water, perhaps more rapidly than in air. If the water is intensely cold, and the person has struggled violently, the last struggles of life may be indicated by the contorted state of the limbs persisting through rigidity. A young man, while skating, fell through the ice of a pond about seven yards deep. This was in Feb., 1847. He was not totally immersed, for he kept his head and shoulders out of the water above the ice, with his arms resting upon it; and as the ice gave way under his weight he sprang to a fresh portion. Before assistance could be rendered, he sank. The body was recovered the next day; it was found at the bottom of the pond, beneath the hole in the ice. The arms of the deceased were stiff, and still retained the position in which he had rested upon the ice: his legs were quite extended, and the muscles on the fore part of the thigh were very much contracted, as if they had been powerfully exerted in keeping him erect while he was hanging on the ice. There was no appearance of his having attempted to breathe after he had gone below the water. His countenance was quite natural, and there was no water or froth in his mouth; the external appearances resembled those which are seen in a body immersed after death from some other cause. There was no internal inspection. Beardsley's opinion was that the water, being about 32° F., the man was in reality killed by cold, or frozen; and there is no doubt that, if this did not operate as the direct cause of death, it materially accelerated it. This case is of interest in reference to the fact of the bodies of persons who have been drowned at the same time by a common accident being frequently found clasped in each other's arms. A contracted state of the muscles at the time of death may pass into perfect rigidity by the effect of cold water; and thus the attitude or the last act of life of the individual, may be preserved.

In the case of *The Queen* v. *George* (Hereford Lent Ass., 1847), a woman was indicted for the murder of her infant child by drowning it. When taken from the water (in the month of Dec.), about nine days after the supposed murder, there were no marks of external violence. The arms and legs were contracted, and the hands closed. On inspection, the vessels of the brain were congested, the lungs were collapsed, and there was farinaceous food in the stomach, partially digested. The state of the windpipe, and the presence or absence of mucous froth, are not referred to. It will be seen from this description, that there was no appearance to indicate death from drowning with any certainty; and the medical witness admitted that but for the discovery of the body in water, a suspicion of death from drowning would not have been entertained. From the state of the brain death might have been caused by convulsions. The defence was, that the child had probably died of convulsions, and that, in order to dispose of the body, the prisoner had stripped it of its clothes, and thrown it into the water after death. The medical evidence failed to show that the child

had died from drowning, and the prisoner was acquitted. The rigid and contracted state of the child's limbs appears to have created a difficulty in the defence. The clothes of the child were neither cut nor torn, and the witness considered, that had the limbs been so contracted as they were when the body was found, these could not have been removed without cutting or tearing. The medical question therefore was, whether the state of the child's limbs did not prove that it had been put into the water while living. As the usual appearances of death from asphyxia were entirely wanting, it is proper to consider whether there may not be some explanation of the facts consistently with death before immersion. The admission made by the witness in cross-examination, appears to supply all that is necessary for this explanation. If the child had died of convulsions, if the clothes were then removed, and the body thrown in immediately, the sudden effect of the cold water might have occasioned the contraction of the limbs; or the child may not have been really, but only apparently dead, when the mother stripped it and placed it in the water. If some time had elapsed before immersion, so that the body had become cold, then the limbs would have been found either relaxed, or stiffened in a straight position. The persistence of this contracted state for so many days may be explained by the immersion having taken place at the coldest season of the year.

The dead body may be found with some article grasped in the hand. (See case, 'Ann. d'Hyg.,' 1829, 1, 464.) It may be the hair of the deceased or the prisoner's hair torn off in the struggle for life; and on this point an important question of identity may be easily raised. (*Reg.* v. *Ellison*, Bodmin Sum. Ass., 1845.) In a case which was tried some years since, a man was charged with the murder of a woman with whom he cohabited. The body of the deceased was found lying dead in the house, with such injuries about the head, as to render it certain that she must have been murdered. In her right hand was found a considerable quantity of brown hair, and in the other hand some grey hair, grasped evidently in the struggle for life. On the morning following the murder, the prisoner went to a hairdresser's in the town, and desired to have his hair and whiskers cut. This man observed that the hair and whiskers had been recently cut, and evidently by some one unaccustomed to hair cutting. There was a difference between the hair of the whiskers and that of the head, the former having turned grey. The hairdresser was of opinion, that the hair found in the hands of the deceased, was of the same colour and kind as the hair of the prisoner. This, with other corroborating circumstances, led to his conviction. In a case which occurred to Marc, a woman was found assassinated in her house, and when the body was discovered, a small snuff-box was still held firmly in one hand. This proved that the murder must have taken place very suddenly, and without any resistance on the part of the deceased. ('Ann. d'Hyg.,' 1829, 1, 465.) Great light is often thrown upon a question of suicide or murder by attention being paid to these minute points connected with a dead body. It has been elsewhere stated (p. 65) that a weapon may be found grasped in the hand of a person who has destroyed himself; and when a weapon is thus found, the fact is strongly confirmatory of suicide. It does not seem possible that a murderer could simulate this condition after destroying the deceased. The hand of a dead person, while still warm and pliant, could not be made to grasp a weapon in the same way as that hand which had firmly held it by powerful muscular contraction at the last moment of life. At any rate, the attempt to produce this appearance has signally failed. At the trial of a man named *Saville*, in 1844, it came out in evidence, that the deceased, his wife, was found dead, with her throat severely cut, and there was a razor,

not grasped, but lying loosely in her hand. There was no blood upon the hand which held the razor, and this, together with the fact of its being loose, rendered it probable that the weapon had been placed there by some person, after the throat of the deceased had been cut.

The case of the woman *Gardner* (*Reg.* v. *Gardner*, C. C. C., Oct., 1862) was marked by a similar incident. The woman had died from several wounds in the throat which could not have been self-inflicted, and a common table-knife was found loosely lying in her right hand, with the back of the blade towards the palm of the hand, and the weapon in the direction of the length of the body. According to the evidence of the medical witnesses, the principal wound in the throat was of such a nature that it could not have been inflicted with the right hand. This at once proved that there had been murderous interference. On these occasions it may be suggested that a weapon, although grasped by an alleged suicide to inflict the death-wound, may either drop from the hand or be found loosely in it, as a result of the relaxation of the muscles in death. This must be admitted; hence the mere fact of a weapon being found loose, should not be taken as evidence of murder, unless other circumstances—such as the nature of the wound, the freedom of the hand from blood, the position of the body, &c.—concur to prove that the act was not one of suicide. Küssmaul asserts that the fact of a weapon, whether a razor, knife, or pistol, being found firmly grasped, should not be taken as any proof of suicide; because if this position be given to the fingers when in the stage of relaxation, they will in that of rigidity, embrace the article so closely, that it will be difficult to disengage it. He gives this as a mere surmise, and not as being based on any experiment. That it should present itself as a serious objection in practice, we must infer that assassins are fully aware of the forensic necessity of causing the hand of the victim to grasp the weapon with the greatest firmness, and that they can remain by the corpse thus holding the hand clenched, until the fingers have stiffened with sufficient firmness to retain it. Assuming this improbable state of things, other circumstances, as in Gardner's case, may show that the weapon after all has been placed in the wrong hand, or that the blood-marks on it and on the hand, have no correspondence. The difficulty of thus endeavouring to imitate an act of suicide, when the facts are properly observed and compared will be apparent from the following case (*Reg.* v. *Heywood*, Liverpool Ass., 1855). The deceased in this case, a female, was found dead in bed with her throat cut. The medical evidence showed that the wound was six inches from right to left, extending across the throat to a point under the left ear: the upper portion of the windpipe was severed, and the jugular vein, as well as the muscular branches of the carotid artery, were divided. The medical witnesses considered that the wound in the throat had not been inflicted by herself. It was such a wound as a *left*-handed person would have inflicted, and the hand inflicting it, as well as the weapon, could not have escaped being marked with blood. It appears that when the body was found, there was a razor in the *right* hand, not tightly held. The arms were folded across the chest, the right hand resting on the left, the back of the razor being towards the person of deceased. There was *no blood on the hands*, arms, or chest, and only one small spot on the razor. There was blood on the underside of a pillow, and a corresponding stain on the bolster, showing that this must have been turned over, and the head placed on the clean side after the infliction of the wound. All the circumstances concurred in showing, that an attempt had been made to simulate an act of suicide, while the facts were only consistent with homicide. The prisoner was connected with the act by the moral as well as circumstantial evidence, and he was convicted and executed.

Neither during nor after the cessation of rigidity could this spasmodic condition of the muscles of the hand be simulated; in no case is it possible to give an appearance of grasping, similar to that which is occasionally found after death as a result of cadaveric spasm and rigidity.

The discovery of a weapon thus held in a dead hand has been assumed to furnish evidence of murder. In 1835, a medical man at Bordeaux was called to examine the body of a gentleman supposed to have been murdered. Upon entering the apartment, which had been left undisturbed, he found the deceased perfectly dead, sitting in an arm-chair by the side of the bed, the left elbow resting upon a bolster. His right hand, which held a recently-discharged pistol, rested upon the middle of the right thigh, the greater part of the barrel projecting over the inner surface of the thigh, so that the slightest motion of the part would apparently have been sufficient to cause it to fall on the floor. The bullet, which could not be found, had fractured and traversed the left parietal bone, after having torn off nearly the whole of the face. The clothes of the deceased were saturated with blood; a large quantity had also drained through the seat of the chair, and had formed a considerable clot on the floor. The temperature of the body indicated that the deceased had not been dead above two hours; and it was at about that time that the discharge of a pistol had been heard by some of the neighbours. The other facts ascertained relative to the case were that the deceased, who was about sixty years of age, had never shown any disposition to destroy himself; and there was no moral circumstance which seemed likely to have acted as an exciting cause, except perhaps the loss of a law-suit by a favourite sister, which, however, was deemed scarcely sufficient to explain the event. He had a son, who lived in the house with him, and slept in the same room. They were both dissipated in their habits. On the morning of the event, after breakfast, the son (according to his own statement) threw himself on his bed, which was by the side of that of his father; he fell asleep, and knew nothing of the circumstance until he was aroused out of his sleep by the discharge of a pistol. The son was accused of having destroyed his father, and of having placed the pistol in the hand of his parent after death, in order to lead to the supposition of suicide. The circumstance seemed so much the more probable to the police officers and those who were present at the finding of the body, since, when the hand with the pistol was carefully carried to the position in which the weapon must have been held by the deceased in order to have committed the fatal act himself, and the hand was afterwards allowed to fall by its own weight, the pistol each time fell from the hand to the floor. Besides, on the moral side of the question, it was shown that the son would be benefited by the death of the father.

The medical examiner having duly reflected on the position in which the deceased was discovered, satisfactorily accounted for the hand retaining the pistol after death by the contractile state of the muscles, from the effect of volition at the moment of death being sufficiently strong to prevent the weapon from falling. The experiments performed with the hand and pistol subsequently were very properly stated to be unsatisfactory; since, when this contracted state of the muscles has been once destroyed by much handling, it could not be restored. The specious argument thus founded upon a popular error was, by the tact of the medical witness, satisfactorily refuted. The reporter of the case candidly confesses that, owing to his having been misled by popular prejudice, he was at first almost inclined to believe that the son had been guilty of parricide; and probably if a hasty and careless examination had been made, or if the body had been officiously interfered with, previously to its being seen by a medical man, the son might have been committed for trial on a charge

of murder. So soon as this apparently physical proof of his guilt had been explained away, it was then seen that all the other circumstances rebutted the presumption of homicide. The discovery of a weapon so held, may be considered as one of the best possible proofs of suicide.

The postures in which the bodies of persons found dead from any cause are discovered may, in numerous cases, be brought forward to support a charge of murder, or, at least, of criminal interference; but great care is always required in the application of medical principles to the elucidation of these cases, as well as a good general acquaintance with the various phenomena immediately preceding and following death.

As the body becomes rigid in the position in which it happens to be on cooling, and assumes exactly the attitude of the person at the time of death, careful observation may, in some instances, show whether, in a case of violent death, it was or was not interfered with *before* rigidity took place. A question of this kind arose in the following case. The deceased was found lying dead in the room where the murder had been perpetrated; there were marks of blood in various places, and the body had evidently been removed from the spot where it had fallen: it had been laid out. The clothes had been tucked round it, and a piece of black cloth had been placed over the face. A question arose as to whether the body had been thus removed before or after rigidity occurred? As it was found evenly laid out, the probability was, that it had been removed while the limbs were pliant; and they had then become rigid in this position. If a body be removed during the state of rigidity, it may be in some instances indicated by the position of the still rigid limbs not being adapted to the surface on which the body is found lying. It has been already stated that the first effect of death, in the absence of cadaveric spasm, is relaxation of the muscles; the body then disposes itself according to the surface on which it happens to be lying; the arms or legs may be more or less fixed or contorted, and become rigid in the position which they assumed by gravitation at the time of death. The lower jaw, if left to itself, drops and becomes rigid in this position. When a body is found rigid, with the members evenly extended, and the jaws closed, this is, *cæteris paribus* strongly indicative of interference while there was warmth and pliancy in the limbs. When, on the other hand, the body is found rigid and doubled up, with the limbs more or less twisted lying on an even surface like a bed, the probability is, according to circumstances, that the body has been moved from the spot in which the person had died, and in which rigidity had supervened. In suicidal hanging, the body, and especially the extremities, are now and then found twisted in a singular manner around articles of furniture. In such cases, the general muscular convulsion, at the moment of death, will physiologically explain, what to uninformed persons may appear physically incompatible with the deceased having destroyed himself.

The following case will serve as an illustration of the occasional importance of these inquiries. In June, 1855, *Robert Reid* was tried before the High Court of Justiciary, at Edinburgh, for the murder of his wife. Among the medical circumstances which gave rise to conflicting opinions was one which referred to the posture in which the body of the deceased was found, at half-past two o'clock, on the day of the supposed murder. It was thus described by the witnesses. 'She (deceased) was sitting on the floor by the side of the bed, nearly naked, with a portion of the bed-clothes wrapt around the lower part of her body; the head erect, but inclined a little backwards and to one side, the face being towards the bed. The left arm hung down by her side, with the back of the hand on the

ound, the right arm resting by the elbow on the bed, and maintained in e upright position without any further support, as if she had been in the t of putting it to her face. The legs were crossed under the trunk, the t being less protruded than the right.'

This extraordinary posture was presumed by all who saw it and by the dical witnesses for the prosecution, to be such that the deceased could have assumed it herself in the act of dying; and this was rendered still probable when it was considered that the cervical vertebræ were fracd, and one of them was displaced, so that she had probably died a lent and very sudden death. The attitude appeared to be also quite concilable with the supposition of death from accident or suicide. The f question seems to have been, whether, admitting that the prisoner actually placed his wife in this posture, the maintenance of it was to scribed to a convulsive spasm, simultaneously occurring with death, or he supervention of ordinary cadaveric rigidity. If the posture were itted to have been due to cadaveric rigidity naturally supervening, then inference would be that the deceased had been dead, at least some rs. The prisoner was proved to have been at home from nine until -past nine: the deceased's body was discovered at two, and as the oner had not been at the house between half-past nine and two, so it owed that, supposing him to have been guilty, he must have committed murder during the half-hour that he was at home. Hence, cadaveric dity must have come on in four hours and a half after death. On the er hand, it was urged, that the attitude of the body, and the singular pendicular position of the right arm, were due to a spasmodic contrac- of the muscles in a fit, at the moment of death, persisting under the m of cadaveric spasm. The non-medical witnesses stated that the body deceased when found was perfectly flexible, and the arms and legs so nt, that they could be easily stretched down; indeed, the whole body s so yielding as to admit of its being directly laid out at length on the r. The body was partially warm when first found, but, as it has been ady observed, this is quite compatible with the occurrence of rigidity. rtainly, however, where a body is warm and the members are easily ved from their position, the presumption is rather in favour of the fixed ture being due to muscular spasm than to cadaveric rigidity.

The witnesses for the prosecution considered that the posture of the deed was owing to simple rigidity. Fletcher attempted to explain the cts by supposing that the deceased had probably fallen in a fit while tting out of bed, during the absence of the prisoner; admitting that the isoner might on his entrance, at about nine o'clock, have attempted to se the body, and thus have given the erect position to the trunk, while e perpendicular position of the arm was entirely due to spasm. It was ged that the woman had been previously subject to slight paralysis d convulsive fits, and that the occurrence of a fit, under the circumnces, was not unlikely. The position was not such as we might suppose body to assume when a person has died under a cataleptic seizure. On e other side, it was considered to be improbable that the prisoner could ve placed the deceased in the attitude in which she was discovered, mitting her to have died in any other posture—since at the time he did , the body must have been either rigid or not. If it were rigid, he could t easily have bent the members from the position which they had already sumed; and if it were not rigid, he must have used artificial means to ep the members and trunk in the extraordinary position in which they re found: for it was not likely that he would have purposely held her ad and arm in such a singular attitude, until her body had become fixed. deed, in order to accomplish this, he must have waited until it had become

cold, whereas it is stated to have been found with some warmth and pliancy about it. Besides, it would be impossible to assign any reason for so doing, since he would be ignorant of the medical difficulty connected with it.

The prisoner was discharged on a verdict of not proven, because it was not satisfactorily made out that he had really caused his wife's death. The state in which the deceased was found, created a presumption that she had died from natural causes not long before the discovery of her body; therefore, at some time between half past nine and two, and while the prisoner was absent from the house. The account of this case, as given by Fletcher, was most favourable for the prisoner. He suggested many ingenious explanations for circumstances which were certainly very strong against the prisoner. The verdict of 'not proven' sufficiently attests the opinion of the jury; and had the medical evidence respecting the cause of death from violence been a little clearer, there is hardly a doubt that the prisoner would have been convicted.

Whether this was a case of death from natural causes, or, as alleged, from an injury to the spinal marrow, we must regard the attitude in which the body was discovered as very unusual. There were difficulties in the way of an explanation, whether we suppose the prisoner to have interfered or not with the position of his wife's body. Had a proper examination been made by medical men when it was first discovered by the neighbours, some of these difficulties would not probably have existed. With a fracture of the dentiform process, and a dislocation of the first and second vertebræ, it is not likely, unless the body had been supported mechanically by the clothes which it is said presented the appearance of having been dragged off the bed with it, that a person so injured would die in the attitude in which the deceased was discovered, or that she could have had the power to assume it spontaneously after such a severe injury to the spinal column. The probability is, that the body would have been found lying on the floor.

A question was raised upon this trial respecting the duration of muscular spasm after death; and this may become a point upon which a medical witness may be required to express an opinion. There is but little doubt, from numerous collateral facts, that it may remain for a considerable time after death and even pass into cadaveric rigidity, *i.e.* the posture assumed by a limb from spasm at the moment of death, may be retained as the posture of cadaveric rigidity, supposing the body not to have been disturbed. An instance is reported, in which a drowned body, after having remained in water from twelve to fourteen hours, was drawn up with the hands still grasping firmly the cable of a vessel, which the deceased had caught hold of in the act of drowning. The bodies of persons drowned in a common accident, are found not unfrequently after twenty-four hours firmly locked together by their arms, when taken out of water, cold and rigid. In persons who die under violent spasmodic contraction of the muscles, as in cholera and tetanus, whether from natural causes or the effects of strychnine, the state of spasm is sometimes preserved after death and passes into rigidity.

The attitude in which a dead body is found rigid, may easily give rise to an erroneous suspicion of murder. The following case has been reported by Marc:—The deceased, *Courbon*, was found dead in a ditch; his head was bent upon his chest, and the lower part of the trunk was so curved, that the whole weight was borne by the neck. The body was very rigid, but there were some slight traces of warmth when it was found. On inspection there were all the appearances of apoplexy, and the deceased was well known to have been of drunken habits. Notwithstanding these facts, two

ons were convicted of murder upon some loose evidence—principally the ground that the unnatural position in which the deceased's body found could only be explained on the supposition of murderous interence. The accused were condemned to the galleys for life; but after years' punishment, a proper medical investigation of the facts was the first time instituted, and they were discharged. The evidence lished that the deceased had died of apoplexy; and that the body had med the peculiar position in which it was discovered owing to the sed having fallen into the ditch in a state of drunkenness, by which as rendered helpless and incapable of extricating himself. ('Ann. g.,' 1832, 1, 569.) While rigidity may sometimes indicate murder, me form of violent death, by fixing the body in a position which it l not naturally have assumed, and which cannot be easily altered during igid state, we must beware that we do not give an undue importance is sign of death as a proof of violent usage. This caution is especially red in the cases of drunkards, for the body of a person who dies in a drunkenness may be found contorted and disposed in a way which t be apparently incompatible with either accident or suicide.

Muscular Irritability.—In order to determine the reality of death, s been proposed to test the irritability of the muscles by the applica- of an electric current. If a voluntary muscle, laid bare for this pur- does not contract under the application of this stimulus, the inference it the person is dead; but if it should contract under these circum- es, it furnishes no proof that the person is living, in the ordinary ing of the word. It has been elsewhere stated that the cardiac and involuntary muscles, which are readily affected by a mechanical ulus soon after death, lose their irritability or power of contraction, under a galvanic current, much sooner than the voluntary muscles. result either of disease or exhaustion, of the action of certain poisons, the effect of lightning, the irritability of the whole muscular system be entirely destroyed at the time of death; and in these cases no ulus excites muscular contraction. Under these circumstances rigidity putrefaction follow so rapidly, that the use of an electric current for ional evidence would be superfluous. On the other hand, in certain , as in the body of a decapitated man whose case is recorded by en, the irritability of the muscles may remain for twenty-six hours death. In short, it is now known, that until cadaveric rigidity mences in the body, muscular irritability is retained. When this com- ces it begins to disappear. Contractility of the muscles under the ent would, therefore, prove either that the person was living, or that body was in the first stage of death. All the muscles do not retain irritability under the electric stimulus for the same length of time, nor hey all lose at once their susceptibility of contraction. The voluntary cles retain their irritability on the average about three hours. One ee of stimulus may excite them, while another may not. Living muscle an amphichroitic or faintly alkaline reaction, while dead muscle is acid. Dowler has shown by numerous experiments on the recently dead y, that post-mortem contractility may be excited by slight blows on the cles given with the hand or any weapon, and thus electricity may be ensed with. When the arm of a recently dead person was extended right angle with the trunk, a blow over the biceps muscle, not cient to injure a living person, caused the forearm to bend, carrying hand to the chest repeatedly. In fact, before rigidity set in, the arm his corpse, by the mere effect of slight blows, performed supination, ation, and flexion perfectly. This effect of slight mechanical violence

is most distinctly observed within *half an hour*, but Dowler has seen it manifested as late as six or seven hours after death. It disappears when rigidity sets in. ('Exper. Researches on Post-mortem Contractility,' by Bennet Dowler, New York, 1846, p. 601.)

It is a curious fact that the blood has no appreciable influence upon the post-mortem contractility of the muscles, for when the limb was severed from the trunk, and drained of its blood, its action was not thereby diminished. ('Amer. Jour. Med. Sc.,' Oct. 1846, p. 440.) Contractions as the result of slight blows were observed in forty-three cases. The contractions were in many cases so forcible, as to cause a heavy weight to be lifted by the limb in which they occurred. The integrity of the corpse was not necessary; they were excited some hours after the dissection of the body, and after the limbs were severed from the trunk. Dowler considers that these muscular contractions have occurred spontaneously after the death of the body. Spontaneous movements in a corpse have been seen after death from cholera, and the same may take place after death from yellow fever and other diseases. Dowler suggests that the changes in the position of the limbs of bodies sometimes observed after death, which have given rise to tales of premature interment, may be explained by the occurrence of spontaneous post-mortem contractions, depending on the long retention of muscular irritability in a high degree. Haller endeavoured to lay down the order of cessation of this irritability in different muscles after death. Many physiologists since his time have also occupied themselves with this question. Haller found that it varied according to the kind of stimulus employed: thus the irritability of the heart was excited by *mechanical* agents for a longer period than any other part of the muscular system;—a circumstance which was supposed to account for the reports of persons having been dissected alive, to be found recorded in some works on Medical Jurisprudence, an accidental puncture by the knife or forceps having given rise to contractions of this organ. But to admit this explanation, we must suppose that the body was inspected within one or two hours after death.

Nysten concluded from his observations that the successive disappearance of muscular irritability in the bodies of decapitated persons took place in the following order:—1. The left ventricle of the heart. 2. The stomach and intestines. 3. The urinary bladder. 4. The right ventricle. 5. The gullet. 6. The iris; and 7. The voluntary muscles of the body.

The power of making the muscles contract under the electric current has been found to vary according to the nature of the disease of which the individual died. When it was such as to exhaust the strength, the time was very short. From experiments performed at La Charité, it appeared that in death from peritonitis, irritability ceased in about three hours; in phthisis, scirrhus, and cancer, in from three to six hours; in death from profuse hæmorrhage, or from mortal lesions of the heart, in about nine hours; in apoplexy with paralysis, in twelve hours; and in low fevers and pneumonia, the irritability disappeared in from ten to fifteen hours. In these experiments, the muscles of the trunk and limbs alone were examined; since it is upon these, should the necessity ever occur, that a practitioner must operate. Although the periods are thus laid down in figures, yet the results must be regarded only in the light of approximations to the truth; but the period of three hours may be accepted as the usual limit.

We have now to apply these different data connected with death and the changes in the dead body, to the solution of some medico-legal questions—such as the reality of death, and the period at which death has taken place.

THE REALITY OF DEATH.—This question, of course, can only be raised in the period preceding the occurrence of putrefaction; therefore our observations on this point may be restricted within a very narrow compass. The question, indeed, might be passed over altogether as unimportant, were it not that many men ranking high in the profession have devoted much attention to the subject; and have thought themselves justified, from their observations, in declaring that premature interment was not unfrequently the means of consigning living individuals to the tomb. There is something terrible in admitting the bare possibility of such an event; and therefore we ought not to reject the supposition, without examining the numerous cases which have been brought forward in support of it. In the work of Fontenelle *forty-six* cases are recorded, either of the premature interment of the living, or of apparent being mistaken for real death. From a careful examination of all these cases, it appears that the greater number of them are derived from such sources as to render them perfectly inadmissible as evidence of what Fontenelle so strenuously endeavoured to prove. He has collected these cases from every source, whether scientific or not, from the time of Plutarch downwards. This very circumstance would make reasonable men distrust those instances of supposed death which are undoubtedly authentic, did not the facts appear explicable on the most common physiological principles.

The fears which works like that of Fontenelle are likely to excite, respecting premature interment, have been kept up by other French writers. Carré maintained that there was *no certain sign* of death but putrefaction; and that no body should undergo interment until this process had become plainly manifested. According to him, a *presumption* of death may be deduced from a great number of signs; a *probability*, from the combination of some of the most important, such as the collapse of the eyes, and especially cadaveric rigidity; but *absolute certainty* can be obtained only by the occurrence of the putrefactive process. Like other theorists, Carré attacked each sign of death individually, but he ignored the fact, that a judgment in proper hands was always formed from a combination of many signs or conditions; and medical men are not responsible for the results, when the decision of an important question of this kind is entrusted to ignorant and uneducated persons. A petition was, on one occasion, presented to the French Chamber of Deputies, in which the petitioner declared that he had known six interments of living persons to have taken place within a period of eight months. Resting on similar authority, Carré asserted that since 1833 there have been forty-six cases of premature burial. Among these, twenty-one persons returned to life at the time they were about to be deposited in the earth, nine recovered owing to the affectionate attentions of their relatives, four from the accidental falling of the coffins, two from a feeling of suffocation in their coffins, three from the punctures of pins in fastening the shrouds, and seven from unusual delay in the funerals; and, it is added, after this marvellous recital, that the decease of all these individuals was officially attested. A statistical calculation was then made by him from the deaths which occur annually in Paris, of the average number of persons who were likely to be buried alive.

Statements of this kind can only be received with incredulity, since no particulars by which their accuracy can be tested are given. The cases of alleged premature interment that have yet been adduced, will not bear close examination, as they are nothing more than the idle tales of ignorant and superstitious persons, with the usual amount of exaggeration. In this country we have no official attestation of death by specially appointed persons; but if the account given by Carré be true, we

have no reason to regret the absence of this system; since it is doubt whether, under the practice of the ancient searchers of London in t worst days of the plague, when bodies were indiscriminately thrown i large pits soon after death, greater negligence could have been sho than that which is here alleged to have occurred on the part of the Fre officials in modern times.

About, in his popular novel 'A New Lease of Life,' has given an am ing description of the popular ideas as to the possibilities of resuscitat of a presumed corpse. Cases have undoubtedly presented themselves which persons labouring under concussion, syncope, catalepsy, hysteria, lifelessness from exhaustion, have been pronounced dead by bystande merely because there happened to be inanimation, coldness of the surfa and no outward signs of respiration or circulation. If the decision of question of life or death was always left to such persons, and interme were to follow in a few hours upon their dictation, there is no do living bodies would be exposed to the risk of premature burial. I this can rarely happen in any civilized country of Europe, and t only as the result of gross and culpable neglect. In France the l ordains that every death must be verified by a medical officer; and t no interment shall take place until after the lapse of twenty-four ho from the time of death. This rule, it is said, applies only to Paris s some of the chief cities of France. No post-mortem examination should made, and no interment take place, until after a certificate of death l been issued by the proper medical officer. A similar law prevails in Nap and in Portugal: but Fontenelle states that in the latter country, as w as in Spain, bodies are sometimes interred within *five* or *six* hours af death. In the Protestant parts of Germany and Switzerland, the dead rarely buried until after the lapse of three days, a period being fixed law, before which interment cannot take place. In this country there no legal provisions relative to the period of interment; but, except un severe and continuous epidemics, the dead are rarely buried until after lapse of from one to five days. It would, no doubt, be a good regulat if every dead body were seen and examined by a medical man twenty-f hours after apparent death, and the fact of death were officially attested him according to circumstances. The defect of the continental system that a medical opinion may be given at any time after the supposed dece and there may be occasionally great negligence in the performance of t duty. Still it is impossible to admit that, except under the most culpa neglect, persons can incur the risk of being buried alive, when the bo has been kept at least twenty-four hours from the time of the suppo decease. It is stated on the authority of Salignac-Fénelon, that in a per of twenty years, during which mortuary houses have been established Germany, no body has ever been restored to life, although during t time no fewer than 46,000 bodies have been deposited therein. ('A d'Hyg.,' 1870, 2, 317.)

This statement is fully confirmed by investigations in France. (' 'Ann. d'Hyg.,' 1867, 1, 293.) The results depend on the care taken the attestation of death by the appointed medical officers. The sa care given to every case of alleged death, would of course be atten with similar results, whether the dead body is placed in a mortuary not. When a death has not been properly attested by a medical ma mistake may be made. A case of this kind, on which Devergie made an elaborate report ('Ann. d'Hyg.,' 1870, 2, 310), occurred n Morlaix, in France. A woman died, as it was supposed, from chol She was seen while ill by a medical man, but not after the suppo death. She was placed in a coffin in an hour, and buried in sixt

ours. During the interment a noise was heard in the coffin. Time was ost in sending for a medical man, and the coffin was not opened until he rrived. The shroud was found twisted and folded about the neck and eet, as if struggles had been made, and there was a quantity of liquid on it, which had issued from the mouth and nostrils during efforts made to breathe. The body was warm and not rigid; there was a general relaxation of the muscles; the hand was translucent to light, and the pulsations of the heart had not completely ceased. Efforts were made to resuscitate the person, but without success. These conditions are consistent with death from cholera, with the exception of the last. If the medical officer was correct in his observation, this person had really been buried alive.

This and other cases were made the subject of a petition to the French Senate in 1869, and subsequently remitted to Devergie for a report. He convincingly proved that the catastrophe was owing to the non-observance of the law. There had been no medical attestation of death. The relatives were over-anxious to bury the supposed corpse, probably from fear of contagion; and not having any place for the deposit of the body, they were in haste to remove it from the house.

The remedy for an evil of this kind is not to discover some certain sign of death to guide ignorant persons, for it would be always dangerous to give them a power of judging, but to enforce strictly the rule that no body shall be buried except on a medical certificate of death and its cause. Mortuaries are useful in poor districts for the reception of bodies after verification of death, until interment can take place; but not on the ground that there are no means of determining the reality of death before putrefaction has taken place.

Non-professional persons may readily mistake a state of insensibility for death, and in acting upon this belief, may lead to the death of a living person. Guthrie mentions the case of a man labouring under concussion, while on board a vessel. He was supposed by his brother and the captain to be dead or dying, and without being able to make any movement to indicate that he was alive and understood their conversation, he heard them discussing the question whether his body should be buried at sea or carried on to Rotterdam. Fortunately the latter alternative was adopted. Druitt reports two cases of a somewhat similar kind. A gentleman who was most severely affected with cholera in India, told him that when the disease had gained the complete mastery over him, he lay utterly deprived of speech and motion, whilst he could distinctly hear his attendants, who conceived him to be insensible, speculate on the time of his decease, which they judged to be very near at hand. He then, besides being speechless, became blind and deaf; but although thus cut off from all communication with the external world, and, in common language, insensible, he still retained his consciousness and self-possession, and reflected on his apparently inevitable death. Afterwards he lost all thought and consciousness, and remained thus on the very threshold of death for some hours, and then recovered. The other case was that of a boy, æt. 6. He had the small-pox, was pronounced dead, and his body was put into a coffin. After some hours, he became conscious, heard the voice of his mother, who sat by the coffin, and he essayed to speak; but, as he afterwards said, he was unable to make any movement or sound to show that he was alive. At last, however, his mother's attention was drawn to some apparent change in the features: she watched him narrowly, perceived the lips to quiver, and soon he was able faintly to articulate a wish for wine ('Ed. Month. Jour.,' Ap., 1844, p. 355). These two cases have led the reporter to believe in the possibility of the hasty interment of the living as dead, while the unfortunate person is conscious of his condition, but unable to communicate

his feelings to others. Mistakes of this kind are not likely to be made by medical men. In order to avoid the possibility of such occurrences, no interment should be allowed to take place until after the lapse of twenty-four hours, at the least, from the time of the supposed death; and not even then, except upon the certificate of a medical practitioner who has examined the body. At present the *cause* of death is certified, and a body cannot be buried except upon the certificate of the registrar; but the medical attendant has it in his power to give the certificate without seeing or examining the body of the deceased at that period after death which is necessary for the clear development of the signs of dissolution. Hence, unless, as it commonly happens, the interment be delayed by the relatives for twenty-four hours at the least, there might be a risk of prematurely consigning a living person to the grave.

During the prevalence of epidemic disease, as in cholera times, a provision was made, that interments should not be delayed beyond twenty-four hours, when death had taken place from the disease. There is no doubt that many bodies were interred during the raging of the epidemic within eight or ten hours after apparent death. One instance was communicated to the author where the body was wrapped in a pitched cloth and buried within *six hours* after the signs of life had ceased. This is assuredly a most condemnable practice, especially in cases in which the deceased has not been attended by a medical practitioner. Under no circumstances should a body be buried within a shorter period than twenty-four hours, when death has taken place from chronic disease, or without any obvious and satisfactory cause. No mischief is likely to result to the living by the adoption of such a practice; while it would effectually guard against premature interment among the lower classes of society. In assigning twenty-four hours, this is to be taken as an average period; there are cases in which the most striking phenomena of death, such as coldness and rigidity, may manifest themselves within a much shorter time than this, and in such cases a medical opinion may be given without any difficulty. No coroner's inquest should be held upon a body until twenty-four hours after death. In one instance an inquest was held on a body half an hour only after the apparent cessation of life.

If we allow a proper interval to elapse after the supposed death, there can be no difficulty in solving the question, whether a person is really dead even before any of those changes, which arise from putrefaction, have manifested themselves. The circumstances on which we may rely as furnishing conclusive evidence of death, are the following:—1. The absence of circulation and respiration for at least *an hour*, the stethoscope being employed if necessary; 2. The gradual cooling of the body, the trunk remaining warm while the members are cold; and 3. As the body cools, the gradual supervention of a rigid state of the muscles, successively attacking the limbs and trunk, and ultimately spreading through the whole muscular system.

When these conditions are observed, the proof of death is conclusive; it is unnecessary to wait for any sign of putrefaction. These changes are as certainly the forerunners of putrefaction as the process of putrefaction is itself the forerunner of the entire destruction of the body. It may be safely said that there has not been a single instance of resuscitation after rigidity had once commenced in a body. During the raging of epidemics, if additional evidence be required for early burial, it might be obtained by exposing a superficial muscle to the electric stimulus. If the fibres do not contract, death is certain. If they do, this is no proof that the person can be restored to active life; but further time may be allowed before the body is committed to the grave.

ollowing case death was only apparent, but the fact created no
In Dec., 1830, Ancelon was called to see a woman, æt. 34, and
ed on his arrival that she had been dead for more than half-
)n examination, no signs of respiration could be detected, the
not be felt, the skin was livid, the belly soft and flaccid, and
ad legs were cold. It appeared that the woman had suffered
ie hæmorrhage up to the time of her supposed death. He
e contents of the uterus, and at this time a bubble of air was
escape from the mouth of the woman. On clearing the uterus,
e were gradually manifested by the woman. The respiration,
; first by air-bubbles, which succeeded one another on the lips,
rned; the circulation was also re-established. She did not
intelligence for three days. ('Month. Jour. Med. Sci.,' Oct.,
'Amer. Jour. Med. Sci.,' Jan., 1855, p. 268.) This woman
ad, but in a prolonged syncope from excessive hæmorrhage.
n was not resorted to, or the sounds of the heart might probably
ieard, although the pulse could not be felt.

w remarkable cases of an authentic character the process of
a has been considerably retarded, and coldness and rigidity have
ited themselves in the ordinary course. Such cases of apparent
d necessarily give rise to doubt; the phenomena observed were
wing to the presence of some traces of molecular life persisting
after active life had entirely ceased. One of the most singular
ies was reported in Hufeland's 'Journal of Practical Medicine.'
ig man, who was a patient in the hospital of Paderborn in
ed, as it was supposed, under symptoms of phthisis, but not of
ked character. He had recently recovered from an attack of
e cause of death appears to have been obscure, and after, as it
ed, he had expired, his eyes were suddenly opened, and the
thought they detected for some minutes an irregular beating of
Some wounds and cauterizations were made on the body without
im, and on the third and fourth days these, it is said, had passed
: of suppuration. On the fifth day his right hand turned back and
m the fifth to the ninth day a clammy perspiration was perceived
kin, and some vesicles containing serum were formed on the skin
c. During this time there was no appearance of respiration or
, and the limbs, although cold, were pliant and flexible. The
as furrowed with vertical wrinkles, and the countenance had an
not usually observed in a dead body. On the eighteenth day
esented their usual red colour, and although the body was lying
; time in a warm room, there was no disagreeable odour and no
ecchymosis. On the twentieth day, the signs of putrefaction
ie apparent, leaving then no doubt of the reality of death. As
this case was published in a medical journal of repute, although
are imperfectly given, it may possibly be considered authentic.
he conclusion to which it leads has already been anticipated.
ary signs of death, *i.e.* slow cooling and progressive rigidity,
observed. Further, when the body was exposed to conditions
to putrefaction, the changes indicative of this process are stated
e been manifested for a period of twenty days. Such a case was
exceptional, and was thus treated by the hospital officials. The
ieither inspected nor buried, but simply watched until death was
ain by the actual occurrence of putrefaction. Had this patient
the hands of ignorant nurses or attendants instead of profes-
l, it is probable that the body might have been consigned to the
wo or three days. Although, as the event subsequently proved,

this would not have furnished another instance of the premature interment of a living person, yet the proper course in all doubtful cases is to wait until that doubt has been satisfactorily resolved by the appearance of the obvious signs of decomposition.

A case of a somewhat similar nature occurred at Deptford in 1844. A youth died suddenly, and, in consequence of the body showing no signs of decomposition after several days, it was believed by the friends that the deceased was in a trance. The body was seen by several medical men, and they, in spite of some unusual phenomena, came to the conclusion that the youth was really dead. Some days after death the features acquired a natural character, and there was no change indicative of commencing putrefaction. The body retained its general appearance for twenty-eight days; but several medical men who saw it at this period agreed that decomposition had begun. It was not until thirty-five days after death that the friends would allow an inspection to be made, and it was then found that deceased had died from an attack of congestive apoplexy. It was observed at the inspection that, in spite of the long period which had elapsed since death, and the exposure of the body to a warm temperature, putrefaction had made but little progress. In Oct., 1849, a youth died at Bristol, from an attack of malignant cholera, in about fourteen hours. After the lapse of forty-eight hours, it is stated that the warmth of the body was perceptibly retained, and there was no appearance of decomposition. Some days afterwards, however, the process manifested itself as usual.

Death-trance.—The slow access of putrefaction in certain cases is no doubt the basis of the Wallachian superstition, described by Mayo under the name of Vampirism. When dead bodies were disinterred and had apparently undergone but little change, it was believed that they were transformed into vampires, and that they had been nourished and preserved by sucking the blood of the living. As a mere effect of panic, the prevalence of this popular belief led to numerous deaths: those who died were hastily buried: the bodies of suspected persons were disinterred, and if found undecomposed they were either staked or burnt. Mayo, in his 'Letters on the Truths contained in Popular Superstitions,' has shown the absurdity of this superstition.

It may be occasionally difficult to form an opinion of the reality of death in cases of recent drowning or hanging. Coldness and stiffness of the body in the drowned should not prevent the application of means for the restoration of life. One or two hours may elapse before signs of animation appear, and in one instance a drowned person was not restored until the means of resuscitation had been applied for eight hours and a half. There is reason to believe that some persons removed from water in a state of apparent death are consigned to actual death, owing to want of timely application of the means, and a want of perseverance in the treatment. The continued coldness of the body, and the absence of any evidences of success after a few trials, are commonly taken as sure signs that the person is really dead. There appears, however, to be in some cases a lingering vitality about the body. In an attempt to resuscitate a drowned person who had been five minutes below the water, and was speedily treated after removal, it was observed that the face which had been pale became suddenly livid, and underwent a remarkable change of expression. This appearance, however, was only momentary; continued efforts failed to restore life. In this form of asphyxia, as well as in hanging and suffocation, some caution is required in pronouncing that a person is really dead, since it at once discourages the efforts of those who are employing means for resuscitation.

If the body has been for half an hour or longer under water—if it has been found hanging or in a suffocating medium and is cold and rigid—there can be no hope of resuscitation.

In new-born children it is sometimes difficult to say whether life has or has not ceased. Brachet has succeeded in restoring children, in whom the heart's action had been suspended from fifteen to twenty minutes. Respiration and circulation are carried on in such a tranquil manner in an apparently lifeless body, that except by the presence of some degree of warmth, and the absence of rigidity, the child might be pronounced dead. Cases are elsewhere recorded in which children have survived birth for six, and even for twenty-four hours, in this state of passive life. After death no air was found in the lungs. (See INFANTICIDE.)

CHAPTER 5.

INFERENCE OF THE TIME OF DEATH FROM THE STATE OF THE BODY BEFORE PUTREFACTION—PRIORITY OF DEATH—PRESUMPTIONS OF SUICIDE OR MURDER—OF SURVIVORSHIP — STAGES OF CHANGE AFTER DEATH — CADAVERIC LIVIDITY—SUGILLATION—ECCHYMOSIS.

THE changes which take place in a dead body before the commencement of putrefaction, if accurately observed, may sometimes enable a medical witness to form an opinion of the time at which the deceased died. The dead body of a person may be found in a house with marks of murderous violence upon it; the crime may have been so recently perpetrated, that the body still retains the warmth and pliancy observed in the recently dead, or it may be found in a cold and rigid state. A person charged with the murder may be able to prove that he had not been in the house for many hours, or days; or evidence may be adduced to show that he was there at a time which would correspond to the condition of the body when found. In cases of sudden death from violence or suspected poisoning, a medical man, by observing the state of the body, may frequently form a judgment of the time at which death occurred, and, therefore, of the period at which poison was taken by deceased, or violence was inflicted on the body.

In the following case of murder and suicide, the murderer was clearly pointed out by the difference in the condition of the two dead bodies when they were first discovered. In 1836, a man and his wife were found dead in bed, and their bodies were covered with blood from wounds inflicted on both. In the case of the woman there was a deep incision in the throat, besides a wound under the chin, and another on the side of the head. The man's throat was also severely cut; the razor with which the wounds had been inflicted was found on the bed, within a short distance of his right hand, as if, in the last act of life, he had endeavoured to throw the weapon from him, but had failed in the attempt. The body of the woman was cold and rigid, that of the man was warm. The nature and direction of the wounds, and the marks of violence on the woman's person, were such as to render it probable that she had not committed suicide, and the condition of her body showed that she had been dead many hours. On the other hand, the wound in the man's throat was such that he could not have long survived its infliction; and as his body, when found, was warm and pliant, it was a reasonable inference that the wife had died first, and from wounds inflicted by her husband, as no other person had access to the house. If the body of the wife had been found warm, while that of

the husband was cold and rigid, the inference of his having been her murderer (the wound in her throat being of a nature to produce instant or very speedy death) could not have been sustained. In forming a judgment of priority of death in such cases, the sufficiency of the wound to produce instant or rapid death must always be taken into consideration. A person may inflict on another a slight wound, which may prove fatal by hæmorrhage only after some hours, while he may afterwards inflict upon himself a wound which would instantly destroy life. In such a case the body of a murderer would be found cold, while that of the victim, by reason of the death being more recent, would be warm. In the case of a woman who was found dead in her apartment with her throat cut, in 1847, it was ascertained that, when first discovered, the body was so warm as to render it highly probable that the crime must have been committed within an hour. This observation tended to prove the innocence of a person who was suspected of the murder, because it was known that he had been absent from the house for at least five hours.

In the following case, which is a type of many, the theory of suicide was sustained, and that of homicide completely rebutted, by a medical inference from the condition of the body. In 1830 the Prince de Condé, or *Duke of Bourbon*, was found dead in his bedroom, in the Château of St. Leu. When discovered, at eight o'clock in the morning, the deceased was found, partly undressed, hanging by his cravat to one of the window-shutters. The body was cold, and the lower extremities were quite rigid. As in asphyxia from hanging the warmth of the body is usually preserved longer than under common circumstances, *i.e.* from twelve to fifteen hours, before which period rigidity is seldom complete, the medical examiners inferred that the deceased must have died very soon after he had retired to his bedroom on the previous night. As this was proved to have been 10 p.m., it followed that only ten hours had elapsed—a short time for cooling and rigidity to have taken place. It was thus rendered probable that the hanging took place soon after the deceased had entered his bedroom. It was alleged that the duke had been murdered, and his body afterwards suspended by his murderers to create the suspicion of suicide. The condition of the body, among other circumstances, was, however, adverse to this presumption. From 10 till 12 p.m. it was proved that there were numerous attendants moving about near to the duke's apartments. These persons must have heard any unusual noise, which the duke would probably have made in resisting his assailants. But no noise was heard in the apartment at that or any other time, and the presumption of this being an act of homicide was therefore strongly rebutted. Had the body been found warm and pliant, and the joints flexible, the inference would have been that the deceased had died more recently, and therefore at a time when murder might have been perpetrated without attracting the observation of his attendants. As it was, the coldness and rigidity of the body justified the medical opinion expressed, and tended to prove that this was really an act of suicide.

Criminals sometimes unknowingly furnish important evidence in reference to the condition of the dead body. At the Lewes Autumn Assizes, 1860, a schoolmaster named *Hopley* was convicted of flogging a pupil to death. There was reason to believe that the boy had died during the actual beating. The accused stated before the coroner that he went into deceased's bedroom about six o'clock in the morning, and found deceased dead, his body cold, and his arms stiffening. He suggested that he might have died from natural causes. It was proved that the prisoner was heard in the act of beating the deceased up to half-past eleven on the previous night; and as the body was cold when found, and rigidity was

commencing, there was a strong probability that deceased must have been dead at least six or seven hours, and, therefore, at a time when the prisoner was last known to have been with him. The body was well developed, covered with bedclothes, and the temperature not at the time low.

In the case of *Doidge* (Bodmin Aut. Ass., 1862), who was charged with murder, medical evidence derived from the state of the dead body when found tended materially to corroborate the circumstantial evidence against the prisoner. The deceased was last seen alive at 10.30 p.m. He was found, about 9.30 the next morning, dead in his house; he was lying on his face with his clothes on—one arm under the chest, and the other by his side. He had received, on the back of the head, some severe blows, which must have proved speedily fatal. The body when found was quite cold, and the limbs were rigid. It was considered by Mr. Thompson, who saw the body, and by the author, that deceased, under these circumstances, had been dead from eight to ten hours. There was no doubt that this was an act of murder, and that the deceased had been killed while taking off his boots to go to bed. The prisoner was connected with the act by a chain of circumstances. He was seen drinking and conversing on friendly terms with deceased at a beer-shop the evening before. The prisoner left the shop at a quarter-past ten, and deceased at half-past ten. They both lived near to the shop and to each other. A neighbour of deceased's, who was out as late as twelve o'clock, heard at that time the voices of two persons in conversation in the deceased's kitchen. One of them he recognized as that of the deceased, and the other as the voice of the prisoner, with which he was well acquainted. This witness heard the voices for some minutes, returned into his house, and went to bed. He was soon afterwards suddenly awakened by a noise like that of a heavy fall proceeding from the deceased's kitchen, in which the dead body was afterwards found. His evidence was corroborated by that of his wife; and hence it is clear that deceased was alive for some time after twelve o'clock that night. It was further proved that, contrary to his usual practice, the prisoner did not return home to his lodging until one o'clock in the morning; and then, in order to account for his return at so late an hour, he made a statement which was proved to be untrue. The coldness and rigidity of the body, therefore, when discovered at 9.30 a.m., considering the season of the year, and the circumstance that deceased was in his clothes, were facts in themselves quite consistent with the occurrence of death soon after twelve o'clock at night, or about the time when a heavy fall was heard by the neighbour. Other circumstances, which were proved, left no reasonable doubt of the prisoner's guilt, and he was convicted.

Perhaps no case has brought the importance of questions of this nature so prominently before the public as that of *Gardner*, a chimney-sweep, who was tried and convicted of the murder of his wife, at the Central Criminal Court, in Oct., 1862. The prisoner lived with his wife and another woman named Humbler. The wife was found dead in her bedroom, with wounds in her throat, at 8 a.m. The nature and direction of the wounds, the position of the body and of the weapon, as well as other circumstances, conclusively proved that this was an act of murder; and as there were no persons in the house at the time of the occurrence excepting the woman Humbler (the servant) and the prisoner Gardner, it followed that one or both must have been concerned in the act. Gardner accused the servant, Humbler, of having perpetrated the murder during his absence from home; but as there was no evidence against this woman, he alone was subsequently called upon to answer the charge. The facts, as they bear upon the question which we are now considering, are very simple. Sequeira saw the body of the deceased, a healthy, well-developed woman, æt. 37,

at 8 a.m. Her body was found lying on a wooden floor, covered w flannel petticoat and a chemise. The upper limbs were cold and rigid face, shoulders, and chest were cold; the neck was so rigidly fixed wit trunk that the entire body was lifted up with it when the head and were raised; the thighs and legs were quite cold, but there was no rig in these parts. The only warmth found about the body was in the l part of the abdomen, and this obviously arose from the contents o uterus, the deceased being in the seventh month of pregnancy. opinion given by Sequeira regarding the time of death before its bearing on the guilt of the prisoner could have been known was tha deceased had been dead *above four hours*, certainly more than three that she could not have been dead so short a time as two or three h when he first saw the body. This opinion was corroborated at the tri another medical witness, Comley, who affirmed that, considering general coldness of the body, the deceased, when seen at eight o'clock been dead above rather than under four hours. There was a severe w on the throat, involving the superior thyroidal artery and other ve From this about two pints of blood had flowed on each side of the nec the floor. The larynx had been laid open between the thyroid and cr cartilages. Blood had flowed into the windpipe through this aper and had thus, by obstructing respiration, produced death by asphyxia.

Without going into all those circumstances which tended to fix crime beyond any reasonable doubt upon the man Gardner, it ma sufficient to state that the defence turned principally upon the conditi the dead body when found. It was proved that from 4 to 8 a.m., i.e about four hours, the prisoner was absent from home, following his u occupation as a chimney-sweep. It was contended by his counsel within this short period the body might have become cold and rigid was found, and, therefore, that the murder had been perpetrated by s one during his absence. On this theory the woman Humbler alone guilty. The facts proved at the trial were, however, considered by jury to be quite inconsistent with the innocence of the prisoner, an was convicted of the crime. The subsequent commutation of the sent to penal servitude for life is a proof that the authorities considered he was the principal, if not the sole perpetrator of this crime.

The opinions given by the medical witnesses at the trial, regarding inference derivable from the state of the dead body, were reasonable, an accordance with scientific observations. In assigning *four hours* for almost entire cooling and commencement of rigidity in the dead body woman suddenly dying in the prime of life, the body not being expose any specially cooling influences, it is obvious that they could not be cha with overstating, but rather with understating, the period of time requi Considering that death had taken place by asphyxia, if they had assig six or eight hours, it would have been only consistent with ordinary ex ence. It is, indeed, more probable that this time had actually elapsed, that the woman had died in from two to four hours before the male pris had left the house, than that her body, under the circumstances pro had become cold and partially rigid in less than four hours. In one hun cases observed by Wilks and the author, there was not an instanc which such rapid cooling and access of rigidity occurred. In Gardi case, it was supposed that the loss of blood would account for this s of the body at so early a period after death; but, in the first place, deceased did not die from hæmorrhage, but from suffocation; and, secon a well-marked case elsewhere related (page 48), shows that the loss of t as much blood in hæmorrhage proving suddenly fatal, led to no accelera of cooling or rigidity in the dead body.

As cadaveric rigidity had commenced in the upper part of the body of deceased when it was first discovered, we may take this as a point of parison with the actual observations of Nysten and Brown-Séquard. ording to Nysten, in cases in which death took place suddenly in thy persons, either from asphyxia or as a result of hæmorrhage, cada- c rigidity did not commonly appear until sixteen or eighteen hours r death, and sometimes lasted six or seven days. Brown-Séquard es, that in the bodies of healthy persons decapitated or asphyxiated, veric rigidity did not appear sooner than ten or twelve hours after h ('Proc. Roy. Soc.,' 1861, p. 211). Considering these facts, and the umstances under which this body was found, the assignment of a period ix or eight hours would have been quite within the limits of experience observation. The medical opinions given at the trial were consistent ı ordinary experience, and with the other facts proved in the case.

The case of *Jessie McPherson*, for the murder of whom a woman named achlan was tried at the Glasgow Autumn Circuit, 1862, furnishes an tional proof of the correctness of these views in reference to the bodies ersons found dead from loss of blood. Macleod saw the body of ased on the night of July 7th, when it was first discovered. The mean perature of the air on that day had been 50° F. 'The rigor mortis was ent in all the articulations, but it was then departing. The body perfectly cold, even on the abdomen, and at the flexures of the joints. the following day, at 10 a.m., the rigidity had gone from all the joints pting the knees and ankles. There were no signs of decomposition, the temperature was very cool, unusually so for the season. The room hich the body had lain was well ventilated, but without a draught. It below the level of the street, and the body lay on a wooden floor, was partially covered. Further, death had resulted from violence; it been attended with profuse hæmorrhage, and the victim was free a disease, in the prime of life (æt. 35), and of a thin, wiry frame.' leod considering that the rigor mortis commonly appears in from ten rs to three days after death, and that in sudden death from violence it nly slowly developed, thought it most probable that forty-eight hours r death (at the longest) would represent the time when rigidity would ear. 'The more rapidly it is developed, the sooner it disappears, and ı versâ. The average period of disappearance is from twenty-four to rty-six hours. In the case under review, resting on the same considera- ns as influenced the opinion formed of the time of the establishment of ı stiffening, it was thought that about thirty hours would probably resent the period of the continuance of the rigidity; and by summing se periods—forty-eight and thirty—together, the conclusion was arrived hat about *three days* had probably intervened since death; and it will be embered that it was afterwards proved that this was, as nearly as could be, time which had passed between death and the examination of the body.' 'Putrefaction appears on an average, under a mean temperature, in n three to six days. It is influenced by many circumstances, of which heat and moisture of the surrounding atmosphere, the obesity and age he person, the cause of death, the position and coverings of the body, the chief. In the case of McPherson there was no appearance of mposition. The cool atmosphere, the thin body drained of its blood, the dle age, and thin covering, all opposed its development' ('Account of Medical Evidence at the trial of Jessie McLachlan,' by G. H. Macleod,). Glasgow, 1862, p. 8). This medical opinion, formed from the state he body, tended to confirm that part of the prisoner's story which ted to the time of death.

On these occasions, unless we have a due regard to all the circumstances

of a case, great errors may be committed. A period for death may be assigned which is inconsistent with the proved facts, and thus give impunity to murderers. Ollivier and Devergie were once required to examine a medical report by two physicians, in which they stated that they had found the deceased, a woman, aged sixty, dead in her apartment from strangulation. When the body was found it was lying on the floor, clothed in her usual dress of cotton and flannel, in a state of cadaveric rigidity, with general lividity of the surface of the skin. It was cold, with the exception of a slight warmth which remained in the abdominal viscera when the inspection was made. From these data the inspectors came to the conclusion that deceased had not been dead more than from fifteen to twenty hours before the time at which they saw the body. This would have fixed the date of the murderous assault at 1 p.m. on March 6th, whereas the general evidence tended to show that the crime must have been committed on the night of March 4th or 5th.

Considering that the deceased had died from asphyxia, in which case warmth is usually retained, that her body was well clothed, and yet rigid and cold, with the exception of a doubtful trace of warmth in the abdominal viscera, Ollivier and Devergie came to the conclusion that she must have been dead for a longer period than fifteen or twenty hours; and, without defining the precise time, which, under the circumstances, was not necessary, they affirmed that there was no medical ground on which such a restriction of the period of death was justifiable. They contended that cadaveric rigidity, when once established, might remain two, three, or four days, according to the season of the year and other circumstances; and that when it existed, there was no rule by which it could be determined whether the body had been in this state for two or three hours or two or three days ('Ann. d'Hyg.,' 1833, 1, 212). The retention of warmth by the abdominal viscera may be met with after fifteen to twenty hours, in a much more marked degree than in this case. In one case, already referred to, the temperature of the viscera of the abdomen, more than seventeen hours after death, was found to be 76° F., although no care had been taken to preserve the warmth of the body.

These changes in the dead body may occasionally have an important application to civil suits. When two persons are found dead under similar circumstances, a presumption of survivorship might arise in favour of one, by reason of the condition of the body showing a more recent death. A husband and wife, the latter possessing property in her own right, may be found dead in the same apartment; the body of the husband may be cold and rigid, while that of the wife may be warm and pliant. It might in this case be presumed that the wife had survived the husband, and the heirs of the wife, if she died intestate, might claim her property. On the other hand, if the body of the wife was found in a state of decomposition, while that of the husband was either cooling or in a state of commencing rigidity, there could be no doubt, medically speaking, that the presumption of survivorship lay with the husband, although no human eye may have witnessed the death of either. In this case the few hours' survivorship might be held to transfer the property of the wife to the husband, or through him to the claimants on his part. In these contested cases of presumed survivorship, the litigation between contending parties is often carried to an extreme degree, so that every medical or scientific fact which can be made available, will be brought out on either side.

Some French medical jurists have attempted to give a more definite character to these changes in the recently dead body, by dividing the interval between the permanent cessation of the heart's action and the commencement of putrefaction into three stages or periods. In the first,

the warmth and pliancy of the body and muscular irritability remain; in the second, these conditions are lost, and the body is cold and rigid; in the third, the body is cold and pliant, the muscles are relaxed, and the joints are flexible, cadaveric rigidity having entirely ceased. A fourth period is marked by the access of putrefaction, in the appearance of one or more well-known signs indicative of chemical decomposition. There can be no doubt about the existence of these stages, but when we attempt to define the precise time at which they commence and succeed each other, the subject is beset with great difficulty. Thus, according to Devergie, the first stage ranges over a time which cannot be more closely defined than by stating that the person may have been dead from a few minutes to twenty hours. From the differences observed in different bodies, there would be some danger in fixing these times too strictly; and a medical jurist must be prepared to find that in a question of murder, a counsel who defends a prisoner will reject averages, and take for the purpose of defence, the longest or shortest period of time within which the respective changes have been known to occur. In spite of this objection to medical evidence, it may be convenient to consider the subject in reference to the three stages or periods proposed by Devergie.

First Period.—This is characterised by the warmth of the body being more or less preserved, and by a general or partial relaxation of the voluntary muscles. In such a case as this, after attentively considering the various circumstances special to each, which may have retarded or accelerated the cooling of the body, an inference may be drawn that death has taken place from a *few minutes* to *twenty hours*. These are the extreme limits, and the time will vary according to the degree of heat in the trunk and extremities, and the degree of rigidity in the muscles, as well as in the parts of the body affected, the neck and the jaw commonly showing this condition first and the legs the last. It is rare that the warmth of the body is preserved for so long a time as twenty hours; in general it is sensibly cold within ten or twelve, but this estimate will be more or less affected by the condition of the person who makes the observation. During this period, the muscles are susceptible of contraction under the galvanic stimulus, and in the early stage under the stimulus of blows.

Second Period.—In this the body is perfectly cold throughout, and the cadaveric rigidity is well marked. The muscles are no longer susceptible of contracting under galvanic or mechanical stimuli. In such a case death may have occurred from *ten hours* to *three days*. It is impossible to give a more definite opinion than this, since there are conditions which may develope rigidity, and under which a body may become cold in ten hours or even in a shorter period. In one instance already related, a body was found cold and rigid nine hours after death. Again, there are, as we have seen, other conditions which may prevent the cooling of the body, and delay the occurrence or prevent the disappearance of rigidity for so long a period as three or even four days after death. The duration of this stage from ten hours to three days includes the average cases. Here, again, in forming an opinion we are bound to regard the age, the mode of death, and the circumstances under which the body of the deceased may have been exposed.

Third Period.—The body is perfectly cold; the members and trunk are pliant, and are quite free from any remains of cadaveric rigidity. As this condition has ceased spontaneously, the muscles no longer contract under the influence of the galvanic stimulus. Under these circumstances it may be assumed that the person has been dead from *three to eight days*. In the summer season, however, this period is much shorter: it will more commonly be found to be the condition of bodies which have been dead from one to three days.

Fourth Period.—This commences with the access of putrefaction. It is first manifested by a slight blueish-green discolouration of the skin of the abdomen, and it gradually spreads throughout the body in the manner elsewhere described. Any doubt concerning the reality of death, must cease when the body has reached this stage, at whatever period of time it may manifest itself. Devergie considers this state to represent the condition of the body from *six to twelve days* after death, but the fact is well known that putrefaction may manifest itself on the first or second day, and sometimes as late as the twelfth day after death. These different periods are somewhat arbitrarily selected, and they can be looked upon only as affording approximative results. During the heat of summer a body may undergo in twenty-four hours all those changes which Devergie assigns to a period of from six to twelve days; while in winter the same changes may not be complete in a shorter period than fifteen days. The power of giving a safe medical opinion, must therefore depend on an accurate observation of the state of the dead body when first seen, and a proper estimation of all the causes which influence or modify the successive changes. Notwithstanding the apparent want of precision which medical evidence necessarily presents in investigations relative to the period at which a person died, yet the cases already related show that approximative results are often of great value. When founded on a correct knowledge of the state of the body, and when they are corroborated by other circumstances, they are received in law with the greatest benefit to the administration of justice.

Cadaveric Lividity, or Hypostasis. Ecchymosis.—There are certain external changes which take place in a dead body before the access of or during putrefaction, to which it is necessary that a medical jurist should attend. There is what is called *cadaveric lividity*, or *hypostasis*, which comes on during the act of cooling. At a still more advanced period, dark livid spots or patches are met with in the skin, to which the name of *sugillation* or *post-mortem ecchymosis* has been given. These appearances have often been mistaken for the effects of violence applied during life, and serious mistakes have thence arisen. Innocent persons have been accused of murder or manslaughter, and have been tried on charges afterwards proved to be groundless. Christison refers to two cases, in one of which two persons were convicted, and in the other, three narrowly escaped conviction, upon a mistake of this kind.

A man named *Keir* and his mother were tried on the Aberdeen circuit, for the murder of the father of the man. This case excited great interest at the time, and for many years afterwards. The prisoners were condemned, but the only evidence of any weight against them was the appearance of a broad blue mark on the fore part of the neck, which the witnesses compared to that produced by strangulation. There was, however, great reason to believe, from their own description of it, that it was due to natural changes taking place after death. The other case occurred in Edinburgh. Three men left a publichouse, intoxicated and quarrelling with each other. On the next morning one of them was found expiring in a wood, and he died soon after he was discovered. Two surgeons deposed, that they found the marks of numerous contusions all over the body; and upon this deposition, the two companions of the deceased were committed, and subsequently tried for the murder. On the trial, Bell and Fyfe proved to the satisfaction of the Court, that the apparent contusions were nothing else than the livid patches, or hypostases, which sometimes occur spontaneously on the dead body, after many kinds of natural death. Of course, this led to the liberation of the accused persons.

These spontaneous changes in the dead body must, therefore, be attended

by the surgeon. They may be considered, by dividing them into those ich take place *before putrefaction*, and those which take place *afterwards*. The first form, *hypostasis* (before putrefaction), is dependent on a stag- ion of blood in the capillary vessels. So long as there is life, the capillary ulation continues. This may be ascertained by puncturing the skin or with a fine needle; if the capillary circulation is going on, a drop of od will escape, otherwise not. When after death the capillaries have their contractility, the blood appears to stagnate in them in an irregular ner, producing *lividity*. The skin of the body, although pale at the e of death, becomes covered during the act of cooling by extensive patches a blueish or slate colour, diffusing themselves over the greater part of the ck and limbs. The colour is sometimes of a deep purple, often mottled, generally abruptly terminating in the white skin. These hypostases are fly seen on the bodies of those who have died suddenly in full health, or a violent death, as in apoplexy, hanging, drowning, suffocation from coal vapour, and other causes. In the latter case, it has been found in e instances to be especially developed. It is rarely seen in the bodies of se who have died from loss of blood; the skin is in these cases commonly id. When the skin in which the lividity is seated is divided, it is seen the colour is confined to the upper layer of the true skin (cutis), or to space between the cuticle and cutis, and never to extend through the er. There is no sanguineous effusion, but apparently a simple conges- in the minute capillary vessels.

The unruffled state of the cuticle, the great apparent extent of the dis- ration, the fact that it affects many parts of the trunk and members, and n entirely envelopes the whole circumference of one or both limbs, are, ether with its abrupt termination, and the absence of extravasated blood he cellular membrane beneath, circumstances sufficient to distinguish it m the ecchymosis produced by violence.

Sometimes this lividity is disposed in a peculiar form over the body. If tout and muscular person has died suddenly, and the body, wrapped ely in a sheet is allowed to cool, the lividity may be sometimes disposed he form of a number of stripes or bands over the whole surface—the gestion of the vessels taking place in the interstices of the folds, while parts actually compressed remain white. The appearance of the body uch that we can hardly divest our minds of the idea that the person must ve been flogged. The unbroken state of the cuticle, with the other aracters just now mentioned, are, however, sufficient to distinguish this pearance from the effects of violence. This kind of lividity is sometimes med *vibices*. It is often seen on the backs of subjects that have been owed to cool either in their clothes or on any rough and uneven surfaces. e author saw a well-marked case, in which the suspicion was so ong that violence had been used to the deceased, that a coroner's inquest k place. The fore part of the body was covered with stripes, which re of a red and livid colour: they appeared to correspond exactly to the ds of a sheet drawn tightly across the chest; and it was subsequently certained that the body of the deceased had been treated in this manner on after death. The blood was superficially diffused, and the cuticle injured. The circumstance above mentioned at once satisfactorily plained the cause of the appearance. These hypostases are commonly n in plethoric persons; they indicate great vigour of circulation at the ment of death. But lividity in the dead body may occasionally present lf under a more deceptive form than in either of the instances just men- ned. This is well shown in the case of a man who died in 1837, on board e Dreadnought hospital ship. The subject of this case, æt. 33, died ddenly from disease of the heart. Just before death the deceased had

been ausculated, and no marks then existed on the skin. The bo about eighteen hours, was examined, and then it was found to p detached places, patches of discolouration, varying in size from sn to several inches in diameter. Although closely simulating bruises of violence during life, a slight examination showed that they wer to hypostasis, because those parts of the back and limbs which compressed by the surface on which the body of the deceased w were the only parts discoloured. The calves of the legs, the loins back, which bore the pressure, were white. On cutting into these the layers of the skin, as well as the tissues beneath, were thoroughl dened by congested blood, and small rounded semi-coagulated mas out from the cellular membrane on slight pressure.

These characters somewhat resembled those produced by violen living body; but there was another, and an unexampled circu in which the resemblance to *vital* ecchymosis existed. Arou of the patches there was a wide border, or zone, of a pale stra with various shades of green and blue, precisely similar to those v seen in the gradual disappearance of an ecchymosis from the livi By most medical jurists it has been hitherto considered that the colour are peculiar to vital ecchymosis, and are never seen in th mosis produced after death. The occurrence of this case shows w caution general rules should be framed for medico-legal practice. body of this person been found lying dead and exposed on a high had it been proved that another man had been seen quarrelling what might have been the opinion expressed? We can scarcely h say, unfavourable to the accused person. This kind of ecchymo have been distinguished from that of violence during life only unruffled state of the skin, and the slight effusion of blood, compa the extent of discoloured surface. It is worthy of note, also, that seat of hypostasis was in those parts which were recumbent or d The formation of the coloured zones around some of the patches c was fully explained by the fact of the man having laboured unde dropsy. The serum effused in the cells, here acted upon and di liquid blood, as it exuded from the vessels and diffused it around, the same manner as the serous exhalation of the cellular membran the blood effused in the living body.

A question, connected with hypostasis, was raised on the tria (p. 70), namely:—Whether this cadaveric lividity always *preca* veric rigidity or not? Rigidity is not in general strongly manife the body is cold; the lividity here described takes place while th cooling and the blood is liquid. The occurrence of rigidity depen time at which muscular irritability is entirely lost: but pos discolouration of the skin is closely connected with the presence o in the body, and with fluidity of the blood; hence cadaveric lividi to develope itself often soon after death, and continues to incr the body is cold, when its formation is entirely arrested. It a consist simply in a hypostatic congestion of the capillary vesse produced by gravitation before the coagulation of the blood in stage or period after death. As it has now been clearly proved tha affects the heart and coats of the arteries before rigidity of the muscles manifests itself, it is highly probable that in the conta these tubes, the blood is forced at first through the capillaries venous system, and afterwards, from want of sufficient power of p it stagnates unequally in these vessels, producing livid patches on although the arteries are relaxed and become quite flaccid, the bloo in the minute vessels in which it has collected.

One form of hypostasis observed in the dead body, is that which pears to proceed from an infiltration of blood pigment into the depending rts of the body, and to be a result of incipient putrefaction. They who) much engaged in inspections are well aware that the skin of the back, ecially that covering the loins and buttocks, often presents irregular colourations resembling ecchymosis. The skin of the back of the head l nape of the neck is a well-known seat of this form of hypostasis. On ting into the skin of any of these parts, it is found to be more or less coloured throughout, and the fatty tissue is filled with a bloody serum, ich readily escapes. In proportion as putrefaction advances, the dis- ouration becomes greater, passing from a dark red to a green colour. e general characters of this kind of hypostasis are so well marked, that annot easily be confounded with the ecchymosis of violence. The parts the body in which it is known to occur, as well as the state of the body, circumstances which distinguish it from all the other forms described. is variety of hypostasis is *true hypostasis*, is also termed sugillation by ne medical jurists. (On the subject of Ecchymosis, see 'Ann. d'Hyg.' 8, 2, 383.)

CHAPTER 6.

TREFACTION—ITS NATURE AND PROGRESS—PRODUCTION OF GASES—POST-MORTEM HÆMORRHAGE—PRESSURE ON THE VISCERA—NATURE OF THE GASES OF PUTREFACTION—CHANGES IN THE COLOUR OF THE SKIN AND OTHER ORGANS—PUTREFACTION IN AIR—CONDITIONS FOR THE PROCESS—CIRCUMSTANCES WHICH MODIFY IT—INFLUENCE OF DISEASE AND CERTAIN POISONS—PUTREFACTION IN BODIES BURIED IN GRAVES—PRODUCTION OF ADIPOCERE—ITS CHEMICAL NATURE.

TREFACTION.—By putrefaction, we are to understand those chemical anges which take place spontaneously in dead animal matter, during ich offensive gases are evolved. The ultimate effect of these changes is, ter a longer or shorter period, to reduce the organic to the condition of organic compounds consisting chiefly of water, ammonia, and carbonic id. It is in the stage of transition that noxious effluvia are evolved, from ich the process derives its name. These consist of compounds of nitrogen, ulphur, carbon, and hydrogen.

This process does not begin to manifest itself in the dead body until ter the cessation of cadaveric rigidity, and generally about the third day. is then observed, if the body has been exposed to the atmosphere in an artment of mean temperature (60° F.), that the limbs and trunk become pple and pliant, and yield a faint odour. The skin covering the abdomen comes of a pale green colour, which gradually deepens. A similar dis- loration slowly makes its appearance in the chest, between the ribs, in the ce, the neck, the legs, and lastly, in the arms. The colour appears to pend on the decomposition and infiltration of the animal fluids, especially e blood, into the skin. In the neck and limbs it is observed to be more arked in the situation of the large venous trunks; and sometimes, indeed, e course of the superficial veins is accurately traced out by greenish-blue dark lines; these have been mistaken for marks of violence. This change the colour of the blood infiltrated into the tissues is probably owing to e action of ammonia as a result of decomposition, on the red colouring tter. In a more advanced state the blood contains sulphuretted hydrogen well as ammonia in the form of ammonium sulphide and carbonate.

Its colour is then dark brown, almost black, and it effervesces strongly when an acid is added to it. Gaseous products are formed, not only in the hollow organs of the abdomen, but beneath the skin generally; so that on making an incision, the edges of the skin are rapidly forced apart or everted. The pressure of this confined gas accounts for the occasional escape of alimentary and fæcal matter from the outlets:—as also for the escape of blood some days after death from wounds involving any of the large veins.

This *post-mortem hæmorrhage* requires one or two remarks. Its occurrence formerly gave rise to the most superstitious notions, and even in the present day an undue importance may be attached to it by a coroner's jury. In order to explain this, and some other apparently vital phenomena connected with a dead body, it will be necessary to refer to those spontaneous changes which commence soon after death. When a person has died suddenly from violence or convulsive disease, it may happen that within a short period the whole of the cavities, including the veins, arteries, and cellular tissue beneath the skin, become distended with gases derived from putrefaction. The gases collected in the abdomen push back the diaphragm, in consequence of which, mucus with air-bubbles issue from the mouth and nostrils; the face is swollen, and the eyes are bright and prominent, owing to the blood having been forced back to the head and neck, by the distended state of the abdomen and viscera. For a similar reason the contents of the stomach are sometimes discharged, escaping into the windpipe, or flowing externally by the mouth and nostrils. That which, however, more immediately concerns us at the present time, is the development of these gases within the heart and large blood-vessels, in consequence of which blood may be forced out of a wound made before death, long after all the phenomena of life have entirely ceased. If an attempt has been made to bleed a person immediately before death, without success, and the operator has neglected to secure the opening in the vessel, it may happen some hours after death, that a large quantity of blood will escape by the wound—conveying to those, who are uninformed on these matters, the idea that the person had again come to life, but had died from the bleeding. An accident of this kind gave rise to considerable discussion, on the occasion of an inquest held at Oldham, on the body of *John Lees*, killed in the Manchester riots; as also in the case of the Crown Prince of Sweden, who was supposed to have been poisoned. A similar flow of blood may take place from a large incised wound, made recently before death. This post-mortem hæmorrhage is facilitated by pressure, and on this was based that ancient test of guilt: viz., the touch of the murderer.

Post-mortem hæmorrhage may take place from wounds made after death, and quite irrespective of putrefaction. If the blood is warm and fluid it may ooze from an open wound in the body and partially coagulate after its escape (see 'Observations,' by Dr. Wilks, p. 64). The quantity which thus flows from a recently dead body is not large, unless some large veins are implicated. Even some hours after death, when the body is cold, bleeding may take place from a post-mortem wound, and might give rise to a suspicion of criminal violence. In 1871 a prisoner hanged himself in his cell at Newgate before the door. A warder who found him thus suspended passed his arm through the opening of the door and cut the ligature. The body fell forwards on the floor. It was soon afterwards dragged to the further end of the cell. The body was then cold and becoming rigid. It was found that where the head had rested there was a small pool of blood (about six or eight drachms), and the floor was smeared along which the head had been dragged. The blood was of a bright colour, but there was no separation into clot and serum. On

One form of hypostasis observed in the dead body, is that which ppears to proceed from an infiltration of blood pigment into the depending rts of the body, and to be a result of incipient putrefaction. They who e much engaged in inspections are well aware that the skin of the back, pecially that covering the loins and buttocks, often presents irregular scolourations resembling ecchymosis. The skin of the back of the head d nape of the neck is a well-known seat of this form of hypostasis. On tting into the skin of any of these parts, it is found to be more or less scoloured throughout, and the fatty tissue is filled with a bloody serum, hich readily escapes. In proportion as putrefaction advances, the dis-louration becomes greater, passing from a dark red to a green colour. ie general characters of this kind of hypostasis are so well marked, that cannot easily be confounded with the ecchymosis of violence. The parts the body in which it is known to occur, as well as the state of the body, circumstances which distinguish it from all the other forms described. is variety of hypostasis is *true hypostasis*, is also termed sugillation by ne medical jurists. (On the subject of Ecchymosis, see 'Ann. d'Hyg.' 38, 2, 383.)

CHAPTER 6.

PUTREFACTION—ITS NATURE AND PROGRESS—PRODUCTION OF GASES—POST-MORTEM HÆMORRHAGE—PRESSURE ON THE VISCERA—NATURE OF THE GASES OF PUTREFACTION—CHANGES IN THE COLOUR OF THE SKIN AND OTHER ORGANS—PUTREFACTION IN AIR—CONDITIONS FOR THE PROCESS—CIRCUMSTANCES WHICH MODIFY IT—INFLUENCE OF DISEASE AND CERTAIN POISONS—PUTREFACTION IN BODIES BURIED IN GRAVES—PRODUCTION OF ADIPOCERE—ITS CHEMICAL NATURE.

PUTREFACTION.—By putrefaction, we are to understand those chemical anges which take place spontaneously in dead animal matter, during hich offensive gases are evolved. The ultimate effect of these changes is, ter a longer or shorter period, to reduce the organic to the condition of organic compounds consisting chiefly of water, ammonia, and carbonic cid. It is in the stage of transition that noxious effluvia are evolved, from hich the process derives its name. These consist of compounds of nitrogen, ulphur, carbon, and hydrogen.

This process does not begin to manifest itself in the dead body until fter the cessation of cadaveric rigidity, and generally about the third day. t is then observed, if the body has been exposed to the atmosphere in an partment of mean temperature (60° F.), that the limbs and trunk become pple and pliant, and yield a faint odour. The skin covering the abdomen comes of a pale green colour, which gradually deepens. A similar dis-loration slowly makes its appearance in the chest, between the ribs, in the ce, the neck, the legs, and lastly, in the arms. The colour appears to pend on the decomposition and infiltration of the animal fluids, especially e blood, into the skin. In the neck and limbs it is observed to be more arked in the situation of the large venous trunks; and sometimes, indeed, e course of the superficial veins is accurately traced out by greenish-blue r dark lines; these have been mistaken for marks of violence. This change the colour of the blood infiltrated into the tissues is probably owing to e action of ammonia as a result of decomposition, on the red colouring atter. In a more advanced state the blood contains sulphuretted hydrogen well as ammonia in the form of ammonium sulphide and carbonate.

It will generally be found that the sulphuretted hydrogen is combined with ammonia, since paper impregnated with a solution of sodium nitroprusside acquires a crimson colour when held in a jar containing the decomposed viscera. Other gases and vapours, of which chemistry can at present render no account, are also present. On some occasions the exhalations have been of a most offensive and nauseous character, and the tests have not indicated the presence of sulphuretted hydrogen.

Lewis examined and reported on the external condition and appearance of 22,000 coffins accumulated in the vaults of London churches. He examined the state of the contents of about one hundred of these. The experiments were made on the bodies of persons of all ages, and on coffins which had been deposited from a short period to upwards of a century. He did not find therein sulphuretted, phosphuretted, or carburetted hydrogen, or any compound of cyanogen. The gases which he uniformly detected in the coffins and the vaults were nitrogen, carbonic acid, and atmospheric air holding putrescent animal matter in suspension. Ammonia was occasionally found in large quantities; this, when present, overcame all other odours. When absent, the animal matter had a smell resembling that of putrid moist cheese. He opened one leaden coffin in which the corpse had been enclosed for nearly a century; the ammoniacal gas which escaped from it formed dense white fumes when brought into contact with hydrochloric acid gas. It was so powerful that the head could not remain near it for more than a few seconds at a time ('Amer. Jour. Med. Sc.,' Jan., 1852, p. 275). The same results were noticed in reference to a body which was exhumed after six months' interment. When the coffin lid was removed by the side of the grave a large quantity of fœtid ammonia escaped. On throwing into the coffin some chloride of lime, dense white clouds of ammonium chloride were evolved from the interior of the coffin, to the great alarm of some of the bystanders, who were not aware of the chemical changes produced. It would appear that the air enclosed in coffins is in general completely deoxidized. When tested it was not inflammable, but was found in every instance to extinguish flame. In leaden coffins putrefaction is so much retarded that the remains of bodies were found in them after the lapse of a century. The metal is slowly corroded and changed into white lead.

Changes in the Viscera.—During these changes in the dead body various discolourations take place on the mucous surface of the stomach and bowels, which often closely simulate the effects of disease or poison. The mucous membrane of the stomach may be found of various tints—from a red brown, becoming of a brighter red by exposure to the air, to a deep livid purple or slate colour, and sometimes black from a decomposition of the blood. At the greater end, where the stomach is in contact with the spleen or liver, the lividity is often well marked and clearly defined through all the coats. The peritoneal or outer coat is of a greenish hue, and the course of the superficial vessels is marked by greenish-brown or black lines. These spontaneous changes, which are the result of putrefaction, may be easily mistaken for the effects of irritant poisoning. There are no rules that will always enable a medical jurist to distinguish such cases. Much must depend on the progress of putrefaction, and the period after death at which the body is examined: hence, each case must be judged by the circumstances which attend it. We may presume that the redness has taken place during life, and is not a result of post-mortem changes,—1. When it is seen soon after death. 2. When it is met with in parts not dependent, nor in contact with other organs gorged with blood. 3. When it is accompanied by a considerable effusion of coagulated blood, mucus, or flakes of membrane, the result of ulceration, corrosion, or destruction of the coats of the viscera. When the body is not inspected until a long period after

th it is difficult to distinguish these pseudo-morbid appearances from se depending on the action of irritant poison. In a really doubtful case i therefore better to withhold an opinion, than to express one which must purely conjectural.

The signs of internal putrefaction first appear on the mucous membrane the larynx and trachea. It is impossible to assign a definite period to ich the effects produced by irritant poisons are destroyed by the process putrefaction. If the poison were of an antiseptic character, and the y had been speedily buried, a decided redness of the stomach, as a result nflammation, may be perceived after five or six weeks. On one occasion effects of arsenic on the mucous membrane of the stomach were dis-guishable in the case of a child whose body had been interred for a period iwenty-eight days; and in other cases in which the viscera were well served, after a year and nineteen months. Of course, when the inflam-ion is only slight, it will be much more speedily obliterated, or merge he redness caused by decomposition.

The effects of gravitation (hypostasis) in leading to a discolouration of stomach and bowels in the recently-dead body, should not be overlooked. e experiments of Trousseau and Rigot have determined, that the simple cts of gravitation will produce a livid or even a red appearance ll the dependent portions of the intestines. This *cadaveric congestion*, hypostasis, has been long known to exist in the lungs; but it does not ear to have attracted sufficiently the attention of pathologists, in respect he stomach and intestines. It has been especially remarked by Andral l others, in the small intestines, particularly in those portions found hin the cavity of the pelvis; and this last-mentioned pathologist noticed, t in a body placed with the face downwards soon after death, the anterior ll of the stomach became strongly reddened. As this effect of gravita-a ceases so soon as the blood coagulates by the cooling of the body, so s it follow that when the body has been a long time in cooling, it will much more strongly marked.

The mucous membrane of the stomach and upper part of the small estines often presents, during putrefaction, a yellowish or green tinge, pending on the transudation of the bile, or the colouring matter of the es contained in the colon. This must not be mistaken for the appear-ce of poisoning by the mineral acids. There is, in these cases, no soften-g or corrosion, and the throat and gullet are not implicated, as they are this form of poisoning. So, again, melanosis in the stomach—*i.e.*, a posit of black colouring matter beneath the mucous coat, might be mis-ken for the effect of sulphuric or oxalic acid or caustic alkalies; but elanosis is unaccompanied by any marks of inflammation, corrosion, or struction in the mucous membrane beneath, and it is always seen in well-fined spots.

Among the *external* changes produced by incipient putrefaction, a nge of colour in the skin covering the abdomen, has been already ticed. It slowly acquires a pale green hue, gradually deepening and tending to the skin of the chest and limbs. This colour has been re-rded, by Deschamps, as a certain sign of death, and one better fitted an any other to guide us in determining the reality of death. This sign, wever, is not available, under common circumstances, until three days ter death, and it is scarcely possible that a well-informed practitioner uld require to wait so long a time before expressing an opinion. schamps has laid down the following rules respecting this green lour acquired by the skin of the abdomen:—1. A greenish-blue colour, tending uniformly over the skin of the belly, is the only real and certain n of death. 2. The time at which this sign appears after death varies

much; but it commonly takes place in about *three days*, under favourable conditions of warmth and moisture. 3. Although discolouration of various kinds, and from various causes, may occur in other parts of the body, this characteristic mark of death is always to be found in the abdomen. 4. Apparent death can no longer be confounded with real death, the abdomen never becoming coloured green or blue in any case in which death is only apparent. 5. This colouring of the abdomen, the appearance of which may be artificially hastened by exposing the body to warmth, will, if observed, entirely prevent the possibility of premature interment. 6. There is no danger to public health from keeping a body until the appearance of the characteristic sign of death.

There are some facts connected with the progress of putrefaction as it takes place in the atmosphere, in the earth, or under water, which are of interest to a medical jurist.

1. Putrefaction in Air.—Putrefaction cannot take place in the *living* body. Some have conceived that putrefaction might begin under a diminished state of vitality, as when a person is about to perish from a slow and wasting disease; they have thus explained the peculiar odour perceptible in the breath and perspiration of many dying individuals, some hours previous to dissolution. But it is certain that so long as *life* remains, no phenomena resembling those of ordinary putrefaction in the dead body are observable. It is unnecessary to make any remark in this place relative to local gangrene; since, although this may take place in a living body, it is only observed in a part already deprived of life, and does not involve the whole of the body. It is a molecular or partial death.

In some cases, before dissolution, the breath has been observed to be luminous: this has been ascribed to the evolution of phosphorus, which is said to have been distinctly recognized by its peculiar odour. It is stated also, that the countenance of a dying person has, on more than one occasion, become distinctly luminous or phosphorescent in the dark. The cause of this phenomenon is unknown, and so far as we are aware it has been only in advanced cases of consumption or wasting disease, that this evolution of light from the countenance shortly before death, has been observed (see cases by Marsh, 'Ed. Med. Jour.' vol. 58, p. 497; and by Donovan and Stokes, 'Dub. Med. Press,' Jan. 15, 1840). M'Cormack has reported the case of a child, aged sixteen months, suffering from dentition, in which the skin of the hips was observed to be luminous. There was no odour of phosphorus, and no application which could account for it, had been made to the skin ('Ed. Med. Jour.' vol. 66, p. 285). The dead human body may become luminous under incipient decomposition. A remarkable case of this kind occurred in 1823–4, in the dissecting-room of the Webb Street School of Anatomy. The greater part of a dead body which had been dissected appeared luminous or phosphorescent in the dark. The cause of this evolution of light in the dying and dead, is not well ascertained: in the dying it may possibly be owing to certain chemical changes analogous to decomposition, commencing during life; while, in the dead, it may be due to the production of luminous matter of a phosphorescent nature. It is well known that certain kinds of dead fish and decayed wood become luminous in the dark. These singular facts will account for many of the superstitions which formerly existed.

The time after death at which putrefaction commences, may vary from a few hours to many days and even weeks. It never begins until cadaveric rigidity has ceased, and therefore not until the muscles of the body have entirely lost their irritability. Whatever conditions of the body during life or after death may operate to cause the disappearance of muscular irrita-

ty, will *pari passu* accelerate rigidity and putrefaction, and *vice versâ*.
re are three primary conditions which are indispensable to the establish-
t of this process in a dead body. These are: 1st, a certain tempera-
; 2nd, the presence of moisture; and 3rd, the free access of air. There
many other conditions of a secondary kind which may retard or
lerate its commencement, and when established, may affect its progress
duration. These will be considered in their order.

Temperature.—The process is found to go on most favourably in a
erature varying from 70° to 100° F. It will commence, other circum-
ces concurring, at any temperature above 50° F.; but at 32° F. it
ars to be wholly arrested. The dead body may thus be preserved a
iderable time in snow, ice, or in frozen soil; but if, after removal, it is
sed to a temperature between 70° and 100° F., the ordinary putrefac-
changes are stated to take place with more than their usual rapidity.
an states that the body of Prince Menchikof, one of the favourites
eter I., was exhumed at Beresov, in 1821, after a burial of ninety-
years in the frozen soil of Siberia. Although so long a time had
ed, the body had undergone but little change. The heart and some
parts, with a portion of the grave-clothes, were removed and sent
ie descendants of the deceased ('Travels in Siberia,' vol. 1, p. 462).
a still more remarkable instance of the preservative or antiseptic
r of cold, is exhibited in the discovery of the body of an ancient
ant (*elephas primigenius*), the race of which was extinct before the
rical period, in a mass of ice at the mouth of the River Lena in
ia, in 1805 ('Quart. Journ. of Sci.,' vol. 8, p. 95).

low temperature is said to arrest putrefaction by congealing the mois-
within the animal body; but this explanation is not of itself sufficient,
a body at 33°, has no more tendency to putrefy than one at or below
'. It is said, again, that a certain temperature is essential to the
ination of the gaseous elements of the body during putrefaction, as well
the existence of the gaseous products resulting from their union. At
gh temperature again, *i.e.* about 212° F., putrefaction is arrested. The
animal solids lose their water, become hard and brittle masses, and may
be exposed to the atmosphere without undergoing any further change.
at between 100° and 212° F. may also speedily put a stop to the process,
using a rapid evaporation of the water contained within the solids.
become thereby dried. Thus it is that bodies buried in the hot and arid
s of Egypt are dug up, many years after interment, in the state of
cated mummies, putrefactive decomposition having been long since
ted. The effect of temperature on this process is strikingly seen in
nfluence of season. A dead body exposed to air during summer, when
hermometer is above 60° or 70° F., may undergo more marked putre-
ve changes in twenty-four hours, than a similar body exposed for a
: or ten days in winter. This is a fact which demands consideration,
1 an opinion is required to be formed, respecting the date of death
body concerning which nothing is known.

ight has not been found to have any influence over the process.

The presence of moisture.—Unless the animal substance is impregnated
water or moisture it is impossible that putrefaction can take place.
animal solids commonly contain sufficient water for the spontaneous
blishment of the process. In a human body weighing 150 lbs. there
about 100 lbs. of water. The soft organs differ much from each other
spect to the quantity of liquid contained in them, and therefore in the
ee in which they are prone to putrefaction. Thus the brain and the
are in this respect contrasted with the teeth, bones, hair, and nails.
fluids of the eye are rapidly decomposed, while the teeth and hair may

remain for centuries unchanged. Quekett examined a portion of dried human skin with hair upon it, which had been exposed for many centuries on a door of Worcester Cathedral, and also other portions taken from the church doors of Hadstock and Copford in Essex. He found upon them some hairs, which were proved by the microscope to be human, thus confirming the old tradition that the skins of persons who had committed sacrilege were nailed to the doors of the churches which they had robbed ('Ed. Month. Jour.,' July, 1848, p. 63).

If the organic substance is deprived of its water, putrefaction is arrested. Gay-Lussac found that flesh might be preserved for a considerable period, simply by suspending it under a bell-glass placed in a dish of fused calcium chloride. Albumen and gelatin, deprived of water, or dried by calcium chloride, have been kept in a dry state for a period of twenty years, during which time they have been exposed to air and a favourable temperature without undergoing putrefaction. An excess of water, however, tends to retard and modify the process; thus, by allowing a current of water to fall on animal matter, it may be preserved for a long time. Water in excess seems to retard putrefaction by merely cutting off the access of air. By long contact it produces an alteration in the soft solids, converting them into a white substance.

Influence of air.—Putrefaction may take place to a slight extent independently of air, but the process is soon arrested; and thus bodies sealed permanently in leaden coffins are found perfect, and may be identified after very long periods of time. The products in all cases in which air is excluded are chiefly of an ammoniacal nature. Air operates by its free oxygen combining with the tissues, and forming gaseous and liquid products. The only limit to this process of decomposition under a free supply of oxygen is the loss of water by evaporation. Nitrogen, the other element of air, has no influence; it appears to be antiseptic, so that flesh may be preserved in it for a very long period without change, although heat and moisture are present.

In gaseous mixtures it is necessary to putrefaction that the oxygen should be *free* as in the atmosphere, and not chemically united to any other element. Thus carbonic acid and nitric oxide—especially the latter, since it at once combines with free oxygen—act as most powerful antiseptics. In a series of experiments on the properties of these gases in retarding putrefaction the author found in one that a large piece of fresh muscle was preserved effectually in a bell-glass of nitric oxide over water for eighteen weeks; in a second experiment, for nineteen weeks; in a third, for a period of thirty-two weeks, or 224 days; and in a fourth, for a period of seventeen months. The last experiment was commenced in October, and after eighteen months the muscle suspended in the gas retained its red colour, and had undergone no change indicative of putrefaction. These experiments were carried on under all variations of temperature, in a room not below 40° in the winter season, but which sometimes reached 80° F. in summer. As the vessel containing the gas was placed over water the gas was, of course, always saturated with aqueous vapour. Two of the conditions for putrefaction were therefore present. Air only was removed. In some parallel experiments in air and oxygen putrefaction had gone on to a full extent in eight or ten days. These facts show that oxygen, in a free state, is eminently necessary for the destruction of the soft parts of the body by putrefaction.

The influence of the atmosphere is not merely confined to its affording oxygen. It modifies putrefaction, according to its dry or humid condition, and according to its state of rest or motion. Dry air retards putrefaction, since evaporation is increased. Humid air accelerates the process, by

iving rise to an opposite effect. Air in motion, as a brisk wind, retards he process, since, *cæteris paribus*, evaporation is greater. Air at rest, as he calm still atmosphere of a close apartment, is, on the other hand, favourble to the process. On the whole, it may be inferred that the conditions ost favourable to the putrefaction of a dead body are a temperature of bout 70° F. in a humid and tranquil atmosphere. It has been observed that hen putrefaction has once begun in a part of the body it has rapidly tended itself throughout the whole. It seems as if the first products ted as a kind of ferment, to induce chemical changes throughout the ass.

Modifying conditions.—There are some circumstances which modify the ogress and duration of the process. They chiefly relate to the condition the body at the time of death. Orfila thought that age and sex, as well peculiarity of constitution, had some influence, but there are no facts to nfirm this view.

Fat and flabby bodies are observed to undergo putrefaction more readily an those which are thin and emaciated. Connected with the state of the dy, we may also mention the influence which wounds or bruises, or mutiions of any kind, have over this process. Those parts which at the time death are affected by contused or incised wounds, ecchymosis, or extravsation, rapidly pass into a state of putrefaction. Thus, in examining dies which have been subjected to violence during life, contusions and chymoses may appear greatly aggravated in extent, unless the examiner aware that such parts become more speedily decomposed.

The bodies of persons who have died from acute diseases have been served to putrefy more readily than those of persons who have died from sting and chronic disease. In the numerous examinations of the dead ade at Guy's Hospital by Wilks he observed, as a rule, that the bodies those who had been long ill, and were emaciated, remained unchanged r a longer time than those who had died from acute disease ('Guy's osp. Rep.,' 1863). It would appear as if some diseases had either rectly or indirectly a retarding influence over the process. It has been so remarked that the bodies of plethoric persons who have died suddenly hile in good health have undergone rapid decomposition. In persons ho have died from asphyxia, as by drowning, suffocation, or strangulaon, the bodies are, *cæteris paribus*, observed to putrefy with great rapidity; nd, as a general rule, all those parts of the body which at the time of death re irritated, congested, or inflamed are rapidly attacked by the putrefactive rocess.

Conflicting statements have been made regarding the process of putrefaction in the bodies of those who have died from certain poisons. Thus has been stated that in death from prussic acid, morphia, and other egetable poisons, putrefaction generally commences early and progresses ith rapidity; while strychnine has been supposed to exercise a retarding ower. In poisoning by vegetable narcotico-irritants the blood is observed be frequently dark-coloured and very liquid, and it may therefore have ndergone some chemical change which may render it more prone to ecomposition. But the observations elsewhere made will at once account r the conflicting statements, and show that putrefaction may be accelerated or retarded under the influence of the same poison, according to the ode in which it operates on the muscular system at the time of death. hus when strychnine destroys life rapidly, without exhausting the muscular irritability by frequent convulsive fits, putrefaction takes place owly; but if muscular irritability is destroyed before death, it speedily upervenes, and runs through its stages rapidly. As a general rule, putre-

faction is not set up in a body so long as cadaveric rigidity remains in the muscles. When this condition comes on late, and lasts for a long time, it is slow in appearing, whatever may be the nature of the poison: under opposite conditions putrefaction takes place rapidly, provided the circumstances are favourable. In a death from nicotine, in which all muscular irritability appeared to be destroyed, putrefaction commenced early, and in a few hours had made great progress. The body was bloated, and the skin tense and much discoloured.

Some poisons, by chemically combining with animal matter, appear to confer on it the power of resisting putrefaction, at least to a very great degree. This is now a well-known property of arsenic, and in the arts this poison is largely employed as an antiseptic. When a solution of it is injected into the arteries of a dead body, it tends to preserve it for a long time from putrefaction. In examining the bodies of persons poisoned by arsenic, after an interment of six, twelve, and twenty-four months, the author found the stomach and bowels remarkably preserved, and the liver, spleen, and heart also preserved, but in a less perfect manner. The preservative effects are occasionally such that I have seen the pathological changes in the mucous membrane well marked after the body had been nearly two years in the grave. At the same time, it must be admitted that this preservative property is not manifested in all cases; hence we must not fall into the error of affirming that the person has not died from the effects of arsenic because the viscera are much putrefied. The greater part of the poison may have been expelled before death, or only a small dose may have been given to the deceased. These facts respecting the action of arsenic are now so well known to lawyers and medical men that they are seldom disputed. Nevertheless in a trial for murder (Lewes Sum. Ass., 1849, *Reg.* v. *Geering*), an attempt was made to refer the non-occurrence of putrefaction, in a case of poisoning by arsenic, to another cause. The deceased, Richard Geering, died on Sept. 13, 1848, and his body was exhumed Ap. 27, 1849, after an interment of rather more than seven months. When the coffin was opened, the face and upper parts of the body were much decomposed. The viscera were in a remarkable state of preservation. The substance of the heart was quite firm. Arsenic was found in well-marked quantity in all these parts. In the defence, a village undertaker was called to prove that, in burying the body, he had placed a slab of wood immediately above the coffin in order to keep the earth from it. An attempt was thus made to account for the preservation of the body irrespective of the action of arsenic. But this hypothesis was inadmissible. A slab of wood could scarcely affect the ordinary course of putrefaction in a grave; and if it did, it would influence it in all parts equally. In this instance those parts of the body only were preserved in which arsenic was found: the abdominal viscera, which are commonly the first to undergo putrefaction in its ordinary course, were here less changed than the other organs of the body ('Med. Gaz.,' vol. 45, p. 19). Zinc chloride, a powerful irritant poison, is another well-known preservative. It retards putrefaction apparently by combining with the tissues. In the case of *Ann Palmer* (*Reg.* v. *Palmer*, 1856), whose body was exhumed after twelve months' burial, all the organs were found preserved; they contained antimony, which had penetrated even to the ovaries and the substance of the uterus. In the case of *Harriet Lane* (1875), her murderer, *Wainwright*, attempted to destroy the body by the use of chloride of lime; but this substance acted as an antiseptic.

Accelerators of Putrefaction.—It has been alleged that there are certain chemical substances which have the property of accelerating the process of putrefaction; and among these *lime* has been particularly mentioned.

The mineral acids and alkalies, in a concentrated state, act powerfully as solvents of the soft structures of the body: but they destroy it by immediately corroding it, and not by producing any changes in it analogous to putrefaction. Persons who have been guilty of murder have endeavoured, but ineffectually, to destroy the dead human body rapidly; —sometimes by attempting to burn it, and at other times by the use of nitric acid, lime, or chloride of lime. The attempt has generally failed. Dr. Webster endeavoured to dispose of the dead body of Dr. Parkman by employing various chemical reagents, but without effect. In the case of the Mannings (*Reg.* v. *Manning and wife*, C. C. C. Oct., 1849), it came out in evidence, that the body of the deceased O'Connor was buried in a hole beneath the stone floor of a kitchen. The two prisoners, in order to destroy the body, poured over it a pint and a half of vitriol, and then covered it with fresh burnt lime, which was slaked upon it under the idea that this would rapidly destroy it; but the body was disinterred, and all the facts necessary to show that the deceased had been murdered, were clearly brought out. At the trial it was stated by one of the medical witnesses that lime would certainly cause a dead body to decompose more rapidly, that the features would be thereby much disfigured, and the brain reduced to a fluid state. This theory was set up in order to account for the apparently rapid putrefaction of the body, compared with the time that deceased had been missing; but this was sufficiently accounted for without resorting to this hypothesis, by the season of the year (August) and the superficial interment. The medical opinion here given regarding the effect of lime, was in accordance with a popular view which appears to be incorrect. Some years previously to the trial of the Mannings, the dead body of a child, placed in a box and covered with lime, was brought to the author for examination in reference to a charge of infanticide. Considering the period of death and the season of the year, the body was in a better state of preservation than might have been expected. The abdomen and lower extremities, which had been completely covered with powdered lime, were very well preserved. There was nothing to show that the lime had exercised any accelerating influence. On the contrary it had probably retarded putrefaction by keeping off air. A stiff cream of lime has no corrosive or caustic action on the skin or muscles; its chief use in the tanning of skins is not to corrode them, but to combine with and remove the fatty portions. Comparative experiments were performed with powdered lime partially slaked by exposure, on portions of raw flesh. The flesh acquired a greenish colour on the outside, but was speedily dried by the action of the lime and after five weeks it was found that putrefaction had become arrested, and the flesh was harder and firmer than a similar portion which had been exposed to air during the same period ('Med. Gaz.,' 1850, p. 20). John Davy, from the results of his experiments, has arrived at a similar conclusion. With the exception of cuticle, hair, and nail, which were softened by the action of wet lime, he found that this alkaline earth did not exercise any destructive or corrosive power on animal substances generally, or had any effect in promoting their decomposition. On the contrary, in the dry state, it exerted a preservative and decidedly antiseptic power, arresting putrefaction even after it had commenced ('Med. Gaz.,' Jan. 1850).

2. PUTREFACTION IN THE EARTH.—Exhumations are occasionally required for the purposes of justice, and it is under these circumstances that opportunities may occur for observing the progress of putrefaction in the dead. Unfortunately the results of these observations have hitherto led to no satisfactory conclusions; for sometimes one body has been found more

decomposed after six or eight months' burial, than another which has la interred for a period of eighteen months or two years.

From facts hitherto collected, especially from the researches made l Orfila, it would appear that the changes which take place are similar those described in speaking of putrefaction in air. There is in the fir instance a discolouration of the skin of the abdomen, owing to decomp sition taking place more readily in the contents of the viscera. The sk of the whole body becomes green, and the epidermis loose and eas detached by pressure or friction. The muscles also acquire a dark gre colour, become more or less pulpy, and in the course of time lose their fibro character. The lungs are distended with gases, and completely fill th cavity of the chest. The heart and liver are softened, and acquire a da slate colour. The same change is observed in the spleen and kidneys—the t around the latter organs being commonly white and firm. The whole of the organs will be found much reduced in size: thus the liver may weigh n more than a pound or twenty ounces. The surfaces of the soft organs especially of the liver, frequently present small circular patches of a ha white crystalline substance, which is insoluble in water. It consis chiefly of crystals of calcium phosphate with organic matter, and in son instances associated with triple ammonium and magnesium phosphate. Th author has found these crystalline deposits in bodies which have been e humed at periods varying from one to three years after interment. Whe the process is farther advanced, the soft organs are filled with vesicles c gas, and float on water. The stomach, intestines, and urinary bladder ha their mucous surfaces stained with patches of a brown, green, or dee slate colour. Sometimes these stains are are of a coaly blackness. Th coats of the stomach, if entire, may be closely adherent. They are ver thin, difficult to separate, and are frequently ruptured in the attempt t examine them. All the contents may have disappeared with the exceptio of a thin layer of a black substance, which is probably decomposed bloo The lining membrane is sometimes covered with deposits of small ha crystals of calcium phosphate, or ammonium and magnesium phosphat These must not be mistaken for crystals of white arsenic. The stomach an intestines may be stained of a deep orange or yellow colour with bile. Th may be identified by its forming a green-coloured solution when boiled i hydrochloric acid. The marks of irritant poisoning, and those path logical changes in the viscera, which are so characteristic of death fro poison, are now lost in the discolourations produced by putrefaction. A the process advances, the body becomes covered with fatty incrustations of reddish-brown colour, and the interstices are filled with the common blu white, or green mould, intermixed with another reddish-coloured fung The skin and soft parts become thin, fall off in places, and expose th bones. The coverings of the chest and abdomen are so collapsed as to l in contact with the anterior portion of the spine. The muscles are co siderably reduced in bulk; and they may be found in part converted in adipocere. The viscera are also much shrunk, collapsed, and often, if v except the stomach and duodenum, so intermixed, that it is not possible identify or separate them. The liver may in this way be found incorp rated with the lungs, owing to the destruction of the diaphragm; and th brain completely collapsed. In one exhumation, after four years' buri the whole of the soft parts of the chest and abdomen formed a soft whitis yellow mass disposed in condensed layers. It was impossible to distingui the stomach from the liver, intestines, or lungs. The periods of time ov which the author has had an opportunity of examining exhumed bodi have varied from one month to eight years. In the case of *Peter Maw* whose remains were exhumed at Boston in 1862, after eight years' burial

a damp grave, the body was in fragments, the soft parts loosely adhering to the bones, immersed in a large quantity of water in the coffin. The muscles, soft organs, and skin were converted into a white sodden mass, in which no organ or part could be identified. The mass had a fibrous structure: it contained oily matter, and had a very offensive odour like decayed cheese. The bones were of a dark colour: they could be drawn perfectly clean out of the soft parts. The water of the coffin contained ammonium phosphate and sulphate, with animal matter.

At this period the features are entirely destroyed, and the form of the skull and skeleton generally, is apparent. In a still more advanced stage, scarcely any traces of the soft organs are to be met with. The muscles, if not already changed as above described, pass into the condition of brown foliaceous masses. This is chiefly observed in those bodies which have been buried in a dry gravelly soil. The bones are disarticulated, the long bones giving the perfect outline of the skeleton, while the short and flat bones, including the bodies of the vertebræ with the base of the skull, are converted into a brownish-white pulverulent mass, mixed perhaps with the friable remains of the wooden coffin in which the body was buried.

It has been found impossible to assign any definite period of time to these changes, or, from an observation of them, to give any certain opinion respecting the length of time which a body has been interred. The reason is obvious: bodies undergo these changes with very different degrees of rapidity, even when they have been interred under similar circumstances. In one body, buried for a period of nine months, and in another for thirteen months, there were no traces of the coverings of the abdomen to be discovered; in a third, these coverings were found almost entire after a burial of twenty-three months; yet these three bodies had been wrapped in cloth of the same texture, and buried by the side of each other in coffins of the same kind of wood (Orfila). In the removal of the remains of about two thousand bodies from St. Andrew's churchyard for the Holborn Viaduct, some bodies were found well preserved. They were mummified, dry and like tanned leather. In one case, that of a man, the clothes were quite perfect; in another, that of a lady whose body had been buried considerably over a century, the lace on the grave-clothes was perfect and only slightly changed in colour.

It is commonly said that the soft parts are entirely destroyed in a period of from seven to ten years; but this must depend on the circumstances under which the body is buried, *i.e.*, the kind of coffin, the nature of the soil, and the depth of the grave. Devergie states, that in one instance he met with no trace of a shroud in a body which had been buried three years and a half, while in another a portion was discovered after seven years' interment. The author had an opportunity of examining a grave in which a body had been buried twenty-five years. Soft fragments of the coffin of a dark brown colour were found, but of the body only the skull (excepting the base) and some portions of the long bones remained. In an adjoining grave, nearly the entire skeleton was discovered lying at full length, surrounded by the decomposed coffin. This was after thirty-four years' burial, and the bones were nearly all perfect. He also found here traces of the shroud on the inside of what had been part of the coffin-plate, and the texture of linen was made evident by submitting it to the microscope. Unless the body has been buried in metal, or converted into adipocere, it is not probable that any of the soft parts will be found, in a soil favourable for decomposition, after ten or twelve years. They may exist as a sort of unctuous fat mixed with the wood and earthy matter, but they are not likely to be in a condition to admit of identification. Perhaps the usual period for the destruction of the soft parts in thin wooden coffins may be taken at about ten years.

In most instances of judicial exhumation the period of interment is well known, and no opinion is required of a medical witness on this matter. The only case on which he may be called upon to give an opinion is, where a skeleton or some bones have been discovered lying loosely in the soil. This part of the subject will be considered hereafter. Great embarrassment might exist in defining the period of interment in an unknown case, when a body has been buried in a coffin; but this does not, for obvious reasons, occur in practice. The bodies of those who have died by a violent death are commonly buried superficially in loose ground without a coffin; hence the data obtained by examining the progress of decomposition of bodies placed in coffins, even if they were more precise, could rarely be available for practical purposes. As the teeth, the bones, and the hair are among the most indestructible parts of the body, it will be necessary in an exhumation to look for any portions of these that may remain. They often throw light upon the age and sex of the individual, and serve to determine questions of identity.

The circumstances which modify the progress of putrefaction in the earth may be in some measure anticipated from what has been already said of this process in air. Among them may be enumerated the period during which the body may have been exposed to the atmosphere before interment, the nature of the soil in which it is buried, and the depth of the grave, with other circumstances, the precise influence of which it is difficult to estimate. There are a few special conditions which may affect the decomposition of bodies buried in the earth; and without a knowledge of them a witness may be led to express an erroneous opinion. The most important are—

Date of interment.—It is well ascertained that a body putrefies much more rapidly in air than in any other medium; hence, if it be kept long exposed before it is interred, putrefaction will take place much more readily, and advance to a much greater extent, than if it had been buried soon after death. If a body be kept exposed during the summer for five or six days, and then interred, it may be found on exhumation, after the lapse of a month, that putrefaction is as far advanced as it would have been after the lapse of several months, supposing that the subject had been interred within a few hours after death. Owing to this circumstance there is a difference in the rapidity of decomposition according to whether the bodies on which the observations have been made were interred after exposure to a hot and moist, or cold and dry atmosphere. It has been already stated that the period at which cadaveric rigidity of the muscular system ceases is that at which putrefaction may be considered to commence. Many circumstances have been pointed out, which retard or accelerate the access of this condition of the body. When cadaveric rigidity has been retarded by any of the circumstances mentioned, the putrefactive process will necessarily be a longer time in making its appearance. When the rigidity is a speedy consequence of dissolution, we may expect that putrefaction will take place rapidly.

Nature of the soil in which the interment takes place.—If the ground is elevated or on an acclivity, it will commonly be dry, and decomposition will be retarded: if a body is buried in a low situation, or in a valley, the soil being generally damp, decomposition will be hastened. A dry and absorbent soil retards putrefaction; and thus, bodies buried in the sands of Egypt, become often perfectly desiccated, and resist the process for a long series of years. The chemical nature of the soil, also, has an influence, which may be briefly stated. In sand, gravel, or chalk, putrefaction goes on more slowly than in other soils, and adipocere is rarely met with, unless there is free access of water, when that portion of the body exposed to the contact of water may become adipocerous. In marl or clay, if air has access, the

rocess takes place more quickly, especially in loose mould or in any porous oil much impregnated with animal or vegetable matter. It is in these last-entioned soils, provided they are not too dry, that the formation of dipocere is observed; and however great the rapidity with which putre-ction may have advanced previously, it is either suspended or modified on e occurrence of this change. By a reference to the nature of the soil, erefore, we may often explain why a body, after having been interred for considerable number of years, may be exhumed apparently unaltered by composition. The whole of the soft parts may have become converted to this white substance; but although the physical outline may be pre-rved, the texture of the organs will be completely changed.

Depth of the grave.—Observation shows that the deeper the grave, the ager putrefaction is retarded. This may depend upon several circum-nces: as the want of a free access of air in deep graves, and the uniformly w temperature which is known to prevail, at all seasons of the year, at a rtain depth below the surface of the soil. Bodies buried in shallow graves e subject to the fluctuations of temperature which take place during the y and night, and throughout the seasons of the year; they are therefore st favourably placed for the rapid progress of putrefaction. According the most accurate observations, the diurnal changes of temperature extend about three feet in depth below the surface, while the monthly changes e perceptible to the depth of six feet. Bodies buried below this depth trefy slowly, *cæteris paribus*, owing to the uniform and comparatively low mperature which is there maintained. As in these cases there is no free cess of oxygen, ammonia and sulphuretted hydrogen are abundant pro-cts of decomposition. The exposed parts of the skin are soft, completely rown like the skin of a mulatto, and the limbs, as well as the face, are ickly covered with a soft white fungus. Such has been the condition of odies of which the author has witnessed the exhumation, after an inter-ent of from one to two years.

The state in which the body is buried.—Putrefaction is more rapid in odies buried naked, than in those which have been buried wrapped in lothes. This point may be a subject requiring especial attention in inves-igations relative to infanticide, since the bodies of children are often hrown naked into a pit, and loosely covered with earth. The process is ss rapid when the body is interred in a close coffin: and when the latter s formed of an imperishable material, such as lead closely sealed, putrefac-ion is speedily arrested; and the deceased may be recognized after the lapse f many years. The reason why bodies are better preserved under these circumstances, is obviously owing to the access of air being cut off. Any confined mass of air, so soon as the whole of the oxygen contained within it is removed by combination, acts antiseptically, forming an atmo-phere of nitrogen which retards putrefaction, and thus the body may be reserved for a long period.

Formation of Adipocere. Saponification.—In the course of these observa-ions, there has been frequent occasion to speak of the dead body becoming ometimes converted into adipocere: it will be therefore proper to explain hat is meant by this process of conversion.

The substance called *adipocere* was first observed and described by Four-roy during the removal of vast numbers of bodies from the Cimetière des nocens in Paris. He gave to it this name, owing to its properties being ntermediate between those of wax and fat. He considered it to be consti-uted of fatty matter and ammonia. From an analysis by Chevreul, the ubstance described by Fourcroy was proved to be a real ammoniacal soap ith some extraneous colouring matter, which gave it a yellowish or brown

colour. It contained, besides, an undefined bitter substance, and an odoriferous principle, to which it owed its smell. Chevreul also detected in some specimens compounds of calcium, potassium, and other salts. The composition of adipocere does not appear to be uniform: it is liable to vary according to the nature of the medium to which the body has been exposed. Thus, in hard or river water, the white substance so called, discovered in the dead body, is formed with a calcium base; so, in bodies laid in graves or vaults which are traversed by springs of water containing calcium sulphate or carbonate, an adipocere of calcium stearate and oleate is found as a hard white solid. It is not improbable, as Orfila has suggested, that in the first instance an ammoniacal soap is produced, and that this is subsequently converted into a calcareous soap by contact with calcareous water. Indeed, Orfila states that he experimentally established this point, by placing ammoniacal soap in maceration in a solution of calcium sulphate. In three weeks, he found that a calcareous had been substituted for the ammoniacal base.

Any part of the human body may undergo this change, but all parts are not equally susceptible of it. In order that the adipocere described by Fourcroy should be found, it is indispensable that the animal fat should be in contact with substances containing nitrogen. Experiment has clearly established that neither pure fat, nor pure fibrin, when kept apart, will become thus saponified. Orfila found by comparative experiments, that the skin deprived of all fat did not undergo this change; but when the fat was allowed to adhere to it, it became saponified. Upon the knowledge of these facts, the following theory of the production of adipocere was founded. The fat containing no nitrogen, could not furnish ammonia; consequently it could not spontaneously change into this substance. The fibrin of the muscular system was therefore supposed to produce ammonia, by giving off hydrogen and nitrogen; and this alkali combined with the fatty acids of the body to form a soap (see 'Ure's Dictionary,' art. Adipocere). Devergie has shown, that the fat of the female breasts, that of the hollow of the cheeks, and other large fatty accumulations, are the first to take on this change, while the fatty layers immediately in contact with the muscles, present no appearance of saponification, until a considerably later period. We have observed this change in a body after interment for a year, in the fat of the kidneys and omentum, as well as in the fatty appendages of the large intestines. As the fat of the body is contained in a cellular membrane (a nitrogenous compound), and is traversed by the blood and other nitrogenous fluids, the nitrogen is as readily furnished by these, as by the fibrin of the muscles. So, again, the skin and fat, separated from the muscles, will become converted into adipocere. The fibrin of muscles, therefore, although unquestionably it may be one source of the ammonia, is not the sole source. Oil or fat exists throughout the soft organs and tissues of the whole body; hence every part may undergo this transformation. When the change is complete, the body maintains its condition for many years. Thus, in one instance, after seventeen years' burial in a grave, an exhumed body was found to be converted into this substance, and many of the organs could still be identified ('Phil. Med. Exam.' April 1847, p. 247).

This process takes place most readily—1. In the bodies of young persons, the fat being chiefly external and very abundant. 2. In those adults whose bodies abound in fat. 3. In bodies exposed to the soil of water-closets. 4. In those immersed in water, but somewhat less rapidly in stagnant than in running water. 5. Readily in humid soils, especially in graveyards, where numerous bodies have been piled in contact with each other. In this latter case, those which are situated at the lowest level have been observed to become the soonest saponified. The period required for saponification to

take place varies according to circumstances. Devergie states that the body of a new-born child in the soil of water-closets may become entirely saponified in from six weeks to two months; while in a drowned subject in water, saponification may be partially met with in three or four months; and in one buried in a damp grave, from two to three years may sometimes elapse before saponification is complete. There is no doubt, however, that the process may take place partially in the dead body, within much shorter periods than these. A body floating in water has been found converted into this adipocerous state in a little more than five weeks; and with regard to the period in an ordinary grave, the case of a female may be referred to, exhumed at Bristol, in 1835, after fourteen months' interment. The lower part of the body was here found adipocerous. It appears that the grave was very damp, and the line of adipocerous transformation in the deceased was bounded by the level to which the water had reached. These facts are of more importance than may at first sight appear, once a legal question of survivorship, in at least two cases, has turned upon the shortest period required for the production of true adipocere in the dead body.

Properties of Adipocere.—Fourcroy and other chemists have described adipocere as an unctuous, soapy substance, varying in colour from a pale white to various shades of yellow or brown. In the first instance it is soft, but becomes harder and lighter in colour when dried. It melts at 200° F., and when strongly heated in air gives off an ammoniacal odour, takes fire, and burns. It is easily suspended in cold water, and forms an opaque mixture on boiling. Acids decompose the solution by combining with the base, forming salts. When heated with lime, ammonia is evolved. It is only partly dissolved by boiling alcohol. Adipocere with a calcareous base is harder and whiter than that with an ammoniacal base. There is no trace of organized structure in either.

The author having had an opportunity of examining this substance as it is found in bodies after long interment in damp graves, a description of its properties is here subjoined. A man named *Peter Mawer* died and was buried at Boston in Oct., 1854, and his body was exhumed for judicial purposes in June, 1862. The condition in which it was found after an interment of eight years has been already described (p. 103). The white substance into which all the organs had been completely transformed was unctuous to the touch, and had a peculiar and highly-offensive odour. When completely dried it was soft, white, somewhat brittle, with a fibrous structure, and crumbled under the knife. Examined by the microscope, it presented none of the usual characters of muscular fibre. It appeared to be a confused network of fibres cemented by a white, fatty-looking substance. It had a disagreeable rancid odour, which was increased when the substance was heated. It was in great part dissolved by alcohol, and the solution became opaque on adding to it water. It readily floated on water, forming an opaque solution when boiled; the greater part was dissolved, but the liquid did not become clear on filtration. The solution had a slightly acid reaction to litmus paper. When heated with potash, it became clear, and evolved ammonia. The substance was almost entirely soluble in potash, and the solution gave a white precipitate with acids. The potash solution gave no trace of the presence of sulphur. It formed a red-coloured liquid when boiled in strong hydrochloric acid. It was carbonized by sulphuric acid. The aqueous solution contained no calcium, sulphate or phosphate: it contained an abundance of alkaline chloride with animal matter which produced silver nitrate. It was only partially fused at 212° F. When heated in a close tube, it gave out an offensive rancid odour, evolving ammonia and traces of sulphur compounds; it readily melted, and by con-

tinuing the heat, a dense oily vapour having an acid reaction distilled ov —a carbonaceous residue being left in the tube. When heated on platinu it melted, took fire, and burnt with the bright yellow flame of a hyd carbon. It left an ash of a brownish colour owing to the presence ferric oxide; this residue amounted to five per cent. of its weight. T residue was in great part soluble in water, the solution having a stro alkaline reaction and effervescing with acids. It contained potassium a sodium carbonates, with calcium phosphate and sodium chloride, as w as traces of alkaline sulphate and ferric oxide. Adipocere, therefo does not appear to be a definite compound. It is a variable mixture the fatty portions of the body with altered organic tissues. It conta in a concentrated form, besides ammonia as a result of decompositi the bases as well as the salts which are found in the animal solids a fluids. These appear to be intimately combined with the fatty portio of the tissues.

Casper has laid down certain data as signs of death, which may here summarized, and these also serve to determine the period which h elapsed since death, due allowances being made for the modifying circu stances of temperature, &c. The following is a summary of his co clusions:—

1. Respiration and circulation have ceased, and not even the faint murmur is heard on auscultation. The eye loses its lustre, and has peculiar dull listless stare; the pupil is inactive to light. No stimulus h any power of producing a reaction. The whole body is ashy white. T animal heat is more or less lost. The muscular system is relaxed. A bo which only presents those signs of death may be regarded as that of person dead from ten to twelve hours at the longest.

2. The eyeball has lost it vital turgidity, and is soft or inelasti There is flattening of the muscles of those parts of the body on which lies. External hypostases, resulting from the gravitation of the blood i the capillaries, form and increase in size. They usually form in fro eight to twelve hours, and are internal as well as external. Cadave rigidity has set in. A body which only presents these four signs of dea in addition to, or in supercession of those previously detailed, may presumed to be that of a person who has died within from two to thr days at the longest.

3. When bodies are green from putridity, blown up and excoriated, t period of death cannot be fixed with even approximate certainty; and the expiry of one month, or from three to five months after death, *cæte paribus*, cannot with any certainty be distinguished from one another.

This subject will be again referred to in the next chapter.

CHAPTER 7.

ICE OF THE PERIOD OF DEATH IN A BODY AFTER PUTREFACTION—IN-NCES OF RAPID DECOMPOSITION OF THE BODY—PROBABLE CAUSES—ERMINATION OF THE TIME OF DEATH—PUTREFACTION SUSPENDED: CASE OF HA—PUTREFACTION ACCELERATED—CASES OF MRS. BYRNE AND JOSEPH AIG—MARKS ON THE SKIN—PROTRUSION OF THE EYE AND TONGUE AS ESULT OF PUTREFACTION OR STRANGULATION—PUTREFACTION IN WATER ERIOD OF IMMERSION IN WATER.

ce of the period of death in reference to a body after Putrefaction.—after having devoted many years to the investigation of this subject, ter the comparative examination of some hundreds of exhumed of all ages, and of both sexes, came to the conclusion, that it was the reach of science to determine with accuracy the period of death, ıe progress of putrefaction. Bodies which had been buried for an ength of time in the same soil under apparently similar conditions, ıtly presented such differences as to baffle all attempts at generaliza- This question becomes even more difficult, when the body is sub- to examination, and none of the conditions under which the person d, or to which the body has been exposed after death, are known. be perceived from what has been already stated, that the circum- which affect the rate and progress of putrefaction, are numerous a variable character. If we can obtain no history of the case, a l opinion can be little more than a conjecture; if, however, we are ed of the atmospheric and other conditions to which a dead body ın exposed, it may then be in our power to arrive at a probable, if definite conclusion. In the description of the modifying conditions given, the practitioner will find some points which may render him ıce, or, at any rate, enable him to avoid some of the serious errors have been made by medical witnesses in reference to this subject. been elsewhere stated, that putrefaction does not commonly com- until about the third day after death, at any rate there is usually ernal sign of the process until that date; but there are many in- known of its commencing almost immediately after death, and ling with great rapidity, while, in other cases, more than twenty ıve passed without any indication of its presence. (See p. 108, *ante*.) experience of Wilks, who inspected more than four thousand odies, may be here briefly referred to. At Guy's Hospital, most re inspected within twenty-four hours after death, when, as a rule, ly is rigid and no decomposition has taken place. If after two or ays much change should be present, it is generally to be attributed peculiarity in the cause of death. The decomposition is not shown, still later period, by a mere change of colour, as a greenish hue of lomen, but by a redness of the whole body, and by dark stains in of the superficial veins. Even when these external changes are observable, there may be found considerable alterations within the hown more especially in a discolouration of the heart and arteries blood. These changes appear to be connected with a diseased state blood, and are met with in those who have died of fever, pyæmia, nilar maladies. In those cases of strangulated hernia, in which peedily follows an operation, the post-mortem changes are some- bserved to be very rapid. It is a common observation, that moisture ıtmosphere appears to favour decomposition much more than heat:

thus putridity is much more rapid on a moist winter's day than on a hot dry day in summer. These facts may be illustrated by cases from the records.

In Sept. 1855, the body of a man was examined thirty-eight hours after death from an accident: it had begun to undergo decomposition in the ordinary manner. The body of another man, who had died of phthisis, was examined forty-four hours after death, and in this there was no trace of decomposition. On the following day an inspection was made of the body of a man who had died in a few hours after fracture of the ribs. Only forty-eight hours had elapsed since death, but considerable decomposition had already taken place.

Sometimes decomposition is so rapid that in a few hours the features of a person are unrecognizable. A man, æt. 26, died in Nov. 1855, of typhoid fever and perforation of the ileum. The weather was cold and moist. When the examination was about to be made sixteen hours after death, the body was wholly unlike that of the man when alive. There was no rigidity; the whole body was bloated; the cellular tissue was greatly distended, so that when the skin was pierced the gas which escaped was easily ignited. The colour of the surface was of a reddish hue. The internal organs were also much decomposed; of a dark colour, soft, and emitted a very fœtid odour. The liver was full of air. The patient was a temperate man, and had resided in the country.

In Nov. 1864, a plethoric man met with an accident, and died at 10 o'clock P.M. Mr. Clegg held an inquest on the body the next morning at 11 A.M. Although only thirteen hours had elapsed since death, the body was highly putrefied, presenting a bloated appearance, and the face was so swollen and discoloured that the features could not be recognized. The gases which escaped were so offensive that the jury could not approach the body. No inspection was made.

A man, æt. 35, shot himself with a pistol, producing fracture of the skull and injury to the brain, from which he died in six days. On Dec. 13th, 1854, the atmosphere being cold but moist, the body was brought into the room for examination, thirteen hours after death. The rigidity was imperfect, but still present to a slight degree; the body was warm; when opened, it showed that a remarkable change had taken place internally, so that it was even suggested whether decomposition had not commenced before death. The brain was soft and decomposed; the lungs showed recent inflammation and the air-tubes were deeply stained by imbibition; the interior of the heart and arteries was of a dark purple colour, and the clots in the heart were mixed with air; the peritoneum was discoloured; the liver presented a remarkable appearance, it was full of air, and thus resembled a mass of fermenting dough; on the surface were bubbles of air ready to burst: this organ contained two small pyæmic abscesses. The spleen was of a greenish colour; the kidneys closely resembled the liver, being like it distended from decomposition, and containing air-bubbles throughout their substance. (See 'Guy's Hosp. Rep.' 1863, p. 181.)

In addition to these cases, Wilks met with another, in which a man, æt. 50, died from an accident in Dec. 1860. He lost much venous blood, and, without showing any sign of rallying from the accident, he died on the fourth day after his admission. For a few hours before death he suffered from great difficulty of breathing, and his pulse was not perceptible. The man died at 6 P.M., and in an hour or two his body was carried to the dead-house. The weather was frosty, and there was a hard frost during the night that the body lay in the dead-house. On the following day (only twenty hours after death), putrefaction had advanced

o such a degree, that the deceased could scarcely be recognized. The kin was throughout distended by the gases of putrefaction. All the iscera were decomposed, the liver contained putrescent gases, and even he coats of the gall-bladder were distended with them. This was a case f rapid death, probably from blood-poisoning.

The following is a remarkable instance of the rapidity with which utrefaction may take place in a dead body. A man, æt. 39, was admitted nto Guy's Hospital in Oct. 1849. He was fat, of pale complexion, and of ntemperate habits. The muscles were flabby. He died suddenly after a few days, without suffering from any symptoms indicative of danger. His death took place at 10.30 P.M., the body remained in the ward until 3 A.M. the following morning, the air having a temperature of from 60° to 35° F. The conditions as to cooling and rigidity were not observed during he night; but when removed at the hour mentioned, decomposition had lready commenced. The skin on the left side was raised in large vesicles, ontaining a bloody liquid. At 2.30 P.M. *i.e. sixteen* hours after death, the ntire skin was more or less of a blue or purple colour; the eyes protruded rom the sockets, and the nostrils were filled with a bloody froth, from hich minute bubbles of gas continually issued. The abdomen, as well s the scrotum, was greatly distended with gas. The groins were much putrefied and were covered with minute blood-vesicles. *Seventeen hours* fter death the skin of the neck and face had a bloated and tense appearance from the collection of gas beneath. Blue, green, and livid red iscolourations were seen more or less over the whole surface, with vesicles s in the advanced putrefaction of bodies after some days' exposure in hot eather. The gases which issued in jets from every part of the skin in hich a puncture was made, were highly offensive. When a flame was pplied to the puncture, the gas took fire with almost explosive violence. The gas did not discolour slips of paper moistened with lead acetate or itrate of silver: hence neither sulphuretted nor phosphuretted hydrogen was present. It burnt like marsh gas; and was probably this gas, ixed with other gases and vapours derived from putrefaction. When he tense skin of the scrotum was punctured, a jet of carburetted hydrogen escaped, which burnt steadily, with a pale yellowish flame, for bove a minute. The state of the body precluded a post-mortem examination, which was considered unnecessary ('Med. Gaz.' 1850, vol. 45, p. 17).

The condition of this body in reference to the process of putrefaction was such as Devergie assigns to dead bodies at a period of six to twelve days after death, on the assumption that they have been freely exposed to the air, at a mean temperature ('Med. Leg.' vol. 2, p. 406). Had the body of this person been found in a house under these circumstances, and had the history of the case been entirely unknown, a medical man, asked to assign a period of death, from common experience in such matters, might have declared it to be impossible that the deceased could have been living within twenty-four hours previously to the discovery. Suspicion might thus be removed from persons really guilty of murder, because it might be proved that they had not been in or near the house until within a day of the discovery of the body. On the other hand, an innocent person who had been seen in company with the deceased five or six days previously, or who had voluntarily remained in the same room with the body, might be unjustly charged with having been accessory to his death. This, with other instances of a similar kind, shows that unusual caution is required in expressing a medical opinion on the time at which death took place, in bodies which are found much decomposed.

The causes of this rapid access and progress of putrefaction in the

body of a man dying in the prime of life, cannot be assigned to the season of the year, or to the operation of any unusual external influences. It may have been due to the condition of the body, especially of the blood, at the time of death. This man was of intemperate habits, with a flabby muscular system, and low vital energy. These were precisely the conditions favourable to the speedy loss of muscular irritability after death, with the appearance and disappearance of cadaveric rigidity after an unusually short duration. The fourth or putrefactive stage was therefore reached in a few hours. The ward-temperature, 65° F., was favourable to the process, and the blood and other fluids were probably prone to decomposition. Although the body was removed into a cooler atmosphere on the morning following death, yet the process having once commenced, progressed with great rapidity.

Marsh described a case of a somewhat similar kind. A man who had been ill about fourteen days, was admitted into the Hotel Dieu at Paris, under Bally. He died on the night after his admission; and on examination only *eight hours* afterwards, his body presented the following appearances:—The whole of the skin was distended with air; it was of a violet colour, and studded with a vesicular eruption in detached spots, the vesicles being filled, some with a reddish-coloured serum, and others with gas. The abdomen was also much distended by gas, this having accumulated not in the intestines, but in the cavity of the peritoneum. Upon cutting into any emphysematous part, an inflammable gas escaped which was readily ignited by the flame of a candle. From a perforation in the abdomen it issued and burnt with a blueish flame ('Ed. Med. Journ.' vol. 58, p. 501.) It was thought this state of the body indicated putrefaction before death; but it was merely an instance of its rapid supervention after death.

The experiments and observations of Brown-Séquard, already referred to, tend to explain many of the supposed anomalies which present themselves in the commencement, progress, and duration of the process of putrefaction. The various physical and physiological conditions which affect muscular irritability, and, with this, cadaveric rigidity in a dead body equally influence the process. The time for its commencement in a dead body is defined by the cessation of cadaveric rigidity, and this condition again has its commencement defined by the loss of muscular irritability. Some experiments on dogs, elsewhere related (page 59), show that when rigidity appears and disappears shortly after death, putrefaction is speedily manifested in a body, and it progresses with great rapidity. It has been long known that the flesh of hunted or over-driven animals rapidly undergoes putrefaction. Brown-Séquard saw two sheep that had been overdriven to reach a fair. They were killed by the section of the carotid arteries. In less than five minutes after death rigidity was evident in both of them; and putrefaction was manifest before the end of the day, *i.e.* in less than eight hours after death ('Proc. Roy. Soc.' 1861, p. 210). Whatever exhausts muscular power at the time of death, whether it be violent exercise, disease, or poison, tends *cæteris paribus* to accelerate putrefaction, and to cause it to spread rapidly. Thus among persons killed by lightning or by strychnine, the body of one may putrefy rapidly, while that of another goes through the ordinary course. It is not due so much to the effect of the agent as it is to the mode in which it has destroyed life.

There is great difficulty in the practical application of these principles to the determination of the probable period of death, in reference to the body of a person found dead. Medical opinions are frequently required in cases of alleged child-murder on the probable date of death of a child, whose body has been found in a putrefied state. With a due regard to the con-

der which the body has been placed, a medical witness may
y be able to say whether its state was such as to be consistent or
ıt with the delivery of an accused woman at a particular period

: difficulties occur on charges of murder in reference to the bodies
ound dead under suspicious circumstances. The connection of
l person with the act may occasionally turn upon a medical
specting the state of the dead body. Beck furnishes a case
› of this statement. A man named *Desha* was charged with the
Francis Baker. The deceased was last seen with the prisoner
ıd, 1824. The body of the deceased was found on Nov. 8th, *i.e.*
terwards, in a sheltered hollow, with the throat cut, with several
. the head, and a wound on the chest. There was no doubt from
of the wounds that the deceased had been murdered, and that
ıve died soon after their infliction. The defence of the prisoner
a great extent on the condition of the body when found, the
ıuestion being, whether the state of the body was consistent
uggestion of violent death caused *six days* previously. When
, it had undergone so little change that it was considered de-
st have been alive some days after the prisoner had been last
› company. The body when first found, is described as having
le stiff; but after carrying it some distance it became pliant.
no appearance of putrefaction about it, either by the smell or by
e of colour in the skin. In two days after its discovery, during
iod it had been placed in a room in which there was a fire,
ɔn set in, and the abdomen and face became much swollen and
d. At this time, *i.e.* the eighth day after the deceased had been
, much blood issued from the wounds; according to one medical
e wounds at this date appeared fresh, according to another they
There was some conflicting evidence, lay and professional, on the
whether putrefaction could be so completely suspended during
› as it had been in this instance. The counsel for the prisoner
ı the absence of the process as a proof that death must have been
d therefore that the prisoner could have had no share in it. The
› inclined to this view. In addressing the jury he said, 'It is
› suppose that a body, at this or any season of the year, could
ıined that long without exhibiting some symptoms of putrescence:
so that in two or three days after it was found, it did show such
as in that time might naturally be expected.' Another singular
ed in the prisoner's favour, was that the beard had grown after
very of the body, and it was quite short when it was first seen,
he appearance of having been recently shaven; but in the interval
y and Thursday, after its discovery, it had become a little longer.
ontended that the beard will grow after death; and as, when the
found, the chin was cleanly shaven, this pointed to recent and
note death, as the beard would have already become elongated
body was found, had the deceased been dead six days. The
itnesses, in reference to this theory, stated that the appearance
after death was to be ascribed to a shrinking of the skin. The
rned a verdict of guilty. The prisoner subsequently destroyed
nd, while dying from his wounds, protested his innocence of this
'Beck's Med. Jur.' vol. 2, p. 45.) This case does not appear to
ıch difficulty. The fact that the body of the deceased remained
ı a sheltered spot during the month of November, without under-
' of the usual changes from putrefaction, is consistent with death
›reviously. When found, the body had reached the third stage

described by Devergie: it was cold and pliant, or readily became so had passed through the stage of cadaveric rigidity. According to the servations of Devergie, a dead body, *cæteris paribus* would assume condition in from three to eight days after death. The fact that pu faction came on in two or three days after its discovery, is fully explai by the cessation of cadaveric rigidity and the high temperature to wl the body was then exposed. The state of the beard did not justify inference that death had been more recent. Neither the age nor the dition of the deceased's body is stated, but it is clear that he died sudd from loss of blood, as well as other injuries. It may be inferred, theref that his muscular system was endowed with the ordinary amount irritability. In cases of healthy persons suddenly killed by decapitati Brown-Séquard observed that cadaveric rigidity did not appear until or twelve hours after death, and that it lasted more than a week when weather was not extremely warm. The retardation of putrefaction in above case may have been due to a similar cause.

The medical difficulty in the case of Desha arose chiefly from the s pension of the putrefactive process beyond the average period. Ot cases have occurred, in which the rapid access of putrefaction follow sudden death has implicated persons in charges of murder, and they h narrowly escaped conviction, apparently because the changes produced putrefaction had been mistaken for the effects of violence. In 18 *Ellen Byrne* was tried at the Commission Court, Dublin, for the murde her husband, by strangulation, suffocation, or other violence ("' Trial of Mrs. Ellen Byrne, for the Murder of Mr. Augustine By specially reported by T. R. Dunckley,' Dublin, 1842). The priso and deceased, who were in a respectable condition of life, were in habit of drinking to excess. On this occasion they had retired to th bedroom, and about four days after the deceased had been last seen ali and eight days after they had been in the room, the body of the husba was found dead on the bed, while the wife was in the room. She p fessed not to know that her husband was dead, and sent for a medical m From his evidence, it appeared that when he first saw the body on t evening of July 9th, it was so much decomposed, that he was led believe the deceased had been dead at least four or five days. The f and neck were black, and decomposition had gone on to such a degree these parts, as to obliterate, it was believed, any marks of violence t might have been there at the time of death. The right eye was protru —the tongue projected between the teeth to about half an inch: the e were black, the lips were swollen, and the fingers were contracted. Th was a frothy liquid issuing from the mouth and nostrils in bubbles, a living maggots were seen in these parts. The whole of the body was gre swollen, discoloured, and passing rapidly into a state of decompositi When first seen, deceased was lying on his face. There was a faint, he smell in the room. An inspection made the next day revealed the fact th putrefaction had taken place in all parts: but the head and neck w most decomposed—the black colour of the skin appeared to decline a got down to the lower part of the neck. Internally, the heart was emp and the vessels of the brain were perfectly empty: the blood was flu Fæculent matter had been discharged from the bowels before death.

There were two medical questions in this case, on which the guilt the prisoner rested: 1. When did the deceased die? and, 2. Was de to be ascribed to violent or natural causes? On July 1st, eight days bef his body was found, deceased had retired to his bedroom with his wi and during that time a large quantity of spirits had been taken to t room and consumed by him, by his wife, or by both together. On the 3

e voice of deceased was heard, as if he and his wife were quarrelling. n the 4th they were not seen: on the 5th, a man-servant deposed that e was called upstairs by the deceased, who spoke to him, and gave him alf-a-crown to fetch whisky. He then heard deceased's voice, and saw is bare arm through the partly-opened door; but from the position in hich he was placed, he could not see the whole of deceased's body. After his date, deceased was neither seen nor heard—he was found dead on he evening of July 9th, his body being then in the highly-decomposed tate above described. On July 6th, prisoner left the bedroom for a short ime, and closed the door. On the 7th and 8th, she was seen at the door f the bedroom by the man-servant, and on the latter day by her maid-ervant, and she was then quite sober, and spoke to them as usual. On he 9th, at ten o'clock in the morning, she ordered the servant to bring p *two* cups of tea. Between six and eight o'clock on the evening of that ay, she suddenly called to one of her sons, to turn the deceased on his ack. On entering the bedroom, he found deceased dead, and his body as bove described. As the prisoner had been in the bedroom alone with the eceased, either living or dead, from July 5th when he was last seen, ntil the 9th, she must, it was alleged, have been cognizant of his death, f it had not been directly caused by some act on her part. The prisoner ade two statements: first, that she slept in the bed on the 7th and 8th, nd that deceased died on the 8th. She subsequently stated that he died n the 9th, the day on which the body was discovered.

From the state of decomposition of the body, two of the medical witnesses or the prosecution assigned a period of at least four or five days, during hich deceased must have been dead. Two declined to give an opinion s to the number of days, but Geoghegan stated his belief that such hanges might take place in from twenty-eight to thirty hours. A edical witness called for the defence deposed that he had seen a body s much decomposed twenty-four hours after death. On referring to cases lsewhere related, it will be perceived that the shorter period assigned by hese two witnesses, one for the prosecution and the other for the defence, s quite within the limits assigned by experience, although instances of such apid putrefaction are not common. In this case, however, it must be emembered that the dead body was shut up in a close room, at the hottest eriod of the year, and the circumstances were therefore most favourable o the process. Admitting that this was an exceptional instance of rapid decomposition, the changes described by the witnesses might have occurred within twenty hours of the time at which the body was discovered, thus arrying the death to the night of the 8th, at the time when prisoner was, ccording to her statement, in bed with the deceased.

The other question, as to the cause of death, gave rise to a conflict of pinion. On the one hand, it was alleged that the appearances in the ody, *i.e.* the black and decomposed condition of the head and neck, ompared with other parts, the protrusion of one eye from its socket, and he projection of the tongue between the lips, as well as the absence of ny natural cause of death, were medical proofs that deceased had died y strangulation and not by any disease or accident. On the other hand t was asserted that the deceased might have been accidentally suffocated hile helplessly intoxicated, by falling with his mouth on the pillow, that he might have been carried off by a sudden attack of apoplexy epilepsy. The discolouration of the face, the protrusion of the eye and ngue, and the discharge of fæces, might be accounted for by his dying uring a convulsive struggle; while the two supposed indications of rangling afforded by the eye and tongue, might be simply the result the advanced state of decomposition in which the body was found. All

the witnesses were agreed, that there were no marks on the indicate death by strangulation; but this want of physical evid accounted for by some of them, on the theory that all such mar be completely obliterated by putrefaction. The heart contained and the vessels of the brain were empty, the blood in the body and dark-coloured. The state of the lungs is not mentioned, condition of the larynx and air-passages, so that it is left whether any mechanical cause of obstruction existed in these par emptiness of the heart, which was adverse to the theory of strangulation (asphyxia), was referred to the mechanical effect o putrefaction on the organ. The emptiness of the brain was le plained. It was inferred by most of the witnesses for the pro that the marks of manual strangulation on the neck externally, usual appearances of asphyxia internally, had existed at the time and that these appearances had been destroyed by putrefaction who adopted this view, contended that the protruded eye and ton conditions which had resulted from strangulation alone, and t could not be produced or removed by rapid putrefaction.

The alleged guilt of the prisoner rested chiefly on these two poi facts showed, even allowing no more than twenty hours to hav between death and the discovery of the body, the prisoner must h cognizant of the death; and, unless hopelessly insensible from drin appears to have been disproved by the evidence, she would, it was su if innocent, have given an alarm. She ultimately called to her so reason can be assigned why she did not call for assistance earlier. impossible to assume that she was speculating on the rapid decon of the body, and watching for the stage when marks of violen be obliterated. No motive could be assigned for the murder, no remaining shut up in the same room with her husband, as it was for four or five days. Under these circumstances, with the a by some of the scientific witnesses, that the protrusion of the tongue might have been caused by putrefaction, the jury ret verdict of not guilty. There was nothing to exclude the supposi the deceased might have died in an epileptic fit, as a result of drinking. In any case, it was obvious that the body had undergo putrefaction. The greater decomposition observed in the head a might have arisen from the congestion of blood in the superficial As other causes beside manual violence may produce congestion head and neck, the blackening of these parts in a highly-decompo furnished no medical evidence of homicide. The protrusion of and tongue did not strengthen the theory of strangulation, sinc properly admitted by some of the medical witnesses that these c were consistent with the effects of putrefaction in an advance There was, therefore, no medical evidence to show that decea died by violence; and, instead of drawing the inference that such had existed and had been destroyed by putrefaction, it would h safer to have said that the highly decomposed state of the b vented any correct medical opinion from being formed. No opini the length of affirming that death was necessarily produced by and the jury were informed by the judge that they were not to the prisoner on probability, however strong, or on a mere prepo of medical opinion.

The medical evidence at this trial raised the question wh protrusion of the eye and tongue in a highly-decomposed stat head and neck should or should not be regarded as an absolute homicidal violence applied to the neck. One of the scientific w

affirmed that these states could not result from putrefaction. Another deposed that they might result from gaseous decomposition taking place in the orbit; the gases thus confined would cause a projection of the eye and its coverings, while, in reference to the tongue, the effect might be aided by the face being inclined downwards, and the mouth being partly open. The fact that only *one* eye was protruded is less reconcilable with the effect of mechanical pressure on the neck than with the theory that decomposition took place from effusion of blood or other causes more in one orbit than in the other. With regard to the tongue, whatever causes congestion of the head and neck, is likely to cause congestion of this organ; and putrefaction, by the production of gas in its substance, may lead to its enlargement and protrusion.

It is strange that the protrusion of the eye as a result of putrefaction should have been doubted and even denied, by some of the witnesses at this trial. So conflicting was the evidence regarding this appearance, that Geoghegan made it a subject of experiment on the dead body of a child, and he observed that the eyes protruded, as a result of decomposition, on the eighth day; they began to present the appearance of protrusion on the fourth day. A case of rapid putrefaction, in which both eyes protruded as early as sixteen hours after death is reported ('Med. Gaz.,' Jan. 1850, p. 17). The time at which such an appearance may present itself after death, must obviously depend on the period at which gaseous putrefaction takes place in the orbits. Although, in the dead, the eyes are usually collapsed owing to transudation of the fluids, yet it has been pointed out by Orfila, that the lids may bulge forwards and the eyes protrude, from the production of gases within the cranium and orbits.

In Dec. 1863 a trial took place, involving questions almost identical with those which arose at the trial of Mrs. Byrne (*Reg.* v. *Mahaig*, Kingston Wint. Ass., 1863). On this occasion the body of a woman was found dead in a room in an advanced state of putrefaction. The deceased and her lover, a soldier, had retired to a bedroom some days before, and had kept themselves there secluded: the soldier was found with his throat severely cut. This man was charged with the murder of the deceased, by strangling her with a rope, and the medical questions to be solved were: How long had she been dead? and, Did she die from strangulation, or any other cause? The author attended the inquest and the trial on the part of the Crown, having made an analysis of the stomach in order to determine whether poison was present therein. Taking the two questions in their order, it may be observed that the medical evidence showed, that when the deceased was first discovered, on Nov. 6th, at 6.30 A.M., she was lying on her back in bed, her body being covered with clothes as usual, the head and neck only being exposed. There was a pillow lying loosely over the face. There was no rigidity, and the hands were not clenched. The upper part of the body, including the head, neck, and shoulders, was very much decomposed. The skin of the face was so black that the features could not be described. The tongue was protruded and swollen. The lips were everted and blown up with gas. Gases escaped from between the tongue and lips with a slight hissing sound. The abdomen was enormously distended with gas, and at the lower part much discoloured. On opening its cavity the intestines protruded. The liver was in a putrefied state. On cutting into the skin of the chest a large quantity of air escaped; the lungs were found collapsed, and the heart was empty and contracted. Owing to the putrefied condition of the body the head was not examined. From the blackened and decomposed state of the upper part of the body, a medical witness

formed the opinion that death had been caused by violence, and he inferred that deceased must have been dead for some time.

According to the evidence, the prisoner and deceased took the bedroom as a lodging at the public-house on Nov. 3rd. The deceased was seen on that night about nine o'clock, as well as the following morning. On the last occasion the landlady, who took the breakfast to the door of the room, saw her face in bed. She was lying still, and, as she did not speak, the witness could not say whether she was then living or dead. It was observed, however, that of the breakfasts taken up, which had been ordered for two the previous evening, only one was eaten. From that time deceased was not seen alive. The prisoner came downstairs on Nov. 5th, at 9 A.M. There was nothing unusual in his appearance or manner. He asked to borrow a razor to shave himself, but there was no razor in the house. Breakfasts were not taken up that morning; and the following morning, as neither appeared, the room was entered, and the body of deceased was then found in the state described. The prisoner was lying on the bed with his throat severely cut: the wound had obviously been inflicted some hours, and had bled a great deal.

From the time when the deceased was last seen living, about sixty hours had elapsed. Considering that the weather was close and damp, and the body shut up in a small room, there was ample time for the putrefactive changes described to have taken place; although such a degree of putrefaction is rarely seen until after the lapse of three or four days in warm damp weather. It was therefore an exceptional instance of rapid decomposition, like those elsewhere described. As the prisoner alone was in the room with the deceased, he must have been cognizant of her death; and yet he gave no alarm. His statement was, that they had both resolved to die; that they had purchased poison on the 3rd, and took it on the evening of that day, and that deceased died in his arms. In the afternoon, having left the room for a short time, he found on his return a cord round her neck, which he removed. The highly-decomposed condition of the body was consistent with his statements; for although one day might be sufficient for such changes, they are seldom witnessed in less than two days. This would place the death of the deceased on the night of the 3rd.

The main question, however, was this:—had the deceased been strangled by the prisoner on that night, or did she die from any other cause? The putrefied condition of the body was consistent with either hypothesis, and it was a strong circumstance against him that he had remained in the room with the dead body. There was, however, an entire absence of motive for the alleged murder. The prisoner and deceased had been apparently happy together. No quarrelling or struggling was heard at any time by the people of the house. There were no marks of violence on her person indicative of struggling or resistance. It was proved, as prisoner had stated, that the deceased had, on Nov. 3rd, purchased at a druggist's, under a false pretence, a threepenny packet of Butler's vermin-killer. This contains about one grain of strychnine, mixed with soot and flour; and the paper wrapper of this packet, with the empty bag which had contained the poison, was found in the prisoner's possession. Several letters written by the prisoner, one apparently at the dictation or with the cognizance of deceased, referred to their mutual intention to destroy themselves; and another, dated Nov. 4th, stated that deceased had taken poison and had died in his arms. With these facts there was reason to believe that the deceased had really taken the poison which she herself had purchased, and had died from its effects. Assuming that muscular irritability had been exhausted by violent tetanic convulsions

fore death, and that the deceased had died in one of these convulsive fits ith great congestion of the head, the rapid putrefaction and the blacken- ıg of the features from the decomposed blood in the vessels, would then e explained. The empty and contracted state of the heart was also con- istent with this view. The stomach was examined chemically by the nedical man who was first called in to see the deceased. He found it empty, ontaining only mucus with some black particles, the nature of which ould not be defined. It was at first thought that it contained strych- nine, but on making an analysis of the remainder of the stomach, and the pirit in which it had been preserved, the author found that it contained no trychnine, and that the chemical results which had led to this conclusion were owing to the colouring action of sulphuric acid on potassium bichro- mate in contact with organic matter. In the state in which the stomach was brought, cut into two portions and macerated in spirit, it was im- possible to determine whether it had originally contained starch or soot (the substances with which the strychnine in the purchased powder was mixed), or gin (the liquid in which the prisoner said the deceased had taken the poison). This negative result did not show that the deceased ould not have died from the effects of a small dose of strychnine (half ı grain) such as would be contained in one half of the packet which he purchased: for such a quantity might have been removed by bsorption, especially as the poison was taken on an empty stomach. The heory adopted by the medical men who examined the body, was that leceased had probably taken strychnine, but that, before the poison had ad time to operate fatally, she had been strangled by the prisoner by neans of a rope placed round her neck. This, in their judgment, would ccount for the contracted and empty state of the heart and lungs: they ssumed that as the strychnine was in the system, it would prevent that ccumulation of blood in these organs which is considered to be charac- eristic of death by asphyxia. Another suggestion was, that assuming trychnine not to have been taken by deceased, the empty condition of the eart and lungs might be accounted for by the effect of gaseous putrefac- ion in the abdomen. A few ounces of bloody serum were found in the avity of the chest, but no blood was present in the heart or great vessels onnected with it.

As the head was not examined, and the internal appearances of the hest did not support the theory of death by strangulation, it was sought o establish this view by the external appearances. Here, however, the ame difficulty arose as in the preceding case. The advanced state of decom- osition in the head and neck rendered the medical conclusions, to say the east, unsafe. The facts relied upon, to show that deceased had died from trangulation, were,—1. The black and decomposed state of the head and eck, compared with other parts of the body. 2. Certain marks found on he neck, at the upper part, and chiefly on the left side. 3. The peculiarly oist condition of the head and upper part of the neck, and the drier ppearance of the lower part, near the chest. 4. The enormous distension f the head, and the protrusion of the tongue between the lips.

The first and third reasons assigned indicate, not the cause of death, whether by violence, disease, or poison, but simply an advanced stage of he putrefactive process, in a case in which death had taken place sud- enly, and the conditions were favourable to putrefaction. The surgeon who first inspected the body, found, on the day following its discovery, hree marks on the neck, corresponding to three similar marks at the back art. There was no abrasion of the cuticle in front, nor any indentation r depression, but at the back, the cuticle was peeling off as the result of utrefaction, and serum exuded from it. On removing the integuments

there was no appearance of escape or coagulation of blood beneath; and this is generally found in death from strangulation. The cellular tissue was much blown up with the gases of putrefaction. At the adjourned inquest before the coroner, while the facts were recent, the witness had thus described the appearances on the neck: 'On the external surface of the neck, there were two or three *indistinct* marks, most distinct on the left side. On removing the skin, there was not the least escape of blood, but here and there the muscular tissue was more discoloured than the remainder.' Another witness, who saw the body twenty-four hours later, described the marks as consisting of two or three lines of dark discolouration. There were no signs of violence beneath the marks, but the structures were of a darker colour below. He further stated that there was much blood beneath the skin from the chin to the chest; and on the arms there were apple-green streaks from putrefaction in the course of the blood-vessels. The protrusion of the tongue was referred by both, not to putrefaction, but to mechanical pressure on the neck as a result of strangulation.

A long clothes-line was found in the room, under the bed. This was proved to belong to the landlady, who stated that it had been lying a long time in the room before it was let to the prisoner and deceased. On it was one small spot of coagulated blood, as if from a wound, and some long hairs of a female. When these were compared with some taken from deceased's head, there was found to be no resemblance. It was suggested for the prosecution, that this rope had been employed by the prisoner as the instrument of murder.

The author's evidence on this part of the case, the cause of death, was to the effect that, as the deceased was not seen in the act of dying, any medical opinion of the cause of death must be speculative; that there was nothing inconsistent with death from strychnine as alleged by the prisoner, while there were no medical facts on which the hypothesis of death from strangulation could be safely based. The internal appearances, so far as they were observed, were more consistent with death from strychnine, than with death from strangulation, a fact admitted by the two medical men who ascribed death to homicidal strangulation; that the non-detection of strychnine in the body was not inconsistent with the fact that a small but fatal dose had been taken by deceased; that a rigid state of the limbs in a dead body would not be found where putrefaction had advanced to such a degree as in this case. Further, the external appearances did not prove that violence sufficient to cause death by strangulation had been applied to the neck of the deceased. The marks of discolouration on the neck, with the protrusion of the tongue, might have arisen from extreme putrefactive changes. Had they been produced by the application of a cord, such a degree of violence as would have caused the tongue to protrude would have produced indentation and depression of the soft parts of the neck, with an effusion of blood in the course of the depression, and a ruffling or abrasion of the skin. There was no protrusion of the eyes; the tongue was not indented or bitten by the teeth, and the hands were not clenched as in death by violent strangulation.

It was suggested by counsel that strangulation might have been produced by other and less violent means than by the use of the rope, and the slight appearances thereby produced might have been obliterated by putrefaction. It was admitted that this might happen, but there were no medical facts on which such an opinion could be based. The appearances were all consistent with putrefaction in an advanced stage, without resorting to the assumption that any violence whatever, sufficient to cause death, had been done to the neck. In the defence, it was urged that the prisoner and deceased had agreed jointly to take away their own lives: this was

ed by the letters and their conduct. Deceased herself had purchased on for this purpose, and had taken it, according to the prisoner's state- it, on the evening of the day on which she procured it. Everything in case was consistent with the theory of voluntary suicide, and of an mpted suicide by the prisoner in a state of despair. The powder con- ing the poison had disappeared, while the paper bag in which it was l remained.

In his charge to the jury, Pigott, B., observed that the great question them to decide, was whether the prisoner had any part in the death of deceased. If they were of opinion that her death was caused by the e, and by his act, then their verdict must of course be wilful murder. hey thought that death was caused by poison, then they would have to sider whether the deceased took the poison without any participation his part, in aiding and abetting her act, and if she did, then they must uit him. But if, in their judgment, the two agreed together to take on, and took it together, and she died, and he survived, then their dict must be also wilful murder. The jury adopted this view, and d that the prisoner was guilty as an accessory before the fact, *i.e.* that was not guilty of murder by strangulation, but that he aided and tted deceased in the voluntary act of self-murder.

The two medical men, while expressing their belief that death had n caused by strangulation, admitted in cross examination, that they ld not swear that deceased had not died from strychnine or some r cause; and one of them stated that his reason for thinking that chnine had not caused death was, that none could be detected in the r. It is obvious, however, that a person may take a dose of strych- , and yet, by the act of another, die from strangulation before the on has been wholly absorbed, or before a quantity sufficient to cause h has penetrated into the blood. The discovery of some portion of chnine in the stomach would not prove that the deceased had not been ngled, and its non-discovery, therefore, could not be taken as a fact in ur of death from strangulation. In short, this form of violent death ld be clearly and conclusively established by medical facts, inde- dently of the administration of poison. Here the cause of death was ply based on medical belief or probability; not on absolute certainty, ch alone would justify a jury in coming to the conclusion that murder been thus deliberately perpetrated. According to the prisoner's state- nt, the rope was really around the neck of the woman on the night of 3rd, and he removed it. Assuming that the coloured marks on the k arose from mechanical pressure, and not from putrefaction, it omes a question whether the rope may not have been thus used by eased, in attempting to strangle herself, or by the prisoner in aiding l abetting her in the attempt. Such a degree of pressure might be le on the part of the neck where those marks were found, without sing death, and this would account for their presence, without rendering ecessary to suppose that murder by strangulation had been actually petrated. The description does not convey the idea that it was im- sible for deceased thus to have produced them, or that they could have been produced without necessarily causing death; and thus re was nothing to support the hypothesis of murder but medical jecture.

It was stated in evidence, by one of the medical men, that if strych- e had been taken and death was subsequently caused by strangu- on, this fact would account for the absence of the usual appearances of hyxia in the heart and lungs, *i.e.* that strychnine would operate by ducing a contracted and empty state of the heart. Some questions on

this point were put by the judge, in answer to which, the author stated that no case of this compound character had, so far as he knew, occurred, or been recorded; but that on general medical principles, if, after taking poison, a person underwent strangulation, there was no reason, *quoad* the poison, why the usual appearances of strangulation should not be found in the heart and lungs. The poison being in the body, would not prevent the appearances which attend a sudden form of violent death; and although a contracted and empty state of the heart may be found in numerous cases besides death from strychnine, it is reasonable to infer that if the action of the poison had proceeded so far as to cause the emptiness and contraction of the organ, it had gone far enough to cause death, thus rendering it unnecessary to resort to any other hypothesis. From all the facts of this case, it is in the highest degree probable that deceased took a portion of the powder containing strychnine on the evening of Nov. 3rd, and that she died from its effects in the course of the night; that when her body was found, she had been dead more than two days; that the prisoner aided and abetted her in the act of self-murder; that he was cognizant of her death, and was for at least two days in the room with her dead body, without giving any alarm or calling for assistance; that he may or may not have taken part of the powder, but that in accordance with their mutually expressed intentions, he had attempted to destroy himself by inflicting a serious wound in his own throat. The wound was not of that slight nature which is observed in wounds self-inflicted for the purpose of concealing or masking crime. He had lost much blood, and was depressed and faint when found.

These cases will serve to show that the changes produced by putrefaction in a dead body may often involve questions of life and death, and that they require more attention from the medical profession than they have hitherto received. In alleged child-murder it has been generally considered that a highly putrefied state of the lungs prevents a correct medical opinion being formed of their actual condition at birth; and there are few who would venture to infer from experiments on such lungs, that a child had breathed after its birth. In reference to poisoning, when, in any suspected case, the mucous membrane of the stomach and bowels has undergone extensive changes from putrefaction, it would be unsafe to rely upon the appearances as evidence of death from poison, although they might at first sight resemble those produced by irritants. The same caution should be observed in forming an opinion from the state of the skin when putrefaction is far advanced. The discolourations which here take place, especially in parts of the body in which the venous trunks and capillaries are congested from any cause at the time of death, are liable to deceive the examiner when death is attributed to violence, and he is searching for proofs of this. In another place (page 89) several cases of this description are quoted, and in one, according to the statement of Christison, a man appears to have been wrongly convicted of murder by strangulation, chiefly because a broad blue mark was found in the front of the neck of the deceased. This was at first attributed to violence. There seems, however, to have been little doubt that it was due to post-mortem changes in the body.

Putrefaction, unless advanced to the last stage, cannot entirely destroy marks of violence when attended by physical injury to parts, such as abrasions or lacerations of the skin, laceration or crushing of the muscles with fracture of the trachea or larynx, protrusion of the tongue, accompanied by marks of indentation or laceration by the teeth. In such cases, a safe medical opinion may be formed in spite of the decomposed state of parts; but it is otherwise with superficial marks unattended with mechani-

injury. These are precisely the appearances which occasion mistakes, they may be really due to post-mortem changes, and not to violence. is true that life may be destroyed by a slight degree of mechanical ssure, and the injury thus occasioned may be masked or obliterated by trefaction. There is, however, this conclusion to be drawn: it is far ter that a few cases of real homicidal violence should thus escape ognition, than that we should incur the serious risk of involving an ocent person in a charge which on conviction might lead to capital nishment. Murder by strangulation is murder in its worst and most gravated form. The act itself implies malice and deliberate design. the body is not decomposed, we may act safely: if decomposition has vanced to a great degree, whether generally or locally, it would be safe to base an opinion on superficial discolourations.

3. PUTREFACTION IN WATER.—The process here takes place more slowly in in the atmosphere, owing to the low temperature, and the free access of being cut off. The skin covering the palms of the hands and the soles the feet is found thickened, white, and sodden from imbibition, when the ly has remained several days in water. Owing to this cause, ecchymoses, ulting from violence during life, are not always apparent in a body ently removed from water; it is only when the skin has lost the greater t of the water by evaporation that ecchymoses and other marks of lence begin to show themselves. The influence of air upon the skin of ody, which has been for some days submerged, is chiefly seen, after its oval from water, in the face and chest. In a few hours, if the tempera- e of the atmosphere be moderately high, the face will commonly be nd bloated, and either livid or black. The features are so distorted, t they cannot be recognized by those who knew the person during life. e change chiefly consists in the skin becoming first of a livid brown our, and afterwards passing to a deep green. According to Briand, en putrefaction takes place in bodies which have been lying in water, discolouration of the skin is first seen in the face and lower part of the k. It then spreads successively over the shoulders, chest, and legs. In lies exposed to air, the discolouration is first seen in the abdomen, and nce spreads to the chest, neck, face, and upper and lower limbs. These colourations are chiefly apparent in those parts which are freely exposed the atmosphere. They are not commonly found on surfaces which have en in close contact, as in the armpits and upper and lower limbs, where e former have been closely applied to the sides of the body, and the latter ve remained in close proximity to each other. For the same reason the colourations are not commonly met with at the back of the body, or on ose parts which have been closely wrapped in clothes.

Gaseous putrefaction takes place in bodies immersed in water, as well as those which are exposed to air. The abdomen, chest, and cellular mem- ane beneath the skin are thereby distended: the body acquires buoyancy d rises to the surface. It requires but a very slight expansion of the vity of the abdomen for this effect to follow, since the human body is ly slightly heavier than its bulk of water. The position in which a dead man body floats is commonly with the abdomen or back on the surface, d the head with the upper and lower extremities depending. The bodies females, it is said, are more commonly found floating with the abdomen wards. The period of time required for a body to rise to the surface, m gaseous putrefaction, must depend on many circumstances. It is ted to happen usually from the third to the fifth day after death from mersion. The gases may be then liberated and the body will sink; y may be again generated and it will rise. The facts connected with

the buoyancy of the dead body became of great importance in the trial of *Spencer Cowper* (1699), for the alleged murder of a woman. (See DROWNING.) If the dead body has been submerged for some weeks or months, or has remained long exposed before inspection, the skin will be found of a deep blue, black, or green colour, the muscles soft and discoloured, or the fatty parts may have been converted into adipocere. Ultimately the soft parts will be washed from the bones and the skeleton separated.

The changes from putrefaction, even when comparatively slight, may, as Casper justly remarks, seriously affect the value of medical evidence. The blood becomes decomposed, acquires a darker colour, and produces congestions in the brain, lungs, right side of the heart, and other parts of the body, so as to render it difficult to form a conclusion on death from apoplexy or asphyxia.

The researches on drowning made by Casper and Kanzler show that putrefaction of the bodies of the drowned generally commences at the upper part and extends downwards. Thus, after a few days, while the lower part of the body may be in a tolerably fresh condition, the face, head, neck, and upper part of the chest may present a reddish colour passing into patches of a blueish-green, first seen on the temples, ears, and nape of the neck, thence spreading to the face, and afterwards to the throat and chest. These changes may be observed in summer, when a body has remained in water from eight to twelve days, and in winter for a still longer period. The head of a drowned person is sometimes much discoloured from putrefaction, when the rest of the body is in its ordinary condition. Casper considers that this inverted order of the putrefactive process may be taken as a strong indication of death from drowning; but while it may be admitted that attention should be given to this circumstance, it yet remains to be seen whether a dead body thrown into water (when death has taken place from asphyxia by suffocation or strangulation) would not undergo decomposition in a precisely similar manner. It is worthy of remark that the uterus resists decomposition more than other internal organs. In a case in which the body of a female, who had been missing nine months, was found and examined, although all the other organs were completely decomposed, the uterus was firm in structure, of a reddish colour, and its parts were recognizable, so that Casper, who conducted the inspection, was able to affirm that the female was not pregnant at the time of her death.

Attempts have been made by the aid of baths of chlorine, salt, and hydrochloric acid, as well as by injections of chlorine, zinc chloride, and ferric chloride, so to restore the features of a drowned body as to enable persons to identify it. ('Lancet,' 1863, I. p. 551.) After the occurrence of such changes from putrefaction in the drowned as those above described, it would be hopeless to attempt to restore the expression of the features of the living man. It is one thing to arrest or prevent putrefaction by these agents, but another to suppose that the chemical changes can be reversed, and the corpse put in the position of a body recently drowned. It may be well to state in this place that great mistakes have been frequently made by persons relying upon the features as proof of identity in the drowned. A singular case of this kind came before Wood, V.-C., in March 1866. (*Holliss* v. *Turner*.) The plaintiffs instituted this suit in order to establish the death of one William Turner. This person was of restless, unsettled habits, wandering about the country, and in a state of great mental and bodily depression. On May 7, 1865, he walked into the house of some people named Waller, at Guildford. He was shivering with ague, covered with boils and sores, and had a fortnight's unshaven beard. His sores were dressed with rags. On the

ıg day he left the place, and was never again seen alive. Ten
ter his disappearance, the body of a man much decomposed was
ı the river Wey, near Guildford. An inquest was held on it the
ay, but it was claimed by two men, named Etherington, as the
their father, who was missing. Mrs. Waller and others saw
y, and stated their conviction that it was the body of Turner. The
owever, was buried as that of Philip Etherington, a ragged piece
erchief having been previously removed from the neck. Some
afterwards, Etherington, sen., the supposed deceased, walked
daughter's house. It was therefore clear that the sons must have
ceived as to the identity of their father. There was no doubt that
s the body of Turner. A fragment of an old neckerchief, found
he bed where this man slept on May 7th, corresponded exactly
at which was removed from the neck; and further, it was remem-
ıat there were sores on the body, which had been dressed. The
ıancellor held that the evidence adduced was sufficient to identify
y found in the river Wey as that of Turner, and made an order
ıgly.

rmination of the period of death in the drowned.—Some attempts have
ade to generalize on the phenomena of putrefaction in water, in
o enable us to say for how long a period a body may have been
ed. No satisfactory data, however, have been obtained to guide us
nquiry. The changes which take place are modified in their degree
rapidity of their progress by numerous and often inappreciable
Devergie believed that he had obtained a certain series of
ers whereby he could determine with sufficient precision the length
which a dead body may have been in the water, supposing the
ıg to have occurred during the winter season. Thus, according to
bodies immersed *from three to five days* we shall find:—cadaveric
; coldness of the surface; no contraction of the muscles under
ranic stimulus; and a white or sodden appearance of the skin of the
From *four to eight days*:—pliancy of all parts of the body; no
ır contractions under the galvanic stimulus; natural colour of the
uticle of the palms of the hands very white. From *eight to twelve*
-the whole of the body flaccid; the cuticle of the back of the hands
ng to whiten; the skin of the face softened and pallid, differing
ıe skin of other parts of the body. About *fifteen days*:—the face
ıat bloated and covered with red patches; a greenish tint in the
of the sternum; the cuticle of the hands and feet perfectly white,
oming raised in folds. About *a month*:—face of a reddish-brown
eyelids and lips green; a reddish-brown patch surrounded by a
order on the fore part of the chest; the cuticle of the hands and
ite, thickened, and corrugated. About *two months*:—face brownish-
d and swollen; the hair becoming loose; the cuticle of the hands
t in great part detached; the nails still adherent. *Two months and*
—cuticle and nails of the fingers detached; that of the feet the same,
nails still adherent. In the female there is a reddish colour of the
ıneous cellular tissue in the cervical region, as well as that which
ıds the windpipe and the organs contained in the chest; partial
ication of the cheeks and chin, superficial in the breasts, groins, and
rt of the thighs. *Three months and a half*:—destruction of part of
lp, eyelids, and nose; partial saponification of the face, of the upper
the neck, and groins; destruction of the skin in different parts of
ly; cuticle of the hands and feet as well as the nails entirely
d. *Four months and a half*:—almost complete saponification of
y part of the face, neck, groins, and fore part of the thighs; the

appearance of a calcareous incrustation or deposit on the thighs; incipient saponification of the fore part of the brain; opalescent condition of nearly the whole of the skin; destruction and removal of the hairy scalp; the bones of the skull laid bare and beginning to become brittle. There are no data to give even approximate opinions for a longer period than this: and it is admitted that even these imperfect data are not available for determining the period of death in subjects drowned during spring and summer.

There is a common belief that the dead human body is soon destroyed by submersion in water; but this is not borne out by experience. In those who are drowned during winter, and whose bodies remain long below the surface, or are covered with mud so as to prevent a free access of air, decomposition takes place slowly. Mr. Eager, of Guildford, met with a case, in which a man, æt. 70, was missing from Jan. 6 to Feb. 4, 1864. His body was found in a river, and there was reason to believe that he fell in and was drowned on the day he was last seen. The head, neck, and a portion of the chest, where unprotected by clothing, were thickly covered with mud. When this was removed, the features were perfectly recognizable, and although twenty-eight days had elapsed identification was easy. The only changes observed were as follows:—The cuticle peeled away from the cutis when slight friction or pressure was made over those parts which had been covered with mud. The face and neck were somewhat darkened in colour, and the front part of the chest was marked with slight lines of lividity. There was no tumefaction whatever over any part of the body. The thickened skin of the hands and feet was corrugated and whitened by long-continued maceration, but remained firmly adherent to the tissues beneath it. With these exceptions the body presented no appreciable alteration of appearance, nor any departure from that which would be observed in a recently dead body.

In 1857, some parts of the body of an infant were found floating on the surface of water in a pit. There was the skull with the sodden skin upon it, but the brain, eyes, and ears had disappeared. The upper part of the chest and one arm were found. The soft parts appeared to enclose the bones, which were quite loose and discoloured, but saturated with water. Some of the articular cartilages were still attached, although very much softened and easily separated. There were the remains of a woollen cloth in which the body was probably wrapped. It had been kept at the bottom of the water for some time by a heavy stone found there, which was no doubt attached to the body. Upon these facts the questions submitted to the author, in reference to a woman delivered of a child eighteen months previously and suspected of murder, were, whether it was possible that a human body could remain so long a time as eighteen months in water, without being totally destroyed. Further, whether the action of water would not increase the bulk of the body, so as to make a new-born child appear some weeks old. The answers to these questions were:—1. That a dead human body submerged is not necessarily destroyed in eighteen months: and in reference to this case, it appears probable from the description that the body had been immersed for a longer period. 2. That in the early stages of gaseous putrefaction, the body may appear larger from general distension; but this stage had been long passed in reference to these remains. Although this was probably a case of infanticide, there were no data to determine whether the child had been placed in the water living or dead.

Mr. Harris, of Redruth, met with a remarkable instance of the effects of water on the human body after submersion for the long period of twenty-six years. In 1828, a healthy muscular man, æt. 24, fell into the shaft of a mine, fifty fathoms deep, of which thirty fathoms consisted of water. The

ts to recover the body were unsuccessful. The shaft was closed over, so it remained until April 1854, when the working of the mine was med. The skeleton of the missing miner, with portions of the clothes ch he wore, was discovered in one of the levels, in which there was er. The remains, as well as the clothes, buttons, and boots found on skeleton, were identified by his brother. All the soft parts, with the ption of a small piece of fatty substance, were destroyed, but the bones e firm and well preserved. There was no muscle, tendon, ligament, or a cartilage about any of them. They were all detached from the joints. y were of a dirty brownish or almost black colour. The skull was full a brown soft substance, which was without smell. There was nothing he water calculated either to destroy the soft parts or preserve the es.

It is not often that any very precise opinion is required of a medical ness respecting the probable period at which death has taken place from wning. A question has, however, arisen respecting the time required the production of *adipocere* in the drowned, and on this has depended important question relative to the presumption of survivorship. The perty of a gentleman who had committed suicide by drowning, was ed under a commission, and an action was brought to recover it at the rwick Lent Assizes, 1805, on the ground that the insolvent was dead he time the commission was issued. The following is an outline of the e:—

The deceased, who was in a state of insolvency, left his home on r. 3rd; and on Dec. 12th following, *i.e.* five weeks and four days r his departure, his body was found floating in a river near the place ere he resided. A commission of bankruptcy had been taken out inst him a few days after he was first missed, and before it was known t he had destroyed himself. It became therefore important to determine ether he had drowned himself (for there was no doubt of his having mmitted suicide) *before* or *after* the date of issuing this commission. If could be shown that he was already drowned when it was issued, the mmission would be void in law, and his property could not be seized der it. The litigation then turned upon the question, whether he had wned himself on the day of his leaving his house, or at some subquent time. The body was found floating with the head and feet bmerged. On being taken out, the face was covered with a muddy slime. e body was discovered on a Wednesday, and a coroner's inquest was ld on the following Saturday. On the day before the inquest, three edical men examined the body with a view to ascertain whether any ange had taken place in it, which could justify an opinion as to the ne during which it had been lying in the water. The muscles of the ttocks were found to be converted into a fatty substance, very much reembling suet (adipocere). The face was completely disfigured by putrefaction. The hair of the head separated from the scalp by a slight pull. he other parts of the body were firm and white, without any putrefactive ppearance. The clothes externally seemed unchanged in any way; but e shirt and neckcloth were so rotten as to be torn by the slightest force.

A medical witness for the plaintiffs stated it as his opinion that the body uld not have been less than *six weeks* submerged. Three or four weeks ould not have sufficed to produce the appearances met with; the adipocerous state of the body could not have been brought about in *less* than x weeks. He admitted that he had met with an instance in which a dy taken from the Severn had a spermaceti appearance within a shorter me, although the change had not advanced so far as in this instance. nother witness said that the parts of the thigh and abdomen were

changed into a soapy fat or adipocere. He supposed the body must have been under water for more than six weeks; he therefore thought the deceased's body must have been in the water during the whole time that he was absent. If it had been exposed to the air it would not have presented the appearances met with. He admitted he had said that the body was in such a state, that it would be impossible to express an opinion. Gibbes had been able to procure a small quantity of adipocere from muscle by maceration in water for *a month;* but in general, it required a much longer period for this transformation to take place. Upon this evidence, the jury were of opinion that the deceased was not alive at the time the commission was taken out, but that he had been dead for the whole period of his absence, and the bankruptcy was accordingly superseded.

In medicine, as in law, there are always two sides to a speculative question. The case, *primâ facie*, as we have seen, was in favour of the plaintiffs. The state of the body supported this view, although it might have been contended for the defendants that a few days more or less would have made no difference in the results, and that deceased might therefore have been alive when the bankruptcy was declared. The verdict of the jury was physiologically well founded. The general period required for the production of adipocere in drowned bodies, is stated by most observers to vary from three or four months to a year. Its occurrence in a body to any extent, within five weeks and four days, must be regarded as an exception to an extensive series of observations. The witnesses for the plaintiff were then justified in assigning the longest possible period, that the circumstantial evidence would admit, for its production in this instance. The facts of this case show that adipocere may be produced in the body of a drowned subject within a period of six weeks. The defendants wished to make it appear that the adipocerous transformation might take place with much greater rapidity, but there were no facts to render this view probable, while there were many facts in support of the contrary opinion. One instance of its early production is related by Harlan. He had occasion to macerate the cranium of a fat negro in the summer; it was placed in a barrel of water, and kept closely covered over. About six weeks afterwards he observed the head floating on the surface, and rather inclined on one side. The portion of the head which floated above the level of the water was tumefied, and on cutting into it, the whole substance down to the bone, was found converted into adipocere: but that portion of the head and face which was immersed in water, was in a putrescent state.

It may be as well to compare the facts of this case with the rules laid down by Devergie, for determining the period during which bodies have remained in water. The deceased was an adult, and the drowning took place during the winter season:—it is therefore a favourable case for testing the value of these rules. Devergie fixes the earliest period for the production of adipocere at about two months and a half: he then speaks of its commencing in the cheeks, chin, breast, groin, and fore part of the thighs. Here, however, in less than six weeks, the adipocerous change had taken place completely in the muscles of the lower part of the abdomen and of the buttocks. Devergie states that the hair of the scalp becomes loose in about two months: here it separated with the slightest pull in six weeks. The data furnished by this medical jurist, would therefore tend to assign a much longer period of submersion than six weeks, to a body presenting the characters observed in this case. It is scarcely necessary to remark that rules of this kind must be regarded as remote approximations to the truth.

When a dead body is immersed in a liquid of a preservative nature, as in the water of a peat-bog, the changes which take place are of a peculiar

ind, and they render it difficult to arrive at even an approximate con-usion respecting the period of death. A male human skeleton was found ar the surface of a peat-moss or bog. All the bones were detached, and re of deep chocolate colour. The right femur had been accidentally ctured obliquely. The skin and muscles were closely adherent to it. ey were free from any unpleasant odour, and were completely tanned. e bones were destitute of calcium phosphate, and in consequence were as ible as cartilage. It was calculated by a comparative measurement of e thigh-bone, that the stature was five feet seven inches. The sex was termined as usual by the roughness of the bones, and the size and shape the pelvis. There were no means of determining the cause of death. e skull had not been fractured. It was supposed that the person had en shot and the body deposited in the bog ten years previously, but it ght have been lying there fifty years. The removal of the calcium osphate was a remarkable fact; it probably depended on the action of e water. Tannin was, no doubt, the agent by which the soft parts were eserved.

CHAPTER 8.

ENTITY OF MUTILATED REMAINS—CASES—EXHUMATION OF SKELETONS—HUMAN AND ANIMAL BONES—DETERMINATION OF SEX, AGE, AND PERSONAL PECULIARITIES—DETERMINATION OF AGE BY THE TEETH—QUESTIONS OF PERSONAL IDENTITY—EVIDENCE FROM FRACTURES, DISEASE, AND DEFORMITY.

ntity of mutilated Bodies.—A DEAD body partially putrefied, may be nd mutilated, and parts of it may be discovered in localities distant m each other. There is less difficulty here in making out identity, than ere only bones are discovered; for it is by no means easy to say whether tain bones belonged to the same skeleton or not. So long as the soft rts are attached to them, there will be no difficulty in forming an opinion. ose who commit murder, and thus dispose of a body, believe that ntity must be entirely destroyed, if they only deposit the parts in mote places. In this respect, however, they are generally deceived: for tisfactory medical evidence may still be forthcoming. In the case of the oman Brown, murdered by *Greenacre* in 1837, the head, trunk, and nbs were scattered in widely distant parts of London. The limbs were t found until six weeks after the trunk, and then at a considerable stance, and under very different circumstances. In the examination of e trunk, it was observed that the fifth cervical vertebra had been sawn rough, leaving only about the tenth of an inch of that bone. When the ad was found it was observed that the fifth cervical vertebra had also en sawn through, leaving only the posterior spinous process. On com-ring the head with the trunk they fitted exactly, even to the continua-n of a superficial cut on the skin. On afterwards comparing the trunk ith the legs, it was ascertained that the cut surfaces exactly corresponded. he thigh-bones remaining attached to the trunk, had been sawn through bout an inch below the trochanters, to about one-half of their thickness, nd then broken off. When the limbs were discovered six weeks after-ards, the portions of thigh-bones found exactly corresponded in the arks produced by the saw and in the portions broken. Not only were e parts of the body thus proved to belong to one and the same woman, t the individual was further identified by the peculiarity of the absence a uterus.

In a case of infanticide, which was the subject of a trial in 1839, the arm of a child was found concealed in a dust-hole of the house, while at about the same period, a body without an arm, and the head of a child, were found in a ditch at some distance from the house where the accused person was living. The identity was, however, distinctly made out by the fact, that the arm and scapula attached to it, fitted exactly to the trunk, and that the incisions through the muscles and vessels completely corresponded.

On the occasion of a murder perpetrated at Brighton the head and subsequently the body of a female were found in different and distant places. They were identified as belonging to the same individual: first, from the fact that there were four cervical vertebræ attached to the trunk and three to the head; and secondly, from the divided vessels and cartilaginous rings of the trachea exactly corresponding. The importance attached to this kind of anatomical evidence, shows that when a portion of a dead body is found, the whole of the parts which form the boundary of the section, should be attentively observed and accurately described.

The case of *Dr. Parkman*, for the murder of whom *Professor Webster* was tried and convicted at Boston, U.S., in March 1850, presents a remarkable instance of the value of scientific evidence, in establishing the identity of a mutilated body. It also proves that even all the refinements of science will fail in the attempt so to dispose of a dead body in a case of murder, as to prevent its identification. On Nov. 23, 1849, the deceased, Parkman, was traced to the laboratory of the prisoner, and from that date he was missing. A week after his disappearance, there were found concealed, in the vault of a privy belonging to the prisoner's laboratory, a pelvis (the hip-bones), the right thigh (from the hip to the knee), the left leg (from the knee to the ankle);—and with them certain towels bearing the initials of the prisoner, and being such as were used by him. Among some cinders and slag, connected with a furnace, were found portions of bones, apparently of the cranium, fragments of vertebræ, blocks of artificial teeth, and some gold which had been melted. On the day following, in a remote corner of the laboratory, there was found a tea-chest containing, imbedded in a quantity of tan and covered with minerals, the entire trunk of a human body, with the left thigh from the hip to the knee. When the parts were placed in apposition with the portions previously found, they corresponded; so that they were obviously parts of the same body. This observation also applied to the remains of bones (cranium and vertebræ) found in the slag of the furnace. There was no duplicate portion. All the fragments fitted so as to form part of the same human skeleton. The portions thus found resembled in every particular the body of Parkman, and in no single particular were they dissimilar from the body of the deceased. There were missing from these remains, when they were placed in apposition, the head, the arms with the hands, both feet, and the right leg from the knee to the ankle.

The parts found (which are light in the engraving *fig.* 1), were examined by several medical men. They deposed that they were human remains, parts of one and the same male human body; that they had not undergone dissection for anatomical purposes, and had not been submitted to any process of preservation. Further, that they had been cut and hacked in different directions without any reference to their anatomical relations, and evidently by a person only partially acquainted with the structure of the body. The chest was still covered with the muscles and skin. It was noticed, that under the left nipple, between the sixth and seventh ribs, there was an opening which penetrated into the cavity.

he opening was slightly ragged, and about one and a half inches in ngth.

It seems that Parkman was sixty years of age, and his stature was ve feet eleven inches. The portions of the ody thus restored, were those of a person etween fifty and sixty years of age; and with espect to stature, the portions found, extending om the seventh cervical vertebra to the outer nkle (malleolus) measured 57½ inches. The istance from the sole of the foot to the outer alleolus, measured in another subject of the me age, was 3 inches; and the distance from he top of the head to the base of the sixth rvical vertebra was 10 inches. Adding these easurements to the missing portions, the total ngth of the body found would be 5 feet 10½ ches, being within half an inch of the stature Parkman. There were marks of identity out the teeth and jaws which left no doubt at the remains were those of the missing an. An attempt had been made to destroy e skin and flesh of the chest, by the use of strong solution of potash, but this had failed. he defence of the prisoner rested upon the fact at the charge was based entirely on circumantial evidence, that the identity of the reains had not been satisfactorily made out, and hat no cause of death had been proved. The ury, however, returned a verdict of guilty, and he prisoner was subsequently executed (see Rep. of the Trial of Prof. Webster,' by Dr. Stone, Boston, 1850).

Fig. 1.




Dr. Parkman's remains restored. The missing parts are black.

A singular case involving somewhat similar questions occurred in ondon in Oct. 1857, when the remains of a human being were found n a bag on one of the buttresses of Waterloo Bridge. It appeared that hey had been accidentally deposited there the night previously—the ntention of the person who carried them being, no doubt, to lower them nto the river, but by accident they lodged on one of the buttresses of the ridge. A number of articles of clothing were in the bag with the remains. These remains were submitted to the examination of the Divisional Surgeon of Police and the author.

They found them to consist of parts of a human body, and obviously of the same body; as, when allowance was made for the missing portions, they admitted of an accurate adjustment to each other. There were twenty-three portions of the body discovered, consisting chiefly of bones with flesh adhering to them. The flesh had been roughly cut from the bones, apparently with a view to remove as much of it as possible, and to destroy the identity of the body. The parts had been cut and sawn into small lengths, probably to reduce their bulk and to allow them to be packed within a small space. The trunk, including part of the chest and spine, had been cut into eight pieces; the upper limbs had been cut or sawn into six, and the lower limbs into nine pieces. The hip and elbow-joints were in a strongly flexed condition. The missing portions (which are marked black in the engravings *fig.* 2 and 3) were the head, with the greater part of the spine, namely fourteen out of twenty-four vertebræ (seven cervical and seven upper dorsal), the hands, the feet, and some portions of the left side of the chest. It will be observed that these were also the parts which

were missing in the case of Parkman. In fact, a murderer intending to destroy personal identity, would in general most effectually succeed in his object by removing the head, feet, and hands. The whole of the viscera of the chest and abdomen had also been removed. The twenty-three fragments found weighed only eighteen pounds. This is about one-eighth part

Fig. 2. Fig. 3.



Waterloo Bridge remains restored. Front and back view of the Skeleton. Dotted lines showing where the bones were cut or sawn. Missing parts black.

of the average weight of the adult body. The questions which required solution in this case were the following:—1. The sex, age, and stature of the deceased; 2. The presence of any physiological or pathological peculiarities in reference to personal identity; 3. The presence of any wounds or marks of violence, with reference to the probable cause of death; 4. The general condition of the remains, with a view to determine whether they were parts of a dissected body, and whether they had undergone any chemical process for the purpose of preservation; 5. The length of the period which had probably elapsed since the death of the deceased. The details of this examination will be found elsewhere ('Med. Gaz.' Oct. 31, 1857, p. 445). There was no difficulty in determining the sex of the deceased, as a portion of the sexual organs, which had been mutilated (not dissected), still remained attached to the pelvis. The long bones were in their full state of development. The stature was determined by taking the length of the portions found, and adding a certain number of inches for the missing skull, cervical vertebræ and feet. The bones had been sawn through near the joints with a fine bone-saw, such as is used by bone-boilers. On the left side of the chest, between the third and fourth ribs, there was a stab which had penetrated the cavity, and which, if inflicted on a living person, would have been in a direction to enter the heart. The edges of this wound were everted and wide apart, and the muscles around were infiltrated with blood. It had those characteristics which are

cal injury. These are precisely the appearances which occasion mistakes, as they may be really due to post-mortem changes, and not to violence. It is true that life may be destroyed by a slight degree of mechanical pressure, and the injury thus occasioned may be masked or obliterated by putrefaction. There is, however, this conclusion to be drawn: it is far better that a few cases of real homicidal violence should thus escape recognition, than that we should incur the serious risk of involving an innocent person in a charge which on conviction might lead to capital punishment. Murder by strangulation is murder in its worst and most aggravated form. The act itself implies malice and deliberate design. If the body is not decomposed, we may act safely: if decomposition has advanced to a great degree, whether generally or locally, it would be unsafe to base an opinion on superficial discolourations.

3. PUTREFACTION IN WATER.—The process here takes place more slowly than in the atmosphere, owing to the low temperature, and the free access of air being cut off. The skin covering the palms of the hands and the soles of the feet is found thickened, white, and sodden from imbibition, when the body has remained several days in water. Owing to this cause, ecchymoses, resulting from violence during life, are not always apparent in a body recently removed from water; it is only when the skin has lost the greater part of the water by evaporation that ecchymoses and other marks of violence begin to show themselves. The influence of air upon the skin of a body, which has been for some days submerged, is chiefly seen, after its removal from water, in the face and chest. In a few hours, if the temperature of the atmosphere be moderately high, the face will commonly be found bloated, and either livid or black. The features are so distorted, that they cannot be recognized by those who knew the person during life. The change chiefly consists in the skin becoming first of a livid brown colour, and afterwards passing to a deep green. According to Briand, when putrefaction takes place in bodies which have been lying in water, the discolouration of the skin is first seen in the face and lower part of the neck. It then spreads successively over the shoulders, chest, and legs. In bodies exposed to air, the discolouration is first seen in the abdomen, and thence spreads to the chest, neck, face, and upper and lower limbs. These discolourations are chiefly apparent in those parts which are freely exposed to the atmosphere. They are not commonly found on surfaces which have been in close contact, as in the armpits and upper and lower limbs, where the former have been closely applied to the sides of the body, and the latter have remained in close proximity to each other. For the same reason the discolourations are not commonly met with at the back of the body, or on those parts which have been closely wrapped in clothes.

Gaseous putrefaction takes place in bodies immersed in water, as well as in those which are exposed to air. The abdomen, chest, and cellular membrane beneath the skin are thereby distended: the body acquires buoyancy and rises to the surface. It requires but a very slight expansion of the cavity of the abdomen for this effect to follow, since the human body is only slightly heavier than its bulk of water. The position in which a dead human body floats is commonly with the abdomen or back on the surface, and the head with the upper and lower extremities depending. The bodies of females, it is said, are more commonly found floating with the abdomen upwards. The period of time required for a body to rise to the surface, from gaseous putrefaction, must depend on many circumstances. It is stated to happen usually from the third to the fifth day after death from submersion. The gases may be then liberated and the body will sink; they may be again generated and it will rise. The facts connected with

of an over-coat must have been inflicted with great force, as it wa to extend through corresponding parts of the under-coat and wa All these articles of dress had stains of blood on the inside, and ch the left side of the body, in the parts corresponding to the stab on side of the chest. The cutting and tearing of the dress may hav from the removal of the clothes while the body was in a state of in a constrained attitude. The state of the clothes was consiste their having been worn by the deceased when he was subjected to which led to his death.

From inquiries made by the police, there was reason to believe remains were those of a Swedish sailor from a vessel then in the ri is believed that he met with his death by stabbing, and that after concealment, his body, cut up and mangled in the manner descril disposed of by throwing it into the river. The head and other parts had probably been thus got rid of; and it was only by the of the bag lodging on a buttress of the bridge, instead of falling river, that these remains were found. As the deceased was most p a foreigner whose name was not known, and of whose personal app no description could be given, there was no clue to the perpetrators murder. In this respect it resembles some murders of recent which the bodies have been discovered entire.

In reference to this case of mutilation, there is one point which a brief notice. When parts of dead bodies are found, a sectior public adopt the hypothesis that some medical student has resc this method of disposing of parts of a dissected subject. Thus case of *Greenacre*, there was a disposition to refer the first portior mutilated remains which were discovered to a wanton act of th The erroneousness of this view was proved only by the subsequ covery of the corresponding parts of the dead body and the dete the murderer. So in reference to the case of Parkman, the m remains were at first described as anatomical preparations. Such s thesis is of course favourable to the escape of criminals, and is pr to the course of justice. It points out to the assassin an easy m deceiving the public; and it shows that if he only mutilates a cc removing and destroying the head, hands, and feet, leaving the re of the body to be discovered accidentally, he has a far better ch escaping detection and punishment than by attempting to con entire murdered body. The Waterloo Bridge case formed no exce the protection thus unintentionally extended by public opinion t act of murder. Any one acquainted with anatomy and the disse bodies would at once perceive from the description that no portior body could have been used for such a purpose. Medical students as part of their anatomical pursuits, hack and mangle a dead body destroy muscles, vessels, nerves, and spinal-marrow; they have no to make away with those parts by which a body may be ident to boil and salt the remainder; they do not receive corpses for d with their clothes, nor is there any conceivable reason why, if t they should produce cuts and stabs and stains of blood on the insic clothes with such accuracy as to correspond to the effects of inflicted on a living man. It was suggested that no murderer wo secreted the clothes with the remains. It is difficult to speculat proper course which should be pursued by men who are fresh f perpetration of an atrocious crime, and who are anxious to conce this may be fairly said,—the bag of clothes with the remains was over the bridge with a view that it should fall into the water carried away by the tide: it was owing to mere accident that it wa

n the situation described. The head and other parts had no doubt been lready successfully disposed of by a similar proceeding.

In 1875, the remains of a woman, *Harriet Lane*, were conveyed into he Borough, she having been murdered by her paramour, *Henry Wainright*, in Whitechapel. On Sept. 7, 1874, the deceased woman went n a cab to premises in Whitechapel Road, and was never again seen live. In Sept., 1875, a year later, the premises were likely to pass om Wainwright into the hands of others; and he resolved to remove the dy of the woman, whom he had murdered and buried, to another hiding-lace in Southwark. A few days before, the prisoner employed his rother to purchase for him a spade and a small chopper or axe. These rticles were found on the premises after the removal of the body. The hopper had on it putrescent animal matter, and the spade clay mixed ith lime. On the same day, Wainwright purchased three yards of merican cloth and a quantity of cord. On Sept. 11, 1875, a man, nployed by Wainwright, was arrested in the Borough, having in s possession two packages, wrapped in similar American cloth and cured with similar cord, containing human remains. On opening these, r. Larkin found one parcel to contain the trunk, and the other bundle e remaining portions, which collectively were the remains of a human male, about five feet high, and about twenty-five years old, and those of thin person. The body, which was supposed to have been dead about a ar, had been very recently and most unscientifically dissected. It was a stinking and decomposed state; some parts were more or less mummi-d, whilst other parts were in a condition tending to adipocere. The body as, roughly speaking, divided into ten parts, as follows:—two arms; two nds; two legs and feet connected, the left leg including part of the tella; two thighs including portions of the pelvis (the right thigh cluded the patella, the left thigh included part of the patella); one trunk, xcept the front of the pelvis; one head and neck. Though the woman d been dead a year, and buried in a grave on the premises, certain rts had been well preserved, owing to the use of chloride of lime, nployed with the mistaken view of destroying the body, whereas it had cted as a preservative.

The cause of death was obvious. There were two bullets in her brain, d a third was found in a hair-pad at the back of the head. There was cut extending from the centre of the throat to the angle of the lower w, which had severed all the tissues, and which must have been inflicted ith considerable force. There could not be a doubt that the woman had en deprived of life by pistol-shots. There was reason also to think that he first shot was just behind the right ear, and the bullet was found to have aused an extravasation of blood three inches in circumference. Another ullet was found in the brain; there was a cut in the throat, the other ullet having probably been fired when life was ebbing; and another had attened against a mass of hair-pins, which had no doubt prevented it oing into the head. Probably the murderer came up from behind, and red the first shot from the back of the head; and that, finding the first hot ineffectual, he had brought the pistol round and fired it just behind he right ear; and then, not certain that it would answer the purpose of estroying life, the third shot was fired. The cut in the throat was of old ate, and must have been inflicted either immediately before or immedi-tely after death. As the principal arteries of the neck were divided, it ould have been sufficient of itself to cause death. Probably this wound as inflicted after the pistol-shots had been fired.

In this case the identification of the remains was based partly on edical facts, and partly on the discovery of certain articles of dress in the

grave from which the body had been removed. The features were recognizable. The body had been cut into ten pieces and much mangled. It was decomposed; but, as a quantity of chloride of lime had been used in the burial of it, putrefaction had been in some degree retarded. The relatives could only speak generally to the slender form and stature of the body, and the smallness of the hands and feet, as points in which it resembled that of Harriet Lane. The light auburn colour of the hair, the absence of a tooth in the upper jaw on the right side, and the presence of a scar or cicatrix from a burn received many years before, and still remaining on the right leg below the knee, were also circumstances which strengthened their opinion. Some buttons and other articles of dress found in the grave, such as those which were actually worn by the deceased on the evening of her death were identified by her relatives. The direct proofs of identity were: 1. The *age*. The age of the deceased was twenty-four. Judging by the wisdom teeth, three of which had appeared, this corresponded with the age assigned to the body. 2. *Stature*. It was inferred, but by no means directly proved, that the deceased was five feet and a quarter of an inch in height. The remains, when put together, represented a stature of four feet eleven and one-eighth inches. This makes about an inch difference, which was accounted for by one of the medical witnesses, as a result of the shrinking of the intervertebral substance, hence the defective length of an inch was consistent with the remains being those of a person of the height of the deceased. 3. The *colour of the hair*. This is stated to have been slightly different; but the difference was consistent with the hair of the remains having been buried for a year in the earth, and exposed to the action of chloride of lime. But there are indeed so many women in the world with hair of a similar shade of colour, that no great reliance can be placed on a resemblance of this kind in a disputed case of identity. 4. The *scar*. There was a scar or cicatrix from a burn in the right leg, below the knee. On removing the adipocere and other matter on the body, which concealed such superficial marks, it was found in a part indicated by the father of the deceased woman. The scar was distinctly puckered, and presented all the usual marks of a scar produced by a burn from a red-hot poker. 5. The *state of the uterus*. The missing woman had had two children by Wainwright, the last having been born about nine months previous to her disappearance. From their examination of the womb, the medical witnesses for the Crown, Messrs. Bond and Larkin, came to the conclusion that the woman whose remains were discovered had borne a child. On the other hand, Dr. Meadows, who appeared as an obstetric witness for the defence, stated that, in his opinion, the woman of those remains had never borne a child; an opinion which he qualified by stating that he believed it to be impossible to decide this question in any case with absolute certainty. If this witness had been able to testify positively that the indications of child-birth were certain, and could never be mistaken for an unimpregnated state of the uterus, his evidence would have gone far to show that this could not have been the body of Harriet Lane. The womb was described by Bond as much decomposed; the cavity large, but the walls thin; the os transverse and broad, and the neck projecting very little into the vagina. Larkin said that the general appearance of the uterus was most inconsistent with virginity, which fact, also, was to a great extent borne out by the appearance of the skin of the lower part of the abdomen. This showed here and there amidst the decomposition one or two white lines in the hypogastric region, and other marks of a darker colour, near to and in the inguinal region, apparently the remains of the peculiar violet lines which, together with the above-mentioned *linea albicantes*, are peculiarly characteristic,

hen taken in conjunction with other evidence, of delivery having taken lace at some more or less remote period; and what seemed to bear out his idea more strongly was the fact, that the decomposition had progressed more rapidly with the little raised portions of integument between the icatrix-like lines than at any other part of the whole trunk, or upper part of the thighs, where the surface of the skin was even. The dimensions of he womb were in every way enlarged; its measurements were—extreme ngth 3 inches; width at fundus 2½ inches; cervix, upper part 1⅜ inches, wer part 1½ inches; thickness ⅝ inch; length of cavity 2½ inches, breadth tween Fallopian tubes 1½ inches, centre 1 inch, lower orifice ¼ inch, thick- s of cervix ¾ inch, width ⅞ inch. The weight of the womb was 12 chms. It was so flaccid that the most trivial manipulation sufficed to r its shape.

In 1879, in the case of *Mrs. Thomas*, who was murdered at Richmond *Kate Webster*, the identification of the body was made, spite of its ection, the boiling of portions of it in a copper, and the entire absence ie head, which was never discovered.

The identity of the bodies of soldiers and sailors has been sometimes blished by the existence of marks on the skin, such as anchors, stars, als, &c., indelibly impressed in the structure by colouring matter. presence of mothers' marks (nævi), or of scars from wounds or injuries ived many years previously, and situated in particular parts of the r, have also proved the means of identification. Cicatrices from ding, cupping, or from vaccination, should be noticed at these examina- s; also whether there are any scars or depressions in the skin indica- of small-pox.

It is not often that a question arises whether a portion of a body found hat of a human being or of an animal. In 1838 that which was at supposed to be a human hand was found in a dust-bin in the City. as alleged that a murder had been perpetrated, and an inquiry took e at the Mansion House in reference to the supposed atrocious crime. ie doubts were raised whether the relic produced was really the hand human being. In order to have these doubts removed, it was sent to Thomas's Hospital for the inspection of Solly and other medical men, n it proved to be the fin or paddle of a turtle.

Exhumation of Skeletons.—It occasionally happens that medical investi- ions are required to be made so long after interment, that all the soft ts of the body are destroyed, and nothing but the entire skeleton or a bones may be discovered. In either case numerous important questions arise affecting identity as well as the mode of death. Indications nurder or violent death may be obtained long after the entire destruc- of the soft parts. Briand relates the case of a woman, whose body disinterred after eleven years' burial. It was believed and alleged t she had been murdered, and her body afterwards buried by her rderers. This was found completely reduced to a skeleton, but never- less the third, fourth, fifth, and sixth cervical vertebræ were still d together by a dark-coloured mass derived from the decomposition the fleshy parts of the neck; and this mass was still surrounded by eral folds of a cord, which had been employed as the means of strangu- ion. Proof was thereby obtained of the mode in which the murder had n perpetrated. It was also possible to determine the length and our of the hair, the state of the teeth, and the form and length of the ses. A ring was found on the bones of one finger, which left no doubt atever of the identity of the deceased.

In 1829, a man named *Guérin* was condemned at the assizes at Ver- lles for the murder of his brother. The murder had been perpetrated

on Aug. 21, 1825, and the body had been buried in the corner of a d cellar. The exhumation of the remains took place three years a interment, and it was ascertained by inspection that the deceased been destroyed by blows on the cranium with a bruising instrumen large surface, and the identity of the deceased was clearly made ou the disposition of the teeth, the malformation of the vertebral column, the curved form of the bones of the legs. All these facts were depose by witnesses.

The case of *Eugene Aram*, although of old date, also furnishe instance of the necessity for closely examining skeletons when it is suspe that the individuals have died from murderous violence. This man spired with another to murder a person named Clarke. The dece suddenly disappeared in Feb. 1745, and his absence could not be accou for. In 1758, *i.e.* thirteen years after his disappearance, some bones accidentally discovered in a cave near the town where he lived. An accomplice was arrested on suspicion; and, losing his presence of m when charged with the murder, he denied that those were the bones, mentioned the spot where the bones of Clarke were buried. A skel was there found, and the traces of a fracture and indentation of a temp bone were plainly perceptible. The manner in which the murder committed was confessed by the accomplice, and the medical evid corroborated this confession. Aram, who was a man of some ab argued in his defence that it was impossible to identify a skeleton a the lapse of thirteen years; that the fracture of the skull and the pie bone beaten inwards proved nothing; that it might have lain long in cave where it was found, which had been a hermitage, and therefo likely place of sepulture in ancient times; and that the violence to skull might have been produced in times of disorder, when in searc for treasure, the graves and coffins of the dead were violated. He positively denied the conclusions as to the sex of the skeleton; but objection was entirely set aside by the medical evidence. In spite of ingenuity of this defence, the facts were too strong against him, an was convicted and executed.

Aram's defence throws some light upon the questions of doubt w are apt to arise when evidence is given from the examination of exhu bones. Thus, for example, we find three points strongly urged, invol the consideration of the time required for the destruction of the skel and therefore of its identity: of the form, situation, and appearance fracture of a bone, so as to enable a medical witness to determine wh it be of recent or of old standing, and whether it was likely to have caused by accident previously to or during the exhumation, or had a from the direct application of violence to the skull during life. Last clear determination of the sex may be required from an examination o bones. This, of course, is material to identity, and therefore one of first circumstances to which a medical witness should direct his attenti

Perfect has reported a case which shows the importance of att ing to *sex* in exhumed skeletons. Two brothers lived together in a f in the neighbourhood of London. The younger of the two was diss and irregular in his habits, so that they lived unhappily. One win night, when the ground was covered with snow, the younger bro absconded from the house by letting himself down from his cha window; and when he was missing the ensuing morning, his footsteps clearly traced in the snow to a considerable distance, but there wer footsteps of any other person. Time passed on, and nothing was afterwards heard of the missing brother. The elder brother left the f and it passed into the hands of a stranger. During the progress of s

lterations in the grounds surrounding the house, a skeleton was dug up. t was immediately conjectured that the one brother had murdered the ther; an investigation was called for, and an inquest was held. erfect, who was not summoned as a witness, requested permission to amine the bones. Having disposed them in their natural order, he found at they represented a person of short stature; and from the obliteration f the sutures of the skull, and the worn state of the crowns of the teeth, e inferred that they must have belonged to an aged person. On examin- g the bones of the pelvis, it was perceptible that they had belonged to a *male*. When this fact was communicated to the jury, the two medical en, who had given their opinions from a hasty examination, were sent for, d one of them immediately corroborated the statement that the skeleton d belonged to a female. The proceedings were of course at an end, and heavy suspicion, amounting to a charge of fratricide, was thus removed om an innocent man. On further inquiry, it was ascertained that the nes had been removed from an old gravel-pit, where gipsies had been ustomed to assemble and occasionally bury their dead.

From the examination of many reported cases in which medical evi- nce has been required on these occasions, it appears that the circum- ances to which inquiries have been especially directed are the following:—

1. Whether the bones are those of a human being, or of some animal. If of a human being, whether of a male or a female. Having thus r established their identity as part of a human skeleton, some subordi- te questions may arise respecting them. 3. The length of the period uring which they have probably remained in the ground. 4. The robable age of the individual to whom they belonged. If the upper and wer jaws be found, we shall derive much assistance in solving this ques- on by an examination of the teeth. 5. The probable stature of the dividual when living. 6. The race to which he belonged: for, from the ixed nature of our population, even this may become a material question relation to the guilt or innocence of an accused person. We are then ound to examine the bones for certain special characters, the observation f which may be necessary to throw a light upon the general evidence; hile inattention to them, or a misinterpretation of them at the time of amination, may lead to the defeat of justice, and to the censure of the edical witness. 7. It should be determined whether solitary bones belong o the right or left side of the body, and whether they form parts of one, or f more than one skeleton. 8. Whether they have sustained any mechanical jury during life, *i.e.* whether at any antecedent period they have or have ot been fractured; and if a fracture has existed, whether this has occurred aring life or by accident during the exhumation: if during life, whether t be recent or of old standing. 9. The presence or absence of personal eformities, the presence or absence of supernumerary fingers or toes, of curvature of the spine, of a curvature of the bones from mollities ossium, r of anchylosis (union) of one or more joints. 10. Murderers sometimes ttempt to make away with their victims by burning the bodies; it should herefore be determined whether the bones have or have not undergone alcination. This especially applies to cases of infanticide. Sometimes ut a very small portion of the fœtal skeleton can be procured for the ormation of a medical opinion.

Other points of circumstantial evidence also demand attention—the osition of the bones when discovered in the ground, whether lying at full ength or grouped together confusedly. In bodies which have undergone Christian burial, the skeleton is found lying at full length, usually with the ead to the west and the feet to the east, and one skeleton may be found elow another. By an attention to these points, the locality has been at

once identified as the site of a burial-ground, where bones have been di covered during excavations for the foundation of new buildings. Th inference is confirmed when the bones of persons of all ages and both sex are found in or near the same spot. In 1866, a remarkable discove was made at Milcote, near Stratford-on-Avon. Within two feet fro the surface of the soil upwards of two hundred human skeletons we found. They were placed closely side by side upon their backs, with the feet to the east and their heads to the west, and all were well preserve There were young and old, and skeletons of both sexes, the bones presentin no marks of injury from weapons. This was no doubt the site of a ancient but long-forgotten burial-ground. In pre-historic times, the bo was consigned to a stone chest in a sitting posture, with the arms clasp about the knees. Thus, in these ancient graves, the skeleton has be discovered with the thigh-bones folded on the chest. It is not unusual find human mixed with animal bones. The author procured from a de grave in an old cemetery the bones of a horse mixed with the bones of a m human skeleton. Occasionally, in ancient times, this animal was killed a buried with his deceased owner: and probably the disinterment of the bones in old burial-grounds has given rise to the fables of giants. In o cemetery in the vicinity of London, the bones of the horse were frequent found, when the excavations were carried on to a great depth. The bon of the ox have also been met with in graves mixed with human bon The author had sent to him the upper part of the thigh-bone of an ox, whi was dug out of a deep grave in a country churchyard: it was forward to him as an unusually developed thigh-bone of a human being.

Identity is sometimes strikingly made out by the presence or absen of the teeth, by their form, position, worn appearance, and the numb that may be deficient: and if absent, whether removed recently or lo before death. The examination of the teeth often aids considerably in t determination of the age of a skeleton. The discovery of certain artic of clothing, known to have belonged to a missing person, in associati with the bones of a skeleton, will sometimes remove any doubts that m arise on the subject of identity (see case of *Lane*, p. 135). Metal butto brooches, or rings, are imperishable, and should be sought for by sifting washing the earth. In *Reg.* v. *Platts* (Derby Lent Ass. 1847), the prison was charged with the murder of a man named Collis. The deceased h not been seen alive since Dec. 7th, 1845. On Aug. 28th, 1846, some m in cleaning out a cesspool in the neighbourhood, found some human bon with certain articles of dress, which were supposed to be those of t missing man. Besides the ribs, there were two thigh-bones, and two l bones. The flesh readily came off the bones and fell into the soil. Wi these remains, there was the ordinary dress of a man—namely, coat, h trousers, and neckerchief, including two garters, one red and one whi These were still around the bones of the legs. Walker stated that had examined the bones, and found them to be those of a male hum being, from twenty-three to thirty years of age. All the bones w complete excepting a few belonging to the neck, and three ribs. examining the skull, he found a deep fracture in the region of t forehead five inches in extent. There was another fracture over t left eyebrow, and a third across the base of the skull. These fractur in his opinion, were inflicted on the body while living. The oth bones, which appeared to have been separated by the yielding of the li ments as a result of putrefaction, presented no marks of violence. T injuries to the skull were produced by some cutting or sharp-edged inst ment. They were sufficient to cause death, which might have taken pl either immediately or after some time. The clothes were identified as th

orn by the deceased at the time of his disappearance, and the white and ed garters found round the leg-bones were identified by a woman who ade them, and gave them to the deceased.

The prisoner was connected with the act of murder by a chain of circumtances. On Dec. 7th, he was seen with a hammer in his hand quarrelling ith the deceased. At a later period, he was seen with two men pushing he deceased, who appeared to be in a stupefied state, into his shop. On the ight following he was seen in company with two men carrying a heavy abstance in a sack, in the direction of the cesspool in which the skeleton as afterwards found. The prisoner had made false statements respecting he transactions between himself and deceased, and the watch and boots of he deceased were traced to his possession. The deceased had been seen ith the watch up to within half an hour of his disappearance. For the efence it was contended that there was not sufficient proof in law hat the remains found were really those of the missing man. The nding of some portions of the clothes of the man in the cesspool was ot sufficient to prove the *corpus delicti*—the murder. There must be ositive evidence that the remains were those of Collis. Patteson, J., overuled the objection, observing that the identity of the remains was altoether a question for the jury. It was further contended for the defence, hat there must not only be clear proof that the remains were those of the eceased, but it must be proved that the deceased had died by the act of he prisoner, and not from any accidental cause. The prisoner was onvicted.

But for the discovery of the clothes, more particularly of the two ifferent coloured garters round the leg-bones, the identity in this case ould not have been satisfactorily established. The suggestion that the eceased might have fallen into the cesspool by some accident, was negaived by the fact that had this occurred, the watch and boots would have een found with the remains, whereas these articles were traced to the ossession of the prisoner. It is worthy of note that in this case the ead human body, in clothes, was reduced nearly to the state of a skeleton ithin the short period of nine months. This must be ascribed to the nfluence of the putrescent animal matters by which it was surrounded. hat the bones had not been for a longer period in the place where they ere found, was proved by the fact that the cesspool had been cleared out nly a short time before the disappearance of the deceased.

In July 1863, the bones of a child were found in a nursery-ground at slington, under suspicious circumstances. It appeared that a girl named *lizabeth Hunter*, aged eight years, had been missing from the neighbourood since March 30th, 1862, and it was important to establish, if possible, hat these were the bones of a female child of the age of the deceased. Until the skull was found it was supposed that the bones were those of a og, but their human character appears to have been ultimately established y the discovery of the skull with some hair, and also of the lower jaw. he medical witness at the inquest assigned the age at from eight to ten ears, but could not well define the sex, as at this early period the sexual ifferences on the pelvis are not well marked. The articles of clothing ound with the body served, however, to establish the sex, as well as the dentity of the bones with those of the missing child. The remains had he appearance of having been longer in the earth than sixteen months, but t seems they were only superficially covered, and this might account for he rapid destruction of the bones and soft parts. It is probable that the ones of young persons decay more rapidly than those of adults. Cases nvolving medico-legal questions on the exhumation of skeletons after arious periods of interment will be found in the 'Ann. d'Hyg.,' 1834, 1,

117; 1836, 1, 214; and 1845, 1, 379. See also Friedreich, 'Ueber die Knochen in foren. Bezieh.' Ansbach, 1853.

Human and Animal bones.—The greatest ignorance prevails among the public on this subject. The bones of horses, cows, dogs, and sheep are frequently mistaken for those of human beings. In an antiquarian collection of relics obtained from a neighbouring Roman castrum, the author saw, some years since, the tibia of a dog carefully labelled and religiously preserved as a bone of an ancient Roman. The same collection contained fragments of bones of various animals, carnivorous and herbivorous, all marked as human relics. This collection belonged to an antiquary who had preferred adopting his own view of the nature of the relics, to taking the opinion of any one acquainted with anatomy. In a church in the north of England two bones from oxen were shown as the thigh-bones of St. Lawrence. They were of ancient date and greatly prized by the sexton. Even well-informed men may be easily mistaken on such subjects. Belzoni, the celebrated traveller, brought from Egypt, with his sarcophagi, a number of bones taken from the interior of the pyramids, which he pronounced to be the bones of King Cephrenes, and of some of the Shepherd kings. Clift examined them after they had been submitted to public exhibition, and he found that they were the bones of oxen. The osseous relics of saints, as they are collected and preserved in glass and crystal cases in Roman Catholic countries, often present anomalies which would surprise an anatomist. Supernumerary ribs and vertebræ are not uncommon, and intermixed with them bones which certainly never appertained to a human being. In the medico-legal returns for India 1868–9, it is stated that on one occasion as evidence of an important murder some bones brought from a distance of thirty miles with the usual formalities and precautions as to identity, proved on examination to be those of a bullock, and on another occasion the remains turned out to be those of a goat. These facts show the importance of entrusting the examination of bones, in all judicial inquiries, to well-educated medical men. The lower classes of society are ever ready to suspect murder when bones are exhumed; and it will not always be easy to satisfy them that the bones exhumed could not have belonged to a human being.

The lamentable effects of popular ignorance on this subject were displayed in a case that occurred at Damascus in 1840, which at the time excited great public notice. A Roman Catholic priest, with his son, suddenly disappeared in the early part of that year, and a strong suspicion arose that they had been murdered. Certain Jews were charged with having murdered the father and son for horrible purposes. The sewer in the quarter of the town in which they lived was examined, and some bones were there found. These were pronounced by the persons who discovered them to be human bones; and the discovery was considered to confirm the suspicion of murder which had arisen. Several of the accused Jews died under the tortures to which they were subjected. It seems that the state of anatomy was at that time so low in Syria, that there was no one in the country competent to solve the question whether these were really animal or human bones. Some persons who inspected them, pronounced that they must have been lying in the sewer for a great length of time, and that they had belonged to an animal. A proposition was then made that the bones should be forwarded to the Parisian Academy of Medicine, for their decision. It was subsequently proved that they were animal remains. Such a case is not likely to occur in England, for there are few professional men who would not be at once able to pronounce an opinion even from the examination of a fragment.

It will be, in most cases, easier to say whether a particular bone has

ned part of a human skeleton or not, than to determine to what animal nay have belonged; this is commonly all that is expected from a dical witness. A moderate acquaintance with osteology will enable a to give an affirmative or negative opinion: but where part only of the ft of a bone—as of the humerus, radius, tibia, or fibula—is produced, ne caution is required in forming a judgment. It will not be necessary this place to describe all the peculiarities of human bones, but rather to nt out certain well-marked differences which are observed to exist ween the bones of man and animals.

With respect to the *skull*, the foramen magnum in all animals, except ape tribe, is placed very far back, and has its posterior edge turned ards. In the ape tribe, and especially in the ourang-outang, it is er to the centre of the base of the cranium than in any other animal, is more nearly on a level with the plane of the base of the skull. animals, including the ourang-outang and ape tribe, have two bones ie face, in addition to those found in man. These are situated between uperior maxillary bones, and are called intermaxillary bones, or, from holding the incisor teeth, the ossa incisoria. The suture which rates them from the maxillary bones becomes obliterated in some of animals at an early period; but still traces of it may be seen. To e of the facial angle as a mark of distinction is quite unnecessary; dical opinion can never be required except in those cases where only one, or the fragment of a bone, is presented for examination. The r jaw in animals is destitute of a protuberance corresponding to the ; it is also longer, in proportion to the cranium. The condyles of the vary in shape according to the nature of the food.

The trunk calls for no particular remark. The *vertebræ* are strikingly nguished by their form, and by the direction of their spinous and verse processes. Their bodies are longer, and deeply grooved laterally, vertical direction. The sacrum is generally narrower in proportion in man; it is wide in those animals which occasionally stand erect, a the ape and the bear, but it is also in these animals longer. The s is in all cases much elongated, is narrower, and has less of a basin-appearance, the level of the brim having a much greater obliquity in man. The *thorax* of animals without clavicles is commonly com-ed at the sides, so as to render it much deeper from the sternum to spine. This is especially observed in the dog, cat, bear, and in long-ed animals. The ribs, or fragments of ribs, might perhaps be occasion-confounded. Most mammalia possess more ribs than are found in man, number corresponding to that of the dorsal vertebræ. The ribs vary h in form, but in herbivorous animals they are generally broad and t; in the bear and dog they are more rounded. The sternum or chest-of the ourang-outang somewhat resembles that of man; it is flat but owed, and the division of its pieces is more apparent: in all other als it differs in being considerably narrower, more or less of a rounded , and in being evidently composed of many moveable pieces. Most lrupeds want clavicles: they exist in the ape tribe, and very much mble those of man, so that the clavicle of the ape might be easily mis-n for that of a young child: in the dog and cat, there is a clavicular suspended in the muscles. The scapula or blade-bone of animals, ding the ourang-outang and ape, is much longer in proportion, and is equally divided by the spine, the fossa infra-spinalis being much ler in proportion than in man. The *humerus*, or arm-bone, of animals, served to become short as the metacarpus is elongated: in the ape , it very closely resembles that of man. In apes the bones of the arm have the same general appearance as in man; but the two bones

are long and slender, and the radius is as long as the ulna. In all carnivorous animals, the olecranon is extended farther back, and is more irregular than in man. The carpus, or wrist, in apes, has one bone more than in man. The size and strength of the thumb are much greater in man than in any animal. Even in the ape tribe, although separate and opposed to the other fingers, the thumb is very small and much shorter than in the human species. The *femur*, or thigh-bone, in most quadrupeds is so short that it scarcely projects beyond the abdomen: it varies in length according to that of the metatarsus. The neck of the thigh-bone is remarkably short, but the great trochanter rises considerably above the head of the bone even in the ape tribe. In some animals, as in the horse, the trochanter ends in an unciform process projecting above the head of the bone. In the ourang-outang, the thigh-bone is straighter than in man, while in the bear it closely resembles the human bone. The bones of the leg in the ourang-outang are nearly as in man, but the *tibia*, or leg-bone, is in general considerably longer than the femur. In the bear it preserves a proper proportion. In the ape tribe, these bones are nearly of equal length. In the dog, the fibula is placed behind the tibia, and is attached to it in its lower half. In the horse, the fibula forms merely a kind of splinter anchylosed by age to the upper part of the tibia. In ruminants, the fibula is wanting: in the pig it is anchylosed to the tibia throughout its whole length. In apes, while the great toe is shorter than the rest, the smaller toes are much longer than in man. In none of the mammalia, except man, does the foot rest completely on the ground. The os calcis generally wants the tuberosity of the heel; but this exists in the ape tribe, although to a less extent than in man.

Such are the most prominent differences assigned by anatomists to the bones of animals, and based on the observations of skeletons. It is not improbable, however, that in some cases assistance may be derived from the use of the microscope. This instrument may be especially serviceable in those cases of difficulty in which an opinion may be required from only minute fragments of bone. The Haversian canals and bone-cells (lacunæ) exist in all classes of animals which have a bony skeleton; and it has been shown that the bone-cells differ in size in the four great classes of animals. They are smallest in birds, and largest in reptiles: in the mammalia they occupy an intermediate position. In fish, they are entirely different in appearance from those existing in the other three classes. These bone-cells are said to be of the same size in the same class; thus, among mammalia, they are no larger in the bones of a horse, than they are in those of a mouse. In human bones, the cells are sometimes almost triangular in outline, at other times they have more of a linear or elongated shape. Their number is in an inverse proportion to the Haversian canals in bone. It is desirable that further observations should be made on this subject; and that differences in the microscopical structure of bone should be sought for in the human subject, and in the various orders of mammalia. Quekett ascertained that the cells of bone bore a certain relation, in point of size, to that of the blood-discs of an animal; thus, for instance, the blood-discs were found to be largest in reptiles, smallest in birds and mammalia, while in fishes they were of an intermediate size: and he further discovered that the bone-cells followed the same law. ('Med. Gaz.,' Dec. 11, 1846.) It has happened on several occasions in cases of infanticide, that great difficulty has been experienced in identifying small portions of bone, when the skeleton has been found partially consumed by fire.

When it has been proved that the bones are not those of a human being, this branch of inquiry is at an end.

Determination of Sex in skeletons.—The determination of the sex from n examination of the skeleton or of certain detached bones, can be made nly in subjects which have passed the age of puberty; for sexual differnces in the skeletons are scarcely apparent until adult age has been eached. The author has, however, seen the well-marked sexual differnces of the pelvis in the skeleton of a boy of eleven. The skeleton of the male is smaller and more slender than that of the male. The full-grown one of a female is distinguished from that of a male by its ridges, depresions, and processes being less marked,—the shaft of a long bone is smoother nd more polished, while the articular surfaces are flatter. The skull f the female is more contracted in front, and forms a longer oval from efore backwards. The chest, which is naturally shorter, smaller, and less rominent than in the male, is rather wider about the fourth rib: it then ontracts somewhat below, so that while the general shape of the chest pproaches to an oval in the female, it is conical in the male skeleton, eing wider at the base or lower part. The form of this cavity is often attened laterally to a considerable extent, owing to the pressure of the tays worn by women. This altered condition of the ribs by pressure may erve to indicate the sex. The sternum or chest-bone, is shorter, termiating opposite the fourth pair of ribs, but its upper portion is larger than n the male; in the latter it terminates opposite the fifth pair of ribs. The ribs are shorter, more slender, and less arched, and take a more orizontal course in the female; their upper and lower borders are sharper. The false ribs are proportionately larger; and the cartilaginous portions f the true ribs are longer than in the male. The shoulders are lower, nd the scapulo-humeral articulations nearer to each other. The clavicles re more slender, more round, and pass in a straighter direction to join he acromion processes. In the male they have somewhat the form of the talic *S*: they are flatter, larger, and run more directly backwards. The male scapula is thinner, smaller, flatter, and has sharper angles than that f the male. The bodies of the vertebræ are smaller, the hole for the pinal marrow and the foramina are larger; and the lumbar vertebræ have greater length than in the male.

The upper limbs are shorter, the carpus smaller, and the metacarpus and phalanges are more slender in the female than in the male. The thigh-bones have a greater curvature forwards at the upper part, and below, are turned more obliquely inwards. The neck of the thigh-bone in the female forms nearly a right angle with the shaft, whereby the trochanter major is brought more nearly on a level with the head of the bone. In the male the neck of the femur is inclined obliquely upwards, and the trochanter major is below the level of the head. In the female the internal condyles are larger; and the bones of the leg are more slender and those of the foot are smaller than in the male.

The greatest difference is observed in the *pelvis*, and it is by an examination of this portion of the adult skeleton, when it can be obtained, that the sex may be most satisfactorily made out. In the female the ossa ilii are flatter and more everted, giving to the whole pelvis a greater capacity; the os sacrum is broader, and turned more backwards; the os coccygis more slender, moveable, and turned more backwards, the space between the ossa pubis larger, and the cartilage of the symphysis broader. The angle formed by the rami of the ossa pubis with the symphysis is larger. In a well-formed male skeleton the author found the angle to be 75°, while in a well-formed female skeleton the angle was equal to 90°. The tuberosities of the ossa ischii are flatter and at a greater distance from each other. The brim of the pelvis is wider and of an oval form, corresponding with the head of a child, and the longest diameter extending between the

ilia or transversely. In the male the brim is more circular, and the greatest diameter is between the pelvis and sacrum. The foramina ovalia in the female are wider, and approach more to a triangular form than in the male, one sharp angle being at the junction of the pubis with the ischium; the acetabula are farther distant from each other. The pelvis of the female loses some of its well-marked sexual characters in advanced life.

It will be understood that these differences are for the most part relative; and some are so slight that they can scarcely be regarded as characteristic of the sexes. Great difficulty in forming an opinion will exist in those cases where only a fragment of a bone can be procured; but a medical witness is not expected to work out impossibilities: if he has a sufficient portion of a skeleton before him, he may be able to determine the sex, otherwise it would be advisable to state that the remains produced did not enable him to answer the question, and that the bone or a fragment might have belonged either to a male or a female. In a contested case of presumption of survivorship which occurred some years since, it became necessary to determine the relative weights of the adult male and female skeletons. A perfect male skeleton was found to weigh ten pounds six ounces; and a perfect female skeleton eight pounds thirteen ounces. The bones were completely dry. It may be observed that bone is the heaviest part of the human body: its specific gravity is 2·01.

Date of interment.—One of the first questions asked on the disinterment of bones, relates to the length of time during which they may have remained buried in the ground. The period at which the bones begin to undergo decomposition, will depend upon that at which the soft parts have entirely disappeared. The common opinion is, that the soft parts are destroyed in ordinary graves in about ten years. Bernt, however, mentions a case seen by Navier, in which some fleshy parts of the body remained after an interment of twenty-one years. The changes in the bones are observed to commence by the loss of animal matter, so that they become lighter; externally they acquire a dark incrustation when in contact with the earth. This dark incrustation is sometimes confined to the surface; but in some very ancient bones, the osseous shell is of a dark-brown colour throughout, like old oak. The animal matter is never entirely lost; it exists in bones which have been buried for many centuries, and may be made evident by digesting them in hydrochloric acid. Even in sawing them, the heat developed by friction brings out a peculiar animal odour. The shaft of a long bone becomes, after long burial in a dry soil, light and very brittle; it may be easily broken, and cut or scraped with a knife. It appears to be impossible to assign, with any approach to precision, the period required for the production of these changes; they vary with the age of the subject, taking place more rapidly in the skeletons of the young: they vary also with the nature of the soil in which the bones are buried, according to whether this is dry or humid, sandy, cretaceous, or clayey. Some have alleged that the bones of a person buried in an ordinary coffin are entirely destroyed, with the exception of the skull and thigh-bones, within a period of thirty years; but there are cases on record, where the skull and long bones, and even the perfect skeleton, have been found, in ordinary graves, quite perfect after a much longer period than thirty years. In general, the lower jaw of adults is preserved for a great length of time, and with it the teeth, which from the hardness of the enamel resist decomposition longer than any other parts of the body. The ultimate destruction of the bone is effected by the complete disintegration of its earthy parts, the calcium phosphate and carbonate falling into and mixing with the earth around. Bones owe their preservation to the large proportion of mineral matter contained in them. This is greater in the adult

an in the child. Von Bibra found the following proportions of mineral atter per cent. in recent bones of different ages:—In a woman (æt. 62), ·82: in a man (æt. 25), 68·97: in a child (æt. 5), 67·80: in a child of o months, 65·32: in a fœtus of seven months, 65·19: and in a fœtus six months, 59·62. The proportions in the bones of animals, are similar those of the human adult.

On the discovery of a bone, or of a skeleton, the question may be: Can have been buried for a longer period than fifteen or twenty years? uspicion may arise that they were the bones of a person alleged to have en murdered, and who had disappeared about that period. In some ses this question may admit of a ready answer. If it were the long bone an adult, and it was found to be light, friable, brittle, and easily scraped powder, it is probable that it had been interred for a much longer period an that above mentioned. We can form only a rough opinion of the eriod of interment of bones, by the presence or absence of the soft parts; marrow in the interior; by the firmness and weight, or brittleness, dry- ess, and lightness of the bone. Even these remarks can scarcely be made pplicable to bones preserved in durable coffins or vaults; for in this state ey are to a great extent removed from all the common causes of chemical hange. Devergie states that the bones of King Dagobert were found in tolerably perfect state at St. Denis, although they had been buried in a ault twelve hundred years. In the year 1868 the skeleton of William ufus was found in a stone coffin at Winchester, nearly perfect, after 780 ears' burial. The skull was in fragments, the vertebræ were almost omplete; parts of the pelvis and sacrum (showing the male characters), he bones of the arms, the femoral bones and two tibiæ were found. The ower jaw with nine teeth, the enamel apparently unchanged, was also iscovered. There were no clavicles and only six ribs, and the small bones f the hands and feet had disappeared.

In bones long buried, a portion of the animal matter is lost, the bone ecomes light and brittle, and is easily reduced to powder. In 1868, the uthor examined a portion of the scapula and rib of a skeleton which was ound eighteen inches below the surface in the sandy soil on the top of a hill. he skeleton, which was that of a female, was perfect, excepting the lower nds of the tibiæ and feet, which were decomposed. It had the appearance f having been thrust violently into the ground. There were no traces f soft parts. The teeth in the upper jaw, including the wisdom teeth, ere perfect and regular, and the age was considered to be from twenty- hree to twenty-eight years. No hair and no articles of clothing were iscovered. On analysis the bones were found to contain 72 per cent. of ineral matter, and the presence of fluorine was detected in a small quantity f bone reduced to powder. The date of interment was assigned at from fty to one hundred years.

A question which has yet to be determined is whether, as with the ssil remains of animals, human bones after long interment may not contain larger proportion of calcium fluoride than when recent. It has been scertained that the ancient bones of extinct animals contain a large pro- ortion of fluoride, while in recent bones the proportion is so small that requires a large quantity of bone to determine its presence. These edico-legal questions are likely to arise only in those cases in which he bones have been found under suspicious circumstances in an unusual cality, as in the cellar or basement of a house, or in a garden: and t will always be proper to make further exploration to see whether the ones of different persons may not be found lying near.

Determination of age in skeletons.—In regard to the remains of the oung, the age may be best determined by an examination of the jaws

and teeth, although the skeletons of the young are at once characteris by the smallness of the bones. If the jaw of a child can be found, medic evidence may be given of its probable age. In a case of alleged infan cide, there were found among the exhumed bones of two children, par of the jaws, containing the rudiments of the molar teeth, which appe about the eighth or ninth month of pregnancy. This fact showed, wh was rather important to the inquiry, that the child to whom the ja belonged must have been born at or about the full period. It may l alleged that the bones are those of a child which has been murdered but the medical witness may be able to prove, by an examination c the jaws, that the bones must have belonged to a child older or younge than that which is missing. There are numerous other cases in whic a question of this kind may become important. The determination c age by an examination of the bones of young persons, is by no means s satisfactory as by the observation of the *teeth*.

The alveolar cavities which contain the teeth are formed about th sixth month of uterine life. At birth the rudiments of the whole c the temporary teeth, and of the anterior permanent molars, are forme in capsules within the gums; and about this period, the fangs of th incisors begin to appear. Great difference of opinion exists respecting th time at which the *temporary teeth* begin to rise above the gums in a chil after birth. According to Bell, these teeth appear in the followin order:—The four central incisors in from *five to eight months;* the fou lateral incisors in from *seven to ten months;* the four anterior molars i from *twelve to sixteen months;* the four cuspids in from *fourteen to twen months;* and the four posterior molars in from *eighteen months to three year* The temporary are known from the corresponding permanent teeth b their much smaller size, by the absence of bicuspids, by the fact that th fangs diverge at a greater angle from the molars; and there is anothe and remarkable point of difference, according to Saunders, namely that the enamel at the neck is collected into a kind of ridge, instead c terminating, as in the permanent set, evenly on the fang. This is especiall apparent in the incisors and cuspids, but, as Saunders has remarked, i applies to all the temporary teeth. Between six and seven years of ag the jaws contain forty-eight teeth—twenty of the temporary set in perfect state, and twenty-eight of the permanent set more or less develope and placed behind the temporary teeth which they are to replace. Accor ing to Saunders, the order in which the permanent teeth appear is a follows:—At *seven* years of age, the four anterior molars; at *eight* year the four central incisors; at *nine* years, the four lateral incisors; at *te* the four anterior bicuspids; at *eleven*, the four posterior bicuspids; a from *twelve to twelve and a half* years, the four cuspids; and at fro *twelve and a half to fourteen* years, the four posterior molars: thus makin the total number of teeth in the jaw at this period twenty-eight. Th wisdom teeth seldom make their appearance before the age of eighteen and often not until a much later period in life. In general, the teeth the lower jaw make their appearance before those of the upper. Som irregularities may occur in the periods at which the teeth appear; but th description just given is applicable to a large majority of cases, and sufficiently correct for practical purposes.

In addition to the examination of the teeth, medical jurists are accu tomed to rely upon the progress of ossification in the skeleton, as furnishin evidence of age at the early periods of life. At *one year*, ossificati commences in the lower extremities of the humerus and ulna, in the hea of the femur and humerus, and in the upper cartilage of the tibia. A *two years*, ossification takes place in the lower cartilage of the radius, an

the tibia and fibula. At *two years and a half*, it takes place in the eater tuberosity of the head of the humerus, in the patella, and in the wer ends of the four last metacarpal bones; at *three years*, in the tro-anters; at *four years*, in the second and third cuneiform bones of the rsus; at *four and a half years*, in the small tuberosity of the head of e humerus, and the upper cartilage of the fibula; at *six years*, the scending ramus of the pubis meets the ascending ramus of the ischium. t from *eight to nine years*, the upper cartilage of the radius becomes sified. At *nine years*, the ilium, ischium, and pubis, meet in the cotyloid vity to form the pelvis. At *ten years*, ossification begins in the cartila-nous end of the olecranon; at *twelve*, in the pisiform bone of the carpus; *thirteen*, the three portions of the ossa innominata bone still admit of paration into ilium, ischium, and pubis, although nearly united; the neck the femur is ossified. *At fifteen*, the coracoid process is united to the apula; and *between fifteen and sixteen*, the olecranon to the ulna. From *teen to twenty*, the epiphysis at the upper end of the thigh-bone is joined the body of the bone; as well as those belonging to the metacarpus, tatarsus, and phalanges. At *twenty*, the upper and lower epiphyses of e fibula, as well as the lower epiphysis of the thigh-bone, are respectively ited to the bones. At *twenty-five years*, the epiphyses of the sternal end the clavicle, and of the crista ilii, are united to the bones. This account the progress of ossification may be taken as a representation of average ults. In the cavity of the skull of young persons, the furrows produced the convolutions of the brain and by the vessels, are commonly very ongly marked on the bones.

When ossification is once completed, it is difficult to determine the age an examination of the bones. That the person has reached *adult age*, ll be indicated by the union of all the epiphyses to the bones, by the at firmness and solidity of the bones, with their rough surfaces for the tion of muscles, their well-marked processes, grooves, and foramina. the jaws, we may expect to find the wisdom teeth; while the other teeth ll probably be found much worn, although this last sign is not of any at importance. The lower jaw forms a great angle, being somewhat an elliptical form, and is strongly contrasted with the semicircular shape the jaw at an early period of life; the sutures are also closed, and are nd in some instances nearly obliterated.

The bones of an old person are generally lighter than those of an adult the same size, the medullary cavities of the long bones being larger. The nes lose that ivory-looking character which they have in adults, become llow from the quantity of oil which they contain, more earthy, and brittle. ose parts of the skeleton which are cartilaginous in adults, are commonly re or less ossified in old age. The bones of the cranium are thinner; the tures entirely disappear, first on the inside, and then on the outside of the ull. The teeth have either dropped out, or the crowns are worn away to e sockets. Sometimes no trace of alveolar cavities is to be seen, the wer jaw being a mere rounded bone, with a smooth surface on each side. remarkable case occurred in 1869, which shows the necessity of using treme caution in giving an opinion respecting the age of bones, and of lowing sufficient latitude in years for the bones of adults. In 1851, merous portions of a mutilated human body, consisting of flesh and nes, were found around the suburbs of Norwich. The portions of ne found belonged to one body, and the pelvis and thigh-bone as well as portion of the breast and skin, showed that it was the body of a woman of ult age. The opinion then given from the bones was that the deceased s a 'young adult female' between sixteen and twenty-six years of age. bout eighteen years after this discovery, a man of the name of *Sheward*

confessed that he had murdered his wife at Norwich in 1851, that he had cut the body to pieces and disposed of the mutilated portions in the suburbs. It appeared further that his wife had really disappeared about that time, and had never been seen since; but she was a woman in her fifty-fourth year; and without some strong corroboration the man's confession could not be received against himself. The facts all concurred to show that the remains found in 1851 must have been those of the missing wife, the only circumstance opposed to this view being the medical opinion given at the time that the bones were those of a woman considerably younger than the deceased. The man was tried for the murder (Norwich Lent Ass. 1869, *Reg.* v. *Sheward*), and the medical witnesses who had given their opinion respecting age were cross-examined on this point. They admitted that the remains might have been those of the deceased woman. Indeed every fact in the case pointed to this, and the confession of the prisoner (subsequently withdrawn) was so far confirmed, that the prisoner was convicted. There could be no doubt that a mistake had been made in limiting the age to twenty-six. The correctness of the verdict was proved by the confession of the prisoner after conviction. The mutilation had been carried to that extent that even the ring-finger had been cut off, and portions of flesh had been found which had apparently been immersed in hot water. The prisoner stated in his confession that he had endeavoured to get rid of some portions of the remains by boiling them. The same condition was observed in the Waterloo Bridge case (p. 131). The state of the remains indicated death within a week or ten days of their discovery; this was also confirmed by the prisoner's confession. The prisoner, after committing the murder, occupied about a week in disposing of the mutilated remains. He cut the long hair into short portions, and scattered it to the winds as he walked along the roads.

Identity from the teeth.—Observations carefully made on the state of the jaws and teeth may have an important bearing in cases of disputed identity. The loss of particular teeth, the presence of supernumerary teeth, or the entire absence of teeth for a long period, may, if noticed by the medical inspector, lead to the removal of many difficulties in the identification of skeletons. An instance of this kind occurred some years ago. It was a trial for murder under circumstances in which the body was never discovered, and in which, as it happened, an important question of identity arose, founded on the presence of the incisor teeth in a female of advanced age. The case was that of *Elizabeth Ross*, who was tried at the Old Bailey Sessions in Dec. 1831, for the murder of a female of the name of *Caroline Walsh*.

It appeared in evidence, that the deceased, Caroline Walsh, an old Irishwoman, had been repeatedly solicited by the prisoner to come and live with her and her husband, but refused. By much persuasion on the part of the prisoner, however, she at last consented, and went for that purpose to the prisoner's lodgings in Goodman's Fields on the evening of Aug. 19th, 1831, taking with her, her bed and an old basket, in which she was accustomed to sell tape and other articles. From that evening all traces of the deceased were lost; and when the prisoner was required by her relatives to account for her disappearance, she prevaricated, but finally asserted that deceased had gone out early on the morning of that day, and had not returned. The testimony of the prisoner's son, who was the chief witness for the Crown, went to prove clearly, that the deceased had been wilfully suffocated on the evening of her arrival, by his mother (the prisoner) placing her hands over the mouth of the deceased and pressing on her chest. He deposed that on the following morning he saw the dead body of the old woman lying in the cellar of the house, and

on the evening of the same day, he saw his mother leave the house with something large and heavy in a sack.

Now it happened most singularly that on the evening of Aug. 20th, the day following the alleged murder, an old woman of the description of the supposed deceased, was found lying in the street in the immediate neighbourhood, in a completely exhausted condition, and in a most filthy and squalid state. On being questioned she stated that her name was Caroline Welsh, and that she was a native of Ireland. Her hip was found to be fractured, in consequence of which she was conveyed to the London Hospital, where she subsequently died, and was buried. The prisoner Ross, when apprehended, asserted that this was the female whom she was accused of having murdered. Hence, setting aside the direct contradiction given to this statement by the evidence of her son, it became highly important, for the ends of justice, that the identity or non-identity of the two women should be clearly established.

The extraordinary resemblance of names, and the exact coincidence of time and place, struck every one in Court; but by the examination of about twenty witnesses, the following points of difference were elicited. It was proved that they were both Irishwomen, but Caroline Walsh came from Kilkenny, Caroline Welsh from Waterford. The former (the alleged murdered person) was eighty-four years of age, tall, of a sallow complexion, with grey hair, and had (an extraordinary circumstance for her years) very perfect incisor teeth. The latter, Caroline Welsh (who died in the London Hospital) was about sixty years of age, tall of stature, dark like a mulatto, but had no front teeth; in addition to which it was deposed by a medical witness that the alveolar cavities corresponding to them *had been obliterated for a considerable time.* The witness brought the skull and jaw into Court—for the body had been purposely exhumed for this examination—but the judge, Lord Denman, would not allow it to be produced, and said he would be satisfied with the witness's statement respecting the condition of the jaws.

Other circumstantial points of difference were deposed to—as, for example, Caroline Walsh was healthy, cleanly, and neat in her person, and her feet were perfectly sound. Caroline Welsh was considerably emaciated; she was in a dirty and filthy condition; her hip was broken, her feet were covered with bunions and excrescences, and one toe overlapped another. The dress of the two women was somewhat similar. That of Caroline Walsh was proved to have been sold by the prisoner Ross to different persons; and almost every article was reproduced in Court, and sworn to by witnesses. The clothes of Caroline Welsh were proved to have been burnt by order of the parish authorities. Both of these women had similar baskets in their possession; that of Caroline Walsh had no lid or cover, while that found on Caroline Welsh had a cover. Lastly, the body of the latter was taken up from the burial-ground of the London Hospital for the purpose of identification, and it was sworn by two of the grand-daughters of Caroline Walsh not to be the body of their grandmother.

This is a singular case of disputed identity. We have a coincidence of name, time, place, age, occupation, and circumstances, so extraordinary that but for two circumstances it is probable the prisoner would have escaped on the presumption of a mistake, the body of the deceased not having been found although all the dissecting-rooms in London were repeatedly searched for it. These circumstances were—1st. That the relatives of the deceased swore that the exhumed body was not that of the missing woman; and 2nd, the medical proof of the entire obliteration of the alveolar cavities in the jaw of the exhumed body, proving that the

incisor teeth must have been lost long before death, while t witnesses testified to the presence of these teeth, as a striking pec in the missing old woman. Even had the features of the exhume been obliterated by putrefaction, the non-identity would have been lished by this medical fact. The prisoner was convicted.

In 1864, a man named *Weekly Ball* was charged with the mu a woman named *Lydia Atlee*, with whom he had cohabited. It that, while in the last stage of pregnancy, she had suddenly disa on July 22nd, 1850, and was never seen again. It was rumoured t had been murdered, and the prisoner, who, it was alleged, had a motive for getting rid of her, was suspected of the act; but no leg could be obtained against him, and the matter dropped. On Feb. 3r as a labourer was digging in a lane, by the side of a ditch n village of Ringstead, in Northamptonshire, were deceased and the had lived, he found a human skull and ultimately a skeleton, lying length with its face downwards. The medical evidence at the ma inquiry was to the following effect:—The skeleton was lying in a about twenty inches below the surface of the ground in a swan The feet were close together, the heels touching each other. Fro facts Mr. Leete expressed an opinion that the body must have bee naked. The skeleton, when laid out, was that of a middle-aged about five feet two inches in height. The bones were complete, e the right thigh-bone and skull, which were broken in their r He considered that the skeleton had been in the earth from tv twenty years. The missing woman was far advanced in pregna no *fœtal bones* were found. In reference to this, the surgeon stated bones of a fœtus contained more animal matter, and might ha decomposed, although he declined to swear that within the p fourteen years they would have entirely disappeared. No hair wa although sought for, and no traces of clothes of any kind could covered; but there was a singular fact connected with the lower which it was supposed the skeleton could be identified as that missing Lydia Atlee. A witness stated that a *fortnight* before the was missing, he drew on the left side the first molar tooth fi lower jaw. When the exhumed jaw was shown to him, thi was absent, and he affirmed that that was the place where he d tooth. He thus appeared clearly to identify the skeleton as tha missing woman. The evidence of other witnesses was adduced that on the evening of July 22nd, 1850, the accused and Lydia At seen to go together into an orchard at the back of the accused's They were overheard quarrelling, and the woman's voice was id muttering the words, 'I believe you mean killing me to-nig appeared that the skeleton was found buried about a mile fr orchard. Markham said in reference to the pregnancy of the w it was a nine months' fœtus, some of the fœtal bones ought to ha found with the skeleton; the hair might have disappeared in years. With regard to the lower jaw, he observed that if the to extracted, it could not have been removed long before death. Th was partly filled up, a fact which might however be explained tooth having been extracted without one or all of its fangs.

Although the identity of the skeleton, as that of the missing was thus left a little uncertain, the accused was committed for In the meantime the ground was again searched for fœtal bones, result was that, about eighteen inches deeper in the earth, the ske a full-grown man was found, foot to foot with that of the female s above. That of the man was lying on its back, and the bones appe

have been much longer in the ground. On this discovery, it was suggested that the spot might have been a gipsy's burial-place, in which one body was laid in a grave over another without the ordinary clothing. That the accused should select a spot a mile away from his dwelling for burying the body of a woman whom he had recently murdered, and that he should then place the body at full length, over another dead body just below it, was most improbable. The entire absence of the fœtal bones was another fact adverse to the alleged identity. The author was assured by an eminent dentist who examined the lower jaw, that the tooth, supposed to have been drawn a fortnight before death, is one of the most common teeth to be absent in the jaws of middle-aged persons, and further, that it might have been removed from the jaw for three or more months before death. There was nothing by which a more recent date could be fixed, as part of the cavity had been filled up by the usual osseous structure. At the assizes, the accused was discharged on bail.

Questions of identity may turn, not only on the number and nature of the natural teeth, but also on the presence of artificial teeth, with the mechanical appliances for securing them. On the trial of *Webster* for the murder of Parkman, the evidence given by a dentist, Keep, established the identity of the mutilated remains of the deceased, in spite of an attempt which had been made to destroy the jaws by fire (p. 130). He deposed that about four years previously, he had made and fitted for Parkman sets of artificial teeth in blocks for each jaw. He saw Parkman with these teeth in his head, for the last time, about a fortnight before his disappearance. He then put a new spring to the teeth. He recognized the artificial teeth, taken from a furnace, by certain peculiarities about them, and also by their fitting the original plates and moulds, which he retained in his possession. The gold plates attached to them had been melted in an assay furnace, in an attempt to destroy the head of the deceased, but the greater part of this gold was recovered, and the artificial teeth, to which the gold plates had been fastened, had acquired a pink colour from a portion of the finely divided metallic gold, showing that they had been submitted to a high temperature, but had not undergone fusion, although minute particles of gold were fused into them. The left side of the lower jaw presented a great natural irregularity. The block corresponded to this, and thus placed the identity of the jaws beyond dispute. ('Report of Trial of Prof. Webster,' Boston, 1850, p. 50.) Dental peculiarities frequently serve to assist identification. In the 'Medico-legal Returns for India' (1868–9), it is stated that a wife was able to swear to the identity of her husband's skull, shown to her in open court, from a peculiarity of the incisor teeth of the upper jaw, brought to notice by the civil surgeon. It seems that these cases of identity from bones are very common in India. The records of 1869 contain nineteen reports upon bones and fragments. The character of the fragments were very various—a skull and a few bones picked out of a river, pond, or well, or gathered out of a jungle. In one of these cases an imperfect skeleton, alleged to belong to a man murdered eighteen days before, was brought for examination, and found to be the remains of a woman.

The importance of the teeth as a means of identification of deceased persons was well shown in the case of the late French Prince Imperial, in 1879. The body had been so much disfigured by his assailants that identification would have been extremely difficult but that the prince had had four small cavities in the first molar teeth filled with gold, and had met with a slight accident from a blow on the front teeth, which had made it necessary to file them a little, in order to smooth the enamel. These constituted signs which are unalterable even by ages, and they afforded

an unerring means of identification, which, in this instance, was of great value.

Bones and teeth which have been long buried may, by percolation of water through the soil, become impregnated with ferric oxide, calcium sulphate, or magnesium and calcium carbonates. They are heavy, of a dark brown colour, and generally contain much lime and iron, with calcium fluoride. In some bones, disinterred near one of the plaster quarries of Paris, Lassaigne found, besides 66·7 of the usual mineral constituents, 2·3 per cent. of calcium sulphate, with traces of ferric oxide. Other bones of soldiers killed in 1814, and buried near the same spot, yielded 56·1 of calcium phosphate and carbonate, 0·5 of sulphate, and 8·2 per cent. of argillaceous sand. These bones had been buried for a period of thirty-three years. They contained 15 per cent. of animal matter and 20 of water. Those taken from the plaster quarry contained the same quantity of water, but only 11 per cent. of organic matter. ('Ann. de Chim.' 1847, p. 759.)

Determination of stature.—The average stature of Englishmen is from five feet six to five feet nine inches, or, according to Beddoe, five feet seven inches; about four out of one hundred are calculated to have a stature of from six feet to six feet three inches. In determining the stature from the measurement of the entire skeleton, it is usual to add from an inch to an inch and a half for the thickness of the soft parts. When the bones are entirely disarticulated, they should be laid out in their natural order, and an estimate made. Medical jurists have endeavoured to determine the stature of a skeleton from the measurement of one or more of the long bones—as, for example, of the femur, tibia, fibula, humerus, radius and ulna; but the rules for this mode of calculation are unsatisfactory and, as Devergie has shown from the tables, they are liable to lead to an error of five inches at the least. The fact is, there does not appear to be any uniform relation between the length of these individual bones and the stature of a person. In tall persons it is observed that the bones of the lower limbs are proportionably longer than those of the upper, but we are liable to meet with all kinds of anomalies, and the best that can be said of this mode of measurement is, that it can never be proved wrong: for in general there can be no witness to speak to the stature of the person while living, in cases in which a medical investigation of this kind is directed to be made. We advance very little to a solution of this question, even by deducing the average length of a long bone from the measurement of a large number of similar bones. The differences in the length of the bones will be great according to whether the measurement is made from the edge of one articular surface to the other, or whether the processes are included or excluded, such as the styloid process of the ulna and the inner malleolus of the tibia.

On next page are drawn up the measurements of three adult male skeletons, which were taken as accurately as possible by the repeated examination of the numerous skeletons in the museum of Guy's Hospital. Nos. 1 and 2 comprise nearly the average stature of Englishmen; No. 3 represents the skeleton of a tall man. The height here is the bare measurement of the bones with the soles of the feet resting on the ground; an addition of at least an inch should be made for the soft parts. The lengths of the tibia and fibula were taken between the articular surfaces. From end to end the fibula is a remarkably long bone. The author has found it in adults to be in many cases as long as fifteen inches.

Adult Male Skeletons.

	No. 1. Ft.	In.	No. 2. Ft.	In.	No. 3. Ft.	In.
ure (sole on e ground) .	5	6,	5	9	6	0
nsverse measurement from tremity of iddle fingers	5	6½	5	10½	6	1
ur . .		17⅞		18		19½
a } between		15⅞		14⅞		15½
ila } art. surf.		13½		14		14½

	No. 1. Ft.	In.	No. 2. Ft.	In.	No. 3. Ft.	In.
Humerus . .		12		12		13½
Radius . .		9		9½		9⅞
Ulna . . .		10		10⅞		10⅝
Clavicle . .		5⅝		6		6
Hand from carpus, joining the radius . .		7		7½		6½

The subjoined table contains the measurement of two female skeletons; one of an adult, the other of an aged woman.

Female Skeletons.

	Adult Female. Ft.	In.	Aged Female. Ft.	In.
ure . . .	5	2½	5	
nsverse length	5	2½	5	⅜
ur . . .		16		16
a . . .		12⅜		12½
ila . .		12½		12½
erus . .		11½		11½

	Adult Female. Ft.	In.	Aged Female. Ft.	In.
Radius . .		8		7½
Ulna . . .		9		8⅜
Clavicle . .		5½		5
Hand from the wrist . .		6½		6½

These are the measurements of the bones of the arm of a well-formed ier.

Arm of a Soldier.

	Inches.
erus	12½
ius	9½
a	10½
icle	6
d from wrist . . .	7⅛

	Inches.
Total length of arm . . .	29½
29½ × 2 = 59	
Clavicles 12	
Sternum 1½	
Stature about 6 feet.	

The following are full-length measurements of perfect but detached es of a male skeleton used for anatomical demonstration:—

Detached Bones of a Male Skeleton.

	Inches.
ur	18
a	15½
la	15

	Inches.
Humerus	12⅜
Ulna	10½
Radius	9½

In the course of these investigations an attempt was made to determine ther there was any correspondence between the transverse length of the eton, measured from the extreme ends of the phalanges of the middle ers, the arms being maintained in a horizontal position. It will be seen , both in the male and female there is a very near approximation in these surements. We have only the bones of the arm of a male adult; we , by doubling its length, and adding twelve inches for the two clavicles, an inch and a half for the sternum, determine approximatively the ure. Thus, by applying this rule to the arm of the soldier, of which measurements have been just given, we should have a stature of six . This method of taking a whole extremity, although only approxi- e, is likely to lead to less error than that of determining the stature the measurement of a solitary bone. In the disinterment of the remains William Rufus (p. 147), an attempt was made to determine the stature the king. The tibias were 16¼ inches long, the thigh-bones were 19 hes, and the spine was 26 inches in length. Comparing these measure-

ments with those above given, the inference is, that Rufus was a tall man, nearly if not quite six feet in height.

Below are two measurements, the one of a male skeleton between *ten and eleven years of age*, the other of a mature child at the end of *nine months'* utero-gestation. The dried cartilages at the ends of the long bones are not included in the measurement of the latter, because they are never found in graves; we have merely the osseous portions to examine.

	Male Skeleton naturally articulated. Ft. In.	Mature Child at 9 months. In.		Male Skeleton naturally articulated. Ft. In.	Mature Child at 9 months. In.
Stature	3 10	19¾	Ulna	6¾	2¼
Femur	11⅜	3	Clavicle	4	1⅛
Tibia	9⅜	2⅛	Hand from wrist	5	2
Fibula	9⅛	2⅛	Arms each		8½
Humerus	8⅛	2¼	Measurement across the chest		3½
Radius	6	2			

Béclard remarks on the stature of the body, as determined by the dimensions of the skeleton, that it is about five feet four inches for an adult male and about five feet for an adult female; but it is subject to great variation, not merely in the various races of men, but in individuals of the same race and nation. The extremes, however, are comprised within certain limits. Thus dwarfs (as adults) are rarely less than one-half of the average stature, while giants are seldom more than one-half above the average.

Determination of age from stature.—In attempting to determine the age of a skeleton from the measurement of the bones, it must be remembered that there is a great difference in the rapidity of growth, not merely in children of the same sex, but in children of different sexes. Sometimes a child will be much under the average stature before puberty, but will rapidly grow after having passed this period: hence the subjoined table, taken from Sue, is scarcely available for practical purposes. We must, at any rate, allow of the possible existence of great deviations. Here is the table, somewhat modified by additional observations.

Age.	Stature. Ft. Ft. In.	Age.	Stature. Ft. Ft. In.
At one year	2 to 2 3	At fourteen to sixteen	4 to 5
„ three years	3	„ twenty to twenty-five	5 to 5 6
„ ten to twelve	4		

The full stature, however, according to some recent observations, is rarely attained until the age of from twenty-five to twenty-seven years. This table refers to the stature of living persons; it will be somewhat less for the skeleton.

M. de S. Luca brought before the Academy of Sciences the results of his researches on the relative length and weight of the bones which constitute the human skeleton. ('Cosmos,' Oct. 2, 1863, p. 386.) He demonstrated the existence of relative proportions among parts of the body which had not previously been suspected. His view is, that in the construction of animals there is among the various organs a uniform relation of weight, length, and surface. The average stature of an adult man is, according to him, five feet three inches (1 mètre, 60 centimètres), that of an adult woman one-twentieth less, *i.e.* five feet. The head forms one-eighth part of the total height of the body: this is divided into two equal parts immediately below the eyes, while the nostrils are midway between the eyes and chin. In a vertical section of the body, the pubis is a central point between the two extremes. When the arms are raised vertically above the head, the umbilicus or navel, which is one mètre (39·37 inches) from the sole of the

foot, then becomes the centre of the length. It may be further remarked that the height of a man corresponds to the distance which separates the extremities of the two hands, when the arms are extended in a horizontal line from the body. The arm may be divided into five parts, the hand representing one part, while two others are occupied by the forearm, and the remaining two parts by the upper arm, the elbow being the boundary of these divisions. Whatever the length of the hand, five times that length will represent the total length of the arm, so that if the hand is 133 millimètres (5·22 inches) the arm will be 666 millimètres (26·13 inches) in length. In reference to the hand, the carpal and metacarpal bones represent one-half of its length. The first phalanx of the middle finger is equal to one-fourth of the hand, and the two last phalanges of this finger, taken together, are exactly equal to the length of the first phalanx. The last phalanx is itself naturally divided by the nail into two equal parts. The sole of the foot is a third longer than the palm of the hand, but the back of the foot or instep is of the same length. The observations made on the weight of the bones showed:—1. That the bones of the right side of the body were heavier than those of the left. 2. The weight of the bones above the navel is equal to the weight of those which are below that point. 3. The weight of the bones of the hand is equal to the fifth part of the weight of the bones of the arm. There is the same relation here as in length. 4. The total weight of the hand may be divided into five equal parts, one represented by the carpal, two by the metacarpal bones, and two by the bones of the fingers. The first phalanx is equal to two-thirds of the weight of the entire finger, the other third being represented by the two remaining phalanges. 5. The bones of the hand are equal to half the weight of the bones of the foot. 6. In the foot there are similar relations. The weight of the tarsal is double that of the metatarsal bones, and the weight of the toes is divided into three parts, two for the first phalanges and one for the two small phalanges.

Difference of race.—There are certain differences in the skeleton, according to whether it belongs to an individual of the Caucasian, Mongolian, or Negro race. The differences chiefly relate to the proportion which the skull bears to the face, and the relative lengths of the upper and lower extremities. In the Caucasian the skull is rounded, the forehead raised, and the facial portion small in proportion to it. In the Mongolian, the upper and lower extremities are small, the cranium more of a square form, the forehead inclined, and the face large and flattened; the malar bones being especially prominent. In the Negro the proportions of the skeleton are smaller in the lumbar and pelvic regions; the upper extremities are long in proportion to the body, and the forearm and leg are large in proportion to the arm and thigh; the hands are small, the feet wide and flat, and the heel bones project much backwards. The skull is narrow and elongated, the forehead small and compressed, the malar bones and jaws project, and the teeth are placed obliquely, so as to form a considerable angle at their point of union. The most marked characteristics exist in the configuration of the skull; but the skull of Ho Loo (a Chinese), in the museum of Guy's Hospital, scarcely possesses the characters assigned to the Mongolian; it closely resembles the skull of the Caucasian. That of the Negro may be more clearly identified. The skull of the Hindoo is a mixture of the Negro and Caucasian. It would be difficult, if not impossible, to pronounce an opinion of the race to which the skeleton belonged, from a few detached bones or parts of bones.

Identity from fractures.—With regard to other circumstances connected with the skeleton, it will be proper to observe whether the bones belong to the same or different individuals, to the right or the left side of the body;

and these questions may be determined in many cases by the mere inspection of fragments. The existence or non-existence of *fractures*, and the progress which may have been made towards ossific union may also become an important subject of inquiry. The body of Dr. Livingstone was identified by means of an old fracture of the humerus. In general the past existence of a fracture is easily determined in an exhumed bone, by the appearance of a knot or ridge, or in some cases a thick deposit of bone where union has taken place badly. In a fractured bone which has united in a curved form, it will be observed, on making a section, that the shell is considerably thicker on that side which has had to bear the greatest weight or pressure. All these facts, trivial as they may appear, may in reality be material in a case of disputed identity; and unless carefully observed at the time, valuable evidence may be lost.

An English gentleman residing in India, 1833, was charged with the murder of a native, *Meer Khan*. The evidence against the prisoner was of a twofold character:—1, that which preceded death; and 2, that which followed it. With regard to the first, it will be only necessary to refer to it briefly. There was great discrepancy in the statements of the witnesses as to the manner in which the deceased was alleged to have been destroyed. It was shown that the deceased had received a beating at the hands of the accused, but it was not proved that the man had died in consequence of the beating. There was no effusion of blood; there were no marks of violence of any kind upon the body before or after death, unless, indeed, we except a burning of the skin of the legs, which was alleged to have been produced by burnt paper or straw, but the evidence respecting this was anything but coherent and conclusive. Be that as it may, however, there was no evidence to prove that the alleged burning was the cause of the man's death. Two of the men (natives) who said they carried the dead body to be buried at midnight, testified to the presence of marks of burning, but contradicted each other respecting the appearance of the legs; one swearing that they were covered with plasters, the other that the wounds and burns were not covered. The latter witness prevaricated, and, when asked how he knew that the legs were burnt, replied that he judged so from their being *white*.

The testimony respecting the degree and effects of the violence applied to the deceased during life being so inconclusive, it was left to the jury to decide whether a quantity of human bones produced were those of the deceased, as it was alleged by the witnesses for the prosecution, or whether they belonged to the skeleton of some other person. According to the depositions, they were found in the following manner. *Three months* after the burial, one of the witnesses who had assisted in burying the deceased, after some search, discovered, as he supposed, the grave, on the verge of the bank of the river Damoodah. The body, it seems, had been buried pretty deeply in the sand, above the common water-mark, at the distance of sixty or eighty yards from the bed of the river, at a place which the waters had never reached, or could reach only on extraordinary occasions. The bones were uncovered, but not removed, until five days afterwards. It does not seem to have been clearly made out whether other bodies were ever interred in that spot or not, nor was the grave properly identified as that of the deceased. The bones were subsequently examined by a medical officer, who stated in his evidence that twelve of the vertebræ, six of the ribs, and the sacrum were wanting; that the whole of the bones found were clean and dry, and free from periosteum, ligaments, and cartilage; that *one rib was broken*, and apparently had an osseous callus (new bone) formed upon and around the fractured ends. The witness gave it as his opinion that the fracture must have occurred at least seven or eight days

efore death; he had never heard of an instance of exhumed bones eing deprived of soft parts and ligaments by natural decomposition in hree months. He should not expect the cartilages and ligaments to be eparated from the bones within a year of the interment. He considered t, therefore, extremely improbable that these were the bones of the eceased, or of any person who had died within three months from the ime of examination.

From this evidence several considerations suggest themselves; as, for xample, the identity of all the bones as those of one individual, the age f the person, the nature of the bony excrescence or callus found on the roken rib, the time necessary for the formation of new bone in order o settle the period at which the fracture took place, the time required or the total spontaneous destruction of the muscles, tendons, ligaments, nd viscera; also the time required for the spontaneous separation of he sacrum from the other bones in a man of the age of fifty or sixty. Many of these points, important as they were, were altogether passed ver. The witness gave it as his opinion, that they were the bones of a *male* subject; but of this, he said, he could not be quite certain, as the acrum was wanting. No opinion was asked or given as to the supposed ge of the person to whom the bones belonged. Only one bone was pro-uced in Court, viz. the broken rib, with the deposit of callus (new bone) t its extremity. From the state of this callus there could be no doubt, upposing the bone to have belonged to the deceased, that the *fracture* ust have been produced about eight or ten days before death; therefore t some time previous to the violence employed by the prisoner. The on-identity of the bones as those of the deceased seems, however, to have een clearly established by the condition in which they were discovered. ven in a tropical climate the period that must elapse before the total estruction of the soft parts of the body in a grave, so that nothing but he bare bones shall remain, must be considerably greater than three onths. In one instance, in which a body was exhumed four months fter death, the soft parts were still present.

Another curious feature was the separation of the sacrum from the ones of the pelvis. The junction of these bones by ligaments and fibro-artilage is perhaps one of the strongest in the body. In the skeletons f the young these bones are rather difficult of separation; but in the ld, in whom anchylosis (or bony union) in general takes place to a reater or less extent, the difficulty of separating them becomes incom-arably greater. It may readily be conceived, then, that the entire separa-ion of this bone by decomposition, would require, even in a hot climate, a very long period in a body interred in the ground—probably from hree to ten years. Now, when we consider that the deceased had not been uried above three months, it is clear, both from the entire destruction of he soft parts and the separation of the sacrum, that the bones discovered n the bank of the river could not have belonged to the deceased, but must ave been part of the skeleton of a person whose body had been buried in he spot many years before. There was, therefore, a complete failure of dentity, and the accused was discharged.

Identity from disease or deformity.—Questions of identity in relation to keletons may be in some cases solved by reference to certain special haracters of the bones. They may have about them indications of disease; s rickets, softening of the bones, or syphilis. There may be, again, some ersonal peculiarities, such as the presence of supernumerary fingers or oes, which, if observed, may tend to throw some light upon the case. An nstance of this kind is mentioned by Orfila. In the year 1823, a man amed *Bonino*, who had been residing in a small village in the neighbour-

hood of Montpellier, suddenly disappeared. It was some time afterwards reported that he had been murdered by a girl with whom he had cohabited and by a man of the name of Dimont, who was known to have been for some time her associate. It was only in the year 1826, after the lapse of more than two years, that the magistrates were first induced to direct an investigation of the case. A strict search was ordered, and the remains of a body, chiefly the bones, were found buried in the garden of Dimont, who had married the girl nine months after the disappearance of Bonino. It was of course essential to identify this skeleton as that of the deceased. It was well known that he had laboured under a singular personal deformity in having a sixth finger on the right hand, and a sixth toe on the left foot. The bones, which were nearly all perfect, were carefully removed and put together, when it was found that those belonging to the two smaller toes of the left foot were wanting; but the metatarsal bone of the fifth toe had a process on the outer side, with a small articulating surface, which might have formed a supernumerary joint. Still, however, this was considered insufficient to establish the point, and the attention of the examiners was then directed to the right hand. The fifth bone of the metacarpus was shorter and broader than the one belonging to the opposite hand, while its digital extremity was divided into two parts, of which one formed a smooth, rounded, articulating surface in the axis of the bone; while the other, which presented a more flattened articular surface, formed with it an angle of about 8°. On attempting to articulate the first phalanx of the little finger, it fitted exactly the first articular surface, and presented on the outer side a distinct groove, the oblique direction of which coincided with the direction of this second surface. This left no doubt of the nature of the peculiarity of structure; although the phalanges of the sixth finger could not be discovered. The left hand and the right foot were complete in all their parts. Other corroborating circumstances transpired with respect to the marks of violence on the body, and the two prisoners were tried, condemned, and executed. (For other cases see 'Ann. d'Hyg.' 1861, 2, 114.)

Deformities of the spine or limbs are easily observed, and may form well-marked points of identity. Briand mentions the following case. In 1825 a man named *Guérin* suddenly disappeared. Three years afterwards an excavation was made in the cellar of the house where he and his brother had resided, and some human bones were discovered. Among other circumstances, the medical men to whom the examination of these bones was referred, remarked that the body of the fifth lumbar vertebra was depressed and thin as it is met with in rachitic individuals, that the pelvis was more contracted on the left than on the right side, that the tibia and fibula of each leg presented a remarkable curvature, greater, however, on the left than on the right side, so that the left leg was half an inch shorter than the right. There were certain peculiarities about the teeth of the lower jaw, the canines forming a considerable projection in front of the incisors. These facts, together with other circumstances, established the identity of the bones, as being those of the person who had been missing.

The bones of the skull in children may occasionally present appearances arising from natural causes, but which may simulate the effects of violence applied to the head. The following case of suspected child-murder occurred in 1847. The dead body of a new-born child, wrapped in brown paper and a towel, was found in a pond. Mr. Lord examined it for the coroner's inquest. The head was much decomposed, and the scalp was extensively lacerated and destroyed over the parietal bones, which readily separated. The brain was reduced to a pulp. The umbilical cord, which had not been tied, was cut obliquely at about six inches from the navel. The

which were very crepitant, readily floated on water, and bore up
art. The body was generally bloodless. The point of difficulty
the case presented consisted in the presence of two apertures on
rietal bone. These apertures were small and rounded, and it was
t doubtful whether they had not been wilfully produced by some
ting instrument applied to the head. It was remarked that one
re was situated near the temporal ridge, and in this situation the
was entire and uninjured. The other was situated in that part
bone which corresponded to the lacerated portion of the scalp.
ascertained that no violence had been used in the removal of the
rom the water. The bone was macerated, and carefully examined
aid of a lens. It was then perceived that the apertures were
regular at the edges, which were remarkably thin, evidently pass-
to a membranous condition. The internal table was also deficient,
, from the interior, the bone was bevelled off gradually from each
re. This examination left no doubt that the holes in the bone were
e to any mechanical violence applied during life, but to deficient
tion. These spaces had been membranous, and the membrane
ed by decomposition. The putrefaction of the scalp, and its
tion, might have been accelerated by a bruised condition of these
during a difficult labour. In examining a skull, disinterred under
ous circumstances, natural defects in the bones must not be mistaken
rtures made by deadly weapons. These natural defects are generally
aracterized. They may be found at all ages. Turner has described
gured some of these cases of defective ossification. ('Ed. Med.
Aug. 1865, p. 133.) These apertures from defect are generally
terized by rounded and regular margins. They are not rough and
lar, like those produced by the violent use of weapons.

e bones which we are required to examine may have undergone
tion. In several cases of child-murder which have occurred, an
t has been made to dispose of the body by burning it. This method
posing of a dead body is by no means unusual in cases of alleged
icide and concealment of birth. There will be no great difficulty in
an opinion whether a bone has or not undergone calcination. Its
ter is entirely altered. Its shape may be preserved, but if burnt in
en air, it will be white; if in a close fire, it will be black or ash-
The bone is brittle, easily pulverisable, and dissolves in hydro-
acid, leaving, if perfectly calcined, only some charcoal but no
l matter.

the case of *The Queen* v. *Varney* (Oxford Lent Ass. 1837), it was
l that the woman had been pregnant, and subsequently delivered of
l. Its body had been burnt, and only a few remains of the bones of
an fœtus were found in the ashes of a grate. The prisoner was
ted of concealment of birth. In a case like this, in which an attempt
en made to destroy the body of a child by burning, it will, of course,
essary to have good evidence that the bones are those of a *human*
r child. A small fragment only of either end of any well-marked
ill suffice for identification. If the jaws be forthcoming, the alveolar
s should be sought for, and the number and condition of the teeth
l. The period of uterine life which the child had attained may be
n some instances determined, as also by the presence or absence of
ossificatory points in the bones.

he body has been burned to a complete ash or powder, it will then
icult to identify the bones. Orfila was consulted in a case of this kind,
a woman had burnt a child in an oven, and its ashes had become
with those of wood. He suggested that on calcining the residue

with potash, the ashes of a human fœtus might be known by their yi potassium cyanide, owing to the nitrogen which would remain i about them. The ashes of wood do not yield the cyanide under s circumstances. ('Ann. d'Hyg.' 1845, 2, 129.) The conclusions under such circumstances might, however, lead to a serious error presence of a flannel dress, of an old hat, shoe, or any nitrogenou stance, would, on incineration, give rise to precisely similar results. the *form* of a bone cannot be recognized, all that medical evidenc accomplish may be thus stated:—The detection of a large quant *calcium phosphate* in the ash would indicate that bones were presen thus distinguish the ash of bone from the ashes of other substances. the bones might have belonged to an animal, and not to a human There are no means of distinguishing the ash of human from t animal bone, or the ash of fœtal from the ash of adult bones. In th of the *Lemoines*, mother and daughter, tried before the French Cou 1859, the evidence went to show that the elder prisoner (the mother) the body of a child of which her daughter had been secretly deli Some bones of a child were recovered, and among others the frontal The medical evidence was to the effect, that the bones were thos child which had reached about the seventh or eighth month. Upo corroboration, the jury convicted the elder prisoner, and the Court sent her to twenty years' imprisonment.

In a case of concealment of birth (*Reg.* v. *Berryman*, Guildford Ass. 1854), it was proved by medical evidence, that the prisone been recently delivered of a child of not less than seven months u age. She said that she had burnt the body to conceal her shame had buried the remains in a garden. Some bones which had calcined were there found buried in ashes; and after an examinati them, a medical man stated that they were the bones of a child nine m of age; but in comparing them with the skulls of nine months' child Museum collections, it was admitted that the skull, of which the part been found and restored, was larger. This admission threw some dou the identity of the bones, and the prisoner was discharged.

In 1863, a man named *Barton*, a fireman employed at a co near Wigan, was missing. From the appearance of blood about the n of the steam furnace, and the discovery of a burned portion of the worn by the deceased, there was reason to believe that the man had murdered and his body thrust into the furnace. Edwards examine ashes of the furnace and found:—1. Portions of the occipital bone o human skull; 2. Base of the skull and two fangs of teeth,—a fang incisor and a fang of a molar tooth; 3. Portions of the arches of the d vertebræ; 4. A portion of the lumbar vertebræ; 5. A portion of the body, and joint of the humerus; and 6. A portion of the head and of the thigh-bone. These bones had been heated to a high tempera which had destroyed their internal structure, but the external was well preserved. They were human bones. A chemical and m scopical examination of some of the clinkers showed that there was upon them, having the character of human blood. There was no d that these were the remains of the missing man. He was last seen at eight in the evening, and at four the following morning nothing rema of him but the few bones above mentioned.

In the exhumation of remains, portions of *hair* may be found a about the skull, or in the earth surrounding it. The hair shoul separated by washing it first in water, and afterwards in a mixtur distilled water and acetic acid. When dried on paper the colour wil observed, and this may be of some value in determining a questio

ity. French medical jurists lay great stress upon the necessity for mining whether the hair has been artificially dyed or not. The non hair-dyes are compounds of lead, silver, or bismuth; and these ls, when the necessity arises, may be sought for, and easily found, by sses similar to those required for their detection as poisons when bed into the tissues. This will be a matter for future consideration.

CHAPTER 9.

S OF DEATH—SUDDEN DEATH—SYNCOPE, ASPHYXIA, COMA—PRESUMPTION OF EATH—MEDICAL EVIDENCE OF PRIORITY OF DEATH IN CASES OF SEVERAL ERSONS PERISHING FROM A COMMON CAUSE—PRESUMPTION OF SURVIVORSHIP.

CAL jurisprudence takes cognizance of all violent causes of death, and ly indirectly involved in those cases of natural death which simulate ffects of violence. Thus all causes which operate to produce death enly, as by syncope, asphyxia, or coma, especially demand the attention medical jurist. These may be either natural or violent; and the dis- ion between them is of importance, since the guilt or innocence of a n charged with crime may depend on a correct determination of the e.

he continuance of life depends upon the proper and regulated action e heart, the lungs, and the brain; and the interdependence of these ns is such that the arrest of the functions of one of them, is speedily wed by the arrest of the others. Hence they have been called the tripod e. When the suspension of the motions of the heart is the primary cause ath, the person is said to die by syncope. The term asphyxia is applied ath which begins by the lungs; and coma to that which arises from a ary disturbance of the functions of the brain. The term apnœa, at time used for asphyxia, is now applied by physiologists in a different e; and deaths from coma usually terminate in either asphyxia or ope.

SYNCOPE (*συγκόπτω*, signifying 'to cut down').—In order that the action e heart should be maintained, it is necessary, first, that the blood sup- l to it should be in sufficient quantity, and secondly, that this blood ld be of proper quality. In death from *hæmorrhage* we have an instance eficiency, and in death from certain poisons, as well as diseases, an tration of defect of blood (*asthenia*). In ordinary syncope (fainting or ming) there is simply a deficiency in the quantity of blood which passes gh the heart, although there is no actual loss of this fluid from the lation. Certain diseases which affect the muscular structure of the t, and its nervous apparatus, as well as the membranous valves and l-vessels, may also lead to a sudden arrest of its functions. These id conditions produce a mechanical impediment to the motions of the n by which the blood is propelled, and death by syncope is the necessary t. One of the most striking of the phenomena which attend this mode ing (death from hæmorrhage or anæmia), is an extreme pallor of the hands, and lips, and, indeed, of the body generally. The patient is very ss, tossing the limbs about in all directions. Giddiness and nausea are complained of, and actual vomiting may occur. In many cases vision tinguished, everything appearing black. There is transient delirium, h soon passes into insensibility. The pulse becomes more and more and irregular, until at length it is imperceptible. The respiratory

movements are repeated at uncertain intervals, and have a sighing or gasping character. Towards the last there are general convulsions. (Fagge, on the 'Different Modes of Dying,' Guy's Hosp. Rep. 1879, p. 343.) In these cases the heart is found empty and contracted at the autopsy. When, however, from any cause, there is sudden stoppage of the heart, the right and left cavities of this organ are found to contain blood in the normal proportion in which that fluid is ordinarily circulated. Blood is found in the large veins (venæ cavæ), as well as in the arterial trunks. There is no congestion or accumulation of blood in the lungs or the brain.

ASPHYXIA (ἀ priv. and σφύξις pulse, signifying pulselessness).—This state is induced by any cause which arrests the function of respiration. The term apnœa (from ἀ priv. and πνέω I respire) is less appropriate, and is applied by physiologists to an exactly opposite condition, that which consists in an excessive supply of oxygen to blood, rendering respiratory movements for the time unnecessary. The various forms of death by suffocation, as in the obstruction of the air-passages from mechanical causes, in drowning, hanging, and strangulation, furnish illustrations of death commencing by the lungs, or asphyxia. The effect of cutting off air from the lungs is that the blood is not aërated, and it is therefore circulated in a state unfitted to support the nutrition of the heart and brain. It is necessarily distributed with the impurities derived from the waste of tissue, and thus acts as a poison to all the organs. It is incapable of sustaining nerve-force or muscular irritability. It stagnates in the capillary vessels of the lungs, produces a languid action of the heart by its circulation through the muscular structure of this organ, and causes insensibility by its distribution through the blood-vessels of the brain. The lungs are essential to the circulation by purifying the blood. Death from asphyxia may be therefore regarded simply as death from *defect* of blood. The observations of Brodie ('Lect. on Pathology,' 66) and others have clearly proved, that in spite of the impurity of the blood the heart will continue to act and the circulation be maintained after respiration has entirely ceased. This may be proved by hanging or strangling an animal and observing the condition of the heart. As the action of this organ continues after the animal has ceased to breathe, life is not actually extinct: and under favourable circumstances, it may be restored, so long as this action continues. Supposing that the suspension of respiration is complete, the action of the heart gradually slackens and finally ceases. It is at this period of the complete arrest of the motions of the heart that asphyxia passes into death. The circulation of the unaërated blood through the brain appears to annihilate sensibility, so that no consciousness or feeling exists: the person is, to all appearance, dead. There are many diseases which operate fatally by arresting the functions of the lungs, and these may be regarded as furnishing the natural causes of asphyxia. The violent causes, including not only the ordinary modes of suffocation, but the effects of certain poisons, are not difficult to appreciate, provided a true history of the case can be obtained.

Michael Foster has shown how, in experiments on animals, it is very soon observed that the expiratory efforts become exaggerated out of all proportion to the inspiratory, and how they quickly pass into convulsions. This period lasts about a minute, during which time the pulse is increased in frequency, and the arterial blood-pressure rises. Deep, slow breathing then supervenes, and the inspiratory movements are now more marked than the expiratory, the more yielding parts of the chest wall receding at every inspiration. The cardiac beats decrease in number, but remain

rcible, though the arterial pressure falls. The respiratory rhythm comes irregular, long pauses being followed by quick inspirations with ief intervals. The inspirations next become shallow and gasping, the celeratory muscles of respiration being brought into active play; and at st the gasps end in a convulsive stretching of the whole body; and with tended limbs and a straightened trunk, with the head thrown back, the uth widely open, the face drawn, and the nostrils dilated, the last eath is taken in. There are three distinguishable stages in these phenoena of asphyxia which result from a continued deficiency of air:—1. A ge of dyspnœa, characterized by an increase in the respiratory moveents both of inspiration and expiration. 2. A convulsive stage, chacterized by the dominance of the expiratory efforts, and culminating in neral convulsions. 3. A stage of exhaustion in which lingering and ng-drawn inspirations gradually die out. When brought about by dden occlusion of the windpipe, these events run through their course in om three to five minutes. The phenomena of slow asphyxia, where e supply of air is gradually diminished, are fundamentally the same, and e same stages are seen, but with their development taking place more wly than where there is a sudden and total deprivation of air. The art continues to beat for some seconds after all respiratory movements ve ceased, whether the asphyxia be rapidly or slowly developed.

In animals the cardiac chambers at the moment of death are all gorged th blood,—the left ones as well as the right. When rigor mortis sets in, e left auricle and ventricle empty themselves; and in ordinary autopsies the human subject, the pulmonary artery, the right cavities of the heart, d the venæ cavæ are found gorged with blood. The pulmonary veins, e left cavities of the heart, and the aorta, are either empty or contain t little blood. In certain cases of asphyxia, the right cavities of the art, as well as the left, have been found empty. When the access of air the lungs is suddenly and completely cut off, the circulation of the blood speedily arrested; but supposing the occlusion of the air-passages to be rtial or gradual, the circulation of the blood may continue for a time, d thus cause congestion of certain organs. Hence the appearances in phyxia differ greatly. A mixed condition, under the name of syncopal phyxia, has been described by some pathologists. In this, the cavities of e heart are found empty.

Coma.—Besides a due supply of aërated blood, the brain requires for the ercise of its functions a proper quantity of blood, so that either by the dden withdrawal of this fluid, or by a distribution of impure blood, these e arrested. A person thus affected falls into a state of complete insensibility (coma), so that it is impossible to rouse him. The functions of the art and lungs are not always suddenly arrested under these circumances. They appear to be less dependent on the brain than the brain is on them; but this is rather a question of degree. A due supply of rvous force is required for the action of the muscles, whether of the art or of the chest; and when this is withdrawn, the heart ceases to ulsate, and the respiratory muscles cease to act: circulation and respiran are thus arrested by the absence of innervation. This is sometimes scribed as death by paralysis of the heart and lungs. The blood is ither aërated nor circulated. Sudden death from apoplexy is an illustration of death by the brain. Coma may also be a result of the introction of certain poisons into the blood, and of fractures of the skull ading to compression of the brain or destruction of its substance. Death ginning at the brain is, indeed, scarcely to be regarded as a mode of ing, since it may usually be resolved into either death from *sudden*

paralysis of the respiratory centre, when death is often absolutely quiet; or the coma ends in *asphyxia*, when the extinction of respiration is brought about more slowly. In death by the brain, usually the appearances observed consist chiefly in a congested state of the cerebral membranes and substance of the brain. As, before death, respiration is affected, the lungs are congested, and blood accumulates in the cavities of the heart, more on the right than on the left side. The appearances described as characteristic of the different modes of death by the heart, lungs, and brain, are liable to variation by reason of the intimate relation of the organs, and thus there may be a mixed condition.

With regard to the interruption of the functions of the brain as a result of pressure by the effusion of blood or serum, it is to be observed that a very small quantity of either of these effused at the base or in the substance of the medulla oblongata, is sufficient to cause death; while, generally speaking, a larger quantity is required to be effused in the membranes, ventricles, or substance of the brain in order to produce a fatal result. In cases of chronic hydrocephalus, in which the brain has resisted the pressure of a large accumulation of serum for many years, a slight and sudden increase in the quantity at any period of life may lead to coma and death by apoplexy. This condition may be mistaken for narcotic poisoning.

All causes of death, whether from disease or violence, are referable to an effect produced primarily on the heart, the lungs, or the brain; but, as has been elsewhere stated, death does not take place until the action of the heart has entirely ceased. The arrest of the circulation produces an immediate impression upon the functions of the brain and lungs; while the lungs and brain are affected and can only affect each other indirectly through the medium of the circulation: hence, systemic death, or the death of the body, is resolvable into death by syncope or a failure of the action of the heart, and this depends in all cases either upon defect or deficiency of blood.

The natural causes of *sudden death* may be generally traced to some injury or impediment to the action of the heart, lungs, or brain. It would be foreign to the objects of this work to give a description of them. The violent causes are those which demand the especial attention of a medical jurist; they will be considered hereafter. In its relations to medicine and medical jurisprudence, the subject of sudden death has been treated of by Herrich and Kopp ('Der plötzliche Tod aus inneren Ursachen,' Regensburg, 1848); as well as by Devergie ('Ann. d'Hyg.' 1838, 2, 145).

The *violent* causes of death, whether sudden or protracted, which chiefly require the skill of a medical jurist for their elucidation, are poisoning, wounds, and personal injuries, such as burns and scalds, as well as those forms of death which commence by the lungs, including drowning, hanging, strangulation, and suffocation. In nearly all cases, the body of the deceased is produced, and a medical opinion can be based upon a careful examination.

Presumption of death.—Before proceeding to describe the violent cause of death in their order, it may be well in closing this part of our subject to state that the fact of death may be proved by presumptive, as well as by direct evidence. The death of any person once shown to have been alive, is a matter of fact to be determined by a jury; and when the body is not forthcoming, as the legal presumption is in favour of the continuance of life, the onus of proving the death lies on the party who asserts it. (Best on 'Presumptions of Law and Fact.') When a person goes abroad and has not been heard of for a long time, the presumption of the

continuance of life ceases at the expiration of seven years from the period at which he was last heard of. The same rule holds generally with respect to a person who has gone away from his usual place of resort, and of whom no account can be given, but the presumption does not extend to the *time* of his death, *i.e.* whether he died at the beginning or at the end of any particular period of the seven years. In the case of *Watson* v. *England*, which came before the Court of Chancery, it was attempted to enforce as a presumption, that a female who had left her father's house in 1810, and had not been heard of for thirty-four years, was dead. No decision was come to, the Vice-Chancellor observing, from the great uncertainty of the evidence, that if he presumed her death, the woman might walk into Court and disprove all. In one case, according to Best, the Court of Queen's Bench said, that they could not assume judicially that a person alive in the year 1034 was not alive in 1827. (Op. cit.) Without adopting this extreme legal view of possible longevity, it is obvious that Courts of Law may be easily deceived if such presumptions are admitted too readily. In *Church* v. *Smith* (Exch. Dec. 1853), the question was whether plaintiff was then a married woman, or whether by reason of the long absence of her husband, his death might not be legally presumed, and that she was, therefore, a widow, and could sue in her own right. According to the statement of her counsel, she was married to a man who had deserted her fourteen years ago, and she had heard nothing of him during the last twelve years. An end was put to the case by the appearance, in the witness-box, of an aged man who turned out to be the missing husband. The plaintiff, therefore, not having the power to sue in her own right as a widow, was nonsuited, the Chief Baron observing to the jury that he should have directed them to presume that the husband was dead, if, as the counsel stated, it had been proved that he had not been heard of for twelve years; but after his appearance in Court, he could not ask them to presume a man to be dead who was actually living before their eyes. In *Reg.* v. *Briggs* (Nov. 1856), a woman was deserted by her husband four months after marriage, and he had been absent from her seven years. The woman married again in her maiden name; and on an indictment for bigamy, it was contended in her favour that the husband had been absent for the period above mentioned, and the prisoner had no knowledge of his existence. She was convicted, but the conviction was quashed on appeal. In a case before Malins, V.-C. (Jan. 1869), (*Re W. Beasney*), the person whose death was in question was last seen in Aug. 1860. He was then suffering from pulmonary disease, and was much emaciated. He announced his intention to go to New York, but to return before October. He was never afterwards heard of. The petitioner was entitled to the principal of the legacy in the event of the death of W. Beasney before Nov. 7th, 1860, and contended that he must be presumed to have died before that day, as, although in needy circumstances, he had not applied for the dividends then due to him, and that when last seen he was in a precarious condition of health. On the other side it was asserted that the onus of proof was on the petitioner, and no proof of death had been given. The Vice-Chancellor decided in favour of the petitioner that Beasney died before Nov. 7th, 1860, chiefly on the ground that he had punctually applied for and received the dividends on an annuity up to the time of his disappearance. None had been applied for since that time, and ten years had elapsed.

Great injustice would be done unless some rule were adopted regarding the disposition of the property of those who have been long absent, and not heard of for many years. In the case of *Davy* (Probate Court, 1858), it was proved that the testator was a master-mariner. He made his will

on Dec. 2nd, 1856, and sailed for Melbourne from Southampton in Dec. of that year. He then made a voyage to Calcutta, where he arrived in Oct. 1857, and in the following Dec. cleared from Calcutta for Port Louis in the Mauritius. His vessel never arrived at her destination, and nothing had been heard of her since that date. The correspondent of the owners of the vessel at the Mauritius had from time to time reported her non-arrival. This was considered sufficient to establish a presumption of his death, although not more than two years had elapsed since his departure from England; and probate of the will was granted.

In *Green* v. *Green* (Vice-Chanc. Court, July 1861), a question was raised whether a person who had not been heard of for upwards of eighteen years must be presumed to have died. The testator in the cause, who died in Aug. 1838, by his will, dated in April 1838, gave an annuity of £30 to his son, James Green, and upon the death of such son, the testator gave £750 to the children of Jas. Green, and if he should die without leaving children, then the testator gave such sum of £750 to the brothers and sisters of Jas. Green who should be living at his (Jas. Green's) death. In Sept. 1840, Jas. Green left this country for New South Wales, and he had not been heard of since Feb. 1st, 1843, when he wrote a letter acknowledging the receipt of the last payment of the annuity of £30. Edward Green, one of the brothers of Jas. Green, died on Jan. 25th, 1846, and the question was, whether the absent Jas. Green must be presumed to have died before or after his brother Ed. Green. On the former presumption Ed. Green's representatives would be entitled to a share of the £750; and on the latter presumption, they would not be so entitled. The bill was filed by one of the children of the testator, who was interested in the presumption that Jas. Green had died after his brother Edward, and in that state of circumstances, the Vice-Chanc. ruled that the burden lay on the plaintiff to show that James was alive at the death of his brother Edward. As above stated, there was nothing to show that Jas. Green had been heard of since Feb. 1st, 1843. A decree was made to the effect that Jas. Green must be presumed to have died before Ed. Green, and that the fund should be distributed upon that presumption.

A remarkable case was tried in the Court of Exchequer, in Feb. 1862 (*Hiorns and Drew* v. *The Rail. Pass. Insur. Comp.*), which involved a question of the presumption of death from circumstantial evidence; but in which it was suggested that a fraud had been perpetrated by the parties concerned. The action was to recover from defendants the sum of £250, on a policy of insurance on the life of one *F. D. Hiorns*. The alleged deceased, Hiorns, was a single man, æt. 26. He insured his life against accident, for the above-mentioned sum, on Sept 6th, 1856; and on Sept. 13th he went to Brighton by an evening train, taking a return ticket. He spent the 14th and 15th with his friends, and on the morning of the latter day he had a bath in the sea; in the evening he parted from his friends, at about seven o'clock, to go to his lodgings before returning to London, expressing his intention of taking a second bath before doing so. He was seen to go towards the sea, and from that time up to the date of the action he had not been seen alive. On the day that he was missing, a person discovered a suit of clothes lying on the top of the steps of a bathing-machine, but no trace of the owner of them could be discovered. The police took possession of the clothes, and upon searching the pockets a purse, containing a return-ticket, was found, and they were identified as belonging to Hiorns. Advertisements were issued, and every inquiry made to discover the missing man, but without avail. On Oct. 30th, forty-five days after the disappearance of Hiorns from Brighton, the naked body of a man was washed up at

Walton-on-the-Naze, on the Essex coast, about 150 or 160 miles from Brighton. The body, according to the opinion of some medical men, had been in the water some six or seven weeks, and it was, of course, very much decomposed, all traces of the features being destroyed. An inquest was held, at which the plaintiff, G. B. Hiorns, attended, giving evidence that the remains were, to the best of his belief, those of his brother. In consequence of the complete destruction of the features, according to the medical evidence, there was nothing whatever on which to base a proof of identity, and the jury found that it was the body of a person unknown. The defence to the action was: that the assured was still living and within reach of his friends, awaiting the receipt of the money from the Office. It seems that the alleged deceased had been a bankrupt in 1855; and in Sept. 1856, he effected several policies of insurance in different Offices, and made his will, directing that the policies after his death should be realized and the money appropriated to the payment of his debts. The jury could not agree, and were discharged without a verdict. As in this case the body of Hiorns was not found, there was no direct proof of death. The discovery of the clothes was only a circumstance from which a presumption might be raised either way. Considering that the man's life had been insured in this and other Offices for only one week, at the time of this mysterious disappearance, there was strong reason for suspicion.

In 1878 a similar case occurred at Barmouth, North Wales. A gentleman left his hotel before breakfast ostensibly for the purpose of bathing. He was missed; and his clothes, with his watch and some money, were discovered on the shore; but the body was not discovered. On the strength of these facts, an insurance on the life of the missing gentleman was paid. Some months subsequently he was challenged by a friend who met him in South America. He had been in pecuniary difficulties; had absconded; and to avert suspicion left his clothes and other personal effects on the shore, having taken out with him an extra suit of clothes.

In Sept. 1866, a merchant of Bordeaux, named *Vital Douat*, who had become bankrupt, endeavoured, in collusion with his wife, to defraud an Insurance Company of Paris. Shortly before his bankruptcy he insured his life for 100,000 francs. He was subsequently declared a fraudulent bankrupt, when he suddenly disappeared, and about a month afterwards his wife presented to the Office a certificate purporting to be a copy of the register of the death and burial of her husband in England, and claimed the amount for which his life had been insured. A full investigation in this country led to the discovery that the man had passed under various names; had purchased a coffin; procured a certificate from a Registrar of Deaths, recording his own death in a circumstantial manner; and had followed to the grave in a churchyard in Essex, the coffin which was supposed to contain the body of himself, the missing bankrupt. The coffin was exhumed. It contained only a mass of lead, evidently placed there to give it weight. The man fled the country, but was subsequently captured at Antwerp and delivered to the French authorities. The possibility of such a case as this occurring, shows that our system of registration of deaths is sometimes fallacious. It is known that a wrong cause of death may be assigned by an ignorant or interested person, but this and some other cases prove that a living person may register himself as dead, and a fraudulent use be made of the certificate thus procured.

It is obvious that such cases can be elucidated by medical evidence only when it is proved that the missing party was labouring under some serious disease, likely to prove fatal, for which he may have received medical advice; an opinion might then be required as to the degree to which the disease had advanced, and the probability of its causing death within a

certain period. No general rules can be laid down; every case must rest upon the circumstances which accompany it.

A presumption of death may arise in a question of life assurance, as when, for instance, the amount of a policy is made payable on the death of a person. He may have sailed in a ship which has not been heard of for many years; and from circumstances it may appear to have been overtaken by a storm in which other ships were lost. In such cases, payment is commonly made under a deed of indemnity. If the case be disputed, the presumption of death is left as a question for the jury. A verdict was returned for the plaintiffs in an action to recover a sum insured on the life of a Mr. Macleane, the evidence being that about Nov. 28th, 1777, the insured sailed from the Cape in a small sloop, and was never heard of afterwards. Several vessels of a stronger build sailed at the same time, and they encountered a violent storm in Jan. 1778, in which it was supposed the sloop was lost. It is clear that unless a presumption of death were allowed in such cases, injustice would be done to the representatives of persons who had insured their lives.

Priority of death. Presumption of survivorship.—Let us now take the case that several persons have perished together from some common cause; it may be material to determine which probably survived the other, since property may be claimed by different heirs through the several deceased persons. According to the civil law, when the parties who perished together were parent and child, the latter, if under the age of puberty, was presumed to have died first, but if above this age, the rule was reversed. In the case of husband and wife, the presumption was in favour of the survivorship of the husband. These presumptions were based on the assumption that the party deemed to have survived was, by his superior strength and vigour, likely to have struggled longest against the common death. The law of France is in some measure based upon these provisions; but in England there is no absolute rule on the subject. The question,—Which of two parties survived the other,—is left to be determined by a jury or judge, according to the facts proved; such as the comparative age, strength, and danger to which they were respectively exposed, and any other circumstances capable of proof which are calculated to throw light upon the case. It has, however, happened on several occasions, that there have been no such indicia, and the case has then generally terminated by a compromise of the suit. There is a well-known instance which is referred to by most medico-legal writers, that of *General Stanwix*, in which the General, with his second wife and a daughter by a former marriage, sailed in a vessel from Dublin to England. The ship with all on board was lost at sea, and no account of the manner of her perishing was ever received. Several suits arose out of this accident. The maternal uncle of the daughter claimed the effects of the General, under the principles of the civil law. This case was not decided: the suit was compromised on the recommendation of Lord Mansfield, who said he knew of no legal principle on which he could decide it. In another case, Sir W. Wynne said, that in his judgment, the most rational presumption was that all had died together; and that, therefore, none could transmit rights to another. In a third, where husband and wife were drowned, and a claim was made by the wife's relations, Sir J. Nicholl said he assumed that husband and wife perished at the same moment; and he therefore granted administration to the representative of the husband, as the person in whom the property really vested at the time of the decease of both. He, however, expressly observed that in giving this judgment, he was not deciding that the husband actually survived the wife.

In a more recent case, the property was vested in a wife, and she and

her husband were drowned together without any of the circumstances being known. A claim was made by the husband's heirs, on the presumption that he was the survivor. Sir H. Jenner decided according to the principle that where a party dies possessed of property, the right to that property passes to his next of kin, unless it be shown to have passed to another by survivorship. Here the next of kin of the husband claimed the property which was vested in the wife; that claim must therefore be made out: it must be shown by him that the husband survived. In the absence of evidence, the parties must be presumed to have died at the same time, and the property therefore would remain where it was vested, unless there was evidence to show that it had been devested by survivorship. (See also case of *Rivoire*, p. 179.)

Some years ago the following question was referred for a medical opinion:—whether it was likely, in the drowning of persons of different ages and sexes, in a confined apartment (the cabin of a vessel), that one should have survived the other. An officer in the army died in 1819, leaving a wife and two daughters, bequeathing property among them. In 1823, the widow married again, and by this second marriage she had several children: one of these, a son, survived. One of the daughters by the first marriage, Margaret, died in 1825, before majority, intestate, and leaving only as next of kin, her sister Johanna and her mother. In 1834, the mother, her daughter Johanna, and her son, the last surviving child of the marriage between her and her second husband, were drowned on the coast of Norfolk, in the cabin of a sailing-packet, while on their way to Scotland. The vessel filled with water from the skylights of the cabin during a storm. A few minutes before the catastrophe, all in the cabin were seen and spoken to, but not one of them was heard to speak or was seen alive after the cabin had become filled with water, which was said to have happened instantaneously. The deaths of the mother, daughter, and son were supposed to have taken place at one and the same instant of time; at least it could not be proved by the direct testimony of any person that he saw any one of the three alive, or that he heard the cry or speech of any one of these three, after the death of the other or either of them. It may be mentioned that the mother was corpulent, and, by the ill-treatment of her husband, a broken-hearted woman, about forty-two years of age; the daughter was a stout healthy girl of about twenty, and the son about six years of age. Physical and constitutional strength were thus decidedly in favour of the survivorship of the daughter Johanna, who was in right of considerable funds at the time of her death, and she died intestate. A claim was made for her property by her nearest blood relation, her paternal uncle-german. Her mother's second husband being still alive, claimed the property, as the representative of his wife, or his son, presuming that Johanna died before them, and that her property became vested in them. The opinion of Dr. Lushington, as counsel, being requested on this case, he stated that as to the question of survivorship, the presumption of law, in the absence of evidence to the contrary, was that the mother, daughter, and son all died at the same moment. The consequence would be, that none of the parties could transmit to the other. The paternal uncle would therefore be entitled to Johanna's property, on the principle already applied in so many cases, that the property being vested in her, those who desire to take it on a presumption, must produce evidence to show that she died before those persons through whom they set up a claim.

In this case there was not the least ground, medically speaking, for assuming that one of these persons survived the other. There was no evidence as to whether they were in different parts of the cabin, or whether the water reached one before the other; and in the absence of all facts of

this kind, it would be an arbitrary assumption to assign survivorship t one.

It has been supposed that when males and females, and the young an aged, are placed in exactly similar circumstances with regard to impendin danger, that a male or adult would survive; but on what principle c such an inference be drawn, when many inappreciable circumstances m have really led to the prior death of the male adult? A case which w decided in America some years since is calculated to show that a fix arbitrary principle, like that of the Roman law, with regard to the dea of husband and wife, must operate unjustly.

There is no doubt that the rules which influence English Courts these occasions are based on equitable principles. A right to property on acquired is not permitted to be taken away upon a mere *presumption;* t right may be averted by the production of satisfactory evidence, medical general, but until this is brought forward, the property is considered to vested in the holder and his heirs. Presumptions founded on age, se or the relative strength of persons are rather to be regarded as *assumptio* inadmissible, except when most strongly supported by direct evidence.

Under these circumstances it is scarcely necessary to refer to the rul which have been laid down by some medico-legal writers, in reference the priority of death among persons who perish by a common cause, by fire, starvation, suffocation, drowning, cold, or collisions on railway Devergie asserts that a female will survive a male adult when both a equally exposed to suffocation from carbonic acid; but no sufficient numb of cases have been observed to allow a fair medical inference on th point to be drawn; and very strong evidence would be required by English judge to satisfy him that such an opinion was universally corre As little can it be presumed that the young perish from suffocation befo the old. These events are commonly treated as involving circumstanc which are from their nature unascertainable; and they are therefore de with according to fixed legal, and not according to variable medical rul There are probably no two cases of death from a common cause, in whi all the circumstances will be alike; hence any general medical rule f assigning survivorship to one in preference to another, is inapplicable.

The case of *Underwood* v. *Wing* (Rolls Court, July, 1854), involv a singular question of survivorship. The opinions of Sir J. Paget, Brinte and the author, were requested on one of the questions at issue in this ca namely, whether, under an apparently simultaneous death from drowni as a result of shipwreck, the husband survived the wife or the wife t husband for even the shortest conceivable period of time. The following an outline of the facts:—

Mr. Underwood, æt. 43, and his wife æt. 40, had a daughter aged 1 and two sons of the respective ages of 15 and 13. The husband a wife were entitled to some property, and being about to go to Au tralia, with their children, they respectively made their wills, the o giving to the other absolutely, the whole of their respective properties, a by each such will, they declared, that if the one to whom the same w given should *die in the lifetime of the donor*, the property should go and divided among their three children on their attaining majority; and th in case all their said children died under 21, they then directed that th property should go to their mutual friend, Mr. Wing, the defendan Underwood was a tall, powerful man with a full and broad chest, of t height of six feet and one inch; he weighed about twelve stone. His wi was a little woman of rather delicate habit, not exceeding five feet tv inches in height, and weighing between eight and nine stone. The together with their three children, sailed from London on Oct. 13th, 185

by the ship 'Dalhousie,' and were wrecked off Beachy Head. Every person on board, with the exception of one seaman named Read, perished. Read stated that the ship foundered early on the morning of Oct. 19th, and went over on her beam-ends, and so floated for about twenty minutes, and then went down. Shortly after she so went over, Underwood, his wife, and their two boys were pulled out of the cabin window on to the side of the ship, Underwood having nothing on but his coat and trousers, his wife and the two boys being in their night-clothes. In the excitement of the moment, Underwood clasped his wife in his arms, and the boys clung to their mother: while in that position a heavy wave swept the four from the side of the ship into the sea, and as the sailor says, he never saw them afterwards, so he presumes they all went down together. The daughter was seen alive on the deck shortly afterwards, and she was lashed by him to a spar and set adrift on the sea. It further appeared from the evidence of Read, the only witness of the facts, that he saw the daughter alive in the sea, after the spar of timber had been cast adrift, and long after the father, mother, and sons had been swept overboard. Upon the question of survivorship, as to Mr. or Mrs. Underwood or of the two sons, a great body of evidence was adduced. Wooton and Hancock were examined, and they deposed that in their opinion the deaths of all the four, *i.e.* the father and mother and two sons, had been *simultaneous*. Other surgeons had been examined, who gave it as their opinion that Underwood, who was a strong man, and a good swimmer, must have survived his wife and children in the waves, and that a man accustomed to swim would have it in his power to preserve his breath longer than a woman or boys so young as his two sons. Others thought that whilst the woman and her sons died of asphyxia, the man, being strong and muscular, might have died before them from an attack of apoplexy.

The Master of the Rolls held that the weight of evidence as to Mr. and Mrs. Underwood and the sons, was that they had been swept off the wreck at one and the same moment, and had perished simultaneously. The evidence of Read, who conducted himself with great courage and humanity upon the occasion, appeared to be worthy of credence, and he decided that as respected these four individuals, there was no survivorship. With respect to the daughter Catherine it was established, beyond a doubt, as he thought, that she had been seen alive after her parents and brothers had perished in the raging sea. Then in her instance there was no doubt she survived them, and the result must be that the property could not vest in the defendant, but in the plaintiff, who was the next of kin of Catherine Underwood. The event upon which the defendant was to take never arose, and the claim of the plaintiff, as next of kin, was fully established.

The case was carried by appeal to the Lord Chancellor's Court. The point referred for our consideration, was not whether the daughter survived the parents (as all the children died under the age of 21), but whether, upon ordinary physiological principles, the husband must not have survived the wife, or the wife the husband, and in either case the defendant would have a well-founded claim to the property. The plaintiff, Underwood, a lady, and next of kin of the husband, claimed the property on the ground that neither survived the other, and that both must have died together.

The joint opinion was to the effect that the great strength of the husband, with the knowledge that he was a good swimmer, would justify a medical inference that he might probably have survived his wife, although only for a short period. Further, we were of opinion that, considering the nature of death by asphyxia, even if husband and wife were submerged at the same instant of time, there was no proof that they had really died at the

same instant. Taking death to consist in the entire and permanent stoppage of the action of the heart, it could not be inferred of these two persons, differing as they did in age, sex, and strength, that the heart in each ceased to pulsate at the same fractional part of a second of time. Unless this physiological improbability, if not impossibility, were admitted, then it followed either that the husband survived the wife, or the wife the husband, and in either case, Wing, the defendant, would take the property under the will of either. The case was heard by the Lord Chancellor (Cranworth), and two of the Common Law Judges; and in Feb. 1855, the Lord Chancellor delivered the following judgment:—

The Master of the Rolls held, that as the only title of the defendant rested upon a survivorship, it was incumbent upon him to make out his case. No such case had been made out, and therefore the plaintiff, as representing the next of kin, was entitled to the property. His Honour was also reported to have stated it to be his opinion that the evidence had the legal effect of proving that Mr. and Mrs. Underwood died at the same time. In this latter opinion the judges differed from the Master of the Rolls, but agreed with him on the main point, that the defendant had failed to make out his title. His Lordship in now giving judgment said, that he had had a conversation with the Master of the Rolls since the opinion of the judges had been given, and his Honour had stated that he did not mean, by any expressions he might have used, to declare it to be his opinion that Mr. and Mrs. Underwood died at the same time. All that he meant was, that in the absence of any positive evidence on the point, the property must go in the same way as if they had actually expired at the same moment. Without doubt it was almost impossible that two human beings could die at the same moment. Time, like space, was divisible into infinitesimal parts, and one of them might be considered as having died a millionth part of a second before the other. The real point in the case, however, was that it was not known, and could not be ascertained, which of the two, the husband or the wife, was the survivor. The first and simple view of the case was, that a lady disposed of her property by will to a particular person in the event of her husband dying in her lifetime. Now, in the absence of any proof that the contingency upon which the gift depended had taken place, the property must be considered as undisposed of, and the appeal would, as a matter of course, have been dismissed. An ingenious argument had, however, been made use of for the defendant, to the effect that, as there was a manifest intention in the will of Mrs. Underwood to dispose of her property in the event of her surviving her husband, the onus of proving that she did not survive him lay upon the parties disputing the disposition, and a great number of cases had been cited in support of this view. His Lordship then analyzed the cases, and stated it to be his opinion that they did not affect the present case, and he therefore came to the conclusion that the decision of the Master of the Rolls was correct. The appeal must be dismissed, but, under the peculiar circumstances of the case, without costs. Litigation did not stop here. The case was carried by appeal to the House of Lords, and in February 1860, six years after the commencement of the suit, a final judgment was given confirming the decree of the Master of the Rolls and of Lord Cranworth, the then Lord Chancellor (Campbell) dissenting from this decision.

The remarks made by Best, although published some years before the occurrence of this singular case, embrace the whole subject by anticipation. He says, 'The true conclusion seems to be, that the law of England recognizes no *artificial* presumption in cases of this nature; but leaves the real or supposed superior strength of the parties perishing by a common

ity to its natural weight, as a *circumstance* proper to be taken into leration by a jury or judge called on to determine the question of rorship, but which *circumstance* standing alone, is insufficient to shift urden of proof. If, therefore, the party who, by laying claim to rty on the ground of the survivorship of one individual over another, upon himself the onus of proving *that* survivorship, has no further ıce than the assumption that, from age or sex, one party struggled r against their common death than his companion, it seems that no ɔ would have been made in favour of the claim. But, on the other it is not quite correct to say that the law *presumes* both to have ıed at the same moment. This would be to establish an artificial mption against manifest probability, although the practical conıce is in many cases the same; because if the party on whom the lies, cannot show affirmatively which died first, the question will ɜarily be treated by the tribunal as a thing from its nature unascerɔle, and that for all that appears to the contrary, both died at the moment.' (Op. cit. p. 201.)

reference to the case of *Underwood* v. *Wing*, it is obvious that the ılty was created by the legal rule which threw the onus of proof on aimant under the two wills. The case for the next of kin, who was ıentioned in the will, was that the husband and wife died at the same ıt of time; but this was a physiological impossibility; and had the of this been thrown upon the plaintiff the case must have failed. ontention of the defendant was that the testator and testatrix could ıve died at the same instant. This negative proposition could not, of ɛ, be proved by direct evidence; it became simply a medical inference: hen the law declares that in the absence of evidence the property go in the same way as if the parties had actually expired at the same ıt, *i.e.* as if they had died intestate, this is deciding such questions by which is as arbitrary in its operation as that of the Code Napoleon. derwood v. *Wing* this rule of law practically affirmed that an event place which was physiologically impossible, and upon that event the of husband and wife were set aside, and the property was handed to hose name was excluded from both wills.

ugh *Swinton Ball*, with his wife and adopted daughter, was lost on the steamer 'Pulaske,' on the coast of America, on June 14th, 1838. is will Ball bequeathed his property to his wife, and a claim was by her heirs on the ground that she had survived her husband. It that an explosion took place on board the steamer at eleven o'clock ght, and that husband and wife were at the time in different parts of essel, and thus separated from each other. Mr. Ball was not seen the explosion, and, although he perished with many others, the precise ıt which he died could not be determined. Mrs. Ball was seen after plosion, rushing in a terrified manner about the deck, calling for her nd, but no reply was made. She was soon afterwards missed, the ɛnade deck to which she had retreated, having been submerged with lf and all who were on it. Chanc. Johnson, before whom the case ırgued, said that it was a case to be decided by testimony, and as ght on the part of Mrs. Ball was derivative, the burden was on the iffs to prove that she was the survivor. The evidence regarding the ppearance of Ball, when, had he been living, there was sufficient for him to have shown himself with others on deck, and to have an effort to join his wife, was considered by the Chancellor to be ısive of his death at the time that the wife was seen and recognized any who knew her. On these considerations he decided in favour ɔ plaintiffs, that the wife survived the husband, and, therefore, she

succeeded to his estate. On appeal, this decision was confirmed. ('Amer. Journ. of Med. Sci.' July 1845.) This case is peculiar in the fact that the wife alone was seen living, and the nature of the accident was such as to render it probable that the husband had perished in the explosion. The counsel for the defendants ingeniously argued that as the death of the wife could be fixed, while that of the husband could not be fixed, it was fair to presume that she died first, but this argument failed to satisfy the Court. The plaintiffs were not required to prove when the husband really died: they established enough to render it probable that the wife was the survivor.

A husband and wife quarrelled. The wife was a passionate woman; she suddenly ran across a lawn from the room in which they were sitting (the windows being open to the ground), and threw herself into a deep pond. Her husband followed immediately, and tried to save her from drowning. He either rushed or fell into the pond, and both were drowned. There was some evidence that the wife rose to the surface of the water after submersion, while the husband, it was stated, sank at once; but it was not made clear whether this reappearance of the woman's body on the surface took place before or after the submersion of her husband. There was, therefore, a want of evidence to fix the priority of death on either. The suit was compromised.

The following cases, one of which was tried in England and the other in Scotland, arose out of the fate of the expedition to the Polar seas, undertaken by Sir J. Franklin in the year 1845. The first is that of *Ommaney* v. *Stillwell* (Rolls Court, Nov. 1856). His Honour, in giving judgment, said that, although there was no point of law in it, it was one of great difficulty to decide upon, from the paucity and singular nature of the evidence adduced. The sole question in the case was whether a father or son, *i.e.* James or Ed. Couch, died first. James, the father, died in Jan. 1850. Of this there was no dispute. Edward, the son, went as mate on board Sir J. Franklin's ship 'Erebus' on the Arctic Expedition in Aug. 1845. The fact to be determined, was whether he was alive or dead, and, if dead, whether he predeceased his father or not. The only evidence on this point was to be found in the statement of Dr. Rae upon the probable fate of Franklin and his crew. Rae stated that he discovered the remains of a number of persons, supposed to be part of the 133 persons who joined in Sir J. Franklin's expedition, and in 1854 he was informed by some Esquimaux that in April or May 1850, they saw a party of about thirty white men dragging a boat along, their ship being crushed up in the ice. Of these men, all were pulling or pushing at the boat but one, who appeared to be their leader, and was supposed by Rae to be Sir J. Franklin. The Esquimaux further added that they saw the white men kill some birds which never visited that region before the month of May. Now, if this story of the Esquimaux could be relied upon, and it could in any way be shown that Ed. Couch was among those persons whose remains Rae had discovered, there would be some kind of evidence, at any rate, to show that Ed. Couch being alive in May 1850, survived his father, Jas. Couch, who died in Jan. of that year. But there was nothing to show that Ed. Couch was one of these persons, or anything whatever that could satisfy his mind that Ed. Couch was among these then survivors of Sir J. Franklin's crew. One of the Chief Clerks of the Court had, however, decided in favour of the son having survived the father, and, as it was just as impossible to say whether he did so survive or not, the Court, for the purpose of avoiding further litigation, so far as lay in its power, would confirm the Chief Clerk's report. Decree accordingly.

The second case came before the Court of Session in Scotland in 1857. ıe question at issue, was whether a naval officer who went out with the anklin expedition was dead; and, if so, when must he be held to have d. The late *Adam Fairholme*, who died in 1853, bequeathed his pro- rty to his nephew, Jas. Walter Fairholme, lieutenant in the Royal Navy, ıo sailed from Northfleet, on board the 'Erebus,' for the North Seas, in y 1845, and had not since been heard of. George Fairholme, another phew, had instituted an action to have it found, under the destination of odicil, that he was entitled to the whole of the testator's personal estate. ıis was opposed by other relatives, whose interests depended on whether not Jas. Walter survived his father. Proof by commission was taken th the view of legally establishing the questions raised in the case, and ong those examined were Rae, Sir J. Richardson, Jas. Hargreave, chief ctor in the service of the Hudson's Bay Company, Capt. Penny, and hers. Rae expressed his belief that those persons who were reported have been seen in the spring of 1850, must have died in the May of st year, and these he believed to have been the last survivors of Frank- n's party. Hargreave thought that some of the party might have sur- ved a single winter after they had been seen by the Esquimaux in 1850, t certainly not longer. Richardson said: 'That if any of the party ached the country where they were said to have been seen at the end the winter of 1849–50, it was impossible for them to survive a single ar with any means they could have at their disposal.' Penney re- arked: 'I do not think that any of the party could have survived 1852; ey must either have perished from hunger, or the hostile attacks of the tives.' The Lord Ordinary reported the whole circumstances of the se to the Inner House, expressing his own opinion that there was thus ong presumptive evidence that Fairholme perished together with his mpanions some time prior to the end of 1852, and consequently that he deceased his uncle, the testator, who died in May 1853. He thought st under these circumstances, the pursuer, George Fairholme, was en- led to a decree in his favour, but qualified by this condition, that before yment, he should grant a bond with sufficient security to warrant the fender against all hazard from any claim to the money decerned for, by ut. Fairholme or others in his right.

It would seem from an old case, *Broughton* v. *Randall* ('Croke's Eliza- th,' 503), that provided there be some direct evidence, a very small amount proof is required for survivorship. A father and son were seised as joint ants and to the heirs of the son. Both father and son were hanged at same time, in one cart; but because the son, as deposed to by some of witnesses, survived, as appeared by the shaking of his legs and probably ne other tokens, the wife was held entitled to her dower. (Best, op. p. 194.)

There has been much ingenious discussion as to the survivorship of e mother or child, when both die during delivery, and nothing is known specting their deaths. So far as we are aware this question has only curred once in an old case, quoted by Beck; and then some local German urt arbitrarily decided that the child survived the mother, basing its cision, according to Valentin, upon the grounds—1. that the mother as exhausted by the labour, and 2. that the infant would not have died, til deprived by the death of the mother of its nourishment. Now it is ite possible that the child might have died soon after its birth, and the other have survived: at any rate the medical reasons for this view are just good and just as forcible as those against it, and the only equitable mode dealing with such cases, when a legal question of a right to property is pendent on the decision, is to treat them according to the principles

followed in contested survivorship. Those who would benefit by the presumption that the child survived the mother should be required to adduce satisfactory proofs.

In some cases of presumed survivorship medical evidence may be of service—as were two persons are found dead from wounds affecting different parts, and these wounds are of different degrees of severity—or where two are found dead from any cause, and the body of the one is cold and rigid, while that of the other is warm and pliant. Here we have medical facts which may serve to guide the Court, and enable it to come to a correct decision.

In *Greetham* v. *Milnes* (Rolls Court, Nov. 1871) a question arose in reference to the survivorship of one *Hentig*, who was a member of Leichhardt's exploring party in Australia. They left Sydney for the interior in Feb. 1848, with the intention of traversing the continent, and have not since been heard of. The testator died in Feb. 1850, having bequeathed property to Hentig, who was his nephew. The heir-at-law of the testator claimed the property on the ground that Hentig died before the testator, who did not die until two years after Hentig was last seen and known to be alive. The heir-at-law of Hentig rested his claim on the absence of any proof of death at any time, and that the members of the expedition, including Hentig, might have survived at least two years in Central Australia. The Master of the Rolls said that the inference he must draw from the established facts was that Hentig died within a year of the exploring party leaving Sydney, and that the heir-at-law of the testator was therefore entitled to the property.

In a similar case (*Lewis's Trusts*, V.-C. Malins, Dec. 1870) the question was whether a legatee did or did not survive a testator so as to take a sum of 4000*l.* bequeathed to him under the will, which was dated in the year 1858. The testator died on Feb. 20, 1860. The legatee, Thomas Lewis, went to Australia in the year 1858, and the last that was heard of him was by a letter written to a cousin dated Jan. 3, 1859. Seven years having elapsed, he was presumed to be dead, but the question was whether he survived his father. The Vice-Chancellor said that the law in cases of this kind presumed the continuance of life until the expiration of seven years, when the contrary presumption of death arose. The case of *Phene's Trust* had, however, displaced that rule, and had laid down that in all cases it was incumbent on a person claiming property by reason of a person being alive at any particular time, to establish affirmatively that fact. It was manifest, therefore, that the representatives of the legatee, in order to claim their legacy, must show that the legatee survived the testator—the *onus probandi* being, according to the case cited, thrown upon them. They had not discharged, and could not discharge, that *onus*; therefore, as he was bound by the case in the Court of Appeal, he must hold that the legacy was never validly given, and that the residuary legatee took the fund as part of the estate.

In *Huelin* v. *Wilson*, before V.-C. Malins, July 1871, the question was whether the deceased Huelin survived his housekeeper or not. He had made a bequest in favour of this woman. In May 1870, Huelin and his housekeeper were found dead in a house at Brompton. They had obviously been murdered. The body of Huelin was found buried, while that of the woman was packed in a box, and had marks about it of more recent death. The medical and circumstantial evidence left no doubt that the murder of the woman had not taken place until after the death of Huelin, the testator, and the Vice-Chancellor decided accordingly that she survived to take the bequest. In April 1872, a case came before the Probate Court which involved the question of survivorship of husband or wife (*Re J. R.*

Jeferies). It appeared in evidence that they had died on the same day and within a short time of each other, but there was some evidence that about an interval of two hours elapsed between the deaths of husband and wife, the husband being at the time an inmate of a lunatic asylum. The administration of the estate was claimed by the relatives of both, but as there was proof that the husband had really survived, although but a short time, the decision was made in favour of the relatives of the husband.

In a case, in which husband and wife were found dead, both severely wounded and the bodies burnt, Ollivier remarked that the burns on the body of the wife had the characters of those which are produced during life, while those on the body of the husband were exactly like burns which are caused on a dead body. He thence inferred, as they were exposed to the same cause of burning, that the wife survived the husband; for he considered that all signs of vitality must have ceased in him before the fire could have reached his body.

In 1881 a man named Rivoire, and his wife, both of the age of 35 years, were landing on the bank of the Rhone, when their boat was swamped by a passing steamer. They and their friends were simultaneously precipitated into the water. The woman seized another man of the party, one Maniette, who, however, disengaged himself from her grasp, seized her by the hair of the head, and proceeded to swim to the bank with the woman in tow. She was then apparently in a state of syncope. At this juncture the husband, who was frantically uttering cries, seized Maniette by the neck; the result being that the two Rivoires sank simultaneously, and did not again rise to the surface. The body of the husband was not recovered, but that of the wife was found *in situ* next day. The countenance was placid, and there was great pallor of the surface. The property of the deceased pair was so disposed by will that the blood relatives of the survivor acquired the whole. The respective representatives of Rivoire and his wife claimed the property; but the suit in the end was compromised. M. Beauvais energetically contended that, taking into consideration the sex of the woman, which would favour syncope—and hence a slower death in the water than from asphyxia—the fact that she was observed to be to all appearance insensible before her final disappearance, and the state of her body after death, Madame Rivoire must of necessity have been the survivor. He strenuously contended also that M. Rivoire must of necessity have perished from rapid asphyxia. Brouardel more cautiously declined to express any opinion, in the absence of an examination of the body of the husband, as to which of the two was the survivor. ('Jour. de Méd. de Paris,' t. ii. pp. 91, 121.)

POISONING.

CHAPTER 10.

DEFINITION OF THE TERM POISON—DEADLY POISONS—MECHANICAL IR
INFLUENCE OF HABIT AND IDIOSYNCRASY—CLASSIFICATION—SPE
RACTERS OF IRRITANT, CORROSIVE, AND NEUROTIC POISONS.

Definition.—A POISON is commonly defined to be a substance, wh
administered or taken *in small quantity*, is capable of acting del
on the body: in popular language, this term is applied only to t
stances which destroy life in small doses. This popular view of t
of a poison is too restricted for the purposes of medical jurispruc
would obviously exclude numerous compounds, the poisonous pro
which cannot be disputed—as, for example, the salts of copper,
lead, and antimony; these, generally speaking, act as poisons o
administered in *large* doses. Some substances, such as nitre,
been observed to have a noxious action except when taken in large
while arsenic acts as a poison in a small dose; but in a medico-le
whether a man dies from the effects of an ounce of nitre, or two
arsenic, the responsibility of the person who criminally admin
substance, is the same. Each may be regarded as a poison, diffe
the other only in its degree of activity, and in its mode of operat
result is the same; death is caused by the substance taken, and th
required to destroy life, even if it could be always accurately de
cannot enable us to distinguish a poisonous from a non-poisonous s
If, then, a medical witness be asked, 'What is a poison?' he mu
of adopting this popular definition, or of confining the term pc
substance which is capable of operating as such in a small dose
once.

In legal medicine, it is difficult to give such a definition of a
shall be entirely free from objection. Perhaps the most comprehens
can be suggested is this:—'A poison is a substance which, when
into the blood, is (by a direct action—Ed.) capable of seriously
health or of destroying life.' There are various channels by whic
enter the blood: some are in the form of gases or vapours; thes
rapidly through the lungs: others are liquid or solid, and these n
the blood either through the skin or through a wound; but more c
through the lining membrane of the stomach or bowels, as when
taken or administered in the ordinary manner. The latter chi
rise to medico-legal investigations. Some substances act as po
any one of these channels: thus arsenic is a poison whether it e
blood through the lungs, the skin, or the stomach and bowels:
poisons as those of the viper, of rabies, and of glanders, appear t
affect the body only through a wound in the skin. When introdu
the stomach, these animal poisons have been found to be almost i
adopting the above definition of a poison in a medical sense, it is
remark that there are some substances which are regarded as
although absorption into the blood does not appear to be always n
to their action. The mineral acids and alkalies belong to this
bodies. They are corrosive poisons: they operate injuriously by

he destruction of living parts; and whether applied to the skin, the tomach, or (in the form of vapour) to the air-cells of the lungs, they estroy life by the local changes to which they give rise, and the inflammation which is a consequence of their action.

It is not easy to define the boundary between a medicine and a poison. It s usually considered that a medicine in a large dose is a poison, and a poison in a small dose is a medicine; but a medicine such as tartarated ntimony may be easily converted into a poison, by giving it in small (medicinal) doses at short intervals, either under states of the body not dapted to receive it, or in cases in which it exerts an injuriously depressing ffect. Some deaths have been occasioned by this wilful misuse of antimony n doses which might be described as *medicinal*, although in the cases eferred to, no other intention could have existed, in the secret administraion of this substance, than that of destroying life. A person may die ither from a large dose of a substance given at once, or from a number of mall doses given at such intervals that the system cannot recover from he effects of one before another is administered. This remark applies to great number of medicines which are not commonly included in a list of oisons.

In reference to the *medical* definition of a poison, it is necessary to bserve that the law does not regard the manner in which the substance dministered acts. If it be capable of destroying life or of injuring health, t is of little importance, so far as the responsibility of a prisoner is conerned, whether its action on the body is of a mechanical or chemical nature, or whether it operates fatally by absorption into the blood or not. Thus a substance which simply acts mechanically on the stomach or bowels ay, if wilfully administered with intent to injure, involve a person in a riminal charge, as much as if he had administered arsenic or any of the rdinary poisons. It is, then, necessary that we should consider what the w strictly means by the act of poisoning. If the substance criminally dministered destroys life, whatever may be its nature or mode of operaon, the accused is tried on a charge of murder or manslaughter, and the uty of a medical witness consists in showing that the substance taken was e certain cause of death. If, however, death be not the consequence, n the accused may be tried for the attempt to murder by poison (24 & Vict. c. 100, s. 11). The words of this statute are general, and embrace l kinds of substances, whether they are popularly or professionally arded as poisons or not. Thus it is laid down that—

'Whosoever shall administer, or cause to be administered to or taken by y person, any poison, or *other destructive thing*, with intent to commit rder, shall be guilty of felony.'

Whether the administering be followed by any bodily injury or not, the t is still a felony, provided the *intent* has been to commit murder. The empt to administer or the attempt to cause to be administered to, or to taken by any person, any poison or *other destructive thing*, with the like ent, although no bodily injury be effected, is also a felony (s. 14). If y doubts formerly existed whether the *external* application of poisons, . by wounds or ulcerated surfaces, would be included in the words dministering or taking,' they are now entirely removed by the Criminal w Consolidation Act, 1861. The 22nd section specially applies to such offence, and the 15th section provides that 'Whosoever shall, by any ans other than those specified in any of the preceding sections of this t, attempt to commit murder, shall be guilty of felony.' Under the same t. of this statute, in reference to attempted poisoning, some offences are mprised, which formerly escaped punishment: 'Whosoever shall unlawlly apply or administer to, or cause to be taken by, or attempt to apply

or administer to, or attempt to cause to be administered to or taken by any person, any chloroform, laudanum, or other stupefying or overpowering drug, matter, or thing, with intent, in any of such cases, thereby to enable himself or any other person to commit, or with intent, &c., to assist any other person in committing any indictable offence, shall be guilty of felony.' A medical man was charged with 'attempting to cause to be administered' to an infant, a poisonous dose of laudanum. It was stated by a woman who nursed the child that the accused delivered to her two bottles containing a brown liquid, labelled 'one teaspoonful every three hours,' and directed her to give it to the child. None was given. Some months after the death of the child from natural causes, this charge was raised, and the bottles, still full of liquid, were produced as evidence against the accused. On analysis the prescribed dose contained about five minims of laudanum, or nearly one half-grain of opium—a dose likely to prove fatal to an infant only a month old. Assuming the statement of the nurse who made the charge to be true, the only inference to be drawn from the prescription of such a dose for an infant by a medical man, would be that he intended to destroy the life of the child. The charge fell to the ground, as clear proof was given that the woman who made it was not to believed on her oath, and that it had originated in a desire to extort money.

Poison is not always administered with intent to murder. On many occasions it has been mixed with food, and thus administered with a view to injure or annoy a person. Cantharides have been thus frequently given, and in one instance (Nov. 1859) eight members of a family suffered from severe symptoms of poisoning by reason of the wanton administration of this drug. In April 1860, several members of a family suffered from severe sickness, as a result of tobacco having been put into water contained in a teakettle; and tartar emetic has been in some cases dissolved in beer or other liquids as a mere frolic, without any proved or probable intention on the part of the offender to destroy life. The case of *M'Mullen* (Liverpool Aut. Ass., 1856), revealed an extensive system of poisoning in the northern counties, in which tartar emetic was the substance employed. This drug, mixed with cream of tartar, was openly sold by druggists under the name of 'quietness powders,' and the evidence established that women gave these powders to their husbands with a view to cure them of habits of drunkenness. Hitherto, when the intent to murder had not been proved, the offender had escaped, although great bodily injury might have been done by his wanton or malicious act. Sect. 23, 24, and 25 of the Consolidation Act, c. 100, provide for this omission :—

'23. Whosoever shall unlawfully and maliciously administer to, or cause to be administered to or taken by any other person, any poison or *other destructive* or *noxious thing*, so as thereby to endanger the life of such person, or so as thereby to inflict upon such person any grievous bodily harm, shall be guilty of felony.'

'24. Whosoever shall unlawfully and maliciously administer to, or cause to be administered to or taken by any other person, any poison or other destructive or noxious thing, with intent to injure, aggrieve, or annoy such person, shall be guilty of a misdemeanour.'

'25. If, upon the trial of any person charged with the felony above mentioned, the jury shall not be satisfied that such person is guilty thereof, but shall be satisfied that he is guilty of the misdemeanour above mentioned, then and in every such case the jury may acquit the accused of such felony, and find him guilty of such misdemeanour.'

It will be perceived that the words of the statute leave the question 'What is a poison?' to depend upon the medical evidence adduced: and in order to include all substances of an injurious nature, although they

may not be strictly speaking poisons, the words '*destructive* or *noxious thing*' are employed. Hence, on these occasions, a medical witness must be prepared to prove that the substance was either a poison or a destructive or noxious thing. In a trial (Essex Lent Ass. 1850, *Reg.* v. *Hayward*), a woman was charged with administering *white precipitate* to her husband, with intent to kill. She was acquitted on the ground that there was no evidence to show that white precipitate was either a poison or a destructive thing. It is, however, placed beyond doubt that this substance is not only capable of producing all the effects of an irritant poison, but of destroying human life; hence this acquittal was based on a pure mistake. *White hellebore*, *Lobelia inflata*, and *Oil of turpentine*, have been erroneously pronounced not to be poisons under similar circumstances; in fact, when this question is raised, unless the medical evidence received by a Court be very closely investigated, mistakes may arise, owing perhaps to want of experience, or want of reflection, on the part of those to whom the question is put.

The quantity of a poisonous substance found in an article of food, or in a dead body, does not affect the culpability of a person indicted for administering it. In the case of *Hartley* (C. C. C. May 12, 1850), in which an attempt was made to administer sulphuric acid mixed with coffee, Cresswell, J., stated—if poison be administered with intent to murder, it is not necessary there should be enough in the article administered to cause death. If any poison be there, and the intent be proved, the crime of attempting to administer poison is complete. Erle, J., ruled to the same effect, in reference to the discovery of a small quantity of arsenic in a dead body (*Reg.* v. *Bacon*, Lincoln Sum. Ass. 1857). In *Reg.* v. *Southgate* (Chelmsford Lent Ass.), Parke, B., said, in reply to an objection taken, it was quite immaterial to define or prove in what vehicle a poison was given, or whether it was administered in a solid or liquid state.

This question, 'What is a poison?' may present itself under another aspect. In *Reg.* v. *Cluderay* (Exch. Chamber, Jan. 19, 1849), the prisoner was indicted for administering poison with intent to murder. He was proved to have administered to a child nine weeks old, two berries in the husk, of *Cocculus Indicus*, and the berries passed through the body of the child without doing any injury. It was submitted for the prisoner, that being in the husk, they could not be considered a poison. The point was reserved by Williams, J., who tried the case at York. It was now contended for the prisoner, that although the kernel of this nut was poisonous, still having been given in the husk, which was hard of digestion, it could not be considered an administering of poison within the statute. The Chief Justice said the Court was of opinion that, when a man administered something that was poison with intent to murder, but in such a way that it did not act, he was guilty. Conviction affirmed. This is the only reasonable view to take of such a frivolous objection. The seed contains the poison, but the husk is inert: nevertheless the berry as a whole must be regarded as a poison.

Deadly Poison.—The term 'deadly' can be applied with propriety only to those poisons which may prove speedily fatal in small doses, *e.g.* prussic acid, arsenic, strychnine, aconitine, and nicotine; and although it has been used in indictments in reference to such substances as blue or green vitriol, and sal volatile, this has arisen from an unnecessarily strict adherence to old legal forms. In a case (*Reg.* v. *Haydon*, Somerset Spring Ass. 1845), in which 'spirit of hartshorn' was thus described as a 'deadly poison,' and an objection was taken to the validity of the indictment, Erle, J., held that the word *deadly* was not essential; it was mere surplusage ('Law Times,' April 12, 1845).

Mechanical Irritants.—The substance administered may not be a poison in the medical signification of the term, and may it not be popularly considered as such; yet, when taken, it may be noxious to health or destructive to life. We have examples of substances of this description in iron-filings, powdered glass, sponge, pins and needles, and such like bodies, which have been administered with the wilful design of injuring, and have on various occasions given rise to criminal charges. In cases of this kind, the legal guilt of a prisoner may often depend on the meaning assigned by a medical witness to the words *destructive thing*. Thus, to take an example, liquid mercury might be poured down the throat of an infant, with the deliberate intention to destroy it. A question of a purely medical nature will then arise, whether mercury be a 'destructive thing' or not; and the conviction of a prisoner will probably depend on the answer. Should a difference of opinion exist, the prisoner will receive the benefit of the doubt.

Influence of Habit on Poisons.—Habit, it is well known, diminishes the effect of certain poisons: thus it is that opium, when frequently taken by a person, loses some of its effect for a time, and requires to be administered in a much larger dose. Indeed, confirmed opium-eaters have been enabled to take at once a quantity of the drug which would have killed them, had they commenced with it in the first instance. Even infants and children, who are well known to be especially susceptible of the effects of opium, and are liable to be poisoned by small doses, may, by the influence of habit, be brought to take the drug in very large quantities. This is well illustrated by a statement made by Grainger ('Rep. of the Children's Employment Commis.') It appears that the system of drugging children with opium in the factory districts at that time commenced soon after birth; and the dose was gradually increased until the child could take from fifteen to twenty drops of laudanum at once. This had the effect of throwing it into a lethargic stupor. Healthy children of the same age would be killed by a dose of five drops. The same influence of habit is manifested more or less in the use of tobacco, alcohol, ether, chloroform, morphia, strychnine, and other alkaloids. Christison has remarked that this influence is chiefly confined to poisons derived from the organic kingdom: it is so limited with regard to mineral substances that it can scarcely be said to exist, except with respect to arsenic and corrosive sublimate. There is satisfactory evidence that a human being has accustomed himself, by habit, to take arsenic daily in doses that would prove poisonous to the generality of adults.

In reference to the Styrian practice of arsenic-eating, Roscoe has published a case in which, according to information supplied to him, a Styrian took in one day four and a half grains of white arsenic, and on the day following five and a half grains, crushing the mineral between his teeth and swallowing it. The day after he had swallowed the second dose, the man left the place in his usual health, and there is no further record of him. Knapp states that a man once took in his presence seven and a half grains of arsenic; it did not produce the slightest visible influence on his feelings. A portion of his urine passed on the same and the following day was examined by Marsh's process, and it was found to contain arsenic. ('Ed. Month. Jour.' Jan. 1869, p. 669.) Other cases of a similar kind are related by C. Maclagan, in the same journal, Sept. 1864, p. 200. He saw one man swallow between four and five grains of arsenic in powder. This man had been accustomed to take it for a year, beginning with small doses; he did not suffer from any bad effects. A man, æt. 46, swallowed six grains of arsenic, washing it down with cold water. Arsenic was detected in the urine about an hour after the poison

ras swallowed; but as they were habitual arsenic-eaters, it is probable hat the eliminated arsenic may have been of longer date.

That such cases as these are of an exceptional nature is proved by a ase communicated to the 'Ed. Med. Jour.' 1864, p. 116, by Parkes, of Halifax. A man who had carried on the practice of arsenic-eating for hree or four years suffered from all the symptoms of arsenical cachexia. He sank under this practice, and after death the usual appearances of hronic poisoning by this substance were found. A chemical analysis howed only slight traces of arsenic in the liver, and none in the stomach. *Habit* appears to have usually so little influence on this substance under he most careful medicinal use in this country, that the author believes o medical practitioner has ever succeeded in causing a patient to take a lethal quantity, two grains at a dose. Hunt fixed the maximum dose at ne grain (two drachms of Fowler's solution). In Roscoe's informant's ase, the man swallowed, in two doses, on two successive days, a quantity f arsenic equivalent to *two ounces* and *a half* of Fowler's mineral solution, ia sufficient to kill five adults. There is, however, a difficulty in assign- ng the alleged tolerance of this poison merely to *habit*. Roscoe quotes rom Schäfer, 'a most important case of the administration of no less han 555 grains of arsenic to a horse in twenty-three days, without any vil effects being produced.' It is not stated that the animal began to ake arsenic in early life; and habit could have had but little influence in hree weeks on the large quantity here given, even admitting that small oses were given at first, and that these were gradually increased. As o evil effects were produced, the only inference is, that by some speciality f organization, arsenic was not a poison to this animal. There are on ecord several instances of human beings having recovered from very rge doses.

Roscoe's pamphlet satisfactorily shows that symptoms of acute poison- g, gastro-enteritis and death, are sooner or later the results of the adop- on of this dangerous practice in Styria. It would be difficult to persuade a English peasant, however ill-educated, that he could safely put into is daily food a substance which he used for destroying vermin,—or an nglish woman, that she could safely take, to improve her personal attrac- ons, a mineral which pregnant women were in the habit of using to rocure abortion.

The alleged impunity of the Styrians in the habitual use of arsenic, ay be occasionally quoted to explain the detection of the poison in a ead body or a motive for its purchase; but no scientific witness who has en anything of the operation of arsenic in this country can allow these atements to influence his opinion of its effects on human beings.

The only form in which the author has known the question of habit to be riously raised in medical jurisprudence is this: whether, while the more rominent effects of a poison are thereby diminished, the insidious or tent effects on the constitution are at the same time counteracted. The nswer is of some importance in relation to the subject of life-insurance: for the concealment of the practice of opium-eating by a person whose fe was insured, has already given rise to an action, in which medical ridence on this subject was rendered necessary. As a general principle, e must admit that habit cannot altogether counteract the insidious effects f poisons; and that the practice of taking them is liable to give rise to isease or to impair health. (See case by Parkes, *supra*).

Influence of Idiosyncrasy.—Idiosyncrasy differs from habit:—it does ot, like habit, diminish the effect of a poison: for it is not commonly und that any particular state of body is a safeguard against the effects f these powerful agents. Some constitutions are observed to be much

more affected than others by certain poisons: thus opium, arsenic, mercury, lead, and antimony are substances of this description, and this difference in their effect is ascribed to idiosyncrasy. Christison mentions an instance, in which a gentleman unaccustomed to the use of opium, took nearly an ounce of laudanum without any effect. ('On Poison.') This form of idiosyncrasy is very rare. Certain substances generally reputed harmless, and, indeed, used as articles of food, are observed to affect some persons like poisons. This is the case with pork, certain kinds of shell-fish, and edible mushrooms. There may be nothing poisonous in the food itself; but it acts as a poison in particular constitutions —whether from its being in these cases a poison *per se*, or rendered so by changes during the process of digestion, it is difficult to say. The subject of idiosyncrasy is of importance in a medico-legal view when symptoms resembling those of poisoning, follow a meal consisting of a particular kind of food. In such a case, without a knowledge of this peculiar condition, we might hastily attribute to poison, effects which were really due to another cause. It would appear that in some instances idiosyncrasy may be acquired—*i.e.* a person who, at one period of his life, had been in the habit of partaking of a particular kind of food without injury, may find at another period that it will disagree with him. When pork has been disused as an article of diet for many years, it cannot always be resumed with impunity. In cases in which the powers of life have become enfeebled by age, the susceptibility of the system to poisons is increased; thus aged persons may be killed by comparatively small doses of arsenic and opium. Cases of acquired idiosyncrasy are very rare; it appears to be, if we may so apply the term, a congenital condition. There are, however, certain diseases which appear to confer a power of supporting large and even poisonous doses of some substances. Very large doses of opium have been taken without producing dangerous symptoms by persons labouring under tetanus and hydrophobia. This condition is called *tolerance*. It has been also witnessed in diseases of the lungs in reference to the use of antimonial medicines.

Classification of Poisons.—Poisons may be divided into two classes, according to their mode of action on the system; namely, Irritants and Neurotics, as the special action of the latter is to affect directly one or more parts of the nervous system. No satisfactory classification has, however, hitherto been proposed.

Irritants.—The irritants are possessed of these common characters. When taken in ordinary doses, they occasion speedily violent vomiting and purging. The symptoms are either accompanied or followed by pain in the stomach and bowels. The peculiar effects of the poison are manifested chiefly on these organs, which, as their name implies, they irritate and inflame. Many substances belonging to this class of poisons possess corrosive properties; such as the strong mineral acids, caustic alkalies, bromine, corrosive sublimate, and others. These, in the act of swallowing, are commonly accompanied by an acrid or burning taste, extending from the mouth down the gullet to the stomach. Some irritants do not possess any corrosive action—of which we have examples in arsenic, the poisonous salts of barium, lead carbonate, and cantharides; these are often called pure irritants. They exert no destructive chemical action on the tissues with which they come in contact; they simply irritate and inflame them.

Difference between corrosive and irritant Poisons.—As a result of the action of *corrosive* poisons, symptoms are commonly manifested immediately, because mere contact produces the destruction of a part. In the action of

purely *irritant* poisons, the symptoms are generally more slowly ıifested, rarely showing themselves until at least half an hour has ıed from the time of swallowing the substance. Of course, there are ıptions to this remark; for sometimes irritants act speedily, though ıly with the rapidity of corrosive poisons. It is important in a ctical view, to ascertain whether, in an unknown case, the poison ch a person requiring immediate treatment may have swallowed, is tant or corrosive. This may be commonly determined by a knowledge he time at which the symptoms appeared after the suspected substance ı taken. We may thus often easily distinguish between a case of ıoning from arsenic and one from corrosive sublimate. There is also ther point which may be noticed. As the corrosive substance exerts a idedly chemical action, an examination of the mouth and throat may ble us in some cases to solve the question.

It has already been stated that there are many irritant poisons which e no corrosive properties, but every corrosive may act as an irritant. ıs the action of corrosive sublimate is that of an irritant poison, as, le it destroys some parts of the coats of the stomach and intestines, ritates and inflames others. So again most corrosive poisons may lose r corrosive properties by dilution with water, and then they act simply rritants. This is the case with the mineral acids, and bromine. In e instances, it is not easy to say whether an irritant poison possesses osive properties or not. Thus oxalic acid acts immediately, and ıches and softens the mucous membrane of the mouth and throat; but author has not met with any decided marks of chemical corrosion luced by it in the stomach or viscera. Irritant poisons, for the most , belong to the mineral kingdom; and they may be divided into the *-metallic* and *Metallic* irritants. There are a few derived from the nal and vegetable kingdom; but these, if we except cantharides, are often employed criminally. Some of the gases likewise belong to the s of irritant poisons.

Neurotics.—Neurotic poisons act upon the nervous system. Either ıediately or some time after the poison has been swallowed, the patient ers from headache, giddiness, numbness, paralysis, stupor, and in e instances convulsions. They have not, as a rule, an acrid burning e like the corrosive irritants; and they only occasionally give rise omiting or purging. When these symptoms follow the ingestion of poison into the stomach, the effect may sometimes be ascribed either he form or quantity in which it has been taken, and the mechanical ct on the stomach thereby produced, or to the poison being combined ı some irritating substance, such as alcohol. The pure *narcotics* are found to irritate or inflame the stomach and bowels.

Notwithstanding the well-defined boundary thus apparently existing ween these two classes of poisons, it must not be supposed that the stances arranged in each class always act in the manner indicated. ıe irritants have been observed to affect the brain or the spinal marrow, this may be either a primary or a secondary consequence of their on. Arsenic and oxalic acid, although classed as irritants, have in e instances given rise to symptoms closely resembling those of narcotic oning; namely, coma, paralysis, and tetanic convulsions. In a case poisoning with arsenic, which occurred to Morehead, the symptoms ıarcotism were so strongly marked, that it was believed at first the ı had taken a narcotic. ('Med. Gaz.' vol. 43, p. 1055.) Cases of oning by arsenic have been met with in which there was paralysis he limbs, with an entire absence of purging. On the other hand, in ıse of poisoning by a large dose of opium, there was an absence

of the usual symptoms of cerebral disturbance, and the presence of others resembling those of irritant poisoning—namely, pain and vomiting. Thus, then, we must not allow ourselves to be misled by the idea that the symptoms are always clearly indicative of the kind of poison taken. The narcotic chiefly belong to the vegetable kingdom. Some of the poisonous gases and vapours, nevertheless, possess a narcotic action.

Some poisons have a compound action. They are chiefly derived from the vegetable kingdom. At variable periods after they have been swallowed, they give rise to vomiting and purging, like irritants; and sooner or later produce stupor, coma, paralysis, and convulsions, owing to their effects on the nervous system. In the state of vegetables, as leaves, seeds, or roots, they possess the property, like irritants, of irritating and inflaming the stomach and bowels. As familiar examples we may point to nux vomica, monkshood, hemlock, and poisonous mushrooms. These poisons are very numerous, embracing a large variety of well-known vegetable substances. The fact of the symptoms occurring after a meal at which some suspicious vegetables may have been eaten, coupled with the nature of the symptoms themselves, will often indicate the class to which the poison belongs. Some of these poisons have a hot acrid taste; others, like aconite, produce a sense of numbness or tingling, while others again have an intensely bitter taste, as nux vomica, strychnine, veratrina, and picrotoxin. Strychnine may be regarded as a pure spinal poison.

In the description of poisons no systematic classification can be consistently followed.

CHAPTER 11.

EVIDENCE OF POISONING IN THE LIVING SUBJECT—ACTION OF POISONS INCREASED OR DIMINISHED BY DISEASE—SYMPTOMS CONNECTED WITH FOOD OR MEDICINE—SEVERAL PERSONS ATTACKED SIMULTANEOUSLY—EVIDENCE FROM THE DETECTION OF POISON IN THE FOOD.

We now proceed to consider the evidence of poisoning in the *living* subject. To the practitioner the diagnosis of a case of poisoning is of great importance, as by mistaking the symptoms produced by a poison for those arising from natural disease, he may omit to employ the remedial measures which have been found efficacious in counteracting its effects, and thus lead to the certain death of the patient. To a medical jurist a correct knowledge of the symptoms furnishes the chief evidence of poisoning, in those cases in which persons are charged with the malicious and unlawful administration of poison. The symptoms produced during life, constitute also an important part of the evidence in those instances in which a poison proves fatal. At present, however, we will suppose the case to be, that poison has been taken and the patient survives. Most writers on toxicology have laid down certain characters whereby it is said symptoms of poisoning may be distinguished from those of disease.

1. *In poisoning, the symptoms appear suddenly, while the person is in health.*—It is the common character of most poisons, when taken in the large doses in which they are usually administered with criminal intent, to produce serious symptoms, either immediately or within a very short period after they have been swallowed. Their operation, under such circumstances, cannot be suspended, and then manifest itself after an indefinite interval; although this was formerly a matter of universal belief, and gave rise to many absurd accounts of what was termed *slow* poisoning.

The symptoms of poisoning by nicotine, prussic acid, oxalic acid, or salts of strychnine, appear immediately, or generally within a few utes after the poison has been swallowed. In an exceptional case, which the dose of prussic acid was small, and insufficient to produce th, the poison was supposed by the patient not to have begun to act il after the lapse of fifteen minutes. ('Ed. Med. and Surg. Journ.' vol. p. 72.) The symptoms caused by arsenic and other irritants, and, ed, by all poisons generally, are commonly manifested in from half hour to an hour. It is rare that the appearance of symptoms is pro-ted for two hours, except under certain peculiar states of the system. s said that some neurotic poisons, such as the poisonous mushrooms, remain in the stomach twelve or twenty-four hours without giving to symptoms; and this is also affirmed to be the case with some nal irritants, such as decayed meat; but with regard to the first point, as been shown by Peddie that mushrooms have produced symptoms alf an hour; and a case has fallen under the author's own observation, hich the symptoms from noxious animal food came on within as short me after the meal, as is commonly observed in irritant poisoning by eral substances. In cases of poisoning by phosphorus, no obvious ptoms have occurred until after the lapse of some days.

Influence of disease.—A *diseased* state of the body may render a person paratively insusceptible of the action of certain poisons, while in other ances it may increase their action, and render them fatal in small s. In dysentery and tetanus a person may take, without being erially affected, a quantity of opium sufficient to kill an adult in rage health. In mania, cholera, hysteria, and delirium tremens, large s of opium may be borne with comparative impunity. In a case emiplegia, a woman, æt. 29, took for six days, three grains of strychnine y without injurious consequences—the dose having been gradually ed ('Gaz. Méd.' Mai 1845); while one grain of strychnine is commonly rded as a fatal dose to a healthy adult. In a case of tetanus, Dupuy-n gave more than two ounces of opium at a dose (60 grammes), out serious consequences. Persons affected with tetanus are not ly salivated by mercury. This morbid state appears to create the er of resisting the ordinary effects of poisons. The effect of certain ases of the nervous system, as well as of habit, either in retarding appearance of symptoms or in blunting the operation of a poison, it ot difficult to appreciate; they are cases which can present no practical culty to a medical jurist. On the other hand, in certain diseased es of the system, there may be an increased susceptibility of the action oison. Thus, in those persons who have a disposition to apoplexy, mall dose of opium may act more quickly and prove fatal. In a on labouring under inflammation of the stomach or bowels, there ld be an increased susceptibility to the action of arsenic, antimony, ther irritants. In debility from any cause these mineral substances ld also act injuriously even in ordinary doses. Antimony is a most erful depressant, and might, by its effect on the heart, cause death syncope. The influence of disease in increasing the operation of on, has been noticed in cases of diseased kidney (granular degenera-), in which small doses of mercury have produced severe salivation, ling to exhaustion and death. In diseases of the lungs affecting l persons, opium in full medicinal doses has been observed to exert oisonous action. The effect of the drug appears to be intensified the disease. This observation applies equally to morphia. Chloro-n vapour in ordinary quantity has been found to produce fatal ts in cases in which there was latent disease of the heart or of the

coronary arteries. A fatty condition of the muscular tissue leading to great feebleness of the heart's action, is thought to be favourable to death by syncope, under the use of chloroform. A knowledge of these facts is of importance in reference to charges of malapraxis when death has arisen from ordinary or extraordinary doses of medicines, administered to persons labouring under disease. In such cases another mode of treatment should be substituted, or a smaller dose than usual given, and its effects carefully watched. In some instances, however, full and large doses of powerful drugs have been recklessly given, and when a fatal result has followed, there has been a strong disposition to refer death to the supposed disease, of which, however, sometimes no trace could be found in the body.

Symptoms appear during a state of health.—Symptoms of poisoning manifest themselves in a person while in a state of *perfect health*, without any apparent cause. This rule is of course open to numerous exceptions, because the person on whose life an attempt has been made, may be actually labouring under disease; and under these circumstances, the symptoms may be so obscure as often to disarm all suspicion. When poison is secretly given in medicine, a practitioner is very liable to be deceived, especially when the disease under which the person is labouring is of an acute nature, and has been attended by symptoms of disorder in the alimentary canal. Several cases of poisoning have occurred in which arsenic was criminally substituted for or mixed with medicine, and given to persons while labouring under a disorder of the bowels. We are, however, justified in saying, with respect to this character of poisoning, that when in a previously healthy person, violent vomiting and purging occur suddenly and without any assignable cause, such as pregnancy, disease, or indiscretion in diet, to account for them, there is strong reason to suspect that irritant poison has been taken. When the person is already labouring under disease, we must be especially watchful on the occurrence of any sudden change in the character or violence of the symptoms, unless such change can be easily accounted for on common or well-known medical principles. In most cases of criminal poisoning we meet with alarming symptoms without any obvious or sufficient natural causes to explain them. The practitioner will of course be aware that there are certain diseases which are liable to occur suddenly in healthy people, the exact cause of which may not at first sight be apparent; therefore this criterion is only one out of many on which a medical opinion should be founded.

2. *In poisoning the symptoms appear soon after a meal or soon after some kind of food or medicine has been taken.*—This is by far the most important character of poisoning in the living body. It has been already stated that most poisons begin to operate within about an hour after they have been swallowed; and although there are a few exceptions to this remark, yet they occur under circumstances easily to be appreciated by a practitioner. Thus, then, it follows that, supposing the symptoms under which a person is labouring, to depend on poison, the substance has most probably been swallowed, either in food or medicine, from half an hour to an hour previously. It must be observed, however, that cases may occur in which the poison has not been introduced by the mouth. Oil of vitriol and other corrosive liquids have been thrown up the rectum in injections, and have thus caused death; the external application of arsenic, corrosive sublimate, and cantharides to ulcerated surfaces has destroyed life. In one case, arsenic was introduced into the vagina of a female, and she died in five days under all the symptoms of arsenical poisoning. (Schneider, 'Ann. der ges. Staatsarzneik.' i. 229.) Such cases are rare, but, nevertheless, the certainty that they have occurred, where their appearance could hardly

› been anticipated, shows that in a suspicious case a practitioner should deny the fact of poisoning, merely because it may be proved that the on could not have taken poison in the usual way, by the mouth. in, persons may be destroyed by the vapours of ether, chloroform, sic acid, or other powerful volatile poisons, introduced into the body ugh the lungs. Such a mode of suicide, or murder, might disarm icion, from the fact of no noxious material being found in the stomach. et us suppose, however, the circumstances to have been such that e secret means of destruction could not have been resorted to, and that ubstance is one of those most commonly selected by a murderer, such rsenic, tartar emetic, oxalic acid, or corrosive sublimate, then we may ct that this character of poisoning will be made evident to us, and that ething must have been *swallowed* by the patient shortly before the ning symptoms appeared. By observations attentively made, it may ı our power to connect the appearance of the symptoms with the use of rticular article of food, and thus indirectly lead to the detection of a inal. Supposing that many hours have passed since food or medicine taken by the patient, without any effect ensuing—it is probable that ymptoms are due to natural causes and not to poison. When symptoms mbling those of poisoning speedily follow the ingestion of food or icine, there is, however, reasonable ground for suspicion; but caution ıld be observed in drawing inferences, since the most extraordinary cidences sometimes present themselves. In the case of *Sir Theodosius ghton*, who was poisoned by his brother-in-law, *Donellan*, in 1781, the of alarming symptoms coming on in *two minutes* after the deceased had llowed what was supposed to be a simple medicinal draught, was most ortant as evidence against the prisoner. There is no doubt that laurel- er had been substituted for the medicine by the prisoner, and that this caused the symptoms which preceded death. The practice of substi- ng poisonous mixtures for medicinal draughts or powders is by no means sual, although it might be supposed to indicate a degree of refinement knowledge not commonly to be found among criminals. Medical ctitioners are thus apt to be imposed upon, and the following case, ted by a deceased judge, will serve as a caution:—An apothecary pared a draught, into which another person put poison, intending reby to destroy the life of the patient for whom the medicine was scribed. The patient, not liking the taste of the draught, and thinking re was something suspicious about it, sent it back to the apothecary, , knowing the ingredients of which he had composed it, and wishing to ve to his patient that he had done nothing wrong, drank it himself, and l from the effects. He was thus the unconscious agent of his own th; and though the draught was intended for another, the party who soned it was held guilty of murder.

On the other hand, the occurrence of symptoms resembling those duced by poisoning, soon after food or medicine has been taken, may a pure coincidence. In such a case, poison is always suspected by the gar; and it will be the duty of a medical jurist to guard against the ouragement of such a suspicion, until he has strong grounds to believe to be well founded. No public retractation or apology can ever make ends for the injury which may in this way be inflicted on the reputa- n of another; for those who hear the accusation may never hear the ence. In all such cases, a practitioner may entertain a suspicion, but, til confirmed by facts, he should avoid *expressing* it or giving it publicity. nen death is not a consequence, it is difficult to clear up such cases, ept by the aid of a chemical analysis; but this, as we know, is not rays applicable. If death ensue, the real cause is usually apparent,

and a suspicion of poisoning is thus often removed by an examination of the body.

3. *In poisoning, when several partake at the same time of the same food or medicine (mixed with poison), all suffer from similar symptoms.*—This character of poisoning cannot always be procured; but it furnishes good evidence of the fact when it exists. Thus, supposing that after a meal made by several persons from the same dish, only one suffers, the suspicion of poisoning is considerably weakened. The poisoned article of food may be detected by observing whether they who suffer under any symptoms of poisoning, have partaken of one particular solid or liquid in common. In a case of accidental poisoning at a dinner-party, a medical man who was present observed that those who suffered had taken port-wine only: the contents of the bottle were examined, and found to be a saturated solution of arsenic in wine. In general, considerable reliance may be placed upon this character, because it is improbable that any common cause of disease should suddenly attack with violent symptoms of a similar kind many healthy persons at the same time, and within a short period after having partaken of food together. We must beware of supposing that, when poison is really present, all will be attacked with precisely similar symptoms; because there are many circumstances which may modify their nature and progress. In general that person who has partaken most freely of the poisoned dish will suffer most severely; but even this does not always follow. There is a well-known case, recorded by Bonnet, where, among several persons who partook of a dish poisoned with arsenic, they who had eaten little and *did not vomit*, speedily died; while others who had partaken largely of the dish, and had in consequence vomited freely, recovered.

It was just now remarked, that there is no disease resembling poisoning which is likely to attack several healthy persons at the same time, and in the same manner. This is undoubtedly true as a general principle, but the following case will show that mistakes may occasionally arise even under these circumstances. It occurred in London, during the prevalence of the malignant cholera in the year 1832. Four of the members of a family, living in a state of great domestic unhappiness, sat down to dinner, apparently in good health: some time after the meal, the father, mother, and daughter, were suddenly seized with violent vomiting and purging. The evacuations were tinged with blood, while the blueness of the skin, observed in cases of malignant cholera, was absent. Two of these persons died. The son, who was known to have borne ill-will against his father and mother, and who suffered no symptoms on this occasion, was accused of having poisoned them. At the inquest, however, it was clearly shown by the medical attendant, that the deceased persons had really died of malignant cholera, and there was no reason to suspect that any poison had been administered to them. In this instance it will be perceived that symptoms resembling those of irritant poisoning appeared suddenly in several individuals in perfect health, and shortly after a meal. We hereby learn that the utility of any rules for investigating cases of poisoning, depends entirely on the judgment and discretion with which they are applied to particular cases.

It is well to bear in mind, in conducting these inquiries, that symptoms resembling those produced by irritant poison, may be sometimes traced to *food*. Meat rendered unwholesome by disease or decay, pork, bacon, sausages, cheese and bread, as well as certain kinds of shell-fish, may give rise to symptoms of poisoning, and even cause death. Such cases may be regarded as poisoning by animal or vegetable irritants. All the characters above described, as indicative of poisoning, may be observed, and the

culty of forming an opinion is often increased by the fact that some of persons attacked may have previously partaken of the same kind of l without inconvenience.

4. *The discovery of poison in the food taken or in the matters vomited.*— of the strongest proofs of poisoning in the living subject, is the ction of poison by chemical analysis, or, if of a vegetable nature, by a roscopical examination, either in the food taken by the person labouring er its effects, or in the matters vomited, or, after the lapse of a few rs, in the urine. The evidence is of course more satisfactory when poison is detected in the matters vomited, and more especially in the e, than in the food; because this will show that it has really been n, and it will readily account for the symptoms. If the vomited ters have been thrown away, we must examine the food of which the ent may have partaken. Should the results in both cases be negative, no trace of poison be found in the urine, it is probable that the ptoms were due to disease.

n investigating a case of poisoning in a living subject, a medical jurist t remember, that poisoning is sometimes *feigned*, and at others *imputed*. easy for an artful person to put poison into food, as well as to intro- it into the matters vomited or discharged from the bowels, and to se another of having administered it. There are few of these accusers go so far as to swallow poison under such circumstances, as there great dread of poisonous substances among criminals; and it will be nce apparent, that it would require a person well versed in toxicology sign a series of symptoms which would impose upon a practitioner at cquainted with the subject. In short, the difficulty reduces itself to :—What inference can be drawn from a chemical detection of poison ood? All that a medical man can say is, whether poison is or is not ent in a particular article of food: he must leave it to the authorities he law to develope the alleged attempt at administration. If the on has been actually administered or taken, then we should expect ind that the person had suffered from the usual symptoms. The nce of these symptoms would be a strong fact against the alleged inistration. The detection of poison in the matters vomited, affords lecisive proof that it has been swallowed, except under two circum- ces:—1. When the accuser has previously laboured under the usual ptoms of poisoning, in which case there can be no feigning, and the stion of imputation is a matter to be established by general evidence. When the matters are actually vomited into a *clean vessel* in the ence of the medical attendant himself, or of some person on whose imony perfect reliance can be placed. The detection of absorbed on in the *urine* or *saliva*, furnishes a clear proof that poison has been n, that it has passed into the blood, and has been subsequently inated by the kidneys or the salivary glands.

CHAPTER 12.

ON THE EVIDENCE OF POISONING IN THE DEAD BODY—PERIOD AT WHICH POISONS PROVE FATAL—CHRONIC POISONING—APPEARANCES PRODUCED BY THE DIFFERENT CLASSES OF POISONS—REDNESS OF THE MUCOUS MEMBRANE MISTAKEN FOR INFLAMMATION—ULCERATION AND CORROSION—SOFTENING—PERFORATION OF THE STOMACH FROM POISON AND DISEASE.

SUPPOSING that the person is dead, and we are required to determine whether the case is one of poisoning or not, we must, in the first instance, endeavour to ascertain all the particulars which have been considered in the last chapter, as indicative of poisoning in the living subject. Should the deceased have died from poison, the circumstances of the attack, and the symptoms preceding death, ought to correspond with the characters already described; and in these investigations, it is well to bear in mind the following rule:—There is no one symptom or pathological condition which is peculiar to poisoning; but at the same time there is probably no disease which presents *all* those characters which are met with in a special case of poisoning. The additional evidence to be derived from the *death* of a person, may be considered under the following heads:—

1. *The time at which death takes place after the first occurrence of symptoms.*—This question requires examination, because the more common poisons, when taken in fatal doses, generally cause death within definite periods of time. By an attention to this point, we may, in some instances, be enabled to negative a charge of poisoning, and in others to form an opinion of the kind of poison which has been taken. In a Court of Law a medical practitioner is often required to state the usual *period of time* within which poisons prove fatal. It is to be observed that, not only do poisons differ from each other in this respect, but that the same substance, according to the form or quantity in which it has been taken, may differ in the rapidity of its action. A large dose of prussic acid, *i.e.* from half a fluid ounce to an ounce of two per cent. acid, may destroy life in less than two minutes. In ordinary cases of poisoning by this substance a person dies, *i.e.* all signs of life have commonly ceased, in from ten to twenty minutes: if he survives half an hour, there is some hope of recovery. In the case of seven epileptics, accidentally poisoned by a similar dose of this acid in one of the Parisian hospitals, the first died in about twenty minutes, the seventh survived three-quarters of an hour. Oxalic acid, one of the most energetic of the common poisons, when taken in a dose of from half an ounce to an ounce, may destroy life in from ten minutes to an hour: if the poison is not perfectly dissolved when swallowed, it is a longer time in proving fatal. The strong mineral acids in poisonous doses, destroy life in about eighteen or twenty-four hours. Arsenic under the form of arsenious oxide or acid (white arsenic), operates fatally in from eighteen hours to three or four days. It has, however, in more than one instance, killed a person in two hours. Opium, either as a solid or in the form of laudanum, commonly proves fatal in from six to twelve hours; but it has been known, in several instances, to destroy life in less than three hours: those who survive the effects of this poison for twelve hours, are considered to have a fair chance of recovery. This must be understood to be merely a statement of the average results, as nearly as we are warranted in giving an opinion; but the medical jurist will of course be aware that the fatal period may be protracted or shortened, according to all those circumstances which have been elsewhere stated to affect the action of poisons.

There are various forms which this question may assume. It may be

hat the death of a person, alleged to have taken poison, has occurred pidly or too slowly to justify a suspicion of poisoning. The following will serve as an illustration: A woman of the name of *Russell* was and convicted (Lewes Sum. Ass. 1826), for the murder of her nd, by poisoning him with arsenic. The poison was detected in tomach; but the fact of poisoning was disputed by some medical sses for this among other reasons, that the deceased had died *three* after the only meal at which the poison could have been administered n. The authority of Sir A. Cooper and others was cited to show that, ding to their experience, they had never known a case of poisoning by ic to have proved fatal in less than seven hours. This may be ted, but, at the same time, there was sufficient authority on the other o establish that some cases had actually proved fatal in three or four . So far as this objection was concerned, the prisoner was properly cted. In reference to the medical question raised at this trial, I may ve that two cases have occurred in which the individuals died nly within *two hours* after taking arsenic; and several instances been reported, in which death has taken place in from three to four after the administration of this poison. It seems extraordinary in resent day, that any attempt should have been made by a professional o negative a charge of criminal poisoning upon so weak a ground as but this opinion was expressed many years ago, when the facts cted with poisoning were but little known. It is quite obvious that is nothing, so far as we know, to prevent arsenic from destroying life hour, or even within a shorter period. A case will be related, in death took place from arsenic probably within twenty minutes. matters can be settled only by a careful observation of numerous and not by any *à priori* reasoning, or by a limited individual ience.

all instances of sudden death there is generally a strong tendency on art of the public to suspect poisoning. They do not consider that ns may die a natural death *suddenly*, as well as slowly; or, as we shall ntly see, that death may really take place slowly, and yet be due to n. This prejudice often gives rise to the most unfounded sus- ns of poisoning, and, at the same time, leads to cases of chronic or slow ning being frequently mistaken for natural disease. One of the means mended for distinguishing narcotic poisoning from apoplexy or se of the heart, is the difference in the rapidity with which death takes

Thus, apoplexy or disease of the heart may prove fatal either ntly or within an hour. The only poisons likely to operate with such rapidity, are prussic acid and nicotine. Poisoning by opium is only protracted for five or six hours. This poison has never been n to destroy life instantaneously, or within a few minutes. Thus, then, y happen that death will occur with such rapidity as to render it sible, under the circumstances, to attribute it to narcotic poison.

Chronic poisoning.—When a poison destroys life rapidly, it is called a of *acute* poisoning, to distinguish it from the *chronic* form, *i.e.* in death takes place slowly. Chronic poisoning is a subject which ently requires medico-legal investigation. Most poisons, when their s are not rapidly manifested, owing either to the smallness of the or to timely treatment, are capable of slowly undermining the powers s, and killing the patient by producing emaciation and exhaustion. is sometimes observed in the action of arsenic, corrosive sublimate, tartarated antimony, but it has been remarked also in cases of ning by the mineral acids and caustic alkalies. Death is here an ect consequence;—in poisoning by the acids or alkalies, either

stricture of the gullet is induced, or the lining membrane of the stomach is destroyed, and the process of digestion impaired, a condition which leads to exhaustion and death. The time at which these indirect effects may prove fatal, is of course liable to vary. A person has been known to die from a stricture of the gullet, brought on by sulphuric acid, *eleven months* after the poison was swallowed; and there is no reason to doubt that instances may occur of a still more protracted nature. In cases of *chronic poisoning* there is sometimes great difficulty in assigning death exclusively to the original action of the poison, since the habits of life of the person, a tendency to disease, and other circumstances, may have concurred either to accelerate or produce a fatal result. To connect a stricture of the gullet proving fatal, with the effects of poisoning by a mineral acid, it would be necessary to show that there was no tendency to this disease before the acid was administered; that the symptoms appeared soon after the first effects of the poison went off; that these symptoms continued to become aggravated until the time of death; and lastly, that there was no other cause to which death could with any probability be referred. These remarks apply equally to the secondary fatal effects of any poison, such, for instance, as the salivation occasionally induced by corrosive sublimate, and the exhaustion and depression which are caused by tartarated antimony, when the acute symptoms of poisoning by these substances have passed away.

Several cases have come before our tribunals, in which the facts connected with this form of poisoning were of some importance, *e.g.* that of Miss *Blandy*, tried at Oxford, in 1752, for the murder of her father by arsenic; and of a woman named *Butterfield*, tried at Croydon in 1775, for the murder of a Mr. Scawen, by administering corrosive sublimate. Among more recent cases, may be mentioned that of Mrs. *Wooler* (*Reg.* v. *Wooler*, Durham Wint. Ass. 1855), in which it was proved that the deceased had been under the influence of arsenic, administered at intervals in repeated doses, for a period of about seven weeks before her death. She died from exhaustion and the secondary effects of the poison. In three other cases tartarated antimony was the poison selected. It was given in repeated doses, over different periods, and caused death, by the specific effects of poisoning in a chronic form. 1. The case of *Ann Palmer*. ('Guy's Hosp. Rep.' 1857.) 2. The case of *M'Mullen* (Liverpool Sum. Ass. 1856), in which a woman was tried and convicted for causing the death of her husband; and 3rd, the case of *Reg.* v. *Hardman* (Lancaster Sum. Ass. 1857), in which a man was convicted of the murder of his wife. In most cases, murderers destroy life by administering poison in large doses; but in the instances referred to, small doses were given at intervals, a fact which, in some of them, led to a medical doubt of the real cause of the symptoms. The case of *Isabella Banks* (*Reg.* v. *Smethurst*, C. C. C. Aug. 1659) gave rise to a conflict of medical opinion respecting the cause of death. Julius and Bird, who attended the diseased throughout her illness of about a month's duration, Todd, and the author, referred the symptoms and cause of death to chronic poisoning by antimony and arsenic, and in confirmation of this opinion traces of antimony were found by Odling and the author in the intestines after death. A small quantity of arsenic was also found in an evacuation passed by the deceased three days before her death. Tyler Smith, Richardson, and others, referred the symptoms and appearances partly to pregnancy, and partly to a sudden attack of severe dysentery. The jury found the accused guilty, but upon the doubt raised respecting the cause of death, the accused was subsequently pardoned.

A similar question arose in *Reg.* v. *Winslow* (Liverpool Aut. Ass.

860). The prisoner was charged with the murder of a Mrs. James
y administering to her small doses of antimony. The suspicions of
ameron, who attended deceased, were excited by the intermittent and
olent nature of the vomiting, as well as by the extreme depression.
ntimony was found in the urine and fæces by Edwards; and, after death,
is substance was discovered, in small quantity, in the viscera, by Edwards,
iller, and the author. The deceased was at the time labouring under
alignant disease of the cæcum, but it was alleged that the antimony had
celerated her death. The jury acquitted the accused. The examination
the bodies of the sister of deceased, as well as of two other members of
e family, led to the discovery of antimony also in small quantity, in the
scera of each; and from the nature of the symptoms preceding death,
well as the general healthiness of the organs, no doubt was entertained
the medical witnesses that all these persons, members of the same
usehold, had died from the effects of antimony administered at intervals
small doses. A set of cases somewhat similar was brought to light by
rtain inquests on exhumed bodies at Bilston (Dec. 1871). Three children
a family died at different times, under similar symptoms. Hill found
timony in two of the bodies, and the body of a third child was exhumed
er two months' burial, and antimony was also found in it. It appears
at this child died on Oct. 10th, and its death was registered on the 13th
that month as death from 'asthenia,' and 'gastric fever' 'six days.'
ey all received medical attendance, and their names it is stated were
tered in some burial club.

The occurrence of such cases as these, suggests grave reflections on the
ecurity of life, when poison is used with skill and cunning, and they
monstrate the inefficiency of the present system of registering causes of
ath.

These cases show that medical men in signing certificates, do not
ficiently inquire into the nature of the fatal illness, or the cause of death
e 'Lancet,' 1870, i. p. 341): but this is an evil which admits of an easy
nedy. The public have much more to dread in the fact that, even in
in cases of poisoning, some physicians of experience and repute have
en unable to discriminate the symptoms from those of natural disease.
us, in the notorious case of *William Palmer*, one physician who appeared
the defence, affirmed that the symptoms under which Cook died were
se of angina pectoris; while another physician, also employed for the
fence, assigned death to epilepsy with tetanic complications. The
nesses came forward as experts to maintain these views. In reference
the death of *Ann Palmer*, which was caused by doses of antimony,
e solid sulphide of this metal was found in the stomach after death,
ile the metal itself pervaded the whole of the tissues. A respectable
ysician, with only a superficial knowledge of the real facts of the case,
ote a pamphlet to prove that this woman had died from an attack of
olera. If these persons had been called in to attend these two victims of
ret poisoning while living, it is quite obvious that they would have had
suspicion of poisoning, and that they would have respectively certified that
ath was caused in the one case by angina pectoris or epilepsy, and in
e other by cholera. They would thus have effectually screened, under
roneous medical certificates, the acts of a man who is admitted to have
en the greatest criminal of the age. If physicians of some standing
d professed experts, can thus overlook ordinary cases of poisoning, it
not surprising that general practitioners, who have not given special
tention to the subject of toxicology, should fall into the error of granting
roneous medical certificates, and of certifying that death from arsenic
opium was due to cholera, convulsions, or apoplexy.

The characters of chronic poisoning have of late years acquired a special interest for the medical jurist. There is a difficulty about them which no accuracy of observation or judgment can surmount. The poison or poisons, if found in the dead body at all, must necessarily exist in fractional parts of a grain. This alone will be sufficient to create a doubt whether death has been caused by the poison, although it is quite consistent with medical experience that a person may die from chronic poisoning, and little or none of the poison be found in the body after death. In the case of Mrs. James (*Reg.* v. *Winslow*), not more than the tenth part of a grain was found in the whole of the tissues of the body: in the case of Isabella Banks (*Reg.* v. *Smethurst*), the quantity was small; while in the case of Mrs. *Peters*, of Yeovil, examined by Herapath, none was found in the body, although this chemist had extracted a quantity of antimony as sulphide from the urine of deceased, in less than nine days before her death. In this case Garland had also found antimony in the evacuations during life, and had referred the intermittent irritation of the stomach and bowels, from which deceased had suffered, to the secret use of this mineral. The jury returned a verdict that deceased had died from disease and that death was accelerated by some irritant. ('Lancet,' 1860, II. p. 119.) On some trials for poisoning it has been a contested scientific question, whether a person can die from poison and no trace of the poison remain in the body. Herapath's evidence in Peters' case not only now proves the affirmative, but goes to show that antimony may act fatally and be entirely eliminated from the system in about a week. ('Med. Times and Gaz.' 1860, II. pp. 190, 271, 317.)

2. *Evidence from appearances in the body.*—One of the chief means of determining whether a person has died from poison, is an examination of the body after death. In relation to *external* appearances, there are none which are specially indicative of poisoning upon which we can safely rely. It was formerly supposed that the bodies of persons who were poisoned, putrefied more rapidly than those of others who had died from natural disease; and evidence for or against poisoning was at one time derived from the external appearance of the body. This is now known to be an error: the bodies of persons poisoned are not more rapidly decomposed, *cæteris paribus*, than those of others who have died a sudden and violent death from any cause whatever.

Irritant poisons act chiefly upon the stomach and intestines, which they irritate, and inflame, and corrode. We may likewise meet with all the consequences of inflammation, such as softening, thickening, ulceration, perforation, or gangrene. Sometimes the coats of the viscera are thickened, at other times thinned and softened, by the action of an irritant.

Neurotic poisons do not commonly leave any well-marked appearances in the body. The stomach and intestines may present no unnatural changes. There may be greater or less fulness of the vessels of the brain and spinal marrow, as well as of their membranes; but even this is often so slight as to escape notice, unless attention be particularly directed to these organs. Effusion of blood is rarely found.

The so-called *Narcotico-irritant* or *Cerebro-spinal* poisons may affect either the brain or the stomach and bowels, and commonly all these parts according to their peculiar mode of action.

It is important to bear in mind, that both Irritants and Neurotics may destroy life without leaving any appreciable changes in the body. To such cases as these, the remarks about to be made do not apply. The proofs of poisoning must, in such exceptional cases, be procured entirely from other sources. Any evidence derivable from the appearances in the body of a person poisoned, will be imperfect unless we are able to dis-

nguish them from those analogous changes often met with as the results ordinary disease. These are confined to the mucous membrane of the mach and bowels. They are redness, ulceration, softening, and perfora-n. Each of these conditions may depend upon disease, as well as upon e action of irritant poisons.

Redness.—It is a main character of the irritants to produce, as a result inflammation, redness of the mucous or lining membrane of the stomach d small intestines. This redness, when first seen, is usually of a deep mson colour, becoming brighter by exposure to air. It may be diffused er the whole mucous membrane: at other times it is seen in patches, s, or lines (striæ), spread irregularly over the surface of the stomach. It sometimes met with at the smaller (pyloric), but more commonly at the ger (cardiac) end of this organ, and again we occasionally find the ds or prominences only of the mucous membrane presenting this red inflamed appearance. Redness of the mucous membrane may, how-er, be due to gastritis or gastro-enteritis as a result of disease; and in ler to assign the true cause of the inflammation, it will be necessary to ve an account of the symptoms preceding death, or some chemical proof the existence of irritant poison in the contents of the stomach or the sues of the body.

In the healthy state, the mucous membrane of the stomach is pale d grey, except during digestion, when it is slightly reddened; and ne observers have remarked that a slight redness has often remained the stomachs of those who have died during the performance of the estive process. When in contact with the spleen or liver, after death, stomach is apt to acquire a deep livid colour from the transudation of od; and it is well known that the bowels acquire a somewhat similar our from the gravitation of blood which always takes place after death. ne of these appearances ought to be mistaken for the action of an itant poison.

There is an important class of cases in which redness of the mucous mbrane of the stomach is found after death, not dependent on the action poison or on any easily assignable cause. These cases, owing to their ng so little known, and involved in much obscurity, deserve the ention of medical jurists, since the appearances closely resemble those duced by irritant poison. A person may die without suffering from y symptoms of disordered stomach; but on an inspection of the body, a neral redness of the mucous membrane of this organ will be found, not tinguishable from the redness which is so commonly seen in arsenical soning. Several cases of this kind have occurred: and drawings ich have been made of the appearances presented by the stomach, are served in the Museum collection at Guy's Hospital. This condition is t infrequent after death from heart disease.

The redness of the lining membrane of the stomach, in cases of poison-g, is so speedily altered by putrefaction, when circumstances are favour-le to this process, as frequently to render it impossible for a witness to eak with any certainty upon its cause. Putrefactive infiltration from e blood contained in the adjacent viscera and muscles, will give a reddish-loured appearance to a stomach otherwise in a healthy condition. Great spute has arisen respecting the length of time during which redness of e stomach produced by an irritant, will be recognizable and easily distin-ishable from putrefactive changes. It is sufficient to say, that no certain le can be laid down on the subject: it must be left to the knowledge d discretion of the witness. The author has seen the well-marked pearances of inflammation produced by arsenic in the stomach and odenum in an exhumed body twenty-eight days after interment (*Reg.* v.

Jennings, Berks Lent Ass. 1845); and in other instances, the reddened state of the mucous membrane, in a case of arsenical poisoning, was plainly perceptible on removing a layer of arsenic, *nineteen months* and twelve months respectively after interment. (See on this question, a case of suspected poisoning by Orfila, 'Ann. d' Hyg.' 1839, 1, 127.) If, however, there should be a reasonable doubt respecting the cause of redness, and no poison is detected, it would be unsafe to rely upon this appearance as evidence of poisoning.

Ulceration.—In irritant poisoning, the stomach is occasionally found ulcerated: but this is, comparatively speaking, a rare occurrence. In such cases the mucous membrane is removed in small distinct circular patches, under the edges of which the poison (arsenic) may be found. Ulceration of the stomach is a more common result of disease, than of the action of poison. As a consequence of disease, it is very insidious, going on often for weeks together, without giving any indications of its existence, except perhaps slight gastric disturbance with occasional nausea, vomiting, and loss of appetite. In this case, the ulceration is commonly seen in small circumscribed patches. It is worthy of remark, as a means of distinction, that ulceration has never been known to take place from arsenic or any irritant poison, until symptoms indicative of irritant poisoning have occurred. In ulceration from disease, the mucous membrane is commonly only reddened in the neighbourhood of the ulcer. In ulceration from poison, the redness is generally diffused over other parts of the stomach, as well as over the duodenum and small intestines. A case, however, occurred in Guy's Hospital, some years ago, in which, with a small circular patch of ulceration near the cardiac opening, the whole mucous membrane was red and injected; but this singular condition of the stomach, so closely resembling the effects of an irritant poison, was unaccompanied by any marked symptoms of irritation during life. The history of a case previous to death will thus commonly enable us to determine to what cause the ulceration found, may be due. Care must be taken to distinguish ulceration from *corrosion*. Ulceration is a vital process: the substance of a part is removed by the absorbents as a simple result of inflammation. Corrosion, on the other hand, is a chemical action;—the parts are removed by the immediate contact of the poison: they are decomposed: their vitality is destroyed, and they combine with the corrosive matter itself. Ulceration requires time for its establishment, while corrosion is either an instantaneous or a very rapid effect.

Softening.—The coats of the stomach are not unfrequently found so soft as to yield and break down under very slight pressure; and this may be the result either of poisoning, of some spontaneous morbid change in its structure during life, or of the solvent action of the gastric juice after death. As this condition of the stomach, when caused by poison, is produced by those substances only which possess corrosive properties, it follows that in such cases, traces of their action will be perceived in the mouth, throat, and gullet. In softening from disease, the change will be confined to the stomach alone, and it is commonly found only at the cardiac or greater end of the organ. When softening is really caused by an irritant poison, it is generally attended by other striking and unambiguous marks of its operation. Softening is not to be regarded as a common character of poisoning: it is only an occasional appearance. The author has met with an instance in which the coats of the stomach were considerably hardened by sulphuric acid; and the editor has found that carbolic acid usually hardens the tissues with which it comes in contact. Softening can never be inferred to have proceeded from poison, unless other well-marked changes are present, or unless the poison is

discovered in the softened parts. The stomachs of infants have been frequently found softened from natural causes: such cases could not be mistaken for poisoning, since the history of them during life, the want of other appearances indicative of poisoning, and the total absence of poison from the viscera, would prevent such a suspicion from being entertained.

Perforation.—The stomach may become perforated, either as a result of poisoning or disease.

Perforation from poisoning.—This may arise:—1, from corrosion; 2, from ulceration. The perforation by *corrosion* is by far the most common variety of perforation from poisoning. It is occasionally witnessed when the strong mineral acids have been taken, especially sulphuric acid. The stomach, in such cases, is blackened and extensively destroyed, the aperture is large, the edges are rough and irregular, and the coats are easily lacerated. The acid escapes into the abdomen, and may be readily detected there by chemical analysis. The perforation from *ulceration*, caused by irritant poison (arsenic), is but little known. There are but few instances on record. In a great number of poisoned subjects examined during many years at Guy's Hospital, not a single case occurred. It must, then, be looked upon as a rare appearance in cases of irritant poisoning.

Perforation from disease.—This is by no means an unusual condition. Many cases of this disease will be found reported elsewhere. ('Guy's Hosp. Rep.' No. 8.) It is invariably fatal when it proceeds so far that the contents of the stomach escape into the abdomen; but sometimes the stomach becomes glued to the pancreas or other organs during the ulcerative process, and then the person may recover. Several instances of this kind of adhesion have been met with in inspections. The symptoms from perforation commonly attack a person suddenly, while apparently enjoying perfect health. Hence these cases may be easily mistaken for those of irritant poisoning. The principal facts observed with regard to this formidable disease are the following:—1. It often attacks young women from eighteen to twenty-three years of age. 2. The preceding illness is extremely slight; sometimes there is merely loss of appetite, or a capricious appetite with uneasiness after eating. 3. The attack commences with a sudden and most severe pain in the abdomen, generally soon after a meal. In irritant poisoning the pain usually comes on gradually, and slowly increases in severity. 4. Vomiting, if it exists at all, is commonly slight, and is chiefly confined to what is swallowed. There is no purging: the bowels are generally constipated. In irritant poisoning the vomiting is usually severe, and purging is seldom absent. 5. The person dies commonly in from eighteen to thirty-six hours: this is also the average period of death in the most common form of irritant poisoning, *i.e.* by arsenic; but in no case yet recorded has arsenic caused perforation of the stomach within twenty-fours hours; and it appears probable that a considerable time must elapse before such an effect could be produced by this or any irritant. 6. In perforation from disease, the symptoms and death are clearly referable to peritonitis. 7. As a result of disease, the aperture is commonly of an oval or rounded form, about half an inch in diameter, situated in or near the lesser curvature of the stomach, and the edges are smooth. The outer margin of the aperture is often blackened, and the aperture itself is funnel-shaped from within outwards, *i.e.* the mucous coat is the most removed, and the outer or peritoneal coat, the least. The coats of the stomach, round the edge of the aperture, are usually thickened for some distance; and when cut they have an almost cartilaginous hardness. These characters of the aperture will not alone indicate whether it is the result of poisoning or disease; but the absence of poison from the stomach, with the want of other characteristic marks

of irritant poisoning, would enable us to say that disease was the cause. Besides, the history of the case during life would materially assist us in our judgment. The great risk in all these cases is, that the effects of disease may be mistaken for those of poisoning; for we are not likely to mistake a perforation caused by irritant poison for the result of disease. Notwithstanding the well-marked differences above described, it is common to meet with cases of imputed poisoning where death has really occurred from peritonitis following perforation from disease: one of them will be found elsewhere recorded. ('Guy's Hosp. Rep.' 1850, p. 226.) In another, the body was exhumed after several months' burial, and the stomach was found perforated from disease in the usual situation.

Spontaneous or gelatinized perforation.—The stomach is occasionally subject to a spontaneous change by which its coats are softened, and they give way generally at the cardiac or greater end. As the effusion of the contents of the organ in such a case never give rise to peritoneal inflammation, and no symptoms occur prior to death to indicate the existence of so extensive a destruction of parts, it is presumed to be a change in the dead body, and the coats of the stomach are supposed to undergo a process of solution or digestion. It is commonly attributed to the solvent action of the gastric juice, the spleen, diaphragm, and other viscera being sometimes softened. Wilks thinks that this post-mortem or cadaveric perforation of the stomach is so rare a condition, that it is not met with once in five hundred cases. In two cases in which it was observed, one patient had died from albuminuria and the other from head affection, but in neither of these could there be found any peculiarities regarding their food, the time of the last meal, or the state of the bodies, to account for the spontaneous destruction of the coats of the stomach. (For remarks on this subject by Budd, see 'Med. Gaz.' vol. 39, p. 895.) In Jan. 1845, the author met with an instance of this perforation in a child between two and three years of age. It was seized with convulsions, became insensible, and died twenty-three hours afterwards. After death, the greater end of the stomach was found destroyed to the extent of three inches, and the edges were softened and blackened. There was no food in the stomach, and nothing had passed into the organ for thirty-two hours before death. It was therefore impossible to ascribe death to the perforation, or the perforation to poison. ('Med. Gaz.' vol. 36, p. 32.) An inspection of the body, with a general history of the case, will commonly suffice to remove any doubt in forming an opinion whether the extensive destruction so commonly met with, has or has not arisen from poison. Thus, in a cadaveric perforation, the aperture is generally situated in that part of the stomach which lies to the left of the cardia; it is very large, of an irregular form, and ragged and pulpy at the edges, which have the appearance of being scraped. The mucous membrane of the stomach is not found inflamed. There is occasionally slight redness, with dark brown or almost black lines (striæ) in and near the dissolved coats, which have an acid reaction. It can only be confounded with perforation by the action of corrosives; but the well-marked symptoms during life, and the detection of the substance after death, together with the changes in the throat and gullet, will at once indicate the perforation produced by corrosive poison. A case of extensive perforation of the stomach, as the result of the action of the gastric fluids, has been reported by Barnes. (See 'Med. Gaz.' vol. 41, p. 293.)

CHAPTER 13.

TO BE OBSERVED IN INVESTIGATING A CASE OF POISONING—THE INSPECTION THE BODY—THE EXHUMATION OF BODIES—IDENTITY OF SUBSTANCES—ESERVATION OF ARTICLES FOR ANALYSIS—USE OF NOTES—MEDICO-LEGAL PORTS.

a practitioner is called to a case of poisoning, it is necessary that ould know to what points he ought to give his attention. Every should be made by him to save life when the individual is living; hile engaged in one duty, it is also in his power to perform another, sing the case to be one of suspected criminal poisoning, namely, e down many circumstances which may tend to detect the per- or of a crime. There is no person so well fitted to observe these as a medical man; but it unfortunately happens, that many facts tant as evidence are often overlooked. The necessity for observing ecording them is not perhaps generally known. A medical man not make himself officious on such occasions, but he would be dful of his duty as a member of society, if he did not aid the course tice by extending his scientific knowledge to the detection of crime. uch to the credit of the medical profession that the crime of murder isoning—a form of death from which no caution or foresight can t a person—is so frequently brought to light, by the announcement spicious facts of a medical nature to magistrates and coroners; n several occasions the highest compliments have been passed by on medical practitioners who have been thus indirectly the means ging atrocious criminals to the bar of justice.

e following are the principal points which demand the attention edical jurist in all cases of suspected poisoning:—1. With respect to—

Symptoms.

The time of their occurrence,—their nature. 2. The exact period ich they were observed to take place after a meal, or after food or ine had been taken. 3. The order of their occurrence. 4. Whether was any remission or intermission in their progress, or whether they ued to become more and more aggravated until death. 5. Whether atient had laboured under any previous illness. 6. Whether the oms were observed to recur more violently after a particular meal, r any particular kind of food or medicine. 7. Whether the patient mited:—the vomited matters, if any (especially those *first* ejected), l be procured: their odour, colour, and acid or alkaline reaction as well as their quantity. 8. If none are procurable, and the ing has taken place on the dress, furniture, or floor of a room—then ion of the clothing, sheet, or carpet, may be cut and reserved for is:—if the vomiting has occurred on a deal floor, a portion of the may be scraped or cut out:—or if on a stone pavement, then a clean of sponge soaked in distilled water may be used to remove any of the substance. The vessel in which vomited matters have ontained will often furnish valuable evidence, since heavy mineral s fall to the bottom, or adhere to the sides. 9. Endeavour to ain the probable nature of the food or medicine last taken, and act *time* at which it was taken. 10. Ascertain the nature of *all* the nt articles of food used at a meal. 11. Any suspected articles of as well as the vomited matters, should be sealed up as soon as

possible in a clean glass-vessel, labelled, dated, and reserved for analysis. 12. Note down, in their own words, all explanations voluntarily made by parties present, or who are supposed to be concerned in the suspected poisoning. 13. Whether more than one person partook of the food or medicine: and if so, whether all these persons were affected, and how? 14. Whether the same kind of food or medicine had been taken before by the patient or other persons without ill effects following. In the event of the *death* of the patient, it will be necessary for the practitioner to note down—15. The *exact time* of death, if known, and thus determine how long a period the person has survived after having been first attacked with the suspicious symptoms. 16. Observe the attitude and position of the body. 17. Observe the state of the dress. 18. Observe all surrounding objects. Any bottles, paper-packets, weapons, or spilled liquids lying about should be collected and preserved. 19. Collect any vomited matters near the deceased. Observe whether vomiting has taken place in the recumbent position or not. If the person has vomited in the erect or sitting posture, the front of the dress will commonly be found covered with the vomited matters.

Inspection of the Body.

20. Note the external appearance of the body, whether the surface is livid or pallid. 21. Note the state of the countenance. 22. Note all marks of violence on the person, or discomposure of the dress, marks of blood, &c. 23. Observe the presence or absence of warmth or coldness in the legs, arms, abdomen, mouth, or armpits. 24. Note the presence of rigidity or cadaveric spasm in the body. To give any value to the two last-mentioned characters, it is necessary for the practitioner to observe the nature of the floor on which the body is lying—whether the body be clothed or naked, young or old, fat or emaciated. These conditions create a difference, in respect to the cooling of the body and the access of rigidity. 25. If found dead—when was the deceased last seen living, or known to have been alive? 26. Note all circumstances leading to a suspicion of suicide or murder. 27. The time after death at which the inspection is made. 28. Observe the state of the abdominal viscera. If the stomach and intestines are found inflamed, the seat of inflammation should be exactly specified; also all marks of softening, ulceration, effusion of blood, corrosion, or perforation. The stomach should be removed and placed in a *separate vessel*, ligatures being applied to the two ends. If cut open for examination at this period, this should be performed in a clean dish, and with such care that none of the contents are lost or are allowed to mix with the contents of the intestines. 29. The fluids of the stomach, if this organ is opened during the inspection, should be collected in a clean *graduated* vessel:—notice *a*, the quantity; *b*, the odour tried by several persons; *c*, the colour; *d*, acid or alkaline reaction; *e*, presence of blood, mucus, or bile; *f*, presence of undigested food; *g*, other special characters. 30. The contents of the duodenum should be separately collected, ligatures being applied to it. 31. Observe the state of the large intestines, especially the rectum, and note the condition of their contents. The discovery of hardened fæces in the rectum would prove that purging had not existed recently before death. In one case this became a question of considerable importance. 32. The state of the windpipe, throat, and gullet, whether there are in these parts any foreign substances, or marks of inflammation and corrosion. This is of essential importance, as it throws a light upon the question, whether the poison swallowed was irritant or corrosive, and whether it had or had not a local

emical action. It also removes any doubt which might arise respecting ath by suffocation from mechanical causes. 33. Observe the state of e lungs and heart, and note all morbid changes. 34. Examine the ain and spinal marrow. 35. The condition of the uterus, ovaries, and nital organs should be examined, as poison has been sometimes introuced into the system by the vagina. 36. The liver with the gall bladder ould be removed for a chemical examination. 37. The urinary bladder, ith any fluid contained in it, should be removed and placed in a parate jar.

Such are the points to which, in the greater number of cases of susected poisoning, a medical jurist should attend. By means of these data, oted according to the particular case to which they are adapted, he will general be enabled, without difficulty, to determine the probable time f death, and the actual means by which death was brought about. He ay thereby have it in his power also to point out the dish or article f food which had contained the poison, if the case be one of poisoning; d to throw light upon any disputed question of suicide or murder in elation to the deceased. Many cases of poisoning are rendered obscure, wing to these points not having been attended to in the first instance.

Details respecting the mode of performing an *inspection* are not entered to. This the practitioner will have acquired during his study of natomy; and the only essential points in addition to those mentioned re,—1. To examine all the important organs for marks of natural disease: d 2. To note down any unusual pathological appearances, or abnormal eviations; although they may at the time appear to have no bearing the question of poisoning. It is useful to bear in mind on these casions, that the body is inspected, not merely to show that the person s died from poison, but to prove that he has *not* died from any *natural use*. Medical practitioners commonly give their attention exclusively the first point; while lawyers, who defend accused parties, very properly rect a most searching examination to the last-mentioned point, *i.e.* the althy or unhealthy state of those organs which are essential to life, and ith which the poison has not probably come in contact. The usual uses of *sudden death* have their seats commonly in the brain, the heart d its great vessels, or in the lungs. Marks of effusion of blood, conestion, inflammation, suppuration, or a diseased condition of the valves of e heart, should be sought for and accurately noted, whatever may be e condition of the abdominal viscera. It has also been recommended at an examination of the spinal marrow should be made. If the cause f death be obscure after the general examination of the body, there is od reason for inspecting the condition of this organ.

Exhumation of Bodies.—Sometimes the inspection of a body is required be made long after interment. So long as the coffin remains entire, ere may be the expectation of discovering certain kinds of mineral ison in the organs; but decomposition may have advanced so far as to stroy all pathological evidence. The inspection in such cases is mmonly confined to the abdominal viscera. The stomach is often found thinned and collapsed, that the anterior and posterior walls appear form only one coat. This organ should be removed with the duodenum, d ligatures should be applied to each. The liver and the spleen should so be removed, in order that they may, if necessary, be separately alysed. If poison is not found in one or more of these parts, it is not ely that it will be discovered in the body. It has been recommended at a portion of earth immediately above and below the coffin should e removed for analysis, as it may contain arsenic; but this appears to

me to be an unnecessary piece of refinement when the coffin is c or when the abdominal parietes still cover the viscera. If decompo has so far advanced as to have led to an admixture of earth wit viscera, and the poison is found in minute quantity in the tissues the source of the poison may be regarded as doubtful. The body deceased person, when exhumed, should be identified by some frie relative, in the presence of the medical examiner. In one case of m by poison, the evidence almost failed, owing to this precaution not h been taken.

It is important that the viscera taken from a body which has long in the grave should be sealed up immediately. They should be allowed to come in contact with any metal, nor with any surface e that of clean glass, porcelain, or wood. It has been recommended they should be washed with chloride of lime, or placed in alcohol; this is decidedly improper: the use of any preservative chemical l would not only embarrass the future analysis, but would render a s examination of an unused portion of the liquid necessary, the id of which would have to be unequivocally established. Preservation air in clean glass vessels, with well-fitted corks, covered with ski what is still better, sheet-caoutchouc or gutta percha, is all th required in practice. There is seldom any objection to the use of a s quantity of chloroform. The vapour of this liquid is diffused thr the vessel and tends to retard putrefaction. The contents of a stom consisting of blood and mucus, have thus been preserved in an uncha state for several months.

Identity of Substances.

It is necessary to observe, that all legal authorities rigorously i upon proof being adduced of the *identity* of the vomited matters or c liquids taken from the body of a deceased person, when poisonin suspected. Supposing that during the examination, the stomach viscera are removed from the body, they should never be placed on surface, or in any vessel, until we have first ascertained that the su or vessel is perfectly *clean*. If this point be not attended to, it will l the power of counsel for the defence to raise a doubt in the minds of jury, whether the poisonous substance might not have been acciden present in the vessel used. This may be regarded as a very re presumption; but, nevertheless, it is upon technical objections of this l that acquittals follow, in spite of the strongest presumptions of g This is a question for which every medical witness should be prep whether he is giving his evidence at a coroner's inquest, or in a Cou Law. Many might feel disposed to regard matters of this kind as volving unnecessary nicety and care, but if they are neglected i possible that a case may be at once stopped: so that the care subseque bestowed upon a chemical analysis will be labour thrown away. Evid of the presence of poison in the contents of a stomach was once rejecte a trial for murder, because they had been hastily thrown into a borrowed from a neighbouring grocer's shop; and it could not be s factorily proved that the jar was clean and entirely free from trac poison (in which the grocer dealt) when used for this purpose. W the life of a human being is at stake, as in a charge of murder by poi ing, the slightest doubt is always interpreted in favour of the accused.

Not only must clean vessels be used for receiving any liquid des for subsequent chemical analysis, but care must be taken that the *ide* of a substance is preserved, or the most correct analysis afterwards n

l be inadmissible as evidence. The suspected substance, when once ced in the hands of a medical man, should never be let out of his tody. It should be kept sealed under his private seal, and locked up ile in his possession, in a closet to which no other person can have ess. If he has once let the article out of his hands, and allowed it to s through the hands of several other persons, then he complicates the dence for the prosecution, by rendering it indispensable for these sons to state under what circumstances it was placed while in their session. The exposure of a suspected substance on a table, or in a set or room to which many have access, may be fatal to its identity; the chemical evidence, so important in a criminal investigation, will bably be altogether rejected by the Court. A case was tried, in which analysis of certain matters vomited by a person poisoned with arsenic, s not admitted as evidence against the prisoner, because the medical n had left them in the custody of two women; and these women had owed the vessel containing the suspected liquid (which was proved contain arsenic) to be exposed in a room open to the access of many rsons. In another case, the analysis of some suspected liquids was not owed in evidence, because the practitioner, who lived in the country, d was unwilling to take the responsibility of analysing them, had sent m up to town by a carrier to be examined by a chemist. If sealed a private seal, and this is observed by the receiver to be unbroken, fore he proceeds to an analysis, this mode of transmission may not rhaps be objected to. When any article is reserved for analysis, care ould be taken to attach, securely, immediately to it, or to the vessel ntaining it, a label, upon which is plainly written, in ink, the name of e deceased and the date, including the day of the week and month. is is especially necessary when there are two or more articles for alysis. The greatest inconvenience has resulted from the neglect of this mple precaution.

Preserving articles for analysis.—In removing viscera or liquids from e body, and reserving them for analysis, it is necessary to observe rtain precautions. A clean vessel with a wide mouth should be lected; it should be only sufficiently large to hold the organ or liquid be less air remaining in it the better); it should be secured by a closely-ting clean cork, covered with fine skin, bladder, or gutta percha tissue. nother piece of skin should then be tied over the mouth, or, for this, ost-caoutchouc or gutta percha may be substituted with advantage. It ould lastly be covered with a layer of white leather. In this way any ss by evaporation or decomposition is prevented, and the viscera may be eserved (in a cool place) for some time. If the mouth of the vessel s too wide for a cork, the other articles cannot be dispensed with. Paper ily should not be used: the appearances after death of the viscera of infant, suspected to have died from poison, have been entirely de-troyed by drying, from the evaporation which took place through the ores of paper with which the vessel in which they were contained, was overed. The practitioner should bear in mind that all these matters are kely to come out in evidence; and whatever is worth doing at all, is orth doing well. For reasons already stated, antiseptic chemical com-unds should not be used.

The articles used for the preservation of viscera should be in all cases rupulously examined. Some kinds of calico are dressed with arsenic d starch paste, and many kinds of wrapping-paper as well as wall-papers e strongly impregnated with this poison. An observation made by ickin shows that this is not an unnecessary caution. He was engaged examining the body of a child, in order to determine the cause of death.

The organs were healthy, and as no sufficient cause presented itself, he removed the stomach, with a view of making an analysis of its contents. He was suddenly called away; and, to preserve the stomach, he wrapped it in a piece of paper (used for papering rooms), placed it on the uncoloured side, and he locked it in a closet until the following day. Assisted by a friend, he then analysed the contents, and found a trace of morphia with a large quantity of arsenic. As the symptoms from which the child had suffered were not those of poisoning with arsenic, and there were no appearances of the action of this substance on the body, he came to the conclusion that there must be some extraneous cause to account for its presence. He examined a portion of the wall-paper in which the stomach had been wrapped, and then found that that part of it which was coloured yellow was tinted with arsenious sulphide or orpiment. It was therefore evident, as orpiment contains white arsenic, that the stomach and its contents had imbibed a portion of the poison during the night. ('Lancet,' June 23, 1855, p. 632.) This satisfactorily accounted for the presence of arsenic, under circumstances which might have given rise to a false charge of murder. Many wall-papers, having any tinge of green or golden yellow in them, contain arsenic, and this arsenic spreads by imbibition to other parts of the paper not so tinted. It would, of course, be proper to avoid in all cases the use of any wrapper having upon it mineral colours of any description. The above case shows in a striking point of view the danger of trusting to chemical analysis alone. Unless we look to physiology and pathology, a most erroneous opinion may be expressed.

Arsenic is sometimes found mixed with ferric oxide in ochreous deposits or soils. It is thus occasionally present in the soil of cemeteries, but in an insoluble form. Even in the fur deposited in tea-kettles, in which there is generally some ferric oxide, arsenic has been found in an insoluble form. From about a pound and a half of the crust or fur of a vessel used for boiling water, Otto obtained well-marked arsenical deposits. Pöllnitz detected in the fur of kettles—copper, lead, tin, and even antimony. Osborn confirmed Pollnitz's conclusion, namely, that lead is present in an insoluble form in the deposits of kettles and boilers. ('Med. Times and Gaz.' Dec. 22, 1860, p. 608.) Otto discovered a much larger proportion of arsenic in the calcareous crust taken from a kitchen boiler. Ten ounces of this gave a deposit of arsenic in a glass tube, and several stains on porcelain. He thinks that, if a sufficient quantity is employed, arsenic will be found in the sediments of all spring and well-waters. ('Ausmit. d. Gifte,' 1856, p. 61.) The author has found arsenic in the water of rivers used for the supply of towns, and has extracted a well-marked quantity from two ounces of the dried mud of the Thames, as well as from similar quantities of earth taken from three churchyards in the north of England. ('Guy's Hosp. Rep.' 1860. On Arsenic and Antimony.) These facts tend to show the extreme danger of placing reliance on minute chemical results in the absence of good physiological and pathological evidence.

The results of an analysis, in the shape of sublimates or precipitates, should be preserved as evidence, distinctly labelled in small glass tubes hermetically sealed. They can then, if asked for, be produced for examination at the inquest or trial.

On the use of Notes.—It has already been recommended, as a rule in these criminal investigations, that a practitioner should make notes of what he observes in regard to symptoms, appearances after death, and the results of a chemical analysis. His own observations should be kept distinct from information given to him by others. He may base his conclusions on the

not on the latter. From the common forms of law in this
ierson charged with the crime of poisoning may remain im-
weeks before he is brought to trial. It is obvious, however clear
tances may at the time appear to a practitioner, that it will
e than ordinary powers of memory to retain for so long a
tinct recollection of all the facts of a case. If he is unpro-
notes, and his memory is defective, then the case will turn in
ie prisoner, who will be the person to benefit by the neglect
ess. In adopting the plan here recommended, such a result
ly prevented. It may be remarked that the law relative to
ility of notes or memoranda in evidence is very strict, and,
murder, is rigorously enforced by the judges. In order to
notes or memoranda admissible, it is indispensably necessary
ould be taken by the witness at the time the observations are
soon afterwards as practicable; and further, it must be
that a witness can refer to them only for the purpose of
is memory.

gal Reports.—One of the duties of a medical jurist is to draw
of the results of his examination: 1, in regard to symptoms;
to appearances after death; and, 3, in regard to the results of

With respect to the two first divisions of the report, the
erred to the rules for investigating cases of poisoning (p. 203).
ly be observed that the time at which the person was first seen,
umstances under which the attendance of the practitioner was
well as the period of death, should be particularly stated. The
y of the week, and the month, should be invariably mentioned.
al witnesses merely state the day of the week, without that of
or *vice versâ*. At a trial this sometimes creates great confusion,
a reference to almanacs necessary. The words yesterday, next
ould never be used. The facts which it will be necessary to
report are specially stated under the heads of investigation

If these facts are not observed in the order there set down,
as evidence of the cause of death or of the criminality or inno-
ticular parties, will be entirely lost. In drawing up a report of
nd appearances after death, the facts should be in the first
inly and concisely stated *seriatim*, in language easily intelligible
ssional persons. A reporter is not called upon to display his
it to make himself understood. If technical terms are employed,
g should be stated in parentheses. When a subject is thoroughly
there can be no difficulty in rendering it in simple language;
is not well understood, the practitioner is not in a position to
eport. Magistrates, coroners, solicitors, and barristers, easily
ance, even when it appears under the mask of erudition.

ling facts, a reporter should not encumber his statements with
erences, or comments. The facts should be first stated, and the
should be reserved until the end of the report. The language
nclusions are expressed, should be precise and clear. It must
red that these are intended to form a concise summary of the
t, upon which the judgment of a magistrate, or the decision
r's jury, will be ultimately based. They should be strictly
the matters which are the subject of inquiry, and which have
en under the observation of the witness. Thus, they commonly
following questions:—What was the cause of death? What
lical circumstances which lead you to suppose that death was
oison? What are the circumstances which lead you to suppose
was *not* caused by natural disease? Answers to one or all of

these questions comprise, in general, all that a reporter is required to introduce into the conclusions of his report.

The reporter must remember that his conclusions are to be based only upon *medical* facts,—not upon moral circumstances, unless he is specially required to express his opinion with regard to them when they are of a quasi-medical nature. Further, they must be founded only on what *he has himself seen or observed*. Any information derived from others, should not be made the basis of an opinion in a medico-legal report. It is scarcely necessary to remark that a conclusion based upon mere *probabilities* is of no value as evidence.

In drawing up a report on the *results of a chemical analysis*, the following rules should be borne in mind. A liquid or solid may be received for analysis. 1. When, where, and of whom, or how received? 2. In what state was it received—secured in any way, or exposed? 3. If more than one substance received, each to be separately and distinctly labelled; appearance of the vessel, and the quantity of liquid (by measure) or solid (by weight) contained therein. 4. When did you proceed to make the analysis? 5. Did any one assist you, or did you make the analysis yourself? 6. Physical characters of the substance. 7. Processes and tests employed for determining whether it contained poison. All the steps of these processes need not be described: a general outline of the analysis will suffice. The magistrate may thus satisfy himself by an appeal to others (if necessary) whether the analysis has or has not been properly made. 8. Supposing the substance to contain poison—is this in a pure state or mixed with any other body? 9. The strength of the poison, if an acid, or if it be in solution in *all* cases the *quantity* of poison found, determined if possible by actual weighing. 10. Supposing no poison to be contained in it, what was the nature of the substance? Did it contain anything of a noxious nature, i.e. likely to injure health or destroy life? 11. Could the supposed poisonous substance exist naturally or be produced within the body? 12. Was it present in any of the liquids or solids employed in the chemical analysis? 13. Was it contained in any of the articles of food or medicine taken by the deceased? 14. Is its presence to be ascribed to the use of any mineral matter employed by injection after death for the preservation of the body of the deceased? 15. What quantity of poison was actually separated in the free or absorbed state? 16. How much of the substance found would, under the circumstances, be likely to destroy life?

There are few reports in which answers to many of these questions, although not formally put, will not be required; and unless the whole of them are borne in mind by the operator at the time an analysis is undertaken, those which are omitted can never receive an answer, however important to the ends of justice that answer may ultimately become.

IRRITANT POISONS.

CHAPTER 14.

SULPHURIC ACID, OR OIL OF VITRIOL. SYMPTOMS—APPEARANCES AFTER DEATH—FATAL DOSE—PERIOD AT WHICH DEATH TAKES PLACE—MODE OF DETECTING THE POISON IN PURE AND MIXED LIQUIDS—ON ARTICLES OF CLOTHING.

Sulphuric Acid, or Oil of Vitriol. Sulphate of Indigo.

Sulphuric acid, or oil of vitriol, is more extensively used in the arts and manufactures than any other acid; hence cases of poisoning by it are very common. Occasionally it is used for suicidal purposes, more especially by women; and accidents in consequence of its having been mistaken for some other liquid are numerous. It has often been used externally (vitriol-throwing), where the object was to injure a person, in fits of rage or jealousy.

Symptoms.—When this poison is swallowed in a concentrated form, the symptoms produced come on either *immediately*, or during the act of swallowing. In a case which came under the notice of the editor, a girl swallowed about a fluid ounce of brown oil of vitriol in mistake for a magnesian mixture which she was in the habit of taking, and did not discover the mistake till severe symptoms had supervened. There is violent burning pain, extending through the throat and gullet to the stomach, and the pain is often so severe that the body is bent. There is an escape of gaseous and frothy matter, followed by retching and vomiting, the latter accompanied by the discharge of shreds of tough mucus and of a liquid of a dark coffee-ground colour, mixed with blood. The vomited matters may contain shreds of mucous membrane from the gullet and stomach, and even portions of the muscular structures of the former. These may form complete casts of some portion of the gullet or stomach. The mouth is excoriated, the lining membrane and surface of the tongue white, or resembling soaked parchment; in one instance the appearance of the mouth was as if it had been smeared with white paint. After a time, the membrane acquires a grey or brownish colour; the mouth is filled with a thick viscid substance, consisting of saliva, mucus, and the corroded membrane; this renders speaking and swallowing difficult. If the poison has been administered by a spoon, or the phial containing it has been passed to the back of the throat, the mouth may escape the chemical action of the acid. A medical witness must bear this circumstance in mind when he is required to examine an infant suspected to have been poisoned by sulphuric acid. Around the lips and on the neck may be found spots of a brown colour from the spilling of the acid and its action on the skin. There is great difficulty of breathing, owing to the swelling and excoriation of the throat and larynx, and the countenance has, from this cause, a blueish or livid appearance; the least motion of the abdominal muscles is attended with increase of pain. These symptoms, although characteristic of the action of a corrosive liquid, have been sometimes mistaken for those of disease. ('Henke, Zeitschr. der S.A.' 1843, 2, 284.) The stomach is so irritable that whatever is swallowed is immediately ejected, and the vomiting is commonly violent and incessant. In a case reported by Geoghegan, the patient vomited for three or four

hours. This symptom then ceased, and did not recur, although the woman did not die until thirty-four hours after the poison had been swallowed. ('Med. Gaz.' vol. 48, p. 328.) The matters *first* vomited generally contain the poison; they are acid, and if they fall on a limestone pavement there is effervescence; if on coloured articles of dress, the colour is sometimes altered to a red or yellow, or it is entirely discharged and the texture of the stuff destroyed; on a black cloth dress, the spots produced by the concentrated acid are reddish-brown, and remain moist for a considerable time. Attention to these circumstances may often lead to a suspicion of the real cause of the symptoms, when the facts are concealed. After a time there is exhaustion, accompanied by great weakness; the pulse is quick, small, and feeble; the skin cold, mottled or dusky, and covered with a clammy sweat. There is generally great thirst, with obstinate constipation of the bowels; should any evacuations take place, they are commonly either of a dark brown or leaden colour, in some instances almost black, arising from an admixture of altered blood. There are sometimes convulsive movements of the muscles, especially those of the face and lips. The countenance, if not livid from obstructed respiration, is pale, expressive of great anxiety and intense suffering. The intellectual faculties are quite clear, and in the greater number of cases of acute poisoning by this acid, death takes place very suddenly in from eighteen to twenty-four hours after the poison has been taken.

Appearances after death.—The marked effects of this poison are not always observed in the stomach; they may be confined to the region of the throat and windpipe. In an inspection of the body, the whole course of the alimentary canal from the mouth downwards, should be examined; since in recent or acute cases it is in the throat and gullet that we generally obtain strong evidence of the action of a corrosive poison. The discovery of the usual marks of corrosion in these parts is always highly corroborative of the signs of poisoning found in the stomach. During the inspection, the examiner must not omit to notice any spots on the skin produced by the spilling of the acid: these are commonly of a dark brown colour, and are situated about the mouth, lips, and neck. The appearances met with in the body vary, according as death has taken place quickly or slowly. Supposing the case to have proved rapidly fatal, the membrane lining the mouth may be found white, softened, and corroded. The mucous membrane of the throat and gullet is commonly found corroded, having a brown-black or ash-grey colour, and dark-coloured blood is effused in patches beneath it. The corroded membrane of the gullet is occasionally disposed in longitudinal folds, portions of it being partly detached. The *stomach*, if not perforated, is collapsed and contracted. On laying it open, the contents are commonly found of a dark brown or black colour and of a tarry consistency, being formed in great part of mucus and altered blood. The contents may or may not be acid, according to the time the patient has survived, and the treatment which has been adopted. On removing them, the stomach may be seen traversed by black lines, or the whole of the mucous membrane may be corrugated and stained black or of a dark brown colour. This blackness is not entirely removed by washing. On stretching the stomach, traces of inflammation may be found between the folds, indicated by a dark crimson colour. On forcibly removing the blackened membrane, the red colour indicative of inflammation may be seen in the parts beneath. Both the dark colour and marks of inflammation are sometimes partial, being confined to isolated portions or patches of the mucous membrane. When the stomach is perforated, the coats are softened, and the edge of the aperture is commonly black and irregular. In removing the stomach, the opening is

ble to be made larger by the mere weight of the organ. The contents not always escape; but when this happens, the surrounding parts are icked by the poison. In one case, the spleen, the liver, and the coats the aorta, were found blackened and corroded by the acid, which had ped through the perforation. In some rare cases the lining membrane he aorta has been found strongly reddened. When a person has rived for eighteen or twenty hours, traces of corrosive and inflammatory on may be found in the small intestines. In one case the mucous nbrane of the ileum was corroded. The interior of the windpipe, as l as of the bronchial tubes, has also presented marks of the local action the acid. The acid has thus destroyed life without reaching the nach. A remarkable instance in which the poison penetrated into l destroyed both lungs has been reported by Gull. ('Med. Gaz.' 45, p. 1102.) It is important for a medical witness to bear in mind, t the mouth, throat, and gullet are not always found in the state ve described. Ogle met with a case in which the membrane of the gue was but slightly affected. The man had swallowed a large dose the acid and had died in nine hours. ('Med. Times and Gaz.' Ap. 21, 0.) Strange as it may appear, cases are recorded in which, notwithding the introduction of this poison into the stomach, the gullet has ped its chemical action. Dickinson has reported a case of poisoning sulphuric acid, in which there was no corrosion of the mouth and oat. The patient, a female, æt. 52, recovered in about five months. The nach had probably sustained injury, as the most urgent symptoms e constant vomiting after taking food, and obstinate constipation. The ntity of acid swallowed was half an ounce, mixed with half an ounce of er. The patient felt *immediately* a burning sensation at the pit of the nach. ('Lancet,' Nov. 26, 1853, p. 502.) The acid had here evidently its corrosive power by dilution. Cases of recovery are rare. A man took into her mouth a quantity of the acid by mistake; she spat it immediately. Magnesia was given to her, and two hours afterwards was suffering from intense burning pain in the throat, gullet, and nach. Her lips were swollen and blistered; the lining of the mouth s whitish, but not excoriated; the soft palate and uvula were congested l partly destroyed. Olive oil and bicarbonate of soda were given at rvals. At a later period, there was vomiting of an opaque, milky-king substance. Two days after there was some difficulty of breathing, this symptom subsided, and the patient was discharged apparently l. ('Lancet,' 1871, II. p. 540.) When the acid has been taken in a l more *diluted* state, the marks of inflammation on the mucous membrane less decided, and the blackening is not so considerable. Nevertheless, acid, unless too much diluted, acts upon and darkens the blood in the sels, as well as that contained in the stomach, although it may not ken the mucous membrane or the contents.

Walker met with a case in which a man, æt. 30, swallowed fifteen achms and a half of sulphuric acid (sp. gr. 1·842), and died twenty- hours afterwards. Half an hour after taking the poison he re-abled a patient in the collapsed stage of cholera. The inside of the lips, well as the tongue and throat, were swollen, and had the appearance being smeared with thin arrow-root. He suffered severe pain, but did vomit until *three-quarters of an hour* had elapsed: the vomiting peared to be then excited by the liquid which had been given to him. e vomited matters were dark, bloody, and viscid. The patient was sible up to the time of his death. An inspection revealed the usual pearances. The mucous membrane of the stomach was destroyed, and whole surface was darkened. The greatest amount of injury was

at the pyloric end, where three small perforations were found. The orifice of the pylorus was swollen, constricted, and hardened; it was so contracted as to admit only a silver probe. The duodenum had also suffered. The first two inches of the arch of the aorta were much inflamed. There were no traces of the acid in the stomach; there was a slight trace in the duodenum; a trace in the serous fluid at the base of the brain; but the largest quantity was found in the blood contained in the heart ('Edin. Month. Jour.' June 1850, p. 538.) This case is remarkable in the fact that vomiting was not immediate; that there were no spots on the face; that the poison was swallowed in large quantity on an empty stomach; and there was free voluntary exertion, as, twenty hours after he had taken the poison, the man got out of bed and sat on a night-stool. In the London 'Medical Gazette,' vol. 48, p. 328, a full account of the symptoms and appearances after death in a well-marked case of poisoning by sulphuric acid, is given, as well as a process for detecting this poison when absorbed.

Quantity required to destroy life.—The dangerous effects of the acid appear to arise rather from its degree of concentration, than from the absolute quantity taken. The quantity actually required to prove fatal must depend on many circumstances. If the stomach is full when the poison is swallowed, the action of the acid may be spent on the food and not on the stomach; and a larger quantity might then be taken than would suffice to destroy life if the organ were empty. The smallest quantity which is described as having proved fatal was in the following case:—Half a teaspoonful of concentrated sulphuric acid was given to a child about a year old by mistake for castor oil. The usual symptoms came on, with great disturbance of breathing, and the child died in twenty-four hours. The quantity here taken could not have exceeded *forty drops.* ('Med. Gaz.' vol. 29, p. 147.) It is, however, doubtful whether this small quantity would have proved fatal to an adult. The smallest fatal dose which Christison states he has found recorded, is *one drachm;* it was taken by mistake by a stout young man, and killed him in seven days. (Op. cit.) Even when moderately diluted, it will destroy life rapidly. A man swallowed, on an empty stomach, six drachms of the strongest acid diluted with eighteen drachms of water. He suffered from the usual symptoms, and died in two hours and a half. ('Med. Times and Gaz.' 1863, 1, p. 183.) Two-thirds of the cases prove fatal.

Period at which death takes place.—It has been already stated, that the average period at which death takes place in cases of acute poisoning by sulphuric acid, is from eighteen to twenty-four hours. When the stomach is perforated by the acid, it commonly proves more speedily fatal. In one instance, reported by Sinclair, a child about four years old died in four hours: the stomach was found perforated. When the poison acts upon the windpipe, death may be a still more speedy consequence, from suffocation and, owing to this, it appears to be more rapidly fatal to children than adults. Craigie mentions a case in which three ounces of concentrated sulphuric acid destroyed life in three hours and a half. Remer met with an instance in which death took place in *two hours.* A case is reported by Watson, in which a woman swallowed two ounces of a strong acid. She died in *half an hour*, but it appears that a quarter of an hour before death she had made a deep wound in her throat, which gave rise to great bleeding. The stomach was found extensively perforated: but it is highly probable that the wound accelerated death in this case. The shortest on recorded, occurred to Rapp. A man, æt. 50, swallowed three ounces and a half of concentrated sulphuric acid. He died in *three-quarters of an hour.* ('Gaz. Méd.' Dec. 28, 1850.) On the other hand, there are numerous

nstances reported in which the poison proved fatal from secondary causes, t periods varying from one week to several months. These secondary auses, such as contraction and occlusion of the gullet, may threaten, and ven cause, death from starvation, and require operative procedures. When he passage of bougies to dilate the stricture of the œsophagus has failed to rocure relief, gastrotomy has been successfully performed, and the patient ed through an artificial opening into the stomach. Eleven deaths from ulphuric acid poisoning were recorded in England and Wales in the year 880.

Chemical Analysis.—This acid may be met with either concentrated or iluted; and a medical jurist may have to examine it under three condiions:—1. In its simple state. 2. When mixed with organic matters, as ith liquid articles of food, or in the contents of the stomach. 3. On solid rganic substances, as where the acid has been thrown or spilled on articles f dress or clothing.

In the simple state.—If *concentrated*, it possesses these properties: 1. Wood, sugar, or other organic matter plunged into it, is speedily carbonized r charred, either with or without the application of heat. 2. When boiled ith wood, copper-cuttings, or mercury, it evolves fumes of sulphurous cid; this is immediately known by the odour, as well as by the acid vapour irst rendering blue, and then bleaching starch-paper dipped in a solution f iodic acid. 3. When mixed with an equal bulk of water, great heat is volved.

The diluted Acid.—For the acid in a diluted state, but one test need be pplied, either the *barium nitrate* or the *barium chloride*. Having ascertained y test-paper that the liquid is acid, we dilute a portion of it, and add a ew drops of nitric acid, and then a solution of the barium salt. If sulphuric cid is present, a dense white precipitate of barium sulphate will fall down: his is insoluble in all acids and alkalies. The precipitate is collected, ashed, dried, and mixed with five parts of charcoal in powder. This ixture is placed in a small platinum crucible, which should be closely overed, and then heated to full redness for five minutes. If the precipitate is a sulphate, it will thus be converted into a sulphide. In order to prove his:—1. A portion of the mixture when cooled may be mixed with water, ell stirred, and filtered. A pale yellowish liquid will be obtained, having n alkaline reaction, and giving a brown or black precipitate with a solution of lead acetate. 2. If in small quantity, the mixture may be placed at nce on glazed card (coated with lead carbonate) and wetted, when a stain of lead sulphide will be produced. 3. The powder may be heated with trong hydrochloric acid, when sulphuretted hydrogen will be copiously volved, known by its smell and other properties. If the quantity of precipitated sulphate is very small, it may be mixed with one-third of its weight of potassium cyanide and heated in a reduction-tube to full redness. This residue, placed on glazed card, and wetted, gives the reaction indicative of the presence of a sulphide, proving that the original precipitate was a sulphate, and that sulphuric acid was present in the liquid submitted to analysis.

Diluted sulphuric acid does not carbonize organic substances which are immersed in it. The application of heat will only effect carbonization when the water of the acid is entirely evaporated. Thus, paper or linen, wetted with the diluted acid, becomes charred when dried and heated. This may serve as one method of identification in the absence of tests.

In liquids containing organic matter.—If sulphuric acid is mixed with such liquids as porter, coffee, or tea, the liquid is first rendered clear by iltration. Some liquids, such as vinegar, beer, and most wines, generally ontain a soluble sulphate and have an acid reaction. Should the liquid

be thick and viscid like gruel, it may be diluted with water, and then boiled with the addition of a little acetic acid. For the action of the barium test, it is not necessary that the liquid should be absolutely clear, provided it is not so thick as to interfere mechanically with the subsidence of the precipitate. So far with regard to liquids administered, for of which the administration has been attempted. A similar process may be applied to the examination of matters *vomited* and of the *contents of the stomach*, care being taken to separate the insoluble parts by filtration, before adding the test. The coats of the stomach should be cut up and then boiled in distilled water for some time for the perfect extraction of the acid. The decoction filtered and concentrated by evaporation may then yield evidence of its presence, and is then tested for the presence of a free mineral acid in one of two ways. Ferric acetate is mixed with a solution of potassium sulphocyanide. This mixture will yield a blood-red colour when added to the suspected liquid should a free mineral acid be present. An alcoholic solution of methyl-violet is also rendered blue when 1-4000th part of sulphuric acid is added. If there be evidence of a free mineral acid, and the liquid yields a decided precipitate with barium nitrate solution, it should be concentrated by evaporation if necessary, and strong alcohol be added till the mass contains 75 per cent. by volume of absolute alcohol. The soluble sulphates are thus precipitated; and after standing and filtration to remove these, the filtrate is neutralized with solution of potash, the alcohol distilled off, the solution evaporated to dryness. The residue, when taken up with water, may then be tested with barium nitrate after acidification with hydrochloric acid. One part of the precipitate corresponds to 0·42 part by weight of sulphuric acid.

Fig. 4.



Beaker and tube for the dialysis of liquid poisons.

When the acid is mixed with milk, decomposed blood, and mucus, or other substances which render it thick and viscid, it may be readily separated by dialysis; a process which is applicable to the other acid poisons, such as the nitric, hydrochloric, and oxalic. A portion of the acid viscid liquid should be placed in a test tube, about five inches long and one inch in diameter, open at both ends, the neck being securely covered with a layer of thin bladder, or parchment paper. The tube is then immersed, mouth downwards, in a vessel containing distilled water. After some hours the acid will pass through the membrane, and may be detected in the water. This process may be employed as a trial test of the contents of the stomach when they have a strongly acid reaction. In thus testing for sulphuric acid it must be remembered that a sulphate, such as Epsom salts, may be present in the liquid, and an innocent acid like vinegar or lemon-juice may give the acid reaction. To remove any fallacy on this ground, a portion of the liquid tested should be evaporated, and treated with alcohol as already described.

It is an important fact that the contents of a stomach in a case of poisoning by sulphuric acid, are sometimes entirely free from any traces of this poison, even when it has been swallowed in large quantity. The acid is not commonly found when the person has been under treatment, when there has been considerable vomiting, aided by the drinking of water or other simple liquids, or when he has survived several days. If the case has been under treatment, the acid is either wholly absent or neutralized by antidotes. A girl swallowed four or five ounces of diluted oil of vitriol, and died in eighteen hours. No portion of the acid could be detected in the stomach; but she had vomited considerably, and the acid was easily proved to exist in the vomited matters, by

amining a portion of the sheet of a bed which had become wetted by
m. In another case, nearly two ounces of the concentrated acid were
llowed; the patient died in twenty-five hours; the stomach was exten-
ly acted on, and yet no trace of the acid could be discovered in the
ntents. The liquidity of the poison, and the facility with which it
omes mixed with other liquids and ejected by vomiting, will readily
nish an explanation of this fact. In many cases of poisoning by sul-
uric acid, therefore, a medical witness must be prepared to find that
mical analysis will furnish only negative results. This, however, is not
onsistent with death having taken place from the poison. The facts
so conclusive on this point, that it would be unnecessary to add to the
dence accumulated on the subject, but that an erroneous statement
been made that no person can die from poison, except the poison be
nd in the body. Casper has dealt with this question. He relates three
es of poisoning by sulphuric acid, which occurred in his practice, one
ich proved fatal in eight days, a second in five days, and a third in
ee days. In not one instance could a trace of the poison be found.
andb. der Ger. Med. 1, pp. 421, 429.) In the second case two table-
onfuls were swallowed by a girl. The analysis revealed merely the
idental presence of a fractional part of a grain of alkaline sulphate in
stomach and bowels. Thus there was an entire failure of proof from
mistry, while the facts of the case, and the appearances in the body,
blished conclusively that death had really been caused by sulphuric
d. In one instance, in which death took place on the eleventh day,
author found no trace of sulphuric acid in the body. If the stomach
uld be perforated, the contents will be found in the abdomen, or
haps in the lower part of the cavity of the pelvis: they may then be
lected, boiled with distilled water, and the solution examined for the
id by the process already described. If the contents of the stomach
highly putrefied, the sulphuric acid may be found combined with
monia.

On solid organic substances.—It sometimes happens in cases of poisoning
sulphuric acid that it is spilled upon articles of clothing, such as cloth
linen, and here a medical jurist may succeed in detecting it, when every
her source of chemical evidence fails. Again, sulphuric acid is often
ed for the purpose of seriously injuring a party, as by throwing it on
person, and under the Criminal Law Consolidation Act it is enacted
t whosoever shall cast or throw at, or upon, or otherwise apply to any
son any corrosive fluid with intent to burn, maim, disfigure, or disable
y person, or to do some grievous bodily harm, shall, whether any *bodily*
ury be effected or not, be guilty of felony, and punished accordingly. A
mical examination of the clothes may furnish the only evidence of the
rosive nature of the fluid, which, when accompanied with bodily injury,
ders the offender liable to a severe punishment. On such occasions,
oof of the corrosive nature of the liquid is required; and this is easily
tained by a chemical examination of a part of the dress. A case of this
nd was tried at the Liverpool Winter Assizes, 1866 (*Reg.* v. *Goff*). The
jury appears to have been of a superficial kind. The jury found the
soner guilty of throwing the corrosive fluid, but with no intent to injure.
is was tantamount to an acquittal. Injury to the clothes only does not
stitute the crime. There must be injury to the person. There have
en many instances of vitriol-throwing for the sake of damaging the
ss. The process of analysis is simple. The spot, unless it has been
shed, strongly reddens litmus paper pressed upon it. The stained fabric
uld be digested in rectified spirit at a gentle heat, whereby a brown-
-coloured liquid may be obtained on filtration. If sulphuric acid is

present, the liquid will have an acid reaction, and produce the usual effects with the barium test after evaporation and dilution with water. Old stains are known by the complete destruction of the organic fibre: fresh stains by their dampness. The acid remains fixed in the stuff. Sulphuric acid has been thus detected in clothing after the lapse of twenty-seven years. The detection of spots of this acid on articles of dress, has in some cases served to supply the place of direct evidence from a chemical analysis of the stomach; and in other instances it has aided justice in fixing on an accused person the act of administration.

The importance of analysis applied to articles of clothing was made evident in *Reg.* v. *Brown* (Bury St. Edmunds, Lent Ass. 1864). The deceased, aged three years, was an illegitimate child of the prisoner. It was living with the prisoner's father and mother. On the day of its death, the prisoner came to see the child, and was with it alone in a bedroom: in *five minutes* after she had left the room, no other person being present, the child was heard to be sick, and it was found to be suffering from the effects of some corrosive acid. The child died in nine or ten hours, and the symptoms during life, when it was seen by a medical man, as well as the appearances in the body after death, were clearly those of poisoning by oil of vitriol. The acid was detected in vomited matter on the shirt of the child, and on a dress worn by the mother on the occasion of her visit. It was further proved that a bottle of vitriol, kept in a closet of the house where she was servant, was missing. In spite of these strong facts in proof of administration, the jury, under the charge of Cockburn, C.J., acquitted the prisoner. It was somewhat remarkable that the child did not scream from pain during the act of swallowing, and that attention should not have been called to its condition until after the lapse of five minutes. Still, the facts appeared to point to the prisoner only, as the person who administered the poison.

Sulphate of Indigo.

Several cases of accidental poisoning by this liquid have occurred. As the compound is a solution of indigo in strong sulphuric acid, the symptoms and appearances after death are similar to those which have been already described. This kind of poisoning may be suspected when, together with these symptoms, the membrane of the mouth has a blue or blue-black colour. The vomited matters, as well as the fæces, are at first of a deep blue-black tint; afterwards green; and it was observed in two instances that the urine, voided by the patients, had a blue tinge.

As indigo is one of the substances now directed to be mixed with arsenic when this poison is sold in small quantities, the detection of this colouring principle in the mouth and vomited matters will not necessarily show that it has been taken in the form of sulphate.

Analysis.—This solution is of a dark blue colour, and strongly acid. Sulphuric acid is detected in it by the methods above described. The blue colour is discharged by chlorine, or when a portion, previously diluted, is boiled with nitric acid.

CHAPTER 15.

POISONING BY NITRIC ACID OR AQUA FORTIS—APPEARANCES AFTER DEATH—PROCESSES FOR DETECTING THE POISON IN LIQUIDS CONTAINING ORGANIC MATTER—POISONING BY HYDROCHLORIC ACID.

NITRIC ACID is popularly known under the name of Aqua Fortis, or Red Spirit of Nitre. According to Tartra, it seems to have been first used as a poison about the middle of the fifteenth century. Although it is perhaps not much used in the arts as oil of vitriol, cases of poisoning by it are not very common. In the year 1880, five deaths from this acid were recorded in England and Wales.

Symptoms.—When nitric acid is taken in a concentrated state, the symptoms, on the whole, bear a close resemblance to those produced by sulphuric acid. They come on *immediately*, and the swallowing of the acid is accompanied by intense burning pain in the throat and gullet, extending downwards to the stomach: there are gaseous eructations, from the chemical action of the poison, swelling of the abdomen, violent vomiting of liquid or solid matters, mixed with altered blood of a dark brown colour, and shreds of yellowish-coloured mucus, having a strongly acid reaction. The abdomen is generally exquisitely tender: but in one well-marked case of poisoning by the acid, the pain was chiefly confined to the throat: probably the poison had not reached the stomach. The mucous membrane of the mouth is commonly soft and white, after a time becoming yellow, or even brown; the teeth are also white, and the enamel is partially destroyed by the chemical action of the acid. There is great difficulty of speaking and swallowing, the mouth being filled with viscid mucus: the power of swallowing is, indeed, sometimes entirely lost. On opening the mouth, the tongue may be found swollen, and of a citron colour; the tonsils are also swollen and enlarged. The difficulty of breathing is occasionally such as to render tracheotomy necessary, especially in young persons. ('Med. Gaz.' vol. 12, p. 220.) As the symptoms progress, the pulse becomes small, frequent, and irregular—the surface of the body cold, and there are frequent rigors (shivering). The administration of remedies, even the swallowing of the smallest quantity of liquid, increases the severity of the pain, occasions vomiting, and gives rise to a feeling of laceration or corrosion. (Tartra, 144.) There is obstinate constipation. Death takes places in from eighteen to twenty-four hours, and is sometimes preceded by a kind of stupor, from which the patient is easily roused. The intellectual faculties commonly remain clear until the last. In one instance the patient was insensible, but she ultimately recovered. Death may be occasioned by the action of this acid on the larynx, as in the case of sulphuric acid. Should the patient survive the first effects of the poison, the mucous membrane of the throat and gullet may be ejected, either in irregular masses, or in the form of a complete cylinder. There is great irritability of the stomach, with pain on taking food, frequent vomiting and ultimate destruction of the powers of digestion: the patient becomes slowly emaciated, and dies, sometimes after many months, from starvation or exhaustion. A man swallowed nitric acid in beer: he recovered from the first symptoms, but died six months afterwards, evidently from the injury caused by the poison to the mucous lining of the stomach. He suffered from pain and from such irritability in this organ, that neither solids nor fluids could be retained. ('Lancet,' 1860, II. p. 510.)

The *vapour* of this acid is destructive to life. In 1854, *Mr. Haywood*,

a chemist of Sheffield, lost his life under the following circumstanc
He was pouring a mixture of nitric and sulphuric acids from a c
containing about sixty pounds, when by some accident the vesse
broken. For a few minutes he inhaled the fumes of the mixed acid
it does not appear that any of the liquid fell over him. Three hours
the accident, he was sitting up and appeared to be in moderately
health. He was then seen by a medical man, and complained mer
some cuts about his hands. He coughed violently. In three hours
there was difficulty of breathing, with increase of the cough. The
a sense of tightness at the lower part of the throat, and the puls
hard. At times he said he could scarcely breathe. He died eleven
after the accident. On inspection, there was congestion of the wir
and bronchial tubes, with effusion of blood in the latter. The hea
flaccid, and contained but little blood; and the lining membrane c
heart and aorta was inflamed. The blood had a slightly acid rea
The windpipe was not examined. It is very probable that the s
mischief was in this organ, and that the deceased died from inflamm
effusion and a swelling of the parts about the opening of the win
('Lancet,' Ap. 15, 1854, p. 430.) A similar accident occurred t
Stewart and one of the janitors of an educational institution in
burgh, in 1863. A jar of nitric acid, which he was carrying, fell c
floor and was broken. He and the janitor, instead of withdr
from the spot, wiped the floor, and attempted to save some of the
They thus inhaled the fumes which were immediately diffused. S
returned home unconscious of the mischief which had been done.
an hour or two, difficulty of breathing came on, and in spite of
effort to save his life, he died in ten hours after the accident.
janitor suffered from similar symptoms, and died the day foll
('Chem. News,' 1863, p. 132.) It is probable that in these cases
was great bronchial effusion, leading to the entire obstruction of r
tion. The fumes of nitrous acid vapour, which are generally asso
with nitric acid, are of a very deadly kind. In the manufacture o
cotton acid vapours are evolved, which, if respired, although
may produce no immediate ill effects, are liable to cause pneu
and death. On one occasion, in preparing gun-cotton, the
accidentally inhaled the vapour, and suffered from severe const
of the throat, tightness in the chest, and cough for more than a
The fumes from batteries worked with nitric acid are often produc
serious results; and the editor has met with serious cases resultin
their inhalation.

Appearances after death.—Supposing death to have taken place
from the liquid acid, the following appearances may be observed.
skin of the mouth and lips will present various shades of colour, fr
orange-yellow to a brown; it appears like the skin after a blister o
and is easily detached from the subjacent parts. Yellow spots pr
by the spilling of the acid may be found about the hands and ne
yellow frothy liquid escapes from the nose and mouth; and the ab
is often much distended. The membrane lining the mouth is som
white, at others of a citron colour; the teeth are white, but pre
yellowish colour about the coronæ. The pharynx and larynx are
inflamed; and the latter is sometimes œdematous. The lining mer
of the gullet is softened, and of a yellow or brown colour, easily de
often in long folds. The windpipe is more vascular than usual, a
lungs are congested. The most strongly marked changes are, ho
seen in the stomach. When not perforated, this organ may be
distended with gas, its mucous membrane partially inflamed, and c

r patches of a yellow, brown, or green colour; or it may be even black. his green colour is due to the action of the acid on the colouring matter the bile; but it must be remembered that a morbid state of the bile elf may give a similar appearance to the mucous membrane in many ses of death from natural disease. There is occasionally inflammation the peritoneum, and the stomach is adherent to the surrounding organs. s coats may be so much softened, as to break down under the slightest ssure. In the duodenum similar changes are found; but in some cases e small intestines have presented no other appearance than that of slight lness. It might be supposed that the stomach would be in general rforated by this corrosive liquid; but perforation has not been often served. Tartra met with only two instances, and in one of these the rson survived twenty, and in the other thirty hours. In giving this ison to rabbits, he did not find the stomach perforated, although the acid d evidently reached that organ, as its coats were stained of a deep yellow lour. In these experiments the non-perforation appeared to be due to e protective influence of the food with which the stomach was distended. the few cases that are reported in English journals, it would appear at the stomach has not been perforated: the poison had been swallowed en after a meal, and its coats had thus escaped the corrosive action of e acid. In a case which proved fatal after the long period of six months, ere was, at the intestinal end of the stomach, a distinct cicatrix with ckering and hardening of the surrounding mucous membrane, causing slight contraction of the pyloric orifice. The only other appearance sisted in some dark longitudinal lines on the posterior surface of the ing membrane of the gullet. This had probably been caused by the id. ('Lancet,' 1860, II. p. 510.) In 1871 a man died in Guy's Hospital venteen hours after swallowing three fluid ounces of commercial nitric id. On examination the stomach was found much disorganized. There as a small aperture on the anterior surface, half an inch from the lower rder, and one inch to the left of a vertical line drawn from the entrance the gullet. Around the opening the peritoneum was ecchymosed, but lymph was exuded; and it is probable that the rupture had taken place out the time of death. The duodenum showed signs of sloughing on e valvulæ conniventes; whilst the jejunum and ileum were natural in ppearance. ('Guy's Hosp. Rep.' xvii. 1872, p. 223.)

Quantity required to destroy life.—The *smallest* quantity of this acid hich the author finds reported to have destroyed life, is about *two drachms.* was in the case of a boy, aged thirteen: he died in about thirty-six urs. But less than this quantity, even one drachm, would doubtless suffice kill a child, and, under certain circumstances, an adult; for the fatal sult depends on the extent of the mischief produced by this corrosive ison in the windpipe, gullet, and stomach. What is the largest dose of ncentrated acid, from the effects of which a person has recovered, it is ficult to say; since in most of the cases of recovery mentioned by authors, e quantity of the poison taken was unknown. A case of recovery from out half an ounce of the strong acid mixed with the diluted acid, is ported ('Lancet,' 1870, 1, p. 549). The patient was a man, æt. 21. e had the usual symptoms, with the exception that there was no yel- wing of the teeth nor corrosion of the mouth. The vomited matters ere bloody and of a dark colour. He suffered from stricture of the llet, and this remained when he left the hospital about fifteen weeks er his admission. In the editor's case (*supra*) of poisoning by three nces of nitric acid death resulted in seventeen hours. The stomach as perforated.

Period at which death takes place.—Sobernheim relates a case of poi-

soning by nitric acid, which proved fatal in *one hour and three quarters*. (Op. cit. 402.) This the author believes to be the most rapidly fatal instance on record, where the acid acted as a poison. The usual well-marked effects were found in the gullet, stomach, and small intestines. In infants, however, life may be destroyed by this poison in a few minutes, should it happen to effect the larynx. The longest case is, perhaps, that recorded by Tartra, where a woman perished from exhaustion, produced by the secondary effects of the poison, *eight months* after having swallowed it.

Chemical Analysis.—In the simple state. This acid may be met with either concentrated or diluted. The *concentrated acid* varies in colour from a deep orange red to a light straw yellow. It may be recognized, 1. By evolving acid fumes when exposed to the air or when heated. 2. By its staining nitrogenous organic matter, such as wool, yellow or brown, the colour being heightened and turned to a reddish tint by contact with caustic alkalies. 3. When mixed with a few copper cuttings, it is rapidly decomposed, deep red acid vapours are given off, and a blueish-green solution of copper nitrate is formed. Tin or mercury may be substituted for copper in this experiment. 4. The addition of gold-leaf and a few drops of hydrochloric acid. On warming the mixture, if nitric acid is present the gold is dissolved. Common aqua fortis (nitric acid) sometimes contains as impurity, a sufficiency of hydrochloric acid to dissolve gold-leaf by heat. *In the diluted state.* This acid is not precipitated, like sulphuric, by any common reagent, since all its alkaline combinations are soluble in water. 1. The liquid has a highly acid reaction, and on boiling it with some copper turnings, red nitrous fumes are given off, unless the proportion of water is very great. At the same time the liquid acquires a blue colour. 2. A streak made on white paper with the diluted acid does not carbonize the paper when heated; but a faint yellow stain is left. 3. The liquid is not precipitated by a salt of barium or of silver. The two last experiments give merely negative results: they serve to show that sulphuric and hydrochloric acids are absent.

In order to detect nitric acid, the liquid should be first tested for the presence of a free mineral acid in the way described for sulphuric acid; then carefully neutralized by a solution of potash, and evaporated slowly to obtain crystals. If the liquid contain nitric acid, these crystals will possess the following characters:—1. They appear in the form of lengthened fluted prisms, which neither effloresce nor deliquesce on exposure. One drop of the solution, evaporated spontaneously on glass, will suffice to yield distinct and well-formed prismatic crystals. This character distinguishes potassium *nitrate* from a large number of salts. 2. When moistened with strong sulphuric acid, the powdered crystals slowly evolve a colourless acid vapour. By this test the nitrate is known from every other deflagrating salt. 3. A portion of the powdered crystals should be placed in a small tube and mixed with their bulk of fine *copper* filings. The mass is then to be moistened with water, and a few drops of strong *sulphuric acid* added. Either with or without the application of a gentle heat, orange-red nitrous fumes are evolved, recognizable *by their colour*, odour, and reaction, and by their setting free iodine on *starch-paper* moistened with a solution of potassium iodide. A small crystal

Fig. 5.



Crystals of Nitre, magnified 30 diameters.

sulphate may be substituted for the copper. This acquires colour, and on warming the mixture orange-red fumes ıpected nitrate should be free from any alkaline chloride, reduction tube should be used when the quantity of the If the nitrate is mixed with chloride, the following ɔund preferable. 4. We add to the powdered crystals a gold-leaf and strong hydrochloric acid; then boil for a he gold will either wholly or entirely disappear if nitric is present. Its partial solution will be indicated by a dark colour on the addition of stannous chloride to the liquid

ıtaining organic matter.—Nitric acid may be administered as tea, vinegar, or beer. In this case, besides the acid ɾill be a peculiar smell produced by the strong acid, when ıtances of an organic nature. The application of the usual ·e counteracted: thus, unless the quantity of nitric acid in her large, the orange-red nitrous fumes are not evolved on ɔopper cuttings. The action on gold-leaf will enable the ct nitric acid in coffee, tea, and similar organic liquids, ɔroportion of acid is small. Boil a fragment of gold-leaf loric acid, and add while boiling a few drops of the sus- iquid to the mixture. If the acid is present the gold will When the acid liquid is thick and turbid, a portion of it in a tube and submitted to the process of dialysis (see ɔd matters, as well as the contents and coats of the stomach d be boiled in water, and filtered. If not cleared by fil- ay be submitted to dialysis, and the acid water obtained potash, and concentrated. If by filtration we succeed in ır acid liquid, the colour is of no importance. The liquid ılly neutralized with a solution of pure potash, and con- aporation. Drops of this may be placed on a slide, and the ıcopically examined and compared with those of nitre. nto the concentrated neutralized liquid, and dried, burns ın like touch-paper.

ı obtained by evaporating the neutralized liquid are gene- ɾith organic matter, but they fuse into a white mass when ınum capsule. The pure nitre thus obtained may be tested bed. The organic matter in the crystals does not interfere ı of the copper and gold tests.

r the nitric acid, or the nitrate into which it has been con- d with common salt, the copper test cannot be employed. ɾill in such a case furnish the best evidence. Hydrochloric ıll portion of gold-leaf may be added to the dried residue, re boiled. If nitric acid or a nitrate is present, even in tion, some portion of the gold will be dissolved, a fact y the addition of stannous chloride.

may be detected in *stains on clothing*, if recent, by simply ned cloth in water. An acid liquid will be obtained, unless f old date or the stuff has been washed. This liquid, when nay be dealt with in the manner already described. The s acid on black and blue cloth are of a yellow or brownish- When long exposed they become dry, but the cloth is easily le method of detecting the acid is to boil at once a piece of h with a fragment of gold-leaf and hydrochloric acid. If nitrate is present in the stain, a portion of the gold will be

Hydrochloric Acid. Muriatic Acid.

Hydrochloric or muriatic acid, popularly known under the name of spirit of salt, is occasionally taken as a poison. In the year 1880, it was the cause of six deaths in England and Wales. In the cases which have been hitherto observed, the *symptoms* and *appearances* have been similar to those caused by nitric acid. A woman, æt. 63, swallowed *half an ounce* of concentrated hydrochloric acid. She was received into the hospital in three-quarters of an hour. The prominent symptoms were burning pain in the throat and stomach, feeble pulse, cold and clammy skin, retching and vomiting of a brown matter streaked with blood and containing shreds of membrane. There was great exhaustion. The throat became swollen, the patient lost the power of swallowing, and died in eighteen hours. She retained her senses until the last. The *appearances* in the body were as follows: the mucous membrane of the mouth and throat was white, softened, and destroyed in many places by the corrosive action of the acid. The membrane of the gullet was red and inflamed. The back part of the stomach near the pylorus was black, stripped of its mucous membrane (which was generally softened), and marked with black lines. It was not perforated. ('Lancet,' July 16, 1859, p. 59.) The smallest quantity of hydrochloric acid which has as yet been known to prove fatal was a teaspoonful in a girl 15 years of age. For other cases in which an ounce was taken and the persons recovered, see 'Lancet,' July 27, 1850, p. 113, and the 'Med. Gaz.' Dec. 28, 1849. Otto reported a fatal case in a child ('Horn's Vierteljahrsschr.' 1865, vol. 1, p. 361). It is not often that hydrochloric acid is administered with criminal intent. A trial took place at the Taunton Winter Assizes, 1866 (*Reg.* v. *Somers*), in which a girl of twelve years of age was charged with administering this acid to her mistress in beer, with intent to murder her. Some of the acid had been purchased for domestic use, and the prisoner had been cautioned not to touch it as it was poisonous. On tasting the beer prosecutrix perceived an unpleasant taste, and had a burning sensation in her throat. On analysis the beer was found to contain hydrochloric acid. Life was not endangered, and no grievous bodily harm was done. The prisoner was convicted of a misdemeanour under the statute, of administering poison with intent to injure, aggrieve, and annoy.

. *Chemical Analysis.*—In a *concentrated* state, hydrochloric acid evolves copious fumes. The pure acid is nearly colourless: the commercial acid is of a lemon-yellow colour, and frequently contains iron, arsenic, common salt, and other impurities. It reddens litmus paper strongly and gives the general reactions of a mineral acid. (See p. 216.) When boiled with a small quantity of black oxide of manganese, chlorine is evolved. It does not dissolve gold-leaf until a few drops of nitric acid have been added to it, and the mixture is heated. In the *diluted* state, these properties are lost. It gives a dense white precipitate when a solution of silver nitrate is added to it. This precipitate is insoluble in nitric acid, but soluble in ammonia: it acquires a purple and black colour if exposed to light, and when heated it melts without decomposition, forming a yellowish-coloured substance on cooling. If the acid is contained in organic liquids in moderate quantity, it admits of separation by distillation to dryness. In this case any fixed chlorides present are left in the retort. It may also be procured by dialysis in a state fit for testing. (See page 216.)

Hydrochloric acid, in small quantity, as well as alkaline chlorides, are natural constituents of the fluids of the stomach and bowels. The presence of local chemical changes in the throat and stomach, would show whether

the acid had been taken as a poison. If the acid is found only in minute quantity, no inference of poisoning can be drawn unless there are distinct marks of its chemical action upon the throat and stomach. It darkens the blood like sulphuric acid, although it has not the same degree of carbonising action on organic matter. The *stains* produced by this acid on black cloth are generally of a slight reddish colour. As the acid is volatile, it may possibly disappear from the stuff. If recent, the acid may be separated by boiling the stuff in water and applying the silver test, or by boiling a portion of the stained cloth with gold-leaf and nitric acid. An unstained portion of cloth should be similarly tested for the sake of comparison, as neutral chlorides give a similar precipitate with silver nitrate.

CHAPTER 16.

POISONING BY VEGETABLE ACIDS. OXALIC ACID—SYMPTOMS AND EFFECTS—APPEARANCES AFTER DEATH—CHEMICAL ANALYSIS—ACID OXALATE OF POTASH OR SALT OF SORREL. TARTARIC ACID. ACETIC ACID. VINEGAR.

Oxalic Acid.

Symptoms.—If this poison is taken in a large dose, *e.g.* from half an ounce to an ounce of the crystals dissolved in water, a hot burning acid taste is experienced during the act of swallowing the poison. This is accompanied by a similar sensation extending through the gullet to the stomach. There is sometimes a sense of constriction or suffocation: the countenance is livid, and the surface of the skin soon becomes cold and clammy. Vomiting occurs either immediately or within a few minutes. Should the poison be diluted, there is merely a sensation of extreme sourness, and vomiting may not occur until after a quarter of an hour or twenty minutes. In some cases there has been little or no vomiting; while in others, this symptom has been incessant until death. In a case in which an ounce of the acid was swallowed, the vomiting with pain in the stomach continued until the fifth day, when the man died suddenly. ('Lancet,' 1860, I. p. 209.) In a case in which the poison was much diluted, vomiting did not occur for seven hours. ('Christison.') The vomited matters are highly acid, and have a greenish-brown or almost black colour; they consist chiefly of mucus and altered blood. In one reported instance they were colourless. ('Med. Gaz.' vol. 37, p. 792.) In another case, fluid blood of a bright arterial colour was vomited after some hours. ('Prov. Med.' June 25, 1851, p. 344.) There is great pain and tenderness in the abdomen, with a burning sensation in the stomach. There are cold clammy perspirations and convulsions. In a case in which about two ounces of the poison had been swallowed, there was no pain. Violent vomiting and collapse were the chief symptoms. There is in general an entire prostration of strength, so that if the person is in the erect position, he falls; there is likewise unconsciousness of surrounding objects, and a kind of stupor, from which, however, the patient may be roused without difficulty. The pulse is very feeble. Owing to the severity of the pain, the legs are sometimes drawn up towards the abdomen. The pulse is small, irregular, and scarcely perceptible; there is a sensation of tingling or numbness in the extremities, and shortly before death the respiration is spasmodic. The inspirations are deep, and a long interval elapses between them. Such are the symptoms commonly observed in a rapidly fatal or acute case. In the majority of fatal cases death takes place within an hour.

Should the patient survive the first effects of the poison, the following symptoms may appear: there is soreness of the mouth, constriction and burning pain in the throat, pain in swallowing, tenderness in the abdomen, and irritability of the stomach, so that there is frequent vomiting, accompanied by purging. The tongue is swollen, and there is great thirst. The patient may slowly recover from these symptoms. In a case related by Edwards, the patient, a female, lost her voice for eight days. Another case has been reported by Bradley, from which it may be inferred that a loss of voice may result from a direct effect of oxalic acid on the nervous system. A man swallowed a quarter of an ounce of the acid, and suffered from the usual symptoms in a severe form. In about nine hours his voice, although naturally deep, had become low and feeble. This weakness of voice remained for more than a month, and its natural strength had not returned even after the lapse of nine weeks. During the first month there was numbness with tingling of the legs. ('Med. Times,' Sept. 14, 1850, p. 292.) The editor has seen a similar case in which a man almost lost his voice for some time. The occurrence of the sensation of numbness, and its persistence for so long a period after recovery from the symptoms of irritation, point to an effect of the poison on the nervous system. Spasmodic twitchings of the muscles of the face and extremities have also been observed in some instances. ('Lancet,' March 22, 1851, p. 329.)

Appearances after death.—The mucous membrane of the tongue, mouth, throat, and gullet, is commonly white, as if bleached; but it is sometimes coated with a portion of the brown mucous matter discharged from the stomach. This latter organ contains a dark brown mucous liquid, often acid, and having almost a gelatinous consistency. On removing the contents, the mucous membrane will be seen pale and softened, without always presenting marks of inflammation or abrasion, if death has taken place rapidly. This membrane is white, soft, and brittle, easily raised by the scalpel, and presents the appearance which we might suppose it would assume after having been boiled for some time in water. The small vessels are seen ramifying over the surface, filled with dark-coloured blood, apparently solidified within them. The lining membrane of the gullet presents the same characteristics. It is pale or dark, and appears as if it had been boiled in water, or digested in alcohol; it has been found strongly raised in longitudinal folds, interrupted by patches where the membrane has become abraded, and presenting a curious worm-eaten appearance. In a case which was fatal in eight hours, the tongue was covered with white specks; the gullet was not inflamed, but the stomach was extensively destroyed, and had a gangrenous appearance. Portions of the mucous membrane were detached, exposing the muscular coat. With respect to the intestines, the upper portion may be found inflamed; but, unless the case is protracted, the appearances in the bowels are not strongly marked. In a well-marked instance of poisoning by this acid, however, which is recorded by Hildebrand, the mucous or lining membrane of the stomach and duodenum was much reddened, although the patient, a girl of eighteen, died in three-quarters of an hour after taking one ounce of the acid, by mistake for Epsom salts. (Casper's 'Vierteljahrsschr.' 1853, Bd. 3, p. 256.) In a case of poisoning in which two ounces of the acid had been taken, and death was rapid, the coats of the stomach presented almost the blackened appearance produced by sulphuric acid, owing to the colour of the altered blood pigment spread over them. In protracted cases, the gullet, stomach, and intestines have been found more or less congested or inflamed. In a case in which an ounce was swallowed, and death occurred on the fifth day, the stomach was slightly

gested, and contained a bloody fluid, but the mucous membrane was ire. ('Lancet,' 1860, II. p. 509.)

The following case is furnished by Welch:—A woman, aged 28, llowed *three drachms* of the crystallized acid. She was found dead *hour* afterwards. Both lungs were extensively congested, and the rt and large vessels were full of dark-coloured blood. The stomach tained about three-quarters of a pint of a dark-brown fluid, and its ng membrane was reddened generally. The other organs, except the in, were healthy; and this presented appearances indicative of long-ding disease. This case is remarkable from the smallness of the dose, rapidity of death, and the early production of a well-marked redness he mucous membrane of the stomach. The diseased state of the body y have tended to accelerate death from the poison. In one instance larynx was found filled with frothy mucus, and the left side of the rt and the lungs were gorged with dark-coloured fluid blood. In ther, the appearances of sanguineous apoplexy were found in the brain. person fell dead after retching violently. Apoplexy was supposed to the cause of death. On an inspection of the body, it was found that a ge clot of blood was effused on the brain, and this appeared satis-torily to account for death. But when the stomach was examined, lic acid was detected in it. This poison had been taken, and had pro-ed its usual effects. The deceased had taken it with suicidal intention, l the violent vomiting which it caused had led to death by apoplexy n effusion of blood. ('Lancet,' 1863, I. p. 47.) Without a chemical estigation, it is obvious that the real cause of death would have been this instance overlooked. In a few cases there have been scarcely any rbid appearances produced by this poison.

The glairy contents of the stomach or its coats do not always indicate ng acidity until after they have been boiled in water. Oxalic acid s not always appear to have a strongly corrosive action on the stomach. is therefore rare to hear of the coats of the organ being perforated it. In many experiments on animals, and in some few observations the human subject, the author found nothing to bear out the view t perforation is a common effect of the action of this poison. The d undoubtedly renders the mucous coat soft and brittle, and perfora-n of the coats may occur either during life or after death as a result its chemical action. Wood has recorded the case of a female, æt. 27, ad dead, whose death had been obviously caused by oxalic acid, but quantity taken, and the duration of the case, were unknown. The nach presented, at its upper and fore part, near the cardiac opening, irregular aperture of a size to admit the point of the finger. From , a dark gelatinous-looking matter, resembling coffee-grounds, was ping in abundance. The perforation was enlarged during the re-val, and presented the appearance of two large apertures separated by arrow band. The stomach contained a bloody fluid, in which oxalic l was detected, and the mucous membrane had an eroded appearance. small intestines (jejunum and ileum) were similarly affected.

Diagnosis.—This is not usually difficult. If a patient, after swallowing rystalline substance which tastes strongly acid, is seized almost imme-tely with violent vomiting, pain in the stomach, feeble pulse, cold sweats, l collapse, and dies within half an hour, or even earlier, there can rcely be a doubt that oxalic acid has been administered (Christison).

Quantity required to destroy life.—The smallest quantity of this poison ch has been known to destroy life is *sixty grains*. The boy, æt. 16, took acid in a solid form, and in about an hour was found insensible, pulse-, and his jaws spasmodically closed. He had vomited some bloody

matter: his tongue and lips were unusually pale, but there was no excoriation. He died in eight hours. ('Lancet,' Dec. 1, 1855.) In one case (p. 227) *three drachms* destroyed life in an hour. Two cases occurred at Guy's Hospital, in each of which half an ounce of oxalic acid had been swallowed. Active treatment was adopted and both patients recovered. When the dose is upwards of half an ounce, death is commonly the result; but a case has occurred in which a man recovered after having taken an ounce of the acid. Brush has communicated to the 'Lancet' a case in which recovery took place after a similar dose of the poison had been taken. (See also a case by Alison in the same journal, Nov. 2, 1850, p. 502.) The acid was in this instance taken by mistake for Epsom salts. Ellis met with a case of recovery in a woman æt. 50. She swallowed an ounce of the acid in beer. In half an hour she was found complaining of a burning pain in the stomach, and rolling about. Chalk and water were freely given, and she recovered. ('Lancet,' 1865, II. p. 265.)

Period at which death takes place.—Similar quantities of this poison do not always destroy life within the same period of time. In two cases, in which about two ounces of the acid were respectively taken, one man died in twenty minutes—the other in three-quarters of an hour. Christison mentions an instance in which an ounce killed a girl in thirty minutes; and another in which the same quantity destroyed life in *ten minutes;* but in a third case death did not occur until the fifth day. Ogilvy reported a case of poisoning by oxalic acid, in which it is probable that death took place within *three minutes* after the poison had been swallowed. The sister of the deceased had been absent from the room about that period, and on her return found her dying. The *quantity* of poison taken could not be determined. When the dose of oxalic acid is half an ounce and upwards, death commonly takes place within an hour. There are, it must be admitted, numerous exceptions to this rapidity of action. Christison reported two cases which did not prove fatal for thirteen hours; and in an instance that occurred to Fraser, in which half an ounce was taken, the individual died from the secondary effects in a state of perfect exhaustion, thirteen days after taking the poison. Twelve deaths from this poison in England and Wales were recorded in the year 1880.

Chemical Analysis. In the simple state.—This acid may be met with either as a solid or in solution in water. *Solid oxalic acid* crystallises in long slender prisms, which, when perfect, are four-sided. In this respect it differs from other common acids, mineral and vegetable. The crystals are unchangeable in air; they are soluble in water and in alcohol, forming strongly acid solutions. When heated on platinum-foil they melt, and are entirely dissipated without combustion and without being carbonized. Heated gently in a close tube, they melt, and the vapour is condensed as a white crystalline sublimate in a cold part of the tube. The crystals are prismatic, like those obtained from the solution. There should be no residue whatever if the acid is pure: but the commercial acid generally leaves a slight residue of fixed impurity. By this effect of heat, oxalic acid is easily distinguished from those crystalline salts for which it has been sometimes fatally mistaken, namely, the sulphates of magnesium and zinc. These leave white residues in the form of anhydrous salts. A teaspoonful of oxalic acid in small crystals weighs seventy-six grains, and half an ounce of the crystals is equivalent to three teaspoonfuls.

Tests for the solution.—1. *Silver nitrate.* When added to a solution of oxalic acid, it produces an abundant white precipitate of silver oxalate.

ion containing so small a quantity of oxalic acid as scarcely to litmus-paper, is affected by this test; but when the quantity of is small, it is always advisable to rate the liquid by evaporation before g the test. The silver oxalate is ed by the following properties:—1. It pletely dissolved by cold nitric acid. cted on a filter, thoroughly dried, and on thin platinum-foil, it is dissipated slight detonation. When the oxalate nall quantity, this detonation may be d in detached particles on burning the reviously well dried. 2. *Calcium sul-* A solution of oxalic acid is precipitated by lime water and by all the salts of . Lime water is itself objectionable st, because it is precipitated white by other acids. The salt of calcium as a test, is open to the least objection, is the *sulphate*. As this a very soluble salt, its solution must be added in rather large y to the suspected acid poisonous liquid. A white precipitate of oxalate is slowly formed. This precipitate should possess the g properties:—1. It ought to be immediately dissolved by nitric ochloric acid. 2. It ought not to be dissolved by ammonia, nor ic, tartaric, acetic, or any other vegetable acid.

Fig. 6.



Crystals of Oxalic Acid, magnified 30 diameters

iquids containing organic matter.—The process is the same, whether plied to liquids in which the poison is administered, or to the *vomited*, or lastly, to the *contents of the stomach*. This poison combines with albumen and gelatin, and it is not liable to be osed or precipitated by these or any other organic substances: it fore, commonly found in solution in the liquid portion, which will more or less acid. As a trial-test we may employ either a solution er sulphate or lime water. 1. A portion of the liquid should be o remove any albumen, and after filtration, a solution of copper should be added to it. If oxalic acid is present in moderate , a greenish-white precipitate will be formed. 2. Lime water may d to a portion of the clear liquid. A white precipitate will be d, insoluble in acetic acid, if oxalic acid is present.


n milk, gruel, coffee, blood, mucus and other viscid liquids, oxalic readily separated by the process of dialysis, as described under ic acid (p. 216). The liquid should be first boiled—the coats of nach (cut up) being included, if necessary. The distilled water n the outside of the tube will receive the acid. This may be con- d by evaporation. Prismatic crystals may thus be procured, and r and lime tests may be applied. Oxalic acid may be completely d from the boiled and filtered organic liquid by the following

To the filtered liquid, acidulated with acetic acid, *lead acetate* be added until there is no further precipitation; and the white ate formed, collected and washed. If any oxalic acid was present iquid, it would exist in this precipitate under the form of lead

To separate oxalic acid from the lead oxalate we diffuse the ate in water, and pass into the liquid, for about half an hour, a of sulphuretted hydrogen gas, taking care that the gas comes in with every portion of the precipitate. Black lead sulphide will be and with it commonly the greater part of the organic matter, may have been mixed with the lead oxalate. Filter, to separate

the lead sulphide: the filtered liquid may be clear and h
Concentrate by evaporation; the sulphuretted hydrogen disso
liquid is thereby expelled, and oxalic acid may be ultimatel
crystallized by slow evaporation in a dial or watch-glass, or
slide, for microscopical observation. If there was no oxa
the precipitate, no crystals w
cured by evaporation. If c
obtained, they must be dissolve
and tested for oxalic acid in t
above directed.

Fig. 7.



Crystals of Calcium Oxalate obtained by dialysis of Coffee containing Oxalic Acid, magnified 350 diameters.

The presence of oxalic aci
ganic liquid may be detected
method. Place a portion of
containing the poison in a b
insert in this a tube secured
containing a solution of calciu
By dialysis or osmosis the oxal
penetrate the membrane, and
inside the mouth of the latte
of crystals of calcium oxalate,
their octahedral form.

Sometimes the chemical evi
depend on *stains* on articles
Oxalic acid discharges the colour of some dyes, and slowly redd
but unless the stuff has been washed, the acid remains in the
may be detected there. It does not corrode or destroy the stuf
as mineral acids. In *Reg.* v. *Morris* (C. C. C. Dec. 1866) it
that the prisoner had attempted to administer a liquid poison
her daughter, a girl aged six years. The liquid was sour in
her lips smart, and caused vomiting. There was dryness of th
inflammation of the lining membrane of the mouth. No
the substance administered could be procured, but a crystallin
oxalic acid was obtained from some stains on the dress of the
woman was convicted.

White (U.S.) published a report of a case of poisoning
acid, in which the symptoms and appearances are contrasted
caused by disease, and compared with those usually assigne
acid. The poison was not detected in the contents of the st
the sheets on which the patient had vomited yielded one to tw
oxalic acid. The patient lived forty hours after vomiting
('Boston Med. and Surg. Jour.' Jan. 27, 1870.)

As oxalic acid is very soluble in alcohol, this liquid may be
employed for separating it from the contents of the stomach
many organic compounds. Large and perfect crystals may b
from the alcoholic solution, and these may be purified and te
methods already described.

In cases of poisoning, the residuary quantity found in the
generally small. In one instance, in which about an ounce and
been taken, and the person died in two hours, the author
thirteen grains. In a case which occurred at Bristol, in 1868
took upwards of three-quarters of an ounce of oxalic acid (3
and died in ten minutes. It is stated that not more than two g
obtained from the coats of the stomach. The vomiting had b
and the greater part of the poison had been thus ejected. It
the woman had vomited into a pail containing calcareous water,
observed that this water acquired a milky white appearance, ow

action of the acid on the salts of calcium. ('Chem. News,' April 24, 1868, p. 205; and 'Pharm. Jour.' May, 1868, p. 543.) In *Reg.* v. *Cochrane* (Liverpool Sum. Ass. 1857), in which it was charged that two children, aged six and four years respectively, had been wilfully poisoned by their mother, it was stated by the medical witness, Edwards, that he found forty-two grains of oxalic acid in the stomach of the elder, and twenty grains in that of the younger child. It was not clearly established when or how this large quantity of poison could have been wilfully administered to the children, and the prisoner was acquitted.

Since the soluble oxalates give the same reactions as oxalic acid itself, to prove the presence of oxalic acid it will be necessary to prove both the presence of an oxalate, and also to determine the amount of free acid present in the solution submitted to analysis, by titration with an alkali. Since, however, the soluble oxalates are themselves highly poisonous, in practical toxicology it is not always necessary to do this in order to prove that a poison has been taken.

Acid Potassium Oxalate, Binoxalate of Potash, or Salt of Sorrel.

Symptoms and Effects.—The poisonous effects of this salt are similar to those of oxalic acid. It is much used for the purpose of bleaching straw and removing ink-stains, being sold also under the name of essential salt of lemons. Its poisonous properties are not generally known, or no doubt it would be frequently substituted for oxalic acid. Out of nine recorded cases of poisoning by this substance, six proved fatal, while in three the patients recovered. In a case of recovery, a young lady, aged 20, swallowed an ounce of the salt dissolved in warm water. She was not seen by any one for an hour and a half: she was then found on the floor, faint and exhausted, having previously vomited considerably. There was great depression, the skin cold and clammy, the pulse feeble, and there was a scalding sensation in the throat and stomach, with continued shivering. Proper medical treatment was adopted, and she recovered in two days, but still suffered from debility and great irritation of the stomach. During the state of depression, it was remarked that the conjunctivæ of the eyes were much injected, and the pupils dilated. There was also great dimness of vision. ('Med. Gaz.' vol. 27, p. 480.) In another case, two hundred and twenty-five grains were taken (about half an ounce). Sodium bicarbonate was given as an antidote, and the patient completely recovered. ('Med. Times and Gaz.' Feb. 12, 1859.) The recovery must have taken place in spite of the antidote, for sodium oxalate is as poisonous as potassium oxalate. For a third case of recovery, see the same journal, Oct. 15, 1859, p. 378.

This salt destroys life almost as rapidly as oxalic acid itself; and in the symptoms which it produces, it closely resembles that poison. In one case, half an ounce killed an adult in so short a time as *eight minutes;* but probably the fatal effects were in this instance accelerated by the debilitated state of the person who took it. In another case, reported by Chevallier, death took place in ten minutes. ('Ann. d'Hyg.' 1850, 1, 162.) In one instance in which it was supplied by mistake for Epsom salts, it caused death in an hour and a half. ('Pharm. Jour.' 1872, p. 760.) In a reported case ('Ed. Month. Jour.' July, 1862, p. 92), death appears to have been caused by this salt as the result of chronic poisoning. A girl was charged with the murder of her father. He began to be ill about Dec. 5th, and he died on Jan. 26th following. He suffered from vomiting, heat and irritation in the mouth and throat, prostration of strength and constant pains in the chest and abdomen. After death,

the appearances were—inflammation of the mucous membrane of the stomach and part of the bowels. They contained a dark-coloured fluid. The mucous membrane of the gullet was destroyed. The coats of the stomach, which were thickened and injected, had a gangrenous appearance. There was no proof that the prisoner had had possession of the poison until Jan. 11th, five weeks after the symptoms had begun in the deceased. The symptoms before and subsequently to this date were similar. This absence of proof of possession led to the acquittal of the prisoner; still it would be difficult to account for the symptoms and appearances on any theory of disease.

Chemical Analysis.—This salt is not very soluble in cold water, but its solution may be readily mistaken for that of oxalic acid. It is not dissolved by alcohol; and this distinguishes it from oxalic acid. 1st, the aqueous solution has an acid reaction; and 2nd, it is precipitated both by silver nitrate and calcium sulphate, like oxalic acid: but with the latter test the precipitation is much more copious. It is further distinguished from oxalic acid, 1, By its crystals, which when slowly produced on a glass slide assume the shape of small rhombic prisms, sometimes grouped in a plumose form; and 2, By heating a portion on platinum-foil. While oxalic acid is entirely volatile, the binoxalate leaves an ash, which, when sufficiently heated, is white and alkaline; it may be proved to contain potassium carbonate by its dissolving with effervescence in diluted nitric acid, and forming potassium nitrate.

Fig. 8.



Crystals of Acid Potassium Oxalate, magnified 30 diameters.

In some instances this poisonous salt has been supplied by mistake for cream of tartar, and has caused death. Cream of tartar, or acid potassium tartrate, leaves a black alkaline residue when heated in close vessels. Its solution is less acid than that of the salt of sorrel. It is not precipitated by silver nitrate or calcium sulphate. The different action of the two salts on writing-ink affords a simple means of identification. The binoxalate immediately discharges the colour of ink when warmed, while the acid tartrate does not possess this property.

Tartaric Acid.

Symptoms and Appearances.—Tartaric acid is not commonly regarded as a poison; but at least one case has occurred, in which there was no doubt that it acted as an irritant and destroyed life. The case referred to was the subject of a trial for manslaughter. (*Reg.* v. *Watkins*, C. C. C., Jan. 1845.) The accused gave to the deceased, a man, aged 24, *one ounce* of tartaric acid instead of aperient salts. The deceased swallowed the whole, dissolved in half a pint of warm water; he immediately exclaimed that he was poisoned; he complained of having a burning sensation in his throat and stomach, as though he had drunk oil of vitriol, and stated that he could compare it to nothing but being all on fire. Soda and magnesia were administered with diluent drinks. Vomiting set in, and continued until death, which took place nine days afterwards. On inspection, nearly the whole of the alimentary canal was found highly inflamed. The accused admitted that he had made a mistake, and tartaric acid was found in the dregs of the cup. The jury acquitted the prisoner. Another case of poisoning by this acid, with a report of the results of analysis, has been published by Devergie. ('Ann.

rg.' 1851, 2, 432.) This case gave rise to a controversy between Orfila Devergie, the points in dispute relating chiefly to the processes for the ction of the acid in the stomach and tissues. ('Ann. d'Hyg.' 1852, 9, 382; and 2, 230.)

Acetic Acid.

This acid has been generally excluded from the class of poisons. mon *Vinegar*, which contains only four or five per cent. of acetic acid, been often taken in large doses without injurious consequences. From experiments performed by Orfila on dogs, and from one case which he rts as having occurred in the human subject, acetic acid, when con- rated, appears to exert an irritant action on the body. ('Ann. d'Hyg.' , 2, 159: also 'Toxicol.' vol. 2, p. 198.) This is not more than we ıt have expected, seeing that the concentrated acid is highly corrosive. ıe case referred to, the deceased, a female, aged 19, was found dying he highway. She suffered from convulsions, complained of pain in the ach, and died in a short time. On inspection, the stomach was found ıer softened nor corroded, but its mucous membrane near the pylorus almost black. The mucous glands were prominent, and the vessels filled with dark coagulated blood.

Vinegar, which may be regarded as an organic mixture containing a l proportion of acetic acid, may be examined by distilling a portion, testing the distilled liquid for the acid. Vinegar, as it exists in com- e, always contains a small quantity of sulphuric acid, and occasionally s of arsenic, lead, and copper. In general it is easily recognized by its r. Pelletan observed in the case of a child, that the abuse of vinegar o a thinning of the mucous membrane of the stomach; and Landerer rked that the milk of a wet-nurse who had been in the habit of taking e quantities of the Vinegar of Roses, became thin, very acid, and ient in casein and oil. The infant which she was suckling gradually ed and died, and the woman herself suffered severely. (Heller's hiv.' 1847, 2 H. S. 185.)

CHAPTER 17.

ONING BY THE ALKALIES: POTASH, SODA, AND THEIR CARBONATES—SYMPTOMS —FATAL EFFECTS OF CARBONATE OF POTASH—APPEARANCES AFTER DEATH— AMMONIA AND ITS CARBONATE (SAL VOLATILE)—CHEMICAL ANALYSIS.

Potash and Soda.

ptoms.—The symptoms produced by caustic potash and soda, and their onates, when taken in large doses, are similar, and one description will e for both. Cases of alkaline poisoning are, however, rare, and have , generally, the result of accident. The most common form in which e poisons are met with, is in the state of pearlash (potassium carbonate arbonate of potash) and soap-lees (carbonate of soda or sodium car- ate). The patient experiences, during the act of swallowing, an acrid stic taste, owing to the alkaline liquid, if sufficiently concentrated, riating the mucous membrane. There is a sensation of burning heat he throat, extending down the gullet to the stomach. Vomiting is not ays observed; but when it does occur, the vomiting matters are some- s mixed with blood of a dark brown colour, and with detached portions

of mucous membrane: this effect depending on the degree of causticity in the liquid swallowed. The surface is cold and clammy: there is purging, with severe pain in the abdomen, resembling colic. The pulse is quick and feeble. In the course of a short time, the lips, tongue, and throat become swollen, soft, and red.

Appearances after death.—In recent cases there are marks of the local action of the poison on the mucous membrane of the mouth, throat, and gullet. This membrane has been found softened, detached, and inflamed in patches of a deep chocolate colour; sometimes almost black. A similar appearance has been met with in the mucous membrane of the larynx and windpipe. The stomach has had its mucous surface eroded in patches, and there has been partial inflammation. In one instance, as a result of the action of soda, the author found it puckered and blackened.

Period of death.—The most rapidly fatal case reported is that of a boy, who died *three hours* after swallowing three ounces of a strong solution of carbonate of potash. In a case which occurred in 1835, a child, aged three years, took a small quantity of concentrated solution of pearlash which had deliquesced, and died in twenty-four hours. Death was caused in this instance by the inflammation induced in the larynx, causing suffocation. In this respect, the caustic alkalies may destroy life rapidly, like the mineral acids; but death may be also a slow result of these poisons. Thus, a lady swallowed, by mistake, one ounce and a half of the common solution of potash of the shops, which contains about five per cent. of caustic alkali. She recovered from the first symptoms of irritation, but died seven weeks afterwards from pure exhaustion, becoming greatly emaciated before her death. The alkali had probably destroyed the lining membrane of the stomach, and had thus impaired digestion.

Carbonates.—Barclay has reported a case of poisoning by potash, which furnishes a good illustration of the after-effects and appearances caused by this poison. A woman, aged 44, was admitted into hospital about six hours and a half after she had swallowed a quantity of American potash, probably a saturated solution of carbonate of potash (American pearlash). She had vomited immediately after taking it. The mouth and throat were much corroded. There was burning pain in the throat and gullet, extending downwards to the stomach; but there was no tenderness on pressure. Two days after her admission, there was a little vomiting. The mucous membrane, so far as it could be seen, was destroyed; there was difficulty of swallowing, and occasionally pain after food had entered the stomach. In about a month, there was frequent vomiting, with pain on pressure, and constipation; when food or medicine was taken, there was much pain in the stomach, and in a short time the food was ejected. As the case progressed, nothing could be retained on the stomach, and shortly before death the patient was supported only by nutritive injections. She died from starvation on July 8th, about two months after taking the alkali. On inspection, the lower part of the gullet was found much contracted, the lining membrane entirely destroyed, and the muscular coat exposed. The external coats were much thickened. The cardiac end of the stomach, where the ulceration ceased, was considerably contracted. At the intestinal end the mucous lining presented a large and dense cicatrix, obstructing all communication with the bowels, except by an orifice no larger than a probe. The intervening portion of the stomach was healthy, as were also the large and small bowels. ('Med. Times and Gaz.' Nov. 26, 1853, p. 554). In Dec. 1867, a case of poisoning by pearlash gave rise to a trial for manslaughter at Manchester (*Reg. v. Boothman*). A solution of this substance had been prepared for washing purposes. The prisoner offered some to a man, who tasted it and imme-


called for water. The deceased took some, and was soon afterwards the yard vomiting and in great pain. This was on May 31st: he lmitted into an hospital, where he remained until Aug. 2nd, suf- all the time, and unable to swallow anything but thin fluids. On ; the hospital he went home and died on Sept. 20th, nearly four ı after swallowing the alkaline liquid. He died from starvation, as t of stricture of the gullet. The quantity taken was unknown, e liquid was sufficiently strong to soften and destroy the mucous ane of the throat.

ila refers to two cases of poisoning by carbonate of potash, in each :h half an ounce of this substance was taken by mistake for aperient The patients, two young men, recovered from the first effects, but :ely died: the one three months, and the other four months, after son had been taken. The secondary fatal effects appear to have ıe to constant purging, great irritability of the stomach leading to nt vomiting, and loss of the functions of this organ from the tion of the lining membrane, with stricture either of the gullet or apertures of the stomach,—either of which causes might prove ; almost any period. A fatal case of stricture, produced by soap- ter the lapse of two years and three months, is reported by n. ('Lancet,' March 2, 1850.) The constant use of the alkalies or r carbonates appears to be productive of insidious mischief: yet the y which may be sometimes taken in divided doses without de- g life is enormous. Tunstall relates the case of a man who, for n years, had been in the habit of taking sodium bicarbonate to dyspepsia. It is stated that for sixteen years he took *two ounces* bicarbonate daily. The man died suddenly, and on examining the h it was found to be greatly distended and extensively diseased itions which were referred by Tunstall to the action of the car-

('Med. Times,' Nov. 30, 1850, p. 564.) The *quantity* of any of lkaline poisons required to destroy life is unknown. The fatal depend rather on the degree of concentration of the liquid, than on olute quantity of alkali present. Forty grains of caustic potash ved fatal.

mical Analysis.—Solutions of CAUSTIC POTASH AND SODA have a y alkaline reaction; they are distinguished from those of their re- ə carbonates by giving brown precipitates with a solution of itrate. The CARBONATES, on the other yield a whitish-yellow precipitate. is known from SODA by the following ers:—1. Its solution, when not too iluted with water, and acidified with hloric acid, is precipitated of a canary- colour by platinic chloride. 2. It is ated in granular white crystals, on the alkaline liquid gradually to ex- a strong solution of tartaric acid, ing a small quantity of alcohol, and ally stirring the mixture. SODA is ecipitated by either of these tests, will serve equally to distinguish the *potash* from those of soda, if we except the acid oxalate and acid of potassium: these, from being but little soluble in water, are not ated. 3. If we neutralize the two alkalies by diluted nitric acid, ystallize the liquid on a slip of glass,—should the alkali be potash, stals will have the form of long slender fluted prisms (p. 222); if

Fig. 9.



Rhombic crystals of Sodium Nitrate, magnified 30 diameters.

soda, of rhombic plates. 4. Potassium and its salts are known by their giving a reddish-violet colour, while sodium and its salts give a bright yellow colour to a colourless gas or spirit flame.

In liquids containing organic matter.—Such liquids are frothy; they possess an alkaline reaction, a peculiar alkaline odour, and are soapy to the feel. The organic liquid may be evaporated to dryness, then heated in a porcelain capsule to char the animal and vegetable matters, and the alkali will be recovered from it in a state of carbonate by digesting the residuary ash in distilled water.

Ammonia. Spirit of Hartshorn.

The *vapour* of strong ammonia is poisonous. It may destroy life by producing violent inflammation of the larynx, or of the lungs and air-passages. It is often injudiciously employed to rouse persons from a fit. A case is on record of an epileptic having died under all the symptoms of croup, two days after the application of strong ammonia in vapour to the nostrils: it was employed to rouse him from a fit. A singular case of recovery from the poisonous effects of this vapour is reported by Sanchard. ('Ann. d'Hyg.' Jan. 1841.) A case of poisoning by the vapour breathed in the manufacture of ice by means of liquefied ammonia is reported (Husemann's 'Jahresber.' 1872; Toxicol. p. 470.) The effects were chiefly manifested in the lungs, and many days elapsed before recovery took place. Two solutions of ammonia are met with in commerce, containing about 10 and 30 per cent. respectively of ammonia.

Symptoms and Appearances.—The strong *solution* of ammonia produces symptoms similar to those described in speaking of potash. The only difference observed is, that the sense of heat and burning pain in the throat, gullet, and stomach, is much greater. Cases of this form of poisoning are rare. Sanchard relates an instance that occurred in France, in which a boy, only six years old, poisoned his younger sister by pouring several teaspoonfuls of a strong solution of ammonia down her throat. In one case a strong dose of the solution killed a man in *four minutes*, by causing suffocation (Christison): and in another case ('Jour. de Pharm.' Oct. 1846, p. 285), from one to two drachms of solution of ammonia, unknowingly administered, caused death. There was violent vomiting, with bloody purging; and, on inspection, blood was found effused in the intestines. There was also a very fluid state of the blood in the body. In another instance, a man walked into a druggist's shop, and asked for a small quantity of ammonia, to take spots out of his clothes. The druggist poured about a teaspoonful and a half into a glass. The man suddenly swallowed it, and fell instantly to the ground. He soon afterwards died, complaining of the most excruciating pain. ('Jour. de Chim. Méd.' 1845, p. 531.) A similar case occurred at Halifax in April, 1857: a man swallowed a large dose of ammonia, and died in a quarter of an hour. In other cases, in spite of a large dose, death has taken place slowly. Potain met with an instance in which a man swallowed upwards of three ounces of the commercial solution of ammonia, and he did not die from the effects until the eleventh day. ('Jour. de Chim. Méd.' 1858, pp. 311 and 474.)

Serious injury to the organs of respiration is sometimes the result of the action of this poison, as in the following case. A gentleman liable to attacks of fainting died in three days after swallowing a quantity of a liquid administered to him by his son. This liquid, which was at the time believed to be sal volatile, was, in fact, a strong solution of ammonia. The deceased complained immediately of a sensation of choking and

rangling in the act of vomiting. Symptoms of difficulty of breathing
in, with other signs of irritation in the throat and stomach. The
ucous membrane of the mouth and throat was corroded and dissolved:
d it was evident that the liquid had caused great local irritation. The
ficulty of breathing was such as to threaten suffocation, and at one time
was thought that an operation must be resorted to. The state of the
ient, however, precluded its performance, and he died on the third day.
inspection, the viscera presented strong marks of corrosion. The
ering of the tongue was softened, and had peeled off; the lining
mbrane of the air-passages was softened and covered with layers of
e membrane, the result of inflammation, and the larger bronchial tubes
re completely obstructed by casts or cylinders of this membrane. The
ng membrane of the gullet was softened, and at the lower part, near
junction with the stomach, the tube was completely dissolved and
troyed. There was an aperture in the stomach in its anterior wall,
ut one inch and a half in diameter: the edges were soft, ragged, and
ckened, presenting an appearance of solution. The contents of the
mach had escaped. On the inside, the vessels were injected with dark-
oured blood, and there were numerous small effusions of blood in various
ts of the mucous membrane. The coats were thinned and softened at
seat of the aperture. The blackened and congested appearance some-
at resembled that which is seen in poisoning by sulphuric or oxalic
d. The mucous matter on the coats of the stomach was feebly *acid*.
poison of any kind was found in the layer of mucus or in the coats.
ere was not in any part a trace of ammonia, the poison which had
ed the mischief. The deceased had lived three days: remedies had
n used, and every trace of ammonia had disappeared. The immediate
se of death was an obstruction of the air-tubes, as a result of inflamma-
, caused by the local irritant action of the poison. It was quite obvious
t a quantity of the liquid had entered the windpipe. The perforation
the stomach had probably taken place shortly before death, or there
ld have been marks of peritonitis. The injury to the stomach and
let would have been sufficient to cause death, even supposing that the
id had not penetrated to the lungs. A man, æt. 40, swallowed an
ce of spirit of hartshorn. He ejected the liquid almost immediately,
complained of an intense burning pain and feeling of suffocation.
e of it, he thought, had reached the stomach. In two hours, his
ntenance was suffused and anxious, the lips were livid, breathing
cult, extremities cold, pulse 100, and the inside of the mouth and
at was raw and fiery-looking. He complained of pain in the situation
he larynx and under the left ear. The larynx was opened to relieve
breathing, but the relief was only temporary. He vomited blood, and
re death suffered from great difficulty of swallowing. He died in
teen days after taking the poison, obviously from the local injury
to the parts about the larynx. ('Ed. Med. Jour.' 1857, vol. 2, p.
) A man, æt. 70, took two mouthfuls of spirits of ammonia. He was
ediately afterwards seized with a sense of suffocation, cough and
iting, and in spite of treatment he died in four hours. The lining
ibrane of the mouth and throat was destroyed. There was a bloody
, smelling of ammonia, in the stomach. At the lower portion, the
g membrane was corroded and the muscular coat changed into a
k pulpy substance. The duodenum was also inflamed. ('Amer. Jour.
. Sci.' Jan. 1870, p. 275.) A man swallowed by mistake for a dose
od-liver oil, a tablespoonful of solution of ammonia. Œdema of the
is followed, and in five hours he died from suffocation. ('Lancet,'
, 1, 467.) In 1871 a man was admitted into Guy's Hospital who had

swallowed about a teaspoonful of, as was supposed, the stronger pharmacopœial solution of ammonia. He died suddenly not long after admission. The lips, tongue, tonsils, uvula, and pharynx were much swollen, red, glazed, with here and there flakes of white epithelium resting upon the mucous membrane. The gullet was intensely reddened throughout, and at its lower end was of a dark purple colour; but this ceased abruptly at the stomach. The epiglottis and adjacent parts were œdematous. The mucous membrane of the windpipe and bronchi was thickened and injected. Both lungs were œdematous and gorged with blood. Both sides of the heart contained dark fluid blood. There was a circular reddened patch on the mucous membrane of the stomach, at the point on which the liquid would have first impinged: and here the wall of the stomach was thinned. ('Guy's Hosp. Rep.,' xvii., 1872, p. 225.) Two deaths from ammonia are reported to have occurred in England and Wales in the year 1880.

Tyerman attended a case which occurred in Nov. 1858, in which a lunatic, æt. 62, swallowed about two fluid ounces of compound camphor liniment, which contains ammonia. The patient immediately complained of great heat in the stomach; vomiting was induced by giving to him warm water. The uvula, throat, and gullet were so intensely inflamed that he lost all power of swallowing; and the efforts to swallow liquids produced violent retching. The symptoms gradually abated, and the man recovered in four days. In this case the quantity of ammonia swallowed was small, amounting to about two and a half drachms, diluted with about six times the quantity of rectified spirit. In 1882, the editor met with a similar case. Gill met with a case of the poisoning of an infant, only four and a half days old, by a small quantity of this liniment. The case occurred in Sept. 1863. He saw the infant about half an hour after the liquid had been taken; it was then screaming in a suppressed manner, as if the act increased the pain: the hands were tightly clenched; the skin was pale and covered with a cold perspiration; the mucous membrane of the lips was blistered, and that of the mouth and tongue was white. A yellowish froth escaped from the mouth and nostrils; the breathing was painful, and the pulse imperceptible. In about two hours the infant appeared better, but at intervals it suddenly started and screamed, as if from sudden pain. In six hours it continued much in the same state, and swallowing was painful. In seventeen hours the skin was moist and cool: it had had a natural motion, and had been in a drowsy state during the night. After twenty-four hours the infant was much weaker; the limbs were cold, and the breathing was feebly performed. It became drowsy, and died thirty-two hours after taking the poison. There was an inquest, but no inspection of the body. A question of importance arose in reference to the case: namely, whether the mother or a child, two years of age, criminally administered the poison to the deceased infant. The mother stated that this child was playing with the bottle of embrocation on the bed, on which her infant was lying. She left the room for a short time, and on her return she gave the infant a teaspoonful of food which she had previously prepared for it. She was sure the infant swallowed part of the food; but as soon as the food was taken, it screamed violently and struggled for its breath, and then she perceived the food to smell strongly of the embrocation. As from the nature of this irritant compound the symptoms could not be delayed, it is clear that the mother either consciously or unconsciously gave the poison to her infant. On the latter supposition, it must have been placed in the food which was on a chair near to the bed by the child of two years, during her absence; but in this case it is remarkable that she did not perceive the odour until after she

had poured the liquid into the mouth of the infant. The quantity swallowed was unknown. Two cases are reported ('Med. Times and Gaz.' May 26, 1855), in which children were poisoned by swallowing a liniment of ammonia and oil. In one, an infant, death occurred speedily, probably from swelling and closure of the air-passages, thus leading to suffocation. In the other case, death took place on the following morning. Considering the pungent taste of ammonia, it is remarkable that an infant could have had the power of swallowing nearly two ounces of strong ammonia liniment. It had been poured down its throat by another child of five years of age. A solution of strong ammonia has been maliciously used for throwing on the person. It must be regarded as a corrosive liquid, capable of producing serious injury. The editor has seen several cases of severe injury resulting from the accidental spilling of a strong solution of ammonia on the person.

Carbonate of Ammonia, or *Ammonium Carbonate*.—The solution of this salt (sal volatile) is probably more active as a poison than is commonly supposed. The following case occurred in 1832. A man, in a fit of passion, swallowed about five fluid-drachms of a solution of sal volatile. In ten minutes, he was seized with stupor and insensibility; but upon the application of stimulant remedies, he recovered. He suffered for some time afterwards, from severe irritation about the throat and gullet. Iliff reported the case of a little boy, aged two years, who swallowed about half an ounce of a strong solution of spirits of hartshorn, and in spite of rather severe symptoms recovered in a few days. ('Lancet,' Dec. 1, 1849.)

In a paper above referred to (p. 234), Barclay relates the case of a girl, æt. 19, who, while in a state of unconsciousness, was made to swallow a quantity of hartshorn. She felt a severe pain in the stomach immediately, and in about an hour afterwards she vomited some blood. This vomiting of blood continued for several days. These symptoms were followed by great irritability of the stomach, and the constant rejection of food. There was obstinate constipation of the bowels, with great emaciation and loss of strength. She died in about three months from the time at which she had swallowed the alkaline poison. On inspection, the gullet was found healthy; the orifice, at its junction with the stomach, was slightly contracted. The intestinal orifice was contracted to the size of a crowquill, and the coats were thickened. On the posterior wall of the stomach there was a dense cicatrix of the size of half-a-crown, and from this point fibrous bands ramified in various directions. The duodenum and other parts of the intestinal canal were healthy. ('Med. Times and Gaz.' Nov. 26, 1853, p. 554.) A case occurred to Procter, in May, 1852, in which a woman gave to her infant, four weeks old, a teaspoonful of hartshorn of the strength of about nine per cent. The child became more and more depressed, and died thirty-six hours after taking the liquid. There was no vomiting or purging, and the mouth and throat presented no excoriation; there was, however, slightly increased redness of the lining membrane. An examination after death was not made.

The alkaline salts of ammonia are not often used by persons who are bent upon suicide or murder, but there is one instance on record in which a man was tried for the murder of a child by administering to it spirits of hartshorn. (*Reg.* v. *Haydon*, Somerset Spring Ass. 1845.)

Chemical analysis.—The three alkalies, potash, soda, and ammonia, are known from the solutions of the *alkaline earths* by the fact that they are not precipitated by a solution of potassium carbonate. They all three give a powerful alkaline reaction with test paper, which, in the case of ammonia, is easily removed by heat. Ammonia is immediately known from potash and soda by its odour and entire volatility. *Ammonium Carbonate* may be known from other salts by its alkaline reaction, its odour, and

its entire volatility as a solid:—from pure ammonia—1, by its effe on being added to an acid; 2, by its yielding an abundant white pr with a solution of calcium chloride; from the carbonates of potass sodium, among other properties,—1, by its giving no precipitate solution of magnesium sulphate; 2, from the rich violet-blue which it forms when added in excess to a solution of copper sulphat its odour and volatility.

CHAPTER 18.

POISONING BY NITRE, POTASSIUM SULPHATE, AND POTASSIUM IODIDE-CHLORIDE—BARIUM CARBONATE.

Potassium Nitrate, Nitrate of Potash, Nitre, Saltpetre, o Prunella.

Symptoms and Appearances.—This well-known salt has on several c destroyed life, but only when taken in large doses. Three deaths f salt are recorded to have taken place in the four years 1863–7.] which is reported by Orfila, a lady swallowed, by mistake for otl an ounce of saltpetre. In a quarter of an hour there was vomi purging, the muscles of the face were convulsed, the pulse was w respiration difficult, and the limbs were cold; and there was a burning heat and severe pain at the pit of the stomach. She diec *hours*. On inspection, the stomach was found highly inflamed, membrane detached in various parts. Near the pylorus, the infla had a gangrenous character. A large quantity of bloody liquid w in the stomach. (i. 283.) In another case, which proved fatal hours, where an ounce and a half of nitre had been taken, a small tion was found in the stomach. (Ib.) Geoghegan met with th ing case:—A man took from an ounce to an ounce and a half of mistake for salts. Severe pain in the abdomen followed, witl vomiting, but no purging so far as could be ascertained. He about *two hours* after taking the salts. On examining the body, mucus was found in the stomach, the lining membrane was of a b red colour, generally inflamed, and in parts detached from the coat None of the poison could be detected in the stomach; but its na clearly established from the analysis of a portion left in the vess had contained the draught. Two men swallowed, each, one ounce by mistake for Glauber's salt. They almost immediately exper sense of coldness in the course of the spine, trembling in the lin violent vomiting and purging. The evacuations were bloody. covered in the course of a few days. (Casper's 'Wochenschrif No. 18.) A case is reported in the same journal, in which one nitre killed a man in thirty-six hours. In another case an old mai lost his life from an overdose of nitre which he had taken as a r The dose amounted to about ten drachms; it caused profuse purg death in about five hours. Death was referred to inflammatio mucous membrane of the stomach and bowels, owing to the irrita of the nitre. A female, æt. 28, swallowed in two doses, taken on t about an ounce of nitre. After the second dose, she was attacl severe burning pain in the stomach, and violent vomiting foll collapse. There was no purging, and the secretion of urine was The girl recovered in a few days. ('Pharm. Jour.' Feb. 1846,

ard met with a case in which a man recovered in four days after ing swallowed two ounces of nitre by mistake for Epsom salts. In ıt five minutes after taking the salt, he felt a burning pain in his ıacb, and this was immediately followed by sickness. Free vomiting excited by mustard; and this probably led to his recovery. ('Prov. L Jour.' Aug. 19, 1846, p. 382.)

There appears to be some uncertainty in the action of this salt, both o the symptoms and the fatal effects on the body. Fuller had a which proved fatal in 1863. A man swallowed an ounce of nitre, ed with water, by mistake for Epsom salts, about nine o'clock in the ning. It produced vomiting, with severe pain, but no purging. There coldness of the surface and lividity of the face. Death took place hree hours. On inspection the mucous membrane of the stomach found highly inflamed, especially towards the middle of the greater ature, where for several inches it resembled scarlet cloth. The pylorus duodenum were of a deep crimson colour. The peritoneal surface was vascular, especially over the stomach, the vessels having a vermilion olour, as if they had been injected. The heart and lungs were healthy; blood was fluid and more florid than natural. The other organs ented no unusual appearance. No analysis was made of the contents ıe stomach, but that the nitre was the cause of death no doubt could ntertained, and a verdict was returned accordingly at the coroner's est.

n 1882, a farm labourer took an ounce of nitre in mistake for Epsom at 7 A.M. When seen at 1.30 P.M., he was suffering from intense pain ıe stomach of a burning character, with hot distressing eructations. pain had come on immediately after taking the salt, with profuse piration. He felt sick, but did not vomit till 11 A.M. Vomiting was free, and the ejected matters were of a coffee-ground colour, and rently contained altered blood. The pulse was 56, and full and slow; ongue moist, white, and tremulous. Micturation was frequent for rst three hours. Later in the day a liquid stool, of tarry appearance, passed, and very offensive in odour. From this time he made a ıal recovery. ('Brit. Med. Jour.' 1882, 1, p. 304.) Two cases are ted of recovery after the administration of two ounces of nitre. it. Med. Jour.' 1877, 2, p. 520; 1882, 1, p. 500.)

nalysis.—For the chemical properties and method of detecting this see p. 222.

ASSIUM SULPHATE, SULPHATE OF POTASH, SAL POLYCHREST, OR SAL DE DUOBUS.

ymptoms and Appearances.—A lady, about a week after her delivery, by the prescription of her medical attendant, about ten drachms of salt in divided doses, as a laxative. After the first dose, she was l with severe pain in the stomach, nausea, vomiting, purging, and ps in the limbs. These symptoms were aggravated after each dose: ied in *two hours*. It was supposed that some poison had been taken istake; but that was not the case, and the question was, whether her ı was or was not caused by potassium sulphate. On an inspection e body, the mucous membrane of the stomach and intestines was pale, ıt in the valvulæ conniventes (folds), in which it was reddened. In tomach was a large quantity of a reddish-coloured liquid, which, on sis, was found to contain only potassium sulphate, and no trace of other common irritant poison. The examiners referred death to sium sulphate taken in an unusually large dose, whereby it had

acted as an irritant poison on a person whose constitution was already much debilitated. ('Ann. d'Hyg.' Avril, 1842.)

The question whether this is to be regarded as an irritant poisonous salt or not, was much debated among members of the profession, in reference to a case which was tried at the Cent. Crim. Court in Oct. 1842. (*Reg.* v. *Haynes.*) The accused had given to the deceased, the night before her death, two ounces of sulphate of potash, dissolved in water; and it was alleged that a fortnight previously to this she had taken, in divided doses, as much as a quarter of a pound of the salt. The woman thought that she was pregnant, but this was disproved by an examination of the body; and it was charged that the prisoner had given her the salt with the intention of causing a miscarriage. After the last dose, she was seized with sickness, and died within a very short time. The stomach was found empty, but highly inflamed; and there was blood effused on the brain. One medical witness referred death to the action of this salt as an irritant poison; the other to apoplexy, as an indirect result of the violent vomiting caused by it. The prisoner was acquitted of the charge of murder, but subsequently found guilty of administering the sulphate with intent to procure abortion. Both of the witnesses admitted that, in small doses, the salt was innocent; but that in the dose of two ounces, it would produce dangerous effects. A case, somewhat similar in its details, was the subject of a trial at the Cent. Crim. Court in Oct. 1856. (*Reg.* v. *Gaylor.*) A married woman, the wife of the prisoner, under the belief that she was pregnant, took a large quantity of this salt, the prisoner having purchased two ounces, and handed it to her. It was taken with the design of procuring abortion, but it caused the death of the woman under symptoms of severe irritation of the stomach and bowels. The deceased was not seen by a medical man while living, but she suffered from severe pain, vomiting, and purging; the vomited matter had a bilious colour. On inspection, the stomach and the upper portion of the small intestines were of a deep purple colour, as if from the action of some irritating substance. The stomach, when opened, showed marks of irritation, and its mucous coat was much congested. In this organ there was a spoonful of a thick, slimy fluid, which contained a quantity of sulphate of potash. The intestines contained twelve ounces of a thick white fluid, highly charged with mucus, and this when analyzed yielded sulphate of potash. There was no doubt that death had been caused by an overdose of this salt.

According to Mowbray ('Med. Gaz.' vol. 33, p. 54), sulphate of potash is much employed in France as a popular abortive. He quotes several instances in which, in large doses, it produced severe symptoms, resembling those of irritant poisoning, and even death. In one case, two drachms acted powerfully; and in another that fell under his own observation, four drachms of the salt administered to a lady after her confinement, had all the effects of an irritant poison. The above cases are the only instances in which it is publicly known to have proved fatal in England; and they show that substances, commonly regarded as innocent, may sometimes give rise to important questions in toxicology.

There is no doubt that the most simple purgative salts may, under certain circumstances, and when given in large doses, destroy life. A case is elsewhere related, in which magnesium sulphate caused death, and gave rise to a criminal charge in this country. ('On Poisons,' 2nd ed. p. 4.) It is said that potassium sulphate has in some cases caused vomiting and other serious symptoms, from its containing as impurity zinc sulphate. This, if present, would be easily discovered by the appropriate tests. A more serious impurity has been detected in it by Bussy, namely arsenate

potash. He found this poison in a sample of sulphate, supplied by rholesale house in Paris. ('Pharm. Jour.' 1872, p. 954.) This impurity ıy be derived from arsenical sulphuric acid used in its manufacture. would be well to test for arsenic any sample of sulphate which has ısed great irritation. (See ARSENIC.) Arsenic may thus find its way o all medicines in which sulphate of potash is used, *e.g.* compound ocynth pill, and compound powder of ipecacuanha.

Other impurities of a poisonous nature have been occasionally found in ı salt. The reader will find a full account of these by Chevallier (Ann. Iyg.' 1872, 2, 137).

Chemical Analysis.—Sulphate of potash is easily identified. It is a dry d salt, soluble in water, forming a neutral solution. This solution, if ficiently concentrated, is precipitated both by tartaric acid and by platinic oride, whereby potassium is indicated; and the presence of sulphuric d is known by the action of a salt of barium (p. 215). *Organic liquids.* This salt being insoluble in alcohol, may have the organic matter re-ved from it by treating the liquid containing it (previously concen-ted) with alcohol:—or the substance containing the salt may be porated to dryness and incinerated, when the undecomposed sulphate y be obtained by lixiviating the calcined residue with distilled water. lphate of potash exists naturally in some animal fluids, but only in ces.

POTASSIUM IODIDE, OR IODIDE OF POTASSIUM.

Symptoms.—This salt is extensively employed in medicine, but it pears to have given rise, in some instances, to alarming symptoms, en when exhibited in small doses; and it is stated that death has ulted from its use. The following cases may serve to illustrate its ged noxious effects. A gentleman was ordered by his physician to e three grains of the iodide in a draught of peppermint-water three nes a day. After the third dose he felt unwell, and an hour after the rth dose he was attacked with a violent shivering fit, followed by head-he, hot skin, intense thirst, quick and full pulse, with vomiting and rging. These symptoms were succeeded by great prostration of strength. spite of treatment, the purging lasted several days. The effects of the dicine in this case were so violent, although only *twelve grains* had been ken, that there is little doubt, if the patient had taken another dose, he uld have died. ('Med. Gaz.' Sept. 3, 1841.) In October, 1841, a case s reported by Erichsen to the University College Medical Society, which alarming symptoms resulted from a dose of only *five grains* of lide of potassium. There was great difficulty of breathing, discharge m the eyes and nostrils, inflamed conjunctivæ, and most of the violent mptoms of catarrh. The iodide was discontinued, and the patient re-vered. Lawrie found that seven grains and a half of the iodide, in three ses, produced in an adult dryness and irritation of the throat, great fficulty in breathing, and other serious symptoms. In another instance, irty grains, in divided doses, caused severe headache and secretion of ars. In two instances, wherein he had prescribed it medicinally in small ses, it was, in his opinion, the cause of death. ('Med. Gaz.' 27, p. 588.) Though the medicinal dose is ten grains or more, these cases show the cessity of caution in the medicinal use of this substance. The effects m small doses may, perhaps, be attributed to idiosyncrasy; still there ms to be good ground for ranking potassium iodide among noxious itant substances. It has caused death in several cases. One drachm d a half of the salt has been taken by a young female without destroying

life, although it produced serious symptoms of irritation. (Devergie, 'Méd. Lég.' ii. 536.) It has been suggested that the occasional adulteration of the iodide with potassium carbonate may account for the discrepant statements respecting its poisonous properties. In one instance, in which the medicinal dose had been carried to several drachms, the iodide was found to contain 75 per cent. of the carbonate. Large doses of the iodide have been given by surgeons in the treatment of syphilis without producing injurious consequences. Payen has prescribed as much as 60 grains a day in divided doses, and Ricord is stated to have carried the dose to 135 grains in a day.

Chemical Analysis.—The iodide may be distinguished by its cubic crystals and by its solution producing a blue colour with starch on the addition of strong nitric acid. The salt gives a violet colour to flame, indicative of potassium, and yields purple vapours of iodine when treated with sulphuric acid and black oxide of maganese.

Potassium Chlorate, or Chlorate of Potash.

Chlorate of potash in large doses is an acute poison. Brouardel records two fatal cases in children ('Jour. de Méd. et de Chir. Pratiques,' Dec. 1881). A solution containing two drachms of the salt was given in divided doses every ten minutes to two children, the administration extending over a period of about three hours. The symptoms were those of gastro-intestinal irritation, blueness of the surface, and collapse. Death took place within a short time.

Salts of Barium.

The soluble salts of barium (baryta salts) have both a local irritant and remote convulsant action. They usually produce great thirst, excessive vomiting and purging, convulsions, dilated pupils, and paralysis. The post-mortem appearances are variable, except that intense inflammation of the lower bowel (rectum) is constantly observed in fatal cases. It is asserted by some that barium salts are similar in their action to digitalis; and that they are cardiac poisons, the ventricles of the heart after death being found rigidly contracted.

Barium Chloride. Symptoms.—A woman, æt. 23, took by mistake for Epsom salts less than a teaspoonful (100 grains) of the chloride. In half an hour there was a feeling of deadly sickness, with sharp burning pains in the stomach and bowels. Vomiting and purging set in violently, the purging being attended with straining. An hour and a half after she had taken the poison the following symptoms were observed. Face pale and anxious, eyes deeply sunk, surface cold, heart's action feeble, pulse scarcely perceptible, tongue natural and warm, loss of muscular power, sensation and intelligence not affected, pupils natural. Fluids taken were instantly rejected with a ropy mucus. There was pain in the stomach, singing in the ears, twitching of the face, and twisting of the legs and arms. In eight hours and a half the symptoms had abated, but in about fourteen hours the purging had returned, and the symptoms were much worse. There was a loss of voluntary muscular power. The breathing was slow and laboured, and indicated effusion in the bronchial tubes, but the woman was sensible. An hour later she was convulsed, and these convulsions continued in paroxysms for two hours, when she died, seventeen hours after taking the poison. During the fits she had several watery evacuations, and consciousness was lost. There was no post-mortem examination. ('Lancet,' 1859, 1, 211.) A case of poisoning


y this salt is reported by Wildberg. The symptoms were those of ritation, combined with an affection of the brain and nervous system. iddiness, convulsions, and paralysis have been remarked among them. ı the case referred to, half an ounce proved fatal in two hours: in nother instance, one ounce taken by mistake for Glauber's salt, de-royed life in *an hour*. In small doses, even, the chloride has been erved to affect the system powerfully. Orfila found that barium loride was absorbed: he detected it in the liver, spleen, and kidneys animals poisoned by it. ('Ann. d'Hyg.' 1842, 2, 217.) A fatal case poisoning by *barium nitrate*, taken in mistake for sulphur, is reported. Pharm. Jour.' 1869, p. 181.) Another fatal case is recorded in the same rnal for June, 1872, p. 1021. The salts of barium are used for sizing tton warps. A man employed in this work swallowed a portion about e size of a bean, thinking he was taking Epsom salts. He died in about urteen hours. The symptoms were at first those of irritant poisoning, ıt in the latter stage paralysis took place. The medical witness stated at he had found twelve grains of this salt sufficient to kill a dog.

Barium Carbonate is said to have destroyed life in two cases, in each which only one drachm was taken; but the following case shows at this compound is not so poisonous as the chloride. A young woman allowed half a teacupful of the powdered carbonate, mixed with water, a time when she had been fasting twenty-four hours. There was no rticular taste. In two hours she experienced dimness of sight, double ision, singing in the ears, pain in the head, and throbbing in the temples, ith a sensation of distension and weight at the pit of the stomach. here was also palpitation of the heart. After a time she complained of ain in the legs and knees and cramps in the calves. She vomited twice fluid like chalk and water. The skin was hot and dry, the pulse equent, full, and hard. These symptoms gradually abated, and she covered, although the pain in the head and stomach continued for a ng time. ('Med. Gaz.' vol. 14, p. 448.) The carbonate is used as a oison for rats and mice.

A female, æt. 28, finding herself pregnant, took an unknown quantity of rium carbonate with suicidal intent. About 6 P.M. she vomited, and ad severe pain in the stomach. She slept well, however, without further omiting. Next morning after breakfast, at 7 A.M. vomiting was repeated; evertheless, she walked to her situation about three miles distant, where e arrived about 9 a.m. She then looked pale and anxious, and com-lained of severe abdominal pain. She went to the privy repeatedly, either n account of diarrhœa or tenesmus. Nevertheless she attended to her uties as a domestic servant, but the vomiting and desire to go to stool ersisted. At 2 P.M. she went to bed. At 4 P.M. she was found cold, ale, restless, and weak. There was no vomiting. At 8 P.M. she had lternate flushings and rigors. Speech was a mere indistinct whisper. wallowing was difficult, and respiration laboured. At 3 A.M. she was istressed, the breathing was short; she was perfectly conscious. She as found dead at 4 A.M., thirty-four hours after the commencement of mptoms. The exact time at which the poison was taken was not scertained. At the post-mortem examination, made fifty-six hours after eath, the stomach was found much ecchymosed from the fundus to le lesser curvature. The ecchymosis was in large patches over the ndus, in smaller patches towards the middle, and in still smaller patches the pyloric portion of the organ. The intervening membrane was overed with a little mucus. Particles of the poison were found im-edded in the mucous *membrane*. The peritoneal aspect of the stomach as *of a pale red tint. There* were numerous ecchymosed patches in the

duodenum. Two grains of barium carbonate were extracted from the stomach. The quantity taken could not be ascertained. Traces of barium were also detected in the liver. ('Archiv. der Pharm.' [3] iv. 1874, p. 426.)

Fig. 10.



Crystals of Barium Chloride, magnified 30 diameters.

Analysis.—*Barium chloride* crystallises in thin plates: it is soluble in water. 1. The solution yields an insoluble white precipitate with sulphuric acid or an alkaline sulphate. This precipitate is insoluble in nitric acid. 2. The powdered salt, burnt on platinum-wire in a smokeless flame, imparts to it a greenish-yellow colour. 3. Chlorine may be detected by a solution of silver nitrate. (See p. 224.)

Barium carbonate is a white insoluble powder. It is entirely dissolved with effervescence (carbonic acid) by diluted hydrochloric acid. This solution on evaporation yields crystalline plates of barium chloride, which may be detected by the processes above mentioned.

CHAPTER 19.

PHOSPHORUS—SYMPTOMS AND APPEARANCES—CHRONIC POISONING BY THE VAPOUR—FATAL DOSE—CHEMICAL ANALYSIS—PHOSPHORUS-PASTE—RED OR ALLOTROPIC PHOSPHORUS—IODINE.

Poisoning with phosphorus is not very infrequent in this country; but on the Continent of Europe this poison is often selected for the purposes of suicide or murder. In England, in the year 1880, there were thirteen deaths from phosphorus out of 1620 cases of poisoning. In France, within a period of six years, there were 103 cases of poisoning with phosphorus which gave rise to medico-legal inquiry. The tips of lucifer matches and rat-pastes are most commonly used for the purpose of this poisoning.

Phosphorus is not often used in this country in attempts at murder. The smell and taste, as well as its luminosity, commonly reveal its presence. At the Norwich Autumn Assizes, 1871 (*Reg.* v. *Fisher*), a girl of eighteen was convicted of an attempt to poison a family. She put a vermin compound of phosphorus into a teapot containing tea. When hot water was poured on it, the smell at once led to suspicion. Phosphorus was found in it, taken from a pot carelessly left about the house. The girl was convicted. Casper described a case in which the luminous appearance of the poisoned food led to a suspicion of poisoning with phosphorus, and this was subsequently proved. A woman put a preparation of phosphorus into some soup, and gave it to her husband. He ate it in a dark room in the presence of some friends, and they noticed that the liquid as he stirred it was luminous. ('Vierteljahrsschr. f. Gerichtl. Med.' July, 1864.) In this way a person may be warned and a life saved (see 'Ann. d'Hyg. 1870, 2, 203).

The ordinary, yellow, or soluble phosphorus is alone poisonous: the red, amorphous, or insoluble variety exercises no sensible physiological effects. That the red variety does not act as a poison on the human body, appears to be established by the facts of a case reported in the 'Ed. Month. Jour.' Oct. 1860. A woman, æt. 26, swallowed the composition scraped from a number of lucifer-matches: it turned out that these were made with red

. She suffered no inconvenience. She procured other matches hosphorus, took a decoction of them in coffee, and died from

ɔrus is usually taken in this country for suicidal purposes in the -paste, a compound of yellow phosphorus, fat, sugar, and flour, ith Prussian blue. The editor has found a sixpenny pot of o weigh 157 grains, and to contain eight grains of phosphorus. and Germany the heads of matches are commonly used for the se; and 80 or 100 grains are a fatal dose, containing about a osphorus.

ns.—Phosphorus acts as an irritant; and the symptoms of irrita- anifest themselves in a few minutes after the ingestion of the general, however, there is a longer interval of some hours. In the e the patient experiences a disagreeable taste, resembling that of h is peculiar to this poison. An alliaceous or garlic-like odour eived in the breath. There is pain and oppression in the region ach, malaise, eructation of phosphoric vapours, having a garlicky these may be luminous in the dark. Vomiting is sometimes d violent; in other cases quiet and at longer intervals. The distended. Purging is not common. The vomited matters are red, or yellow and bilious, and may be luminous. There is st. The symptoms may increase in severity, ending in death se in the course of a few hours—four to eight in the worst cases. eless, in the majority of cases the progress to a fatal termination, ess sure, is slower and more insidious. The irritant symptoms neasure subside, and though the pulse is feeble, and there is a unt of malaise, the patient may to a casual observer appear to t a normal state of health. But after the lapse of three or four ice sets in and rapidly increases, there is great prostration of ie abdomen becomes distended, the liver is observed to be rged, and vomiting of altered blood may come on with intense skin is cold, the pulse feeble, rapid, and perhaps imperceptible t; the urine is scanty and high-coloured, and contains casts idneys. The fæces, previously suppressed, are now more nd contain blood. Coma sets in, with jactitation of the limbs, r twitchings; and the patient succumbs generally about the ter the administration of the poison.

an, æt. 26, swallowed a decoction of lucifer-matches in coffee. an emetic was given to her, and she vomited half a pint of clear , having the smell of phosphorus, and containing particles of ng matter (Prussian blue) derived from the matches. She had the stomach, and no purging. In four days she appeared to red; but about this time there was bleeding from the nose; she ed, and blood appeared in the matter vomited. Febrile symptoms purpura, and she died in about a week after taking the poison. h. Jour.' Oct. 1860.) A girl swallowed a quantity of phos- e. When seen soon afterwards by Parsons, her lips as well her dress were smeared with this substance, and there was a r of phosphorus in her breath. Her countenance was tranquil: gular: there was no sickness or nausea, and she complained of slight thirst. Her symptoms were so slight, that they excited i that the girl had swallowed the poison. She passed a restless the next day she complained of heat in the mouth and throat, ight sensation of nausea and retching. There was no pain or n the region of the stomach, the pulse was regular but weak. rd day she dressed herself and was able to walk about the

ward: she left the hospital and went home, walking a mile. She had her tea as usual at night, and went to bed. On the following day she complained of pain in her bowels, with sickness and purging. These symptoms became worse. On the sixth day there was pain in the bowels, which were tender on pressure and slightly tympanitic. The pulse was intermittent, and the girl was fast sinking. She died, after having survived the effects of the poison nearly a week, and no well-marked symptoms having set in until *the fifth day*. An inspection of the body was not permitted, and the only fact observed after death was a tendency to rapid putrefaction. The whole of the body became speedily livid, and the finger-nails were blue—a condition noticed by a witness to have existed before death.

It will be perceived that, in reference to the delay in the appearance of symptoms, their slightness taken as a whole, and the time at which death occurred, this case is similar to the one previously related. If it were not for the peculiar character of the circumstantial evidence, these cases might easily throw a practitioner off his guard in forming an opinion. The odour of the breath, and the appearance of phosphorus smeared over the dress, first attracted notice. Other witnesses deposed that whatever the deceased touched with her hand seemed to take fire, and that when she drank water to allay her thirst, a kind of smoke issued from her mouth. Her hands and dress were luminous in the dark.

A female, æt. 20, took several doses of phosphorus-paste; the first on the evening of Jan. 11th, 1877. The dose was repeated thrice on the 12th. The whole quantity of paste taken was of the size of a large cob-nut, containing about two grains of phosphorus. On the morning of the 13th she retched, and at midday her appetite failed at dinner; and in the evening she vomited. At 10 p.m. on the 14th she was first seen by Tyson, about seventy-two hours after the first and forty-eight hours after the last dose was taken. She had then an excited aspect, and her breath had a phosphoric odour. There was tenderness over the region of the stomach. On the 15th there was slight yellowness of the conjunctivæ of the eyes, slight pain over the stomach, and nausea, but no vomiting. The urine was high-coloured and turbid. On the 16th there was decided jaundice, great thirst, and prostration. There was still a slight garlicky odour of the breath; but the urine and fæces showed no luminosity. There was no obvious enlargement of either the liver or spleen. On the 17th the liver was enlarged; only a very little dark-coloured urine was passed; and there was much epigastric pain and tenderness. In the evening there was slight delirium. From this time she gradually sank, and died on the 18th, nearly a week after the administration of the first dose of the poison. On post-mortem examination the liver was found to be of the usual size; but it had undergone extensive fatty degeneration, as had the heart also. There were no marked appearances in the stomach, which was almost filled with a blackish syrupy liquid. ('Guy's Hosp. Rep.' xxii. 1877, p. 452.)

In 1876, a woman, and her daughter æt. 5, each drank some phosphorus-paste in warm water. The woman was seen four days later apparently in her usual health. Subsequently she sickened, became jaundiced, and died a week after the poison was swallowed. The child exhibited no symptoms till 7 a.m. on the day after taking the poison. She then vomited some slimy material, and her breath had a garlicky odour. In a few hours she was in a state of semi-collapse. Next day she became drowsy, then thirsty, restless, and vomited constantly. There was no jaundice. She died fifty-nine hours after the administration of the poison. On post-mortem examination the heart was found to have undergone fatty degeneration, and it, and the aorta, exhibited ecchymosed patches. The stomach was considerably injected, and its surface was thickly coated with tenacious mucus.

small intestine was much congested at its commencement, and to a less ee lower down. The liver weighed 26 ounces, was yellow, anæmic, showed extreme fatty degeneration, except in isolated patches. In er of these cases could the dose of phosphorus be ascertained. ('Guy's . Rep.' xxii. 1877, p. 449.)

'hosphorus-vapour. Chronic poisoning.—Chronic poisoning by phos- us is accompanied by nauseous eructations, frequent vomiting, a sense at in the stomach, purging, straining, pains in the joints, wasting, c fever, and disease of the stomach, under which the patient slowly . Some interest is attached to the chronic form of poisoning by phorus from the researches of Strohl and others, on the effects of the r upon persons engaged in the manufacture of phosphorus- or lucifer- hes. It has been remarked that such persons have suffered from sis of the jaw, carious teeth, and abscesses. There has been also great tion of the respiratory organs, and bronchitis has frequently shown among them. These effects have been attributed to the respiration e vapours of phosphorus, which are supposed, in becoming acidified, to hemically upon the exposed portions of the teeth. (See 'On Poisons,' dit. p. 345.)

ases of chronic phosphorus poisoning are now of extreme rarity, owing e precautions adopted among phosphorus workers to prevent the intro- ion of the poison into the system.

ppearances.—Among the appearances produced by this poison are s of irritation, inflammation, and ulceration in the stomach and intes- . The stomach has been found much contracted, and its mucous brane inflamed, occasionally softened and presenting purple or violet- red spots. Inflammation of the stomach and bowels may be a result e action of phosphorus. A man, æt. 50, took a quantity of phosphorus- used for destroying vermin. He was seen in his usual health at 12 ck at noon, and was found dead in a field the following morning. On ction, it was observed that there was great muscular rigidity. The branes of the brain were congested, and there was serous effusion een them. The substance of the brain was also congested. The heart flaccid and nearly empty. The mucous membrane of the stomach, t, and small intestines was very red, and there were patches in which membrane was destroyed. On opening the stomach a white vapour ped, accompanied by a strong smell of phosphorus. This organ con- d a tablespoonful of a viscid greenish matter, from which particles hosphorus with some Prussian blue (used as a colouring for the n), subsided on standing. ('Lancet,' June 13, 1857, p. 600. See a case by Kessler, Horn's 'Vierteljahrsschr.' 1866, 1, 271.) In a case ained by Herapath, he found, besides inflammation of the stomach, the ous membrane raised in small bladders or vesications. This was ably a change produced by putrefaction, as the body was not examined l twenty-three days after death. Such an appearance is frequently in the inspections of putrefied bodies, and has not been observed in s of recent poisoning by phosphorus. Schuchardt describes, among ppearances, fluidity of the blood, which is of a dark colour, and does become red on exposure to the air. The most remarkable appearance, monly met with, is a fatty change in the liver and other soft organs. ymoses are often found beneath the skin and on the surface of various ns.

n the case of the female described at p. 247, who died after the lapse week, there was no inflammation, ulceration, or softening of the mouth, t, stomach, or small intestines. There was a red patch in the cæcum, another in the colon (the large intestines). The contents of the stomach

and intestines had a coffee-ground colour, like the liquid found in hæmatemesis (vomiting of blood). The brain was slightly congested. There were bloody effusions in the chest and abdomen, and an apoplectic condition of the soft organs. The vomited matters, when shaken in the dark, were luminous, and phosphorus was separated from them by carbon disulphide. The viscera, and even the flesh of animals recently poisoned by phosphorus, have the odour of garlic, and appear luminous in the dark. (Galtier, 'Toxicologie,' vol. 1, p. 184.) In the case of a woman who died while taking phosphorus medicinally, it was remarked that the whole of the viscera of the body were luminous in the dark; indication of the extensive diffusion of the poison by absorption. (Casper's 'Wochenschr.' Feb. 21 and 28, 1846, pp. 115, 135.) For a further account of the appearances, see 'Chemist,' Jan. 1856, p. 244. In one case which the author examined in 1867, that of a girl, æt. 13, who died on the sixth day after taking phosphorus-paste beaten up with egg, there were the usual symptoms, with severe paroxysms of vomiting and pain. The matters first vomited were observed to be luminous in the dark. There were numerous ecchymosed patches in the cellular tissue of the skin of the abdomen over the rectus muscle; these were also seen on the chest and on the diaphragm. The stomach contained a dark-coloured thick fluid like altered blood; the coats were not inflamed; the surface of the inner coat was covered with a brownish-coloured mucus which had no odour of phosphorus. At the greater curvature the surface was dotted over with numerous small dark particles, consisting of coagula of altered blood adhering to the membrane, but easily removed from it. They had the appearance of effused coagula of blood in petechial spots. The contents of the stomach owed their colour to these little masses of blood being diffused through them. The duodenum contained a similar liquid. The intestines presented no abnormal appearance. The liver was in an advanced state of fatty degeneration. This condition of the liver has occurred so frequently in cases of phosphorus poisoning, that it may now be regarded as one of the characteristic appearances. ('Guy's Hosp. Rep.' 1863, p. 242.) This fatty degeneration in poisoning with phosphorus is met with not only in the liver, but in the heart, stomach, kidneys, and muscular tissues generally.

In a case recorded by Habershon ('Med. Chir. Trans.' 1867, vol. 50), in which a woman died on the 5th day, the symptoms and appearances were similar to those above described. The phosphorus was taken in the form of paste, and, as was supposed, in a dose of from three to four grains. There was much ecchymosis in patches in and about the cellular tissue of the abdomen and chest. There was fatty degeneration of the liver and kidneys. The stomach contained a large quantity of fluid like soot and water, and was covered with a tenacious bloody mucus. There was some congestion of the mucous membrane, and there was much redness with ecchymosis in the small intestines. The fatty degeneration induced by phosphorus is usually most marked in the liver, though it may extend to the kidneys, the heart, the glands of the stomach, to the muscular tissue generally, and to the arterioles and capillaries. The editor has seen decided enlargement of the liver produced within forty-eight hours of the time at which the poison was administered. The liver is usually enlarged, doughy, anæmic, and of a uniform yellow or yellowish-white colour. The acini are indistinct. Wagner describes an interlobular hypertrophy of the connective tissue. The hepatic cells are loaded with fat. The heart and muscles generally may be soft, yellow, and of defective tenacity. In place of the transverse striæ, innumerable fat globules and granules of fat are seen by the microscope. The glandular epithelial cells of the gastric follicles are filled with fat globules. The cortex of the kidneys is likewise filled with

bules. (For further information on this subject, see 'Die acute or-Vergiftung von Munk und Leyden,' Berlin, 1865. Horn's ljahrsschr.' 1866, 1, 271, and Wiggers and Husemann's 'Jahresbe-872, p. 472.)

al dose.—That phosphorus is a powerful poison, is proved by two noted by Christison. In one, death was caused by a grain and in twelve days; in the other, by two grains in about eight days. two grains is a fatal dose. It has been supposed to operate as a only by becoming converted into phosphorous acid; but although version takes place, it is probable that phosphorus passes directly blood, since the urine voided during life has been observed to be us: hence it is itself probably a blood-poison. Organic compounds ing phosphorus (phosphines) are found in the urine in case of phos- poisoning. The production of phosphorous acid, by its oxidation, count for the erosions met with in the stomach and bowels. An ary took by way of experiment one grain; on the next day two and on the third day three grains of phosphorus, mixed with sugar. then seized with inflammation of the stomach and bowels, and spite of every attempt to save him. (Casper's 'Wochenschrift,' . 117.) Chevallier refers to a case in which a dose of 2·3 grains fatal, and two other cases in each of which a dose of 4·6 grains ed life. The same writer quotes, on the authority of Löbel, the a lunatic who died from a dose of one-eighth of a grain. ('Ann. 1857, 1, 422.) This is the smallest fatal dose for an adult which hor has met with. A woman, æt. 52, took in divided doses, in ys, about six centigrammes, or less than *one grain*, of phosphorus d. The largest dose taken at once, *i.e.* on the fourth day, is stated been three centigrammes, or nearly half a grain. Symptoms of pain itation appeared, and the patient died in three days. The gullet, , and small intestines were found much inflamed. ('Toxicologie,' . 87.) When the phosphorus is dissolved in any liquid, or when ely divided, as in phosphorus-paste or in lucifer-matches, its action more powerful, as it is in a state well fitted for absorption. has recorded a case in which an infant, seven weeks old, was ed in four hours from swallowing the heads of six or seven s, containing about one-eighth of a grain of phosphorus ('Vier- schr. f. Gerichtl. Med.' N. F. IV. p. 271). Sonnenschein refers to of an infant of five weeks which died from the effects of a single head, containing possibly not more than one-hundredth of a grain poison. In 1882 a man, æt. 32, was admitted into Guy's Hospital, d taken half a sixpenny pot of phosphorus-paste in whiskey M. He had vomited before his admission at 5.30 P.M. An was administered on admission, which acted immediately. The mitted white fumes, and smelt strongly of phosphorus. He was ld, depressed, and showed signs of alcoholism. His breath had a lliaceous odour. There was severe epigastric pain, with a burning n in the throat and gullet. The emetic was repeated; and he l at intervals till 2 A.M. The last vomit had no phosphoric odour. oses of magnesium carbonate were given in mucilage and milk. He eved of the pain in the epigastrium, though there was some tender- pressure. Twenty-four hours after the administration of the he began to take oil of turpentine, beginning with 15-minim and this was increased subsequently to 30 minims. On the ay the liver began to enlarge, and on the fourth day there was jaundice. The liver continued to increase in size till the sixth day, began to decrease. He suffered from headache and drowsiness.

When the liver began to decrease in size, the oil of turpentine was discontinued. The patient made a good recovery. At one time the liver dulness extended to the upper border of the fourth rib on both sides, extending to the left beyond a vertical line from the left nipple; and downwards it reached nearly the navel. The dose taken was probably four grains.

Period at which death takes place.—This has varied greatly, in the cases hitherto observed, from a few hours to a week. In a case related by Orfila death took place in four hours. In another also related by him death occurred only after seventeen days. Habershon quotes a case which is said to have proved fatal in half an hour. ('Med. Chir. Trans.' 1867, vol. 50.) This is the shortest period recorded. In general, several days elapse before a fatal result occurs, and during this time the patient undergoes much suffering. This was observed in a young woman who swallowed a quantity of phosphorus-paste intended for poisoning rats. She did not die until the fifth day. This is a common period. ('Jour. de Chim. Méd.' 1845, p. 580.) In two cases of acute poisoning with phosphorus communicated by Moore, one proved fatal in seventy-two, and the other in eighty-eight hours. The symptoms and appearances were similar to those already described. Fatty degeneration of the liver and other organs was especially marked. ('Med. Press,' Nov. 15, 1865, p. 434.) In a case which occurred to Anderson, a child, aged one year and eight months, had sucked the heads off about twenty phosphorus matches before it was detected. No symptoms appeared until the second day, when the child was drowsy and slept for twenty hours. Castor oil and oil of turpentine were given. On the fourth day it vomited, the skin was hot, tongue dry, there was great thirst, with a quick pulse and cold extremities. On the sixth day there was much vomiting of a matter like coffee-grounds (altered blood). There was great pain of the stomach—the child became unconscious and gradually sank, dying on the seventh day after taking the poison. There was no purging, but the motions were passed involuntarily, and contained coagulated blood. An alliaceous odour was perceived in the breath during the progress of the case, and the body had a yellowish (icteric) tint. On inspection there was marked general ecchymosis. The liver was enlarged, of a yellowish colour, undergoing fatty degeneration. The lining membrane of the stomach was injected, and it contained a dark bloody fluid. There was no odour of phosphorus, and the contents were not luminous in the dark. Phosphorus could not be detected by Mitscherlich's process. ('Lancet,' 1871, II. 189.)

Chemical analysis.—Yellow phosphorus is a solid of waxy consistency, having a peculiar odour and taste resembling garlic. It is the odour and taste which prevent it from being criminally employed as a poison, and render it easy of detection in articles of food. It evolves a white vapour in daylight, and a faint blueish luminosity in the dark. It melts and takes fire at a temperature of 112° F., burning with a bright yellow flame, and producing dense white acid vapours by combustion. It is not soluble in water, but water in which it has been preserved or washed, acquires poisonous properties by reason of the phosphorous acid formed. ('Ann. d'Hyg.' 1857, 1, 423.) It is dissolved by alcohol, ether, chloroform, and the oils, but especially by disulphide of carbon.

Organic liquids.—The smell which phosphorus imparts to organic substances is characteristic. If the smell is not perceptible, or if concealed by other odours, the liquid supposed to contain the phosphorus may be heated in a flask in the dark, when if phosphorus is present a garlicy odour will be perceived, and the vapours may appear feebly luminous as they are condensed in the air. When phosphorus has been taken in a solid

, the particles may be separated as a sediment, by washing the contents e stomach in water. These may be melted under water into one mass, r by plunging the tube containing them into hot water, or by pouring rater upon them in a conical glass. If a portion of the organic liquid aporated to dryness in the dark, the particles of phosphorus will be y recognized by their luminosity, as well as by their combustion when urface on which the material is spread is further heated. Phosphorus be separated from many organic matters by digestion with disulphide arbon. It is thus procured from flour and phosphorus-paste, or from esidue of the contents of the stomach after washing and decantation. he spontaneous evaporation of the sulphide, decanted from the organic d or solid, the phosphorus may be procured in small globules or s. These are ignited when touched with a hot wire. A portion of olution poured upon thin paper, ignites spontaneously when dry, and s with the well-known flame. The vapours of phosphorus blacken r moistened with a solution of silver nitrate.

f the phosphorus is in a state of solution, or is in too small quantity o dissolved out of the material by disulphide of carbon, its presence be indicated by distilling the liquid containing it in the dark—the ig point being raised by the addition of sulphuric acid. The vapour ars luminous as it is condensed in a glass condensing-tube. So delicate is process of distillation, which was first suggested by Mitscherlich, in one experiment with the head of a single lucifer-match the lumi- y appeared for half an hour in the condensing-tube. Absolute dark- is required for the success of this experiment.

f the person has survived several days, it is not likely that any free phorus will be found in the stomach or its contents. None was found e contents of the stomach or in the fatty liver of the girl who died on ixth day (p. 247), but the distillation-process succeeded with the m top of a pot which had held the phosphorus-paste, although this mpty and had been thrown into a tub of water. In Habershon's of death on the fifth day (p. 250), none was found by the editor in the ach or contents. The phosphorus in these cases is oxidized rapidly, hus, like other poisons, it may disappear from the body. If a piece ter-paper imbued with a solution of silver nitrate be exposed to the ars or gases evolved from the suspected articles, and is not darkened ackened, it may be concluded that no evidence of the presence of mbined phosphorus will be obtained by other means. Under these mstances the phosphorus may, according to some authorities, be still vered as phosphoric acid. Mialhe has given an elaborate report case in which the symptoms and appearances were those of phos- us poisoning, the girl dying on the fifth day. Mitscherlich's process l to show any free phosphorus. Eight weeks afterwards portions of iscera were examined by Tardieu and Roussin. They found in the tines and on the liver groups of small crystals of ammonio-phos- e of magnesium, and in the fluid contents an acid liquid having the erties of phosphoric acid. ('Ann. d'Hyg. 1869, 1, 134.) These als, it may be observed, are frequently found as a result of decom- ion in the stomach or the liver, kidneys, and other organs, without ence to poisoning by phosphorus. As the phosphates are found in secretions, which are generally acid, their presence does not prove ning by phosphorus, unless the symptoms, appearances, and circum- ial evidence are so strong that chemical evidence is scarcely necessary. n one case Herapath failed to detect any trace of phosphorus in a on the twenty-third day after death.

hosphorus readily undergoes oxidation in the body, and is thus con-

verted into phosphorous or phosphoric acid. Blondlot suggested a proc for its detection when this conversion into phosphoric acid has tak place. It depends on a peculiar green colour which the lower oxides phosphorus give to the flame of nascent hydrogen when burnt. ('Jo de Chim.' 1862, p. 528; also 1863, p. 581.) Herapath employed t method of detecting phosphorus thus changed in the body, in a medi legal case. Barrett has shown that the flame of pure hydrogen is rende of a vivid green by an infinitesimal trace of phosphorus ('Nature,' 18 p. 483), but as phosphates are constituents of most of the solids and flu of the body, this mode of testing would hardly be applicable to medi legal purposes. It requires for medico-legal application materials absolute purity for procuring hydrogen, as well as a pure atmosphe and perfect darkness.

When the phosphorus has been scraped from the tops of matches may be oxidized and lost; as it is usually coloured with vermilion, Prussi blue, or some other colouring matter, these substances may be fou in the washed sediment of the contents of the stomach. On the m discovery of free phosphorus in the body, these colouring matters, present, serve to indicate the form in which the poison has been taken administered. In a case which occurred to Tardieu and Roussin sulph was found as well as phosphorus. ('Ann. d'Hyg.' 1868, 1, p. 117.) T proportion of phosphorus in matches varies. The dry composition m contain as much as one-fourth of its weight. Phosphorus-paste is said contain one-eightieth of its weight of this substance. ('Ann. d'Hyg.' 18 2, 396.) The editor has found it to contain 5¾ per cent. of phosphorus.

Red or Allotropic Phosphorus.—The remarkable substance, known und the name of allotropic phosphorus, is not possessed of poisonous properti This fact, long since announced by Liebig ('Letters on Chemistry,' 18 has been confirmed by experiments at the Veterinary College at Alfo ('Ann. d'Hyg.' 1857, 1, 432.) Common phosphorus is poisonous i doses varying from one to three grains, while allotropic phosphorus h been given to animals in doses of thirty grains without causing sympto of poisoning. This kind of phosphorus, by reason of its being general in a fine powder, is in a state more favourable for acting as a poison tha common phosphorus; and yet, owing probably to its insolubility, it is inn Bussy in 1850, and De Vrij in 1851, proved that a dog might take wi impunity thirty grains.

Analysis.—Red phosphorus is insoluble in all liquids, and by its insol bility in disulphide of carbon it is distinguished and separated from yello phosphorus. It has no odour or taste, and is not luminous in the dar unless it contains common phosphorus. In any analysis for phosphor we must take care to exclude it by employing disulphide of carbon as solvent for the common or poisonous form of phosphorus. The read will find a full account of the comparative effects of the common a allotropic phosphorus by Chevallier in 'Ann. d'Hyg.' 1856, 1, 374; 18 2, 370; and Casper's 'Vierteljahrsschr.' 1860, 2, 18.

Iodine.

Symptoms.—From experiments on animals, as well as from obse vation of its effects on man, iodine has a strong local action as an irrita on the stomach and bowels. In large doses, it occasions a burning he in the throat, severe pain in the abdomen, with vomiting and purging; th vomited matters having the peculiar odour of iodine, and being of yellow colour, except when any farinaceous food has been taken, in whi case they are blue, or even black. The fæcal matters may also conta

› iodine if the poison has been taken in the solid state. Besides these ıptoms, there is great thirst, with anxiety, headache, giddiness, trembling l convulsive movements of the limbs, and fainting; these last symptoms icating that the poison has become absorbed. When taken for some e in small doses, it gives rise to salivation, vomiting, purging, pain he stomach, and cramps; the pulse becomes small and frequent; there general wasting of the body; and it has been observed that, in this n of chronic poisoning, certain glands are liable to become affected and inished by absorption—the breasts in the female, and the testicles in male. Iodine produces these secondary effects (iodism), whether it is en internally or applied externally. A woman swallowed by mistake drachm of iodine dissolved in an ounce of alcohol. When seen soon rwards, she complained of a violent pain in the throat or stomach, owed by retching and slight vomiting; the pulse was rapid and full, eyes prominent and suffused. Vomiting, promoted by diluents, brought relief to the symptoms. She became much depressed, and died on the owing day. There was no examination of the body. ('Prov. Jour.' ne 30, 1847, p. 356.) For a case of recovery after half a drachm had n taken, see 'Med. Times and Gaz.' 1861, II. p. 669.

Iodine is rarely used as a poison. In 1864 an attempt was made a woman to poison a fellow-servant by mixing tincture of iodine with d in a plate. The remarkable discoloration of the farinaceous food ich it prodnced, led to suspicion, and prevented any ill effects from lowing. Iodine gives a blue, green, or dark colour to most organic ids, and imparts to them a peculiar odour. It stains the skin and her organic substances yellow; the colour being removed by an alkali. hen in strong solution, it is corrosive and destroys the parts which touches; in this state it has been maliciously employed for throwing on person.

Appearances.—As this is an irritant as well as a corrosive poison, the ing membrane of the gullet, stomach, and intestines is found inflamed d excoriated. In one instance, the mucous membrane near the pylorus s corroded and detached in a space of two or three inches.

Analysis.—The odour is in general sufficient to identify it. This may be ncealed by alkalies or alkaline substances. When heated, it sublimes as purple vapour. The addition of a cold solution of starch produces blue colour, but many substances prevent this reaction. It is very luble in disulphide of carbon, forming a rich pink solution. The sulphide s the property of removing it from water or organic liquids in which it dissolved. It may thus be separated for chemical examination by de-nting the watery liquid from the sulphide, which, on evaporation, leaves e iodine in crystals. Chloroform, a good solvent of iodine, may be bstituted for the sulphide.

METALLIC IRRITANTS.

CHAPTER 20.

ARSENIC—ARSENIOUS ACID—SYMPTOMS—CHRONIC POISONING—APPEARANCES AFTER DEATH—FATAL DOSE—CHEMICAL ANALYSIS—ARSENITES—ARSENIC ACID—ORPIMENT AND OTHER COMPOUNDS.

WHITE ARSENIC. ARSENIOUS ACID.—The term WHITE ARSENIC is commonly applied to the arsenious acid of chemists. It is seen under the form of a white powder, visibly crystalline in a strong light, or when viewed with a lens. It is also met with, but more rarely, in opaque, brittle, white masses, resembling enamel. It is called an acid from its power of combining with alkalies, but it possesses only a feeble acid reaction when dissolved in water. It is often described as having an acrid taste, but this does not appear to be correct; a small quantity of it has certainly no appreciable taste, a fact which may be established by direct experiment. It would appear, from numerous cases on record, that it has been unconsciously taken in fatal quantities, in all descriptions of food, without exciting any perceptible sensation on the tongue. Most of those persons who have been criminally or accidentally destroyed by arsenic, have not been aware of any taste in taking the poisoned substance. In cases in which the powder has been taken in *large* quantity, it is described as having had a *roughish* taste. Water boiled for an hour on the poison and allowed to cool, holds dissolved the 40th part of its weight, or about twelve grains in one ounce. If boiled for a shorter time not more than the 80th part will be dissolved. Cold water allowed to stand for many hours on the poison does not dissolve more than from the 1000th to the 500th part of its weight; *i.e.* one half grain of arsenic to nearly one fluid-ounce of water. When arsenic in powder is mixed with cold liquids, a portion of the powder floats and adheres to the sides of the vessel. This appearance has sometimes led to a suspicion of poisoning.

Arsenic, as it is sold to the public in small quantities, is required to be mixed either with the 16th part of its weight of soot, which gives to it a greyish colour; or the 32nd part of its weight of indigo, and then it is blue. Both of these colours are rendered much deeper when the powder is wetted, so that the sooty compound is then nearly black. Sometimes, in place of indigo, artificial ultramarine is employed as a colouring. The Act regarding the colouring of arsenic (14 Vic. c. 13, s. 3) is frequently evaded. It is sometimes sold uncoloured under the name of *mercury*.

Symptoms.—These will vary according to the form and dose in which the poison has been administered. The time at which they come on, is generally in from half an hour to an hour after the poison has been swallowed. This is the average period. They have been known to appear in a quarter of an hour; Christison mentions one instance in which the symptoms began in eight minutes; but in the case of *Lofthouse* (York Lent Ass. 1835), the symptoms were proved to have attacked the deceased while he was in the act of eating the cake in which the *poison was* administered. On the other hand, in an instance where one *drachm had* been taken on an empty stomach, no symptoms appeared *for two hours*. In a case reported by Orfila, the symptoms did not show

ves for five hours; and in another, in which a large dose was taken, ptoms did not come on for seven hours. ('Ann. d'Hyg.' 1837, 1, n a case in which from thirty to forty grains of arsenious acid, same quantity of chrome yellow, were taken, symptoms of poison- not appear until five or six hours afterwards. ('Med. Chir. Rev.' 4, p. 294.) There may be every variety between these extremes, ase their appearance was protracted for *ten* hours, the maximum et known. A remarkable instance occurred in which the poison en by a young female at eleven o'clock in the morning, and no well- symptoms occurred for *eight hours:* there was then violent vomiting. ath, a cyst, formed of mucous membrane containing arsenic, was n the stomach: the poison having thus become sheathed over. in,' vol. 1, p. 535.) In another case ('Med. Times,' Oct. 21, mptoms of violent irritation did not show themselves until twenty- urs after the poison had been taken, and within about half an hour eath of the patient. The girl was sick once shortly after having ie poison, but the first symptoms were those of narcotism. The a confirmed opium-eater, and this habit may have had some in- in delaying the operation of the poison. From a third case Gaz.' vol. 47, p. 722), it appears that the active symptoms of n which commonly attend arsenical poisoning, may not appear er the lapse of *nine hours* from the time at which the poison has allowed. With the exception of the case above referred to, in ie interval was ten hours, this is the longest period of protraction rd. In other instances there have been great intermissions. In in which arsenic enters the system from without, as by its ap- n to the skin, or to ulcerated or diseased surfaces, the symptoms ly manifested until after the lapse of some hours or even days.

individual usually first experiences faintness, depression, nausea, ness, with an intense burning pain in the region of the stomach, d by pressure. The pain in the abdomen becomes more and more and there is violent vomiting of brown turbid matter, mixed with and sometimes streaked with blood. These symptoms are followed ing, which is more or less violent, and this is accompanied by ramps in the calves of the legs. The matters discharged from the and bowels have had in some instances a yellowish colour, as it posed, from a partial conversion of the poison into sulphide, but obably from an admixture of bile. The vomited matters are in ses coloured with blood, and the mixture of blood with bile has ven to them a green or brown colour. In other cases, they may of a large quantity of mucus ejected in a flaky state and having a hite appearance, as if from admixture with the poison. The *colour* omited matters may be blue or black when coloured arsenic has ken, or the admixture of bile may render them of a deep green. niting is in general violent and incessant, and is excited by any r solid taken into the stomach. There is tenesmus (straining at nd the discharges by the bowels are frequently tinged with blood. a sense of constriction, with a feeling of burning heat in the throat, ly accompanied by the most intense thirst. The pulse is small, t, and irregular; sometimes wholly imperceptible. The skin and clammy in the stage of collapse; at other times it is hot. piration is painful from the tender state of the stomach. There is stlessness, but before death stupor may supervene, with paralysis, convulsions, or spasms in the muscles of the extremities. In one trismus (lockjaw) appeared in three-quarters of an hour. ('Orfila,' . 449.) Although pain is in general among the early and well-

marked symptoms, arsenic appears in some cases to destroy sensibility. Thus it has been observed that, even when the stomach has been found intensely inflamed after death, the patient had not complained of pain during the time which she survived.

In one case, where a woman died in three hours after taking arsenic in a pudding served at dinner, there was no vomiting or purging. In two hours she was in a state of complete collapse, and at the time it was noticed that the conjunctivæ (the membranes of the eyes) were red. ('Med. Times,' Aug. 30, 1851, p. 229.)

Chronic poisoning.—Should the person recover from the first effects, or the case be protracted, or should the dose have been small and administered at intervals, there will be inflammation of the conjunctivæ, with suffusion of the eyes, and intolerance of light, conditions which are, however, often present among the early symptoms above described. There is also irritation of the skin, accompanied by a vesicular eruption, which has been called *eczema arsenicale.* Sometimes this has assumed the form of nettle-rash or of the eruption attending scarlet fever, for which disease arsenical poisoning has been mistaken. Local paralysis, preceded by numbness or tingling in the fingers and toes, and other symptoms of nervous disorder are also common consequences. The editor has seen a case of arsenical poisoning in which repeated three-quarter grain doses of white arsenic were given with homicidal intent, followed by general paralysis beginning in the lower extremities, and gradually creeping upwards till the low intercostal and other respiratory muscles were affected. The patient recovered under treatment. Exfoliation of the cuticle and skin of the tongue, with the falling off of the hair, has likewise been witnessed. (Case of the *Turners*, 1815, 'Marshall,' p. 119, Husemann's 'Jahresbericht' 1871, p. 527.) Salivation has been observed to follow, especially when small doses of the poison have been given for a length of time. ('Med. Gaz.' vol. 16, p. 790.) Strangury and jaundice have been also noticed among the secondary symptoms. ('Marshall on Arsenic,' pp. 44, 111.) A well-marked case of slow poisoning by arsenic is recorded by Flandin ('Traité des Poisons, ou Toxicol.' t. 1, p. 510.) It illustrates a not unfrequent form of secret murder, and it is well calculated to inspire caution in making a diagnosis from symptoms. A woman put daily into the food of her fellow-servant, a very small quantity of white arsenic in powder. Shortly after dinner this person was seized with vomiting which led to the rejection of the food and poison before the latter had caused any serious mischief. As this practice was continued at intervals for about six weeks, the stomach became exceedingly irritable; there was pain in the bowels, and the woman was much emaciated. There was also spitting of blood, with such a degree of nervous irritability that a current of air falling upon her, caused an attack of spasms and convulsions. When the patient found that she could not bear anything on her stomach, she left the place and passed two months in the country. Her health became gradually re-established there, and she returned to resume her usual occupations. The prisoner, however, renewed her attempts; and, to make sure of destroying life, gave to her one morning, in coffee, a large dose of white arsenic in powder: violent vomiting ensued, and the poison was expelled with the food taken at breakfast. Arsenic was detected in the vomited matter, and the explanation of the cause of the long previous illness became clear. Under treatment the patient recovered. Such symptoms as those above described, may be easily referred to chronic inflammation, or ulceration of the stomach from natural causes, leading to perforation. There are many anomalous cases on record, in which the symptoms have diverged so much from the ordinary course as to embarrass

medical practitioners. For some of these, the reader is referred to a paper by Ogston, 'Med. Gaz.' vol. 47, p. 181; also to the author's work 'On Poisons,' 2nd Ed. p. 363; and Husemann's 'Jahresbericht,' 1872, p. 481.

Arsenic is not an accumulative poison: it is temporarily deposited in the organs after absorption, but is rapidly eliminated by the urine and other secretions; and in two to three weeks, if the person survives, the whole of it may be removed from the body.

Appearances after death.—The striking changes produced by arsenic are generally confined to the stomach and bowels. They are commonly well marked in proportion to the largeness of the dose, and the length of time which the person has survived after taking the poison. Our attention must be first directed to the *stomach*. Arsenic seems to have a specific effect on this organ, and the mucous membranes generally: for, however the poison may have entered into the system, whether through a wounded, diseased, or ulcerated surface, or by the act of swallowing, the stomach has been found inflamed. The mucous membrane of the stomach, which is often covered with a layer of mucus, mixed with blood or bile, and with a thick, white, pasty-looking substance containing arsenic, is commonly found red and inflamed in dotted or striated patches: the colour, which is sometimes a dull or brownish red, becomes brighter on exposure to the air: at other times it is of a deep crimson hue, interspersed with black-looking specks or patches of altered blood. The redness is usually most strongly marked at the greater end; in one case it may be found spread over the whole mucous surface, giving to it the appearance of red velvet; in another it will be chiefly seen on the prominences or folds of the membrane. In one instance the author found the coats thickened and of a gelatinous consistency, without any marked inflammatory redness.

The stomach has been found highly inflamed in a case which proved fatal, 1863, in *two hours*. Thus it would appear that inflammation of the mucous membrane may be well marked within a very short period. A woman, æt. 24, retired to her bed-room after dinner, at two o'clock, to lie down. At three o'clock she was not suffering from any apparent illness. At half-past four she called to her sister, and then it was found that she had swallowed a quantity of arsenic. There was then no sickness. After this, she was sick once, and purged once, but complained of no pain. She drank some tea, but almost immediately became collapsed, and seemed to those who were with her to be falling into a fainting fit. She died before six o'clock, and was sensible to the last. She could not have taken the poison more than two hours before she died. On inspection the day following, the whole mucous membrane of the stomach was intensely inflamed, presenting a dark scarlet colour, with broad livid patches. Upwards of an ounce of solid arsenic was found in a pasty state on the mucous membrane of the stomach, which was raised, thickened, and velvety. This case shows not only that there may be extensive morbid changes in the dead body within a short period after the taking of the poison, but that, with an unusually large dose, the symptoms of vomiting, purging, and pain may be slight and bear no proportion to the quantity of poison taken. Blood of a dark colour may be effused in various parts within the folds, or beneath the lining membrane—an appearance which has been mistaken for gangrene. A raised circular or oval patch of false membrane with an intensely red border, and with arsenic upon its surface, may be sometimes seen upon the inner coat. [See the case of *Reg.* v. *Dore and Spry*, C. C. C. Aug. 28, 1848; also 'Med. Gaz.' Nov. 24, 1848.] The stomach often contains a mucous liquid of a dark colour tinged with blood. The coats are sometimes thickened in patches, being raised up into a sort of fungus-like tumour, with arsenic embedded in them: at other times they have been

found thinned. The mucous membrane may be found ulcerated, and still more rarely gangrenous. Ulceration of the mucous membrane, as the result of the action of arsenic, has been found as early as ten hours after the poison had been taken. Perforation of the coats is so uncommon a result of arsenical poisoning, that there are but few instances on record. In a case examined by Chevallier, the stomach of a person who had died from the effects of arsenic was found perforated at the larger end. The aperture is described to have been of the size of a franc-piece, round, soft, and somewhat thickened in its margin. There was no redness or sign of erosion about it, nor was there any appearance of ulceration on the other parts of the mucous membrane. Externally the stomach was covered with false membranes, arising from inflammation of the peritoneum. ('Ann. d'Hyg.' 1852, 1, 448.) This case is so imperfectly reported that it is impossible to say whether the perforation was caused by arsenic, or whether it was the result of previous disease. The glands of the stomach have been found enlarged; but this is by no means an unusual morbid appearance from any cause of local irritation, without reference to poisoning. Various appearances are said to have been met with in the lungs, heart, brain, liver, kidneys, and urinary organs; but they do not appear to be so characteristic of arsenical poisoning as to admit of medico-legal use in enabling a medical man to distinguish poisoning from disease. It is to the stomach and intestines that he must look for the basis of reliable evidence in regard to appearances after death. An ecchymosed condition of the lining membrane of the left ventricle of the heart and of its pericardial surface, fatty degeneration of the liver, and bloodlessness of the body, have been met with in cases of acute arsenical poisoning. (Horn's 'Vierteljahrsschrift,' 1862, 2, 345.)

In a few instances the mouth, throat, and gullet have been found inflamed, but in general there are no changes in these parts to attract particular attention. The mucous membrane of the small intestines may be inflamed throughout, but commonly the inflammatory redness is confined to the upper part or to the duodenum, especially to that portion which joins the stomach. Of the large intestines, the rectum appears to be the most prone to inflammation. The liver, spleen, and kidneys present no appearances which can be connected with the action of arsenic, although these, like the other soft organs, may become receptacles of the absorbed poison. It is worthy of observation in relation to the known antiseptic properties of arsenic, that the parts especially affected by the poison (the stomach and bowels) occasionally retain the well-marked characters of irritant poisoning for a long time after death. Absorbed arsenic does not, however, appear to prevent the decomposition of the soft organs in which it is deposited.

Death from external application.—Poisoning by the external application of arsenic is not very common. In 1864, a girl, æt. 9, died rather suddenly, after an illness of about ten days. The mother had rubbed some white precipitate ointment mixed with arsenic on the head of the child, which was diseased. Her object, she stated, was to kill the vermin on the scalp. No symptoms of note were observed until about the fifth day after the application, when the child appeared ill and complained of thirst. On the eighth day she was very unwell; there had been cramp, with slight action on the bowels, but no vomiting. She became drowsy, and died on the tenth day. The lining membrane of the stomach and duodenum was inflamed: in the stomach the inflammation was well marked towards the greater end: these were the principal post-mortem appearances. Traces of arsenic were found in the mucous fluids of the stomach, in the coats of the stomach, in the intestines, and in four ounces of the liver, but arsenic

lid form could nowhere be detected. A portion of the diseased alp was examined, and yielded arsenic as well as mercury (from ecipitate) in large proportion, the arsenic being estimated at from hree grains. From the evidence given at the inquest there was no at the mother's account was correct, and that her child had died e ignorant application of arsenic externally to a diseased portion of p.

remarkable features of the case were these: no symptoms appeared er the fourth day, and then only great thirst; there was slight with cramps on the eighth day, and death took place on the tenth, any vomiting. Arsenic was found in the stomach and contents, presence there might have led to an erroneous inference of its been criminally administered by the mouth. It was, however, merely in traces, and obviously the result of mucous elimination. are and mode of occurrence of the symptoms were also opposed to er presumption. That absorbed arsenic may be thus transferred e blood to the stomach and intestines, has been distinctly proved xperiments of Pavy and the author. ('Guy's Hosp. Rep.' 1860,

878, some remarkable cases of poisoning by the external use of wder mixed with white arsenic occurred at Loughton in Essex, and places. Though a number of children died suddenly with some- nilar symptoms, in two cases only were post-mortem examinations lyses of the viscera conducted. One child, a female, was at birth d by the nurse as a healthy child. It was washed, as usual, shortly th, and was then dusted all over with the violet-powder, a sample was subsequently ascertained to contain 38½ per cent. of white Later on in the day the powder was again applied to the private the body. On the second day the powder was applied four times. day there was very marked redness and inflammation of the skin, led the nurse to apply the powder unusually freely, especially stomach where the redness was most noticeable. On the third day was intensely red, and appeared in parts—especially about the e vagina, and the anus—of a yellow and unhealthy hue. In con- of it being suspected that the violet-powder contained some substance its use was discontinued, and common starch-powder l instead. On the succeeding day the eruption became very much nd in some parts the skin commenced sloughing. On the tenth he child's life, and on the sixth day from the last application of et powder, the child died from exhaustion. A post-mortem tion made five days after death revealed nothing marked in the n of the viscera. From the exhumed body 6½ grains of arsenic tained by Tidy. Another female infant died fourteen days after In this case a similar violet-powder was applied as usual. Within time of the application the skin became red, and vomiting and set in, and continued till death. On section the abdominal showed much inflammatory action; they were thickened and to the viscera. The rectum was highly inflamed; the kidneys en were much congested; and the liver was very slightly congested. s of three grains of arsenic were extracted from the viscera.

e is no doubt that the white arsenic had been accidentally mixed violet-powder in mistake for terra alba (sulphate of lime or l calcium sulphate), which is a constituent of some kinds of violet- This is not the only instance of such a mistake having occurred. lford, in 1858, seventy persons suffered, and seventeen died, from ts of eating peppermint lozenges, adulterated with white arsenic,

in mistake for "daft" (sulphate of lime), which was at one time commonl used for the adulteration of cheap lozenges.

Arsenical vapours.—It is not often that a case is heard of in which whi arsenic has caused death by reason of its having been breathed or swallow in the state of vapour. In 1858, a case involving the effects of arseni vapours was the subject of an inquest in London (see 'On Poisons,' 2 ed. p. 234); but on that occasion there was an entire failure of pr that the arsenical vapour was the cause of death. In a case wh was the subject of a trial at the York Lent Assizes, 1864, the priso placed some burning pyrites, containing arsenic, at the entrance of the d of a small room in which there were eight children, including an inf in a cradle. From the evidence, it appeared that all the children suffe from the fumes, which were chiefly those of sulphurous acid. A can that was in a cage died from the effects. The children were spee removed from the house and recovered, but the infant was left there an hour. It suffered from vomiting, and when seen about seventeen ho afterwards, the child was pulseless: it vomited incessantly, was m purged, and appeared to be in great pain. It died about twenty-f hours after exposure to the fumes. On inspection, the stomach and testines were slightly inflamed. The brain and lungs were congested, the lining membrane of the trachea was of a bright red colour. Al detected arsenic in the contents of the stomach, in the lungs, in coats of the stomach, and in the spleen. None was found in the liver. T pyrites contained arsenic, and gave off while burning arsenious acid vapour and sulphurous acid. Some of the appearances were owing sulphurous acid; but death was probably caused by arsenic. The priso was found guilty of manslaughter. A case is reported, in which it stated that the members of a family were made ill by arsenical vapo escaping from the walls of a room, and that one of them died. ('Pha Jour.' July, 1870, p. 66.)

Quantity required to destroy life.—The smallest fatal dose hith recorded was observed in a case communicated by Castle ('Prov. Jo June 28, 1848, p. 347). A woman took half an ounce of Fowler's solut (arsenite of potash) in unknown doses, during a period of five days. S then died, and on examination the stomach and intestines were fo inflamed. Death took place by syncope (mortal fainting), and there an absence of vomiting and purging. The quantity of arsenic which h destroyed life could not have been more than *two grains*. In another c two grains and a half of arsenic, contained in two ounces of fly-wa killed a robust healthy girl, aged 19, in thirty-six hours. ('Med. G vol. 39, p. 116.) Hence under circumstances favourable to the operat of the poison, the fatal dose in an adult may be assigned at from tw *three grains*. The number of deaths reported to have occurred from ars in England and Wales in the year 1880 was nineteen.

Period at which death takes place.—Large doses of arsenic comm prove fatal in from eighteen hours to three days. The average time which death takes place is twenty-four hours; but the poison may dest life within a much shorter period. There are many authentic c reported, in which death has occurred in from three to six hours. In 1 the author met with a well-marked case of death from arsenic in hours; and in another, which occurred in 1849, death took place two and a half hours. ('Guy's Hosp. Rep.' 1850, p. 183. See also 'A d'Hyg.' 1837, 1, 339.) Foster, of Huntingdon, met with the case o child under three years of age, which died within *two hours* from the effe of arsenic. The quantity taken could not be determined. A case has proved fatal in two hours (p. 259). The most rapidly fatal c


he author met with was that of a youth, æt. 17, who died in 860, from the effects of a large dose of arsenic, the symptoms from e suffered being of a tetanic character. The poisoning was the an accident at Ramsey, in the Isle of Man. The medical evidence nquest was to the effect that not more than *twenty minutes* had between the time at which deceased sat down to eat his supper, ng the poison, and his death. In some instances death does not ıtil long after the average period. In one case in which an adult ed about half an ounce, death did not take place for *fifty hours*, s remarkable that there was an entire absence of pain. ('Med. l. 48, p. 446.) In the case of the *Duc de Praslin*, one large dose en, but death did not occur until the *sixth* day. ('Ann. d'Hyg.' 367.) In 1847, a man who had swallowed half an ounce of was admitted into Guy's Hospital. He died on the *seventh* day. vious that a patient who recovers from the first effects of this may still die from exhaustion or other secondary causes many weeks after having taken it, even although the whole of the poison ı eliminated from the body. Thus in the case of *Dr. Alexander*, ok place on the *sixteenth* day; and although a large quantity had ten, no arsenic was found in the body. ('Med. Times and Gaz.' 3, 1857, p. 389.) In one instance in which arsenic was applied ly to the head, the person did not die until the *twentieth day*. gest duration of a case of poisoning by arsenic is probably that by Belloc. A woman, æt. 56, employed a solution of arsenic in cure the itch, which had resisted the usual remedies. The skin covered with an erysipelatous eruption, and the itch was cured, experienced severe suffering. Her health gradually failed, and after the lapse of *two years*, having suffered during the whole period from general tremor of the limbs. ('Cours de Méd. l.)

ıical *analysis. Arsenic as a solid.*—In the simple state, *white* nay be identified by the following properties:—1. A small quantity owder, placed on platinum foil, is entirely volatilized at a moderate ure (400° F.) as a white vapour. Should there be any residue, it ity; sometimes plaster of Paris or chalk is found mixed with it. ll portion of the white powder is very slowly heated in a glass a narrow bore, it will be sublimed without melting, and form a minute octahedral and tetrahedral crystals, remarkable for their d brilliancy. Under a microscope magnifying 250 diameters, the ıce of these crystals is remarkably beautiful and characteristic: exceeding the 4000th of an inch in diameter may be easily ed by the aid of this instrument. They may be measured even 6,000th of an inch in diameter. (See figs. 14, 15, pp. 264, 265.) be observed in these experiments that white arsenic in vapour s no odour. 2. On boiling a small quantity of the powder in water, it is not readily dissolved, but it partly floats in a sort of um, while a part becomes aggregated in lumps at the bottom of el. It requires long boiling, in order that it may be dissolved ally diffused through water. This property of arsenic has given some important questions on criminal trials. The floating of takes place whether the water is hot or cold, and whether the added to the poison or the poison to the water. (See the case of *Smith*, Wells Lent Ass. 1869.) This property has attracted atten- d in one instance was the means of saving life. 3. When the is treated with a weak solution of ammonium sulphide in a watch- ere is no change of colour, as there is with most metallic poisons:

on warming the mixture, the white powder is dissolved; and on continuing the heat until the ammonium salt is expelled, a rich yellow or orange-red film is left (arsenious sulphide), which is soluble in alkalies, and insoluble in hydrochloric acid. 4. Heated on platinum-wire in a smokeless flame, the powder imparts to it a pale blue colour, while it is volatilized in white fumes. 5. Another test is stannous chloride in hydrochloric acid. The mixture is brought to the boiling point, and it should remain colourless. If the hydrochloric acid contains a trace of arsenic, the liquid will acquire a light brown colour. On adding a minute quantity of solid arsenious acid to it, it is dissolved and metallic arsenic is deposited in the form of a brown or brownish black precipitate. A salt of antimony is not thus affected.

Reduction-process.—When a small portion of the powder, i.e. from one-fourth to one-twentieth part of a grain, is heated with some reducing agent containing carbon, such as *soda flux* (obtained by incinerating sodium acetate or tartrate in a close vessel), in a glass tube about three inches long and from one-eighth to a quarter of an inch in diameter, it is decomposed: a ring of metallic arsenic of an iron-grey colour, is sublimed and deposited in a cool part of the tube. A mixture of one part of potassium cyanide with three parts of dry (anhydrous) sodium carbonate forms an excellent flux for the reduction of arsenic. The materials and tube should be well dried. About two or three parts of either flux to one part of arsenic will be found sufficient. In the absence of these fluxes powdered

Fig. 11. Fig. 12. Fig. 13. Fig. 14.




11. Berzelius's reduction-tube, with sublimate of metallic arsenic.
12. Ordinary reduction-tube, with two sublimates: the upper, brownish black; the lower, the pure metal in an annular deposit.
13. Small reduction-tube, with a crystalline sublimate of arsenious acid.
14. The tube with sublimate magnified, showing the octahedral form of the crystals. These are shown still more highly magnified in fig. 15, at p. 265.

potassium ferrocyanide may be used in a similar proportion. After heating, a minute trace of arsenic remains in the flux. During the reduction, there is a perceptible odour, resembling that of garlic, which is possessed by metallic arsenic only, whilst undergoing oxidation. This *odour* was at one time looked upon as peculiar to arsenic, but little reliance is now placed on it as a matter of medical evidence—it is a mere accessory result. In this experiment of reduction, there are frequently two rings deposited

the tube (fig. 12):—the upper and larger ring has a brown colour, and ears to be a mixture of finely divided metallic arsenic and arsenious l: the lower ring is small and consists of the pure metal. In order to ermine the *weight of the sublimate*, the glass tube should be filed off ely on each side of the metallic ring, and weighed in a delicate balance; sublimate may then be driven off by heat, and the piece of glass again ghed:—the difference or loss represents the weight. These sublimates remarkably light. By heating gently the pulverised tube with the imate in another tube of larger diameter, the metallic arsenic, during tilization, forms octahedral crystals of arsenious acid, which, after nination by the microscope, may be dissolved in a few drops of water, tested by one or more of the liquid reagents. The metallic sublimate, ne crystals produced from it, may be further subjected to the following ess:—Break the glass on which the sublimate is deposited, into ments, and digest these in a few drops of fuming nitric acid, previously ed to be free from arsenic. The sublimate is thereby converted into *sic acid*. The acid solution should be evaporated to dryness: the te uncrystalline residue obtained should be dissolved in a few drops of illed water, and a strong solution of silver nitrate, or of the ammonio- ate (p. 266) added in small quantity to the residue. A brick-red uration indicates arsenic acid, and thus proves incontestably that the imate was of an arsenical nature.


The upper or brownish-looking sublimate (fig. 12), may be readily con- ed into one of the pure metal, by gently heating it in the flame of a it lamp. Arsenious acid is then volatilized, and an iron-grey deposit netallic arsenic appears. If the heat is continued, the whole of the allic sublimate is volatilized and deposited in a cool part of the tube, in sparent and colourless octahedra, or modified octahedra, of arsenious l. This is the special character of an arsenical sublimate: it may be

Fig. 15.



Crystals of Arsenious Acid by sublimation, magnified 36 diameters.

Fig. 16.



Crystals of Arsenious Acid from a solution, magnified 124 diameters.

s distinguished from sublimates of all metals or non-metals. The er metallic sublimate procured by reduction (fig. 12) may appear not an annular form, but in detached nucleated particles of a somewhat bular shape. These are of an iron-grey colour, quite unlike sublimed rcury, and when examined by the microscope, it may be seen that they sist of crystalline masses, that they are angular, and not strictly erical. This sublimate is sometimes produced in the last stage, when residue in the tube is strongly heated.

The *process of reduction*, with the corroborative results above mentioned, hen thus applied, conclusive of the arsenical nature of the substance er examination.

Arsenic in solution in water. Liquid tests.—The solution of ars acid is clear, colourless, possesses scarcely any perceptible taste, and h a feebly acid reaction. In this state, we should first evaporate slo few drops on a glass-slide, when a crystalline residue will be obtained examining this with a microscope, it will be found to consist of nun minute octahedral crystals, presenting triangular surfaces by re light. (See fig. 16, p. 265.)

1. *Silver test.*—On adding to the solution *ammonio-nitrate of si* pale yellow precipitate of silver arsenite falls;—changing, under ex to daylight, to a greenish-brown colour. The test is made by to a strong solution of silver nitrate, a weak solution of am and continuing to add the latter, until the brown silver oxide, thrown down, is almost re-dissolved. The yellow precipitate is solu nitric, tartaric, citric, and acetic acids, as well as in ammonia. It dissolved by potash or soda.


2. *Copper test.*—On adding to a solution of arsenic, *ammonio-sulp copper*, a light green precipitate of copper arsenite is formed, the which varies according to the proportion of arsenic present, and the tity of the test added: hence, if the arsenic is in small proporti green precipitate at first appears; the liquid simply acquires a blue from the test. In less than an hour, if arsenic is present, a bright deposit is formed, which may be easily separated from the blue liq decantation. This test is made by adding ammonia to a weak solu copper sulphate, until the blueish-white precipitate, at first produ nearly re-dissolved: it should not be used in large quantity if concen as the deep blue colour tends to obscure or conceal the green prec formed. The precipitated copper arsenite is soluble in all acids, n and vegetable, and in ammonia, but not in potash or soda. If a quantity of the blue ammoniacal solution of this precipitate is poure a crystal of silver nitrate, a film of yellow silver arsenite will around the crystal. If a strong solution of nitrate is added to tl liquid, nearly neutralized by diluted sulphuric acid, a yellow precipi silver arsenite is also produced. Thus the silver and copper tests employed with the same quantity of liquid. The *dried* precipit copper arsenite when slowly and moderately heated in a well-dried tion tube, yields a ring of octahedral crystals of arsenious acid- cupric oxide being left as a residue.

3. *Sulphuretted hydrogen test.*—Ammonium sulphide gives n cipitate in a solution of arsenic until an acid has been added, by property arsenic is known from most metallic poisons. On adding hydrochloric acid, a rich lemon-yellow coloured precipitate is t down (orpiment or arsenious sulphide). It is better, however, to e in medico-legal analysis, a current of washed sulphuretted hydroge which is easily procured by adding to ferrous sulphide, in a apparatus, a mixture of one part by volume of strong hydro acid and one part of water. The arsenical liquid should be a acidulated with pure diluted hydrochloric acid, *before* the gas is into it: and care should be taken that it is not alkaline. The yellow pound is immediately produced if arsenic is present, and it m collected after boiling the liquid sufficiently to drive off any surplu The precipitation is likewise facilitated by adding to the liquid a s of ammonium chloride. The yellow precipitate is known to be ars sulphide by the following properties:—1. It is insoluble in water, a and ether, as well as in diluted hydrochloric acid, and vegetable acid it is decomposed by strong nitric and nitro-hydrochloric acids. 2 dissolved by potash, soda, or ammonia; forming, if no organic

, a colourless solution. 3. When dried and heated with two parts of a mixture of sodium carbonate and potassium cyanid 4), it gives a sublimate of metallic arsenic. Unless these pro- e possessed by the yellow precipitate formed by sulphuretted in an unknown liquid, it cannot be a compound of arsenic. On hand, when these properties are possessed by the precipitate, arsenic, and can be no other substance.

's process.—The action of this test depends on the decomposition uble compounds of arsenic by nascent hydrogen, evolved from n of diluted sulphuric or hydrochloric acid on zinc. The should be first proved to be free from arsenic. The apparatus most simple kind, and is so well known as to need no descrip- e arsenic to be introduced is best dissolved in water, by boiling with or without the addition of a few drops of potash or ric acid. The metallic arsenic combines with the hydrogen, arsenetted hydrogen gas, which possesses the following pro- 1. Filtering paper wetted with a solu- ver nitrate is immediately blackened by the silver being reduced to the metallic ad-paper is not changed in colour, unless ted hydrogen is also present. 2. It h a pale bluish-white flame, and thick ke (arsenious acid). 3. A slip of glass, te porcelain, held in the flame near the not too long a time) acquires a dark the deposit of metallic arsenic upon it. sit presents a bright metallic lustre in (A), a white film of arsenious acid on e (C), and between the two a dark ring verulent substance (B), which, when y transmitted light, is hair-brown in rards the margin, but opaque in the centre. In order to deter- arsenical nature of the deposits, the following plan may be —Several of them should be received and accumulated in small capsules, held over the burning gas. To one, add a solution ing powder: the arsenical deposit is immediately dissolved. id, add a solution of ammonium sulphide: the metallic deposit d, but not perfectly dissolved: yet on evaporation it yields a w film of arsenious sulphide. To a third, add a few drops of tric acid. The deposit is dissolved: evaporate the acid solution dryness: carefully neutralize the residue, and add one or two strong solution of silver nitrate. A brick-red stain or a dark- itate of silver arsenate will be produced.

Fig. 17.



Deposit obtained by Marsh's apparatus.
A. Metal.
B. Mixed deposit.
C. Arsenious acid.

h's process.—In the application of this process, the liquid sus- contain arsenic, or the solid dissolved in distilled water, is boiled t one-sixth of its volume of *pure* hydrochloric acid (proved to be arsenic), and a small slip of copper is then introduced. A slip d pure copper foil (electrolytic copper) about a quarter of an inch tached to the end of a fine platinum-wire, may be employed for ment. The copper must be first proved to be free from arsenic, a very common contamination of commercial copper in the form uze, or wire. Copper-gauze and wire generally contain arsenic. rolytic copper, free from arsenic, can be procured in the form of or foil. If arsenic is present in the liquid, even in small quan- polished copper acquires, either immediately or within a few an iron-grey metallic coating from the deposit of this metal.

This is apt to scale off if the arsenic is in large quantity, or if the is very acid or long boiled. Remove the coated slip of copper, successively in water, alcohol, and ether, dry it, and gently heat reduction-tube, when arsenious acid will be sublimed in minute oct crystals: if these should not be apparent from one piece of copper, may be successively introduced. When the quantity of arsenic small, the polished copper merely acquires a faint violet, grey, or tint. The deposit is in all cases materially affected by the de dilution, and sometimes it will appear only after the liquid has bee concentrated by evaporation. We are not obliged to dilute th in the experiment, and there is no material loss of arsenic, as in process:—the whole may be removed and collected by the intro of successive portions of pure copper. This process is extremely c and the results are speedily obtained. Among the cautions to be o are these:—1, not to employ too large a surface of copper in t instance; and, 2, not to remove the copper from the liquid to When the arsenic is in minute quantity, and the liquid is much or not sufficiently acidulated, the deposit does not take place soi for half an hour. If the copper is kept in for an hour or longer, acquire a dingy tarnish from the action of the acid and air. T one corroboration required. The copper with the deposit upon it be well dried, cut into small pieces if necessary, and introduced int and perfectly clean reduction-tube. The application of a gentle l a spirit-lamp will cause the metallic arsenic to be volatilized a arsenious acid, which is deposited in a cool part of the tube, in th of octahedra or of the derivatives of the octahedron. When ex by a quarter of an inch power under the microscope, these crysta be seen and recognized by their shape up to the sixteen-thousandt inch in width. The smaller the crystal the more perfect th (See fig. 14, p. 264.) If the copper with the deposit, and the tu not been well dried, the angularity of form is not distinct. These may be tested by the processes already described.

The following is a simple method of detecting arsenic in copper to pure hydrochloric acid, diluted with six parts of water, one or tw of a weak solution of ferric sulphate or chloride. Boil the acid liq introduce the copper, well cleaned and polished, into the boiling Arsenical copper acquires a dark tarnish, while the non-arsenical (lytic) copper retains its red colour under these circumstances. It found from this experiment that copper in the state of gauze or fi generally contains arsenic. This would present no obstacle to the de of arsenic by it, provided the copper gauze were not dissolved. can only be separated from its copper alloy by the destruction of th and the solution of the two metals.

The mere fact that a grey deposit is formed upon pure copp boiled in the liquid under examination when acidulated with pure chloric acid, affords no absolute proof of the presence of arsenic. metals, *e.g.* antimony, mercury, and bismuth, all yield deposit Reinsch's test; and the grey deposit yielded by bismuth may rea mistaken for that of arsenic. The volatility of the arsenical depo crystalline nature of the sublimate, and its reaction when treat cessively with nitric acid and silver nitrate, must in all cases be asce before it is concluded that the deposit is arsenical.

In consequence of the errors into which faulty methods of em Reinsch's test have led, its reliability has been much discredite though in skilful hands the results obtained by it are trustworthy, it perhaps be unsafe to rely upon it in an important criminal investi

may be conceded that Marsh's process will detect a smaller quantity of enic than the process of Reinsch, but the latter, when the quantity of aid is small, and pure materials are used, will detect the 150th or the)th part of a grain of the poison. It appears to the author that in a minal case it would not be safe to depose to the presence of arsenic n Marsh's process alone, when the quantity of poison was *too small* to mit of separation or corroboration by the process of Reinsch. Conely the results of Reinsch's should be corroborated by those of Marsh's cess. It was this over-reliance on the extreme delicacy of Marsh's cess in researches where it admitted of no corroboration whatever, led Orfila to assert that arsenic was a natural constituent of the man body.

Arsenic in solids or liquids containing organic matter.—In testing *solids* erally for arsenic, we may employ the process of Reinsch as a preinary test. The solid is boiled in water acidulated with from one-fourth one-sixth of its volume of pure hydrochloric acid, until it is either solved or its structure broken up. A small portion of pure copper lished is then introduced. In a few minutes, if arsenic is present—even the extent of the thousandth part of a grain—there will be a metallic posit on the copper, and this will yield crystals when heated in a tube. *quids* suspected to contain arsenic may be treated in a similar manner. ater is not required; the liquid is simply acidulated with one-sixth rt of pure strong hydrochloric acid. If the solution of the organic id or the organic liquid is not deeply coloured, the stannous chloride it may be employed in place of the process of Reinsch. (See p. 264.) ss than the sixtieth part of a grain, even under considerable dilution, ay be thus readily detected. It thus reveals traces of arsenic in ordinary lphuric and hydrochloric acids.

The arsenic may be mixed with the organic liquid in the form of heavy mps or powder. The great specific gravity of this substance allows of e liquid being poured off, and the sediment collected. When washed d dried, it will be found to be crystallized. It should be weighed, and en tested by the processes elsewhere described. Let us assume that the ganic liquid is milk or beer, it will be necessary to determine whether y arsenic is dissolved in it. Filter a portion; place it in a dialysing be (fig. 4, p. 216) and immerse the mouth of the tube in distilled water. a few hours the arsenic will have traversed the membrane, and will found in a clear and nearly colourless solution in the water. The id tests may be then applied to this liquid for the detection of arsenic. ey should never be applied directly to coloured organic liquids.


Precipitation as sulphide.—When arsenic has been introduced into an ganic liquid in large quantity, it may be precipitated as sulphide by a rrent of washed sulphuretted hydrogen. The liquid should be boiled, tered, and acidulated with pure hydrochloric acid before passing the gas to it. When precipitation has ceased, it should be again filtered, the cipitate collected, washed, dried, and weighed. By operating on a asured portion of the solution, the amount of white arsenic may be termined, approximately, by the weight of the yellow sulphide obtained—e parts by weight of sulphide being equal to four parts of white arsenic, arly. The properties of the yellow precipitate should be verified accordg to the methods mentioned at p. 266. In some cases arsenic may be sent, but in a quantity too small to be precipitated as sulphide by lphuretted hydrogen. In others the presence of certain substances may terfere with or prevent precipitation. The presence of any free alkali a liquid prevents the formation of a precipitate.

When white arsenic is found in powder, as a sediment in organic liquids,

it is obvious that it must have been taken in the solid state, and, mixed with a liquid or solid, still in an undissolved form. If fo dissolved, it may have been taken either in solution or in a solid f dissolved portion being part of the solid taken up by the fluid stomach, and the remainder having been expelled by vomiting and This question was of importance in *Reg.* v. *Sturt*, Lewes Lent Assi The deceased, in this case, died from the effects of arsenic in administered, it was believed, in a mince-pie. It was suggested poison might have been swallowed in ginger-beer, but then it c have been in a state of solution: it must have been mechanical with the liquid. The Judge who tried this case, was apparently n of any difference existing between the actual solution and the m suspension of a solid in a liquid.

Distillation process.—When the poison is in so small a quantit does not admit of precipitation by sulphuretted hydrogen, and particles of arsenic are found in the stomach, in its contents, o article of food, another method may be resorted to for detecting its This method equally applies to the detection of arsenic depos result of absorption in the soft organs of the body, as in the liver or heart, and to arsenic in all its forms, except the pure insoluble or orpiment. Although, after long interment, white arsenic passes, less rapidly, into the state of yellow sulphide as a result of changes during putrefaction, the conversion is generally only The only condition for success is, that the substance, whether foo mucus, the liver, or other organ, should be first thoroughly drie by exposure to a current of air, or in a water-bath. The dri should then be broken into small portions and placed in a flask of sufficient capacity, with a quantity of the strongest fuming

Fig. 18.



Apparatus for distilling organic and mineral substances containing Arsenic.

chloric acid to drench it completely. The freedom of this acid from should be first carefully determined. The complete separation of from organic substances depends greatly on their perfect desiccati on the concentration of the acid employed. After some hours' d the retort or flask (*a*, fig. 18) containing the mixture—which shou such a size that the materials should not fill it to more than one- one-half of its capacity—should be fitted with a long condensing t and then gradually heated by a sand-bath until the acid liquid b pass over; or the use of a Liebig's condenser is preferable. A sm receiver (*d*) with a loosely-fitting cork may be employed to coll product. This should contain a small quantity of distilled water, *fix and condense* any vapours that may pass over. The receiver, as *the condensing*-tube, should be kept cool by wetting its surface w

rater diffused on a layer of bibulous paper placed over it. The perfect ondensation of the distilled liquid is ensured by this arrangement. The listillation may be carried to dryness, or nearly so, on a sand-bath; and it ay be sometimes advisable, in order to ensure the separation of the whole f the arsenic as chloride, to add to the residue in the retort another portion f pure and concentrated hydrochloric acid, and again distil to dryness. The author has found, however, that portions of dried liver and stomach gave up every trace of arsenic by one distillation, when a sufficient quantity of hydrochloric acid had been used, and the process slowly conducted by a regulated sand-bath heat.

The liquid product may be coloured, turbid, and highly offensive if distilled from decomposed animal matter. Exposure to the air for a few hours sometimes removes the offensiveness, and there is a precipitation of sulphur, or of some sulphide, without any absolute loss of arsenic. The distillate may be separated from any deposit by filtration, and, if still turbid, it may be again distilled at a lower temperature to separate it from any organic matter that may have come over.

If arsenic was present in the solid, the distillate will contain arsenic terchloride, which, although volatile, does not escape from a diluted solution at common temperatures. The quantity of dry organic substance used in the experiment must depend on the quantity of arsenic present, as revealed by a preliminary trial with Reinsch's process. If large, two or three drachms of the dried substance, or even less, will yield sufficient arsenic terchloride for further proceedings. For the absorbed and deposited poison, half an ounce of the dried organ, corresponding to two ounces of the soft organ, will frequently suffice; but a negative conclusion of the absence of arsenic should not be drawn from a smaller quantity than two to four ounces of the dried substance, whether liver, kidney, or heart. These tissues, it must be remembered, contain about 76 per cent. of water, so that the hydrochloric acid used will require less dilution. If oily matter should be distilled over, this may be separated by passing the distillate through a paper filter wetted with water.


The author has found this process efficient for procuring a clear solution of arsenic terchloride from such different substances as ordinary food —the liver and other soft organs—the scalp of the head—blood—contents of the stomach—arsenical wall-papers—metallic copper—blue vitriol—and various mineral powders. He thus discovered arsenic in two ounces of the earth of cemeteries, as well as in the mud of rivers, in spite of the presence of much earthy matter. Wherever the arsenic admits of solution in hydrochloric acid, however small the quantity present, it may be readily obtained as chloride. This distillation-process has the advantage of not interfering with the search for mercury, lead, copper, and other poisonous metals which do not form volatile chlorides. Arsenic is thus separated from them, and these metals may be found in the residue contained in the flask or retort. Even antimony, which forms a volatile chloride, is not so readily distilled over as arsenic. (On the diffusion of arsenic and the detection of this poison in the bones, see a paper by Sonnenschein, Horn's 'Viertel-jahrsschrift,' 1870, p. 169.)

The distilled liquid may be at once submitted to a further analysis. For this purpose one-third of it should be diluted with three or four parts of water and boiled in a clean flask. When boiling, a piece of bright copper-foil (free from arsenic), of about the size of the sixteenth of a square inch, should be introduced at the end of a platinum wire. If there is arsenic in the liquid, even up to the 1-4000th of a grain, its presence will be indicated by a change of colour, and by the deposit of a dark *metallic film on the copper*. If the liquid should be too much

diluted for this purpose, it may be concentrated on the polished copper, and the deposit will after a time be apparent. If the quantity of arsenic present is believed to be very small, the surface of copper introduced should be proportionately small. Add to a solution of stannous chloride its bulk of fuming hydrochloric acid. Warm this mixture, and then add to it a few drops of the distillate. The presence and proportion of arsenic are indicated by a dark brown precipitate consisting of reduced arsenic. (Wiggers' 'Jahresbericht,' 1871, p. 528.)

The remaining two-thirds of the distilled liquid, sufficiently diluted, should now be introduced into a Marsh's apparatus, or into an evolution flask provided with a funnel-tube, the capacity of which must be regulated by the quantity of acid liquid to be examined. The kind of apparatus employed in this stage is represented in the engraving, fig 19. A, the flask,

Fig. 19.



Apparatus for testing arsenic terchloride obtained by distillation.

Fig. 20.




Portion of tube separated with a deposit of metallic arsenic in the contracted portion.

with funnel-tube B, and connecting-piece C; the funnel-tube should be long enough just to dip below the surface of the acid liquid. The short connecting-piece is bent at a right angle, and, like B, is carried through a closely-fitting cork in the neck of the flask. This tube should be only long enough to go through the cork, and its open end should be bevelled off to a fine point, so that any vapour which is condensed on it may fall back as liquid into the flask. D is the drying-tube containing fragments of calcium chloride, secured by cotton-wool at both ends. At the flask end of this tube should be placed some well-dried bibulous paper, saturated with lead acetate and dried. This has the advantage of stopping any gaseous sulphur-compound, which may escape from the zinc or acid liquid. E E, a hard and not easily fusible glass tube, free from lead, contracted in two situations K K', to about the diameter of the tenth of an inch or less, the tube itself having a diameter of from a quarter to three-eighths of an inch. F F are supports made of stout wire, to prevent the tube from falling when heated to redness. G is a test-glass to hold one or two drachms of a strong solution of silver nitrate. H is a Bunsen's burner.

The arrangement being thus made, the zinc and hydrochloric acid are first tested as to their freedom from arsenic. Portions of pure zinc are placed in the flask A, the parts of the apparatus are then connected, and pure hydrochloric acid, diluted with three or four parts of water, is poured into the flask by the funnel B, which operates as a safety-valve. Bubbles of air and gas speedily appear in the liquid in G, if the corks fit well, and *the whole* of the arrangements are air-tight. Pure zinc is sometimes but

ctly acted on by the acid. In this case some clean platinum wire, may be wound round the bars of the zinc, and the evolution of n will be thus accelerated. It is, r, better that the hydrogen should f rather slowly. If the materials are ne solution of silver nitrate should) no change of colour. The glass G be placed on a sheet of white paper, r the slightest tinge of colour is erceptible. When all the air is ex- from the tube, the flame H may be to it at about one inch in front ntraction of the glass, as indicated engraving, and the glass heated to . No metallic deposit should take t K. If the materials are pure, sparency of the glass tube at K will hanged. From a quarter to half r will be sufficient for this experiment. A portion or the whole listillate is now added to the acid liquid in the flask by means of nel-tube, taking care that it is never more than one-third full. st indication of the presence of arsenic is manifested by the olution becoming gradually brown, and finally black, a dense ate of metallic silver resulting from the chemical changes. If it become very suddenly black and flaky, the presence of sulphur suspected. This will be further indicated by a change of colour lead paper in D. Pure arsenetted hydrogen does not alter the of this paper. When the silver solution is nearly blackened, the nay be applied as indicated in the drawing, and kept steadily at int. At a red heat, visible in daylight (1200° F.) arsenetted en is decomposed, and metallic arsenic is deposited; but being a metal, it is carried onward by the hot current of gas, and forms a brown and then a black metallic mirror at K, *i.e.* in the con- part of the tube which is cool. When a sufficiently thick deposit ned, the flame may be applied to the tube about an inch in front of us as many deposits of metallic arsenic may be procured, as there tractions in the glass tube.

Fig. 21.



Tube apparatus for testing a small quantity of liquid containing arsenic chloride.

silver solution is allowed to become saturated with the gas. Any of the gas from the glass, or by leakage from any of the junctions apparatus, is at once indicated by holding near to the spot, filtering moistened with a solution of silver nitrate. This is instantly blackened. ss with the silver solution is then removed, the end of the tube well , or another tube substituted for E E, and this is allowed to dip into ne drachm of the strongest fuming nitric acid, in a test-glass similar into a small porcelain capsule. After a time, the acid loses its and the arsenic is converted into arsenic acid, which may be obtained oration.

further testing of the products is a very simple process. 1. The olution contains arsenic in the state of arsenious acid, with some cid and the excess of silver nitrate. By one or two filtrations ained colourless and clear. A weak solution of ammonia is then o it, and yellow silver arsenite is at once precipitated (see p. 266). nitric acid liquid is evaporated to dryness in a small porcelain . One or two drops of water are added to the residue, with a weak ammonia *if it should* be very acid. A strong solution of *itrate is then added to it*: silver arsenate, of brick-red colour, is


immediately produced. 3. The portions of tube x x' with the metallic deposits in them may be separated by a file, and then hermetically sealed, or, if necessary, one or more of them may be tested by the methods described in a preceding page (see p. 265).

With these results the evidence of the presence of arsenic may be considered as conclusive. The poison is obtained by this process, not only in the metallic state, but in the distinct forms of its two well-known oxides—arsenious and arsenic acid. Reinsch's process is here employed merely as an adjunct to Marsh's process, in an improved form in which the burning of the gas is unnecessary. The arsenic by distillation is first converted into chloride, the chloride into hydride, and the hydride into the respective oxides. In the different stages of this operation, all other metals, excepting antimony, are entirely excluded, and this, under the circumstances, may be easily distinguished from arsenic (see Antimony). The zinc which has been used for one experiment is not fitted for use in a second.

Schneider was the first to suggest a method of extracting arsenic from organic matter as a volatile chloride. For this purpose he employed sulphuric acid and common salt. It has the disadvantage of introducing much mineral matter into the substance distilled—as well as of producing a large amount of froth, and thus embarrassing the operation. The modification of it above described, in which pure hydrochloric acid alone is required, will be found more convenient in practice. It is, however, not easy to obtain fuming hydrochloric acid of sufficient purity for the operation.

Reinsch's process alone may be employed for detecting arsenic, deposited as a result of absorption, in the liver, kidneys, or other organs. About four ounces of the recent organ, or more if necessary, cut into very thin slices, should be boiled in a flask in a mixture of one part of pure hydrochloric acid and two of water, until the structure of the organ is broken up. The flask may be of the shape represented in the annexed engraving (fig. 22), and either a naked gas- or spirit-flame or a sand-bath may be employed. A small glass funnel should be placed in the neck of the flask. This receives and condenses the vapour, which falls back into the flask. By this arrangement the boiling may be continued for a long time, without material loss by evaporation. The flask should not be more than half full, and heated gently until all froth is expelled. A slip of fine platinum-wire, having a small piece of pure copper-foil or gauze attached, should be immersed in the liquid when boiling. This enables the operator to remove the copper and examine it at intervals, after immersing it in distilled water. If it is much coated with a metallic deposit, larger portions of copper foil may be successively introduced until the liquid is exhausted. The deposits on the copper may then be tested by the methods described at page 268. This process will detect arsenic in the urine and saliva eliminated from the living body, and in all liquid articles of food.

Fig. 22.



Flask employed in the analysis of substances by Reinsch's process.

When hydrochloric acid is diluted with this proportion of water, little or no volatile arsenic terchloride distills over. In reference to the recent organs, a larger proportion of acid is used, because three-fourths of the weight of the animal substance really consist of water.

The method of Fresenius and Babo is preferable to all others for the *destruction* of organic matters, and the obtaining of arsenic from organic *mixtures*, *the* solid organs, &c. The substance to be examined—if a *solid, finely* shred—is placed in a porcelain dish, and treated with a quantity

of hydrochloric acid of the sp. gr. 1·12 equal to, or rather exceeding, the weight of the dry substances present, and sufficient water to give the entire mass the consistence of a thin paste. The quantity of hydrochloric acid added should never exceed one-third of the entire liquid present. Heat the dish on a water-bath, adding from time to time—say every five minutes—two grains of potassium chlorate for each fluid ounce of liquid in the dish, with stirring, until the contents of the dish are light yellow in colour, homogeneous, and fluid. A further addition of hydrochloric acid may be requisite when much chlorate is added, for the destruction of the organic matters. The operation is completed when the liquid after a fresh addition of either chlorate or acid does not deepen in colour when heated anew on the water-bath for a quarter of an hour. When this point is attained, add again a little chlorate, and then cool the dish. When quite cold, strain the contents through linen or a filter, wash, and heat the filtrate on the water-bath, with renewal of the evaporated water, until all odour of chlorine, or nearly so, has disappeared. The liquid thus obtained, measuring about thrice the bulk of the hydrochloric acid employed, is transferred to a flask and heated to from 150° to 160° F., and a slow stream of washed sulphuretted hydrogen gas is passed through it for twelve hours. The flask is then cooled, with continual transmission of the gas. The stream of gas is now suspended; and the flask is set aside, lightly covered, in a warm place (85° to 90° F.) until the odour of sulphuretted hydrogen has nearly disappeared. Any precipitate which forms is collected on a filter, and washed with water containing sulphuretted hydrogen till the washings are quite free from chlorides. The precipitate contains the arsenic, and also any antimony, mercury, lead, or copper, which may be present, and free sulphur. Dry the precipitate on the filter in a dish on the water-bath; and then add pure fuming nitric acid (free from chlorine), drop by drop, until the mass is completely moistened; re-dry; and moisten the dry residue with pure warm concentrated sulphuric acid. Heat for two or three hours, first on the water-bath, and then in the air-bath at 340° F. until the charred mass is friable. The mass may, indeed, be heated till the fumes of sulphuric acid begin to be evolved. Warm the residue with a mixture of eight parts of water and one part of hydrochloric acid, filter, and reprecipitate as before with a stream of sulphuretted hydrogen gas. The precipitate which falls will contain all the arsenic in the form of sulphide. This precipitate collected, washed, and dried with the precautions already pointed out, when mixed with a dry mixture of potassium cyanide and sodium carbonate, and heated in a tube through which a stream of carbonic acid gas is passed, will yield a brown glistening sublimate of metallic arsenic, which may be weighed, and to which all the tests for arsenic may be applied.

Armand Gautier has also recommended an excellent method of getting rid of the organic matter in arsenical liquids ('Bull de La Soc. Chim. de Paris,' Oct. 5, 1875).

It is important, in reference to the presence of absorbed arsenic in the tissues, to observe that it may be found at an early period, when it is either absent or only doubtfully present in other parts. A man died within *four hours* after he had been attacked with symptoms of poisoning by arsenic. Arsenic was found in small quantity in the stomach, duodenum, and rectum. It was also detected in the liver and spleen; and the proportion found was greater in the latter than in the former organ. A man died from the effects of arsenic in the most acute form, soon after his admission into Guy's Hospital. He had swallowed a large dose of the poison in water. He was brought to the hospital, and died soon afterwards. Barely *three hours could have elapsed from* the time at which the poison was taken

until his death. There were the usual appearances in the stomach; sm gritty portions of arsenic mixed with masses of coagulated mucus, an false membrane, were found in the contents. The intestines were inflamed and portions of arsenic were discovered as low as the cæcum. Arseni was found abundantly in the stomach, and a comparatively large quantity of the poison was detected in half an ounce of the dried liver, as well a in the spleen and kidney. Hence it is obvious that the poison may b rapidly absorbed and copiously deposited within *three* hours, the quantity thus found depending apparently on the dose taken. In the cases of th *Atlee* family, in 1854, the body of the mother was exhumed after a month Arsenic was *not* found in the *stomach* or *bowels*, but it was readily detected in a small portion of the *liver*. The poison had probably been take several days before death. The fact is of considerable importance i relation to a medical opinion of the presence or absence of poison in a dea body. It is clear, from the above cases, that an opinion might be erroneou unless the liver or spleen had undergone a chemical examination. I preserving viscera for analysis, a portion of the liver should therefor always be set apart for examination. If the person has lived fifteen o sixteen days after having taken the poison, no trace may be found in th tissues or in any part of the body. Orfila long since expressed this opinio from his experiments on animals; its correctness has been strikingly confirmed by the case of *Dr. Alexander*, who died in *sixteen days* from a large dose of arsenic taken by mistake in arrowroot. Geoghegan found no trace of the poison, either absorbed or unabsorbed, in any part of the body which he examined. ('Med. Times and Gaz.' April 18, 1857, p. 389.) It is the more necessary that the fact of entire elimination should b remembered, because it has been impressed on the public mind that no person can have died from poison, except the poison be present in the body after death. If this is untrue with respect to arsenic, it is necessarily untrue with regard to poisons less easy of detection in minute quantities.

In the case of the *Queen* v. *Williams* (South Wales Circuit, July, 1863), a woman was charged with the murder of her husband by administering to him arsenic. The evidence left no doubt that deceased had suffered from the usual symptoms of poisoning, namely, inflammation of the stomach and bowels, numbness of the limbs, and other symptoms. For some days before the deceased's death, owing to his food having been prepared for him by his daughter, the symptoms abated; but he ultimately died from exhaustion on the fifteenth day. Herapath examined the viscera, and found no arsenic. Neither in his reading nor in his experience had he known arsenic to have been detected fifteen days after its administration. As no poison was discovered in the body, the prisoner was acquitted on the charge of murder, but found guilty of the intent. ('Lancet,' 1863, II. p. 47.) In the case of *Souffiard*, a large dose of arsenic had been taken; but according to Legroux, no trace of the poison existed in the stomach or in the ulcerated portions of the bowels. ('Union Méd.' June 30, 1850). Otto met with a case of death from arsenic within twenty-four hours, with the usual symptoms and appearances, but no arsenic could be found in the contents of the stomach. The liver and other organs were not examined (Horn's 'Vierteljahrsschr.' 1865, 1, 175). When arsenic is discovered mixed with food in the stomach, it does not necessarily follow that it has been administered in that particular article of food. Should the person have partaken of liquid food such as milk or *gruel*, subsequently to the swallowing of arsenic, these fluids will necessarily *acquire* an arsenical impregnation from the poison already contained in the *stomach*. The patients may have taken the arsenic in one kind of food,

hen another and an innocent description of food might thus inadvertently e pronounced to have been the vehicle. (See case of *Ann Merritt*, London Med. Gaz.' Aug. 16, 1850, 46, 291.)

It need hardly be observed that the *quantity of arsenic found in the tomach* or other organs can convey no accurate idea of the quantity ctually taken by the deceased, since more or less of the poison may have een removed by violent vomiting and purging, as well as by absorption nd elimination. A large quantity found in the stomach or bowels indicates large dose; but the finding of a small quantity does not prove that the ose actually taken was small. Notwithstanding these very obvious causes r the removal of a poison from the body, there is a prejudice that the hemical evidence is defective unless the quantity found is sufficient to ause death. The value of chemical evidence does not always depend on he discovery of any particular *quantity* of poison in the stomach, but he evidence of its presence should be clear, distinct, conclusive, and tisfactory. At the same time, a reasonable objection may be taken to dogmatic reliance upon the alleged discovery in a dead body of minute actional portions of a grain.

It has been supposed that the *quantity* of arsenic found in the stomach nd bowels may throw a light on the question, whether the poison had een taken voluntarily with the intention of committing suicide, or whether t had been criminally administered by another. There is no doubt that a uch larger dose may be taken by a suicide than could be secretly administered by a murderer. Suicides have been known to take as much as wo tablespoonfuls, or *one thousand grains*, of arsenic. In a case of suicide y arsenic, which occurred at the Bristol Infirmary in 1872, a larger antity had been taken. On a *post-mortem* examination, four ounces of enic were found in the stomach, of which two and a half ounces ere in one mass. The woman, when brought to the hospital, was in a ate of complete collapse. Death took place rapidly. ('Pharm. Jour.' ly 27, 1872, p. 75.) How much may remain in a dead body must depend n the amount of vomiting and purging, and the length of time the person rvives. In the case of *L'Angelier* (*Reg.* v. *Madeline Smith*, Ed. High urt of Justiciary, June and July, 1857), Dr. Penny stated in evidence at the quantity of arsenic which he found in the stomach and contents f the deceased amounted to 88 grains, and that some part of this was in rd, gritty, colourless, crystalline particles. As there was arsenic in the ntents of the intestines, and there had been vomiting and purging, it is vious that the deceased must have taken a very large dose of the poison; d it was one of the suggested difficulties of this case, to determine how e deceased could have taken the poison in so large a quantity unknowngly. The quantity found, however, amounted to no more than half a aspoonful; and admitting that one half of the dose taken had been ected, the question resolves itself into this: whether a teaspoonful of enic might not have been homicidally administered in chocolate, gruel, some thick liquid, or in a state of admixture with solid food (cake). lthough it is unusual to find half a teaspoonful of arsenic remaining in e stomach in a case of homicidal administration, it is impossible to mit that this fact is inconsistent with an act of murder. A man half oxicated might be thus poisoned; and if death took place in a few hours, en a larger quantity than that which was here found might remain in e stomach. Christison set this question at rest by the publication of a se in which a man was homicidally destroyed by arsenic, and the antity found in the stomach after death was from 90 to 100 grains. The an had survived from five to seven hours, and there had been frequent omiting of a yellowish *or greenish* coloured liquid during this period.

The arsenic was administered in whiskey-punch with sugar, and it kept in suspension by constant stirring. ('Ed. Month. Med. Journ.' 1857, p. 481.) In *Regina* v. *Dodds* (Lincoln Ass. Dec. 1860), the prisone charged with administering arsenic to the deceased with intent to m The quantity stated to have been found in the stomach was 150 g There was no reason to suppose that he had taken the poison with su intention; but. on the contrary, there was strong evidence to presume it had been administered to him with a design to destroy life. A w named *Alice Hewitt* was tried (*Reg.* v. *Hewitt or Holt*, Chester Winte 1863), and convicted of poisoning her mother with arsenic. Althoug symptoms of irritant poisoning were very clearly marked, a medica who attended her certified the cause of death as gastro-enteritis. F weeks after the burial of the deceased, the body was exhumed and exa It was proved that shortly before her mother's death, the prisone purchased a quarter of a pound of arsenic, and there was clear evidence ministration, a large dose having been given to the deceased in liquid s before her death. The inspection revealed the extraordinary fact tha grains of solid arsenic were found in the stomach alone. It had bee tially converted into sulphide as a result of putrefactive changes, and i observed that the liver, omentum, and right side of the heart were th coated with yellow arsenious sulphide. In reference to this colour the front of the spinal column behind the stomach has been seen ting a deep yellow from arsenic which had escaped through the coats o organ. If a person has died with arsenic in the body, there is sc any limit to the period at which it may be detected. In the cases o children examined by Herapath, in 1849, the poison was discover the remains of the dead bodies after eight years' interment; in a case by Glover after twelve years ('Lancet,' July 9, 1853, p. 41 in a remarkable instance which occurred to Webster, of Boston, discovered in the remains of a body, after fourteen years' burial. been sought for, and not found, at much shorter periods after dea there was a very strong suspicion that the poison had been taken; highly probable that in these cases there was little or no arseni bodies at the time of death. With respect to its detection in the and bowels, if the vomiting and purging have been violent, and t has survived some days, none may be found. It is singular, to notice with what tenacity the mineral occasionally adheres to t membrane in spite of vomiting and purging. In the case of *Praslin*, who died in six days from a large dose of arsenic, so was still found in the intestines ('Ann. d'Hyg.' 1847, p. 402) case which was the subject of a criminal trial (Leicester Aut *Reg.* v. *Holmes*), arsenic was detected in the intestines, a deceased had survived the effects of a large dose for seven d suffered from the usual symptoms. The preservative effects c the solid organs of the body has been already noticed (p. 10 suspicion of poisoning with arsenic, ten bodies were exhumed of St. Colens, in 1869. Charbonnier found that arsenic w quantity in two of the bodies which had been well preserve no offensive smell of putrefaction about them, but a remark odour like that of phosphorus ('Ann. d'Hyg.' 1872, Juillet, was attributed to the probable escape of arseretted hydrog of decomposition. In several cases of exhumation, in wh discovered in the bodies, no odour of the kind has been per

The condition of the arsenic found in a dead stomach sh be noticed. A witness should be prepared to say whet powder or coarse fragments; whether it is mixed with s

whether it is in the ordinary state of white arsenic. These points may be material as evidence in reference to proof of possession, of purchase, or administration. Arsenic is *not* a normal constituent of the body. Under no circumstances is it found in the tissues after death, except in cases in which it has been taken by or administered to the deceased.

Potassium Arsenite, or Arsenite of Potash. Liquor Arsenicalis. (Fowler's Solution.)—*Symptoms and Appearances.*—There is, perhaps, only one case recorded in which Fowler's solution has destroyed life. A woman took half an ounce (= two grains of white arsenic) in divided doses, during a period of five days, and died from the effects. There was no vomiting or purging, but after death the stomach and intestines were found inflamed. ('Prov. Jour.' June 28, 1848, p. 347.)

A mixture of white arsenic, soft soap, and tar-water, is largely used in agricultural districts for killing the fly in sheep. This has caused death, under the usual symptoms of arsenical poisoning, in several instances. In 1874, the *Coombs* family, consisting of eight persons—the father, mother, and six children—were all poisoned by drinking water from a bucket which had contained an arsenical sheep-dipping composition. The mother and three of the children died. The symptoms produced were unusual; diarrhœa being a less prominent symptom than vomiting. The poison appeared to exercise a profound impression upon the nervous system, producing tetanic spasms, and convulsions. An arsenical rash was a characteristic of the severest and fatal cases. In the bodies of the mother and one child the editor detected arsenic. The bodies of the other two children were not examined for poison.

Analysis.—Fowler's solution is a solution of arsenite of potash. It has the odour of tincture of lavender, is of a reddish colour, and has an alkaline reaction. One fluid ounce of it contains four grains of arsenious acid. It gives at once a green precipitate (copper arsenite) with copper sulphate, and a yellow precipitate with silver nitrate. Acidulated with hydrochloric acid, and treated with a current of sulphuretted hydrogen gas, it yields a yellow sulphide; and when boiled with this acid and copper, a deposit is obtained which readily furnishes octahedral crystals of arsenious acid. When boiled with stannous chloride (see p. 264), metallic arsenic is deposited as a brown precipitate.

Arsenite of Soda is as poisonous as arsenite of potash. In Dec. 1857, three hundred and forty children belonging to an industrial school near London were poisoned by this compound. It had been incautiously used for cleansing a steam-boiler, and had thus become mixed with the hot water which was drawn for the breakfasts of the children. The dose of arsenic taken by each child was about one grain. All recovered, although some suffered severely. (See 'On Poisons,' 2nd edit. p. 378.) In the winter of 1863, a man died under symptoms of acute poisoning by arsenic, owing to his having drunk beer out of a pot which had contained this patent cleansing liquid.

Fly-water is a name applied to solutions of various arsenical compounds in water. Mixtures of this kind are formed by dissolving one part of the arsenite of soda or potash and two parts of sugar in twenty parts of water. Paper soaked in this solution, and dried, is used for poisoning flies; and perhaps this is the safest form in which arsenic can be used for such a purpose. A case of poisoning by fly-water, in which two grains and a half of arsenious acid destroyed the life of an adult in thirty-six hours, is reported. ('Med. Gaz.' vol. 39, p. 116.) Fly-powder is a dark-coloured mixture of metallic arsenic and arsenious acid.

Arsenite of Copper. Copper Arsenite. Scheele's Green. Emerald

GREEN.—This is the only metallic arsenite which is met with in commerce and the arts, and it constitutes, wholly or in part, a great variety of green pigments, known as emerald green (aceto-arsenite of copper) employed for paper-hangings, mineral green, Brunswick, Schweinfurt, or Vienna green. It is thus found in the form of oil-paint, in cakes of water-colours, wafers, adhesive envelopes, or, rarely, spread over confectionery; and lastly, and most abundantly, in various kinds of green decorative papers used for covering the walls of rooms.

Symptoms and effects.—Although copper arsenite is insoluble in water, it is sufficiently soluble in the acid fluids of the stomach to be taken up by the absorbents, and carried as a poison into the blood. A boy, aged three years, swallowed a small capsule of Scheele's green, used as a pigment. In half an hour he complained of violent colic: there was frequent vomiting, with purging, cold sweats, intense thirst, and retraction of the parietes of the abdomen. The mouth and throat were stained of a deep green colour. Hydrated ferric oxide was given: in about an hour the vomiting ceased, and soon afterwards the thirst and pain in the abdomen abated. The next morning the child was well. In another case a child, a year old, ate several pieces of a cake of copper arsenite used for colours. There was immediate vomiting of a liquid containing green-coloured particles of the arsenite, but there were no other urgent symptoms. White of egg, with sugared water, was given. After a short time the child became pale and complained of pain in the abdomen: the pulse was frequent, the skin cold, and there was great depression. Copious purging followed, soon after which the child recovered. (Galtier, vol. 1, p. 636.) In the cases of two children poisoned by confectionery coloured with this substance, the chief symptom was incessant vomiting of a light green-coloured liquid, resembling bile diluted with water. ('Med. Times,' April 28, 1849, p. 507) The symptoms were described as severe, although the quantity of poison swallowed was small. Under the use of an emetic of ipecacuanha, the children recovered. (See also 'Guy's Hosp. Rep.' Oct. 1850, p. 218; 'Med. Gaz.' vol. 43, p. 304; 'Edin. Month. Journ.' July, 1851, p. 1; and 'Lancet,' March 5, 1859, p. 237.) In two cases in 1853, a small quantity of a confectionery ornament, coloured with copper arsenite, proved fatal to two children. The symptoms and appearances were those of poisoning by arsenious acid. The quantity taken could not have been above two or three grains. The children picked up the ornament in the street and shared it between them. The poison was spread over a layer of sugar.

In a case which was the subject of a criminal trial, this substance was proved to have caused the death of a gentleman by reason of its having been employed to give a rich green colour to some blanc-mange served at a public dinner:—the person who employed it considering that emerald or mineral green was nothing more than an extract of spinach, a substance from which the green pigment used in confectionery is made. It led to death under the usual symptoms, and the parties were convicted of manslaughter and sentenced to imprisonment. (*Reg.* v. *Franklin and Randall*, Northampton Sum. Ass. 1848.)

Among other uses of this noxious compound, it has been employed for imparting a bright green colour to the shelves of bakers' and greengrocers' shops. An incident which occurred to the author will show that food may thus acquire an arsenical impregnation. Several loaves of bread were supplied to him, having upon the undercrust some green-coloured pigment, which on analysis turned out to be copper arsenite, containing about *fifty* per cent. of arsenic. On inquiry, he found that the baker had *recently* painted the shelves of his shop with this pigment and the hot

es placed upon them had taken off a portion of the arsenical paint. ed. Times and Gaz.' April, 1854, p. 326.)

Another form of poisoning by this substance which has attracted e attention, is where the green pigment exists in the state of vapour ne dust, and comes in contact with the membrane of the lungs or with skin. A young man, after having been engaged for nine days in ting with an arsenical green pigment, was seized with irritation and ry discharge from the nose, swelling of the lips and nostrils, and lache. The next day he experienced severe colic, and great muscular kness: but these symptoms disappeared in about eight days. It is able that in this case, copper arsenite had been taken into the body ugh the mucous membrane of the lungs in the state of fine powder. ording to Bouchardat ('Ann. de Thérap.' 1846, p. 209), the work- who handle the emerald-green in making wall-papers are subject erious disorders of health. They sometimes suffer from eruptions of skin—one of the local effects of poisoning by arsenic (see 'Assoc. Med. .' 1856, Sept. 6, p. 757, and Sept. 20, p. 810), with œdema (watery ling) of the face, and boils frequently forming in the scrotum. There rritation with discharge of fluid from the mucous membrane of the , and abundant salivation. In the more advanced stage there are ky pains, frequent vomiting, headache, and prostration of strength. an. d'Hyg.' 1847, 2, 56; a paper by Vernois, 1859, 2, pp. 107, 319; per's 'Vierteljahrsschrift,' 1859, 2, p. 8; and 'Jour. de Chim.' 1858, 394, 397.)

Wall-papers covered with the loosely-adhering aceto-arsenite of copper e formerly, from their cheapness as well as their brightness of colour, nsively used in dwellings. This pigment contains fifty-nine per cent. of nic, and from some of these papers in the unglazed state, the noxious erial may be easily scraped or removed by friction. A square foot may d from twenty-eight to seventy grains of the arsenical compound, and in ns exposing five or six hundred square feet, arsenic is thus liable to be ributed in the state of a fine dust or powder through the air of a room. s poisonous dust has been detected on books, picture-frames, furniture, projecting cornices in rooms thus papered. Workmen who hang these ers or who strip them off the walls, suffer from symptoms referable to the action of arsenic. (See Husemann, 'Jahresber. der Toxicol.' l, p. 525, and 'Pharm. Jour.' 1870, p. 218; also 'Lancet,' 1870, II. 56.) One of the author's friends who had his library papered with arsenical wall-paper, suffered severely from symptoms of arsenical oning, which came on after he had been occupied in dusting his books. dust contained a well-marked quantity of arsenic. Roussin has ed the means by which this insoluble poison finds its way through skin, and the circumstances under which it may be absorbed by the roken skin. In two cases which proved fatal in 1865, the workmen ered chiefly from vomiting and colicky pains. The skin was tinged green colour, and arsenic was detected in the soft organs. He found all poisons were liable to be absorbed by the unbroken skin, when as sult of evaporation a solid film was left on the surface. Alcohol and r solvents of fat when used as solvents for the poisonous solid would ur its absorption into the body. ('Ann. d'Hyg.' 1867, II. pp. 179, .) Kirchgässer has published an elaborate paper on this chronic form oisoning, which he calls 'Arsenicism.' He has collected twenty-one s of poisoning, as the result of persons inhabiting rooms the walls of ch were covered with this green arsenical pigment. Some of these red fatal. The poison appears to have entered the body in the form fine powder or dust. *Arsenic* was in many cases detected in the urine

of the patients. (Horn's 'Vierteljahrsschr.' 1868, 2, 96; also 'Ann. d'Hyg.' 1869, 1, 480.) Delpech has published some facts which show that similar symptoms of poisoning have arisen from a person occupying a room filled with stuffed birds and animals, in the preservation of which an arsenical compound had been used. Arsenic was found in the dust of the room and on the furniture. ('Ann. d'Hyg.' 1870, 1, 314.)

The *symptoms* produced are of a uniform character, showing their origin from a common cause. They are as follows:—dryness and irritation of the throat, dry cough, irritation of the mucous membrane of the eyes and nostrils, languor, headache, loss of appetite, nausea, colicky pains, numbness, cramp, irritability of the bowels, attended with mucous discharges, great prostration of strength, sleeplessness, a feverish condition, and wasting of the body. These symptoms may not all present themselves in any one case. No suspicion of the cause may have been entertained until all ordinary treatment had failed to impart relief, and an analysis of the paper has been made. The connection of the symptoms with this cause appears to have been in some instances clearly established by the fact that after the removal of the paper, especially from bedrooms, the symptoms have disappeared. ('Med. Times and Gaz.' 1871, 1, p. 674.) It is, however, proper to observe that, as in reference to the manufacture of white lead, comparatively few of those who are exposed suffer from symptoms of poisoning.

Various deaths from the use of these arsenical papers are recorded; and it is probable that to the practice of covering the walls of sitting and bedrooms with arsenic, many insidious cases of illness and chronic disease may be referred. The arsenical compound has also been much used for colouring artificial flowers, wreaths, and tarlatan dresses. Dressmakers occasionally suffer seriously from this form of poisoning. Two women were employed to make some green tarlatan into ball-dresses. They noticed an unpleasant smell and taste, and their eyes were affected during the performance of the work. The symptoms from which they suffered were swelling of the eyelids, congestion of the conjunctivæ, and copious secretion of tears. The one most affected experienced on the second day salivation, with an unpleasant taste in the mouth, cramps in the limbs, great thirst, restlessness, and difficulty of breathing. These symptoms lasted in one patient eight and in the other fourteen days. Riedel, who describes these cases, suffered severely from a similar train of symptoms for several days, as a result of handling the poisoned dresses for the purpose of analysis. He found that the stuff contained thirteen per cent. of its weight of arsenic. (Husemann, 'Jahresber. der Toxicol.' 1871, p. 525; 1872, p. 480.) To this list may be added the case of a lady (July, 1872) who suffered severely from symptoms of arsenical poisoning, by reason of her having worn, on one occasion only, a dress of this description. Paper used for adhesive envelopes, for wrapping confectionery, children's food, isinglass, chocolate, &c., is also occasionally coloured with arsenical pigments.

Analysis.—For the chemical characters of SCHEELE'S GREEN, see page 266. The pigment called EMERALD GREEN is a mixture of copper acetate and arsenite. The colour is most intense even by candle-light. The presence of arsenic in this compound may be easily detected by the tests for arsenic (pp. 263–269); but the following is a simple method, which admits of speedy application. A slip of the suspected paper should be soaked in a moderately-strong solution of ammonia. The colour is removed, and a blue amide of copper is formed and dissolved in a few *minutes*. This result establishes only the presence of a compound of *copper* soluble in ammonia. If the ammonia does not become blue then

is no copper present: if it does become blue, a crystal of silver nitrate must be placed in a white saucer and a small portion of the blue liquid poured over it. The presence of arsenic is revealed by the production of yellow silver arsenite over the surface of the crystal (page 266). Another method consists in adding a fragment of the paper to boiling stannous chloride, acidulated with fuming hydrochloric acid. Metallic arsenic is precipitated of a brown colour. A small portion of the paper dissolved in hydrochloric acid added to the apparatus represented in fig. 21, page 273, will set free arsenic in the form of arsenetted hydrogen.

ARSENIC ACID. ALKALINE ARSENATES.—Arsenic acid is an artificial product much used in the arts and manufactures. Orfila states that it is a more powerful poison than arsenious acid, but he does not adduce any instance in support of this opinion. Maumé, on the contrary, states that it is less poisonous than arsenious acid. No case of poisoning by it in the human subject is reported. Glover ascertained that four grains of the acid, dissolved in two drachms of water, and introduced into the stomach of a rabbit, killed the animal in four hours with the symptoms of irritant poisoning, and an affection of the nervous system. ('Ed. Med. and Surg. Jour.' vol. 58, p. 121.)

Arsenic acid is largely employed in the manufacture of magenta, rosaniline, and other colours from aniline. There is reason to believe that the colour is often sent into the market contaminated with arsenic. Rieckher has found from one to seven per cent. of arsenic acid in the red colours supplied by good manufacturers, and frequently arsenious acid was also present. ('Med. Times and Gaz.' 1870, 1, 617.) As these red compounds are used for giving a beautiful red colour to liqueurs, syrups, raspberry vinegar, and sugar sweetmeats, there is a possibility that accidents may occur from their use. They are rich in tint and of great cheapness. ('Med. Times and Gaz.' 1870, 1, pp. 46, 84.) The injurious effects of several of these coal-tar pigments when used for dyeing socks and gloves have been ascribed to the arsenic contaminating the dyes.

Analysis.—Arsenic acid is a white noncrystalline deliquescent solid. 1. It is not entirely volatilized when heated on platinum-foil in the flame of a lamp. 2. It is very soluble in water, forming a highly acid solution. 3. It is precipitated of a brick-red colour by silver nitrate or ammonio-nitrate. In these characters it differs from arsenious acid. 4. It yields readily an arsenical sublimate when heated with charcoal. 5. It yields deposits by Reinsch's process (page 267), but less readily than arsenious acid.

The arsenates of potash and soda must be regarded as active poisons, although there are but few instances on record in which life has been destroyed by them. The *tests* are the same as for arsenic acid. Arsenic acid and the arsenates yield a brown deposit of metallic arsenic when added to a boiling solution of stannous chloride (see page 264). A coarse sort of blotting-paper, soaked in a solution of arsenate of potash, is extensively sold for killing flies under the name of '*Papier Moure.*' It has been erroneously represented that the substance with which it is impregnated, is not poisonous to human beings. ('Lancet,' Feb. 11, 1860; also 'Ann. d'Hyg.' 1860, 1, 292.)

SULPHIDES, OR SULPHURETS OF ARSENIC. ORPIMENT.—Orpiment, or yellow arsenic, owes its poisonous properties to the presence of a variable proportion of arsenious acid, sometimes amounting to as much as thirty per cent. of its weight. The editor met with a fatal case in 1865. Orpiment is much employed in the arts, in painting, dyeing, paper-staining, and even in the colouring of toys and sweetmeats for children, but is not often used as a poison. In December, 1859, six persons suffered from the usual symptoms of poisoning by arsenic, owing to their having

caten *Bath buns*. It was found that a confectioner at Clifton had used, as he supposed, chrome yellow (lead chromate), to give the buns a rich yellow colour, and make them saleable; but the druggist to whom he applied had ignorantly supplied him with orpiment. This wholesale system of poisoning is one of the attendant evils of adulterating articles of food. The *Bradford lozenge cases* (Nov. 1858) furnish a remarkable instance of the impunity attendant upon acts of this kind. A confectioner, intending to adulterate lozenges with plaster of Paris, mixed with them a quantity of white arsenic which had been supplied to him through mistake for the plaster. More than 200 persons partook of these poisoned lozenges, and suffered the usual effects. Seventeen persons died: twelve from acute poisoning, and five from the secondary effects. A trial took place, but the law could not fix the responsibility for the act upon any person. Orpiment mixed with lime is extensively used in the process of felmongering, for the purpose of removing the wool of the sheep from the hide. The editor has seen severe injuries result from the mixture coming accidentally into contact with the skin of those engaged in the trade.

Symptoms and Appearances.—Orpiment produces symptoms and appearances similar to those caused by arsenious acid; but the dose required to destroy life varies according to the proportion of arsenious acid with which it happens to be mixed. This is not a common form of poisoning; the yellow colour of the poison would lead to suspicion: but by reason of this colour, orpiment may be given or taken by mistake for mustard or turmeric. In one case, two persons partook of some porridge, in which orpiment had been put by mistake for turmeric. They suffered from continual vomiting, burning pain in the stomach, and collapse. One, an old man, died in twenty-two hours; the other, a boy, recovered. On inspection, there was violent inflammation of the gullet and stomach, the mucous coat of the latter being softened and thickened. There was a sphacelated spot, one inch in diameter, in the gullet; and another in the stomach, three inches in extent. (Wharton and Stille, 'Med. Jur.' p. 434.) According to Chevers ('Med. Jur. for India,' p. 74), orpiment is much used in India both as a medicine and as a poison. He refers to eight instances in which this poison was found, either in food, or in the stomachs of persons who had died under symptoms of irritant poisoning. Orpiment and realgar (another sulphide of arsenic) are sold openly in India, and are used as depilatories. Orpiment has been known to cause death by *external* application as a depilatory (see 'Ann. d'Hyg.' 1834, 459).

Analysis.—The powdered sulphide yields a solution of arsenious acid on boiling it in water acidulated with hydrochloric acid. It readily gives the well-known sublimates of metallic arsenic, both with soda-flux and potassium ferrocyanide (see p. 264). *Organic mixtures.*—The sulphide being insoluble in water, it is in general easily separated mechanically, by allowing the matters mixed with it to become dry upon bibulous paper. If it cannot be separated mechanically, the organic matter suspected to contain it should be dried and evaporated to dryness with strong nitric acid, until it is destroyed. Any arsenic will then be found under the form of arsenic acid, soluble in water (see p. 283).

In *Reg.* v. *Sturt* (Lewes Lent Ass. 1863), a novel question arose respecting this compound. There was some reason to believe that the deceased woman had died from the effects of arsenic administered in confectionery. White arsenic was found in the stomach, and a question was put by the judge, as well as by the counsel for the prisoner, whether the confectioner might not have used yellow arsenic by mistake in order to give a colour, and this yellow arsenic have been converted in the deceased's body in twenty-four hours into white. It need hardly be remarked that

the yellow colour is an essential character of orpiment. White may be converted into yellow arsenic in the dead body, but yellow cannot be spontaneously changed into white arsenic.

CHLORIDE OF ARSENIC.—This is an official solution of arsenic in diluted hydrochloric acid. It contains four grains of arsenious acid in one fluid ounce, which is equal to half a grain to a fluid drachm. It is a highly poisonous preparation, and by a case in Guy's Hospital in May, 1857, this statement is confirmed. A woman took three doses in a period of twenty-four hours. The quantity of arsenic thus taken was not more than the *sixth part* of a *grain*, and yet the symptoms which followed were of a severe kind, resembling those of chronic poisoning. These were constriction of the throat, pain and irritation of the stomach and bowels, tingling and numbness of the hands and feet, loss of muscular power, and a feeling of extreme depression. The medicine (a poison) was withdrawn, and the patient slowly recovered. It seems that she had not taken arsenic previously, and there was no evidence of the existence of a peculiar susceptibility to the effects of arsenic. The quantity taken was very small to produce such alarming effects. The usual medicinal dose of this solution is from three to ten minims.

Analysis.—This compound is obtained in the separation of arsenic from organic solids by distillation (see page 270). It may be tested by the processes of Marsh and of Reinsch, as there described. When boiled with stannous chloride, it is decomposed, and metallic arsenic of a brown-black colour is deposited.

ARSENETTED OR ARSENIURETTED HYDROGEN.—This is a gaseous poison of arsenic, producing, when respired in small quantity, very serious effects upon the system. It has already occasioned death in several instances. (See 'ON POISONS;' 'Chem. News,' Dec. 26, 1863, p. 307; 'Jahresber. der Toxicol.' 1871, p. 522.)

CHAPTER 21.

POISONING BY MERCURY—CORROSIVE SUBLIMATE—SYMPTOMS—CHRONIC POISONING—FATAL DOSE—APPEARANCES AFTER DEATH—PERIOD AT WHICH DEATH TAKES PLACE—CHEMICAL ANALYSIS—PROCESS FOR MERCURY IN ORGANIC LIQUIDS—WHITE AND RED PRECIPITATES—OTHER MERCURIAL COMPOUNDS.

METALLIC Mercury is not usually regarded as a poison. A large quantity of it in the fluid state may often be swallowed without affecting health, or without causing more uneasiness than that which may arise from its great weight. It may, however, when swallowed, produce salivation and the other constitutional effects of mercury. It rapidly passes through the bowels. If the mercury is breathed or swallowed in a state of vapour, or if applied to the skin or mucous membranes in a state of minute mechanical division, in which state it appears to be easily susceptible of oxidation, it is liable to be absorbed, and to produce a poisonous action on the body. The effects are principally manifested by salivation, by trembling and involuntary motions of the limbs, loss of appetite, and emaciation. These symptoms are occasionally seen in workmen engaged in trades in which they are exposed to the inhalation of mercurial vapours. Cases of mercurial poisoning are not so frequent as those of poisoning by arsenic. In England and Wales, in the year 1880, seven deaths from mercurial poison were recorded.

Blue pill and *mercurial ointment* are preparations in which mercury is

finely divided, and probably, as in the mixture of mercury and chalk, more or less oxidized. A woman is reported to have died from taking excessive doses of blue pill ('Med. Times and Gaz.' 1863, 1, p. 446). Blue or mercurial ointment, which contains nearly half its weight of mercury, has attracted attention by reason of its poisonous effects on cattle. It is employed for the purpose of dressing sheep, in place of arsenic, and twenty-five tons of this ointment were sold in one year by a druggist in Boston, chiefly to farmers. Sheep poisoned with mercury ointment have been sent for sale to the dead-meat markets in London. This is an unsuspected source of noxious food to human beings.

Mercury with chalk is commonly regarded as an innocent medicinal compound of the metal; but if long kept and exposed to light a portion of the mercury passes to the highest state of oxidation, and thus produces a poisonous effect upon the system. This may account for the severe symptoms which have sometimes resulted from this preparation in medicinal doses. Duncan and Seely state that in one specimen which should have contained 37·5 parts of metallic mercury, 4·05 parts had become converted into black mercurous oxide, and 22·25 parts into red mercuric oxide.

Corrosive Sublimate.—This substance has received a variety of chemical names. It has been at various times called *Oxymuriate*, *Chloride*, *Bichloride*, *Mercuric Chloride*, and *Perchloride* of *Mercury*. To prevent any confusion from scientific chemical nomenclature, the old and popular name of *Corrosive Sublimate*, expressing the principal properties of the substance, is here retained. It is commonly seen under the form of heavy crystalline masses, or of a white crystalline powder. Its *taste* is powerfully austere and metallic, so that no poisonous quantity of it could be easily swallowed without a person becoming immediately aware of it. It is very *soluble* in water, hot or cold, and speedily sinks in it, in which properties it differs strikingly from arsenic. One hundred grains of a cold saturated solution hold dissolved about seven grains of corrosive sublimate; and one hundred parts of boiling water (212° F.) will dissolve sixty parts of the poison. It is also readily dissolved by alcohol and ether.

Symptoms.—The symptoms produced by corrosive sublimate generally come on immediately, or within a few minutes after the poison has been swallowed. In the first place there is perceived a strong metallic taste in the mouth, often described as a coppery taste; and there is, during the act of swallowing, a sense of constriction almost amounting to suffocation, with burning heat in the throat, extending downwards to the stomach. In a few minutes violent pain is felt in the abdomen, especially in the region of the stomach, which is increased by pressure. Pain in the abdomen has been sometimes wholly absent. There is nausea, with frequent vomiting of long stringy masses of white mucus, mixed with blood; and this is followed by profuse purging. The countenance is sometimes swollen and flushed, in other cases it has been pale and anxious. The pulse is small, frequent, and irregular, and is scarcely perceptible when the symptoms become aggravated. The tongue is white and shrivelled—the skin cold and clammy, the respiration difficult; and death is commonly preceded by fainting, convulsions, or general insensibility. The external parts of the mouth, when examined, are swollen, and sometimes present an appearance as if the cavity had been washed with a solution of silver nitrate: the lips are often swollen. Suppression of the urine has also been frequently noticed among the symptoms. It existed in a well-marked case of poisoning by this substance: the patient lived four days, but did not pass any urine during the whole of this time. ('Guy's Hosp. Rep.' 1844, p. 24.) This symptom was ob-

served in a case reported by Wegeler (Casper's 'Wochenschrift,' Jan. 1846, p. 30), in which a youth, æt. 17, swallowed three drachms of this poison, and died on the sixth day. During the last three days, no urine was secreted. The case was otherwise remarkable from the fact, that no pain was experienced on pressure of the abdomen, and that the pulse underwent no change until shortly before death. In another case, in which twenty grains of corrosive sublimate in solution were swallowed, suppression of urine and salivation came on on the third day, and the patient died on the ninth day. ('Lancet,' Dec. 13 and 27, 1845, pp. 650, 698.) In another case the quantity of urine secreted was small, and it produced a scalding pain when voided. ('Prov. Med. Jour.' Nov. 18, 1843, p. 126.) In this instance there was no purging.

The *external* application of corrosive sublimate to tumours or ulcers may destroy life with all the usual symptoms of acute mercurial poisoning. At the Winchester Lent Assizes, 1859 (*Reg.* v. *Crook*), a quack was convicted of manslaughter by applying corrosive sublimate in powder to a cancerous tumour in the face of deceased. The man suffered from the usual symptoms. After death the bowels were found extensively inflamed and ulcerated. Corrosive sublimate was detected in the diseased part. A girl, æt. 9, died from the effects of this poison, locally applied to the scalp for the treatment of ringworm. The liquid applied was alcohol containing eighty grains of corrosive sublimate to the ounce. She suffered from mercurial poisoning in a severe form, and died on the fifth day after the application. (See 'Pharm. Jour.' Sept. 9, 1871, p. 216; 'Lancet,' 1871, II. 373; and 'Med. Times and Gaz.' 1871, II. 353.) No idiosyncrasy is required to account for death under such circumstances. In the first edition of the author's work on POISONS (1848), p. 394, fatal cases are related of poisoning by corrosive sublimate through the unbroken skin. Two brothers have lost their lives, the one dying on the fifth and the other on the eleventh day. Some persons exhibit a peculiar idiosyncrasy towards mercurial preparations. In 1881, the editor was consulted respecting a lady whose life was brought into jeopardy by the administration of one dose of 1–32nd of a grain of corrosive sublimate. There were the symptoms of severe irritant poisoning, and collapse, followed by salivation. It was clearly demonstrated by two independent analyses that the single dose of medicine contained only the 1–32nd of a grain of the poison.

This poison differs from arsenic; 1, in having a well-marked taste; 2, in producing violent symptoms in a few minutes; and 3, in the fact that the evacuations are more frequently mixed with blood. The symptoms produced by corrosive sublimate, in the first instance, resemble those of cholera; if the individual should survive several days, they are more like those of dysentery—violent straining, and mucous discharges mixed with blood, being very frequently observed.

Slow or chronic poisoning.—The symptoms are much modified when the poison is taken in small doses at intervals for some days or weeks. There are colicky pains, with nausea, vomiting, general uneasiness, and depression. The salivary glands become inflamed and painful; the tongue and gums are red and swollen, sometimes ulcerated, and there is fœtor of the breath. A deep blue line, somewhat like that observed in poisoning by lead, is sometimes found around the edges of the gums. The patient experiences difficulty of swallowing and breathing. The constitutional effects are indicated by looseness of the bowels, difficulty of breathing, spitting of blood, cough, general trembling or convulsive movements of the limbs and palsy, with low fever and emaciation, under which the patient sinks. One of the most marked effects of slow or chronic poisoning by mercurial preparations is *salivation, or ptyalism, indicated by* an increased flow of saliva. This is by

no means a necessary symptom in cases of acute poisoning by corrosive sublimate, but it not unfrequently shows itself about the second or third day. In some instances the patient dies too rapidly for this effect to follow; but even when he survives some days, salivation is not always observed. In placing reliance upon this symptom, it must be remembered that salivation may arise from a variety of causes irrespective of the use of mercury. Another result is the peculiar mercurial erethism, as it is termed, or affection of the nervous system. There is great mental excitability of the patient to external impressions. An unusual word disturbs him; and the question of the physician may cause him to grow pale, stammer, and become profoundly agitated. He is anxious without reason, sleepless, and disturbed by dreams. This condition after a variable period passes into the stage of mercurial tremor, or 'trembles' as it is vulgarly termed. The tremor begins in the tongue, face, and arms, as a slight quivering, especially noticeable when the patient speaks; and it increases till convulsive twitchings are produced, extending over the whole body, and sometimes rendering locomotion impossible. The tremor disappears during sleep; and is increased by the slightest attempt at voluntary effort, or by mental emotion of any kind. If the patient be requested to hold out his hand or to protrude the tongue, these acts are done in a jerky manner; and attempts to walk result in the most grotesque contortions. As mercury may be easily detected in the saliva by a process described below, the discovery of the metal in this fluid will show the real cause of the salivation (see page 294).

Appearances after death.—These, as in the case of arsenic, are chiefly confined to the stomach and bowels. Corrosive sublimate, however, affects also both the mouth and throat; the mucous membrane is softened, of a white or blueish grey colour, and sometimes inflamed; that which lines the gullet is similarly affected, and partly corroded and softened. The mucous membrane of the stomach is more or less inflamed, sometimes in patches; and there are masses of black extravasated blood found beneath it. Occasionally it has a slate-grey colour, and the mucous coat beneath may be found reddened. A case occurred in Guy's Hospital, in which the mucous membrane was simply inflamed: it much resembled the condition presented in cases of arsenical poisoning. The coats of the stomach are sometimes corroded, and so much softened that they cannot be removed from the body without laceration. Similar appearances have been met with in the small and large intestines, especially in the cæcum. In a case in which twenty grains were taken (see p. 287), and death occurred on the ninth day, the mucous membrane of the stomach was softened, but there were no well-marked appearances of the action of the poison on this organ. The cæcum had been the seat of violent inflammation, the whole surface being of a deep black-red colour, and there were patches of sloughing in the coats. ('Lancet,' Dec. 27, 1845, p. 700.) In a case in which a man died forty hours after having swallowed one hundred and twenty grains of corrosive sublimate in powder, the mucous membrane of the stomach, duodenum, upper portion of the ileum, and parts of the large intestines, were found of a bright red colour. This appearance was most marked at the cæcum and sigmoid flexure of the colon. The local action of the poison on the mouth and throat was in this instance considerable. ('Edin. Month. Journ.' Dec. 1851, p. 532.) Perforation of the stomach is rare as an effect of this poison: there is, perhaps, only one case on record. Appearances like those just described have been seen in the alimentary canal, not only where the case has terminated fatally in a few hours, but where it has been protracted for six, eight, and even eleven days. (Chaussier, 'Recueil des *Mémoires*,' p. 363.) In the case of a man, æt. 42, who swallowed, by *mistake*, thirty grains of the poison in solution, and who died on the

h day, the stomach was found empty, and the mucous membrane was lull, dark-red colour, chiefly about the smaller curvature. This was softened, and near the intestinal end was grey, pulpy, and mous. In the gullet, the lining membrane appeared to have been d off in shreds. The intestines were in a state of intense inflamma- assing into gangrene. The other viscera presented no particular ance. In this case the symptoms were manifested in a few minutes: was a burning pain extending down the gullet to the stomach, bed as if the parts were on fire; there was no mark of corrosion in outh; there was a sensation as if the throat were 'grown up:' ere was blood in the vomited matters as well as in the evacuations. was no salivation at any period. ('Med. Times and Gaz.' Feb. 1859, .)

antity required to destroy life.—The *smallest* doses which have destroyed e *two* and *three* grains respectively. These were the cases of children; antities were accurately determined from the fact of its having been up by mistake for calomel, which it was intended to prescribe. cet,' 1845, p. 297.) It is probable that, under favourable circum- s, from three to five grains, or even less, would destroy an adult. ns who had taken large doses have been known to recover when reme- were timely administered, or early vomiting was produced ('Med. and Gaz.' Feb. 1860, p. 162); and sometimes recovery has been rly attributed to the remedy. A man swallowed eighty grains of sive sublimate dissolved in whisky and water. In ten minutes violent ing occurred. A mixture of albumen and milk was first given, and out twenty-five minutes, gold-leaf with reduced iron made into a . Some warm water had been previously administered in order to the stomach of any albumen or mucus. Vomiting recurred with iolence, the matters being mixed with gold-leaf. On the next day, was no salivation, and in about eight days the man perfectly ered. ('Ann. Jour. Med. Sci.' Ap. 1863, p. 340.) The recovery attributed to the gold and iron, but there is not evidence that netals had exerted any action in decomposing the corrosive sub- e; on the contrary, the particles of gold-leaf rejected after the nistration of the antidote were apparently unchanged. The recovery doubtless, due to the early vomiting, and the free use of albumen nilk.

eriod at which death takes place.—In an acute case, a person com- r dies in from one to five days; but death may take place much sooner ter than this. In the shortest fatal case on record, the quantity of n taken was not ascertained, but the man died in less than *half an hour* Poisons,' Cor. Sub.) In a case reported in the 'Edin. Month. Jour.' , vol. 1, p. 958, an adult who took from 60 to 80 grains of corrosive mate, did not die until the *twelfth day*. On the first day there was no laint of pain in the gullet or stomach; the throat was painful on the d day, and the mouth and gums were affected on the third day. On ighth day the man had apparently recovered, but he gradually became er, and died on the twelfth day. In one case ('Lancet,' Feb. 1, 1862), ge dose of corrosive sublimate (112 grains) caused death in three and a quarter. In another, which occurred in 1861, about five grains rrosive sublimate caused death in six days: in both cases the poison aken in solution.

n the above 'Lancet' case, a man, æt. 54, swallowed two pennyworth of oison (a quarter of an ounce) at 11 A.M. When seen, soon afterwards, as on the bed in a state of great prostration; his skin was blanched, covered with a cold clammy perspiration; he vomited a thick, stringy.

glairy substance. There was intense pain over the abdomen, and purging with discharge of blood: the pulse was scarcely perceptible, tongue and the interior of the mouth were perfectly white from the action of the poison. White of egg was given freely, and a mustard poultice applied to the abdomen. At one o'clock he was more depressed. At a quarter past two he expired. An inspection was made twenty-four hours after death. The external coat of the stomach was of a deep red colour. The mucous membrane internally had the appearance of a piece of dark crimson velvet, owing to the large quantity of blood extravasated. The intestines here and there were reddened. The large omentum for about an inch from the stomach was of a deep crimson hue. The other organs were healthy.

In the other case, in which five grains of the poison, dissolved in vinegar, were swallowed by a man, æt. 25, the following symptoms were observed. Immediately after swallowing it, he felt a burning heat in his throat, and vomited freely. In two hours, there was great pain in the abdomen, he passed blood in his evacuations, and brought up a thick yellow frothy matter, tinged with blood. There was suppression of urine. He died on the sixth day. On inspection, the gullet presented marks of the local action of the poison. The mucous membrane of the stomach was reddened, and throughout minutely injected. There was no appearance of corrosion. The small intestines at their lower part, as well as the large intestines, were deeply injected. The cæcum was but slightly affected. Seven ounces of the liver, and one-half of the stomach, yielded only minute traces of mercury. The greater part of the poison had been discharged by vomiting or by elimination during the six days which the patient survived. Thus in spite of the removal of the poison from the stomach, the case may prove fatal. Eade reported a case in which a man swallowed a lump of corrosive sublimate: it was ejected from his stomach in about an hour. It was then smooth on the surface, and weighed about one drachm. The usual symptoms of mercurial poisoning followed, with suppression of urine. There was slight salivation on the fifth day, and the man died on the eighth day. Mercury was found in the liver. ('Lancet,' 1870, 1, p. 303.)

Fig. 23.



Stellated crystals obtained by subliming corrosive sublimate, magnified 30 diameters.

Chemical Analysis.—Corrosive sublimate is usually seen as a *solid* in heavy crystals, or in the form of a white crystalline powder. 1. When the powder is heated on platinum foil it melts, and is volatilized in a white vapour without leaving any residue. 2. When heated in a close tube, it melts and forms a sublimate, consisting of prismatic crystals in stellated groups. 3. The powder is changed in colour by the following reagents: potassium iodide produces a bright scarlet, potash a yellow, and ammonium sulphide a black mass; ammonia does not alter its colour. 4. The mercury and chlorine may be discovered by one process. Mix the powder with four parts of dried sodium carbonate (obtained by incinerating the bicarbonate), until the residue in the reduction-tube fuses and becomes white. A sublimate of metallic mercury in distinct and well-defined globules will be obtained. Cut off the end of the tube containing the fused residue, which is sodium chloride with some undecomposed carbonate. Digest it in water with nitric acid, and apply heat until it is entirely dissolved: then add to the solution silver nitrate. A white preci-

ate of silver chloride, insoluble in nitric acid, will be at once produced. he solid is thus proved to contain both mercury and chlorine, and the ly compound of these elements soluble in water is corrosive sublimate. Corrosive sublimate is dissolved by water and alcohol. A few drops of the aqueous solution evaporated on a glass-slide yield slender opaque

Fig. 24.



Prismatic crystals of corrosive sublimate from solution in water, magnified 30 diameters.


Fig. 25.



Crystals of corrosive sublimate from a solution in alcohol, magnified 80 diameters.

r prisms (fig. 24). The crystals obtained from the alcoholic solution arger and better defined (fig. 25). When a weak solution of potassium le is dropped on them, they acquire a bright scarlet colour. These acters, which may be obtained from the minutest crystal and only one of solution, prove that the body dissolved in water is corrosive imate: it is thus distinguished from y other mineral poison, and all other tances whatever. 1. Stannous chlo- added to a solution of corrosive limate, produces a dark grey precipi- which, after it has been boiled, is lved into globules of metallic mer- easily separable by filtration. The ride should be strong and mixed i its volume of strong hydrochloric . If while boiling the mercurial pound is added to it, there is an ediate precipitation of metallic mer- . The same result is obtained with compounds of mercury excepting sulphide. 2. Sulphuretted hydrogen ammonium sulphide produce, at first llow, and then a black sulphide, not ble in alkalies or diluted acids. 3. If the liquid is acidulated, and ht copper-foil, wire, or gauze is plunged into it, the copper will acquire very-white deposit, even in the cold, but more rapidly by heat. When copper with the metalic deposit is heated in a tube, globules of mercury sublimed.

Fig. 26. Fig. 27.



26. Mercury sublimed in globules, from corrosive sublimate, in a reduction-tube.
27. The same, magnified.

(b) *Organic Liquids.*—The liquid should be separated by filtration from insoluble portions. The latter should be pressed, dried, and set aside a separate analysis. Any heavy sediment may be obtained by ntation, dried, weighed, and separately examined. A slip of bright er-foil or gauze may be *employed* as a trial test for the liquid

portion. In place of copper, a small electrolytic couple, made by a layer of gold-foil round a layer of zinc-foil, may be introduc liquid should be slightly accidulated with hydrochloric acid and

Fig. 28.



A layer of gold-foil round zinc-foil.


The metals should be suspended in the liquid hours. If the mercurial poison is present, even quantity, the gold will sooner or later lose its colou come silvered, while the zinc will be wholly or in solved. The slip of gold-foil may be washed in w afterwards in ether and dried. It should be divi two equal portions. One should be submitted t a tube, when globules of mercury will be obtai other should be heated with a few drops of con nitric acid, until the gold has reacquired its yello On evaporating the excess of acid and adding a so stannous chloride, a dark grey precipitate of meta cury is thrown down. It may be remarked that mercury is wholly unlike any other volatile substan perfect sphericity of the globules, their silvery whiteness by reflec complete opacity by transmitted light, at once identify them as mercury. The sublimate of metallic mercury differs from that o in the fact that, when heated, it sublimes simply as a metal withou It is not oxidized (like metallic arsenic), by heating it in a reduct but is simply transferred with its metallic lustre from one part of to another. The mercurial sublimate is soluble in nitro-hydrochl yielding on evaporation white prismatic crystals of corrosive subli

The yellow colour of the gold may not have been conceale mercurial deposit, owing perhaps to its great tenuity. Hence it well to heat the gold in a reduction-tube before coming to the c that mercury is absent. The tube itself may not show a sublima naked eye, owing to the minuteness of the globules, and their bei scattered. In all cases it should be examined, at first with a subsequently with a high power of the microscope. Minute s globules, varying from the 1-8000th to the 1-16,000th of an inch in may thus be detected. They are frequently deposited in a kind in any minute crack or line on the interior of the glass tube. In of a doubt existing respecting the mercurial nature of the sublir following experiment will remove it. Cut off by a file the portion on which they are deposited: introduce this into a wide short tub few drops of hydrochloric and half the quantity of nitric acid. E the acid liquid to dryness on a sand-bath. White prismatic cr corrosive sublimate will remain, if the sublimate was of a mercuria and too great a heat has not been applied. On touching the whit cautiously with a drop of solution of potassium iodide, the cry acquire a scarlet colour.

Another method of analysis may be sometimes usefully res Place the suspected organic liquid in a small gold capsule, or o coin. Acidulate it slightly with hydrochloric acid, and touch through the acid liquid, with a slip of pure zinc-foil, or with a s Mercury will be deposited in a white silvery stain on the gold, the two metals have come into contact. Wash out the capsule tilled water, and add a few drops of strong nitric acid. Mercuric thus obtained, which may be tested by the processes above describe detection of mercuric salts. Any solid precipitates, or insoluble co of mercury, may be dissolved by strong nitric acid, and the soluti for the metal. If none is found, the dried solid, mixed with dr carbonate, may be heated in a tube, when mercury, if present,

. Organic liquids containing any of the poison dissolved may
ed to dialysis by the method already described under arsenic.
d and eliminated mercury.—Although absorbed mercury, like
ls, is eliminated from the system, yet its elimination through the
ɔretions appears to be slow, and subject to some uncertainty with
the time at which it occurs, as well as to the duration of the
That it is rapidly absorbed and deposited in the tissues of the
undoubted; but when once deposited, the period for its entire
ı can scarcely be predicted. Mercury in a man or animal,
under its immediate effects, is not so readily detected in the
rsenic. Tuson gave to a mare, at first four grains, and after-
grains, of corrosive sublimate twice a day. At the end of
ays, he tested a pint of urine for mercury, but he found none.
apse of three weeks it was easily discovered in this fluid. The
n left the infirmary. In a case of chronic poisoning by mercury,
ntly mentioned (see p. 300), mercury could not be detected in
ces of urine which were voided while the patient was labouring
effects of the absorbed poison, although several weeks had
d mercury was detected in the tissues after death.
search for mercury in living persons labouring under this poison,
ntity of urine should be examined, and an analysis made at in-
'he urine should be evaporated to dryness, and the dry residue or
ated by the following process, which is the same as that required
sues. From four to eight ounces of the liver or other organs
lried, broken up, and then boiled until dissolved, in one part of
ɔchloric acid and four parts of water. The acid liquid may be
ɪrough linen, and the residue pressed. The liquid, if in large
ihould now be concentrated by gentle evaporation, and while
y warm, a small piece of copper-gauze (proved to be free from
hould be introduced, at the end of
ıum wire, into the acid liquid. The
y acquire a white, grey, or silvery
a few minutes or not until after
r hours. It should be removed,
water and in alcohol, dried, and
by a low power of the microscope.
ition of any white metal on the
l then be perceptible. It may be
a pellet and heated in a dry reduc-
when minute globules will appear
mate. The sublimate in the tube
examined with a microscope, and
: should in all cases be heated,
e red colour of this metal appears
ed or not by any deposit. The electrolytic couple, described on
y also be employed for the deposition of mercury.

Fig. 29.




A small sublimate of mercury, magnified 124 diameters.

lleged case of poisoning, a child died after an illness of twenty-
Fourteen hours before death, two grains of calomel had been
This had caused much purging, and mercury was found in one
evacuations passed. Four ounces of the liver were treated as
ı hydrochloric acid and water, and a small piece of pure copper
he acid liquid while warm, and kept there for about forty-eight
acquired a slight silvery lustre, and globules of mercury were
ɔm it by sublimation.
ıic should be present in the tissues at the same time, and the
ıre is boiled, *arsenic* and mercury will be deposited together;

and when the copper is heated, the globules of mercury will be obtained intermixed with octahedral crystals of arsenious acid. In a case of exhumation after twenty-one months' burial, these mixed sublimates were obtained by the examination of the rectum of the deceased. (*Reg.* v. *Bacon*, Lincoln Sum. Ass. 1857.) It appeared in evidence that arsenic had been administered to the woman a day or two before death, and a dose of calomel had been prescribed more recently. This accounted for the presence of the mixed sublimates.

Fig. 30.



Mixed sublimates of mercury and arsenious acid, magnified.

Arsenic is not readily deposited on copper in the cold, while mercury is readily deposited at all temperatures from acid liquids. It is better, however, to destroy the organic matter by means of potassium chlorate and hydrochloric acid, as in the procedure for arsenic (see p. 274), evaporate to dryness, take up the residue with acidulated water, and then immerse in it a slip of gold-foil wrapped round a piece of zinc (p. 291). In the course of twenty-four hours the gold-foil will acquire a white coating of mercury should this metal be present.

In the living body mercury is eliminated in the saliva as well as by the urine. About one drachm of the saliva will suffice for the detection of mercury by the following process. Acidulate the fluid with one-fourth of its volume of pure hydrochloric acid. Immerse in this a portion of copper-gauze, about the sixteenth of an inch square, attached to a fine platinum wire. Place the tube containing the liquid in a warm place for a few hours. If mercury is present in the saliva, the copper-gauze will be whitened. Other portions may then be introduced until the mercury ceases to be deposited. The pieces of copper should be washed in water and ether, and dried—examined by a low power of the microscope, and then heated in a small reduction-tube. Globules of mercury visible under the microscope will then be obtained. In a case of inunction with mercury the metal was thus detected in the saliva on the third day. There was painful swelling of the salivary glands, with the peculiar metallic taste produced by mercury. This analysis of the saliva may not only furnish evidence that the patient is under the influence of mercurial poison, but it will prove, in a case otherwise doubtful, whether the *salivation* from which a person is suffering is owing to mercury or some other cause (p. 287). An examination of the saliva should be made in other cases of metallic poisoning, as arsenic, antimony, and other metals might be thus detected in the act of elimination from the living body.

The processes above described reveal only the presence of mercury. When the quantity of corrosive sublimate dissolved in an organic liquid is moderately large, it may be removed by means of ether. Place the filtered liquid supposed to contain the poison in a stoppered tube, add to it twice its volume of ether, and agitate the liquid at intervals for half an hour. Allow the liquid to subside, pour off the ether into a dial-glass, and submit it to spontaneous evaporation. As the ether passes off, the corrosive sublimate will be deposited in white silky-looking prisms. These may be purified by solution in water if necessary, and again crystallized. Corrosive sublimate may thus be separated from arsenic and other mineral poisons in solution. If mercury and arsenic are associated in a poisonous mixture, or *in the tissues*, the arsenic may be entirely separated by distillation (page *270*). Masses of corrosive sublimate may be sometimes entangled in vessels

mucus; and in such cases, the coarse powder being heavy, it may be separated by simply agitating the viscid liquid in water, and then decanting the upper portion suddenly. This poison is decomposed and precipitated by many organic matters, such as albumen, fibrin, casein, mucous membrane; also by gluten, tannic acid, and other vegetable substances. Thus, then, we cannot always expect to find it in the stomach, in a state of solution. Mercury is not a constituent of the human body. The discovery of it in the tissues, therefore, proves that it must have been received *ab extra*.

By one or other of the processes above mentioned we may be able to show the presence of *mercury*, but not of corrosive sublimate, in the body. Whether the mercurial compound had acted as a poison or not, must be determined from symptoms and appearances: whether it had been given or taken as a medicine or not, is a conclusion which must also be determined from other circumstances. The proof that the mercury was really in the form of corrosive sublimate, could only be derived from the discovery of some undissolved portions of the solid poison in the stomach or its contents, or from a separation of the poison itself by means of ether. If thus obtained after filtration of an organic liquid, it would show its presence in the form of a soluble salt: all the soluble salts of mercury are poisonous, and, with the exception of the chloride and cyanide, are rarely used internally as medicines. If undissolved, the absorbed mercury may have been derived from some mercurial medicine innocently taken by the deceased. Nothing more common than to discover traces of mercury in the stomach, bowels, liver, kidneys, or other organs of a dead body. No importance can be attached to this discovery in the absence of evidence that the deceased has actually suffered from symptoms of mercurial poisoning. As to the mercury found in the tissues, it may have been derived from a soluble or insoluble medicinal compound, or from exposure to the vapours of the metal or of its salts in various trades.

A person may die from the effects of corrosive sublimate, and no mercury may be found in the tissues. A case of this kind occurred some years since at Guy's Hospital; and another, in which deceased died in seven days from a large dose of corrosive sublimate in whisky, has been reported by Geoghegan. On this occasion, although the local effects of the poison on the throat, stomach, and bowels, were of an intense kind, the viscera, on careful analysis, yielded no trace of mercury: the metal had been entirely eliminated in fifteen days. ('Med. Gaz.' vol. 46, p. 253.)

CALOMEL. *Mercurous Chloride. Subchloride of Mercury.*—This substance, although commonly regarded as a mild medicine, is capable of destroying life, in small doses, by causing excessive salivation with ulceration and gangrene; and in large doses by acting as an irritant poison.

Analysis.—It is known from corrosive sublimate by its insolubility in water, alcohol, and ether; and from white precipitate by its being blackened by alkalies. A mercurial sublimate may be obtained from it by treating it with sodium carbonate.

WHITE PRECIPITATE. *Ammonio-Mercuric Chloride. Ammoniated Mercury.*—In 1850, a woman who was indicted for administering this substance to her husband, owed her acquittal to the lenient assumption in her favour that it was *not* a poison. Out of fourteen cases which the author collected, in which white precipitate was taken in doses varying from a few grains to forty, two only proved fatal; and one of these was the subject of a trial for murder (*Reg.* v. *Moore*, Lewes Lent Ass. 1860). The symptoms which it produces are violent vomiting, cramps, purging, and pain in the stomach, with convulsions. After death there is more or less inflammation of the stomach and bowels. A woman, æt. 30, swallowed a pennyworth

of white precipitate and shortly afterwards a pennyworth of acetate of lead. In half an hour, there was violent vomiting with pain over the whole of the abdomen. An hour and a half afterwards the symptoms were, in addition to the abdominal pain, great thirst and a comatose condition. On the second day, there was slight tenderness of the gums, a flow of saliva, flushed face, with great tenderness of the abdomen; and on the fourth day profuse salivation. This subsided on the tenth day, and the woman recovered. ('Med. Times and Gaz.' 1863, 2, 645.) A young woman swallowed about thirty or forty grains of this substance by mistake for carbonate of soda. The chief symptoms were pain in the stomach and a spasmodic twitching of the muscles of the left arm and leg. These spasms continued for twenty-four hours. Emetics were given, and she recovered. ('Lancet,' 1871, II. 540.)

In 1877, a woman, æt. 30, was admitted into Guy's Hospital, three hours and a half after having taken two pennyworth, or 'a good teaspoonful,' of white precipitate. Within a few minutes of swallowing the poison vomiting and severe burning pain in the stomach came on. Twenty minutes after administration an emetic of ipecacuanha was given. On admission an emetic of zinc sulphate was administered. The expression was anxious, the pulse and respiration were quickened; there was great thirst, severe vomiting, and great pain in the abdomen. The bowels acted frequently. She made a good recovery, and was discharged in nine days, no salivation having appeared.

In 1878, a man, æt. 66, took thirty grains of white precipitate. He vomited almost immediately. With the exception of a feeling of soreness in the throat his symptoms were not severe.

In 1879, a third case, that of a woman, æt. 26, was admitted into Guy's Hospital. The patient had taken threepennyworth of white precipitate in milk. There was speedily severe burning pain in the region of the stomach, and a metallic taste in the mouth. She vomited on admission, and the vomit was found by the editor to contain white precipitate. An emetic of zinc sulphate and ipecacuanha was speedily followed by renewed vomiting. Purging set in next day. The woman recovered. Four days after the administration of the poison salivation appeared and continued for a few days.

A trial for attempting to poison by this compound took place at the Maidstone Summer Assizes, 1869 (*Reg.* v. *Seaham*). The compound is white, but as a result of boiling, it gave a yellow colour to the gruel in which it was administered. In *Reg.* v. *Hargreaves* (Manchester Lent Ass. 1866), a girl was convicted of an attempt to poison her father by this substance. The poison was put into milk and medicine. It produced a burning sensation in the throat and stomach, and thus led to suspicion. About ten grains of white precipitate were detected in some buttermilk.

Pavy's experiments on dogs and rabbits show that this is a more formidable poison than it was formerly supposed to be. The greater number of recoveries were probably owing to the substance being early ejected by vomiting. Rabbits, which do not vomit, were killed by a dose of four or five grains in a few hours. After death, mercury was found deposited in various organs, but more in the kidneys than in the other viscera. (For additional facts connected with the action of this poison, see 'Guy's Hosp. Rep.' 1860, p. 483.)

Analysis.—White precipitate is a heavy, insoluble, chalky-looking substance, containing about eighty per cent. of mercury. As it is sold in the shops, it frequently contains corrosive sublimate to the amount of one or two per cent. It is not used internally, but it is much employed by the poorer classes in the treatment of ringworm and other skin-diseases. It

luble in acids, is not blackened by alkalies, and yields a mercurial
nate when heated with sodium carbonate. It is not dissolved by
r, but becomes yellow by long boiling. If boiled in a solution of
sh, it evolves ammonia, and yellow mercuric oxide is precipitated.
ay be detected in organic fluids and solids by boiling them in one part
ydrochloric acid and four parts of water. The mercury may then be
rated by means of copper (p. 293).

Red Precipitate. *Mercuric Oxide. Red Oxide of Mercury.*—This
stance is poisonous; but instances of poisoning by it are rare. The
owing case occurred at Guy's Hospital in 1833. A woman, æt. 22,
o had swallowed a quantity of red precipitate, was brought in labouring
der the following symptoms: the surface was cold and clammy, there
s stupor approaching to narcotism, frothy discharge from the mouth,
l occasional vomiting: the vomited matters contained some red powder,
ich was proved to be red precipitate. There was considerable pain in
abdomen, increased by pressure; and there were cramps in the lower
emities. On the following day, the throat and mouth became painful,
she complained of a coppery taste. The treatment consisted in the
of the stomach-pump, and the free administration of albumen with
n. She left the hospital four days afterwards, still under the influence
ercury. The quantity of oxide taken was not ascertained.
1 1879, a woman was treated in Guy's Hospital, who had taken red
ipitate and laudanum. Severe abdominal pain, vomiting, and bloody
ng, were the most prominent symptoms. The woman recovered
at salivation.
alysis.—Its red colour and the fact that when heated in a close tube,
esolved into oxygen and mercury which is deposited in globules, are
which serve to identify it.

NNABAR. Vermilion. *Mercuric Sulphide.*—The term *Cinnabar* is
d to a dark and heavy compound of sulphur and mercury, while
lion is the same substance reduced to a fine powder. It is well
n as a red pigment, and is sometimes employed in colouring con-
nery and wafers. It is stated to have proved fatal to animals in
oportion of from thirty to seventy grains, when applied externally
wound. Cinnabar is sometimes used for giving a red colour to
ents, *e.g.* sulphur ointment: and it is also employed as a colouring
r to vulcanized rubber for mounting artificial teeth. Although
nsoluble compound of mercury cannot be regarded as an active
it poison in the stomach, the placing of it in such a situation
; should be always in contact with the mucous fluids of the mouth, is
to lead to the usual consequences of chronic poisoning by mercury.
54, a medical man consulted the author under the following circum-
s. Upon the recommendation of a dentist, he had worn this red
sition as a frame for false teeth, in place of gold. After some
e perceived a metallic taste in his mouth, the gums became inflamed
lcerated, there was great weakness and want of nervous power, with
in the loins and an eruption on the legs. When the composition was
ed, these symptoms abated. The substance contained a large
ity of vermilion: it had been mixed with the sulphur and rubber to
he appearance of the red colour of the gums. Wells has directed
tention of professional men to accidents of this nature. A patient
, who had been provided with a frame of this description for the
and lower jaws, perceived, soon after wearing it, a metallic taste
s mouth. His *health failed,* he lost his appetite, and became

emaciated: he suffered from flatulency, fœtid breath, and loosene bowels: his pulse was 100 and weak, and his tongue coated with film. This gentleman was peculiarly sensitive to the action of n He left off wearing the teeth, and became gradually better and s ('Brit. Med. Jour.' 1863, II. p. 366.)

Sutro published a short abstract of a case in which the v *vermilion*, applied externally, produced severe symptoms. A wo the advice of a quack, applied this vapour to a cancerous brea employed three drachms of vermilion, and covered herself with a that the vapour should only reach the body externally. After thr gations, she suffered from severe salivation and violent fever continued for four weeks. The right arm became œdematous. Times,' Sept. 27, 1845, p. 17.)

Analysis.—Vermilion, or an organic compound containing it, entirely decomposed by nitro-hydrochloric acid. The residue, ev to dryness, contains corrosive sublimate. This may be taken up and the usual tests applied (p. 291). Ether will separate corrosi mate from the aqueous solution. The vermilion contained in vulca thus readily detected. Red sulphide of mercury is not blacke red lead, by ammonium sulphide, and is not dissolved by hydrochlo like red oxide of mercury. It yields an alkaline sulphide and gl metallic mercury when heated with potassium cyanide.

Cyanide of Mercury. *Mercuric Cyanide.*—This substance is a poison, and has caused death in at least two instances. In 1823, who had swallowed twenty grains of this compound was immediate with all the symptoms of poisoning by corrosive sublimate, and died days. There was continued vomiting, with excessive salivation, ul of the mouth and throat, suppression of urine, purging, and, las vulsions of the extremities. On inspection, the mucous mem the stomach and intestinal canal was found extensively inflamed. (vol. 1, p. 735). Christison quotes a case in which ten grains destr within the same period of time. (Op. cit. p. 427.) As a poison, the is not much inferior in activity to corrosive sublimate, but it has n sive properties.

Turpeth Mineral. *Mercuric Basic Sulphate. Subsulphate of* —Fatal cases of poisoning by this compound are by no means c Although insoluble in water, it is undoubtedly an irritant poison capable of causing death in a comparatively small dose. A well- instance of its fatal operation was communicated to the Pathological in 1847. A boy, æt. 16, swallowed *one drachm* of this preparat produced a burning sensation in the mouth and throat, and vom ten minutes. In about an hour there was paleness, with an countenance, coldness of surface, constant sickness, sense of h constriction in the throat, and burning pain in the stomach, with The irritability of the stomach continued in spite of treatment, a two days there was salivation with mercurial fœtor. The gums ac deep blueish tint, and began to ulcerate. The patient died in about after taking the poison, without convulsions, and without suffering period from symptoms of cerebral disturbance. The principal appe in the body were inflammation of the gullet, its mucous membrane lower part peeling off; the inner surface of the stomach near the tw ings (cardia and pylorus) was covered with petechial spots; th *intestines* were contracted, the inner coat reddened, and petechia were found, but chiefly in the large intestines. The parotid an

cillary glands were swollen. Mercury was detected in the intestines. [ed. Gaz.' vol. 39, p. 474.) Another case was the subject of a trial for slaughter at the Stafford Lent Assizes, 1862. A young man, æt. 27, he mistake of a druggist, was supplied with turpeth mineral in place of iiop's mineral. He swallowed about forty grains of it, on an empty ach, with a like quantity of cream of tartar and treacle. In ten minutes as seized with violent vomiting and purging, the pulse was slow and ll, the skin cold and clammy, and there was pain in the abdomen, cially in the region of the stomach. Under treatment the symptoms of stion abated, but never entirely subsided, and he died quietly on the nth day after taking the poisonous mixture. On inspection the prin- l appearances were softening of the mucous membrane of the stomach intestines, with patches of inflammation and dark discoloration. A l portion of the liver yielded mercury when treated with copper and ochloric acid.

NITRATES OF MERCURY.—These are corrosive poisons which are used for ous purposes in the arts. They are solid white salts, easily dissolved old water when there is a little excess of acid present. The acid mer- c nitrate has caused death. ('Med. Gaz.' vol. 6, p. 329). A boy olved some mercury in strong nitric acid, and swallowed about a poonful of the solution. Soon afterwards he suffered excruciating in the throat, gullet, and stomach:—there was great anxiety, with skin, small pulse, colic, and purging. He became gradually weaker, died in about two hours and a half. On inspection, the throat, st, and stomach were found corroded and inflamed. Although he ived so short a time, the mucous membrane of the stomach was of a red colour. The author has met with a case in which the applica- of mercuric nitrate to the throat as an escharotic, caused immediate h by asphyxia. ('Guy's Hosp. Rep.' 1850, p. 206.) Acid nitrate nercury has often been employed by accoucheurs as a local application iseases of the neck of the uterus. In one instance in which it was used, the ordinary symptoms of mercurial poisoning showed them- es, and the patient appears to have suffered severely. ('Med. Gaz.' 45, p. 1025.) In another case the application of the acid nitrate to the produced an eschar, and under the symptoms of mercurial poisoning ed the death of the patient on the ninth day. The mucous membrane he stomach and intestines presented an arborescent redness, with patches echymosis. Mercury was found in the liver. (Edin. Month. Jour.' 4, p. 168.)

At the Leicester Summer Assizes, 1857, a girl was charged with ad- istering nitrate of mercury to her mistress (*Reg.* v. *E. Smith*). The lence showed that the accused had put the poison into some camomile-tea scribed for the prosecutrix. Only a small quantity was taken, as the tea a nauseous taste. The symptoms were: a burning sensation in the at and stomach, violent vomiting, and severe pain in the abdomen. woman recovered. In one case death took place under the usual ptoms from the external application of the nitrate in a liniment. ('Edin. nth. Jour.' Aug. 1864, p. 167.) A man, æt. 32, suffering from chronic oning by the nitrate of mercury, was admitted into Guy's Hospital in 3. He had been for four years engaged in packing the fur of rabbits, , and other animals, the dried skins of which had been previously bed over with a solution of nitrate of mercury. For the first three s he suffered only from a feeling of general weakness. For about a lvemonth, he could not hold his hand steadily enough to shave himself, he soon afterwards lost *completely* the control over the voluntary move-

ments of his limbs. Three or four months before his admission, he had had slight twitchings of his muscles when in bed. He was not at all emaciated. He said he had been salivated for about three months, soon after he began his occupation of packing furs; but his gums were not tender, and he had no metallic taste in his mouth. A month before his admission he gave up his work. When he became a patient he could walk with assistance, but on standing or lying down he could not control his limbs, which trembled considerably. There were continued involuntary movements of his body and limbs, like those of chorea. He became much exhausted, owing to want of sleep; he perspired profusely. The urine was high-coloured, but otherwise natural. Twelve ounces of it did not yield any mercury. No treatment appeared to give him rest or relief. Chloroform arrested the spasmodic movements, but only while he was under its influence. In five days he passed his urine involuntarily. He was quieter and slept a little at night. He had difficulty in swallowing; became gradually weaker and died, apparently from exhaustion, a fortnight after his admission. On inspection, the body was well nourished; the muscles were firm and healthy. The brain and spinal cord were found to be quite healthy. The lungs, heart, liver, spleen and kidneys, were free from any morbid appearance, or any change to indicate a cause of death. An analysis was made of the brain, liver, and kidney. Six ounces of each organ were dried, and one-half of the dried residue, treated with hydrochloric acid and water, as elsewhere described, gave, in forty-eight hours, on a small portion of copper-gauze, a greyish white deposit, which yielded globules of metallic mercury when heated. The kidney yielded the largest sublimate; but the quantity obtained from each organ was small, and might be described as mere traces. The globules from the brain and liver had an average size of 1–2600th of an inch; those from the kidney were larger. In the fur similar to that which the man had been engaged in packing a small quantity of a soluble salt of mercury was readily detected. The case, which at first presented some difficulty in accounting for death, thus resolved itself into one of exhaustion as a result of chronic poisoning by mercury under somewhat unusual circumstances. It is probable that the man received the dust of the dried nitrate through the air which he breathed, as well as by contact with his mouth, nostrils, and skin. As other workpeople similarly engaged were not found to have suffered, this may have been a case of mercurial poisoning due to idiosyncrasy.

Analysis.—When heated with dry sodium carbonate in a tube, the nitrate yields a sublimate of mercury. It also responds to the usual tests for the nitrates (see p. 222).

CHAPTER 22.

ON POISONING BY LEAD—SUGAR OF LEAD—SYMPTOMS—APPEARANCES AFTER DEATH—CHEMICAL ANALYSIS—LEAD IN ORGANIC MIXTURES—CARBONATE OF WHITE LEAD—CHRONIC POISONING. POISONING BY COPPER—BLUE VITRIOL—SYMPTOMS—APPEARANCES AFTER DEATH. POISONING BY OTHER COMPOUNDS OF COPPER—CHEMICAL ANALYSIS. COPPER IN ORGANIC LIQUIDS—IN ARTICLES OF FOOD.

SUGAR OF LEAD, *Lead Acetate, or Acetate of Lead.*—This is more frequently taken as a poison than any of the other salts of the metal, although cases of acute poisoning by lead in any form are not common. The substance is commonly met with in solid heavy crystalline masses, white, or of a brown-

white colour; it resembles loaf-sugar in appearance, and has often been taken for it. It has also a sweet taste, which is succeeded by an astringent or metallic taste. It is very soluble in water. Four parts of distilled water at 60°F. will dissolve one part; and it is much more soluble at a boiling temperature.

Symptoms.—Acetate or sugar of lead is by no means an active poison, though it is popularly considered to possess a virulent action. In medical practice it has often been given in considerable doses without any serious effects resulting. Christison states that he has given it in divided doses to the amount of eighteen grains daily for eight or ten days without remarking any unpleasant symptom, except once or twice slight colic. When, however, the quantity taken has been from one to two ounces, the following symptoms have been observed: a burning, pricking sensation in the throat, with dryness and thirst; vomiting and uneasiness at the pit of the stomach, sometimes followed by severe colic. The abdomen is tense, and the walls have been occasionally drawn in. The pain is relieved by pressure, and has intermissions. There is generally constipation of the bowels. If any fæces are passed, they are commonly of a dark colour, indicative of the conversion of a portion of the lead into sulphide. The skin is cold, and there is great prostration of strength. When the case is protracted, the patient has been observed to suffer from cramp in the calves of the legs, pain in the insides of the thighs, numbness, and sometimes paralysis of the extremities. The affection of the nervous system is otherwise indicated by giddiness, torpor, and even coma. A well-marked blue line has been noticed round the margin of the gums, where they join the teeth.

A remarkable series of cases of poisoning by lead acetate has been recorded. ('Lancet,' May 5, 1849, p. 478.) By some accident, about thirty pounds of this substance were mixed at a miller's with eighty sacks of flour, and the whole was made into bread by the bakers and supplied as usual to their customers. It seems that no fewer than 500 persons were attacked with symptoms of poisoning after partaking of this bread. In a few days they complained of a sense of constriction in the throat and the pain of the stomach, violent cramping pains round the navel, rigidity of the abdominal muscles, a dragging pain in the loins, and cramp with paralysis of the lower extremities. There was obstinate constipation, and the urine was scanty and of a deep red colour. The pulse generally was slow and feeble; the countenance anxious and sunken, frequently of a peculiar livid hue; tongue, flabby; gums marked by a deep blue line. The surface was cool, and there was a general arrest of the secretions. Sickness was not a uniform symptom, and even when it existed at first, it speedily subsided. The mental faculties were undisturbed. Not one of the cases proved fatal, but among the more aggravated there was great prostration, with collapse, livid countenance, universal cramps, numbness, and other alarming symptoms. After apparent convalescence, some of the symptoms returned in a more aggravated form without obvious cause, and for a long time the patients were out of health. Purgative medicines were found most effectual in the treatment. The quantity of lead acetate taken by each person could not be determined, as, on analysis, the samples of bread were found to be unequally impregnated with the substance.

Even when the patient recovers from the first symptoms, the secondary effects often last for a considerable time. Two girls, each swallowed an ounce of sugar of lead by mistake. Soon afterwards they felt a burning pain in the mouth, throat, and stomach, and in a quarter of an hour they vomited freely: in half an hour, there was severe pain in the bowels, with purging. Under treatment recovery took place. ('Prov. Med. Jour.' p. 1846.) After the lapse of a year, they both suffered from severe pain

in the pit of the stomach, which was tender on pressure. Nothing could be retained on the stomach; and there was a choking sensation in the throat, with other constitutional symptoms. Paralysis and other symptoms of nervous disorder are, however, by no means necessary consequences. A girl who had swallowed sixty grains of lead acetate, and had suffered severely from the primary symptoms, recovered in about three weeks without any paralysis or other disorder affecting the muscular system. ('Lancet,' Ap. 4, 1846, p. 384.) This lead-palsy appears to be a more common consequence of chronic poisoning; *i.e.* of small doses taken at intervals.

Appearances.—In one acute case related by Kerchhoffs, the mucous membrane of the stomach was removed in several places, especially near the intestinal opening; and most of the intestines were in a highly inflamed state. A trial for murder by this substance took place at the Central Criminal Court, in Nov. 1843 (*Reg.* v. *Edwards*). The stomach and intestines are stated to have been found inflamed, and there were dark spots on the former. In animals, according to Mitscherlich, when the dose is large, the mucous coat of the stomach is attacked and corroded: this change appears to be purely chemical, and takes place in all parts of the body with which the salt of lead comes in contact. If given in a small dose, it is decomposed by the gastric secretions, and exerts no corrosive power on the mucous membrane. When lead acetate was given mixed with albumen and dissolved in acetic acid, death took place with great rapidity; but on inspection, the stomach was not found corroded. This corrosive action is a property of the neutral salt, and is not manifested when the dose is small, or when the poison is combined with an acid.


Quantity required to destroy life.—Nothing certain is known concerning the *fatal dose* of sugar of lead. The facts already detailed show that it may be taken in comparatively large quantities without producing serious effects. Thirty or forty grains have been given daily, in divided doses, without injury. The following additional cases, in some of which recovery took place under disadvantageous circumstances, prove that the acetate of lead is far from being a virulent poison. Iliff met with an instance in which *an ounce* was swallowed in solution: the symptoms were pain in the abdomen resembling colic, with vomiting, muscular rigidity, and numbness. It was three hours before any remedies were used, and five hours before the stomach-pump was employed; but the person recovered. In the second case, also, an ounce was swallowed: magnesium sulphate was freely exhibited, and the stomach-pump was used. On the following morning there was slight excoriation of the gums, which were white, with a sensation of heat in the throat: the bowels were relaxed, probably from the effect of the medicine. The day following, there were pains in the legs and thighs, with restlessness and thirst. In a week the woman perfectly recovered. In a case which occurred to Alderson, a man swallowed an ounce of the acetate of lead in a drunken fit. There was violent vomiting, and the man recovered.

Chemical Analysis. Lead Acetate as a solid.—1. If a portion of the powder is heated in a small reduction tube, it melts, then again becomes solid: again melts, acquiring a dark colour, and gives off vapours of acetic acid; a black mass is left in the tube, consisting of carbon and reduced metallic lead. No sublimate is formed. If heated alone yellow lead oxide with reduced metal remains. 2. It is very soluble in water, even when cold; spring-water is turned milky by it, from the presence of carbonates and sulphates. 3. A small portion of the powder dropped into a saucer containing a solution of potassium iodide acquires a fine yellow colour. 4. When dropped into caustic potash it remains white. 5. In sulphuretted hydrogen water or ammonium sulphide, it is turned black, in

ch respect it resembles the white salts of some other metals. 6. When
powder is boiled in a tube with diluted sulphuric acid, acetic acid,
own by its odour and volatility, escapes. All these properties taken
gether, prove that the salt is lead acetate.

Lead Acetate in solution.—If lead acetate is dissolved in water for the
rpose of making further examination, we should note the following
nts:—1. A small quantity, slowly evaporated on a glass slide, will give
der white prismatic crystals, which are turned yellow by potassium
ide, and black by ammonium sulphide. The solution is said to be
tral; but the common lead acetate has an acid reaction. 2. *Diluted
huric acid* produces an abundant white precipitate, insoluble in nitric
, but soluble in strong hydrochloric acid, also in a large excess of potash.

Fig. 31.



Crystals of lead acetate, magnified 30 diameters.

Fig. 32.



Crystals of lead acetate, magnified 80 diameters.

is precipitated of a bright yellow colour by the *potassium iodide;* the
w lead iodide is soluble in potash, forming a colourless solution. It is
dissolved by concentrated hydrochloric acid. 4. *Ammonium sulphide* or
uretted hydrogen gas, produces a deep black precipitate, even when
han the 100,000th part of the salt is dissolved. 5. Place a few drops of
olution on clean platinum-foil in a platinum capsule, acidulate it with
c acid, then touch the surface of the platinum through the solution
a slip of zinc:—crystals of metallic lead are instantly deposited on
inc: by this method a small quantity of the metal may be detected
collected. 6. Zinc alone placed in acid solutions lowly displaces the
The metal is thus obtained as a dark blue spongy mass.

ead in Organic mixtures in the tissues, &c.—Lead acetate is precipitated
any organic substances, especially by casein, albumen, and tannic
Thus we may have to analyze either an organic liquid containing
or a precipitate of mucus and lead. Sulphuretted hydrogen will not
ate lead from its compounds with albuminous substances. The fluid,
e, or organ—such as a part of the liver—should be dried and incinerated
porcelain vessel. The ash should be heated with a small quantity of
c acid diluted with four parts of water, and then evaporated nearly to
ess. The residue should be digested in a small quantity of distilled
r (free from lead), filtered, and a current of washed sulphuretted
ogen gas should be passed into it. The production of a brown colour
brown or black precipitate, not readily dissolved by acids, indicates
probable presence of lead. The residue insoluble in nitric acid may still
ain some lead in the form of sulphate. This may be extracted by
ng with ammoniacal solution of ammonium acetate. A more
rate method consists in destroying the organic matter by means of
sium chlorate and hydrochloric acid (p. 274), as volatile compounds

of lead may be present. In all cases the brown or black precipitate produced by sulphuretted hydrogen must be redissolved in nitric acid, other tests confirmatory of lead, such as the potassium iodide and sulphuric acid test applied.

GOULARD'S EXTRACT. *Subacetate of Lead. Symptoms and Effects.* This substance has caused death in at least four instances—one in France and three in England. A woman, æt. 21, swallowed about three-quarters of a pint of Goulard's extract of lead (strength not stated), having begun with small doses. When first seen she was in great agony. There was severe colicky pain in the abdomen, which she rubbed frequently, and the muscles of the belly were drawn inwards. The pulse was feeble, there was trembling of the hands, and she was in constant motion with her body from severe suffering. There was heat in the throat and abdomen, with intense thirst, and a desire to vomit; but there was no actual vomiting or purging. A dose of magnesium sulphate produced vomiting, and she recovered; but there remained obstinate constipation of the bowels ('Lancet,' Jan. 14, 1860.) *Goulard Water* is made by adding one drachm and a half of this solution to a pint of water.

WHITE LEAD. *Lead Hydrocarbonate. Carbonate of Lead.*—A case of poisoning by the carbonate of lead was reported by Snow, in Oct. 1844, to the Westminster Medical Society. A child, aged five years, ate a portion not so large as a marble, ground up with oil. For three days he merely suffered from pain in the abdomen, and costiveness. On the third night the child became rapidly worse, and there was vomiting. He died ninety hours after taking the poison, having passed some offensive motions of a greenish-black colour (probably from admixture with lead sulphide) before he died. The mucous membrane of the stomach was much inflamed and of a dark-red colour throughout. Lead could not be detected in the contents or tissues of the stomach, or in the matter vomited. It is remarkable that in this case so small a quantity should have proved fatal without exciting any marked symptoms of irritation in the first instance. A young man, æt. 20, was recommended to take chalk on account of acidity and heartburn. He took by mistake a piece of white lead, and ate about five or six drachms. After a few hours there was vomiting, and he complained of violent burning pains in the stomach. Twenty-four hours afterwards, when first seen, he suffered from severe pain, particularly in the pit of the stomach and at the navel. His face was red and swollen, his eyes were shining and prominent; his tongue and mouth dry and very red; the abdomen was distended and extremely sensitive to superficial pressure, whilst stronger pressure alleviated the pain; there was great thirst; the bowels were constipated. Magnesium sulphate, with twenty drops of tincture of opium, was given to him, followed by larger doses of the same salt with an oily emulsion, under which treatment the patient soon recovered. (Casper's 'Wochenschr.' No. 36, 1844.) Most of the cases of poisoning by carbonate of lead have been of a chronic character.

In 1881, a little girl, aged two years and a half, was noticed to be feverish and restless, and was reported to have had a bad night. The following day she vomited constantly, was unable to take any food, and suffered greatly from thirst. It was considered that she was suffering from severe gastric catarrh, induced probably by sucking cheap coloured crayons, the pink mark of one of which was noticed on the child's mouth. In a few days the child rallied, and it was thought that all danger was over; but, on the twenty-third day of the illness, she was seized with convulsions, and the next day she died. All the organs were healthy, with the exception of the brain and stomach. The left side of the brain is reported

been distended with fluid, whilst the stomach presented signs of acute mation, and in two places perforation had occurred. Either the effu- into the ventricles or the condition of the stomach might, it was dered, have accounted for the fatal issue. An analysis of the crayons ed that they all contained poison. The most poisonous was a pink which contained more than half its weight of white lead, coloured an innocuous vegetable substance. The weight of this crayon was fifty s. Another crayon contained Prussian blue, mixed with Dutch pink. t. Med. Jour.' 1882, I. p. 669.)

ronic Poisoning.—Colica pictonum, or *Painter's Colic*, is a chronic form isoning by carbonate of lead. It is often difficult to trace the source poison, so slowly and insidiously are the effects manifested. In instances the poison is received through the lungs, or skin, or by the , although no physical or chemical evidence of this mode of introduc- an be obtained. In another work ('On Poisons,' 2nd ed. p. 485) the r has referred to cases in which colic and paralysis have occurred sons who have slept in newly-painted rooms. Alderson mentions l instances of this kind. ('Lancet,' Oct. 30, 1852, p. 391.) The r suffered from a severe attack of colic as a result of sitting in a for a few hours a day in which a large surface of canvas for an oil- ng had been covered with white lead and drying oil. An officer, æt. nd of painting in oil-colours, worked for some time in a room eight quare which had a large stove in it. He was attacked with wrist- (paralysis) in Dec. 1855, and soon afterwards with paralysis in both It appears that his servant always ground his colours, mixed them, leaned his brushes. The officer had experienced an attack some years ; but from this, by laying aside oil-painting, he completely recovered. ese instances the emanations of lead appeared to have been received gh the lungs. The symptoms were of the character peculiar to lead- ing, and as they disappeared on the removal of the patient to another phere, there could be no doubt about the cause. These insidious effects d should be borne in mind by those who deny that any noxious emana- can escape from papers in inhabited rooms, merely because the er number of persons who live in them do not suffer. Among white- manufacturers, the carbonate finds its way into the system either e skin, the lungs, mouth and nostrils, or all these channels together; diffused in a fine powder through the atmosphere, and thus enters the lungs. It has been remarked in France, that, in manufactories e the powder was ground dry, not only have the labourers suffered, horses, dogs, and even rats, have died from its effects: the rats have affected with paralysis in their hind legs. Since the practice has n of grinding the carbonate of lead in water, cases of lead colic not been so numerous. A fatal instance of this kind of poisoning orted in the 'Pharm. Jour.' 1865, 1, 38.

len employed in the manufacture of pottery or glazed cards are liable tacks of this kind. There are numerous other cases in which lead, or reparations, by mere contact with the skin, have been known to pro- the usual results of lead-poisoning. An infant was paralyzed by n of its having been washed every morning with water contain- finely-diffused oxide and carbonate of lead. A man suffered from palsy: he had been a potman, and the palsy was attributed to the tant handling and cleaning of pewter pots. ('Med. Gaz.' vol. 48, p. 1047. another case, see 'Lancet,' 1860, I. p. 60.) A case of lead-poisoning traced to the handling of vulcanized rubber, impregnated with lead. man was a trunk-maker, and used this material in his trade. ('Pharm. .' 1870, p. 426.) *The mere handling* of lead or its oxides, is therefore

sufficient to produce all the effects of chronic poisoning. A tea-dealer was seized with symptoms of lead-poisoning, and the cause remained long unsuspected, until he admitted that, in the course of his trade, he had the idle habit of often placing pieces of tea-lead in his mouth, and crushing the metal between his teeth.

One cause of lead-palsy among infants may be the use of farinaceous food wrapped in lead-foil having a thinly tinned surface, sold as patent tin-foil. Such infants' food is sometimes strongly impregnated on the outside with carbonate of lead. ('On Poisons,' 2nd ed. p. 505.) Snuff and tobacco, chocolate, and other substances in ordinary use are frequently wrapped in this spurious tin-foil. If the articles are kept in a damp place, they may thus become impregnated with carbonate of lead. In a case in Guy's Hospital, in 1861, no source of lead could be traced, although the symptoms were those of chronic lead-poisoning, and lead was found in the urine. Cosmetics and hair-dyes containing preparations of lead, commonly called hair-restorers, may also produce dangerous effects. The author met with an instance in which paralysis of the muscles on one side of the neck arose from the imprudent use of a hair-dye containing litharge. These hair-dyes or 'hair-restorers,' are sometimes solutions of lead acetate of variable strength, in perfumed and coloured water. In other cases they consist of lead hyposulphite dissolved in an excess of sodium hyposulphite. In one instance the continued use of such a dye is reported to have proved fatal, and lead was found in the liver and one of the kidneys. ('Pharm. Jour.' 1869, 1, p. 304; also Jan. 1869, p. 440.) Lacy has pointed out the injury to health which is likely to follow the use of white lead as a cosmetic by actors. The glazed white leather lining of hats is strongly impregnated with carbonate of lead, which may penetrate the body by the perspiring skin. Other facts connected with this form of lead-poisoning will be found in the 'Med. Times and Gaz.' Aug. 1852, p. 223: 'Ann. d'Hyg.' 1859, 1, pp. 95, 296; 1861, 1, pp. 342, 389; and 1870, 1, 72.

White lead is sometimes contained in small proportions in loaf sugar, owing to the moulds in which the sugar is set being painted with white lead, and a portion being thus mechanically taken up. Besides the workers in lead factories, plumbers, painters, workers on gas and water pipes, printers (types), potters (glazing with lead glaze), weavers (lead weights on looms), file-makers (striking files on leaden cushions), enamel workers, and others are liable to suffer from chronic lead-poisoning. The use of cosmetics containing lead, the use of lead-glazed crockery, the taking of snuff adulterated with oxides of lead; and the use of aërated beverages, and drinking water which has been allowed to have remained in contact with lead, are all recognized sources of lead-poisoning. In one remarkable case a proof-reader was poisoned by reading printed proofs for many years. Type-metal is an alloy of which lead is a preponderating constituent.

Water which contains more than one-twentieth of a grain of lead per gallon should be rejected as unsafe. Such a water gives a sensible darkening of colour when a wineglassful of it is placed in a white porcelain dish, acidulated with a few drops of hydrochloric acid, and then a drop of ammonium sulphide added. Soft waters, more especially those moorland and ferruginous which are acid, and those contaminated with the products of decomposing sewage, are especially prone to act upon metallic lead.

The most frequent cause of chronic lead-poisoning is the use of water kept in leaden cisterns or pipes, or the careless employment of white or red lead as a cement for pipes. For an instructive series of cases showing the effects of water poisoned with lead, see a paper by De Mussy. ('Dublin Quart. Jour.' May, 1849; also 'Med. Gaz.' vol. 44, p. 260.) These cases

at Claremont, among the members of the ex-Royal Family of
The effects were traced to the use of pure water which had
an impregnation of lead by contact with that metal, in the
n of from one-seventh of a grain to one grain in the imperial
Thirteen out of thirty-eight persons were affected, and to such
that the nails of the toes and fingers acquired a blueish discolora-
ıe children of the family did not suffer. No symptoms appeared
ır the water had been in use for a period of from five to seven
ınd more than half of those who used the water escaped any ill
According to Herapath, the symptoms of lead-poisoning have been
in a community by so small a quantity as one-ninth of a grain
ı a gallon; and Smith, of Aberdeen, concludes from his investiga-
t the limit of manifestly deleterious action would seem to be
ıe between one-tenth and one-twentieth of a grain in a gallon.
Report on Loch Katrine Water,' p. 107.) Waters collected from
ı districts generally contain lead, either in suspension or in
In one of these, proposed to be supplied to Wrexham, the
ınd the proportion of lead to be one-eleventh of a grain in a
ı quantity which might prove noxious to some portion of a town
n, as a result of long-continued use. A medical officer of health
before a Committee of the House of Lords, in May, 1864, that
s less than one-fourteenth of a grain of lead in a gallon, and
proportion, if present, would do no injury, while one-twelfth of a
ıld be noxious, although the data upon which this sharply-defined
n was based were not made public. According to Christison,
s act more or less upon lead, and as a limit of safety for persons
water for domestic purposes, the proportion of lead should not
ne-millionth part, or about one grain in fifteen gallons of water.
. Jour.' 1872, p. 852.) A water which acts chemically on the
ıy soon cease to act by reason of a deposit taking place in the
ıf the pipes, and the metal is thus protected from further chemical
When the water, before entering the pipes, is already provided
much lead that it easily admits of detection in a pint, a slight
l impregnation will suffice to render it poisonous. A safe sani-
would be that suggested by Penny. All lead-contamination is
able, and no degree of it can be considered safe. Lead is an
ıtive poison, and affects some persons powerfully in the smallest
s. For an account of the various conditions under which water is
be poisoned with lead, and the effects produced by the use of such
e reader is referred to the author's work 'On Poisons,' p. 506. An
tice has sprung up of substituting for pure block-tin an alloy of
ead, in the so-called tinning of iron and copper utensils. The small
ɔilers of cisterns, supposed to be tinned, are really covered with a
ɔewter; and lead may thus be conveyed into food and water under
ıances not suspected. Gobley has fully pointed out the danger of
tice in reference to public health. ('Ann. d'Hyg.' 1869, 1, 237.)
50 it was proposed to refine sugar by the use of a salt of lead. It
d that the proportion of lead-salt contained in sugar refined by
ess varied from one-twentieth to one-tenth of a grain in a pound.
ımissioners of Inland Revenue, considering that this small quantity
fect the public health, referred the consideration of the question to
Carpenter, and the author. They came to the conclusion that
s degree of contamination of such a universal article of food as
as objectionable, and that such a process of manufacture should
as possible prohibited.

not so much the quantity of lead taken in any case which deter-

mines the symptoms of lead-poisoning as its continued introduction. Never more than a very small quantity of lead is found in such cases in the blood and in the internal organs. Heubel has stated that the maximum is 0·02 per cent., or one part in five thousand. The metal is eliminated chiefly through the urine: perhaps also through the bile.

Symptoms and Appearances.—The symptoms of chronic poisoning by lead are well marked. These are, first, signs of impairment of nutrition; and even when the patient experiences no diminution of strength and health, the skin assumes a sallow or yellowish tint (icterus saturninus). The patient may experience a sweetish, styptic, or astringent taste in the mouth. A symptom of a peculiar nature was first pointed out by Burton ('Med. Gaz.' vol. 25, p. 687), namely, a *blueness* of the edges of the *gums*, where these join the bodies of the teeth: the teeth are of a brownish colour. Chambers affirms that this blue line on the gums is an early consequence of lead-poisoning in any form, and is a distinguishing sign of lead-colic. This line is absent where the teeth have been extracted. A blue mark round the edge of the gums has been noticed in some cases of poisoning by mercurial preparations; and it is possible that in an advanced stage of chronic poisoning by lead, it may be absent—as where, for example, the individual has ceased to expose himself to emanations of lead. ('Med. Times,' Feb. 14, 1846, p. 395.) Many facts tend to show that in general it is an early symptom.

Specific lead disease now frequently makes its appearance; though in many cases the poisoning stops short here. There are four recognised forms of chronic lead-poisoning; viz. colic, which is by far the most frequent form; pains in the joints (arthralgia), the source of which is often overlooked; paralysis, which, though a less frequent consequence than arthralgia, has attracted more notice; and, still more rarely, cerebral affections. Tanquerel, in 1830, found that these four forms of disease were met with in the following orders of relative frequency:—colic in 57, arthralgia in 35, paralysis in 5, and cerebal affections in 3 per cent. of the cases collected. The usual course is that there is at first pain with a sense of sinking commonly in or about the region of the navel, the seat of the colon, hence called colic. Next to pain there is obstinate constipation, retraction of the abdominal parietes, loss of appetite, thirst, fœtid odour of the breath, and general emaciation, with paralysis of a peculiar kind affecting the extensor muscles, and causing a dropping of the wrist, or showing itself in a general paralysis of the limbs. The paralysis is peculiar, and affects at first almost exclusively the extensor muscles at the back of the forearm, so that the patient loses the power of raising the hand from the wrist: hence the name 'wrist-drop' applied to this form of paralysis. Squinting and amaurosis are occasional symptoms. Albumen is commonly found in the urine in advanced stages of the disease. Chronic poisoning by lead often kills the patient. After death the large and small intestines have been found much contracted, and their coats thickened. These changes have been especially observed in the colon. Granular degeneration of the kidneys is common. The affected muscles are found atrophied and their striæ indistinct. In the year 1880, in England and Wales, sixty-seven deaths were assigned to lead, a larger number than was credited to any other poison.

Analysis.—White lead is a solid white powder, insoluble in water, and immediately blackened by sulphuretted hydrogen or ammonium sulphide. 1. When heated on platinum, it leaves a residue of yellow or orange-coloured oxide of lead, soluble in nitric acid. 2. The carbonate is easily dissolved with effervescence by diluted nitric acid. The lead, combined with nitric acid, may be readily detected in the filtered solution by the tests

already mentioned. Lead is detected in the tissues by incineration, dissolving the ash in dilute nitric acid, and passing sulphuretted hydrogen gas, when a black precipitate of lead sulphide falls. This may be again dissolved in dilute nitric acid and other tests applied to the solution. Satisfactory data are wanting as to the quantity of lead met with in the body after death.

Oxides of Lead.—The yellow oxide (massicot), and the puce-coloured oxide (peroxide), are but little known, except to chemists. *Litharge* and minium or *red lead* are, however, much employed in the arts, and have sometimes given rise to accidental poisoning. A woman who had swallowed two-and-a-quarter ounces of the red lead, was admitted into hospital. No symptoms appeared for nine hours. There was then colicky pain, with urgent vomiting, followed by headache and general tenderness of the abdomen. She entirely recovered in about twelve days. ('Guy's Hosp. Rep.' 1850, p. 209.) In March, 1870, owing to an accident, some red lead became mixed with a quantity of beer at a brewery at Guildford. Several persons who drank this beer suffered from lead-poisoning. One man died, but it was probable that disease of the lungs was the immediate cause of death. Colicky pains, a blue line on the gums, and constipation, were well-marked symptoms among the patients. In the course of a month as many as twenty-seven cases of lead-colic came under treatment. ('Lancet,' 1870, 1, pp. 428 and 495.) One fatal case of poisoning by red-lead has been recorded. ('Report of Calcutta Med. Soc.' July 13, 1881.) The woman died within five hours. The symptoms were pains and convulsions. The only noticeable appearance met with in the body was corrosion of the stomach.

Liquids used for culinary or dietetic purposes, especially if they contain a free *acid*, are liable to become impregnated with lead, derived from the glaze of the vessel in which they are kept, and thus form poisonous salts. If vinegar is used, lead acetate may result. Litharge-glaze is also easily dissolved by alkaline or *fatty* substances. The eating of dripping, or the fat of meat baked in a newly glazed vessel, has been known to give rise to a slight attack of colic; while the symptoms were referred by the person to some substance mixed with the food. (For cases see 'Med. Gaz.' vol. 47, p. 659; also 'Lancet,' 1860, 1, 962.) In 1852, four men partook of rhubarb-pie and milk for supper; shortly afterwards they were all seized with violent vomiting and intense colic. Lead was detected in a portion of the vomited matters and food. The only source to which the lead could be traced was the glaze of the pans in which the milk was kept. *Cider* is sometimes poisoned with lead owing to the use of leaden vessels or pipes in its manufacture. An instance of the fatal effects of cider so poisoned is reported to have occurred in Worcestershire in 1864, and another fatal case occurred in Herefordshire in 1867. Eight men were seized with symptoms of lead-poisoning, and one died. Herapath found one grain of lead in a gallon of the cider. The leaden pipe was found corroded by the acid in the cider. Lead pipes are largely used by publicans for the supply of beer. It is possible, therefore, if the beer is acid, and is allowed to remain some time in the pipe, the first portions drawn may acquire an impregnation of lead, which may give rise to colic and other unpleasant symptoms. When liquids of this kind are impregnated with lead, the fact is immediately known by their being turned of a brown colour by sulphuretted hydrogen. Newly glazed vessels yield traces of lead, more or less, on boiling in them vinegar, pure acetic acid, or a solution of pure potash. In this manner the poisonous nature of the glaze may be tested, the lead being dissolved either by the acid or the alkali. Common acetic acid has been known to contain, as impurity, two per cent.

of lead acetate. Lead is also found in citric and tartaric acids, and in salts which have been crystallized in leaden pans. Litharge was formerly much used to remove the acidity of sour *wine*, and to convey a sweet taste. Lead acetate, or some other vegetable salt of the metal, is in these cases formed; and the use of such wine may be productive of alarming symptoms. Many years since a fatal epidemic colic prevailed in Paris, owing to this cause; the adulteration was discovered by Fourcroy, and it was immediately suppressed. Wine thus poisoned is known by its being blackened by sulphuretted hydrogen.

Snuff has been adulterated with red lead in order to improve its colour. Two instances of chronic poisoning by lead have come under the author's, and one under the editor's notice as a result of the presence of oxide of lead in snuff. One sample contained the oxide in large proportion. This noxious adulteration has frequently given rise to paralysis and other forms of lead-disease. ('Med. Gaz.' vol. 32, p. 138; 'Ann. d'Hyg.' 1831, 2, 197; 'Lancet,' Jan. 21, 1860, p. 60.) It is readily detected by incinerating a small quantity of the snuff in a porcelain capsule, and digesting the ash in warm dilute nitric acid. This may be afterwards diluted with water and filtered for the application of the tests for lead. Sonnenkalb considered that snuff frequently acquires an impregnation of lead, by reason of the coverings of lead in which it is packed. He has collected nineteen cases of this form of chronic poisoning: in fourteen of these there was paralysis, and in five there were symptoms of gastric disturbance. The arms were most commonly affected with paralysis and wasting of the extensor muscles. In twelve cases there was a blue colour of the gums. All suffered from colicky pains and constipation. The poisoned snuff had been used for a period of from six months to twenty years: and on leaving it off, the patients improved rapidly, and eventually recovered. (See also 'Lancet,' 1870, II. p. 781, and 'Pharm. Jour.' 1870, p. 465; and Horn's 'Vierteljahrsschrift,' 1868, 2, 175.)

Preparations of Copper.

All the salts of copper are poisonous. The two most commonly known in commerce are the Sulphate, or Blue Vitriol, and the Subacetate, or Verdigris. The former has been frequently taken and administered in large doses, for the purpose of suicide and in attempts at murder. In the latter case the attempt has been immediately discovered, owing to the strong metallic taste possessed by the salt. This would in general render it impossible that the poison should be taken unknowingly. With the exception of these salts, poisoning by copper is usually the accidental result of the common employment of this metal for culinary purposes. There are two copper salts—the Arsenite (Scheele's Green) and the Aceto-Arsenite (Brunswick Green)—which chiefly owe their poisonous properties to arsenic. This has been elsewhere considered (p. 279). In 1880, one death from copper poisoning was registered in England.

Blue Vitriol. *Sulphate of Copper. Copper Sulphate.*—Copper Sulphate has been frequently given for the purpose of procuring abortion. In doses of half an ounce and upwards, it acts as a powerful irritant on adults, and a much smaller quantity would suffice to destroy infants or children. The salt speedily causes vomiting of the most violent kind: this sometimes expels the poison from the stomach, and the person recovers. The *vomited* matters are remarkable for being generally of a *blue* or *green* colour; and broken crystals of blue vitriol were discovered in them, in a case in which the poison was taken in a loosely pulverulent state. If the *green* colour of the vomited liquids is owing to altered bile it will not

equire a blue tint on adding to a portion of the green liquid a olution of ammonia; but if it be caused by a salt of copper, this change f colour will serve to indicate the fact. There is headache, pain in the bdomen, with purging; the pain is of a colicky character; and in aggrated cases, there are spasms of the extremities and convulsions. ercival met with an instance in which violent convulsions were produced n a young woman by two drachms of the sulphate of copper. Paralysis, nsibility, and even tetanus, have preceded death, when the poison was dministered to animals. Among the symptoms casually met with in the uman subject, may be mentioned jaundice. This has been observed to ttend poisoning by the sulphate, as well as by Scheele's Green. The edicinal dose of copper sulphate as an emetic, is from five to fifteen rains, and as a tonic from one to three or four grains.

There are but few instances in which this poison has proved fatal in the uman subject. In 1836, a girl, sixteen months old, put some pieces of *blue-stone* (copper sulphate), which were given to her to play with, into er mouth. In a quarter of an hour the child vomited a blueish-green loured matter, with pieces of copper sulphate in it; the skin was lternately cold and hot, but there was no purging. The child died in *ur hours*, without being convulsed, but it was insensible before death. 'Med. Gaz.' vol. 18, p. 742.) Unfortunately no inspection of the body was ade. Galippe denies, on inadequate evidence, the poisonous properties f copper salts.

Appearances.—In poisoning with the salts of copper, the mucous embrane of the stomach and intestines has been found more or less ickened and inflamed, in the few fatal cases which have been hitherto amined: the membrane has been also found destroyed and softened in oisoning with verdigris. The gullet has presented an inflamed appearnce. In a case of poisoning with verdigris, quoted by Orfila, the omach was inflamed and thickened, especially towards the intestinal pening, the orifice of which, owing to the general thickening, was almost bliterated. The small intestines were throughout inflamed, and perration had taken place, so that part of the green liquid was effused into e abdomen. The large intestines were distended in some parts, and ntracted in others, and the rectum was ulcerated on its inner surface. 'Toxicologie.') The lining membrane of the intestines has been found roughout of a deep green colour, owing to small particles of verdigris lhering to it. It has been said that this is an uncertain character of oisoning by copper; since a morbid state of the bile often gives a similar lour to the mucous membrane of the stomach and duodenum. This jection cannot apply when the green colour is found in the gullet, and roughout the intestines; and, under any circumstances, the evidence from e presence of a green colour would amount to nothing in the judgment of a udent witness, unless copper were freely detected in the parts so coloured. he green stain, if due to copper, will be turned blue by ammonia.

VERDIGRIS. *Subacetate of Copper.*—This salt produces *symptoms* somehat similar to those caused by the sulphate. There is a strong styptic etallic taste, with a sense of constriction in the throat, followed by severe icky pains, vomiting of a green-coloured liquid, and purging, with olent straining (tenesmus). A woman who swallowed *two ounces* of rdigris died in three days: in addition to the symptoms above described, ere were convulsions and paralysis before death. Niemann relates that female, aged 24, swallowed *half an ounce* of verdigris, and died under mptoms of severe irritation of the stomach in sixty hours. ('Taschenbuch,' 458.) In consequence of the great uncertainty of its operation, subacetate copper is not employed internally.

The SUBCHLORIDE and CARBONATE are also irritant poisons.

Chronic poisoning by copper is occasionally seen among workers in this metal and its salts. The poison enters the system partly by the lungs in the form of dust, and partly by the skin in handling the metal or its salts. The marked symptoms are a coppery taste in the mouth, giddiness, pain in the bowels, vomiting, occasional diarrhœa, and wasting of the body. Clapton has pointed out another symptom, namely, a green line on the margin of the gums. He met with this in a sailor and in some working coppersmiths. ('Med. Times and Gaz.' June, 1868, p. 658.) The green line was well marked, and this was shown by tests to be owing to copper. The perspiration from the hands in working had converted the copper into subchloride, and thus led to its absorption by the skin. Several cases of chronic poisoning by copper among coppersmiths have been treated by Cameron, but this symptom was not noticed. ('Med. Times and Gaz.' 1870, 1, 581.)

The existence of chronic copper poisoning is not doubted by the majority of authorities on toxicology; but it must be admitted that much has been alleged as to this form of disease which is open to question. The fact that the majority of workers in copper and its compounds remain perfectly healthy is not conclusive as to the innocuous character of the metal, spite of the assertions of Galippe. ('Étude Toxicol. sur le Cuivre,' Paris, 1875.) Oppolzer asserts that he has seen a case of copper paralysis affecting the right arm, and very similar to lead paralysis. ('Ziemssen's Cyclop. of Med.' vol. xvii. p. 593.)

Chemical Analysis.—The salts of copper are generally known by their colour; whether in the solid state or in solution, they are either blue or green. The salts of one other metal are also of a green colour, namely, nickel; but there are striking chemical differences between the salts of this metal and those of copper. There are *three* very *soluble* salts of copper; two of these are blue, the sulphate and nitrate, and one green, the chloride. The solutions of the copper salts have generally an acid reaction. The salt should be dissolved in water, diluted, and the following tests may then be applied:—

Tests.—1. *Solution of ammonia* gives a blueish-white precipitate, which is soluble in an excess of the test, forming a deep violet-blue liquid. 2. *Potassium ferrocyanide* gives a rich claret-red precipitate; if the quantity of copper is small, the liquid acquires merely a light-red colour; if large, the precipitate is of a deep red-brown colour, and of a gelatinous consistency. Potassium ferrocyanide will act on the violet-blue solution produced by ammonia, provided acetic acid is added to neutralize the ammonia. One portion of the liquid may thus be tried by the two tests. 3. *Sulphuretted hydrogen gas*, or ammonium sulphide, gives a deep chocolate-brown precipitate, even in an acid solution; or, if the copper is in small proportion, merely a reddish-brown colour. 4. A slip of *polished iron* (a common needle), suspended by a thread in the liquid, slightly acidulated with sulphuric acid, is speedily coated with a layer of copper, even when the salt is present in very small proportion. If the needle is left for some days in the liquid, the iron will be slowly removed, and a hollow cylinder of metallic copper will remain. This may be washed, dissolved in diluted nitric acid, and tested with the foregoing tests; or the iron, coated with copper, may be at once partially immersed in ammonia and exposed to air. The liquid then becomes slowly blue. Half a grain of copper sulphate dissolved in sixteen ounces of water may be thus easily detected. The blue solution, acidified with acetic acid, gives a red colour or precipitate with potassium ferrocyanide. 5. *The Electrolytic test.*—If a few drops of the copper solution are placed on

um-foil, slightly acidulated with a diluted acid, and the platinum
n touched through the solution with a slip of zinc, metallic copper,
well-known red colour, is immediately deposited on the platinum.
the quantity of copper is small, there is merely a brown stain; but
liquid is formed by pouring on it ammonia, and exposing it to air.
lue liquid may be further tested with potassium ferrocyanide
low).

per in Organic liquids.—The copper is liable to be precipitated by
organic substances, *e.g.* albumen, fibrin, casein, and mucous mem-
; but some of these organic compounds are easily dissolved by acids,
n by an excess of the solution of copper salt. A portion at least
salt of copper is, therefore, commonly held dissolved. In such cases
s one peculiar character possessed by these liquids, *i.e.* they have a
dly *green colour*, even when the copper salt is in a far less than
ous proportion. The sulphate of copper, used in medicine and
stry, sometimes contains traces of arsenic. Ten grains of the crystal-
ulphate will occasionally be sufficient to yield evidence of the presence
enic. When the sulphate has been given as an emetic, traces of
may be found in the contents of the stomach or in the matters
d. Sulphate of copper is occasionally met with as a fraudulent
n to bread. (Horn's 'Vierteljahrsschr.' 1870, 1, 322. Also 'Med.
and Gaz.' 1871, 1, 509.)

polished needle, or a fine iron wire, may be used in these liquids as a
st for the presence of the salts of copper. If in large quantity, the
may be precipitated by sulphuretted hydrogen, the sulphide collected,
and converted into a soluble sulphate by the action of strong nitric
If in small quantity, the following is the most expeditious method
aining copper from any organic liquid which contains a soluble
ous salt of this metal. Having added a few drops of diluted sul-
acid, and filtered the liquid, let a portion of it be placed in a
im capsule or crucible, and a slip of zinc introduced. Wherever
atinum is touched by the zinc, metallic copper of its ordinary red
is deposited; and after having in this way coated the platinum
e, the surplus liquid may be poured off and the capsule well washed
The copper is then dissolved in nitric acid, and the tests may be
d to the solution after the excess of acid has been driven off by heat.
ce of nitric acid and heat a strong solution of ammonia may be used
cold. Under exposure to air the metal is oxidized and dissolved in
minutes, forming a blue solution. The ammoniacal solution may be
lized with diluted acetic acid, and potassium ferrocyanide then
d. The red colour of the metal deposited on platinum, is characteristic
per; but should any doubt exist, this may be removed by placing a
ed needle in the ammoniacal solution and adding diluted acetic acid
tralize it. The needle is immediately covered with a red layer of
. Not much importance should be attached to the discovery of mere
of this metal either in the body or in articles of food. Copper,
ted for, may be found in many cases in the tissues and in food,
circumstances quite unconnected with poisoning. ('Guy's Hosp.
1858, p. 303.)

the tissues or urine.—Dry and incinerate the organic matter, digest
sidue in warm nitric acid, and then evaporate to dryness. The
e may be dissolved in a small quantity of water, and a polished
immersed for some hours. The metallic deposit, if any, on the
, may be recognized as copper, either by its colour or by the action
monia.

per in food.—The medico-legal history of poisoning by copper would

be incomplete without some remarks on the action of certain articles of food on this metal, when it is used for culinary purposes. This is not a frequent form of accidental poisoning. The symptoms rarely appear until after the lapse of three or four hours, or even a much longer period. There is commonly nausea, with colicky pains and cramps in the limbs. It results from the experiments of Falconer and others, that metallic copper undergoes no change by contact with *water*, unless the air is present, when a hydro-carbonate is formed. If the water contains an acid such as vinegar, or common salt, or if there is oily or fatty matter in contact with the metal, then the copper is more rapidly oxidized, and the liquor or fat acquires a green colour. If the copper vessel is kept perfectly clean, and the food prepared in it is allowed to cool in other vessels, there is not much risk of its acquiring a poisonous impregnation: nevertheless, no acid, saline, fatty, or oily liquid should be prepared as an article of food in a copper vessel. (See 'Ann. d'Hyg.' 1832, 1, 102.) Under the influence of heat and air, a portion of copper becomes dissolved, and the oily or other liquid acquires a green colour. The preparation of fruits, such as preserves, in copper vessels, is necessarily attended with some risk; for, on cooling, a green crust is apt to form on the copper, just above the surface where the air and acid liquid meet. Some liquids, while boiling, appear to be little liable to this impregnation: thus, coffee, beer, milk and tea have been separately boiled for two hours together, in a clean copper vessel, without any portion of the metal being taken up by either of the liquids. ('Falconer, on the Poison of Copper,' p. 65, London, 1774; also 'Orfila,' vol. 1, p. 611.) Accidents of this kind are usually prevented by lining the copper vessel with tin, or by using vessels of silver; but in very large boilers this plan is not always adopted; cleanliness alone is trusted to, and this, when properly observed, is a sufficient preventive. In reference to culinary vessels the tin is often worn away, and the corroded copper is thus exposed to the action of any acids contained in the food. In 1866, some rhubarb-stems were stewed in a copper vessel imperfectly tinned and dirty, and were supplied to a family for dinner. The children and their governess partook of it—the latter very freely. All were taken ill. The governess suffered most; there was violent sickness, with other symptoms of irritation. She recovered partly under treatment, but had a relapse, and died from the effects of the poisoned food. The oxalic and malic acids in the vegetables probably acted strongly on the copper.

In 1866, a remarkable set of cases occurred in a family at Itchen Abbas, Hants, in which twelve or more members of the family suffered from symptoms of poisoning similar to those produced by copper in food. A badly tinned copper vessel had been used for cooking the food, with much salt. One patient, an old man, æt. 90, died after three weeks, the others recovered. The cook was charged with wilful poisoning, but was subsequently liberated. She brought an action against her master (*Tully v. Corrie*, Queen's Bench, Nov. 1867), but this resulted in a verdict for the defendant. (Guy's Hosp. Rep.' 1866, p. 329.) A set of cases is reported to have occurred at Geneva, in 1870, in which ten persons were taken ill with symptoms of irritant poisoning, and four died. It was found that the food had been cooked in a copper utensil containing a large quantity of verdigris. ('Pharm. Jour.' Aug. 1870, p. 158.) A fatal case of poisoning by copper is reported in the same journal for 1870, p. 874. Copper was found in small quantity in the body. Waldemann published a paper on the effects of copper and zinc and their alloy brass, when used for culinary utensils. (Horn's 'Vierteljahrsschrift,' 1870, 1, 247.)

The tin used for lining copper vessels is frequently alloyed with a large proportion of lead, and thus lead-poisoning may be substituted for poisoning

ith copper. According to Paasch, many of the accidents attributed to is form of copper poisoning are really due to other causes. (Casper's Vierteljahrsschrift,' 1852, B. i. H. i. S. 78.) It has been elsewhere stated at all the ordinary copper employed for culinary utensils, contains senic. In those cases in which the metal is converted into insoluble ides or salts by acid or fat, the arsenic may be found in an insoluble rm in the green incrustation produced. When copper thus forms an soluble salt, arsenic is not dissolved.

It has been stated that an impure gold alloy used by some dentists s been so largely composed of copper as to affect the health of those o have used the plates for the support of artificial teeth. The acid and lts in the saliva facilitate the production of a poisonous salt of copper.

In the making of preserved *fruits* and vegetable *pickles*, the salts of pper (blue vitriol) are used for the purpose of giving a rich green colour. ny of the green pickles sold in shops were formerly thus impregnated th the vegetable salts of this metal, to which they owe their bright grass-een colour. The iron-test is delicate. A bright needle immersed in the kle, or plunged into the solid, will be speedily coated with copper. Only portion of the copper is in a soluble form. The quantity of copper con-ned in such articles may not be sufficient to cause fatal effects; but rious symptoms of gastric irritation are sometimes produced, and in ung persons these may assume an alarming character.

CHAPTER 23.

RTAR EMETIC—SYMPTOMS—APPEARANCES—CHRONIC POISONING—CHEMICAL ANALYSIS—CHLORIDE OR BUTTER OF ANTIMONY—POISONING BY ZINC SULPHATE AND CHLORIDE—PREPARATIONS OF TIN—SILVER—GOLD—IRON—BISMUTH AND CHROMIUM—POTASSIUM BICHROMATE—THALLIUM.

ARTAR EMETIC. TARTARATED ANTIMONY. STIBIATED TARTAR. *Symptoms d Effects.*—When this substance is taken in a poisonous dose, a strong etallic taste is perceived in the mouth during the act of swallowing. In om a few minutes to an hour there is great heat and constriction of e throat, with difficulty of swallowing, violent burning pain in the region the stomach, followed by incessant vomiting, and, later, profuse purging, intness and extreme depression. The symptoms are indeed those of ute gastro-intestinal inflammation. The pulse is small and rapid, some-mes imperceptible; the skin cold, and covered with a clammy perspira-n; and the respiration is painful. Should the case prove fatal, death y be preceded by giddiness, insensibility, great prostration of strength, d sometimes violent spasms of the muscles of the extremities, which may ume either a clonic or a tetanic character. Such are the symptoms in an ute case of poisoning by this substance. Cases of poison by tartar emetic first greatly resemble those of poisoning by arsenic; but in fatal cases e remissions often seen in arsenical poisoning are absent, and recovery is mmon even when there is great collapse. Occasionally a pustular erup-n like that produced by the external application of tartar emetic, appears the skin.

Death may occur within twenty-four hours; but it is more common at later period. The *quantity* actually required to destroy life is unknown. will probably depend in some degree on whether active vomiting and rging have been excited or not; for these symptoms have not been

present in all cases. Doses of from twenty grains to one ounce have been taken without destroying life, although alarming symptoms of irritation have followed. In one case, a man, æt. 50, took forty grains of tartar emetic, and died in about four days. This was the only one out of five cases of poisoning by this substance quoted by Orfila which proved fatal. ('Orfila,' vol. 1, p. 480.) Beck mentions a case in which fifteen grains of tartar emetic in solution killed a child in a few weeks: vomiting and purging were among the symptoms, and these were followed by convulsions and death. This case proves that a patient is not always saved by vomiting and purging: the fatal effects on such an occasion are probably due to rapid absorption. ('Med. Gaz.' vol. 44, p. 334.) An adult was killed in ten hours by a dose of one drachm, in spite of early and violent vomiting. ('Med. Gaz.' vol. 45, p. 801.) In two cases *ten grains* killed each child in a few hours. A dose of four grains, however, has been known to produce alarming symptoms: this dose gave rise to violent pain in the abdomen, vomiting, and purging. The patient then fell into strong convulsions, which lasted half an hour. He became speechless, no pulse could be perceived, the skin was cold, and it was supposed that he was dead. Stimulating frictions and poultices were employed, and he slowly recovered in about fourteen days. This poison, administered in small doses, may occasion death by reason of its exerting a depressing influence on the action of the heart. Aged persons, or those who are debilitated by disease, may die under these circumstances from a medicinal dose or doses which would produce no injury to strong and healthy adults. The effects, however, should be clearly traced to the action of the poison, and not be owing to exhaustion as a result of disease. In 1853, a case was referred to the author, in which it was supposed that two doses of antimonial wine, equal to about *three grains* of tartar emetic, had caused the death of a man who was in a diseased condition, by its remote effects upon the heart. No trace of poison was found in the stomach or tissues; there were no symptoms to indicate poisoning, and under these circumstances death could not be reasonably attributed to the medicine. The man died in about twenty hours, probably from exhaustion of the vital powers as a result of disease, and not from the action of this substance.

In 1881, a young man was killed in six hours by a dose of fifteen grains of tartar emetic. The characteristic eruption of tartar emetic was found on the mucous membrane of the stomach. ('Friedreich's Blatter f. Gerichtl. Med.' 1882, p. 8.) A man, æt. 28, swallowed *two drachms* of tartar emetic by mistake for Epsom salts, and recovered from its effects. An hour after the poison had been taken he was found in the following state:—his pulse was imperceptible; the tongue was dry and red; the countenance cold, livid, bathed with clammy perspiration, and indicative of great suffering; violent pain was felt in the stomach and over the whole of the abdomen, with constant spasmodic contraction of the muscles, particularly of the abdomen and arms. The fingers were firmly contracted, and the muscles quite rigid. He vomited once, about half an hour after he had swallowed the poison; and after this, he had constant involuntary watery purging. An emetic of mustard and salt was given to him, and this produced violent vomiting of bilious matter. Green tea, brandy, and decoction of oak-bark were freely given. The cramps, vomitings, and watery purging continued for six hours. The symptoms then became mitigated, and he gradually recovered, suffering chiefly from profuse night perspirations. ('Lancet,' May 22, 1847, p. 535.) This case is remarkable for the anomalous character of the symptoms, as, in the absence of active vomiting, an emetic was actually required to be given, and also for the recovery of the individual after so large a dose of the poison. In the 'Assoc. Med. Jour.' for April 1, 1853, p. 281, will be

l reported a case in which a physician took half an ounce of tartar
ic by mistake for Rochelle salts. Vomiting did not come on for half
our; but under treatment, he recovered in a few days. Couling
ved a case of recovery from a large dose in 1866. A veterinary
on swallowed, by mistake for carbonate of soda, about 200 grains
rtar emetic in powder. He noticed a peculiar taste. Vomiting came
fifteen minutes, but only after tickling his throat. This continued
ıtly. In two hours there was severe purging, with symptoms of
se. The vomited matters were green, and the evacuations like boiled
There was no appearance of blood in either. In three hours severe
ps came on, affecting all the muscles: he was unable to move or speak.
dy and other remedies were employed, and in six hours, after a warm
iration, he began to recover. There was suppression of urine: only
ll quantity was passed, and this was of a coffee colour. For two or
days he suffered from stiffness in the limbs and in the muscles of the
nen. In one case, fifty-five grains caused the death of an adult in
n hours. In one instance a small dose of this substance caused
by producing intestinal hæmorrhage. ('Assoc. Med. Jour.' June 10,
p. 513.) Procter met with the cases of four children to whom, in
, by mistake, a mixture of sulphur and tartar emetic had been given.
unce of sublimed sulphur and one drachm of tartar emetic had been
ed among the four. The symptoms presented the same characters in
; early vomiting, which became violent and incessant, pain in the
ls, purging, great thirst, cold clammy perspiration, feeble pulse, cramps
e limbs and twitchings of the muscles, with great depression. There
no sense of heat or constriction in the throat, and no difficulty of
lowing. Under treatment they all recovered.
he following cases show the nature of the *appearances* likely to be
d after death. Two children, a boy aged five years, and a girl aged
years, each swallowed a powder containing *ten grains* of tartar emetic.
renty minutes after taking the powders, they were seized with violent
ting and purging, and great prostration of strength, followed by con-
ons and tetanic spasms; there was also great thirst. The boy died
ght hours, and the girl in twelve or thirteen hours after swallowing
lose. The bodies were inspected between four and five days after
h. In that of the boy there was effusion of serum in the right pleura;
ower lobe of the right lung posteriorly was redder than natural, and
peritoneum was injected from recent inflammation. The mucous mem-
e of the duodenum was inflamed, and covered with a whitish-yellow
d secretion; this was observed throughout the intestines, although the
ur was of a deeper yellow in the large intestines: there was no
ration. The peritoneal coat of the stomach was inflamed. The
ous membrane of this organ was also much inflamed, especially about
larger curvature and at the cardiac orifice: but there was no ulceration.
contents (about two ounces and a half of a dark bloody fluid having
ghtly acid reaction) were adherent to it; and in one case there was a
h of lymph. The tests used did not indicate the presence of anti-
y. With regard to other appearances, the tongue was covered with a
e fur, and appeared soddened; the throat was not inflamed; the wind-
and gullet had a natural appearance. On opening the head the dura
r was found congested; the longitudinal sinus contained a coagulum
mph and but little blood. The vessels of the surface of the brain
much injected with dark blood, the whole surface having a deep
le colour. Every portion of the brain, when cut, presented many bloody
ts. The cerebellum and medulla oblongata were also congested; there
no effusion in the ventricles or at the base of the brain. In the body

of the girl the morbid appearances were similar; there were in add
the arms, legs, and neck, patches resembling the eruption of sc
The arachnoid membrane was more opaque than usual; and on the
membrane of the stomach, where the inflammation was greatest, w
or three white spots, each about the size of a split pea, which app
be the commencement of ulceration. ('Lancet,' April 25, 1846,
A girl, æt. 16, swallowed a dose of tartar emetic amounting to fro
to sixty grains. There was severe vomiting in a quarter of an h
this was soon followed by purging: these symptoms continued fo
three hours. She also complained of pain, and a burning sensatio
the gullet. The vomited matters were of a dark colour. On the fo
morning she had recovered from the severity of the symptoms; b
afternoon there was a relapse. She continually threw her head b
screamed; the skin was warm and moist; the pupils were dilated;
knees drawn up. She died in about thirty-six hours after tak
poison, and during the six or eight hours previous to her death
quite delirious. An inspection was made thirty-six hours after dea
throat appeared swollen; the lungs were slightly congested; the h
healthy, and contained about six drachms of fluid blood. The
contained sixteen ounces of a thick bloody fluid: at the greater e
the coats were softened, and blood was effused under the mucou
several places. The small intestines contained a similar fluid, wit
mucus; but there was no appearance of inflammation. Only sligh
of the poison were found in the contents of the stomach by the us
the greater part having probably passed off by vomiting and
('Lancet,' Jan. 21, 1854.) In animals poisoned by this substance, I
the author found general inflammation of the lower half of the int

On April 18th, 1876, Mr. Bravo, a barrister, æt. 30, was pois
tartar emetic. After dining with his wife, and whilst alone in
at 6.30 P.M., he was suddenly seized with violent sickness and v
When seen at 10.30 P.M. by Dr. Moore, he was lying back in a chai
unconscious; the breathing was noisy, and the heart's action wa
perceptible. He did not appear to suffer pain, and his appearance
unlike that of a person under the effects of a narcotic. He had pr
complained of pain in the stomach, and an emetic of mustard an
had been given. The pupils were widely dilated; and he was u
swallow, when seen shortly afterwards by Mr. Harrison. At 1.45
first vomited blood. At 3.30 A.M., on the 19th, soon after he was
Dr. George Johnson and Mr. Royes Bell, a little consciousness re
and he then said, to account for his state, that he had rubbed his gu
laudanum, and that he might have taken some of this liquid. Just
becoming conscious, viz. at 2.45 A.M., he vomited blood, and passed
stools. Throughout the 19th, after the return of consciousness, he
excruciating pain, and was violently purged and vomited frequentl
the 20th the patient was seen by Sir William Gull, at 6.30 P.M., who
him pulseless and dying. He was told that he was dying of pois
was asked how he came by it. He replied, 'I took it myself.' 'W
you take?' 'Laudanum.' When told that he had taken mor
laudanum, he made no further statement bearing upon the matter,
to repeat a second time, 'I took it myself.' Pain, collapse, vomiting,
ing, and occasional convulsions, especially of the upper limbs, contin
near the close, when the vomiting and purging ceased. He died on t
of April, fifty-five hours and a half after the commencement of sym
At the autopsy made next day, the following appearances were obse
Dr. Payne. There was no appearance of inflammation, congestion, o
ration. The stomach contained about eight ounces of thick, gru

:, of a yellowish colour, containing small solid lumps, and had the of alcoholic fermentation. The gullet was natural, and contained of the same matter as the stomach. The first portion of the bowels ry soft, being torn in tying it, but subsequent careful examination l no perforation or ulceration. The surface was pale and yellowish at of the stomach. The whole of the small intestine was like this, the lower part, where there were some red spots. This part of the contained yellow pasty matter without any admixture of blood. quent examination showed, in the portion called the cæcum, several ulcers from which the bleeding had evidently taken place, but there perforation. The remainder of the large intestine was very deeply tained, but without ulceration. The contents were soft, dark-red al, composed of fœcal matter mixed with blood. The liver and were natural, as were also the pancreas, kidneys, and other abdominal . The skull and the membranes of the brain were found quite l, containing only the usual amount of blood. The brain-substance so natural, and contained no excessive amount either of blood or of fluid. The mouth and lips were natural, except that the papillæ at ck of the tongue were somewhat more prominent than is usual. was no other appearance of disease in the body, except what has oted.

om the first vomit of the deceased, Dr. Redwood obtained antimony lent to ten grains of tartar emetic. Antimony was also detected in er, and in fluid taken from the large intestines of the deceased, but the contents of the stomach. Traces of the metal were also dis- d in the urine passed during life. Dr. Redwood was of opinion that t twenty grains of tartar emetic had been taken by the deceased. A ; of wilful murder by some unknown person was returned, no tartar being traced into the hands of the deceased or any other person him. It was also known that Mr. Bravo was well read in medical udence, and was acquainted with the poisonous nature of tartar . Some months after the return of the above verdict, evidence came ossession of the editor, who watched the medical aspects of the case inquest on behalf of one of the persons living in the same house eased, showing that Mr. Bravo had tartar emetic in his possession six or seven weeks of his decease. He had purchased a large number ck powders, extensively advertised as a cure for dipsomania, and d instructions that these, if administered too freely to his wife, would romiting. It is possible that these powders—each of them consist- half a grain of tartar emetic with a pink vegetable pigment—may een taken in fatal amount by the deceased, who was unaware of oisonous nature, for the purpose of causing ejection of the laudanum he had admittedly taken. It is probable that the laudanum would he ejection of the tartar emetic, and thus increase the liability to a sult.

minal trials for poisoning with tartar emetic in the *acute* form are It is a poison which cannot easily be given in a large dose without ing speedily well-marked effects; and as vomiting is a common om, the poison is thus early ejected from the stomach. An extra- ry trial for murder by alleged poisoning with this substance took at Annapolis, U.S., in 1871. *Mrs. Wharton* was charged with ing her friend *General Ketchum*. The trial lasted fifty-two days, a astonishing amount of scientific evidence was brought forward for osecution and defence, apparently owing to the high social position parties; for there is nothing, medically speaking, in the case itself ight not have been settled in *forty*-eight hours. The General died

after a short illness, but the symptoms, taken as a whole, bore no resemblance to those observed in poisoning with antimony, although poisoning was suspected during life. The appearances in the body proved nothing for or against antimonial poisoning, and some physicians of experience deposed that the symptoms and appearances were consistent with disease affecting the membranes of the brain and spinal marrow. (See 'Guy's Hosp. Rep.' 1857, in which thirty-seven cases of poisoning by antimony are recorded.) On examining the chemical evidence, it appears that the process by sulphuretted hydrogen alone was employed, and a red-brown sulphide resembling that of antimony was obtained; but the quantity obtained as sulphide was only four-tenths of a grain, estimated as equivalent to *eight-tenths of a grain* of tartar emetic. Thus the chemical analysis brought out only a fraction of a grain, not amounting to one-twentieth part of the quantity said to be present; and no separation of antimony in the metallic state was made to corroborate the inference drawn from the coloured precipitate produced by sulphuretted hydrogen. No chemical results were produced in Court, although twenty grains would have allowed of the production of metallic antimony in a few minutes by copper, tin, zinc, and platinum, or by Marsh's process. The evidence that antimony was really there was not satisfactory, and that twenty grains were present in the stomach was wholly unproved. The chemical evidence does not therefore conflict with the pathological evidence, for it failed to show with clearness and distinctness the presence and proportion of the poison said to have been found. The prisoner was acquitted. ('Amer. Jour. Med. Sc.' Ap. 1872, p. 329.)

It has been supposed that the cases in which this poison has proved fatal have been few; but the author has reported thirty-seven cases, of which sixteen were fatal. The smallest fatal dose was in a child, *three quarters of a grain*, and in an adult, two grains; but in this instance there were circumstances which favoured the fatal operation of the poison. ('Guy's Hosp. Rep.' 1857.)


Chronic poisoning.—An account of the effects produced by tartar emetic given at intervals in small doses to healthy persons, has been published by Mayerhofer. ('Heller's Archiv.' 1846, pts. 2, 3, 4, p. 100 *et seq.*) The principal symptoms are those of gastro-intestinal catarrh, viz. nausea, and vomiting of mucous and bilious liquids; great depression; watery purging, followed often by constipation of the bowels; small, contracted, and frequent pulse; loss of voice and muscular strength; coldness of the skin, with clammy perspiration; and death from exhaustion. Several cases have occurred in this country, which show that tartar emetic has been thus criminally employed. In addition to the cases of *Ann Palmer* and *J. P. Cook*, there are those of *Reg.* v. *M'Mullen*, Liverpool Sum. Ass. 1856; *Reg.* v. *Freeman*, Drogheda Spring Ass. 1857; and the cases of the *James family* at Liverpool. (*Reg.* v. *Winslow*, Liverpool Aut. Ass. 1860.) The prisoner *Winslow* was indicted for the murder of his mistress, Ann James. It was clearly proved that antimony had been administered to the deceased, not only by the discrimination of the symptoms, but by the detection of the poison in the urine during life. The deceased was at the time labouring under malignant disease affecting the cæcum and stomach, but it was alleged that her death had been accelerated by antimony. The prisoner was acquitted, owing to the difficulty of proving the act of administration. The poison had been given at intervals in small doses, and as deceased survived about a fortnight after the last dose, it was found only in traces in the various organs. The death of this woman led to the exhumation of the bodies of three of her relatives who had lived in the same house with her and the prisoner, and had died suddenly some months previously under

circumstances. The viscera of these bodies were examined, ch case antimony was found in small quantity, but still diffused through the organs. So far as the history of could be obtained, they were victims of chronic poisoning by This cause of death was not suspected at the time. (See . Rep.' 1857 and 1860; also *Reg.* v. *Hardman*, Lancaster Sum.

l Analysis.—Tartar Emetic as a solid, in the state of powder, id crystalline. It has been occasionally sold by mistake for d with soda powders, and sometimes for cream of tartar.—1. r dissolved by fourteen parts of cold, and two of boiling solution has a faint acid reaction, and an acrid metallic s decomposed by long keeping. It is insoluble in alcohol. wder dropped into ammonium sulphide is turned of a deep ur, and is thereby known from other poisonous metallic salts. eated in a reduction-tube, it is charred, but does not, like e, melt before charring. The metal is partially reduced bon of the vegetable acid, and the decomposed mass has a e metallic lustre. A metallic sublimate is not produced in this by the moderate heat of a spirit-lamp. 4. When boiled in aining one-sixth part of pure hydrochloric acid, and metallic mersed in the boiling liquid, a grey deposit of antimony takes is metal. The colour of the deposit is violet-red if the quantity ll, but the deposit is black and pulverulent if very large. 5. n acidulated with one-tenth part of hydrochloric acid gives in the sooty deposit of antimony on a surface of tin-foil. A solution roduces no deposit on tin under these circumstances. A better distinguishing antimony from arsenic, or of detecting arsenic d with antimony, is to employ stannous chloride with fuming c acid. Both acids of arsenic, and all their solid compounds ately precipitated on boiling them in this mixture, as brown enic. Tartar emetic in powder produces no change of colour ate, unless it contains some traces of arsenic, when the liquid brown.

Emetic in solution.—1. On slowly evaporating a small quantity glass it will crystallize in *tetrahedra* and in other derivatives of ron. If obtained from a very diluted is crystallization is confused, and hat of arsenious acid. 2. *Diluted* dded to the solution, throws down ecipitate; the other mineral acids ame way; but, as they precipitate ther metallic solutions, there are to them which do not hold with itric acid. The white precipitate l is easily and entirely dissolved by f tartaric acid: it is also soluble in tric acid, so that if much of the test t once, no precipitate is produced. *m ferrocyanide* does not precipitate n, whereby tartarated antimony is m most other metallic poisons. 4. *Ammonium sulphide*, and *l hydrogen gas*, both produce in the solution an orange-coloured differing in colour from every other metallic sulphide. The tate is not soluble in ammonia, but is dissolved by hot strong ic acid.

Fig. 33.



Crystals of Tartar Emetic, magnified 30 diameters.

The foregoing tests merely indicate the presence of antimony; but it is in reality the poison which we have to seek. Tartarated antimony the only salt of antimony in a soluble form which is likely to be met with in medicine or chemistry. Should it be required to prove the presence of a tartarate, this may be done by filtering the liquid from which antimony has been precipitated by sulphuretted hydrogen gas. evaporating this liquid, cream of tartar may be obtained.

In liquids containing organic matter.—Tartar emetic is precipitated by tannic acid in all its forms, but not readily by albumen or mucous fluids; therefore it may be found partly dissolved in the liquids of the stomach, provided no antidote had been administered. As a trial test, if the liquid is much coloured, a portion of it may, like arsenic, be submitted to dialysis (p. 216); tartar emetic may be thus obtained in water in a state sufficiently pure for testing. The organic liquid should be filtered, and then strongly acidulated with tartaric acid. A current of sulphuretted hydrogen gas is now passed into it, until there is no further precipitation. The sulphide is collected, washed, and dried. If it is antimony sulphide, it will have an orange-red colour, it will be insoluble in a solution of ammonia, and when dried it will be dissolved by boiling hydrochloric acid (forming antimonious chloride) with the evolution of sulphuretted hydrogen gas. The boiling should be continued for several minutes or until the liquid is colourless. On adding this solution, if not too acid, to water, a white precipitate of antimonious oxychloride (powder of Algaroth, *Mercurius Vitæ*) falls down, soluble in tartaric acid. This is characteristic of antimony. A portion of the acid liquid may be introduced with pure zinc and sulphuric acid into a Marsh's tube or apparatus, like that described at p. 272. The gas which escapes at the jet produces a black deposit on paper impregnated with a solution of silver nitrate; but unless sulphur is present it produces no change on paper impregnated with a salt of lead. When ignited, it burns with a pale yellowish-white flame, producing white fumes of antimony sesquioxide. Porcelain, or glass, depressed on the flame, receives a black deposit of reduced metallic antimony, with greyish-coloured layers of oxide at the circumference. There is no metallic lustre, such as is produced by arsenic, under similar circumstances, but on examining the reverse side of the glass, a dim metallic lustre will be perceptible. This deposit, unlike arsenic, is not dissolved by a solution of bleaching powder. If a current of the gas is heated to redness while passing through the tube, a tin-white ring of metallic antimony will be deposited close to the heated spot. This is much more fixed than the deposit of arsenic, and cannot, like it, be resolved into a white sublimate of octahedral crystals. If the gas is made to pass through a small quantity of fuming nitric acid, it is decomposed, the antimony is oxidized, and may be obtained as a white insoluble residue on evaporation. A solution of silver nitrate produces no change of colour in this deposit; but if one or two drops of ammonia are added, there is a black precipitate of silver antimonide.

The following method of detecting antimony, when dissolved in any organic liquid, is based upon electrolysis by which copper and other metals may be detected under similar circumstances (p. 312). Acidulate a portion of the suspected liquid with hydrochloric acid, and place it in a shallow platinum capsule. Touch the platinum, through the acid liquid, with a piece of zinc. Wherever the metals come in contact, metallic antimony, in the state of a black powder, is deposited on the surface of the platinum. The liquid should be poured off, and the capsule thoroughly washed with distilled water. This may be effected without disturbing the deposit. A small quantity of ammonium sulphide poured on the black deposit, speedily dissolves it when heated, and on evaporation an orange-

red antimony sulphide remains. This may be dissolved by a few drops of strong hydrochloric acid, and on adding the acid liquid to water, an oxychloride of the metal is precipitated. By this process antimony in small quantity may be detected in any liquid containing organic matter. In place of ammonium sulphide, strong nitric acid, or a solution of permanganate of potash, may be employed to oxidize the metallic deposit and the dry residue treated as described below.

In the tissues.—The antimony may be deposited in the organs, so that neither the sulphuretted hydrogen nor the electrolytic process will yield any satisfactory results. The liver or other organ should be finely cut up, and boiled in a mixture of one part of hydrochloric acid and five parts of water. After some time, the liquid may be tested by introducing into it a slip of polished copper-foil free from antimony. If antimony is present in small quantity, the copper will acquire a reddish or violet-coloured deposit on its surface: if in large quantity, the deposit will be grey with a metallic lustre, or sometimes in the state of a black powder. The deposit may be removed from the copper by boiling with a dilute solution of potassium permanganate, and the solution thus obtained may be tested for antimony. These deposits do not yield octahedral crystals like those obtained from arsenic. A slip of tin-foil may be suspended in the cold, in another portion of the acid liquid, diluted so that the hydrochloric acid forms only one-tenth part by measure. Either immediately, or in the course of a few hours, if antimony is present, the tin is covered with a black deposit of metallic antimony. As arsenic is not deposited on pure tin under similar circumstances, this furnishes a ready method of detecting the admixture of antimony with arsenic. These may be regarded as trial tests. For the demonstration of the presence of antimony, when in mere traces, we may resort to the following process, by which antimony may be completely separated from organic substances. Coil a portion of zinc-foil round a portion of platinum-foil, and introduce the two metals into the hydrochloric-acid decoction of the tissues, just sufficiently diluted to prevent too violent an action on the zinc. (See fig. 28, p. 292.) Warm the organic liquid, and suspend the coils in it. Sooner or later, according to the quantity of antimony present, the platinum will be coated with an adhering black powder of metallic antimony. Wash the platinum-foil, and digest it in strong nitric acid. So soon as the black deposit of antimony is dissolved from its surface, the platinum may be removed. Add a few drops of nitric acid, and evaporate the acid liquid to dryness. The residue, redissolved in hydrochloric acid, and the solution diluted and treated with a current of sulphuretted hydrogen, will yield an orange-red sulphide of antimony. This black deposit of antimony is also readily dissolved from platinum-foil by ammonium sulphide, yielding on evaporation an orange-red sulphide of antimony; it is soluble in nitric, but not in hydrochloric acid. When kept for a few days in contact with water and air, the black metallic deposit is sometimes converted into a white oxide, and entirely disappears. Antimony in the metallic state is so easily procured from a small quantity of material, by one or other of the above-mentioned processes, that on no account should this be omitted. The procuring of the metal may be made subsidiary to the procuring of the sulphide, as the metal can be easily oxidized and converted into sulphide in a pure form, and obtained entirely free from organic matter. A reliance on a small quantity of a coloured precipitate from sulphuretted hydrogen alone, would be most unsatisfactory as chemical evidence.

It is in all cases best, however, to destroy the organic matter previous to testing for antimony. This may be done, as described under the head Arsenic (p. 274), by means of potassium chlorate; or the organic matter—

liquid or solid—may be heated with sulphuric acid, and successive additi potassium nitrate made till a clear and almost colourless solution is obt This may then be gently heated till the white fumes of sulphuri almost cease to be evolved. The residue, when diluted with wate be tested by the above tests. It must be remembered that the dis of tartar emetic in the contents of a stomach is by no means a proof having been taken or administered as a poison, since it is freq prescribed as a medicine, and often taken as such by persons of the accord. We could only suspect that it existed as a poison, or had death, when the quantity present was large, and there were corresp appearances of irritation in the stomach and bowels. The presence quantity, if not lawfully administered as a medicine, is always a susp fact and demands explanation. In two cases of criminal administra small doses, the quantity found in each body did not exceed three The mere discovery of it in a medicinal mixture cannot of its evidence of an intent to poison.

The detection of antimony in the tissues does not necessarily in that it has been criminally administered or has caused death; t presence should be reasonably accounted for, as antimony may hav unlawfully administered. In several cases of suspected death from deposits on copper, evidently of an antimonial nature, have been ob from the liver or tissues. On inquiry it has been found that anti medicines had been taken shortly before death. Conversely, wh antimony is found, or the metal is present in the tissues in quantity, it is still consistent with medical experience and observatio the person may have died from antimony. The case of *Mrs. Pet* Yeovil (July, 1860), furnishes a remarkable illustration of this fact. lady had symptoms during her illness which were referred by her m attendants to the effects of small doses of antimony. Antimony was in the urine both by them as well as by Herapath: but after (*i.e.* in about nine days) no antimony was found in the tissues or an of the body. Upon this fact, and the evidence of coexisting disease, alleged that she had died from disease and not from poison. Th returned a verdict to the effect that her death had been accelerat irritant poison. ('Med. Times and Gaz.' Aug. 25, 1860, p. 190; Se p. 271; and Sept. 29, p. 317.) The case is important in this respe shows that antimony may be found in an evacuation, and that death be accelerated by the metal; but although the person may die within days, none may be detected in the body.

CHLORIDE OR BUTTER OF ANTIMONY. *Symptoms and appearances.*—A æt. 12, swallowed by mistake for ginger-beer four or five drachms solution of butter of antimony. In half an hour he was seized vomiting, which continued at intervals for two hours. There was ness, with general weakness, and great prostration of strength. Rem means were adopted, and the next day the chief symptoms were heat uneasiness in the mouth and throat, with pain in swallowing. There numerous abrasions on the mucous membrane of the mouth and th and there was slight fever, from which the boy quite recovered in eight days. Another case of recovery from a dose of an ounce is repo ('Lancet,' Feb. 26, 1848, p. 230.) In another case, an army sur swallowed, for the purpose of suicide, from two to three fluid o of chloride of antimony. About an hour afterwards there was e prostration of strength, with coldness of skin, and incessant atte *to vomit.* The most excruciating griping pains were felt in the abdo *and* there was a frequent desire to evacuate the bowels, but not

was passed. In the course of a few hours reaction took place, the pain subsided, and the pulse rose to 120. There was now a strong disposition to sleep, so that he appeared as if labouring under the effects of a narcotic poison. In this state he continued until he died, ten hours and a half after he had swallowed the poison. On inspection the interior of the alimentary canal, from the mouth downwards to the jejunum, presented a black appearance, as if the parts had been charred. In general, there was no mucous membrane remaining, either on the stomach or elsewhere; only a flocculent substance, which could be easily scraped off with the back of a scalpel, leaving the submucous tissue and the peritoneal coat. All these parts were so soft that they were easily torn by the fingers. In 1868, a man swallowed three or four ounces of bronzing liquid, which proved to be a solution of chloride of antimony. He vomited violently, but continued his work for an hour; the vomited matters were of a yellowish-green colour. There was pain in the stomach, but no purging. He was not seen by a medical man. He had passed a sleepless night, and complained much of oppression in the region of the heart. He died in about eighteen hours. On inspection the mucous membrane of the stomach was found much corroded. Near the intestinal end there were numerous putty-like masses. In parts it was of a vividly red colour, and in other parts blackened. There was no perforation. The duodenum presented similar appearances. There was no mark of corrosion on the lips, or in the lower part of the gullet. The upper part of this tube, the fauces and mouth, could not be examined. Antimony was found in the putty-like masses of membrane as well as in the contents of the stomach and the liquid swallowed.

Analysis.—1. If any portion of the chloride is left in the vessel, it may be tested by adding a few drops to a large quantity of water, when the whitish-yellow oxychloride will be precipitated: the supernatant liquid will contain hydrochloric acid, which may be detected by silver nitrate. 2. The precipitated white oxychloride is dissolved by a solution of tartaric acid. 3. This acid solution is precipitated of an orange-red colour by a current of sulphuretted hydrogen gas.

In the tissues.—The method of analysis is the same as for tartar emetic.

Preparations of Zinc.

White Vitriol, *Zinc Sulphate, or Sulphate of Zinc. Symptoms and Appearances.*—The symptoms produced by an over-dose of zinc sulphate, which is a powerful emetic, are pain in the abdomen and violent vomiting, coming on almost immediately, followed by severe purging. After death the stomach and intestines have been found inflamed. The sulphate appears to act as a pure irritant; it has no corrosive properties. This salt may cause death indirectly as the result of exhaustion from violent vomiting when an ordinary dose has been given to a person already debilitated by disease. ('Med. Times and Gaz.' July 16, 1853, p. 78.) A case is reported, in which it is supposed that the sulphate destroyed life by its slow or chronic effects. ('Lancet,' Aug. 27, 1859, p. 210.) Neither the sulphate nor the oxide of zinc can be regarded as powerful irritants, although they are usually described as poisons. Tardieu and Roussin have published a case of criminal poisoning by zinc sulphate administered in soup. A woman, æt. 60, died in three days under the usual symptoms of irritant poisoning (gastro-enteritis). Zinc was detected in the coats of the stomach and intestines, as well as in the spleen and liver. ('Ann. d'Hyg.' 1871, 2, 341.) In one case a lady recovered after taking sixty-seven grains. ('Lancet,' May 17, 1856.) In another, which occurred in 1872, communicated by Mackintosh, a man, æt. 20, recovered in a few days after

taking an ounce of zinc sulphate by mistake for Epsom salts, to whi it closely approximates in appearance. There was early vomiting an purging of a most violent kind, with great prostration of strength. Th greater part of this large dose was no doubt thus carried out of the body.

In cases of epilepsy, zinc sulphate has been given in doses of fo grains three times a day, first commencing with small doses. As a rule ill effects follow, and none of the usual symptoms of irritation are observ With respect to *zinc oxide*, it has been prescribed in large doses with injury to health. An epileptic took as much as one pound in seven mont the largest quantity taken in one day being seventy grains. Although did not suffer from the remedy, the disease was not cured. ('Lanc March 1, 1862, p. 224.)

Analysis.—The sulphate is seen in white prismatic crystals, clos resembling in appearance Epsom salts and oxalic acid; from oxalic acid is distinguished by remaining fixed when heated on platinum-foil; fr Epsom salts, by tests applied to its solution. It is readily dissolved water, this fluid taking up about one-third of its weight at comm temperatures. Tests for the *solution.*—The solution has a slightly a reaction. The following tests may be used for the detection of zi 1. *Ammonia* and potash give white precipitates, soluble in excess of t alkalies. 2. *Potassium ferrocyanide*, a white precipitate. 3. *Sulphuret hydrogen* and ammonium sulphide, milky-white precipitates, provided t solution is *pure* and neutral, or nearly so. If the solution is very ac sulphuretted hydrogen produces no effect whatever. 4. Zinc may be se rated in the metallic state by placing in the solution a slip of magnesiu

In Organic liquids.—If the sulphate is dissolved and the solution is t too acid, we may pass into it a current of sulphuretted hydrogen gas; t presence of zinc is immediately indicated by a milky-white precipita the sulphide may be collected and decomposed by boiling it with hyd chloric acid. The solution may be then tested for zinc. This compou being frequently employed as an emetic, may be innocently present an organic liquid, or in the contents of the stomach. Zinc sulphate h been occasionally fraudulently added to bread. (Horn's 'Vierteljahrsch 1870, 1, 323.)

Zinc Chloride, or Chloride of Zinc.—Zinc chloride is sold to th public as a disinfectant, under the name of 'Sir W. Burnett's Fluid. This is a highly concentrated solution of the pure, or sometimes impur chloride of the metal, containing about 220 grains of the salt per flu ounce; it has been taken by accident in several cases, and in one instan was supposed to have been criminally administered as a poison. Eight deaths from chloride of zinc are reported to have occurred in four yea (1863–7). In 1880, no death was returned from any zinc salt.

Symptoms.—In one case, about two ounces of a solution containing only twelve grains of the chloride were swallowed. The patient immediately felt pain and nausea; vomiting followed, and she recovered, but suffered from some indisposition for three weeks. In a second case, a wine-glassful equivalent to at least 200 grains of solid chloride, was swallowed. The man instantly experienced a burning pain in the gullet, burning and griping pain in the stomach, great nausea, and coldness. Vomiting came on in two minutes; the legs were drawn up to the body; there was cold perspiration, with other signs of collapse. The man perfectly recovered in sixteen days. ('Ed. Med. and Surg. Jour.' Oct. 1848, p. 335; and 'Brit. Amer. Jour.' Dec. 1848, p. 201.) Other cases show that the con centrated liquid has a strong corrosive action, destroying the membrane of the mouth, throat, gullet, and stomach. There has been frothing of the

h, with general lividity, and coldness of the skin. In a case in which a mouthful of the fluid had been swallowed, the patient experienced ness and loss of sight, with immediate burning heat in the stomach: ting and purging came on, and the former symptom continued for a . There was so much irritability of the stomach for a period of three s, that the patient became greatly reduced. Among the early symptoms loss of voice, which did not return for five weeks. ('Med. Times,' 11, 1851, p. 382; and Nov. 8, 1851, p. 497.) R. Hassall met with e in which the nervous symptoms were strongly marked, and were of culiar kind. Three ounces of 'Burnett's Fluid' were swallowed. e was immediately a sense of constriction in the throat, with a hot ing sensation in the stomach. There was no pain in the mouth, and was no appearance of corrosion in this cavity or on the lips. There incessant vomiting, the vomited matters consisting of thick mucus ked with blood; and some portions of mucous membrane were dis-ged. There was no purging until the third day, when the discharges the bowels had a coffee-ground appearance. After the lapse of a ight, a train of nervous symptoms set in, indicated by a complete ersion of taste and smell. The patient recovered in about three hs. ('Lancet,' Aug. 1853, p. 159.) A case which occurred to Mark-proved fatal in about *ten weeks* after the poison had been swallowed. patient, a woman, æt. 46, took half a wine-glassful of 'Burnett's l,' equal to about 100 grains of zinc chloride. Immediately after ng it, she suffered from vomiting and pain in the stomach. She k freely of water: the vomiting ceased in a few days, and she appeared ve recovered. In about three weeks the vomiting returned: it was sant, and with this there was pain in the stomach. She sank exhausted, ntly from the secondary effects of the poison. ('Med. Times and ' June 11, 1859, p. 595.)

uckwell recorded the following case. ('Br. Med. Jour.' 1874, II. 7.) A woman, æt. 21, drank three-fourths of a teacupful of 'Bur-s Fluid.' As the fluid passed down into the stomach she felt no but directly afterwards she was seized with a violent burning pain e pit of the stomach, and vomited. Six hours later, when admitted hospital, an emetic was given, and vomiting encouraged by the nistration of warm water. Next morning she had a feeling of much ness, and a burning pain with tenderness at the epigastrium and under left ribs. The throat was sore, and there was some difficulty in lowing. She had retched frequently; but there had been no action e bowels. The lips, mouth, and tongue were unhurt; but the soft e, uvula, tonsils, and pharynx were inflamed. The pulse was rapid feeble. Pain and sickness continued, with intermissions; she gradually me feebler and emaciated, and died 116 days after the administration e poison. The body temperature, which at first rose to 100·6° F., efore death to 96°.

ppearances after death.—In the case of an infant, aged fifteen months, h died from the effects of this poison, the lining membrane of the mouth throat was white and opaque. The stomach was hard and leathery, ining a liquid like curds and whey. Its inner surface was corrugated, ue, and tinged of a dark leathern hue. The lungs and kidneys were ested. The fluid of the stomach was found to contain zinc chloride. d. Times,' July 13, 1850, p. 47.) The concentrated solution of zinc ride is both a corrosive and an irritant poison, exerting also occa-ally an action on the nervous system. In a case which proved fatal uy's Hospital, in 1856, the coats of the stomach were excessively ened, and had a leathery *consistency*. In another case, the stomach

is described as being shrivelled up and ulcerated. ('Pharm. Jour.' Jan. 1867, p. 420.) In Markham's case, the stomach was so constricted at the intestinal end by a cicatrix, that it would only admit a crow-quill. The pyloric opening was involved in this cicatrix, which was about one quarter of an inch wide. There was no other sign of disease in the body. This case proves that death may occur from the poison even after apparent recovery. Chloride of zinc may destroy life either by producing stricture of the gullet or pylorus, or by its chemical action on the lining membrane of the stomach leading to a loss of power of digestion, emaciation and exhaustion. In 1863 several deaths were reported to have taken place in consequence of 'Burnett's Fluid' having been mistaken for medicine. In one of these a lady swallowed a wine-glassful in place of fluid magnesia. She suffered severely, and died from the secondary consequences of the poison, in six weeks. In another, a girl, æt. 17, swallowed half a wine-glassful of the fluid, and died from the effects in less than two hours. The symptoms here were copious vomiting of frothy mucus with shreds of membrane, and cramps in the legs, which were drawn up to the abdomen. In Tuckwell's case (p. 327), with the exception of the cardiac orifice, which was healthy, the whole of the mucous membrane of the stomach was of a deep red colour, thickened, and softened. This redness was uniformly intense, as far as that part of the fundus which lay in contact with the spleen; here the redness was deeper than elsewhere, and there was an ulcer of the size of a penny-piece, which had penetrated the coats of the stomach, but had been prevented from perforating, partly by the spleen, which formed the floor of the ulcer, partly by adhesions which passed from the spleen to the stomach. The pyloric orifice was small and tight from firm contraction of the sphincter; but there was no real constriction of the opening. There was also congestion along the whole length of the intestinal canal. (Other cases, in which the symptoms and appearances were somewhat similar, will be found reported in the 'Lancet,' 1864, 1, p. 35; and 2, p. 267.)

Analysis.—The chlorine may be detected by nitrate of silver—the zinc by the tests above described. (See Sulphate.) If a portion of the diluted solution is placed in a platinum capsule, and the platinum touched with magnesium, the zinc is immediately obtained in the metallic state.

Zinc can be detected in the *tissues* only by incineration at a low temperature, and an examination of the ash. The chloride is, however, sometimes used for the preservation of the dead body. This might account for its occasional presence.

Preparations of Tin.

The only preparations of this metal which require to be noticed as poisons are the *Chlorides*, or *Muriates*, a mixture of which is extensively used in the arts, under the name of *Dyer's Spirit*. The salts may exist in the form of whitish-yellow crystals; but more commonly they are met with in a strongly acid solution in water. They are irritant poisons; but so seldom used as such, that only one death occurred from them in England and Wales during a period of two years.

Small quantities of tin are not uncommonly taken in articles of tinned food, and in Demarara sugar, prepared by what is known as the 'Bloomer process,' in which a solution of stannous chloride is employed. Such sugar contains about half or one-third of a grain of tin per pound. According to the editor's experiments, neither dogs fed on such sugar, nor persons who habitually consume such sugar as an article of daily dietary, suffer *in health*.

Preparations of Silver.

ver Nitrate, or Nitrate of Silver. Lunar Caustic. Lapis infernalis.—
ıbstance, which is commonly met with either in crystals or in small
of a white or dark-grey colour, is readily soluble in distilled water;
mon water it forms a milky solution. It acts as a powerful corrosive,
ing all the organic tissues with which it comes in contact. There
least two cases on record in which it has proved fatal in the human
: one of these occurred in 1837–8, but the particulars are unknown.
mptoms come on immediately, and the whitish, flaky matter vomited
ered dark by exposure to light. Dark-coloured spots on the exposed
f the skin will also sometimes indicate the nature of the poison. In
ı woman, æt. 51, died in three days from the effects of taking a
ıce mixture containing fifty grains of nitrate of silver (lunar caustic)
n divided doses. She vomited a brownish-yellow fluid before death.
omach and intestines were found inflamed. It is stated that silver
und in the substance of the stomach and liver. A well-marked case
oning with this substance occurred to Scattergood. A portion of a
f lunar caustic dropped down the throat of a child aged fifteen
ı. In spite of treatment, the child died in six hours in violent
ions. ('Brit. Med. Jour.' May, 1871, and 'Amer. Jour. Med. Sci.'
871, p. 287.)

Preparations of Gold.

chloride.—This is the only preparation of gold which requires notice.
powerful irritant poison, acting locally like silver nitrate. Nothing
wn of its poisonous effects on man; but, in administering it to
s, Orfila found that it caused extensive inflammation, and even
ion, of the mucous membrane of the stomach. ('Toxicologie.') The
is absorbed and carried into the tissues, but its poisonous action
s to be independent of absorption.

Preparations of Iron.

rous Sulphate, or Sulphate of Iron; Copperas, or Green Vitriol.—This
ınd has been several times administered with malicious intention.
eath from it took place in 1837–8, and another in 1869 was the
: of a criminal trial in France. A man was convicted of having
his wife and his son by administering to them ferrous sulphate in
(Bouchardat, 'Ann. de Thérap.' 1872, p. 146.) It is not, however,
ve preparation; for a girl who swallowed an ounce of it recovered,
gh she suffered for some hours from violent pain, vomiting, and
g. (Christison.) Green vitriol or copperas is sometimes given
abortive. A suspicious case is reported, in which a woman far
ed in pregnancy, but enjoying good health, was suddenly seized
lnight with vomiting and purging, and died in about fourteen
The body, which had been buried, was disinterred, and iron found
e quantities in the viscera. The symptoms are not always of this
kind. In a case which occurred to Chevallier, a man gave a large
ferrous sulphate to his wife. There was neither colic nor vomiting.
oman lost her appetite, but ultimately recovered. In another case
d by the same authority, a woman was tried and convicted of
ng her husband with ferrous sulphate; but in consequence of the
diversity of opinion among the scientific witnesses at the trial
ing the poisonous properties of this metallic salt, and the dose in
it would be likely to operate injuriously, the Court and jury recom-
l that the sentence of death should not be carried out. ('Ann.

d'Hyg.' 1851, 1, 155; 'Med. Gaz.' 1850, 45, 640.) The reader will find some remarks in reference to the action of ferrous sulphate on the body by Orfila, in the same journal, 1851, 2, 337. At the Nottingham Autumn Assizes, 1859, a woman *Riley* was indicted for administering copperas to two children. She put the substance into gruel. It gave to the gruel a greenish colour and a peculiar taste, which led to the discovery. It caused sickness, but no other serious symptoms. As there was no evidence of an intent to murder, and it was then not unlawful to administer poison with any other intent, the prisoner was acquitted. This salt has been much used for criminal purposes in France. ('Med. Gaz.' vol. 47, p. 307; 'Ann. d'Hyg.' 1850, 1, 180, 416; 1851, 1, 155; 2, 337.) Copperas is said to have proved fatal to sheep. It had been mixed with the pulp of beet-root for cattle-food. ('Med. Times and Gaz.' 1863, 1, p. 511.)

Ferric Chloride; Muriate of Iron; Tincture of Perchloride of Iron.—The last is an acid solution of ferric chloride in rectified spirit: it is of a red-brown colour, and is much used in medicine. The liquor is also made, but without spirit. Christison relates an instance in which a man by mistake swallowed an ounce and a half of this liquid: the symptoms were somewhat like those produced by hydrochloric acid. He at first rallied, but died in about five weeks. The stomach was found inflamed and thickened towards the intestinal end. A case was reported to the Westminster Medical Society, in 1842, in which a girl, æt. 15, five months advanced in pregnancy, swallowed an ounce of the tincture of muriate of iron in four doses in one day, for the purpose of inducing abortion. Great irritation of the whole urinary system followed; but this was speedily removed, and she recovered. In another case, a healthy married woman swallowed, by mistake for an aperient draught, *one ounce and a half* of the tincture of muriate of iron. She immediately ejected a portion, and violent retching came on, which continued for some time. There was great swelling of the glottis, with cough, and difficulty of swallowing. These symptoms were followed by heat and dryness of the throat, with a pricking sensation along the course of the gullet and stomach; and in the afternoon a quantity of dark liquid blood was vomited. The motions were black, owing doubtless to the combination of sulphur with the metal. In about a month the patient was perfectly restored to health. ('Prov. Jour.' April 7 and 21, 1847, p. 180.) Another case of recovery from a large dose has been reported. The patient, æt. 72, swallowed by mistake *three ounces* of the tincture in a concentrated state. The tongue soon became swollen; a ropy mucus flowed from the mouth and nose; there was croupy respiration, with a sense of impending suffocation. The pulse was feeble, the skin cold and clammy, and the face swollen and livid. A castor-oil mixture brought away inky evacuations, and the patient rapidly recovered. ('Dub. Med. Press,' Feb. 21, 1849.) From the occurrence of these cases of recovery, it would be a mistake to infer that this is not a noxious compound. The largeness of the dose has commonly led to early vomiting, and the rejection of the greater part of the acid liquid. Besides, it varies much in strength, and unless this is defined in any given case, it is difficult to draw an inference of the actual quantity taken.

In 1879, a teaspoonful of the stronger solution pharmacopœial of perchloride of iron was given, undiluted, to a girl, æt. 18, by mistake for a linctus. The bowels were freely opened, and she vomited several times within ten minutes of taking the liquid. The stomach was then washed out. Shortly after she again passed a stool, and continued to vomit freely. The nurse and the patient both asserted that vomiting and purging supervened within three minutes of the administration of the poison. Great feebleness and depression came on. In two days she began to recover;

but pain in the gullet continued for several days (unreported case of the editor).

Comparatively small doses may seriously affect pregnant females, and among the criminal uses to which this preparation is put may be mentioned that of procuring abortion. At the Lincoln Lent Assizes, 1863 (*Reg.* v. *Bumble*), a druggist was convicted of having supplied this noxious liquid to a woman with the intent to procure her miscarriage. He directed her to take a teaspoonful three times a day, and at the same time prescribed for her eight pills a day, each containing half a grain of powdered cantharides. Although the woman had taken only two doses of the tincture of perchloride of iron, she suffered from severe pain over the whole of the abdomen, with violent pain in the region of the stomach and bladder: there was constant vomiting of a greenish-coloured matter, and great pain in passing her urine. The quantity of urine secreted was small, and contained much blood. These symptoms were in great part due to the cantharides. The proper dose of the iron-tincture is from ten to forty minims. Here it had been greatly exceeded, without any lawful excuse on the part of the prescriber. A case of recovery from an ounce of this tincture is reported. ('Pharm. Jour.' April, 1869, p. 605.) A woman, æt. 30, swallowed this quantity. She suffered from vomiting and purging, the motions being black. Emetics were given, and she recovered in five hours. ('Lancet,' 1869, 1, p. 9.) A favourite abortifacient is a mixture of the chloride with aqueous solution of aloes. There are three recognized pharmaceutical preparations of this substance. The stronger solution of perchloride of iron of the British Pharmacopœia contains 254 grains of ferric chloride in each fluid ounce. The solution and the tincture respectively of perchloride of iron are of equal strengths—one-fourth that of the stronger solution—and contain each sixty-three and a half grains of the chloride in a fluid ounce.

The perchloride of iron has been used as an injection in uterine diseases; but it is a most powerful local irritant, and in one instance caused death by inducing peritonitis. The symptoms were rigors, severe vomiting, and abdominal pain. The mucous membrane of the uterus was stained of a deep black, and iron was readily detected in its substance. ('Amer. Jour. Med. Sci.' April, 1870, p. 566.)

Chemical Analysis.—The hydrochloric acid may be detected by silver nitrate and nitric acid, while the iron is immediately indicated by a precipitate of Prussian blue on adding a solution of *potassium ferrocyanide*.

Preparations of Bismuth.

Bismuth Subnitrate. Subnitrate of Bismuth. Pearl-White. Magistery of Bismuth.—This substance, in a dose of *two drachms*, caused the death of a adult in nine days. There was a strong metallic taste in the mouth, burning pain in the throat, with vomiting and purging, coldness of the surface, and spasms of the arms and legs. On inspection, the throat, windpipe, and gullet were found inflamed; and there was inflammatory redness in the stomach and throughout the intestinal canal. ('Sobernheim,' 335.) In a case mentioned by Traill, a man took by mistake *six ounces* of the subnitrate in divided doses in three days. He suffered from vomiting and pain in the abdomen and throat, but finally recovered. Outlines,' p. 115.) These cases are sufficient to prove that a substance which is but slightly soluble in water may exert a powerfully poisonous action. The oxide and subnitrate of bismuth, owing to imperfect washing, are frequently contaminated with arsenic in the form of arsenic acid; and as the symptoms produced by large doses have closely resembled those caused by arsenic, *the symptoms may have been due to this impurity*. The

arsenic may be detected by dissolving the subnitrate in hydrochlor slightly diluted, and introducing it into Marsh's apparatus. The ar flame is apparent on combustion, and the usual deposits may be ol on glass and porcelain. The products of combustion may be collect tested by the processes described at p. 273. This impurity in the sub may modify a conclusion respecting the presence of traces of arsen body when bismuth has been administered medicinally. ('Brit. a Med. Chir. Rev.' Oct. 1858.)

Analysis.—The subnitrate is a whitish, chalky-looking, non-cry powder, insoluble in water, soluble in hydrochloric acid, and precipitated white by dilution with water: the white precipitate soluble in tartaric acid, and is blackened by a solution of sulph hydrogen, or by ammonium sulphide. A solution of the substance i acid gives no precipitate with diluted sulphuric acid.

Preparations of Chromium.

Potassium Bichromate, or Bichromate of Potash.—Well-observed in of poisoning by this compound, which is now extensively used arts, are rare; and therefore the details of the following case Gaz.' vol. 33, p. 734), are of interest. A man, æt. 64, was found his bed twelve hours after he had gone to rest: he had been h snore loudly during the night, but this had occasioned no alarm relatives. When discovered he was lying on his left side, his lowe being a little drawn up to his body: his countenance was pale, pla composed; eyes and mouth closed; pupils dilated; no discharge fr of the outlets of the body; no marks of vomiting or purging, r

Fig. 34.



Crystals of Potassium Bichromate, magnified 30 diameters. They have a deep orange-red colour.

stain upon his hands or person, or u bed-linen or furniture. The surfa moderately warm. Some dye-stuff, form of a black powder, was found pocket. On inspection, the brain membranes were healthy and natural was neither congestion nor effusion part. The thoracic viscera were hea well as those of the abdomen, with ception of the liver, which contained hydatids. A pint of a turbid inky- fluid was found in the stomach. The membrane was red and vascular, part at the union of the greater end wi gullet: this was ascribed to the kno temperate habits of the deceased. absence of any obvious cause for death, poison was suspected on analyzing the contents of the stomach they were found to bichromate of potash. The dye-powder taken from the man's pock sisted of this salt mixed with cream of tartar and sand. It is rem that in this case there was neither vomiting nor purging. T does not appear to have operated so much by its irritant pro as by its effects on the nervous system. This, however, is by no an unusual occurrence, even with irritants far more powerful tl bichromate of potash. A boy recovered from the effects of a this salt, but only after the lapse of four months. The first sy were pain, vomiting, dilated and fixed pupils, cramps in the le insensibility. His recovery was due to early and active tre ('Guy's Hosp. Rep.' 1850, p. 216.) Another case in which, ow *timely* treatment, a man, æt. 37, recovered from a large dose of t

as communicated to the author. It seems that with suicidal intent he man swallowed about two ounces of the bichromate in solution, ixed with pearlash. In about two hours he was seen by Andrews, nd he was then apparently in a dying state. He was suffering chiefly om severe cramps, the pupils were dilated, the pulse was scarcely rceptible, and there was vomiting and purging of greenish-coloured acuations. The stomach-pump was used, and olive-oil and diluents ere given. In about nine hours the urgent symptoms abated, and e man complained only of great pain in the shoulders and legs. here was no gastric irritation nor tenderness of the abdomen. He was ischarged cured at the end of a week. A woman, æt. 24, died from the fects of this salt taken for the purpose of procuring abortion. The mptoms were those of an irritant—severe pain, vomiting, and purging. Horn's 'Vierteljahrsschr.' 1866, 2, 113.)

A medical man, who had inadvertently tasted a solution of bichromate of potash, suffered from severe symptoms resembling those of iatic cholera. ('Prov. Jour.' Dec. 24, 1851, p. 700.) Wood furnished he author with the particulars of a case in which two drachms of this ubstance destroyed the life of a woman in *four hours*. In the first wo hours she suffered from violent vomiting and purging, the vomited atters being of a yellow colour. When admitted she was in a dying tate, pulseless, unconscious, and breathing slowly with great effort. he skin was cold, the lower lip swollen and purple, and the tongue wollen. The chief appearances were, a dark and liquid state of the blood; he mucous membrane of the stomach was in great part destroyed, of dark brown colour approaching to purple; the duodenum at its upper art of a florid red colour, and at its lower part much corrugated, as well s the upper half of the jejunum.

This salt, in the state of fine powder or in a saturated solution, has a eal irritant action on the skin and on parts from which the skin has en removed. ('Ann. d'Hyg.' 1864, 1, 83.) It produces what are lled 'chronic sores,' affecting the hands and exposed parts of the face. cording to recent observations, workers in chrome factories—of which ere are only six in the world—suffer from a peculiar irritation of the ptum of the nose, apparently due to the action of bichromate of potash, hich leads to a perforation of the nasal septum. ('Lancet,' Jan. 1882.) romic acid is a powerful corrosive poison, destroying all organic textures. Pharm. Jour.' Jan. 1872, p. 568.)

Lead Chromate (Chrome yellow) is a powerful irritant poison: a dose a few grains of this pigment has proved fatal. (See case of two boys, . Syd. Soc. Bien. Retrospect,' 1873–4, p. 452.)

Analysis.—The bichromate may be recognized by its orange-red our, as well as by the intense yellow colour which it gives to water ien dissolved. Its solution gives a deep red precipitate with silver rate, a pale yellow with barium nitrate, and a bright yellow with a salt lead.

Osmium.

Osmium tetroxide, commonly known as osmic acid, is a highly poisonous bstance, and accidents have occasionally resulted from its use in scientific restigations. It is a transparent, glistening, crystalline body, melting e wax in the hand, beginning to sublime at a moderate heat, and boilg at 212° F. It does not redden litmus, and has a caustic, burning ste. Its odour is most penetrating, and somewhat like that of chlorine of iodine. The vapour, even in minute quantities, causes serious flammation of the lungs when inhaled. It also attacks the eyes, so that

the experiment of volatilizing osmium in the blow pipe is an operation attended with great danger. Deville, who performed the operation twice, was rendered almost blind for twenty-four hours by having become exposed accidentally to the vapour of the tetroxide. This substance produces violent pain and inflammation of the conjunctivæ; and vision may be permanently injured by the subsequent reduction of a film of metallic osmium. The tetroxide also acts violently on the skin, causing a painful eruption.

As treatment, Claus has recommended the careful inhalation of sulphuretted hydrogen as an antidote for the vapour. Sulphur baths are the best treatment for the cutaneous eruption.

Preparations of Thallium.

The salts of this metal are, according to Paulet, highly poisonous, although this does not appear either from his own statement of their effects or from the experiments of Lamy. Paulet found that a dose of fifteen grains of thallium carbonate killed a rabbit in a few hours. The animal suffered from disturbance of breathing, loss of muscular power, and general trembling of the limbs; it appeared to die asphyxiated. The salts of this metal have been found to operate through the skin and cellular membrane—therefore by absorption.

Lamy dissolved seventy-seven grains of the sulphate in milk, and he found that this quantity sufficed to destroy two hens, six ducks, two puppies, and a middle-sized bitch. The prominent symptoms in the dogs were oppression of breathing, salivation, griping pains in the abdomen, the body being drawn up, with trembling and convulsions of the limbs, followed by paralysis. Vomiting and purging are not described among the symptoms. The two puppies did not die until four days after they had taken the poison. On opening the bodies of the animals, Lamy states that there was no mark of inflammation or other striking post-mortem appearance. In one experiment he found that a puppy died in forty hours from a dose of one grain and a half of the thallium sulphate. ('Chem. News,' Sept. 12 and 19, 1863.)

The salts are soluble, colourless, and nearly tasteless; and therefore may be easily administered.

These statements of Lamy and Paulet are not in accordance with the views of Crookes, the discoverer of the metal. Although much exposed to the action of the fumes, the metallic vapour produced no particular effects upon him. He also swallowed a grain or two of the salts without injury. These have a local action on the hair and skin, staining the former, and rendering the latter yellow and horny. ('Chem. News,' Oct. 3, 1863, p. 161.)

Maumé and Rabuteau state that thallium is at once both a cardiac and a muscular poison, in its action resembling mercury in one respect and potassium in another. The history of thallium as a poison is incomplete.

Analysis.—The best and most certain method of detecting thallium is to dry and burn the viscera, when, by the aid of the spectroscope, the green band indicative of thallium will manifest itself in the spectrum from the smallest quantity of the metal, in spite of admixture with other bodies.

VEGETABLE IRRITANTS.

CHAPTER 24.

VEGETABLE IRRITANTS—ALOES—COLOCYNTH—GAMBOGE—JALAP—SCAMMONY—SAVIN—CAPSICUM—CROTON OIL—CASTOR SEEDS—PHYSIC NUT—COLCHICUM—HELLEBORE—YELLOW JASMINE (GELSEMIUM SEMPERVIRENS)—OIL OF TURPENTINE—CAMPHINE—OIL OF TAR—CREASOTE—RESORCIN.

General Remarks.—The poisonous substances of an irritant nature which belong to the vegetable kingdom are very numerous as a class; but it will here be necessary to notice only those which have either caused death, or have given rise to accidental poisoning.

Aloes. Colocynth. Gamboge. Jalap. Scammony.

These different substances, which are used in small doses as medicines, are liable, when taken frequently or in large quantities, to excite vomiting, purging, and other symptoms of irritation. Colocynth has occasioned death in several instances: in one case a teaspoonful and a half of colocynth powder destroyed life; and one drachm of gamboge, a medicine much used by quacks, has proved fatal to man. (Traill's 'Outlines,' § 150.) Aloes and colocynth mixed, are said to be the basis of the quack medicine sold under the name of Morison's Pills. These have proved fatal in many instances from the exhaustion produced by excessive purging, owing to the large quantity of these pills taken in frequently-repeated doses. Our knowledge of the symptoms and appearances produced by these irritants is, indeed, chiefly derived from the cases which have proved fatal under this treatment. In the seventeenth volume of the 'Medical Gazette' will be found four cases of this description. The most prominent symptom is excessive purging, with the discharge of large quantities of mucus; the individual becomes exhausted, and slowly sinks. In some instances, the symptoms are those of inflammation and ulceration of the bowels. In 1836, a man was convicted of having caused the death of a person by the administration of these pills; in this instance the death of the deceased was clearly due to the medicine, and on inspection the stomach was found inflamed and ulcerated; the mucous membrane of the small intestines was inflamed and softened, and there was the appearance of effused lymph upon it. Holloway's Pills are of a more innocent description; the principal ingredient in them is aloes. In all cases it must be remembered that these drastic purgatives may cause serious symptoms, or even death, when administered to infants, or to persons debilitated by age or disease; and it is not necessary that the dose should be very large in order that fatal effects should follow. The question here will be, whether the medicine caused death, or whether it simply accelerated it: although, in a legal view, that which accelerates, causes.

Hierapicra (*Holy bitter*) is a popular aloetic compound, and one death is recorded to have been produced by it in 1837–8. There is reason to believe that it is occasionally used for the purpose of procuring criminal abortion. A man was tried and convicted of this offence (Aylesbury Summ. Ass. 1857, *Reg. v. White*), and the noxious properties of this

compound then became a subject of inquiry. The dose, and the co of the woman to whom it is administered, will of course affect the to this question. At the trial above mentioned, it was probably con to be a noxious substance within the meaning of the statute. T that, under the name of *Pulvis Aloes cum Canellâ*, it was formerly a into the British Pharmacopœias, cannot justify the mischievous which it may be put. *Hierapicra* is a snuff-coloured powder, of an i bitter taste. It consists of four parts by weight of aloes, and o by weight of powdered Canella bark. The proper medicinal d formerly fixed at from five to fifteen grains. Its injurious eff pregnant females are chiefly due to the aloes. This specially aff rectum, and by contiguity, under violent irritation or purging, ma the uterus. From the taste and colour which it imparts to liqui not probable that it could be taken by a female unknowingly.

Death has been caused by aloes taken in nitric acid; but in t the mineral acid was most probably the destructive agent. A case occurred in Germany a few years since, wherein a medico-legal was raised respecting the poisonous properties of *Aloes*. A woman, not labouring under any apparent disease, swallowed two drac powdered aloes in coffee. Violent purging supervened, and she the following morning, twelve hours after having taken the m On inspection the stomach was found partially, and the small in extensively, inflamed. There were no other particular appeara account for death, and this was referred to the effect of the aloes.

Savin. (Juniperus Sabina.)

This is a well-known plant, the leaves of which contain a po the form of an acrid volatile oil of a remarkable odour. The an irritant action, both in the state of infusion and powder. The by distillation a light yellow oil, on which the irritant properties plant depend. The powder is sometimes used in medicine, in a from five to twenty grains. Savin is not often taken as a poison specific purpose of destroying life; but this is occasionally an i result of its use as a popular means of procuring abortion, in this it has proved fatal. From the little that is known of its effects, it producing violent pain in the abdomen, vomiting, and strangury. death, the gullet, stomach, intestines, and kidneys, have been found much inflamed or congested. It has p no action as an abortive, except, like irritants, by causing a violent shock system, under which the uterus may e contents. Such a result can never be o without placing in jeopardy the lif woman; and when abortion follows, sh rally falls a victim. On the other h female may be killed by the poison abortion ensuing. In 1845, the auth with a case in which death had been by savin-powder—abortion having firs place. Eight ounces of green liqui found in the stomach, which, with the and the small intestines, was highly inf

Fig. 35.



Tips of the leaves of Savin, magnified 30 diameters.

The poison was easily identified by placing some of the minute p of the leaves found in the stomach, under a microscope. ('Med. *vol.* 36, p. 646.) The *oil of savin* is also powerfully irritant. F account of this, see 'Criminal Abortion.'

Cayenne Pepper. Capsicum.

medical botanist was charged with having caused the death of a boy, 5, by administering to him dangerous medicines (*Reg.* v. *Stevens*, C. May, 1864). The boy was suffering from diseased hip-joint, and, taking the medicines prescribed by the prisoner, he died. Letheby ined the stomach, and found in it patches of inflammatory redness, as would be produced by an irritant. He could detect no poison, but y bilious matter mixed with cayenne pepper. The mixture prescribed e prisoner contained this pepper, which the witness considered to be ous to a person in the condition of deceased. The prisoner was tted, the connexion of the death of deceased with his act being bly considered by the jury as not proved.


ı small quantities, this is a well-known stimulant, and a useful condi- and medicine. It has a hot, fiery taste, which lasts for a long time. a powerful stimulant, and in large doses produces a feeling of heat in iroat, difficulty of swallowing, pain in the stomach, and inflammation e gullet and stomach. Locally applied, it causes redness and even ring of the skin (Wibmer, 'Arzneimittel,' art. *Capsicum*). There undoubted instance recorded of its having proved fatal. It owes itant properties to an acrid resin (*capsicin*). From five to ten grains powder is considered to be a medicinal dose.

uinea Pepper, known as Grains of Paradise, is popularly considered to ghly noxious; but there are no facts to justify this view. This kind pper is an aromatic condiment.

Croton Oil. (Croton Tiglium.)

his is an oil extracted from the seeds of the Croton tiglium. The seeds, ı are sometimes called *Purging nuts*, resemble castor seeds in size and . The seeds have a dark brown or blackish colour, and are marked igitudinal lines. They have no smell. Their taste is at first mild leaginous, afterwards acrid and burning. When heated they evolve rid vapour. Croton oil is a powerful drastic purgative, producing, large dose, severe purging, collapse, and death. A case occurred in , in 1839, in which a man swallowed by mistake two drachms and a f croton oil. In three-quarters of an hour the surface was cold and ny, the pulse imperceptible, the breathing ılt, and the extremities and face were as as in the collapsed stage of cholera. In ur and a half purging set in; the stools passed involuntarily, and the abdomen ery sensitive to the touch. The patient lained of a burning pain in the course of the gullet. He died in four after swallowing the poison. There was no marked change in the us membrane of the stomach. For another fatal case, see 'Pharm. ' Feb. 1863, p. 379.

Fig. 36.



Seeds of Croton tiglium, natural size.

ı man, a dose of from fifteen to twenty drops of the *pure* oil might rise to excessive purging, and cause death by exhaustion. The cases ded of its fatal operation are few, and do not enable us to solve uestion from observed facts. According to Landsberg (Christison's ensatory'), thirty drops of the oil have killed a dog; and Christison ı that he has known four grains of the oil to produce an alarming e of purging. It is frequently mixed with castor oil and other sub- es, and the presence of these must of course influence the dose required t fatally. An aged woman died from the effects of an embrocation

containing croton oil with other drugs. A teaspoonful was incautiously given to her: she immediately complained of a hot burning sensation in her throat. She died in convulsions in three days. ('Med. Gaz.' vol. 43, p. 41.) A girl, æt. 19, took by mistake a teaspoonful of a liniment consisting of equal parts of croton and olive oils. In about half an hour she was seen by Brydon, and she then complained of an intense burning sensation in the throat and gullet; but there was no pain in the stomach. Her pulse was 84. Vomiting came on in a severe form, and this was promoted by a zinc emetic and warm water. After the vomiting had continued for a quarter of an hour, she complained of a severe pain in the stomach. Purging was not a prominent symptom. In a day or two she recovered. ('Edin. Med. Jour.' Aug. 1861.) In another case, a little girl, six years old, took by mistake about fifty-five drops of croton oil. There was vomiting, with some purging and feverishness for three or four days, but the patient recovered. ('Lancet,' 1870, 1, p. 553.) In these cases it is not improbable that the oil may have been adulterated. In one case reported, a child, æt. thirteen months, died in six hours from a small dose given by mistake. The croton oil was mixed with soap liniment, and the quantity taken was supposed to be less than three minims of the oil. ('Med. Times and Gaz.' 1870, II. 466.)

Chevallier reports two cases of poisoning by this oil. In one a druggist swallowed, by mistake for cod liver oil, half an ounce of croton oil. He felt a burning sensation in the throat and stomach, soon followed by vomiting and copious purging, with symptoms of collapse. He did not recover until after a fortnight. In the other case, quoted from Devergie, a man, æt. 25, swallowed by mistake two drachms and a half of the oil. Violent purging with collapse took place, and the patient died in four hours. ('Ann. d'Hyg.' 1871, 1, 409.)

A case was tried at Liverpool (*Reg.* v. *Massey and Ferrand*), in which the prisoners were charged with having caused the death of a man by placing in food, of which he and others had partaken, two drachms of powdered jalap, and from two to six drops of croton oil. Several persons, including the deceased, suffered from vomiting and purging; but they recovered, and the deceased himself so far recovered as to be able to go about as usual. He was subsequently attacked with inflammation and ulceration of the bowels, from which he died. The prisoners were acquitted, as the medical evidence at the trial failed to make out the connexion of this subsequent illness with the jalap and croton oil which had been put into the food.

Physic Nut (Jatropha Curcas).

The Jatropha Curcas is a West-Indian plant which produces seeds containing an acrid oil, having some of the properties of croton oil. Four seeds act as a violent cathartic, and severe vomiting and purging have been produced by a few grains of the cake left after the expression of the fixed oil from the bruised seeds. The oil operates powerfully in a dose of from twelve to fifteen drops. It produces a burning sensation in the throat, vomiting, purging, and other symptoms of irritation, followed by inflammation of the stomach and bowels. One hundred and thirty-nine children in Dublin suffered from the effects of these seeds ('Med. Times and Gaz.' Aug. 1858); and in 1864, a number of boys at Birmingham suffered severely from eating some of these nuts which they had found in a drug-store, but they all recovered. Chevallier refers to a case in which thirty-three persons were poisoned by eating these seeds. The *symptoms* from which they suffered were nausea, vomiting, and general depression. Twenty were so ill that they were placed in the beds of an hospital; the remaining

een soon recovered. The albumen of this seed is said to have a ur resembling that of the almond. ('Ann. d'Hyg.' 1871, 1, 408.)

The *Jatropha urens*, also a West-Indian plant, is said to produce serious ts upon those who touch its leaves, which are covered with stinging like those of the nettle. The wrist of a person accidentally came in act with some of the hairs. In a few minutes there was swelling of lips, redness of the face, faintness, great prostration of strength, and a degree of collapse, that for some minutes the sufferer was thought dead. He then rallied; there was sickness, and in twenty minutes man recovered. In another case the pain and swelling in the part ed lasted for some days, and an itching sensation continued for a er period. ('Pharm. Jour.' April 17, 1872, p. 863.) Assuming this ant of the symptoms to be correct, the poison connected with the hairs nly has a local action, but it is very rapidly absorbed, and produces ts resembling those of serpent poison.

Castor Seeds (Ricinus Communis).


Of castor oil itself nothing need be said. The seeds from which this extracted contain in the embryo an active poison, and a few of them sufficient to produce serious symptoms. Three or four seeds may act erfully on an adult. Eight may give rise to serious symptoms, and ger number may destroy life. Their taste is said to resemble that ie almond.

Symptoms and Appearances.—The symptoms which mark this form of oning are the absence of any disagreeable taste or sense of heat in the th and throat at the time of eating the seeds. Soon after the pulp has swallowed, there is severe pain in the abdomen, copious and painful iting, with bloody purging, thirst, and convulsions, terminated by death. ichardat, 'Ann. de Thérap.' 1872, p. 103.) A girl, æt. 18, ate about nty, one of her sisters four or five, and another two castor-oil s. In the night they were all taken ill. About five hours after the s were eaten, the deceased felt faint and sick; vomiting and purging on, and continued through the night. On the following morning appeared like one affected with malignant cholera. The skin was cold dark-coloured, the features contracted, the breath cold, the pulse ll and wiry; there was restlessness, thirst, pain in the abdomen, she lay in a sort of drowsy, half-conscious state. Whatever liquid was n was immediately rejected, and the matters passed by stool consisted fly of a serous fluid with blood. She died in five days without rally- ; the two other sisters recovered. On inspection, a large portion of mucous membrane of the stomach was found abraded and softened he course of the great curvature. A similar case, in which three s destroyed the life of a man in forty-six hours, is reported ('Med. es and Gaz.' 1861, 1, p. 555). There was general redness of the nach, and the abraded portion presented the appearance of a granulating ace of a pale rose-colour; it was covered by a considerable quantity of y mucus. The small intestines were inflamed, and the inner surface nem was abraded. The effects produced on the sisters who recovered, out the statement of Christison, that two or three of the seeds will ate as a violent cathartic. Other cases, including one which proved l, are recorded by Chevallier ('Ann. d'Hyg.' 1871, 1, 400). A woman lowed a quantity of the bruised seeds, in place of castor oil. She was seized with violent vomiting and bloody stools, which continued until death on the fifth day after taking the seeds. The mucous membrane he stomach and bowels was of a dark colour, much ecchymosed, and anted small patches of extravasated blood.

An officer took as a purgative seventeen seeds. In three hours there was violent purging, followed by vomiting and severe cramps, the patient passing into a condition resembling the collapse of Asiatic cholera. The vomiting was not stopped until after twenty-one hours, and recovery then took place. There was suppression of urine for forty-eight hours (Wiggers' and Husemann's 'Jahresbericht,' 1872, p. 538). The cake left after the pressure of the oil is poisonous to rats, as well as human beings (Chevallier). When the seeds are swallowed whole, they may fail to produce the severe symptoms above described.

Two children, aged respectively six and three years, ate some castor-oil seeds. The children when brought to the hospital were suffering from extreme collapse, consequent on vomiting and purging, the bodies pale and perspiring, pulse 130. The stools were frequent and watery. The substances ejected from the stomach were pulpy; there was pain in the abdomen, great thirst, and the tongue was furred and dry. There were no cerebral symptoms. Under treatment, they both recovered in two days. ('Med. Times and Gaz.' 1870, 1, 581.)

Fig. 37.




Castor seeds, natural size.

Analysis.—Castor *seeds* can only be identified in the contents of the stomach provided a portion of the outer coat is obtained. These seeds are remarkable for their peculiarly variegated surface. Externally they are of a pale grey, marbled with yellowish brown spots and stripes.

Meadow Saffron (Colchicum).

Meadow saffron (Colchicum Autumnale) contains a poisonous alkaloid —*Colchicine*—the effects of which on animals are similar to those of *Veratria*, the alkaloid existing in White Hellebore. The most noxious parts of the plant are the bulbs (or roots) and seeds, but the leaves and flowers have also an irritant action. Three deaths from colchicum are reported to have occurred in four years (1863–7). The *seeds* of colchicum are of a brown colour, varying from pale to dark. They are without smell, but have a bitter acrid taste. In size and colour they somewhat resemble grains of paradise, and have been mistaken for them. Their shape and size are represented in the annexed engraving.

Fig. 38.



Colchicum seeds, natural size.

Symptoms and Appearances.—In 1839, a gentleman swallowed by mistake one ounce and a half of *wine* of colchicum. He was immediately seized with severe pain in the abdomen: other symptoms of irritation came on, and he died in seven hours. In another instance, in which an ounce of the wine was taken, death occurred in thirty-nine hours. (Schneider's 'Annalen,' vol. 1, p. 232.) In a case in which a similar dose was taken, the person recovered after suffering from cramps in the limbs and twitching of the tendons. ('L'Union Méd.' Aug. 24, 1848.) A woman, æt. 56, suffering from rheumatism, for whom wine of colchicum had been prescribed, took by mistake an ounce of the wine of the seeds, in divided doses, in twelve hours. She suffered from nausea, violent and profuse vomiting, slight purging, with heat and burning pain in the throat, great thirst, cold clammy skin, feeble pulse, pain in the stomach, and pain in the forehead. Inflammation of the stomach supervened, and the retching, vomiting, thirst, and pain continued for three days. She then recovered. ('Amer. Jour. Med. Sci.' Jan. 1857; and 'Brit. and For. Rev.' 1857, 19, 409.) In other cases profuse purging has been the most prominent symptom, followed by death from exhaustion. ('Pharm. Jour.' July, 1861, p. 45.) In one instance, in which two ounces

the wine were taken, the symptoms did not come on for an hour and a lf; there was then copious vomiting of a yellow fluid, severe pain with eat tenderness in the abdomen, tenesmus and thirst. The patient died forty-eight hours, without being convulsed or manifesting any sign of ebral disturbance. The chief morbid *appearances* were a patch of redness the mucous membrane of the stomach, near the cardiac orifice; and ght inflammation of the intestines. The head was not examined. ('Med. .' vol. 10, p. 161; see also Casper, 'Ger. Med.' vol. 1, p. 450.) Three l a half drachms of the wine of colchicum were taken in divided doses, l caused death on the fourth day. There was no inflammation of the tric mucous membrane, but simply extravasation of blood into the cous follicles. The mucous membrane has been found softened in two es of poisoning by the tincture. In two other cases, in which an ounce l a half of the *tincture* was taken, and death ensued in forty-eight hours, morbid appearances were found. (Casper, 'Ger. Med.' 1857, 1, 451.) r a case of alleged poisoning by wine of colchicum, see Casper's ierteljahrsschrift,' 1860, 1, 1.

A woman, after having been tried and acquitted for an attempt to ison with oil of vitriol a man with whom she cohabited, was convicted eg. v. *Catherine Wilson*, C. C. C. Sept. 1862) of the murder of a s. *Soames*, who had died suddenly while nursed by the prisoner : years previously. The body was exhumed, but no poison was found the remains; yet the medical and other circumstances, as well as e conduct and correspondence of the prisoner, proved to the satisfaction the Court that deceased had been destroyed by vegetable poison, st probably colchicum, with the noxious properties of which she was ved to have been well acquainted. From the fact, which transpired reference to this trial, it appeared that the deceased was one of four sons who had at different dates fallen victims to the acts of this man. 1st, *Peter Mawer*, who died in October, 1854: the body was exhumed 1862, but no poison was detected. 2nd, *Mrs. Jackson*, who died in cember, 1859: the body was exhumed in January, 1860, and no poison s detected. 3rd, *Mrs. Atkinson*, who died in October, 1860: the body s exhumed in May, 1862, and no poison was detected. 4th, the case *Mrs. Soames*, above mentioned. All these persons died speedily while a state of health, under similar symptoms, and without any apparent tural cause to account for death. The symptoms as a whole were not concilable with any known disease; and they only appeared after the isoner was proved to have administered, under some pretence or other, od or medicine, the bottle which she employed for this purpose being pt locked up, or in her own possession. The motive for the murder, each case, was the acquisition of property. Two other attempts at rder, which failed, led to the inference that colchicum, either in wine brandy, was the substance which this woman employed. In these r persons, the symptoms were as nearly as possible of the same character burning pain in the throat and stomach, intense thirst, violent vomiting d purging, coldness and clamminess of the skin, excessive depression, and eat weakness. The pulse was small and weak, and death appeared to e place, without convulsions or loss of consciousness, from exhaustion. f these persons, one died on the second, one on the fifth, one on the hth, and one on the fourteenth day. In most of the cases the poison s probably given in divided doses: in the last case, the symptoms always peared every evening after the deceased had taken the tea prepared by e prisoner. McGregor Maclagan collected fifteen cases of poisoning by lchicum ('Month. Jour. Med. Sci.' 1852, p. 1). Roux relates the poisoning five soldiers by the administration of two ounces of wine of colchicum in

each case, in mistake for quinine wine. All died. ('Union. Med.' 1855, No. 36.) Keller reported a case of poisoning by three-fifths of a grain of the alkaloid, colchicine. The patient, a woman æt. 20, recovered. ('Ber. d. Krankenanstalt Rudelfstiftung in Wien,' 1857.)

Analysis.—Colchicum, in the form of tincture, possesses a warm aromatic taste and a peculiar odour. It owes its properties to the alkaloid *colchicine*. The process for detecting this substance consists in neutralizing with potash a portion of the aqueous acid solution (obtained by evaporating the alcoholic tincture) and then adding twice its volume of ether. The mixture should be well shaken. On pouring off the ether, and letting it evaporate spontaneously, an imperfectly crystalline or uncrystalline residue remains. (See 'Pharm. Jour.' 1857, p. 529.) When this is treated with one or two drops of concentrated nitric acid, the presence of colchicine is indicated by the residue acquiring a reddish-violet colour, which soon disappears.

Black, White, and Green Hellebore.

Symptoms and Appearances.—According to Wibmer, the roots of the black hellebore possess the greatest activity: but the leaves are also highly poisonous when used in the form of infusion. By long boiling the poisonous properties of the plant are diminished. The roots and leaves have a local irritant action, producing in small doses violent vomiting and purging, with severe pain in the abdomen, followed by cold sweats, convulsions, insensibility and death. The powdered root, in a dose of a few grains, acts like a drastic purgative. In a case reported by Morgagni, half a drachm of the aqueous extract killed a man, æt. 50, in eight hours. The symptoms were severe pain in the abdomen and violent vomiting. After death the whole of the alimentary canal was found inflamed, but especially the large intestines. (Wibmer, op. cit. *Helleborus.*) A case is quoted by the same writer, in which a table-spoonful of the finely-powdered root caused severe symptoms of irritant poisoning, which did not disappear for four hours. The man recovered on the fourth day. The experiments performed by Orfila on animals, show that this poison acts like a *local* irritant when applied to a wound. (Op. cit. vol. 2, 369.) Hellebore is a favourite quack remedy for worms, and has been given to procure abortion. It is not, therefore, surprising that it should be occasionally administered in an overdose, and cause death. A gentleman swallowed experimentally one drachm of tincture of green hellebore (*veratrum viride*), equal to twelve grains of the powder. He was found soon afterwards in a collapsed state, features sunk, skin cold, and covered with a profuse clammy sweat, pulse scarcely perceptible. He complained of intense pain in the region of the stomach. There was no purging. These symptoms were relieved by treatment, and the next morning the patient had recovered. ('Med. Times and Gaz.' 1863, 1, 5.)

Veratria.—White hellebore owes its noxious properties to the alkaloid *veratria*, which is itself a powerful poison. A physician prescribed medicinally for a lady, one grain of veratria divided into fifty pills, and three were directed to be taken for a dose. Not long after the first dose had been swallowed, the patient was found insensible, the surface cold, the pulse failing, and there was every symptom of approaching dissolution. She remained some hours in a doubtful condition, but ultimately recovered. Supposing the medicine to have been well mixed, and the pills equally divided, not more than one-sixteenth of a grain of veratria was here taken. This case proves that the alkaloid is capable of exerting a powerful effect. The common veratria of the shops is sometimes given medicinally in doses of one-sixth of a grain. It forms a grey uncrystalline powder,

cely soluble in water even on boiling; but is more readily dissolved alcohol and ether. It has a slight alkaline reaction, and combines acids, forming soluble salts. It has a hot, acrid taste, without any rness. Strong nitric acid gives to it a light red, turning to an eous colour. Diluted sulphuric acid, when heated with the powder, residue containing veratria, produces an intense crimson-red colour. ed with strong hydrochloric acid, it yields a fine purple colour. atria differs from colchicine in not being very soluble in water, and he action of strong nitric as well as of diluted suphuric acid. It rgoes no change of colour with iodic acid or sulphomolybdic acid.

Colocynth (Citrillus Colocynth).

Colocynth has occasionally produced death, preceded by symptoms of ric and intestinal irritation, and excessive purging. It is also perhaps sionally used for procuring abortion. Christison recorded the death young woman from a teaspoonful and a half of the powdered pulp. ues states that less than 60 grains of the powder, in decoction, has ed fatal; whilst recovery has taken place after three times that unt (Husemann, Handb. d. Toxicol., p. 625).

Yellow Jasmine (Gelsemium Sempervirens).

An alcoholic extract of the root of this plant and a tincture are used for icinal purposes. It has acted as a poison and destroyed life, but its t place as a poison cannot yet be satisfactorily assigned. From a case rted by Wormley ('Amer. Jour. of Pharm.' Jan. 1870), it appears to ng rather to the irritant than the narcotic class of substances.

A young healthy married woman took by mistake three teaspoonfuls luid extract of gelsemium—a concentrated tincture of the root containing 480 grains to the ounce. She was several weeks advanced in gnancy. In two hours after taking the extract, she complained of pain he stomach, nausea, and dimness of vision. These *symptoms* were wed by great restlessness, ineffectual efforts to vomit, and general peration. In four hours the pulse was feeble, irregular, and intermittent. re was great prostration, with irregular and slow breathing. The skin dry, the limbs cold, the pupils dilated and insensible to light; eyes were fixed, and there was inability to raise the eyelids. The vital ers rapidly gave way, and, without convulsions, death occurred in m hours and a half after the poison had been taken. On *inspection* the nbranes and substance of the brain and spinal marrow were normal. adipose tissue was tinged with bilious-looking matter. The lungs e collapsed, but natural in appearance, and the superficial veins were gested. The heart was normal—the superficial veins were injected and cavities were distended with dark grumous blood, inside of which was ell-defined fibrinous deposit. The stomach contained a small quantity ngesta: the peritoneum and intestines were in a healthy state. The kidney was congested.

It will be seen from this account that while death took place rapidly, re was nothing characteristic in the symptoms and appearances.

A muscular man, twenty-eight years of age, after a drinking bout, took ut two fluid ounces of gelsemium, to 'quiet his nerves.' When seen face was flushed; he was dozing, but could easily be roused, and talked lligently; the pupils were moderately dilated, reacting to light, and re was slight drooping of both eyelids. The pulse was strong and full, ut 100. An hour later the dipsomaniac, eluding his watchers, managed get out to a drug store, and procured half an ounce of fluid extract of

gelsemium, which he drank. He was found twenty-five minutes later, sitting in a shop, with relaxed limbs and pale face; but he was capable of speech. As he refused to swallow an emetic, sulphate of zinc was administered through the nose. Copious vomiting followed this and a second dose that was given. In spite of this he became speedily unconscious; pulse 130; respiration 40, and entirely thoracic; pupils moderately dilated, but acting. Brandy was given subcutaneously and by the rectum, and after faradisation of the diaphragm and intercostal muscles he rallied from the state of collapse into which he had fallen, only to relapse shortly after, when the same measures were repeated, and also hypodermic injections first of atropia, then of carbonate of ammonia, and inhalations of amyl nitrite, were employed. He died about five hours after taking the poison. ('Berl. Med. and Surg. Jour.' Dec. 22, 1881.)

Analysis.—Wormley discovered that the extract contained an alkaloid (*gelsemine*) separable by ether or chloroform, and an organic acid (*gelsemic acid*). The latter he was able to obtain crystallized in various forms by solution and sublimation. He found that if a small quantity of this acid or its salts, in a solid state, was treated with a drop of concentrated nitric acid, it became yellow or reddish, according to the quantity. When an excess of ammonia was added, it acquired a blood-red colour. The hundredth part of a grain was sufficient for this reaction. The solution in potash is fluorescent, presenting a deep blue colouration on the surface. Gelsemic acid was thus detected in the contents of the stomach some months after death.

The alkaloid *gelsemine* is a potent poison. One-eighth of a grain by hypodermic injection killed a rabbit in one hour and a half. In fifteen minutes there were symptoms of great distress, and the animal was restless. In forty minutes there was great prostration, inability to move, respiration gasping, and the pupils were dilated, but there were no convulsions. From his experiments, Wormley infers that the quantity which proved fatal to the woman in the above-mentioned case could not have exceeded the sixth part of a grain.

Oil of Turpentine. Camphene.

The few cases in which oil of turpentine has produced noxious symptoms have occurred among children. From these it appears to have rather the effects of a neurotic (narcotic) than an irritant poison. In a dose of three drachms it has produced intoxication. A dose of a table-spoonful caused in a child, aged eighteen months, symptoms bearing a strong resemblance to those occasioned by an overdose of opium, although they were not so rapidly manifested. (See case 'Med. Times,' Oct. 11, 1851, p. 380.) In three hours there was complete insensibility, with stertorous breathing, strongly contracted pupils, rapid and weak pulse, coldness of the surface, paleness of the countenance, general relaxation of the muscles, and occasional convulsive movements. Two fatal cases are recorded. The first was the case of a child, aged fourteen weeks. The child had had half an ounce of the oil poured down its throat by a brother, æt. 8. It had been left asleep at 9 P.M., and in an hour it was found to be insensible, cold, and slightly convulsed. At midnight it was seen by Miall. It was comatose, pale, with extremely cold surface—pupils contracted; slow and irregular breathing about three times in a minute; pulse quick, small, compressible, almost imperceptible. A strong odour of turpentine issued from the mouth, and there was a spot of liquid on the pillow. The child was unable to swallow. It died in fifteen hours after taking the poison. In the second case the child was five months old. A spoonful of spirit of turpentine was given to it by mistake for peppermint,

death took place rapidly. ('Pharm. Jour.' July, 1872, p. 75.) Oil of pentine is occasionally given to children suffering from worms.

CAMPHENE is oil of turpentine purified by distillation with lime. A man, æt. 22, swallowed a large quantity of this liquid. She was soon ed with violent vomiting, which was increased by milk and other ids. The matter vomited smelt strongly of turpentine. She was less, and in great pain; there was some purging. There was not re loss of consciousness. In two hours she complained of feeling cold, the e was small and weak; the head then became hot, there was headache, the pupils were unchanged; there was redness of the conjunctivæ. A ntity of urine was passed smelling of violets, and the breath also had a lar odour. There were some slight nervous symptoms, but these ed off. She recovered in eight days. (Horn's 'Vierteljahrsshr.' 1866, 37.)

A case of recovery in an infant that had swallowed four ounces of the is described in another work ('ON POISONS'). A case in which this id was criminally administered to an infant, was the subject of a trial C. C. Dec. 1856, *Reg.* v. *Rodanbosh*): it did not destroy life, but the d suffered for some time from the effects. The defence was, that the of turpentine was poured down the child's throat by the mother with iew to cure it of a cough. She was acquitted.

OIL OF TAR. CREASOTE.

Oil of tar is a powerful vegetable irritant. In 1832, about ten drachms t caused the death of a gentleman, to whom it had been sent by mistake a black draught. The druggist who sent it was tried for manslaughter, acquitted. Its properties are owing to creasote. Creasote has properties ilar to those of carbolic acid.

CARBOLIC ACID.

Carbolic Acid, *Phenic Acid*, or *Phenol*, is a crystalline product of the tillation of coal-tar. When pure it melts at 102° F. It has a characistic, and not unpleasant odour. When a small proportion of water is led to the crystals they liquefy. It is moderately soluble in water. e commercial crystals have an unpleasant odour, which is due to imrities; and they acquire a red colour on exposure to light. More nmonly carbolic acid is met with as either a colourless or more or less wn liquid, of nauseous odour, containing about 80 per cent. of phenol, as a dark brown liquid chiefly consisting of heavy oil of tar with ut 30 per cent. of the acid. These are largely used as disinfectants. plied to the skin or to a mucous membrane, it coagulates the albunous constituents, causes a severe burning pain and a white eschar. A ath is stated to have occurred from the external use of the acid Brit. Med. Jour.' Oct. 8, 1870); and its use as an antiseptic lotion has eatedly produced serious, if not fatal, results. Deaths from the internal of carbolic acid—usually accidental, but not infrequently suicidal—now common. In 1880, sixteen deaths were registered in England Wales from this cause. Carbolic acid, so called, does not redden litmus per.

Symptoms and Appearances.—When the poison is swallowed in solution, in the form of an undiluted liquid, the patient experiences a hot burning sation, extending from the mouth to the stomach. This feeling is perienced during the act of swallowing; and the lining membrane of the uth is whitened and hardened. Carbolic acid is rapidly absorbed, and in course of a few minutes the system may be profoundly affected. In o instances the rapidity of action was comparable to that of prussic acid.

Although the local application of the acid to a part is commonly followed by severe burning pain, this may be entirely absent in cases of poisoning by this agent, and even a local diminution of sensibility may be produced. Nervous symptoms are those most strikingly manifested, such as delirium, giddiness, and profound insensibility. Nausea and vomiting were present in not more than one-fifth of the observed cases. These symptoms may, however, be severe and uncontrollable. There is extreme feebleness of the pulse, and dry harsh skin, with lividity of the surface. The urine, as was first pointed out by the editor ('Guy's Hosp. Rep.' 1868, p. 407), is often of an olive green, or even black hue; but this appearance is more common in subacute, than in acute and rapidly fatal cases. The pupils are generally minutely contracted. Convulsions and trismus are not infrequently observed.

A case of carbolic acid poisoning can rarely fail to be recognized. The whitening of the mouth, the brown eschars which form on the skin at its angles where the poison trickles from the mouth, the odour of the breath, and the profound insensibility and stertorous breathing, with minutely contracted pupils, rarely leave any doubt as to the nature of the case. The editor has, nevertheless, met with a case in which a rather pure form of the acid having been taken for suicidal purposes, the odour of carbolic acid escaped notice.

Period of death.—Death has several times occurred within twenty minutes of the administration of the poison; and it usually supervenes within four hours. Occasionally, in fatal cases, life may be prolonged for twenty-four and even forty-eight hours.

Fatal Dose.—This is unknown. There is reason to believe that if absorbed, a few grains of the poison might prove fatal, and six or seven drops have produced serious results. Two fluid drachms of the liquid acid has killed a child, two years of age, in twelve hours. ('Guy's Hosp. Rep.' 1867, p. 233.) In one case a child, six months old, was killed by the administration of a quarter of a teaspoonful of the acid dissolved in glycerine—one part of acid to five glycerine ('Brit. Med. Jour.' May 20, 1882). Recovery has, however, taken place after large doses have been taken. A girl, æt. 14, swallowed six fluid drachms of the undiluted (? 30 per cent.) acid. In twenty minutes she was comatose and breathing stertorously; her face was livid, the pulse was small and irregular; the pupils contracted, but not so much so as in opium-poisoning. The stomach was washed out with soap and water, and then with milk and water. In an hour, the lividity diminished, and consciousness slowly returned. She did not complain of any gastric irritation. ('Brit. Med. Jour.' 1882, I. p. 999.) A robust woman, æt. 30, swallowed nearly half an ounce of an alcoholic solution of carbolic acid, containing 35·8 per cent. of the poison. It was ascertained that by the use of the stomach-pump rather more than half of the poison was removed from the stomach, but that at least 92 grains of the poison must have remained for absorption. The most prominent symptoms were insensibility within ten minutes, and dizziness speedily passing into profound coma, irregular breathing and pulse, contracted pupils, extreme blueness (cyanosis) of the surface of the body, depression of the body temperature to 94° F., and hæmoglobinuria, *i.e.* the presence of unaltered blood-pigment in the urine, which contained no red blood-corpuscles. This last condition set in one hour after the poison was taken, and lasted for seven hours and a half. The urine reacted carbolic acid during two days. The woman recovered. ('Berlin Klin. Wochenschr.' 1881, No. 48.)

Analysis.—Carbolic acid gives a purple colour when a drop of solution of ferric chloride is added. When in solution, it yields a copious precipitate of tribromophenol when an excess of bromine-water is added. This

cipitate when washed on a filter, and treated with sodium amalgam, ain yields phenol (carbolic acid).

To detect phenol in the viscera, vomit, urine, &c., acidulate the suspected terial with sulphuric acid, and distil, using suitable condensing arrangent. The distillate may have the odour of phenol. It is precipitated h an excess of bromine-water; the precipitate is washed with water on ilter, and whilst still moist treated with sodium amalgam in water. ter a time, on acidifying the solution, the peculiar odour of carbolic acid l be perceived. By shaking the mixture with ether, pipetting off the er, and evaporating it in watch-glasses, oily streaks of phenol will be ; these may be tested with ferric chloride, as described above.

Resorcin.

Resorcin is an antiseptic, recently introduced into medicine. It is a nol, *i.e.* a body closely allied to carbolic acid, crystallizing in colourless stals, which are readily soluble in water, ether, or alcohol. Applied in form of crystals, it acts as a powerful caustic to the skin. The comrcial resorcin, which is obtained as a bye-product in the manufacture of igment known as eosine, has a red colour, and a powerful odour resembling t of carbolic acid. It is used internally as a medicine. On one occasion which an overdose of two drachms was given to a young woman, it oduced decided toxic symptoms—insensibility, profuse perspiration, nched lips, equal normal pupils, lowness of body temperature, imperptible pulse, and almost imperceptible breathing. The urine was olive een in colour. The patient recovered. ('Med. Times and Gaz.' 1881, . p. 487.) It thus appears that resorcin acts like carbolic acid on e human organism.

Pyrogallin, or Pyrogallic Acid.

Poisonous properties have been attributed to this well-known substance, hich is so much employed in photography. The author did not meet ith any case of poisoning by it in the human subject; but, according Personne, it operates powerfully on animals. Two healthy dogs were lected, and into the stomach of one a dose of two grains of pyrogallin solved in water was injected; and twice this quantity was administered the other dog. The animals died after fifty and sixty hours respectively. he symptoms are said to have resembled those of phosphorus poisoning, d after death the muscular tissue of the heart was found in each case have undergone fatty degeneration. The acid is supposed to act like osphorus in arresting oxidation changes by absorbing and removing ygen. The alkalinity of the blood would favour this chemical action. Med. Press,' Dec. 1869; 'Amer. Jour. of Med. Sci.' July, 1870, p. 275.)

Petroleum.

Under the term petroleum, or rock oil, are included various oils used r illuminating purposes, of peculiar odour, which spring from the round in various parts of the globe; and consist of mixtures of various ydrocarbons and inflammable products. The commercial material is not in its crude state, but is a product purified by distillation from the ngerously inflammable hydrocarbons. The chemical composition of fferent specimens of petroleum is very varied. Petroleum contains ydrocarbons of the so-called marsh-gas series.

The illuminants which were in use prior to the introduction of American troleum, possess analogous composition, as Solar Oil, Photogene, &c., roducts of the distillation of bituminous shale and brown coal (lignite), c. Cases of petroleum poisoning are rare, considering the frequent use

of this well-known substance. The majority of cases arise from drinking out of bottles supposed to contain spirituous liquors, although there have occurred a few cases of intentional poisoning by this body; for instance, a case at Brescia ('Jour. de Chim. Méd.' Nov. 1866, p. 597), and another in the province of Posen, particulars of which are wanting.

In general the poisonous properties of petroleum, such as the purified American variety, cannot be rated very high; but many varieties of crude petroleum, on account of their containing sulphur compounds, are much more poisonous, according to Eulenberg, as for instance crude petroleum from Canada. In adults a wine-glassful may not kill, and in one case, that of *Mayer* in Antwerp, five fluid ounces did not cause death. According to Köhler ('Physiol. Thér.' p. 437), half a wine-bottleful is not a fatal dose for an adult. Even in the case of children, among whom the editor has seen several cases, the fatal dose is a very large one; and in the event of death supervening, it is due rather to the secondary result of local action of the poison on the stomach and intestines than to the result of the absorption of hydrocarbons.

The action of petroleum corresponds essentially with that of various ethereal oils, particularly oil of turpentine; and is partly that of a local irritant and partly a remote action on the nervous system. The analogy of the action of petroleum with that of oil of turpentine shows itself also in the skin eruptions which petroleum frequently produces in workmen engaged in petroleum refineries, as well as in the appearance of asphyxia through the inhalation of large quantities of petroleum vapour, when after the first symptoms of anesthæsia, pneumonia may follow.

In cases of poisoning, generally after vomiting follow giddiness, sense of fulness of the head, pain and feeling of constriction; and in children collapse, somnolence, pallor of the face, coldness of the skin, cold sweats and weak pulse may supervene. Neither the behaviour of the pulse nor the pupils is constant. In collapse, the latter are dilated; and in an excited condition they appear contracted. For the diagnosis, the odour of petroleum in the breath is generally a safe guide. Eructations and vomiting also betray the presence of petroleum. Finally, the urine may acquire a peculiar odour which may persist for several days. In *Mayer's* case this odour resembled that odour of violets which the urine acquires after the ingestion of oil of turpentine and other essential oils.

Analysis.—The detection of petroleum, either in the vomited matters or in the contents of the stomach, is effected by distilling the suspected matters and determining the physical and chemical properties of the distillate. As commercial American petroleum only contains hydrocarbons with high boiling points a calcium chloride bath will be necessary. The notable feature is the peculiar unpleasant odour, and the inflammability of the distillate. Petroleum is insoluble in water and rectified spirit, but is soluble in absolute alcohol, glycerine, ether, and in ethereal and fatty oils.

ANIMAL IRRITANTS.

CHAPTER 25.

IRRITANTS—CANTHARIDES OR SPANISH FLIES—SYMPTOMS AND EFFECTS—
YSIS—POISONOUS ANIMAL FOOD—FISH—MUSSELS—CHEESE—SAUSAGES—
ISED FLESH OF ANIMALS—TRICHINOSIS.

Cantharides (Spanish Flies).

es and Effects.—Cantharides are not unfrequently administered,
the state of powder or tincture, for the criminal purpose of pro-
abortion, but they are not often a cause of death in this country.
1,620 fatal cases of poisoning in four years, there were only two
ere ascribed to cantharides. When taken in *powder*, in the dose
r two drachms, it gives rise to the following symptoms: a burn-
ation in the throat, great difficulty of swallowing, violent pain
abdomen, nausea, and vomiting of bloody mucus: there is also
irst and dryness of the throat, and in a few cases observed by
, salivation was a prominent symptom. As the case proceeds,
eavy pain is commonly experienced in the loins, and there is an
t desire to void urine, but only a small quantity of blood or bloody
passed at each effort. The abdominal pain becomes of a violent
kind. Purging may supervene; but this is a symptom which is
ays observed: the matters discharged from the bowels are mixed
od and mucus, and there is often tenesmus (straining). In these,
as in the vomited liquids, shining green or copper-coloured par-
ay be commonly seen on examination, whereby the nature of the
f it has been taken in powder, will be at once indicated. After
there is severe priapism, and the genital organs are swollen and
both in the male and female. In one instance, observed by
abortion was induced, probably owing to excitement of the uterus
severe affection of the bladder: for there is no proof that this
e acts directly on the uterus to induce abortion. With respect
phrodisiac propensities said to be caused by cantharides, these can
e excited in either sex, except when the substance is administered
e which would seriously endanger life. When the case proves
ath is usually preceded by faintness, giddiness, and convulsions.
ture of cantharides produces similar symptoms:—they are, how-
re speedily induced, and the burning sensation and constriction
hroat and stomach are more strongly marked: this symptom is
severe as to render it impossible for the person to swallow; and
of swallowing gives rise to excruciating pain in the throat and
. Cantharides have been in some cases wantonly used, and with
nger to life, with a view of exciting sexual feelings. The doses
it has been given have been such as to cause symptoms of irritant
g. In Nov. 1859, six female servants in a gentleman's family, as
the master and mistress, were attacked with the symptoms of
g by cantharides. It appeared that the coachman of the family
rtly before the occurrence, purchased an ounce of this poison;
ad put the cantharides into beer and coffee, and had thus poisoned
le household. He was tried, but acquitted of any indictable

offence, on the ground that his intent was not to murder. It case which led to an alteration in the law.

Appearances.—In one well-marked instance of poisoning by stance, the whole of the alimentary canal, from the mouth do was inflamed. The mouth and tongue seemed to be deprived mucous membrane. The ureters, kidneys, and internal organs c tion were also inflamed. In another instance, in which an oun tincture was swallowed, and death did not occur for fourt the mucous membrane of the stomach was not inflamed; b pulpy, and easily detached. The kidneys were, however, inflan brain has been found congested, and ulceration of the bladder have been met with. There are few fatal cases reported, in v appearances have been accurately noted; indeed, the greater n those who have taken this poison have recovered. In a ca occurred to Saunders, death took place in about twenty-fo The deceased must have taken the greater part of half an cantharides in powder. The symptoms were such as have b described. On inspection the vessels of the brain were filled w coloured blood, and the ventricles were distended with serum. I were highly engorged with dark-coloured blood. The gullet wa inflamed, and there were patches of inflammation on the muco the stomach, which had become detached in several places. inflammatory appearance existed in the small intestines, in th which the powder of cantharides was abundantly present. Tl were distended, and the liver was engorged with dark blood. bladder was much distended with bile, and none of this secretion to have passed into the bowels. The spleen and kidneys were hi gested; the ureters were inflamed; the bladder was contracted a and its internal surface pale. The glittering of the particles of ca in the viscera during the inspection by candlelight, was very re ('Med. Times,' Feb. 3, 1849, p. 287.) Cantharides have no local action. The poison is a pure *irritant*, and the effects observe stomach are entirely due to irritation and inflammation.

The *quantity* of this poison required to produce serious sym to destroy life, has been a frequent subject of medico-legal inqu medicinal dose of the powder is from one to three grains. Th the tincture is from ten minims gradually increased to one fluid-d of the powder from *one* to *two grains*. Doses above this, wheth powder or the tincture, are likely to be injurious, and to giv symptoms of poisoning. On a trial which took place at Abe 1825, it appeared that a drachm of the powder had been admi severe symptoms followed, but the person recovered. A witnes had given ten grains of the powder as a medicinal dose. In th a drachm of the powder, mixed with six ounces of rum, was take person, robust, healthy negroes. They suffered severely, but rec about ten days. In these cases, irritation of the urinary organs appear until after the men had been bled.

Fatal Dose.—The *smallest quantity* of the powder which l known to destroy life, was in the case of a young woman, quoted b —the quantity taken was estimated at *twenty-four grains* in tw She died in four days; but as abortion preceded death, this may h concerned in accelerating that event. Her intellect was clear t last. In one instance a man recovered after having taken *two* ('Med. Gaz.' vol. 42, p. 873). An *ounce* of the tincture has been *to* destroy life. This dose was taken by a boy, æt. 17, and he *fourteen* days. This is, perhaps, the smallest dose of the tinctur

oved fatal. Four drachms and even six drachms have been taken; though the usual symptoms followed, the parties recovered. The se was the subject of a trial at the Cent. Crim. Court, in Sept. 1836. achms of the tincture were administered to a girl, æt. 17: the ns here arose whether half an ounce was sufficient to kill a person, what proportion of cantharides was contained in an ounce of the e. One ounce of the tincture is considered to be equivalent to five half grains of the powder; but as the proportion of *cantharidin*, the ce on which the poisonous properties depend, is subject to varia- t is not unlikely that the tincture varies in strength. A case is l by Pereira ('Mat. Med.' vol. 2, pt. 2, p. 750), in which it is said nces of the tincture were taken by a man without causing dangerous oms. This must have been an unusually weak preparation; and pro- the insects from which the tincture was made, contained little or no aridin. The same writer mentions a case within his own knowledge ich one ounce of the tincture caused serious symptoms. The powder ot be so readily administered as the tincture, since a large portion of ats for a time on any liquid with which it is mixed, and attracts tion by its peculiar appearance. At the Liverpool Lent Assizes, 1861 v. *Wilkins*) a man was indicted for administering powdered cantha- to a woman. The prisoner had mixed it with a cup of tea: the atrix took a portion of the tea, and suffered from vomiting and other toms produced by this substance: she skimmed a quantity of the r from the tea, on which it floated, and its nature was then deter- l. The prisoner was convicted of the act of administration, but a on arose in reference to the intent. The jury found that he had istered the powder with the intent to excite the sexual passion of oman, for which the new statute had not provided, as this makes the e to depend only on the intent to injure, aggrieve, or annoy.


alysis.—For the detection of *cantharidin*, which forms on an average -250th part of the flies, digest the suspected solid or the liquid con- of the stomach (evaporated to an extract) in successive quantities ier, concentrate these ethereal solutions by slow evaporation, and observe whether the concentrated liquid applied to the skin of the r the lobe of the ear, produces blistering. The 1–100th of a grain of aridin dissolved in ether is said to possess blistering properties. For etection of the powder, the suspected liquids, mixed with alcohol, d be spread on sheets of glass, and allowed to evaporate spontaneously ness. The shining scales will then be seen, on examining by reflected either one or both surfaces of the glass. ('Ann. d'Hyg.' Oct. 1842.) e powder is insoluble in water, some portion of it may be obtained shing and decantation. The sediment may be examined on a glass with the microscope.

antharidin is a neutral crystallizable principle. Figs. 39, 40 (p. 352) illustrations of its crystalline form, obtained by the spontaneous ration of its solutions in ether and chloroform.

hloroform may be used for the separation of cantharidin from the are or from an alcoholic or aqueous extract of the contents of the ach. An ounce of chloroform may be frequently shaken with the sus- d matters and left in contact with them twenty-four hours. The oform is then separated by a funnel, filtered, and allowed to evaporate aneously in a watch-glass. A pellet of lint of the size of half a pea, d out, is moistened with a drop of olive-oil, and the residue in the h-glass was taken up by it. This is placed upon the arm, lobe of the r lip, and covered with goldbeaters' skin. When taken off in three ar hours, the skin is very red, and, on wiping it with chloroform, a

vesicle may have been produced. ('Chem. News,' Feb. 14, 1863, p. 7
The quantity of cantharidin detected in this way has amounted to
the 1-80th part of a grain. This mode of operating is preferable to

Fig. 39.



Crystals of Cantharidin from a solution in chloroform, magnified 30 diameters.

Fig. 40.



Crystals of Cantharidin from a solution in ether, magnified 30 diameters.

use of ether, as cantharidin is less soluble in ether than in chlorof
Half an ounce of the tincture of cantharides will yield to chlorofo
crystallizable principle, having the characters assigned to canthar
In practice it will be found advisable to concentrate the liquid as mu
possible before adding the chloroform.

The evidence of the presence of cantharides, or of their having
taken, is necessary to support a criminal charge; for however unambig
the symptoms produced by this poison may appear to be in its pec
effects on the generative and urinary apparatus, the medical jurist sh
be aware that similar symptoms may proceed from disease. An impo
case of this kind has been reported. ('Med. Gaz.' vol. 12, p. 431.)
young lady was suddenly seized with vomiting, thirst, pain in the l
strangury, and considerable discharge of blood from the urethra:
generative organs were swollen and painful. She died in four days.
was governess in a family, and there was some suspicion that she had
poisoned with cantharides. The stomach and the kidneys were f
inflamed, and the bladder also; this contained about two ounces of b
No poison was detected; and indeed it was pretty certain, from the ge
evidence, that none could have been taken.

Noxious Animal Food.

Certain kinds of animal food are found to produce, occasio
symptoms resembling those of irritant poisoning. In some instances
poisonous effect appears to be due to idiosyncrasy; for only one pe
out of several may be affected. These cases are of importance to
medical jurist, since they may give rise to unfounded charges of cri
poisoning. In the absence of any demonstrable poison, we must test
question of idiosyncrasy by observing whether more than one perso
affected, and whether the same kind of food, given to animals, prod
symptoms of poisoning. If, with this latter condition, several person
affected simultaneously, we cannot refer the effects to idiosyncrasy;
are most probably due to the presence of an animal poison. Among
articles of food which have caused symptoms of irritant poisoning, ma
mentioned—

Poisonous Fish. Mussels.—Of all the varieties of shell-fish, none l
so frequently given rise to accidents as the common mussel. The sympt
which it produces are uneasiness and sense of weight in the stom
sensation of numbness in the extremities; heat, dryness, and constric

n the mouth and throat; thirst, shivering, difficulty of breathing, cramps n the legs, swelling and inflammation of the eyelids, a profuse secretion f tears, and heat and itching of the skin, followed by an eruption esembling nettle-rash. These *symptoms* are sometimes accompanied by olic, vomiting, and purging. They may occur within ten minutes or a uarter of an hour; but their appearance has been delayed for twenty- our hours. There is generally great exhaustion and debility. These ymptoms have proceeded from the eating of not more than ten or twelve ussels. Two cases, reported by Christison, proved fatal, the one in hree, the other in about seven hours. In general, however, especially hen there is free vomiting, the patients recover. In the inspection of he two fatal cases above mentioned, no appearance was found to account or death. A case in which two mussels produced, in a boy aged ten, larming symptoms, followed by an eruption resembling scarlatina and ettle-rash, is reported ('Guy's Hosp. Rep.' 1850, p. 213). In 1860, number of persons living at Tralee were poisoned under the following ircumstances. A woman picked up some mussels which she found at the ottom of the basin of a ship-canal. She distributed them among her eighbours, and during the night twenty-one persons who had eaten them, ere attacked with symptoms of poisoning. Three children died, and six ersons were placed in imminent peril. The rest were soon out of danger. ight out of the twenty-one attacked were adults. ('Med. Times and Gaz.' uly 28, 1860.) In October, 1862, an accident occurred at Liverpool in hich a woman died in about four hours, after having eaten some mussels aken from a ship in the docks. Severe pain and vomiting were among he symptoms, which generally resembled those of arsenical poisoning. everal other persons were made seriously ill, but recovered. Although he vessel was not sheathed with copper or yellow metal, it was coated ith a green pigment, of which arsenic may have been a constituent.

A man ate about twenty mussels. He soon began to have nausea and riping pains. In half an hour he vomited and was purged several times. le then felt faint and dizzy. When seen two hours and a half after eating he fish he was collapsed, and the pulse was almost imperceptible, though ot much increased in frequency. The pupils were natural. There was loud heezing and rattling respiration, interrupted by frequent yawnings and ighings. Notwithstanding free stimulation with brandy the patient was ontinually fainting; and he had frequent attacks of clonic spasms of all he muscles of the body. He was calm and conscious, had no pain, but omplained of great thirst. There was itching of the skin, and an erythe- matous rash on the chest. Under the administration of opium and ether his condition speedily passed off ('Brit. Med. Jour.' 1882, I. p. 939).

The poisonous action of mussels can be referred neither to putrefaction or disease; nor in all cases to idiosyncrasy, since in one instance those ussels only which had been taken from a particular spot were poisonous; ll persons who partook of them suffered, and a dog to which some of hem were given, was killed. From a case which occurred to Bouchardat, t would appear that copper is sometimes present, and may be the cause f the poisonous effects. Two women were poisoned by mussels, and he ound on analysis sufficient copper in the fish to account for the symptoms f irritation from which they suffered. ('Ann. d'Hyg.' 1837, 1, 358.) opper is not, however, present in all cases, and it is therefore probable hat there is in some, if not in all instances, an *animal poison* present in he fish. ('Ann. d'Hyg.' 1851, 1, 387; 2, 108.) *Oysters* and *periwinkles* ave occasionally given rise to similar symptoms. *Salmon*, sold in the tate of pickled salmon, or even *herrings* salted, may also act as irritants: his may be due to the fish being partially decayed before it is used, or to

the noxious effects of the pickle. For remarks on the poisonous proper of fish, see 'Pharm. Jour.' Jan. 1853, p. 344.

Cheese.—The symptoms produced by cheese have been those of irri poisoning. The nature of the poison is unknown. In some cases irritant property is due to a putrefied state of the curd, to the produc of a rancid irritant oil, or to the formation of alkaloids. Again, it been supposed that the poison is occasionally derived from certain v tables on which the cows feed. In 1858, twenty-five persons suffered f vomiting and purging, more or less violent, owing to their having part of cheese. The only articles of food in common were bread, beer, cheese. The bread and beer were excluded from any suspicion of con ing poison. All the persons recovered. The cheese was strongly a it had an offensive, musty smell, and yielded a quantity of acrid o ether. It had not been properly pressed, and the casein had under chemical changes. The ash yielded traces of copper and lead. The ch had acquired irritant properties, not from the presence of any poiso matter added to it, but from partial decay. There was abundant evid that cheese from the same dairy had been eaten without causing injurious symptoms. This negative evidence, however, is quite consi with one cheese acquiring noxious properties. We must not lose sigh the fact that cheese may actually contain poison mixed with it thr ignorance. Orpiment and chrome yellow may be used as colouring, the discovery of such mineral substances would at once account for irr effects. ('Pharm. Jour.' Aug. 1862, p. 89.) The milk and cheese of s of the North American provinces is said to be occasionally rend poisonous by the fact that cows pasture at certain seasons on vegetabl a noxious kind. In 1865, twelve cases of poisoning from this cause reported. The symptoms came on in about three hours after the ch had been eaten. There was severe pain in the stomach, cramp, vi vomiting of a greenish fluid, soreness of the throat, and a cold cla condition of the skin. All recovered—recovery being preceded by pr perspiration. ('Ed. Med. Jour.' 1865, 1, 854.)

Sausage Poison.—The symptoms caused by *sausage-poison* partake narcotico-irritant character: they are very slow in appearing—somet two, three, or four days may elapse before they manifest themselves. poison is of a formidable kind: its effects have been chiefly observe Germany. In the 'Medical Gazette' for Nov. 1842, there is an accou the cases of three persons, who had died from the effects of liver-saus which had been made from an apparently healthy pig, slaughtered o week before. The inspection threw no light on the cause of death. poisonous property was supposed to depend on a *partial* decompositio the fatty part of the sausages. It is said, that when extremely putre they are not poisonous. In one case, a few slices of a German sausag old manufacture but not putrescent, caused the death of a child, violent symptoms of irritation of the stomach and bowels. The au examined a portion of the sausage: it contained no poisonous matter w could be detected. The fatty portions were rancid, and the lean por very dry. There was no doubt, however, that it had been the cause of symptoms and death of the child. Tripe published a complete acc of the effects produced by sausage-poison ('Brit. and For. Med. R Jan. 1860, p. 197). It appears that in Nov. 1859, sausages made and by a pork-butcher at Kingsland, were eaten more or less by sixty persons, of whom sixty-four were attacked with violent symptoms irritation, in from three and a half to thirty-six hours after meal. One case only proved fatal, on the seventh day. No sympto appeared in this man until after the lapse of *six hours*. It seems that

ad eaten one of the sausages raw, and three cooked. He was attacked ith severe vomiting and purging, followed by shivering: there was pain the abdomen, violent headache, and great prostration. The pulse was eble and quick, and there was delirium. These symptoms underwent a mission, but he had a relapse, became comatose, and died on the seventh y. Latterly, he chiefly complained of pain in the bowels. Letheby und, on inspection, no signs of inflammation or of the action of an ritant in the stomach. The small intestines were much inflamed at the wer end, and the gall-bladder was distended. The other organs were althy. The viscera contained no known vegetable or mineral poison. he sausages were made with heifer-beef, pork-fat, sage, and pepper. here was no evidence of anything noxious about them, and a chemical alysis yielded nothing of a poisonous nature. There could, however, no doubt that the sausages had caused the symptoms and death; the od in this case acting as a narcotico-irritant poison. Other persons ffered from burning in the throat and stomach, followed by vomiting d purging; then giddiness or confusion in the head, and in some there as delirium. In the man who died, the delirium was well marked, and e eyes were red. In those persons who recovered, the noxious animal atter was probably early thrown off by vomiting and purging. (See Trichinosis,' p. 355.)

Pork. Bacon.—These common articles of food occasionally give rise to mptoms so closely resembling those of irritant poisoning, as to be easily istaken for them. In some cases, the effect appears to be due to idiosyn-asy; but in others it can be explained only by supposing the food to have directly poisonous action. The noxious effects of pork have been rticularly shown by the cases published by Mac-Divitt. ('Ed. Med. d Surg. Jour.' Oct. 1836.) As pork is sometimes salted in leaden ssels, lead may be found in it: but fresh pork has been observed to have noxious action. In 1864, Kesteven met with a case in which all the embers of a family were attacked with symptoms of irritant poisoning, ter eating a leg of pork. The principal symptoms were nausea, vomiting, riping pains in the abdomen, and purging: but dogs and cats fed upon e meat did not appear to suffer. Other portions of the animal from hich the leg was taken were eaten by other families, and no symptoms of isoning were produced. The author examined the food without discover-g any trace of the ordinary poisons. These cases of poisoning by animal od have been examined by Simon and Gamgee. They have traced the jurious effects of pork to a diseased condition of the pig, owing to e animal having been fed on improper food. The term measly pork is now very well known to consist in a diseased condition of the flesh of e animal, in which it is filled with a parasite called cysticercus, which is believed to be the larva of the tapeworm. ('Med. Times and Gaz.' 870, 1, 485.) This parasite undergoes full development when in the ape of food it reaches the human intestines. These parasites may not rectly kill a person who eats this noxious food, but they favour the velopment of fatal disease. In reference to the possible ill effects from nsuming, in a well-cooked state, the flesh of animals afflicted with *anthrax* or carbuncular fever, evidence is still imperfect. An opinion has en expressed that boils and perhaps other like affections are caused in man beings by the consumption of diseased meat.

A large amount of diseased and unwholesome meat is sold to the public, d of the various kinds of flesh used as food none is so subject to disease pork. Some of the changes which it undergoes are of a microscopical aracter, and are not noticed. For an account of the diseases affecting e flesh of the pig, their mode of production, and the prevention of acci-

dents, see papers by Delpech, in the 'Ann. d'Hyg.' 1864, vol. 1, pp. 5, 241 ('De la Ladrerie du porc,' &c.). The parasites found in the flesh of this and other animals are apt to escape destruction by boiling, roasting, or smoking, and those are liable to suffer the most who habitually eat the raw or partly-cooked flesh. The flesh of the pig containing cysticerci, presents in the cooked state the following appearances. When boiled it is paler than sound meat: it appears dryer in patches, and the muscular fibres are more separated than usual. When these are opened, the parasites are seen in the interstices as opaque white spots of the size of a hemp-seed, and presenting much the same aspect as when living. The caudal bladder attached to their bodies disappears when the meat is thoroughly cooked, and the body of the animal then appears isolated in the middle of the muscular tissue. It is friable and breaks down easily under pressure with a crackling sound, owing to the presence of calcareous matter. In this state it does not appear to be necessarily productive of injury ('Ann. d'Hyg.' 1864, 1, 249). All the members of a family were seized with vomiting, purging, and syncope after having eaten a dish of pork. A medical man examined the meat, and found it full of cysticerci. A pork-butcher was accused of having sold bad meat, but it was proved to have been some cheap pork bought of a hawker of provisions ('Ann. d'Hyg.' 1864, 1, 246). If the cysticerci did not cause the symptoms in this case, the meat had undergone some change sufficient to impart to it irritant properties. These parasites occur in all the fleshy parts of the body. They are not commonly found in the fatty portions of man and animals, and are less common in sheep and oxen than in pigs. In two instances, Ballard and Klein were able to trace conclusively that the poisonous effects of hams which had caused illness and death, were due to the presence of living organisms, *bacilli*, and not to any unorganized chemical body.


Trichinosis.—The fatal malady arising from the introduction of the *Trichina Spiralis* into the human body, has recently attracted much attention. Keller has published some important facts illustrating the symptoms produced, and the mode in which this parasite causes death. He considers that it is a question well worthy of the attention of medical jurists, whether many cases of death from suspected irritant poisoning, in which no poisonous matter could be detected in the body, may not have been really due to trichina disease.

The trichina (from θρίξ, a hair) spiralis, a flesh-worm, is found chiefly in the course of the fibres of all the striped muscles of the trunk and limbs, most frequently on those of the front of the chest, neck, and abdomen. It has also been found in the muscular fibres of the heart and gullet. The parasites appear in the form of very small white oval bodies or capsules, perceptible to the eye as white specks, in the midst of the muscular fibres, but only distinctly seen by the aid of a magnifying glass. The trichina or worm is coiled up in the centre of each oval capsule, the greater diameter of which is parallel to the muscular fibre with which it is closely incorporated. The annexed engraving (fig. 44) is taken from a preparation in the Museum of Guy's Hospital; it represents a portion of the abdominal muscles of a man covered with trichinæ in situ, and as nearly as possible of the natural size. The other illustrations in figs. 41, 42, and 43 are from drawings, representing three of the capsules *b b b* magnified, with the trichina coiled up in the centre of one of them.

These parasites are frequently so numerous as to give to the red flesh a white speckled appearance. According to Keller, as many as 300,000 have been estimated to exist in half a pound of raw meat: and Pietra Santa affirms that one grain of diseased meat may contain nearly 400 *trichinæ*, each having from sixty to eighty embryos. ('Ann. d'Hyg.'


I, 317.) The actual size of the capsule has been variously stated. ng diameter may be the 1-50th of an inch, and the short diameter h. The worm itself varies from 1-20th to 1-30th of an inch in . The capsules are remarkably uniform in size. They are slowly

Fig. 41. Fig. 42. Fig. 43.



Magnified view of Trichina spiralis in its capsule.
a. The worm coiled.
b. The capsules.

Fig. 44.



Trichina spiralis in the abdominal muscles of a man: natural size of the capsules containing the worm.

ıp at the expense of the muscular structure by which they are nded.

e history of this animal has been given by numerous pathologists. ription of its anatomy and habits by Bristowe and Rainey will be in the 'Trans. of the Patholog. Soc.' for 1853–4, p. 274. Accounts influence on health by Pietra Santa, have been published in the d'Hyg.' 1864, 1, 305 ('La Trichina Spiralis'), and by Schultze and in Casper's 'Vierteljahrsschr. für gerichtl. Med.' 1864, No. 1, and No. 2, p. 269. Lücke's paper is of especial interest, as its title richinen vor dem Forum' implies, since it points to the medico-earings of the subject, and the possible danger of confounding the s of this parasite with the obscure effects produced in certain forms mic irritant poisoning.

e trichina is a parasite, which passes the greater part of its ıce, in the chrysalis state, in the muscular system of animals, until, consumption of this muscle as food, it finds in the stomach and nes of another warm-blooded animal, a favourable medium for l development into an intestinal worm. According to Virchow and r, the trichina not only frequently presents itself in the human sm, but this organism is most favourable to its development. The of incubation of the chrysalis in the stomach and bowels of man or m-blooded animals, is from six to eight days; and during this time e thrives and propagates to an almost incredible extent. Keller that in three or four days the females produce one hundred or more ones, which begin on the sixth day to leave the parent animal; and mates that in a few days after the ingestion of half a pound of meat, mach and intestinal canal of a person may contain thirty millions of minute worms. Herbst found the muscles of two dogs which had ed upon parts of a badger containing worms, to be loaded with these es. When once introduced into the stomach and intestines, the leave their capsules, become free, and produce young which migrate h the walls of the intestines into the muscles: there they become ed, and are ultimately found appropriating and destroying the lar substance to a greater or less extent. After a long residence in ıscle they appear to acquire calcareous cysts. The sudden liberation rge number of these worms causes irritation and inflammation in the , attended by peculiar symptoms resembling in some respects those mic poisoning.

is worthy of *note that trichinæ* are more frequently found in pork,

and articles of food derived from it, than in any other kind of meat. Measly pork appears to be sometimes of a trichinous character. Further, the vitality of the parasites is not destroyed unless the meat, or other substances in which they are located, has been subjected to a temperature equal to that of boiling water for a sufficient time to ensure that every particle has been exposed to this degree of heat. Salting, smoking, or partial cooking, is not sufficient to destroy the worms in all parts of the food, and they have even been found living in putrefied meat. This may serve to account in some cases for the serious symptoms which have followed the use of pork as food, also of bacon, sausages, and German sausages, which are generally made of raw ham.

The symptoms produced by the use of such food are, in the first stage, those of intestinal irritation, loss of appetite, sickness, pain, general weakness of the limbs, diarrhœa, swelling of the eyelids and of the joints, profuse clammy perspiration, and wasting fever. Death is either the result of paralysis (from destruction of the muscular fibres), or of peritonitis and irritative fever. During the perforation of the coat of the intestines by these worms, the mucous membrane becomes irritated and inflamed: pus is formed on its surface, and bloody evacuations are sometimes passed.

The noxious effects of this food on human beings are well illustrated by a series of cases which occurred at Hettstädt in the Hartz Mountains, in 1863. ('Brit. Med. Jour.' 1864, 1, p. 75.) One hundred and three persons partook of smoked sausages made from a pig affected with trichinous disease. The sausages were fried, and served for dinner in the usual way. On the following day, several persons who had partaken of this food were attacked with severe pain in the bowels, purging, loss of appetite, great prostration of strength, and fever. The number of persons attacked rapidly increased: symptoms of peritonitis and pneumonia appeared, and these were followed by paralysis of the intercostal muscles, and of the muscles in front of the neck. Eighty-three persons died from the effects of this noxious food, and the remainder were seriously injured in health. The remnants of sausage and of pork not eaten at this festival were examined, and were found to be swarming with encysted trichinæ. (Casper's 'Vierteljahrsschr.' 1864, p. 286.) The writer in the above journal affirms that this parasitic disease does not attack sheep, oxen, or horses, and that beef is the safest of all descriptions of food, as no parasites have ever been discovered in it. They have not been found in the blood of animals whose muscles are liable to their attacks.


Reyber relates that, in the year 1862, a series of cases of illness to the number of thirty occurred in Plauen, as the result of the use of pork containing trichinæ. Among the symptoms were great languor, loss of appetite, fever, and pains in the muscles of the arms and legs. The cases spread like an epidemic. A female patient under Virchow died in Dresden, with typhoid and rheumatic symptoms. When the body was inspected, trichinæ were found in her muscles. On inquiry, it was ascertained that, four weeks before, a diseased pig had been killed and eaten in the town in which she resided; the butcher who killed it suffered, but this woman alone died from the effects. ('Ann. d'Hyg.' Oct. 1863, p. 471.) Pietra Santa relates that, at a nuptial festival at Wiesbaden, twenty persons partook of the food placed on the table. In the evening the bride was suddenly seized with symptoms of poisoning, and, in spite of medical assistance, died in a few hours. The bridegroom himself suffered from similar symptoms, and died after two days' illness. The other guests were *not* seriously affected. A physician-expert, who examined the case, found *trichinæ* in the body of the deceased, as well as in certain articles of food

ed from pork, which had been served at the table ('Ann. d'Hyg.' p. 321). The fact that only two out of the party suffered from ɔms resembling poisoning, and that one died rapidly, was calculated te grave suspicion. The real cause of death in these two persons ɔt appear to have been clearly traced to the trichinous food. Sudden from trichinous food are not common.

chinous disease appears to have been prevalent in Germany. It is in addition to the cases above given, that in 1862 thirty-eight s in Kalbe suffered severely from the use of such food, and of ight died from the effects. In 1878 a fatal outbreak of trichinosis ɔd to have occurred on board the training ship *Cornwall*, lying in the s.

ıultze refers to other groups of cases, which, however, do not appear ɔ been attended with great fatality. In Magdeburg, Neustadt, and ı, over a period of five years 1858–62), from three to four hundred f illness were traceable to this cause. ('Die Trichinen Krankheit,' 's 'Vierteljahrsschr.' 1864, p. 278.) In Burg more than fifty s suffered, and eleven died. Other fatal cases have been reported. 4, a whole family was poisoned at New York, and one member om eating part of a ham, which, on microscopic examination, was to be full of trichinæ. Death was referred by the medical attendant cause. There were two outbreaks of this disease in Massachusetts 0. Out of six persons who ate of the noxious food, one died. et,' 1871, I. 515 and 710.) In May, 1865, Senator Dittmere of : and his family, consisting of seven persons, were seized with symp- ɜsembling irritant poisoning some time after eating a ham which had moked but not cooked. On examination it was found to be loaded ichinæ. Four out of those attacked died. ('Lancet,' 1865, I. p. 562.) is probable that some unexplained cases of illness or death from ɔn of the stomach and bowels, simulating chronic irritant poisoning, ıve been the result of eating trichinous food. Medical men have

Fig. 45.



china spiralis from human muscle, magnified 150 diameters.

s taken from a case which proved t weeks. The worm was found to of an inch in length.

Fig. 46.



Trichina spiralis encysted in pork.

This engraving represents the completely encysted worm in horizontal sections, showing six stumps, which proves that the worm lies in three convolutions when it has attained its full size.

ınable to group the symptoms under any known form of disease, ;he marks of irritation in the mucous membrane of the bowels have ıtrength to the supposition that poison must have been taken by the ɔd, although chemical analysis had failed to show the presence of

any ordinary poison in the fluids and solids of the body. In the course of many years' practice, the author has met with several cases of this description, and there has been sometimes manifested a disposition to doubt the accuracy of chemical analysis. Lücke has related a series of fatal cases which occurred in 1845, attributed at the time to poison, which, as he suggests, were most probably caused by the use of trichinous food. (Casper's 'Vierteljahrsschr.' 1864, p. 102.) As means of distinction from irritant poisoning may be pointed out the long time which commonly elapses between the taking of the food and the commencement of the symptoms. The pain, vomiting, and purging are comparatively slight: the pain is in the bowels rather than in the stomach, and peritonitis, pneumonia, and fever are not commonly results of the action of irritant poisons, while they appear to be constant symptoms in trichinosis. The absence of ordinary poison in the food, in the urine, and in the evacuations, at any stage, may also be taken as conclusive evidence against irritant poisoning in its usual form.

In suspected cases, if any of the food can be obtained, this must be examined for the parasite by the aid of the microscope. If the case proves fatal, the voluntary muscles of the deceased must undergo a similar examination. In the 'Canada Medical Journal' for 1870–1, Edwards published a full account of the best methods of detecting trichinæ in the flesh of man and animals. The annexed engravings are from his photographs of the worms *in situ* in human and animal muscle.

In some cases which occurred at Montreal the cause of the symptoms was at first obscure, but Edwards not only found trichinæ in a slice of ham which had been eaten, but in the muscles of two of the patients who recovered. He removed about five grains of muscular tissue from the gastrocnemius muscle, and twelve grains from the tibialis posticus. In both of these portions of muscle, about forty worms were found. (Op. cit. p. 517. See also Thudichum's 'Report to Privy Council for 1864–5.') The subjoined engraving (fig. 47) represents a section of human muscle, from one of the fatal cases at Hamilton. Two generations of worms are visible in this muscle, those in the spiral form being a young generation, while the upper curl on the right is the only portion in focus of a large worm, which lies closely curled up and is slightly encysted.

Fig. 47.



Trichina spiralis in human muscle, magnified 150 diameters.

Putrescent Food.—The effects of disease on animal food must not be confounded with those which result from decay or putrefaction. The flesh of the most healthy animal is rendered unfit for food when it has passed into a putrescent state. It is not merely unwholesome but highly irritant, causing rapidly vomiting, purging, pain, and other symptoms of a severe kind. Fortunately these symptoms lead at once to the expulsion of the noxious food from the body, and the person then recovers: the young, the old, and the infirm may, however, be so prostrated by vomiting and purging, that they may sink from exhaustion. Animal matter in a state of partial *decay*, or in the transition stage of putrefaction, must be regarded as of a *poisonous* nature. Much of the cheap butcher's meat sold to the poor is

in a state of decay. In one year 114,000 pounds of diseased, and 76,000 pounds of putrid meat were seized and condemned in the City of London alone. In 1851, the family of a surgeon near London were all affected with symptoms resembling irritant poisoning, after having partaken of a hare which had been stewed in a clean earthen vessel. The wife was seized with vomiting, purging, giddiness, heat in the throat, and general numbness, with inflamed eyes. Other members of the family vomited, and in the course of a few days the symptoms disappeared. The vomited matter consisted of portions of the hare partially digested, but in a state of putrefaction, so that there was abundant evidence of sulphuretted hydrogen in the liquid. There was no mineral poison of any kind, although the symptoms were rather like those occasioned by arsenic. It had been remarked by the family that a silver spoon, which was used for serving out this unwholesome food, was turned of a brown colour, no doubt from the chemical action of sulphuretted hydrogen; and this may be taken as a good domestic test of the putrefied condition of such food. Nature generally applies an appropriate remedy in the fact that the food itself produces copious vomiting and purging.

Cases of this kind must be distinguished from those in which *poisoned* game is sold to the public. The game may be quite free from putrefaction, but noxious from the poisoned grain which may have caused death. It is a common practice to steep grain in a solution of arsenic, previous to sowing, and pheasants, partridges, and other birds may be accidentally destroyed by eating the grain. In some instances, grouse and other game are maliciously destroyed by the laying of corn, saturated with arsenic or other poisons, in the localities where the birds abound. There is no law, except the Sale of Food and Drugs Act, 1875, to prevent the sale of poisoned game by poulterers, and there is no precaution which can be taken by the purchasers except by observing whether the birds have or have not been shot. (See on this subject, 'On Poisons;' 'Med. Gaz.' vol. 42, p. 1036.)

Mr. Taylor directed attention (Sept. 1862) to the serious symptoms produced by *Canadian partridges* eaten as food. A lady who had partaken of this food was, in about two hours and a half, attacked with the following symptoms. She had sickness, and became insensible; the skin was cold, and no pulse could be felt. She was in a hopeless state for some hours, and only slowly recovered. The birds were quite fresh, having been packed in ice. In another case there were similar symptoms, with constriction of the throat and great pain. Animals were made ill by this food. It was believed that, in these cases, the birds had not been killed by poison, but that their flesh had been rendered poisonous by some vegetable which they had eaten. It is stated that in some parts of Australia the mutton is rendered poisonous by reason of the sheep feeding on poisonous plants. ('Med. Times and Gaz.' 1871, 1, 728.) Pheasants which feed upon the kalmia shrub are poisonous when eaten as food.

NEUROTIC POISONS.

(NARCOTIC OR CEREBRAL POISONS.)

CHAPTER 26.

OPIUM—SYMPTOMS—APPEARANCES—ITS ACTION ON INFANTS—POISONING
—BY OPIATE COMPOUNDS—MORPHIA AND ITS SALTS—PROCESS FOR
OPIUM AND ITS PRINCIPAL CONSTITUENTS IN ORGANIC MIXTURES—LAC

Opium.

Symptoms.—The symptoms which manifest themselves when a l
of opium, its tincture, or any of its preparations, has been tak
general of a uniform character. A condition of pleasurable ment
ment, usually of very short duration, is experienced; but this is
by weariness, headache, incapacity for exertion, a sense of weig
limbs, diminution of sensibility, giddiness, drowsiness, a strong
to sleep, and stupor succeeded by perfect insensibility, the per
motionless, with the eyes closed as if in a sound sleep. In this
may be easily roused by a loud noise, and made to answer a ques
he speedily relapses into stupor. In a later stage, when coma has st
with stertorous breathing, it will be difficult, if not impossible,
him. The pulse is at first small, quick, and irregular, the respiratio
the skin warm and bathed in perspiration, sometimes livid; but
person becomes comatose, the breathing is slow and stertorous, and
slow and full. The skin is occasionally cold and pallid. Th
in the early stage are contracted; in the last stage, and w
gressing to a fatal termination, they may be found dilated.
referred to the author in 1846, one pupil was contracted and
dilated. They are commonly insensible to light. The expressi
countenance is placid, pale, and ghastly: the eyes are heavy, an
are livid. Sometimes there is vomiting, or even purging;
vomiting takes place freely before stupor sets in, there is grea
recovery. This symptom is chiefly observed, when a large dose
has been taken; and it may then be, perhaps, ascribed to the m
effect of the poison on the stomach. The odour of opium is oc
perceptible in the breath. Nausea and vomiting, with heada
of appetite, and lassitude, often follow on recovery. In cases
prove fatal, the muscles of the limbs feel flabby and relaxed, the l
drops, the pulse is feeble and imperceptible, the sphincters are in
relaxation, the pupils are unaffected by light, the temperature of
is low, there is a loud mucous rattle in breathing, and convul
sometimes observed before death, but more commonly in childre
adults. One of the marked effects of this poison is to suspend
secretions except that of the skin. Even during the lethargic s
skin, although cold, is often copiously bathed in perspiration.
tracted state of the pupils has been hitherto considered to furnish a
distinctive sign of poisoning by opium or the salts of morphia. In
upon it, it is necessary to bear in mind the fact pointed out by Wil
in apoplexy which is seated in the Pons Varolii, the pupils are also co
He describes two cases of this form of apoplexy which were mist
poisoning by opium in consequence of this state of the pupils.

nd Gaz.' 1863, 1, 214.) In carbolic acid poisoning the pupils are ntracted, though seldom so minutely as in opium poisoning; and coma and stertorous breathing. As a rule the peculiar odour lic acid in the breath will prevent any mistake as to the nature se.

e symptoms usually *commence* in from *half an hour* to *an hour* e poison has been swallowed. Sometimes they come on in a few , especially in children, and at other times their appearance is ed for a long period. In a case reported by Skae, the person id totally insensible in *fifteen minutes*. As we might expect, from connected with the absorption of poisons, when the drug is taken *olid* state, the symptoms are commonly more slow in appearing en it is *dissolved* in water or alcohol. In a case which occurred at l, in 1863, a lady took, on an empty stomach, a large dose (sup- have been one ounce and a half) of laudanum. No symptoms tic poisoning appeared for four hours and a half, and life was d for twenty-two hours.

as been frequently observed that a person has recovered from symptoms, and has then had a relapse, and died. There is edico-legal interest connected with this state, which has been condary asphyxia from opium, although there appears to be no son for giving to it this name. In 1843, a gentleman swallowed ity of laudanum, and was found labouring under the usual s. The greater part of the poison was removed from the by the pump, and he so far recovered from his insensibility as to to enter into conversation with his medical attendants; but a ook place, and he died the following night. The case of the *Hon.* *son* (Jan. 1859) furnishes another illustration of this singular . This lady swallowed, while fasting, an ounce and a half of n by mistake. In a quarter of an hour emetics were given, but not vomit for half an hour; and she was not treated medically ours and a half. The matter then drawn from the stomach had of laudanum. She was quite unconscious, and had lost the power owing. After remaining in this comatose state for upwards of rs, the patient revived, the face became natural, the pulse steady, r of swallowing returned, she was able to recognize her daughters, thick voice, to give an account of the mistake she had made. This ted about five minutes; the torpor then returned, she again sank ound coma, and died in fourteen hours after the poison had been It is not improbable that, in these cases, death may be occasioned ccumulation of the poison, carried by the absorbents into the *i.e.* the morphia may be more rapidly carried into the system is eliminated from it. A remarkable case illustrative of this form of poisoning by opium has been published. ('Dublin Med. ec. 24, 1845, p. 406.) In compound poisoning, where laudanum the ingredients, it may be expected that symptoms of narcotic will first show themselves. In one case a woman, æt. 22, swallowed of Battle's Vermin Killer, and immediately afterwards two drachms um, and then half a drachm of red precipitate. In three hours found to be suffering from narcotic poisoning alone. None of the strychnine had been produced, and there was no irritation from rial poison. Emetics were given, and the stomach-pump used. quantity of Battle's powder and red precipitate were removed stomach. Albumen was given, and the woman slowly recovered. ,' 1871, II. p. 907.) It was inferred that the opium had here d the action *of strychnine*. *It* would have been more satisfactory

if the powder drawn from the stomach had been examined, and strychnine found in it, as opium is not an antidote for strychnine. There were no symptoms of poisoning by strychnine at any time, although three hours had elapsed before remedies could be applied. Among the occasional symptoms of opium poisoning are vomiting, coming on soon after the poison has been taken; and itching of the skin, with the appearance of a rash. Rarely an unusual period elapses between the taking of the poison and the manifestation of narcotic symptoms. Christison mentions a case in which the stage of excitement lasted eighteen hours before somnolence set in. ('On Poisons.') In another case, which proved fatal, the interval was fourteen hours. ('Brit. Med. Jour.' March 20, 1868.)

Persons may by habit take enormous doses of opium (opium-eating) with comparative impunity.

Appearances.—In a case which proved fatal in fifteen hours, the vessels of the head were found unusually congested throughout. On the surface of the fore part of the left hemisphere of the brain there was an ecchymosis, apparently produced by the effusion of a few drops of blood, and there were numerous bloody points on its cut surface:—there was no serum collected in the ventricles. The stomach was healthy. Fluidity and a dark colour of the blood are mentioned as common appearances in cases of poisoning by opium. There is also engorgement of the lungs: most frequently observed, according to Christison, in those cases which have been preceded by convulsions. (Op. cit. p. 732.) Among the external appearances there is often great lividity of the skin. Extravasation of blood on the brain is rarely seen;—serous effusions in the ventricles, or between the membranes, are sometimes met with. The stomach is so seldom found otherwise than in a healthy state, that the inflammatory redness said to have been occasionally seen may have been due to accidental causes. When tincture of opium has been taken and retained on the stomach, increased redness of the mucous membrane may be produced by the alcohol alone. In a case of poisoning by a large dose of tincture of opium, the following appearances were found twelve hours after death: the body was warm and rigid, and the stomach healthy, containing a quantity of gruel-like fluid, without any smell of opium. The intestinal canal and all the other viscera were healthy. The veins of the scalp, as well as of the dura mater and sinuses, were gorged with blood; but there was no effusion in any part of the brain. The contents of the stomach yielded no trace of morphia or meconic acid, but there was no doubt that death had been caused by opium, taken on the previous night. ('Med. Gaz.' vol. xl. p. 235.) A case was the subject of a trial at the Aberdeen Autumn Circuit, Sept. 1853, in which a child, aged six months, died in a few hours from a dose of sixty drops of wine of opium. The brain was congested to a marked extent. Although the dose was comparatively large, and death rapid, there was no decided indication of the presence of opium in the stomach. From this account of the appearances in the dead body, it will be seen that there is nothing but a fulness of the vessels of the brain, which can be looked upon as specially indicative of poisoning by opium, and even this is not always present. A congested condition of the brain, however, if it exists, can furnish no evidence of poisoning when taken alone, since it is so frequently found as a result of morbid causes in otherwise healthy subjects.

Quantity required to destroy life.—The medicinal *dose* of opium, in extract or *powder* for a healthy adult, varies from half a grain to two grains. Five grains would be a fatal dose to most persons. The medicinal *dose* of the *powder* is from ten to forty minims. One fluid ounce of the *tincture* of opium of the British Pharmacopœia (laudanum) contains the

uble matter of thirty-three grains of opium. This is in about the pro-rtion of fourteen and a half minims of the tincture to one grain of dry um. The *smallest dose of solid opium* which has been known to prove al to an adult, was in the case of a man, æt. 32, who died very speedily a convulsive fit, after having taken two pills, each containing about one in and a quarter of extract of opium. This quantity is equivalent to r *grains* of crude opium. ('Med. Gaz.' vol. 37, p. 236.) The *smallest orded fatal dose of the tincture* in an adult, is *two drachms*. ('Ed. Med. l Surg. Jour.' July, 1840.) The patient was a robust man, æt. 56; he llowed the tincture at ten in the evening, and died under the usual nptoms on the following morning, the case having lasted only twelve rs. The quantity actually swallowed, however, appears to be involved some doubt; for it is subsequently stated that *half an ounce* of laudanum y have been taken. In another case a lady died from a dose of two achms of laudanum mixed, it was supposed, with chloroform. Large es of the tincture have frequently been taken without proving fatal. e author has elsewhere recorded a case in which five ounces of laudanum re taken even without producing sleep, and the patient recovered. Guy's Hosp. Rep.' 1850, p. 220.)

Action of Opium on Infants.—In conection with this subject, it is portant for a medical jurist to bear in mind that *infants* and young sons are liable to be killed by small doses of opium; they appear to be uliarly susceptible of the effects of this poison. A child, four months l, was nearly killed by the administration of one grain of Dover's powder, taining only one-tenth part of a grain of opium;—the child suffered m stupor and other alarming symptoms. In 1822, four grains of ver's powder (containing two-fifths of a grain of opium) were given a child four years and a half old. It soon became comatose, and died seven hours. Death was referred to inflammation of the throat, but re was no doubt, from the evidence, that death was caused by the opiate dicine. Thorn met with the case of an infant only three days old, which ten grains of Dover's powder (containing one grain of opium) re given by mistake. It suffered from the usual symptoms, but survived the long period of forty-four hours. Kelso met with an instance in ich a child, nine months old, was killed in nine hours by four drops minims) of laudanum, equal to about *one-fourth part of a grain* of ium; it was much convulsed before death. A case is referred to in the dical Gazette,' in which two drops (? minims) of laudanum, equal to t the *seventh part of a grain* of opium, killed an infant. A nurse gave an infant, five days old, *two drops* (? minims) of laudanum, at about three lock in the morning. Five hours afterwards the child was found by medical attendant in a state of narcotism. It was revived by a cold th, but a relapse came on, and it died the same evening, about eighteen rs after the poison had been given to it. On inspection, the brain and dominal viscera were found in a healthy state, and there was no smell opium in the stomach. ('Prov. Med. Jour.' Oct. 28, 1846, p. 519.) e fatal dose here, as in the former case, was equal to one-seventh part a grain of opium. An infant, *seven days* old, died in eighteen hours m the effects of one *minim* of the tincture, or *one-fifteenth part of a in* of opium. ('Lancet,' Ap. 15, 1854.) Coma with the usual symptoms s complete in half an hour. On inspection, the heart was found dis-ded with black liquid blood: the lungs were collapsed but not con-ted. The brain was congested, but there was no effusion either into ventricles or on the surface. (See also 'Med. Times and Gaz.' April , 1854, p. 386). The smallest fatal dose recorded (in an infant) was a case communicated by Edwards of Liverpool (Nov. 1857). An

infant, four weeks old, died from the symptoms of poisoning by opium, in seven hours after a dose of paregoric elixir, equivalent to *one-ninetieth* of a grain of opium, had been administered to it. With a knowledge of these facts, it is not surprising that infants are occasionally destroyed by opium under circumstances in which an adult would not suffer. In Dec. 1860, an inquiry took place at Chester respecting the death of a child aged six weeks, under the following circumstances. A fomentation composed of laudanum and gin was applied to the side of the mother, and the child was put to the breast shortly afterwards. The child fell into a sleep from which it did not awaken, and died, in spite of treatment, the next morning. The cause of death was left obscure: but it is not improbable that the child drew a quantity of laudanum into its mouth, sufficient to destroy life. ('Med. Times and Gaz.' 1861, I. p. 70.) In some instances infants have been found to manifest an astonishing power of recovery. An infant of six months recovered after having had administered to it ten grains of Dover's powder, equal to one grain of opium ('Lancet,' June 8, 1850); and in Jan. 1852, an infant of nine months recovered under treatment from a dose of two teaspoonfuls of laudanum, given by mistake. This quantity left by evaporation four grains of an impure extract of opium. In 1860, an infant of between two and three months old recovered after *five grains* of opium had been given to it by mistake for rhubarb. Hays met with a case in which a child, not quite six years old, swallowed a powder containing *seven and a half grains* of opium mixed with powdered chalk. The child was not seen until fourteen hours afterwards. It was at first excited: there had been no vomiting. The narcotism was at no time very profound: it gradually subsided, and at the end of three days the child had recovered. ('Am. Jour. Med. Sci.' April, 1859, p. 367.) In the year 1880 the following number of deaths were registered in England from opium and its preparations:—opium 27, laudanum, 80, opiate 2, Godfrey's cordial 2, soothing cordial 1, chlorodyne (a preparation containing morphia) 9, and Stockport remedy (a preparation containing chlorodyne) 1; total 122.

Period at which death takes place.—It has been remarked that most cases of poisoning by opium prove fatal in from about six to twelve hours. They who recover from the stupor, and survive longer than this period, generally do well; but from cases above related it would seem that there may be a partial recovery, or a remission of the symptoms, and afterwards a relapse. The symptoms, however, generally progress steadily to a fatal termination; or the stupor suddenly disappears, vomiting ensues, and the person recovers. Several instances are recorded of this poison having destroyed life in from seven to nine hours. One occurred within the author's knowledge, in which an adult died in five hours after taking the drug. Christison met with a case which could not have lasted above five, and another is mentioned by him which lasted only three hours. Barwis met with the case of an adult which proved fatal in three hours and a half. Nearly two ounces of laudanum had been taken; but there was no smell of opium in the stomach when inspected thirty hours after death. One case proved fatal in two hours and a half. (Beck, 'Med. Jour.' p. 873.) Procter communicated to the author the case of a female, æt. 50, who swallowed an ounce of the pharmacopœial tincture, and died from the effects in less than *two hours*. Opium was found in the stomach. The only appearance in the body was a congested state of the membranes of the brain. The most rapid case of death yet reported was that of a soldier who was accidentally poisoned in the Hospital of Val-de-Grâce. It appears that he swallowed by mistake about an ounce of laudanum, and it is stated that he died in convulsions in *three-quarters of an hour*. ('Jour. de Méd.'

846, p. 475. For a similar case, see 'Med Gaz.' vol. 45, p. 743.) It
ible that the drug may destroy life even with greater rapidity than
but, as a medico-legal fact, we are at present entitled to state that it
stroyed life within the short period above mentioned. On the other
the cases are sometimes much protracted. There are several in-
s of death in fifteen or seventeen hours; and among those collected
ristison, the longest lasted twenty-four hours.

Poisoning by Poppies.

e heads of the white poppy grown in this country possess narcotic
ties. They yield an inspissated extract called English opium, which,
ing to Hennell, contains 5 per cent. of morphia. The white
heads, therefore, yield to water, in the form of decoction, a poisonous
nce capable of acting deleteriously on children. A child died in
uence of its mother having administered to it two spoonfuls of water
ch a poppy-head had been boiled. ('Med. Times and Gaz.' 1863, II.

Many cases of poisoning have occurred from the injudicious use
rup of poppies, a sweetened decoction of the poppy-heads. This
when pure is said to contain *one grain* of extract (opium) to one
(Thomson). The common dose of it, for an infant three or four
s old, is half a drachm; for adults, two to four drachms. There
e reason to believe that what is often sold by many druggists under
me of syrup of poppies as a soothing or cordial medicine for children,
hing more than a mixture of tincture or infusion of opium with
syrup: it is therefore a preparation of variable strength. This
ccount for what appears to many persons inexplicable, namely, that
ant may be destroyed by a very small dose. In 1841, a child
onths old is said to have died from the effects of less than half
poonful of syrup of poppies bought at a druggist's. This is the
medicinal dose for a child. The symptoms of narcotic poisoning
ully developed in three-quarters of an hour. The syrup in this case
ly contained tincture of opium. Several children are reported to
ost their lives by this syrup in 1837–8. In one of these instances,
poonful and a half was given. Stupor came on in half an hour, and
ild died the following day. Pereira mentions a case in which a
onful proved fatal to a healthy child. The author met with two
which occurred in 1871, in one of which a child eighteen weeks old
a twenty-six hours from the effects of a teaspoonful, and the other
ch an infant five weeks old was killed by three parts of a teaspoonful
s syrup. It is in all cases a most uncertain preparation as to
th.

inslow's 'Soothing Syrup,' called also 'Quietness,' appears to be a
und resembling syrup of poppies. Its effects are those of a narcotic.
loses of this caused the death of a child aged fifteen months, with
sual symptoms of narcotic poisoning ('Pharm. Jour.' 1872, 618).
alysis of this syrup showed that one ounce of it contained nearly
rain of morphia with other opium alkaloids ('Pharm. Jour.' June,
p. 975). It is not surprising that it should prove fatal to infants
all doses.

Godfrey's Cordial.

is is chiefly a mixture of infusion of sassafras, treacle, and tincture
um. The quantity of tincture of opium contained in it is stated, on
thority of Paris, to be one drachm in six ounces of the mixture, or
grain of opium to one ounce: but it is probable that, like the so-called
of poppies, its strength is subject to variation. A case has been

reported, in which half a teaspoonful, = 1-32nd part of a grain of opium was alleged to have caused the death of an infant. In the four years 1863–7, fifty-six deaths, and in 1880, two deaths, were recorded in England and Wales from Godfrey's cordial. The explanation of this great mortality is, that the medicine is usually given in large doses by ignorant persons.

Dalby's Carminative.

This is a compound of several essential oils and aromatic tinctures in peppermint water, with carbonate of magnesia and tincture of opium. According to Paris there are *five minims* of the tincture, or one-third of a grain of opium, in rather more than two ounces of this mixture, or *the one-sixth of a grain in an ounce.* The formula commonly given is—carbonate of magnesia forty grains, oil of peppermint one minim, of nutmegs two minims, of aniseed three minims, tincture of opium five minims, spirit of pennyroyal and tincture of assafœtida of each fifteen minims, tincture of castor and compound tincture of cardamoms of each thirty minims, and of peppermint water two ounces. According to this formula, tincture of opium forms the 1-212th part by measure, or one teaspoonful contains about the 1-50th part of a grain of opium. Like most of these quack-preparations, it varies in strength. An infant is reported to have been destroyed by *forty drops* of this nostrum, a quantity, according to the strength assigned, equivalent to more than *half a minim* of the tincture, or about 1-75th of a grain of opium. Accidents frequently occur from its use, partly owing to ignorance, and partly to gross carelessness on the part of mothers and nurses.

The quack medicine, known under the name of *Locock's pulmonic wafers*, contains opium. A boy, æt. 4, suffered from all the usual symptoms of poisoning by opium as a result of eating a quantity of these wafers or lozenges. ('Lancet,' 1860, II. p. 420.)

Paregoric Elixir. (Compound Tincture of Opium.)

This is a medicinal preparation of proof spirit, opium, benzoic acid, oil of anise, and camphor. Opium is the active ingredient, and of this the tincture contains *one grain* in every *half-ounce.* In one case of poisoning by this tincture, a child, aged seven months, died from the effects of a teaspoonful (equal to one quarter of a grain of opium) given in two doses at an interval of a day. ('Pharm. Jour.' April, 1845.) In another, an infant of five weeks recovered from a similar dose, although no treatment was resorted to for nine hours. ('Med Times and Gaz.' Aug. 6, 1859, p. 145.) An infant has been killed by a dose equivalent to not more than the *ninetieth* part of a grain of opium.

The *ammoniated tincture of opium* is compounded of opium, saffron, benzoic acid, oil of anise, strong solution of ammonia, and rectified spirit. It contains one grain of opium in ninety-six minims, and the medicinal dose is from half a fluid drachm to one drachm.

Dover's Powder. (Compound Powder of Ipecacuan.)

This is a preparation of opium, the effects of which on infants and children have been already described (p. 365). The proportion of opium is one-tenth part, or *one grain* in every *ten grains* of the powder. A child has been killed by four grains; therefore by a quantity containing about two-fifths of a grain of opium. A child at fourteen months took by mistake six grains of Dover's powder—equivalent to six-tenths of a grain of opium—at six P.M. In a quarter of an hour he felt drowsy and fell asleep; at two A.M., eight hours after taking the poison, he had severe convulsions; his pupils were dilated, and his pulse was slow and irregular.

mained insensible, and died at three A.M., nine hours after taking the
:r. (Brown on 'Poisons in the Punjab,' 1863, p. 71.) On the other
an infant of nine months recovered from a dose of five grains.
l. Times and Gaz.' May 19, 1860.) Guy reported another case, in
an infant of six months recovered, under active treatment, from
: of ten grains. ('Lancet,' June 8, 1850). In a still more remark-
nstance of recovery, fifteen grains of Dover's powder were given
infant under five months of age. The mistake was discovered
liately, and by active treatment the child recovered. These cases
)very in infants must be regarded as exceptional.

Black Drop.

is is a preparation of opium, in which the morphia is combined
cetic acid, and very little meconic acid is present. In the Black
ccording to Pereira, verjuice, the juice of the wild crab, is employed
lvent instead of vinegar. Black drop is considered to have from
o four times the strength of the tincture of opium. According to
n, it is a compound of half a pound of opium to three pints of the
sed juice of the wild crab. It resembles the *Acetum Opii*, and has
han twice the strength of laudanum.

Sedative Solution (Battley's).

is is an aqueous solution of opium holding a little spirit and less
ic acid than the common tincture. ('Pereira.') It is considered
e three times the strength of the tincture of opium; but there is
at a difference of opinion on this point, that Neligan represents it
ng only of about the same strength. ('Medicines,' &c., p. 236.)
ates that it is composed of three ounces of extract of opium, six
ns of spirit, and as much distilled water as will make up two pints.
ears to be in some cases an energetic preparation. One drachm and
of it has proved fatal to a lunatic, and twenty minims of the solution
stroyed the life of an old woman. A medical gentleman, lying
ously ill from an attack of dysentery, took, by mistake, about seven
ns of Battley's solution. Within five minutes, salt and water with
d were administered, and twenty-four grains of sulphate of zinc.
ing ensued; the emetic was repeated, and with the same effect, the
vacuated at the second vomiting having the usual smell of opium.
a drachm of ipecacuanha was subsequently given to complete the
ing of the stomach. Notwithstanding repeated vomiting, symptoms
otism presented themselves speedily, with contraction of the pupils,
eat drowsiness—rendering it necessary to remove the patient from
his debilitated state, and keep him constantly moving until about
.M. (seventeen hours), when vomiting came on spontaneously, and
put to bed and allowed to sleep. The original disease afterwards
d its course (complicated by an attack of gastritis), and at length
ated favourably; but the patient had no recollection of what had
ed for twenty-four hours after the administration of the emetics;
appeared to his medical attendants that an excited state of mind
ied for some days afterwards. ('Prov. Jour.' Jan. 28, 1846,
The death of Dr. Baddeley, from a dose of this medicine, furnishes
litional proof of the dangerous uncertainty of its strength.

Chlorodyne.

lady, æt. 23, had been accustomed to take the liquid for the relief of
n doses of as much as sixty drops. She was found dead in bed, and

the cause of death was referred by her medical attendant to her having taken two doses without letting a sufficient interval elapse between them. ('Lancet,' 1871, II. p. 697.) According to E. Smith chlorodyne is thus constituted:—Chloroform four drachms, hydrochlorate of morphia twenty grains, ether two drachms, oil of peppermint eight minims, prussic acid six drachms, mixture of gum acacia one ounce, treacle four ounces. ('Lancet,' 1870, I. 72.) There is reason to believe that this compound is not uniform in composition. According to another formula the tinctures of lobelia and capsicum, and extract of liquorice, are introduced. One sample, on standing, separated into two liquids, one light and of a pale straw colour, and the other heavy and of a brown colour and syrupy consistency. On evaporation it left half of its weight of solid residue as saccharine matter. Another sample remained in a thick syrupy state. A fluid-drachm of the first sample left as a residue twenty-seven grains of a brown saccharine extract. Prussic acid may be detected in it by the reaction of the vapour on silver nitrate. Crystals of silver cyanide are obtained after some time. Morphia may be detected in it by shaking a portion with a mixture of carbon disulphide and iodic acid. The disulphide acquires a pink colour, owing to the separation of iodine by the morphia. Deaths from chlorodyne are frequent.

Nepenthe.

In a case tried at the Chester Assizes, the nature of the compound sold under the above name was a subject of inquiry. It is a pale sherry-coloured liquid, of a spirituous odour, with the smell of opium, and an acid reaction. It contains 3·4 per cent. of solid matter, consisting chiefly of a purified extract of opium with a small quantity of sugar. It also contains a trace of tannic acid, which causes a darkening of the liquid when a ferric salt is added to it for the detection of meconic acid. This disappears, and the red colour of ferric meconate is brought out when a small quantity of diluted sulphuric acid is added to it. Morphia is readily detected in it by shaking with iodic acid and carbon disulphide. The disulphide acquires a pink-red colour. It may be regarded as a purified alcoholic solution of meconate of morphia, with a little excess of acid, and of about the same strength as laudanum. It has a similar mode of action. A very small quantity has sufficed to destroy the life of an infant. An infant fourteen days old died under the following circumstances. Some dill-water was procured at a druggist's, and it was put into a bottle which had contained nepenthe. A teaspoonful was given to the infant. It soon fell asleep, and died in a short time under all the symptoms of narcotic poisoning. ('Pharm. Jour.' 1872, p. 779.)

Morphia and its Salts.

Morphia is the chief poisonous alkaloid of opium, of which it forms from five to ten, or even twenty per cent. The two principal salts of this alkaloid are the HYDROCHLORATE and the ACETATE.

Symptoms.—The symptoms generally *commence* in from *five* to *twenty minutes* after the dose of poison (in solution) has been swallowed; and they closely resemble those observed in poisoning by opium. As a summary, it may be stated that they consist in dimness of sight, weakness and relaxation of the muscular system, the face and hands congested and of a livid or blueish colour, a strong tendency to sleep, stupor, loss of consciousness, coma, stertorous respiration, and, more commonly than in poisoning by opium, there are convulsions. According to Orfila, in nineteen-twentieths of all cases the pupils will be found strongly contracted, a statement which is correct: the few exceptional cases were

those in which the dose was excessive, and the symptoms were unusually violent. The state of the pupils gave rise to a great difference of opinion among the medical witnesses on the trial of Castaing. ('On Poisons,' 2nd ed. p. 619.) The condition of the pulse varies greatly. It has been found small and feeble, sometimes full and slow. In some cases there is great irritability, as well as itching of the skin, and irritability of the bladder with difficulty of passing urine. Vomiting and purging have been met with in those instances in which the dose was large. In one case of morphia poisoning, an apothecary was able to walk for an hour and a half after taking 75 grains of hydrochlorate of morphia (Hay's 'Amer. Jour.' Oct. 1862).

It has been stated that morphia in large doses does not operate as a narcotic, but as a stimulant to the nervous centres, causing violent convulsions. In some instances the convulsions are said to have assumed a tetanic character, resembling those caused by strychnine. This is stated to have been noticed where the alkaloid or its salts had been used hypodermically. The author met with no cases to support the theory, but many adverse to it. It has been alleged that the tetanic symptoms of strychnine are not to be distinguished by those caused by large doses of morphia. One medical authority announced that all the symptoms assigned to poisoning by strychnine in Cook's case (*Reg.* v. *Palmer*) might be explained by supposing that he had taken three grains of morphia. We must wait for well ascertained facts before accepting this theory. In 1882, a woman died in Guy's Hospital from the accidental administration of ten grains of hydrochlorate of morphia, in mistake for quinine. Death supervened very rapidly without the manifestation of any tetanic symptoms.

When morphia is given by subcutaneous injection its narcotic effects are manifested more speedily than when the drug is taken internally; and it is probable that a smaller dose might prove fatal in the former than in the latter case. Death from the hypodermic injection of morphia salts is now a common occurrence.

Poisoning by morphia may take place as the result of external application. In 1867, a woman, suffering from cancer of the breast in a state of ulceration, applied to a druggist for some medicine to relieve pain. He applied at once *thirty grains* of morphia, covering with it the surface of the ulcer. The woman soon afterwards became insensible. When seen by a medical man she was quite unconscious—the pupils were contracted, the skin very cold, the pulse full and compressible. The woman was then in a hopeless state, and she died in ten hours after the application of the morphia to the breast. The druggist, when examined at the inquest, said that in his judgment the application was right and proper, and in spite of medical evidence that the symptoms and death were referable to absorption of morphia, the jury returned a verdict of death from natural causes.

Fatal Dose.—Five cases are known in which a dose of *one grain* of hydrochlorate of morphia has proved fatal to adults: in one it was taken in solution; in a second in a pill; in a third in a powder; and in a fourth it was administered by hypodermic injection into the tissue under the skin of the forearm. In the first of the cases ('Ed. Month. Jour.' Sept. 1845, p. 195), the morphia was taken in divided doses, in six hours. The symptoms and appearances were of the usual character, and insensibility came on rapidly. The patient died in about seven hours. The second case occurred at St. Mary's Hospital, May, 1861: a man, æt. 45, died in [illegible] hours from a dose of one grain of hydrochlorate of morphia, taken in a pill by one of the physicians. The symptoms came on in [illegible] hours, and were of a well-marked character. No morphia was found in the stomach or other organs, and its operation as a poison was

ascribed, without any apparent ground, to disease of the kidneys. In the third case, a healthy man, æt. 52, died in about ten hours from the effects of *one grain*. Three hours after taking the powder, he lost his senses of smelling and hearing, and passed rapidly into a comatose condition, from which he did not recover (case of *Cordery*, Burnham, March, 1863). The practitioner who prescribed the morphia alleged that he had given only half a grain, but the facts of the case were adverse to this statement. No morphia was detected in the stomach. The fourth case occurred at the Middlesex Hospital, in 1863. One-third of a grain of morphia was injected at night under the skin: in two hours the injection of a similar quantity was repeated. On the next morning another third of a grain was injected. The man slept quietly for two hours. He then took some dinner, and talked in his usual way; but in another hour he became almost suddenly insensible, and in two hours he died, the narcotic symptoms being most powerfully developed. The editor met with a case in which two doses, each of half a grain of hydrochlorate of morphia, are supposed to have killed a hale man in middle life. Morphia was detected in minute quantity in the body after death. Anstey met with a case in which three grains of morphia given as an injection per rectum caused death in sixteen hours.

The hydrochlorate is thus proved to be a powerful poison in a small dose; it may operate either quickly or slowly, and destroy life rapidly. An infant has died from a dose of one-twelfth part of a grain. ('Chem. News,' Aug. 22, 1863, p. 98.) Christison considers that one grain of the hydrochlorate is fully equal in power to six grains of the best Turkey opium. There is no reason to suppose that the acetate is less potent: but there are some remarkable instances of recovery where such a result could scarcely have been anticipated. In the 'Lancet,' for 1863, I. p. 8, is reported the case of a child about two years of age, who recovered from a dose of one grain of the acetate. The medicinal dose for an adult of either of these salts of morphia is from one-eighth of a grain to one-half grain. A case in which *one grain* of the acetate, dispensed by mistake in a pill, destroyed the life of a lady, is reported. ('Pharm. Jour.' July, 1872, p. 16.) Narcotic symptoms came on in about half-an-hour, and she died in nine hours.


Appearances.—The only post-mortem appearance which can be referred to the action of morphia is fulness of the cerebral vessels, with, occasionally, serous effusion and bloody points on a section of the brain substance. This poison has no local irritant action, and it therefore leaves no mark of its operation in the stomach and bowels. An account of the appearances produced by an overdose of sulphate of morphia has been published by Orfila in a report of the case of *Dr. Ellenberger* ('Ann d'Hyg.' 1852, 2, 359). The case presents some curious features. The deceased imagined that he had discovered a certain antidote for morphia and its salts, and proposed, while Orfila was at Prague in Oct. 1851, to swallow the poison and the antidote in his presence. Orfila consented to witness the experiment. A powder was produced, which was found to have a bitter taste, and to possess some of the chemical properties of morphia, evidently mixed, however, with some other substance. The doctor swallowed about twenty-three grains of this powder, and immediately afterwards his so-called antidote, which was a fine white powder having a sweetish taste. He did not suffer from any symptoms of poisoning. Orfila, with a keen eye to the practical use of antidotes, inquired whether he had ever allowed a certain interval to pass before taking the remedy. Ellenberger said that the results were the same. Six months after this experiment, Ellenberger died from a dose of about ten grains of sulphate of morphia.

taken his antidote, but not until a considerable interval had
A minute inspection of the body was made, and the principal
ıce was a well-marked congestion of the brain and its membranes.
ere traces of sulphate of morphia in the stomach. The so-called
was examined, and found to consist of a mixture of magnesia and
e of magnesia.

ıical Analysis. Opium.—There are no means of detecting opium
ither in its solid or liquid state, except by its smell and other
properties, or by giving a portion of the suspected substance to
and observing whether any narcotic effects are produced. The
said to be peculiar, but a similar smell is possessed by lactucarium
, which contains neither meconic acid nor morphia. The *odour*
d concomitant test of the presence of the drug, whether it be in a
e or dissolved in alcohol or water, but it is not perceptible when
tion is very much diluted, and it loses its characteristic smell by
e. The odour passes off when an opiate liquid is heated; it also
slowly at common temperatures. Again, it may be concealed by
lours, or the drug may undergo some change in the stomach during
ch may rapidly destroy the odour. (Case by Mr. Barwis, p. 366.)
ılysis in cases of poisoning by opium is therefore limited to the
n of morphia and the acid (meconic) with which it is combined.

ohia.—Morphia may be identified by the following properties:—
ystallizes in fine white prisms. These crystals may be obtained by
weak ammonia to a solution of morphia in hydrochloric acid. (See
) 2. When heated on platinum, the
melt, become dark-coloured, and burn
esin with a yellow smoky flame, leaving
ıaceous residue. If this experiment is
ed in a small reduction-tube, it will
ıd, by employing test-paper, that
a is one of the products of decom-
. 3. It is scarcely soluble in cold
ıs it requires 1000 parts to dissolve it;
uble in 100 parts of boiling water, and
solution has a faint alkaline reaction.
ısolubility in water, it is readily known
salts. It is not very soluble in ether,
ffering from narcotine; but it is dis-
by forty parts of cold water, and rather
n this quantity of boiling alcohol. It
lved by a solution of potash or soda, from which it cannot be com-
removed by ether. It is soluble in acetic ether, and this has been
ed as a substitute for ether in procuring morphia from organic
4. It is easily dissolved by a very small quantity of all diluted
nineral and vegetable. 5. Morphia and its solutions have a bitter
6. The salts of morphia are not precipitated in a crystalline form
ions of potassium sulphocyanide, potassium ferrocyanide, or potas-
ıromate. In this respect they are strikingly distinguished from
s of strychnine, which give well-marked crystalline precipitates
ese three reagents.

Fig. 48.



Crystals of Morphia obtained by adding ammonia to a solution of the hydrochlorate, magnified 124 diameters.

rder to apply the chemical tests for morphia, the alkaloid may be
ed in a few drops of dilute acid, either acetic or hydrochloric.
ıydrochlorate or the acetate of morphia is presented for analysis,
may be at once dissolved in a small quantity of boiling water.
ts for this alkaloid are the following:—1. *Nitric acid.* This, when
to a moderately strong solution of a salt of morphia, produces

slowly a deep orange-red colour. If added to the crystals of or its salts, red fumes are evolved:—the morphia is entirely and the solution acquires instantly the deep red colour above —becoming, however, lighter by standing. In order that t should follow, the solution of morphia must not be too muc and the acid must be strong and added in rather large quan colour is rendered much lighter by boiling; therefore the t never be added to a hot solution. 2. *Iodic acid* with *carbon disu* solution of iodic acid should be mixed with its own volume disulphide. There should be no change of colour. On addin quantity of these mixed liquids to morphia or its salts, either i solution, the iodine is separated from the iodic acid and dissol disulphide, which sinks to the bottom, acquiring a pink or r varying in its intensity according to the quantity of morphi The presence of morphia may be thus easily detected in one d tincture of opium, in chlorodyne or other opiate liquids, i the presence of organic matter. If carbon disulphide is not u may be detected by the blue colour produced on the addition of of starch. 3. *Sulphomolybdic acid.* Dissolve, with a gentle he six grains of powdered molybdic acid in two drachms of strong acid. The liquid should be freshly prepared, and kept from conta and organic matter. When one or two drops are rubbed with *d* or any of its salts an intense reddish-purple or crimson colour is This changes to a dingy green and ultimately to a splendid sapp A minute trace of morphia is thus revealed. This test produces in *strychnine*, but the mixture slowly acquires a pale blue presence of morphia in strychnine is thus easily detected. Wh on *brucine* this acquires a rose-red colour, becoming greenish-l ultimately dark blue. When mixed with *veratria*, the liqui greenish-brown, and gradually passes to a darker shade. Th becomes purple, and ultimately the whole mixture acquires a colour. On chloral hydrate, sulphomolybdic acid produces r 4. *Sulphuric acid* and *potassium bichromate.* When strong sulp is poured on pure morphia in a solid state, there is either no eff alkaloid acquires a light pinkish colour. On adding to this solution of potassium bichromate, or a small fragment of a immediately becomes green (from the production of chromic o retains this colour for some time. Other alkaloids (strychnin thus affected. Narcotine is turned of a bright yellow by sulph therefore, although it becomes green when mixed with pot chromate, it could not be mistaken for morphia: besides, the gre passes to a dingy brown colour. 5. *Iron test.* A minute qua solution of ferric chloride added to a solution of morphia prod colouration. If the iron salt be in excess the colour is green.

It may be desirable to determine whether morphia or any alkaloid is present in a suspected *solution.* For this purpos employ a solution of corrosive sublimate and potassium iod hydrargyrate of potash). If even a small quantity of morph alkaloid, is present, a whitish precipitate is thrown down on a test: this precipitate is an insoluble hydriodate of the alk mercuric iodide. This test is more sensitive with some alka others. A negative result proves the absence of morphia, pr solution does not contain a large excess of alcohol or acetic acid of which liquids the alkaloidal precipitate is soluble. It is not a ammonia, but it gives yellow mercuric oxide with potash or so *solution,* sometimes known as Mayer's solution, may be employ

analysis of most of the poisonous alkaloids, some of which may by means of it be readily distinguished from others. It is made by dissolving six grains of corrosive sublimate and twenty-two grains of iodide of potassium in one ounce of water. As it gives a precipitate with albumen, this, when present, should be first removed by boiling the liquid to be tested. Another delicate precipitant of solutions of the alkaloids is iodine in potassium iodide. It is made by dissolving twenty-four grains of potassium iodide and eight grains of iodine in one ounce of water. It gives a deep brown precipitate with an alkaloidal salt.

Meconic Acid.—This is a solid, colourless, crystalline acid. It is combined with morphia in opium, of which it forms on an average 8 to 10 per cent.; and it serves to render this alkaloid soluble in water and other menstrua. *Tests.*—There is only one test upon which any reliance can be placed, namely, *ferric chloride* or *ferric sulphate*. This test produces, even in a diluted solution of meconic acid, a deep blood-red colour; and it is owing to the presence of this acid that a salt of iron strikes a red colour in tincture and infusion of opium as well as in all liquids containing traces of meconate of morphia, the effects of the iron-test with morphia being counteracted by the presence of meconic acid. The red colour of ferric meconate is not easily destroyed by diluted mineral acids or by a solution of corrosive sublimate, but it is by sulphurous acid and stannous chloride. In liquids containing tannic acid, *e.g.* tea or beer, the action of this test is obscured by the production of ferric tannate. The dark colour is removed by a few drops of diluted sulphuric acid.

Detection of Opium in Organic Mixtures.—Opium itself may be regarded as an organic solid, containing the poisonous salt which we wish to extract. It is not always that, in fatal cases of poisoning with opium or its tincture, even when these are taken in large quantity and death is speedy, we can succeed in detecting meconate of morphia in the stomach. It is probably removed by vomiting or absorption. If the matter is solid, it should be cut into small slices; if liquid, evaporated to an extract; and, in either case, digested with a large quantity of rectified spirit, slightly acidulated with acetic acid. The residue should be well pressed in linen; the alcoholic liquid should then be evaporated at a low temperature until it is dry. The residue should be digested in absolute alcohol, filtered, and the filtrate evaporated to dryness as before. The residue is to be taken up with water, filtered, and treated with lead acetate until there is no further precipitation. This liquid should be warmed and filtered: lead meconate is left on the filter, while any morphia passes through. The surplus lead acetate contained in the filtered liquid (containing the morphia) should now be precipitated by a current of sulphuretted hydrogen—the lead sulphide separated by filtration, and the liquid evaporated at a very gentle heat, so that any sulphuretted hydrogen may be entirely expelled. On treating this extract with alcohol, the acetate of morphia, if present in sufficient quantity, will be dissolved. The alcoholic liquid is again evaporated and taken up by water. On evaporating a drop or two of the watery liquid with a drop of freshly prepared solution of starch, and touching the residue with a drop of a solution of iodic acid, morphia will reveal itself by the production of a blue colour. Other tests may also be applied to the solution.

The lead *meconate* left on the filter is readily decomposed by warming it with a small quantity of diluted sulphuric acid; and in the filtered liquid, neutralized if necessary by an alkali, the meconic acid is detected by the ferric test. A current of sulphuretted hydrogen may be used in place of sulphuric acid. The lead sulphide takes down with it much of the organic matter of *the precipitate*. Wormley has found that he could

thus procure evidence of the presence of meconic acid and morphia from a complex organic mixture, containing only one grain of opium. ('Microchemistry of Poisons,' p. 497.) This analysis requires care as well as some practice in the operator, in order that the morphia should be obtained in a sufficiently pure state for the application of the tests.

Before resorting to this process it is advisable to employ *trial tests* on the original liquid, in order to determine whether any meconic acid or morphia is present or not. The smell of opium may be entirely absent. Meconic acid may be readily detected by the action of a ferric salt on the organic liquid diluted, and morphia may be found by adding to a portion of the liquid a mixture of iodic acid and carbon disulphide. The disulphide acquires a pink colour by dissolving the iodine set free by morphia or its salts. These tests may be equally applied to a solution of opium obtained by dialysis.

Lactucarium (Lactuca).

Symptoms and Effects.—The two species of lettuce, the common garden lettuce (*Lactuca sativa*) and *L. virosa*, contain a substance which is possessed of feebly narcotic properties. Orfila found that the extract prepared by evaporation at a low temperature, acts upon the brain and nervous system of animals; although very large doses were required for the production of narcotic effects. There is no record of these plants having exerted a poisonous action in the human subject. The inspissated juice of the lettuce is known under the name of *lactucarium* or *lettuce-opium*. The juice, when it first escapes, is of a milk-white hue, but, in drying, it forms an extract in small irregular dry masses of a brown colour, a bitter taste, and with an odour similar to that of opium. It has a weak narcotic action when given in doses of from five to twenty grains. It varies much in strength. Wibmer found that *two grains* caused headache and somnolency. It is bitter to the taste. There are no tests for lactucarium, further than the colour, the opiate odour, the want of solubility, and the absence of the other chemical characters of opium.

CHAPTER 27.

PRUSSIC ACID—SYMPTOMS AND APPEARANCES—FATAL DOSE—TESTS FOR THE ACID—PROCESS FOR ORGANIC MIXTURES. POTASSIUM CYANIDE. SILVER CYANIDE. ESSENTIAL OIL OF BITTER ALMONDS.

Hydrocyanic or Prussic Acid.

Symptoms.—This acid has a hot bitter taste, and an odour resembling that of bitter almonds diluted. The time at which the symptoms of poisoning commence in the human subject, is liable to great variation from circumstances not well understood. It is stated that a diluted acid is more rapidly absorbed than a stronger acid. When a large dose has been taken, as from half an ounce to an ounce of the diluted acid, the symptoms usually commence in the act of swallowing, or within a few seconds. It is rare that their appearance is delayed beyond *one or two minutes*. When the patient has been seen at this stage, he has been perfectly insensible, the eyes fixed and glistening, the pupils dilated and unaffected by light, the limbs flaccid, the skin cold and covered with a clammy perspiration; there is convulsive breathing at long intervals, and the patient appears dead in the inter-

mediate period; the pulse is imperceptible, and involuntary evacuations are occasionally passed. The respiration is slow, deep, gasping, and sometimes heaving or sobbing. The following case presents a fair example of the immediate effects of this poison in a large and fatal dose:—A medical man swallowed seven drachms of the common prussic acid. He survived about four or five minutes, but was quite insensible when discovered, *i.e.* about two minutes after he had taken the poison. He was found lying on the floor senseless; there were no convulsions of the limbs or trunk, but a faint flickering motion was observed about the muscles of the lips. The breathing appeared to cease entirely for some seconds: it was then performed in convulsive fits, and the act of expiration was remarkably deep, and lasted for an unusual time. When the dose is large, the breath commonly exhales a strong odour of the acid, and this is also perceptible in the room. Convulsions of the limbs and trunk, with spasmodic closure of the jaws, are usually met with among the symptoms; the finger-nails have been found of a livid colour, and the hands firmly clenched. The breathing is generally convulsive, but when the coma or insensibility is profound, it is sometimes stertorous. This was noticed in a case which occurred to Christison. ('Edin. Month. Jour.' Feb. 1850, p. 97.) It was also observed in the case of *Marcooley* (*Reg.* v. *Broughs*, C. C. C. Feb. 1857). In the inquiry which took place at Rugeley, in 1856, respecting the death of *Walter Palmer*, it was contended that the fact of the deceased having had stertorous breathing was a proof that he had died from apoplexy, and not, as it was alleged, from prussic acid; but the facts here recorded show that such an inference is erroneous. More accurately, the breathing in prussic acid poisoning is of a special and peculiar character. The intervals between the respirations are prolonged, followed by tedious and spasmodic respirations, the inspirations being short, and the expirations very protracted.

A medical student took a drachm and a half of Scheele's prussic acid. He was heard to call out once or twice, and a gentleman sleeping in the next room ran to his assistance. He was heard to fall from the sofa to the floor, and when picked up was found to be already insensible. Hilton Fagge saw him a little later—fifteen to thirty minutes after the poison was taken. He was then lying on a sofa, quite insensible. The limbs were paralysed, and lay in any position in which they were placed; and they were free from all rigidity. The jaws were clenched. The pupils were normal. There were no convulsions, nor had there been any. The face was not livid. The pulse was very rapid, the respirations very infrequent. Cold water dashed on the face produced at each application deep respiratory efforts. An attempt to administer an emetic failed, in consequence of inability to swallow. Strong ammonia applied to the nostrils failed to produce the slightest stimulation. After a time the breathing became slower—seven in a minute; and it was distinctly stertorous. The pulse became slower, and markedly feebler; and now cold affusion failed to produce any effect. The respirations fell to four in a minute, the face became blue, and the pulse imperceptible at the wrist. Breathing ceased in from an hour to an hour and a half after the poison was swallowed. There was a marked odour of prussic acid in the room; but it was not noticed at first whether the breath smelt of the acid. ('Guy's Hosp. Rep.' 1869, p. 259.)

This is, the editor believes, the longest fatal case of prussic acid poisoning on record.

When a small dose (*i.e.* about thirty minims of a weak acid) has been taken, the individual has first experienced weight and pain in the head, with confusion of intellect, giddiness, nausea, a quick pulse, and loss of muscular power; these symptoms are, however, sometimes slow in appearing. Vomit-

ing has been occasionally observed, but it is more common to find foaming or frothing at the mouth, with suffusion or a bloated appearance of the face, and prominence of the eyes. If death results, this is preceded by tetanic spasms, opisthotonos, and involuntary evacuations. Vomiting is sometimes the precursor of recovery. (See cases in 'Med. Gaz.' vol. 36, p. 103; vol. 35, pp. 859, 893.) A case which occurred to Bishop ('Prov. Med. and Surg. Jour.' Aug. 13, 1845, p. 517) was remarkable in several particulars: the man swallowed, it was supposed, forty minims of an acid (of three and a quarter per cent.), or one and a quarter grains of real prussic acid, and was able to give an account of his symptoms. He was conscious for some time after he had taken it, and he recollected experiencing the sensation of his jaws becoming gradually stiff and tight. One of the most marked effects of prussic acid is to produce insensibility and loss of muscular power, much more speedily than any other poison. In some instances, there may be loss of consciousness in a *few seconds*; in others, certain acts indicative of volition and locomotion may be performed, although requiring for their performance several *minutes*.

Appearances.—The body when seen soon after death often exhales the odour of prussic acid; but if it has remained exposed before it is seen, and if it has been exposed to the open air or in a shower of rain, the odour may not be perceptible; again the odour may be concealed by tobacco-smoke, peppermint, or other powerful odours. In a case in which a person poisoned himself with two ounces of the acid, and his body was examined twenty-eight hours after death, the vapour of prussic acid, which escaped on opening the stomach was so powerful that the inspectors were seized with dizziness. In cases of suicide or accident, the vessel out of which the poison has been taken will commonly be found near; but there is nothing to preclude the possibility of a person throwing it from him, or even concealing it if the symptoms should be delayed. (See p. 379, 'Christison.') Owing to the great volatility of the poison, the vessel, if left uncorked, may not retain the odour when found. Putrefaction is said to be accelerated in these cases; but there seems to be no ground for this opinion (p. 99; also case in 'Prov. Med. Jour.' July 30, 1845).

Externally, the skin is commonly livid, or is tinged of a violet colour; the nails are blue, the fingers clenched, and the toes contracted; the jaws firmly closed; foam or froth about the mouth, the face often pallid, but sometimes bloated and swollen, and the eyes have been observed to be wide open, fixed, glassy, very prominent and glistening, and the pupils dilated; but a similar condition of the eyes has been observed in other kinds of violent death. *Internally*, the venous system is gorged with dark-coloured liquid blood; the stomach and intestines may be in their natural state; but in several instances they have been found more or less congested. The mucous membrane of the stomach is often reddened throughout, and may present the appearance met with in cases of arsenical poisoning. In a large number of experiments upon dogs, Nunneley found generally a congested condition of the mucous membrane of the stomach: if empty at the time the poison was taken, the organ was found much contracted, and of a brick-red colour. This appearance of congestion was observed on the mucous membrane of the vagina, the rectum, and conjunctiva, when the acid was applied to these parts. ('Prov. Trans.' N.S. vol. 3, p. 79). Redness of the stomach was noticed in the case of the Parisian epileptics. ('Ann. d'Hyg.' 1829, 1, 507.) In the following case this redness of the mucous membrane was well marked. A healthy man, æt. 30, swallowed a dose of prussic acid. He was soon afterwards found dead in his bed; rigidity was expected in five hours: rigidity had then The face was pale, the eyes were

closed, not presenting any remarkable brilliancy or prominence, and was great dilatation of the pupils. The mouth was closed, and no froth l from it. The abdomen was the only cavity examined. The muscles red, and gave out on section a good deal of fluid blood, which had a g odour of prussic acid; the odour of the poison was also perceptible in domen. About eight ounces of a thick farinaceous mass were found in omach: the odour of prussic acid was very perceptible in this organ, but mixed with that of rancid food. The mucous membrane had every-, except at the greater end and posterior wall, a vivid inflammatory ns of a well-marked character, and it was covered with a layer of mucus to a considerable extent. This membrane, even after it had washed three times in water, gave out a strong odour of prussic acid. ase in which death had been caused by a large dose of the acid, there generally congested state of the mucous membrane of the stomach. dical student destroyed himself by swallowing about one drachm of le's acid. He was found in a state of collapse and breathing heavily, out half a minute from the time at which he was last seen. He died enty minutes. The coats of the stomach were greatly congested ds the cardiac end. The minute vessels throughout were filled with blood, and there were some spots of effused blood beneath the mucous The intestines were highly congested, the small vessels being visible er the coats. There was no congestion of the membranes of the brain. has recorded the appearances in two cases which fell under his notice. 's 'Vierteljahrsschr.' 1868, 2, 179.)

uantity required to destroy life.—The *smallest* dose of this acid which orted to have caused death, was in a case which occurred to Hicks. l. Gaz.' vol. 35, p. 896.) A healthy adult woman died in twenty es from a dose equivalent to *nine-tenths* of a grain of anhydrous c acid. This was equivalent to *fifty-four minims* of the pharmacopœial In one case ('Med. Gaz.' vol. 36, p. 104), a stout healthy man wed this dose, *i.e.* nine-tenths of a grain by mistake, and remained ible for *four hours*, when he vomited and began to recover. The ed matters had *no odour* of the poison, showing that, if not concealed ier odours, the whole of the acid must have been absorbed. He had y narrow escape of his life. Banks published a case in which a n recovered after swallowing thirty drops of prussic acid. ('Ed. Surg. Jour.' vol. 48, p. 44.) The *largest* dose from which an adult ecovered, was probably in a case which has been reported by an. ('Lancet,' Jan. 14, 1854.) His father, æt. 60, of a strong tution, took by mistake a *drachm* of prussic acid, equivalent to 2·4 of anhydrous acid. In a few seconds he perceived the mistake, wallowed half an ounce of aromatic spirits of ammonia with a little . Four minutes after taking the poison cold affusion was employed, rrous sulphate and spirit of ammonia were administered. Vomiting convulsive shuddering and insensibility took place. In twenty s consciousness returned, and fifteen minutes later he was able to upstairs to bed. He perfectly recovered, but in the absence of the treatment resorted to, it is most probable that he would have died. Bacon reported ('Edin. Month. Jour.' Feb. 1850, p. 97) the case of [illegible] who recovered after having taken a dose equivalent to a *grain* half or two grains of anhydrous acid. The treatment consisted in vacuation of the stomach by the stomach-pump, and in pouring [illegible] of cold water on the head. The symptoms were such that the [illegible] have died but for immediate treatment. It is a remarkable [illegible] this case no bottle or vessel could be found in the room or [illegible] w. *The patient hastily* summoned his wife one evening,

told her that he had taken prussic acid, and immediately fell down senseless on a sofa, without either cry or convulsion, but drawing his breath deeply, forcibly, and slowly. He recovered in about three hours, but had an unusual disposition to sleep, even on the following day. Another case of recovery from a dose nearly as large is reported ('Prov. Med. Jour.' Aug. 13, 1845, p. 517). From the facts hitherto observed, we shall not be wrong in assuming that a quantity of pharmacopœial acid (of two per cent.) *about fifty minims* (i.e. *one grain of anhydrous acid*), or an equivalent portion of another acid, would commonly suffice to destroy the life of an adult. This is the nearest approach that we can make to the *smallest fatal dose*. In *Reg.* v. *Bull* (Lewes Aut. Ass. 1860) a question arose respecting the minimum fatal dose of this poison. The accused, a young medical man, was charged with the manslaughter of his mother, a woman æt. 66. He had prescribed for her prussic acid to relieve sickness. He procured a bottle of Scheele's acid, said to contain one drachm. He administered four minims to deceased in the morning, and it appeared to benefit her. In the evening he gave to her another dose amounting, according to his statement, to 'seven drops.' The deceased went upstairs, became insensible, and died in a few minutes. When the bottle was examined twenty-five minims remained in it: hence thirty-five minims were alleged to be missing, but the druggist who sold the acid poured out the quantity conjecturally, and the bottle was found to have a broken cork. The strength of the acid had not been determined. Under these circumstances the prisoner was acquitted. In this case the Court desired to know the relation of drops to minims, but no satisfactory answer could be given. The size of a drop materially depends on the nature of the liquid, the mouth of the bottle, and the rapidity of the measurement. Seven drops of Scheele's acid dropped from a small phial measured seven minims. There can be no doubt in the above case that the poison caused death, and unless we assume that seven drops or minims will destroy life, which is not probable, the deceased must have taken a much larger dose than the accused had intended. Scheele's acid is twice the strength of the pharmacopœial acid: the latter contains two per cent. of prussic acid.

Period at which death takes place.—When the dose is two drachms and upwards, we may probably take the average period for death at from *two* to *ten* minutes. In Hick's case twenty grains of Scheele's acid destroyed life in twenty minutes. In this respect, death by prussic acid is like death by lightning; the person in general either dies speedily or recovers altogether. Death has occurred in the human subject as early as the *second*, and as late as the *seventy-fifth* minute, or possibly the ninetieth. But although death does not commonly ensue until after the lapse of a few minutes, sensibility, and consequently a power to perform certain acts of volition and locomotion, may cease in a few seconds. The time at which this loss of muscular power is supposed to take place has frequently become an important medico-legal question; and on the answer to it the hypothesis of suicide or murder in a particular case may rest.

Chemical Analysis.—Prussic acid is limpid like water; it possesses a faint acid reaction, and its vapour has a peculiar odour, which when the acid is concentrated, although not at first perceptible, is sufficient to produce giddiness, insensibility, and other alarming symptoms. The tests which are best adapted for the detection of this poison, either in liquid or vapour, are equally applicable, whether the acid is concentrated or diluted, and so far as the detection of the *vapour* is concerned, whether the acid is pure or mixed with other liquids or solids. *In the simple state*, the tests are: the *Silver*, the *Iron*, and the *Sulphur* tests.

Silver-test. Silver Nitrate.—This yields, with prussic acid, a hite precipitate, speedily subsiding in heavy clots to the bottom vessel, and leaving the liquid almost clear. The precipitate is l as silver cyanide by the following properties:—*a.* It is insoluble nitric acid; but when drained of water, and a sufficient quantity g acid is added, it is easily dissolved on boiling. *b.* It evolves cid, when digested in hydrochloric acid. *c.* The precipitate, when *d*, and heated in a small reduction-tube, yields cyanogen, which burnt as it issues, producing a rose-red flame with a blue halo. a well-marked character, and at once identifies the acid which he precipitate as prussic acid. By this property, the cyanide is ly distinguished from all the other salts of silver. In the employ- the silver-test for the detection of the *vapour* of the poison, we drop of the silver solution in a watch-glass, and invert it over watch-glass or beaker containing the suspected poisonous liquid. yanide, indicated by the formation of an opaque white film in the is immediately produced, if only in a moderate state of concen- One drop of a diluted acid containing less than 1–50th of a grain hydrous acid produces speedily a visible effect. When the prussic nore diluted, a few minutes are required; and the opaque film show itself at the edges of the silver solution. In this case the nay be accelerated by the heat of the hand. If the vapour is to reach the silver nitrate gradually and much diluted with air, tead of an opaque film of silver cyanide, crystals well defined e microscope will be slowly produced, and these will constitute an l proof of the presence of the acid in f vapour. As shown in the annexed on (fig. 49), these crystals have the slender prisms with oblique termina- They are often grouped, and generally high magnifying power to render ible.

Fig. 49.



Crystals of Silver Cyanide from the vapour of prussic acid, magnified 124 diameters.

Iron-test.—The object of the applica- his test, is the production of *Prussian* e add to a small quantity of the sus- poisonous liquid, a few drops of a solu- potash and of green ferrous sulphate. green or brownish precipitate falls; ing this, and then adding dilute hydro- r sulphuric acid, the liquid becomes d Prussian blue of its well-known colour, unaffected by diluted besides. If the prussic acid is in small quantity, the liquid is at ow, from the ferric salt formed; it then becomes green, but ptate ultimately subsides so as to appear of a deep blue colour in he iron-test may be employed for the detection of the *vapour* of cid, by the same method as that described in speaking of the t. For this purpose we place a few drops of a solution of potash h-glass or saucer, and invert it over the suspected liquid. After a tes' exposure a drop of solution of green ferrous sulphate may be d then a drop of diluted hydrochloric acid, when Prussian blue ear. The silver and the iron-tests may be easily conjoined in he same quantity of poison. If the precipitated silver cyanide, by the addition of silver nitrate to the suspected liquid, is dried moistened with strong hydrochloric acid, the vapour may be in a watch-glass or saucer, on the plan above described. Prussian be procured, and thus *corroborate* the action of the silver-test.

3.—*The Sulphur-test.*—If a small quantity of yellow ammo sulphide is added to a few drops of a solution of prussic acid, an mixture is gently warmed, it becomes colourless, and, on evapor leaves crystals of ammonium sulphocyanate—the sulphocyanic acid indicated by the intense blood-red colour produced on adding t dry residue a solution of a nearly neutral ferric salt: this red immediately disappears on adding a few drops of a solution of cor sublimate. The colour is also destroyed by strong acids, and its int is diminished by moderate dilution with water. This process is delicate, and it therefore requires some care in its application: thus, boiling and evaporation are not carried far enough, the ferric salt v precipitated black by the undecomposed sulphide; and, if the h carried too far, the ammonium sulphocyanate may itself undergo d position, and be lost. It will be perceived, too, that it requires a time for its application than either the silver or the iron-test. prussic acid contains traces of Prussian blue or a salt of iron, acquire a dark colour on the addition of the sulphide.

The great utility of the *sulphur-test*, however, is in its applicat the detection of the minutest portion of prussic acid when in a s *vapour*. In this respect it surpasses any other process yet discovere order to apply it, we place the diluted prussic acid in a watch-glas invert over it another watch-glass, holding in its centre one drop yellow ammonium sulphide. No change apparently takes place sulphide; but if the watch-glass is removed after the lapse of from minute to ten minutes, according to the quantity and strength prussic acid present, crystallized ammonium sulphocyanate will be ob on gently evaporating the liquid to dryness. With an acid of from to five per cent. the action is completed in ten seconds. The addi one drop of the neutral ferric sulphate (free from nitric acid) to the residue, brings out the blood-red colour instantly, which is intense i portion to the quantity of sulphocyanate present. When the acid is much diluted, the warmth of the hand may serve to expedi evolution of the vapour. The author has elsewhere made some re on the application of this process for the detection of prussic acid. 'Med. Gaz.' 1847, vol. 39, p. 765.)

Prussic Acid in organic liquids. Detection without distillation. organic liquid may be placed in a wide-mouthed bottle, to which a glass has been previously fitted as a cover. The capacity of the may be such as to allow the surface of the liquid to be within one inches of the concave surface of the watch-glass. The solution of *nitrate* is then used as a trial-test in the way already described. 1–200th of a grain of prussic acid is present, and not too largely dilu will be detected (at a temperature of 60° F.) by the drop of silver being converted into an opaque white or crystalline film of silver cy the chemical change commencing at the margin. We may then subs yellow ammonium sulphide for the silver nitrate, and proceed i manner above described. It may be sometimes necessary to plac bottle in a basin of warm water. If the solution of silver is tarnish sulphuretted hydrogen, as a result of putrefaction, the sulphur-test should be used. By this process prussic acid was detected in the sto of a person poisoned by it, as late as twelve days after death. Aft stomach had been exposed for a few days longer, all traces of the p had disappeared.

Detection by distillation.—The organic liquid should be faintly ac lated with hydrochloric acid distilled in a water-bath at 212° F., and one-sixth or one-eighth of the contents of the retort, collected in a rec

pt cool by water. The tests may now be applied to the distilled liquid. the trial-test indicate that the quantity of poison is small, a solution of ver nitrate or of caustic potash may be placed in the receiver, to fix the d as it is distilled over; Prussian blue may then be procured in the nner described, or the vapour may be at once absorbed by yellow monium sulphide in the receiver, and the liquid evaporated to obtain phocyanate. Prussic acid has been found in the stomach by *distillation*, late as *seven* days after death, although the odour could not be perceived ore distillation. In the case of *Montgomery* (Rep. of trial of *Thompson*, sgow Cir. Court, 1857, by Hugh Cowan, pp. 9 and 53), the deceased d in about fifty minutes after having taken two drachms of prussic acid uivalent to three and a quarter grains of anhydrous acid). The death k place on the 13th Sept.: the body was buried on the 17th, and exhumed the 30th. The parts removed were then put into stoppered bottles, and the 5th Oct. the Drs. McKinlay detected prussic acid doubtfully by the our, but distinctly by the three tests, in the stomach, before distillation, well as in the liquid distilled from the stomach and its contents. They l not succeed in detecting its presence in the tissues. About five weeks bsequently to this analysis, the viscera, which had been kept closely ured in glass bottles, were examined by Maclagan. The heart, kidneys, d intestines gave no indication of the presence of the poison, but it s detected by the sulphur-test, in the form of vapour, in one half the spleen, although there was no odour of the poison. When the scera containing the poison have undergone putrefaction, no trace of the id may be found either by its vapour or by distillation. In this case it ay have been converted into ammonium sulphocyanate by yellow ammo- um sulphide produced during putrefaction. The sulphocyanate may en be dissolved out of the dried viscera or liquids by alcohol, and the lution evaporated to dryness, the residue redissolved in water and tested r a ferric salt. In this way the editor has detected the poison in blood pt for a year after death from prussic acid. Much is lost by reason of e great volatility of the acid. The author has found the vapour to averse paper and wet and dry bladder in a few minutes. Hence all scera suspected to contain prussic acid should be preserved in well- oppered glass bottles.

In the Tissues.—Soon after death the poison may be easily detected in e blood, secretions, or any of the soft organs, by placing them in a bottle, d collecting the vapour in the manner already described. This will be und to be far more convenient and satisfactory than the process by dis- llation. In 1880, there were thirty-two deaths in England from prussic id, oil of bitter almonds, and laurel leaves.

Cyanide of Potassium, or Potassium Cyanide.

Cyanide of Potassium may be regarded as a compound of hydrocyanic prussic) acid, containing 41 per cent. of the latter poison. The com- ercial cyanide is impure, containing also potassium cyanate and carbonate. Cyanide of potassium is largely used in photography and in electro-gilding nd silvering. In 1880, there were twenty deaths from cyanide of potassium.

Symptoms.—This salt has a bitter taste, producing first a sense of cold- ess on the tongue followed by a feeling of constriction, and burning heat n the throat. It is one of the most formidable poisons known to chemists. It has destroyed life in a quarter of an hour. A dose of five grains, equal o two grains of prussic acid, has proved fatal in three instances. In one ase the person died in two hours. ('Chem. News,' Sept. 5, 1863). The ymptoms which the cyanide produces are similar to those occasioned by prussic acid:—insensibility, spasmodic breathing, convulsions with tetanic

stiffness of the jaws and body. They appear in a few seconds or and run through their course with great rapidity. An acid sta stomach, by liberating prussic acid from the salt, is thought to l effects.

Insensibility is not always an immediate symptom. A woma the time was under medical treatment, took by mistake a teaspoo solution of cyanide of potassium, containing about seven grains o Immediately after taking it she complained of a severe burning p stomach, and a feeling as if the bowels were about to act. She w water-closet, and her strength left her. She was removed to speedily became unconscious. It was found impossible to intro thing into the stomach. She died in less than an hour. The convulsion before death, but a sudden convulsive action of the l place after the heart had ceased to beat. The appearance of the so natural, even on the day following death, that some of her fri posed there might still be life. ('Boston Med. and Surg. Jour.' 1856, and 'Brit. and For. Med. Rev.' 1857, vol. 19, p. 498.) I woman swallowed an ounce and a half of a solution of cyanide of p used for photographic purposes. The quantity taken amounte grains. In two minutes she became unconscious, the whole of was slightly convulsed, and the pupils of the eyes were dila foamed at the mouth, the pulse was small and feeble, and t spasmodic closure of the jaws. Nevertheless, as she had lost so there was sufficient space for the introduction of the tube of the pump, within five minutes after she had taken the poison. Sl twenty minutes. In the Registrar-General's Report for Oct. 3, 1 deaths are stated to have occurred from this salt, among the f soldiers: two were cases of suicide and one of accident. It app they employed it for cleaning lace. The salt has given rise accidents among persons engaged in the practice of this ar photography. (For cases of its fatal action see 'Med. Times Oct. 12, 1850, p. 390; Nov. 9, 1850, p. 482; and July 12, 18 also, 'Chem. News,' April 27, 1861, p. 260.)

Appearances.—In a case in which an inspection of the body two days after death, there was no remarkable odour:—the mu stiff and rigid; the face, and fore part of the body, pale; the l livid, except those portions which had sustained pressure. The fi toes were convulsively bent inwards, the nails blue, the eyelids half-c lips pale, the vessels of the brain filled with blueish-red blood. O a section of the brain and spinal marrow, bloody points were obser lungs were congested posteriorly, and on cutting into them a stro of bitter almonds was perceived. A yellowish mucus was fou stomach, which yielded on analysis cyanide of potassium. Th membrane was reddened near the intestinal end. The poison detected in any part of the body except the contents of the sto intestines. (Casper's 'Wochenscrift,' Oct. 4, 1845, p. 657.) I girl, æt. 18, was brought to Guy's Hospital. Half an hour b admission, she was seen to swallow a solution of cyanide of p She vomited once. It is stated that she was alive when put into but when taken out at the hospital, seven minutes afterwards, completely insensible, pulseless at the wrist, and to all appearan Artificial respiration was at once resorted to, ammonia was applie nostrils, warmth to the limbs, and cold affusion to the spine; but effect, and with the exception of an alteration in the pupils observe the first few minutes of her admission, she evinced no signs of The body was inspected on the following day. The stomach con

e quantity of half-digested food: its mucous membrane was of a pink ur and deeply injected, especially in patches. Every other organ was lthy, and there was no appearance of corrosion about the mouth. The ents of the stomach were of a pale straw-colour, semi-fluid, and had a dedly bitter almond odour. Prussic acid was detected in them. (See 'Lancet,' 1863, II. p. 447.)

This poison is generally fatal. Two cases of recovery from large doses however reported by W. E. Stevenson ('Lancet,' 1871, I. p. 806). 1862, a man swallowed the greater part of a solution containing an ce of the commercial cyanide, which he had dissolved for the purpose. fe found the man a few minutes afterwards lying in the street nsible, and breathing stertorously; and in about ten minutes he applied stomach-pump, and cold affusion freely. In two hours the man vomited, from that time rapidly recovered. This is a rare instance.

Commercial cyanide of potassium has a local chemical action upon the ; and if this is abraded or wounded, it may be absorbed and produce ous effects. Some accidents of this kind have occurred in the practice hotography. ('Ann. d'Hyg.' 1863, 1, 454.)

Analysis.—Cyanide of potassium is usually seen in hard white masses. deliquescent, and very soluble in water: the solution, when pure, is orless, and has a strong alkaline reaction, a soapy feel, and a powerful ur of prussic acid. It is not very soluble in pure and strong alcohol. 1. decomposed by all acids, and prussic acid is set free. 2. The potassium ecipitated by tartaric acid and by platinic chloride. 3. It gives a white ipitate with silver nitrate, which, when dried and heated, possesses all properties of silver cyanide. This precipitate is easily redissolved by ght excess of the solution of potassium cyanide. 4. If a solution of ous sulphate is added to a solution of the potassium cyanide, and after ation dilute sulphuric acid, Prussian blue will result. 5. A single n of this salt moistened with water in a watch-glass, gives a well-ked reaction, by its vapour, with the silver and sulphur-tests. Should experiment fail, a drop of yellow ammonium sulphide may be heated the cyanide—the liquid acidulated with hydrochloric acid, and a solu- of ferric sulphate added. The red colour of ferric sulphocyanate is ediately brought out.

Organic Substances.—The salt may be obtained as a soluble fixed residue organic matter by drying and incinerating it in close vessels; or sic acid may be at once procured by distilling the contents of the ach with diluted sulphuric acid.

Lwow has detected potassium cyanide in the body 100 days after h ('Ann. d'Hyg.' 1882, t. viii. p. 571), and Zillner four months after h. ('Vierteljahrsschrift f. Gerichtl. Med.' xxxv. 1882, p. 193.)

Silver Cyanide.

One death occurred from the taking of this substance in 1880. Not-standing its great insolubility, it is readily decomposed by the free rochloric acid of the gastric juice, prussic acid being liberated.

Essential Oil of Bitter Almonds.

This liquid, which is used for the purpose of giving flavour and odour confectionery, owes its poisonous properties to the presence of prussic l. It contains a variable quantity of the acid, sometimes amounting welve per cent. *Almond flavour* or essence of peach kernels contains drachm of the essential oil to seven drachms of rectified spirit. Thirty- deaths from this oil are reported to have occurred in England and les in four years.

Symptoms.—The following may be taken as a summary: l
the face; eyes glassy, prominent, fixed and staring; pupils di
insensible to light; jaws spasmodically closed; frothy mucus
mouth; in some cases vomiting of food; coldness of the skin;
intermittent, and sometimes stertorous respiration; absence of
head spasmodically drawn backwards, and sometimes the tr
general relaxation of the limbs; an odour of bitter almonds
mouth.

In one case, a woman swallowed about seventeen drops of th
oil, and she died in half an hour. She was seen by Bull in ab
minutes: her face was livid, the lips separated, the teeth
froth about the mouth, the eyes half-shut and glassy, the pup
and fixed, and there were heavings of the chest at intervals;
no pulse, and the action of the heart was scarcely perceptible.
was perceived about the body until after the stomach-pump had
The first symptoms observed in this case were strong convul
deceased throwing her arms about as if in pain. A boy, æt. 13,
a quantity of the oil; he was found lying on the floor motionle
sensible; the face pale, the eyes open and fixed, the pupils dilat
was rolling about and panting for breath; the pulse at the
imperceptible; he died in a quarter of an hour without any c
appearing. A man, æt. 20, swallowed about two ounces of t
person present saw him fall suddenly while in the act of swall
made a loud cry, gave one deep expiration, and died.

In another case, a woman, æt. 46, who had been in the habi
the almond essence for flavouring confectionery, swallowed abo
ounce (equal to thirty drops of the oil). She died in less ths
hour. When seen by a medical man ten minutes after she had
poison, she was perfectly insensible. The face was pale but sw
covered with perspiration; the eyes stared fixedly as if in t
pupils were dilated. The lips were partly closed and livid, an
mucus issued from the mouth. The lower jaw was firmly
while the muscles of the neck and of the limbs, excepting th
fingers, were flaccid. She breathed slowly and heavily, making
respirations in a minute; the pulse was from 30 to 40, and feeb
was an odour of bitter almonds in the breath. Some blood
drawn from the arm was thick and dark, resembling choleraic
spite of the use of the stomach-pump and cold affusion, the patie
show any signs of recovery, but gradually sank. ('Assoc. M
Dec. 13, 1856, p. 1055.) In 1853, a woman, æt. 39, swallow
ounce of *almond flavour*, containing half a drachm of the essenti
ten minutes she was perfectly insensible and motionless; the p
moderately dilated and insensible to light; the mouth was pa
the lips were pale, there was no distortion or spasmodic mo
the features; the pulse was slightly tremulous, and entirely c
few minutes; the breathing was slightly stertorous, and took pl
intervals. She continued in this state for twenty minutes wi
convulsive movements of the body, when she died, *i.e.* half an
she had taken the poison. In another case two drachms destro
seventeen minutes. ('Lancet,' 1863, II. p. 447.)

Appearances.—In Bull's case (*supra*), on inspection nine h
death no odour of the oil was perceptible in the chest, head,
nor in the venous blood with which the system was gorged.
and heart were healthy. The vessels of the brain were cong
there was a general effusion of serum on the hemispheres. T
membrane of the stomach was much congested. On openi

itter-almond odour was quite perceptible. ('Prov. Med. Jour.' Sept. 11, 344, p. 364.) In the case of the boy (p. 386), which proved fatal in a uarter of an hour, on inspection there was pallor of the face, with lividity the depending parts; the lungs were congested; the odour of the poison as perceptible only in the abdomen, and very distinctly in the contents of e stomach. The mucous coat of this organ was generally pale, but there re some patches of ecchymosis scattered over it. The essential oil and ussic acid were detected in it. ('Lancet,' July 12, 1845, p. 40.) In a se which proved fatal in three hours, the skin was partially livid, the ood fluid, and the membranes of the brain as well as the lungs were rged. The contents of the stomach had a strong smell of the oil, and e mucous coat towards the intestinal opening had a red appearance. e other organs were healthy. The blood, with which the venous system gorged, is generally liquid and of a dark colour.

Analysis.—The *essential oil*, which is often called peach-nut oil, is lourless when pure, but it commonly has a pale yellow colour, and a ong odour of bitter almonds, by which it may be identified. It has a t, burning taste, and a feebly acid reaction. It produces, when dropped paper, a greasy stain which does not entirely disappear by the applica- n of heat. It has a sp. gr. of 1·043; it sinks in water, which dissolves out one-thirtieth part. It is soluble in alcohol and ether in all propor- ns. When mixed with a few drops of strong sulphuric acid, it forms a h crimson-red liquid which, if exposed to air, becomes yellow. When ured into cold water, the crimson colour is immediately destroyed, and yellow colouring matter falls in globules. The smell and taste of this , with the chemical tests, are sufficient for its identification; but nitro- nzol possesses similar odour, and has been mistaken for it. When pure d free from prussic acid, it is rapidly converted by oxidation into ystallized benzoic acid. The impure oil undergoes this change slowly.

The vapour of prussic acid does not so readily escape from this oil as om the watery solution: hence the vapour-tests do not give so quickly aracteristic results. *Tests.*—1. Add to one or two drops of the oil a like antity of yellow ammonium sulphide. Mere mixture at a low tempera- re only produces sulphocyanate after standing ten minutes or longer: t if the liquid is warmed with alcohol the conversion is immediate, and e change is indicated by the blood-red colour struck on adding ferric lphate to the liquid. If any unchanged sulphide should give a black lour, this may be removed by the addition of one or two drops of hydro- loric acid. 2. Dissolve one or two drops of the oil in alcohol and add the mixture a few drops of a solution of potash, followed by a solution ferrous sulphate and hydrochloric acid. Prussian blue is formed on rming the mixture, and adding dilute sulphuric or hydrochloric id. The silver-test is inapplicable to the oil in its ordinary state. The pour of the oil produces no change in a drop of a solution of silver trate, except after long exposure. If, however, the oil be heated, there an immediate production of silver cyanide. The two tests above men- ned, combined with the odour, are sufficient for all practical purposes.

Bitter almond water, laurel water, and the essences of peach and cherry rnels, all owe their noxious properties to the presence of prussic acid.

In 1876, a patient was admitted into Guy's Hospital suffering from the fects of a handful of bitter almonds, which he had eaten. The symptoms re those of prussic acid poisoning, from which he recovered.

CHAPTER 28.

NARCOTIC LIQUIDS AND VAPOURS:—SULPHIDE OF CARBON—COAL-NAPHT —WOOD-NAPHTHA—BICHLORIDE OF METHYLENE—AMYLENE— NITROBENZOL—ANILINE—OIL OF WORMWOOD—ABSINTHE—NITROG GLONOIN.

Carbon Disulphide. Sulphide of Carbon.

This liquid is extensively used in the arts as a solvent for p sulphur, and caoutchouc. Nothing is known of its effects on liquid; and from its powerful and offensive odour it could not administered with homicidal intention. The effects of its vapou chiefly observed among workers who employ this liquid. I headache, loss of appetite, colicky pains, impairment of vision a and causes general derangement of health, evidently by an o the nervous system. ('Chem. News,' May 2, 1863, p. 216.) has described with great elaboration the results caused by the in the vapours of the disulphide in caoutchouc factories. ('Nouv. sur l'Intoxic. Spec. qui determine le Sulf. de Charbon, Paris,' 1 results rarely ensue except in close, ill-ventilated establish states that in these chronic cases there is intense oppressive extending from the bridge of the nose to the temples, giddines on going into an uncontaminated atmosphere a feeling of int experienced. Sometimes there is a period of excitement; but there is, at a later stage, dulness, apathy, and often partial p speech. Sight and hearing are affected. There is great loss o power, and anæsthesia. Cramps and fibrillary constrictions muscles are rarely absent. The sexual feeling, at first in eventually completely lost. A number of the workpeople s vomiting, colic, and alternate constipation and vomiting. Fla the odour of the disulphide, may be eructed and passed by t and the urine also not infrequently smells of the poison.

Bernhardt has observed similar cases. (Husemann's 'Jahre p. 495.)

Analysis.—The odour and inflammability of this liquid are s identify it even in the smallest quantity.

Coal-Naphtha.

The light oily product of the distillation of coal, a hydrocar under the name of coal-naphtha, has caused death in one c symptoms of narcotic poisoning. A boy, æt. 12, swallowed in about three ounces of coal-naphtha. He soon appeared as if i and ran about in a wild delirium. When seen in a short time b man, he was insensible, collapsed, breathing stertorously, and h cold and clammy. He had already vomited part of the liqui odour of the vomited matter at once showed what he had take promotion of vomiting, he was made to eject altogether two tab of naphtha, and he partially recovered. In spite of this reactio in about two hours he was again in a state of collapse, insensible gasping for breath, and frothing at the mouth. The eyes wer glassy, and the pupils contracted. There was complete loss o power, and great difficulty of breathing, but no convulsions. E the power of swallowing. In spite of every effort to save him, less than three hours after swallowing the liquid. On inspect

body four days after death, a strong smell of naphtha was perceived throughout the tissues. The blood was fluid, there was slight effusion of serum in the ventricles of the brain. The right side of the heart contained fluid blood, the left was empty, the lungs were not congested but pale. The coats of the stomach were not inflamed or materially changed in appearance. This organ contained a pint of semi-fluid matter, of which four or five ounces were liquid. An ounce of a dark-coloured liquid floated on the top, and was easily skimmed off. The liquid appeared to act in this case as a pure narcotic. There were no convulsions. The respiration of the *vapour* of this liquid diluted with air produces headache, giddiness, severe pain in the stomach, loss of appetite, and general illness. ('Lancet,' Aug. 23, 1856, p. 230.)

Analysis.—The peculiar odour as well as inflammability of the liquid, and the fact that it burns with a bright yellow smoky flame, would be sufficient to identify coal-naphtha. Its lightness and insolubility in water would allow of its being readily separated from the aqueous contents of the stomach.

Benzol. Benzene.

This is a colourless volatile liquid hydrocarbon obtained by the distillation and rectification of coal-naphtha. The breathing of its vapour produces narcotic effects, but with some symptoms indicative of a noxious action on the brain and spinal marrow, *e.g.* noises in the head, convulsive trembling, twitchings of the muscles, convulsions, and difficulty of breathing. ('Med. Gaz.' 1848, vol. 41, p. 1077.) But little is known concerning the action of liquid benzol on the human subject. It is poisonous to the lower animals and to all parasites; and it has been suggested by Sonnenkalb as a remedy for destroying the trichina spiralis. This writer also refers to a case in which a quantity of liquid benzene was swallowed by a man, and it operated as a narcotic. ('Anilin und Anilinfarben,' Leipzig, 1864, p. 13.) Gull observed a case of recovery from this poison.

Analysis.—The odour and inflammability of the liquid, as well as its insolubility in water, are sufficient to identify it, and to allow of its separation from organic liquids.

Wood-Naphtha. Wood-Spirit. Methyl-Alcohol.

The term Naphtha is frequently applied to a product of the destructive distillation of wood, differing entirely in composition and properties from the hydrocarbon above described as coal-naphtha. It is also known under the names of methyl alcohol and pyroligneous ether. It differs from coal-naphtha, among other properties, in being miscible with, and soluble in, water in all proportions. In its commercial form it is a nauseous liquid in odour and taste. When mixed in the proportion of one-tenth part with rectified spirit, it forms a compound now largely employed as a solvent in the arts and medicine, under the name of *Methylated Spirit.* It has a hot, disagreeable, spirituous taste, and like rectified spirit it would no doubt operate as a narcotic poison. Its odour is so powerful and peculiar, that no one could swallow it unknowingly. The author met with an instance of the effects of this liquid on man; and observed the effects produced by the respiration of its vapour on a large scale. It causes headache, loss of appetite, nausea, sickness, languor, and a general feeling of illness. A fatal case from an overdose of wood-spirit mixed with alcohol occurred in London in 1864, and was the subject of an inquest. The evidence showed, on an inspection of the body, that the lungs were congested and the stomach irritated and inflamed.

Analysis.—It is a *very inflammable* liquid, burning with a pale blue

flame. It is light and volatile, readily in part separable from oth by distillation below 200° F. Its odour is peculiar. It mixes w and alcohol in all proportions. Alcohol containing one-tenth (methylated spirit) is rendered so nauseous that it is rarely drinking purposes. The editor has, nevertheless, known it to b this purpose.

Amylene.

The vapour of this liquid was introduced by Snow as a sub the vapour of chloroform. It produces a loss of sensibilit causing complete coma or stupor. Its use has led to at least t and it is not so safe an agent as chloroform vapour for surgical The only *appearance* met with in one fatal case, was an emph state of the lungs, or excessive dilatation of the air-cells ('Med. Gaz.' April 4 and 18, 1857, pp. 332, 381); and in the other, a of the right cavities of the heart with dark fluid blood. The congestion of the brain, and no smell of amylene perceptible in ('Med. Times and Gaz.' Aug. 8, 1857, p. 133.)

Fusel-Oil, or Amylic Alcohol. Amyl Acetate.

Fusel-oil is also known under the name of Potato-spirit or oi It is of an alcoholic nature, but much less volatile than ordinary s ether: hence it is commonly a product at the latter part of the of spirit from fermented potatoes and cereal grains, imparting able odour and taste to the spirit produced. Its vapour whe in a diluted state is irritating to the lungs; it produces headacl and a feeling of giddiness, with a sense of suffocation and inabili or walk. This spirit is used in certain manufactures, as in the se oils and fats, and a question has arisen how far the vapours wc jurious to the health of workmen. There can be no doubt that is noxious when breathed, and that the work could not be carri safety unless there were free and perfect ventilation.

Furst found that two drachms of the liquid injected into th of a rabbit caused great restlessness and loss of muscular powe animal soon recovered. A similar quantity killed another rabb two hours: the principal symptoms were great depression anc of breathing. On inspection of the body, there was extravasati brown blood at the gullet end of the stomach, and the mucous presented brownish-red points. The lining membrane of the of the small intestines was reddened and covered with mucus: t were healthy and bloodless, and the lungs somewhat redder th Three drachms killed a rabbit within an hour. Half an ounce ca in a quarter of an hour, and one ounce in four minutes. Fus liquid, appears to have at first a stimulating and afterwards a action. In small quantities it produces intoxication. ('Lond. vol. 35, p. 430.) This liquid is absorbed into the blood, and a may be detected by its peculiar odour in the breath. Its toxicolog are more powerful in the state of vapour than when it is taken into the stomach.

Analysis.—Fusel-oil is a volatile liquid of a pale yellow colo than water and only sparingly soluble in it. It is dissolved by a ether in all proportions, but not readily by chloroform. Water it from its ethereal solution. It has a hot burning taste and a spirituous odour, which is very persistent and peculiar: by this distinguished from other alcoholic liquids. It is inflammable, with a pale blueish flame. Like alcohol, ether, and wood-spirit,

uses chromic acid, producing green chromic oxide. In organic mixtures ther might be used for its separation. By distilling one part of fusel-oil ith two parts of potassium acetate and one part of oil of vitriol, an ethereal quid, amyl acetate, is produced which is used in confectionery under the ame of *Essence of Jargonelle Pear*. A child on two occasions became artially comatose and had livid lips and a feeble pulse, after eating some nfectionery which it was calculated contained about one drop of this ssence. Hence its use is not without danger. ('Pharm. Jour.' Nov. 1851, . 214.)

Nitrobenzene or Nitrobenzol.

This liquid, which is employed as a substitute for the essential oil of itter almonds in perfumery and confectionery, is a narcotic poison. It is tensively used in the preparation of aniline colours, and has often proved tal. In the second edition of the author's work on Poisons some experiments were quoted from the Lancet (Jan. 10, 1857, p. 46), showing that ne drachm of nitrobenzol killed a rabbit almost instantaneously; and half drachm mixed with two drachms of water rendered a cat insensible for veral minutes, a slimy mucus flowing from its mouth for several hours fterwards. The animal refused all food, and died in twenty-four hours. 'On Poisons,' 1859, p. 701.) In 1859, Casper published an account of is liquid under the name of 'A new Poison' ('Vierteljahrsschr.' B. 16, .1). Its effects on a rabbit and a dog are here described. Two drachms of were given to a rabbit without any symptoms being produced; two drachms ere then given to the anmal at intervals of ten minutes or a quarter of an our, until the animal had taken one ounce. In a minute and a half after the st dose, the animal fell suddenly on its left side. The pupils were dilated, hile the limbs and tail were strongly convulsed. The animal died in a inute. The dose was probably unnecessarily large, but the result shows at nitrobenzol in a large dose may destroy life rapidly. On opening the ody, the powerful odour of the liquid was everywhere perceptible, even in e blood. This odour remained strongly in the body when it was again amined fourteen days after death. About five fluid drachms given to a iddle-sized dog produced no remarkable symptoms. After some hours he animal was observed to be dull and languid: in twelve hours there as profound coma, with slow respiration and coldness of the skin; but here were no convulsions. The animal was then killed. All the solids nd liquids of the body, including the blood, had a strong odour of the ison; and some drops of the oily liquid were separated from the contents f the stomach. The fluid on which it floated had a strong alkaline action. The blood retained the odour for several days.

Symptoms and Appearances.—The following cases are of interest: they nd to show that the vapour is much more potent than the liquid. Nichol- n ('Lancet,' Feb. 1, 1862, I. p. 135), in referring to a fatal case of poison- g by the liquid, states that he has known several instances in which the pour, as it is evolved from almond glycerine soap, has seriously affected rsons. A friend of his who used a cake of the soap in taking a warm bath inted from the effects of the vapour of nitrobenzol set free, and was ill for me time afterwards. In 1863, a case of poisoning by this compound curred, in which the symptoms so closely resembled those of essential oil bitter almonds, that it was at first supposed this oil had been taken. A oman, æt. 30, tasted a liquid which had been used for flavouring pastry, nd perceiving that it was very acrid on her tongue and lips, spat it out mediately and washed her mouth with water. She thought she could t have swallowed more than a drop, but in replacing the bottle she illed about a tablespoonful on the table and did not immediately wipe it

up. The vapour strongly impregnated the small room in which she was, and produced a feeling of sickness in another servant. The burning taste in the mouth was immediately followed by a sensation of numbness and tingling in the tongue and lips, and a strange feeling for the next hour. The woman became worse, and Fotherby saw her in an hour and three-quarters after the occurrence. Her aspect was then quite typical of prussic acid poisoning:—the eyes were bright and glassy, the features pale and ghastly, the lips and nails purple, as if stained by blackberries; the skin was clammy and the pulse feeble. Her mind was then clear, and she described how the accident had occurred and what her sensations were. She was able to swallow a mustard emetic, after which she became rapidly worse, lost her consciousness, the teeth became set, the hands clenched and blue, the muscles rigid and convulsed. She vomited freely a pale fluid matter, which had the odour of nitrobenzol. The stomach-pump was used, but the fluid washed out of the organ had hardly any odour. The breathing became much reduced, and the pulse could scarcely be felt. In about eleven hours there was reaction, consciousness returned, and she was able to swallow. At the end of seventeen hours she was much better; but she then complained of distorted vision, with flashes of light and strange colours before her eyes. For some weeks she continued weak. It was at first supposed the woman had swallowed a larger quantity of the liquid than she had imagined; but it is obvious, from the entire absence of the odour in the fluid drawn off by the stomach-pump, within about two hours, that but little could have passed into the stomach. There is no doubt, from what has been observed in other cases, that these severe symptoms were chiefly due to the breathing of the vapour in a concentrated form. A fellow servant who was in the room at the time the nitrobenzol was spilled, also suffered from the inhalation of the vapour. The liquid was found to be nitrobenzol unmixed with essential oil of almonds.

A clerk in some chemical works took a few drops (supposed to have been fifteen) of nitrobenzol. Immediately afterwards he felt unwell and became insensible. Stimulants restored consciousness, but there was a relapse, and he died the next day. ('Pharm. Jour.' Dec. 1862, p. 283.) A boy, æt. 17, while drawing off some nitrobenzol by a siphon, swallowed a portion of the liquid. There were no immediate symptoms, but he soon felt sleepy, and when at dinner ate but little, and said he felt as if he were drunk. This was between two and three hours after he had swallowed the liquid. He fell into a stupor which became deeper and deeper until death took place, without vomiting or convulsions, twelve hours after the ingestion of the poison. ('Med. Times and Gaz.' 1862, 1, p. 239.) The following cases occurred at Maidstone, in 1865. A boy, æt. 15, applied a bottle containing nitrobenzol to his lips. No symptoms followed at the time, and the boy ate his dinner as usual. Some hours elapsed when he suddenly became insensible. He was almost pulseless, and his jaws were spasmodically closed: the skin of the face was purple, and the lips were livid. He died in about four hours after the seizure, and twelve hours after taking the poison. Some small quantity was most probably swallowed, as the contents of the stomach had a strong smell of the liquid. A cook in the same family also applied the bottle to her lips. It tasted bitter. She had her dinner as usual, but an hour after tasting the nitrobenzol she was seized wth vomiting and felt very ill—her lips were black, and her face was purple and white. The woman recovered. The poison had been wrongly labelled oil of bitter almonds. For several cases of poisoning by this liquid see Husemann's 'Jahresber.' 1872, p. 331; *and* a paper by Schenk, Horn's 'Vierteljahrsschr.' 1866, vol. 1, p 32.

In a paper communicated to the Royal Society in 1863, Letheby

described two cases which fell under his observation. In one a man, æt. 43, spilled a quantity of nitrobenzol over his clothes, and went about several hours breathing an atmosphere saturated with the vapour. The effects were nearly the same in both cases; although in one the poison was inhaled in vapour, and in the other it was swallowed as a liquid. For some time there was no feeling of drowsiness in the man; gradually, however, his face became flushed, his expression stupid, and his gait unsteady; he had the appearance of a person who had been drinking. The stupor gradually increased, until it passed into profound coma, and in this state he died. The progress of each of the fatal cases was much the same as that of slow intoxication, excepting that the mind was perfectly clear, until the coming on of the fatal coma. This was sudden, like a fit of apoplexy; and from that moment there was no return of consciousness or bodily power: the sufferer lay as if in a deep sleep, and died without a struggle. The duration of each case was nearly the same. About four hours elapsed from the time of taking or inhaling the poison to the setting-in of the coma, and this lasted five hours. The *appearances* after death were—flushed face and livid lips: the superficial vessels of the body, especially about the throat and arms, were gorged with blood, which was everywhere black and fluid. The dependent parts were turgid, the lungs somewhat congested; the cavities of the heart were full of blood; the liver was of a purple colour, and the gall-bladder distended with bile; the brain and its membranes were congested, and in the case of the man there was much bloody serosity in the ventricles. Nitrobenzol, as well as aniline, into which it appears to be partially converted in the body, was detected in the brain and stomach. ('Proc. Royal Soc. 1863,' p. 550.) It is not stated what the result of the analysis, if any, was in reference to the case of death from the vapour, in which the poison was absorbed through the lungs. In performing some experiments on animals, Letheby found that the local action on the stomach was slight; there was rarely any vomiting, and there was either rapid coma, or a slow setting-in of paralysis and coma, after a long period of inaction. There was a complete loss of voluntary power, a spasmodic fixing of the muscles of the back, with violent struggles, a look of distress, and occasionally a kind of epileptic fit. The pupils were widely dilated, the action of the heart was irregular, and the breathing difficult. The time of death in the more rapid cases varied from twenty-five minutes to twelve hours after the administration of the poison. In other experiments, in which smaller doses were given, the time that elapsed between the administration of the poison and the coming-on of the first symptoms (an epileptic fit) varied from nineteen to seventy-two hours; in most cases it was about two days, and the time of death was from four to nine days. The appearances were similar to those already described. When death had taken place within twenty-four hours, the odour of the nitrobenzol was clearly perceptible in the stomach, brain, and lungs; and aniline (from the chemical conversion of nitrobenzol) was found in the organs. In the slower fatal cases the odour had often entirely disappeared; but traces of aniline could be detected in the brain and urine, and sometimes in the stomach and liver. Occasionally no trace of the substance was found, although death had taken place from the poison.

This compound differs from the ordinary narcotics in its powerful and persistent odour, which would render it difficult for a person to administer it, either in the form of liquid or vapour, unknowingly to another; in the production of profound coma at an uncertain interval after the stupor; and in the rapidly-fatal effects when coma has followed. It operates powerfully as a poison in vapour as well as in a liquid state; in the human

subject the symptoms resembling those of the first stage of narcot poisoning. The rapidly-fatal cases only would be likely to be mistak for apoplexy, but in these the poison would be detected by its odour.

In 1876, a man, æt. 21, was prescribed three-minim doses of 'ben rect.' three times a day. By mistake, the dispenser read the prescripti as ordering 'benzol nit.,' and gave nitrobenzol. The first day he took th doses the patient was observed to look a little pale and weak, but he was n conscious of feeling ill till after taking the seventh dose at 9 A.M. next da The aggregate amount of nitrobenzol now taken was ascertained to 23 minims. At 2 P.M., five hours after taking this final dose, after wal ing not more than forty yards in the street from his office, he fell dow He was just able to give his address, and then became insensible. 3.15 P.M. when seen by Gross he was cold, and the surface of the bo was blueish-purple. There was no pulse, but by the stethoscope the hea could just be heard faintly beating. The lower jaw was rigidly close but the limbs were flaccid and dropped powerless when raised; the pup were widely dilated. No breathing could be perceived for twenty minut after this. He was treated as for prussic acid poisoning, it being thoug that the poison was oil of bitter almonds. At 7 P.M. he became conscio and complained of headache. At 9 P.M. the skin was still blue. Ne day he was fairly convalescent. From the urine collected on the mornin following the accident, the editor extracted a substance having the odo of nitrobenzol.

Analysis.—Nitrobenzol, or 'Essence of Mirbane,' is a pale lemon-coloured liquid, of a strong odour resembling that of bitter almonds. It has a pungent hot disagreeable taste. It gives to confectionery the smell, but not the pleasant taste, of oil of bitter almonds. It gives a greasy stain to paper, leaving a yellow mark when the stain disappears. It sinks in water, and is partly dissolved, giving to it a yellowish colour. It is soluble in alcohol, ether, and chloroform; but when these are agitated with water, it is in great part separated from its ethereal and chloroformic solutions. It has no basic qualities; its aqueous solution is not precipitated either by tannic acid or the chloriodide of mercury and potassium. It is highly combustible, burning with a yellow smoky flame. It yields no Prussian blue when mixed with ferrous sulphate, alcohol, potash, and subsequently hydrochloric acid; and its vapour produces no silver cyanide with a solution of the nitrate. It is distinguished from all other liquids, except the essential oil of almonds, by its odour, and from this oil by the following test. Pour a few drops of each on a plate and add a drop of strong sulphuric acid. The oil of almonds acquires a rich crimson colour with a yellow border, the nitrobenzol produces no colour. With a crystal of chlorate of potash and a drop of sulphuric acid, it yield a violet colouration. In order to separate it from organic liquids, they may be acidulated with sulphuric acid, and submitted to distillation in an apparatus similar to that which is described at page 270, fig. 18. If any of it exists in a free state, its odour will be sufficient for detecting its presence. It is converted into aniline by acting upon it with acetic acid and iron filings. There is no probability that this liquid will be successfully employed for the purposes of murder without the certainty of detection.

ANILINE.

This is a narcotic liquid resembling nitrobenzol in its toxic effects Schuchardt found that a small rabbit was killed by sixty drops in six hours and a quarter, and a large rabbit by one hundred drops in four hours. There was loss of sensibility with loss of heat, and violent clonic and tonic convulsions ensued which continued until death. Fro

experiments performed, it does not appear to be an active poison as a liquid, and it seems to affect the spinal marrow more than the brain. It has also a local irritant action. Turnbull gave half a drachm of the sulphate to a dog. In two hours and a half the animal vomited, and an hour later it was purged. It became dull, weak, and tremulous; the pulse was rapid, and the breathing laboured. The feet were cold, the hind legs paralyzed, and the tongue was of a blue colour. In five hours the symptoms abated, and the next day the animal had recovered. ('Lancet,' Nov. 16, 1861.)

Letheby found that aniline given to dogs and cats in doses of from twenty to sixty drops, caused a rapid loss of voluntary power. The animal staggered and fell upon its side powerless, the head was drawn back, the pupils were dilated, the breathing was difficult, and the action of the heart tumultuous; there were slight twitchings or spasms of the muscles, and the animal quickly passed into a state of coma, from which it did not recover, death taking place in from half an hour to thirty-two hours. On inspection, the brain and its membranes were congested, the cavities of the heart were nearly full of blood, and the lungs but slightly congested. The blood all over the body was black and coagulated. The poison was easily discovered in the brain, the stomach, and the liver, although it was found that, as nitrobenzol is changed into aniline, so in some cases aniline and its salts are converted into mauve or magenta pigment. This arises from the oxidation of the salts, and it has been especially observed on the surface of the body. ('Proc. Roy. Soc.' 1863, p. 556.) Aniline is a liquid of nauseous odour and taste, and could hardly be taken or administered without the consciousness of the person taking it. The salts appear to have very little action. They have been used medicinally in large doses without producing any unusual effects. In one case, 406 grains of the aniline sulphate were given to a patient, in the course of a few days, without any symptoms of poisoning. (Letheby, loc. cit. See also 'Med. Times and Gaz.' 1862, 1, p. 239.) It is difficult to suppose that combination with an acid to form a perfectly soluble salt can render aniline inert, as this would be contrary to experience in reference to other bases, *e.g.* nicotine and conia.

There are facts which show that the *vapour* of aniline, even when much diluted, exerts a noxious effect on man. A workman accidentally broke a carboy containing a large quantity of this liquid; the aniline fell over him, but none entered his mouth. In his anxiety to wipe up the aniline, he inspired the vapour for some time, felt giddy, and complained of his head and chest. When seen, some hours after the accident, his face and body were of a livid leaden hue, the lips, gums, tongue, and eyes of a corpse-like bluish pallor; his breathing was gasping, and he appeared at the point of death. There was no convulsion; he was sensible, and able to give an account of his feelings. His pulse was small and irregular. Under active treatment he recovered. ('Pharm. Jour.' July, 1862, p. 42.; 'Med. Times and Gaz.' 1862, 1, p. 583.)

A boy, æt. 16, was brought into the London Hospital in a semicomatose condition. In scrubbing out an aniline vat he had breathed the vapour; and although he did not suffer pain or discomfort at the time, he was suddenly seized with giddiness and insensibility. When brought to the hospital he looked like a person in the last stage of intoxication; the face and surface of the body were cold, and the pulse was slow and almost imperceptible, the action of the heart was feeble, and the breathing heavy and laborious. After rallying a little, he complained of pain in his head and giddiness. His face had a purple hue, and his lips, the lining membrane of his mouth, as well as his nails, had a similar purple tint. On the next day the narcotic symptoms *had passed* away, but he was remarkably blue,

and looked like a patient in the last stage of Asiatic cholera. ('Med. Times and Gaz.' 1862, 1, p. 239.) These cases appear to show that aniline vapour is less poisonous than that of nitrobenzol, and that the symptoms follow more rapidly on the inhalation of the vapour. Kreuser has noticed among the workers in aniline that they have suffered from intense bronchitis, with a violent dry spasmodic cough, accompanied by ulcerations on the scrotum and extremities. The parts were swollen and painful, and covered with thick black crusts. This was obviously from want of cleanliness. ('Ed. Month. Jour.' Aug. 1864, p. 172.) For a full account of the effects of aniline on animals, the reader is referred to a pamphlet by Sonnenkalb, 'Anilin und Anilinfarben,' Leipzig, 1864, p. 20. The injurious effects to public health likely to arise from the employment of aniline colours in confectionery and cosmetics, are also fully described in this essay. Some of the aniline dyes by contact with the skin have produced much irritation and sometimes an eczemat. This subject has attracted much attention in Germany. (See Eulenberg's 'Vierteljahrsschr.' 1871, 2, 325.) Many mineral substances of an irritant nature are used in the preparation of these dyes, and the articles are not always freed from them by washing. It is now proved that the pure dyes are not poisonous.

Analysis.—Commercial aniline is an oily liquid of a reddish-brown colour, with a peculiar tarry odour. It produces a volatile greasy stain on paper. It is volatile and combustible, burning with a thick smoky flame. It falls to the bottom of water, and does not readily dissolve in it. It is soluble in alcohol and ether, but only sparingly in chloroform: in the latter property it differs fron nitrobenzol. Sulphuric acid combines with it to produce a white sulphate, soluble in water. A solution of bleaching powder added to the acid watery liquid produces a blue colour passing into various shades of purple and brown.

The solution of aniline sulphate is not precipitated either by tannic acid or by chloriodide of mercury and potassium; but aniline itself, in the small quantity in which it is dissolved by water, yields, like the alkalies, a yellow precipitate with arsenio-nitrate of silver. It also reduces completely a solution of auric chloride—precipitating metallic gold. When pure aniline is heated with powdered corrosive sublimate, it produces a rich crimson dye. When present in organic liquids, aniline may be separated by digesting the concentrated liquid in alcohol, mixed with a little diluted sulphuric acid. The alcoholic extract, distilled at a high temperature with a solution of potash, yields aniline. This may be tested by the methods above described.

Oil of Wormwood. Absinthe.

The following is the report of a case of poisoning by this oil. A druggist's shopman was found early one morning by his master, lying on the floor of the shop, perfectly insensible, convulsed, and foaming at the mouth. He was in a short time no longer violently convulsed, but was still insensible; the jaws were clenched, and the pupils dilated. The pulse was weak, compressible, and slow. From time to time he uttered incoherent expressions, and attempted to vomit. Repeated doses of stimulants—sal volatile and water, lime water, and an emetic of mustard and zinc sulphate were administered. Free vomiting ensued, and consciousness partially returned. Artificial warmth was applied to the limbs, and brandy given at intervals, with draughts of milk and lime water. He gradually recovered. The matters vomited smelt strongly of oil of wormwood, and the nature of the poison was placed beyond doubt by the discovery of the bottle, with marks on its mouth of the oil having been recently poured out. The druggist stated that at least half an ounce had been taken. From the per-

stent smell of the oil in the ejected matters, after repeated vomiting, it is obable that this was even less than the real quantity. The man, on covering, had totally forgotten all the circumstances connected with the se, and persisted in stating that he knew no reason why he should have ken it. It is, however, probable that he imagined himself suffering from orms, and sought relief in an unusual dose of this oil. (See 'Ann. d'Hyg.' 63, 1, p. 227.)

A liqueur called ABSINTHE owes its properties to the presence of is oil, with a large proportion of alcohol. It has been much used in rance, and its effects when taken in excess are those of a narcotic poison. ccording to Legrand it causes derangement of the digestive organs, tense thirst, restlessness, giddiness, tingling in the ears, and illusions of ght and hearing. These symptoms are followed by tremblings in the ms, hands, and legs, numbness in the limbs, loss of muscular power, lirium, loss of intellect, general paralysis, and death.

Magnan, who had under his observation two hundred and fifty patients ore or less injured in health by the abuse of this intoxicating liquid, and ho has besides performed numerous experiments on animals, states that ileptic convulsions are generally observed in these cases. Delirium mens is the ordinary result of the abuse of alcohol, but the epileptic tacks are specially referable to the absinthe. Magnan describes it as bsinthe epilepsy.' (Husemann's 'Jahresbericht,' 1872, p. 499, and Bouardat's 'Ann. de Thérap.' 1872, p. 66.)

Analysis.—Absinthe has a greenish colour, an aromatic odour like that f aniseed, and a hot pungent bitter taste. It acquires a milky appearance n the addition of water, owing to the separation of essential oil from the lcohol. It is a strong alcoholic mixture of oil of aniseed, oil of wormwood of which it contains 0·02 to 0·04 per cent.) and other aromatic substances.

NITROGLYCERIN (GLONOIN).

This is a sweet, oily, powerfully explosive liquid, well known to chemists s a substitution-compound of the innoxious liquid glycerin, obtained in he process of saponification. This liquid is much used in mining under he name of 'blasting oil.' It has a sweet aromatic pungent taste. Field tates that he found one drop of the liquid dissolved in water produced nsensibility and other symptoms of narcotic poisoning. ('Chem. News,' lov. 7, 1863), and that one-fiftieth of a minim produced in three minutes ud noises in the head and other distressing symptoms. Mixed with an nfusorial earth it is known as dynamite.

Symptoms and Appearances.—Murrell has found that one or two minims f a one per cent. solution of nitroglycerin produces painful pulsation ver the whole head; the pulsation soon affects the entire body, and is o marked that a pen held in the hand becomes visibly jerked. In five minutes these symptoms are followed by intense headache, languor, and lepression. Nitroglycerin is now largely employed in medicine in lieu f amyl-nitrite, which it greatly resembles in its effects, except that these re more lasting. The editor has seen the most distressing results ensue rom an overdose: the headache being of an alarming and fearful character.

Nitroglycerin has in several instances been the cause of accidental leath. It is sweet, colourless, and apparently innocent in appearance; and hese properties render it liable to be taken in mistake for other liquids of less potent character. In 1864, a girl, æt. 13, died after drinking some of from a flask. A man drank a considerable quantity of the liquid in mistake for beer. An hour later, he was blue in the face and insensible. When admitted into hospital he was delirious and unconscious, and speedily became comatose. The hands were frequently raised to the head, as if

there was headache. The face was red and swollen. He died six hours after swallowing the poison. The brain and its membranes were congested; and there was some yellow serous fluid in the ventricles. The lungs were œdematous, the windpipe, stomach, and kidneys reddened. Signs of irritation were also noted in the small intestines. There were numerous small ecchymotic spots on the fundus and larger end of the stomach. In a third case, a man drank some glonoin in mistake for brandy, and died in three hours. In a fourth case, a man recovered after swallowing a considerable quantity of the poison. (Schmidts 'Jahresber.' 136, p. 164.)

Honert met with a case of poisoning by this substance. ('Deut. Klin.' 1867, p. 83.) A man took a tablespoonful of gunpowder as a remedy for a boil, and in order to increase its effect, added a few drops of nitroglycerin. Soon afterwards he was seized with great nausea, and violent and repeated vomiting. According to the patient's own account, he became black about the eyes, had extreme headache and giddiness, and several times became unconscious. There was intense vascular disturbance, and perspiration rolled in streams from the head and limbs. After some time the patient became paralyzed; and when seen by Honert, four hours after the administration of the poison, the whole of the voluntary muscles, except those of the face and eyes, were paralyzed. In the face and eyes the paralysis of motion was incomplete. The heart's action was retarded, the pulse being only 39, full and hard. When paralysis was at its height, the breathing became stertorous, and the extremities icy cold. In twenty hours the pulse had risen to 70, then to 90 in the minute; and the paralysis disappeared. After an attack of catarrh of the stomach, the patient quickly recovered.

Many other cases are recorded. A miner swallowed two mouthfuls. A painful feeling in his throat made him aware of his mistake, and he drank a quantity of milk. He was not seen by a medical man for an hour and a quarter. He was then suffering from faintness, difficulty of breathing, and oppression at the chest. In five hours vomiting and purging set in. Shortly before death the man lay quietly as if asleep, breathing feebly and occasionally with a deep sigh. The lips were livid before death. On inspection there was great congestion of the membranes of the brain as well as of the lower lobes of the lungs. The mucous membrane of the air-passages was of a red-brown colour. The greater end of the stomach presented a similar appearance with ecchymosis. (Husemann's 'Jahresber.' 1872, p. 533.)

The vapour of this liquid acts powerfully as a poison, and even when much diluted with air it produces intense headache.

Vrij has prepared nitroglycerin in large quantities, and has examined its chemical and physiological properties. Sobrero, who discovered it in 1847, stated that the smallest quantity was sufficient to produce the most violent headache, and he concluded from this that it was a powerful poison. Vrij found that the vapour caused intense headache, but that it had no poisonous properties. He gave two drops to a rabbit, and no symptoms of poisoning were produced. ('Pharm. Jour.' 1855–6, p. 229.)

Analysis.—Nitroglycerin is a heavy, oily-looking liquid. It is dissolved by water, but is insoluble in alcohol and ether. It explodes violently when struck or subjected to concussion. Nitroglycerin yields a red colour when treated with aniline and strong sulphuric acid; and also a red colour when treated with brucine and strong sulphuric acid (free from nitric acid).

Alcohol.

Symptoms.—Concentrated spirits of wine *i.e.* alcohol with only a small admixture of water, attracts water eagerly from all ordinary organic living

d dead tissues; and hence acts like an irritant poison. Usually, however, local injury to the stomach is small compared with the general results ich ensue from the swallowing of a large quantity of any concentrated oholic liquid. A drawing in the museum at Guy's Hospital furnishes a d illustration of the local action of alcohol: the whole of the mucous mbrane of the stomach is of a brownish-red colour, and highly corrugated. other liquid largely affecting the brain has so intense a local action on stomach. In general, the symptoms produced by a poisonous dose of ohol come on in the course of a few minutes. There is confusion of ught, with inability to stand or walk, a tottering gait, and giddiness lowed by stupor and coma. Should the person recover from this stage, miting supervenes. The insensibility produced by alcohol may not come until after a certain period, and then suddenly. Christison met with instance in which a person fell suddenly into a deep stupor, some time er he had swallowed sixteen ounces of whisky, without any of the ual premonitory symptoms. In another instance, a person may aprently recover from the first effects, and then suddenly become insensible d die convulsed. There is a ghastly or vacant expression in the face, ich is sometimes suffused and bloated; the lips are livid, and the pupils e dilated and fixed; if they possess the power of contracting under the fluence of light, it is a favourable sign. ('Lancet,' Jan. 27, 1855, p. 89.) he whites of the eyes are generally much suffused. The breath has an coholic odour. The more concentrated the alcohol, the more rapidly e the symptoms induced, and they are also more severe in their character. inte alcohol commonly produces a stage of exitement before stupor, while the action of concentrated alcohol there may be profound coma in a few inutes. The cause of death may be generally traced to congestion of the ain or lungs, or both. Alcohol may act as a poison by its *vapour*. If e concentrated vapour be respired, it will produce the usual effects of toxication. There is a case on record in which a child two years of age as thrown into an apoplectic stupor by the alcoholic vapour of eau de logne.

The symptoms arising from apoplexy, from concussion of the brain, the fects of opium, or those of carbolic acid, have been sometimes mistaken r those of poisoning by alcohol, and persons have been wrongly charged ith being drunk. With respect to *concussion*, a difficulty can arise only reference to the more advanced stage of poisoning by alcohol, *i.e.* in hich there is profound coma. Intoxication may in general be easily istinguished by the odour of the breath, for so long as the symptoms ontinue, the alcohol is eliminated by the lungs. If there should be no erceptible odour of any alcoholic liquid, the presumption is that the ymptoms are not due to intoxication. When the alcoholic odour is erceptible, the symptoms may still be combined with the effects of poplexy or concussion—a fact which can be cleared up only by a history f the case, or a careful examination of the head for marks of violence. In oisoning by *opium* there will be a strong smell of this drug in the breath, he symptoms come on much more gradually, and are marked by drowsi- ess and stupor, passing into complete lethargy, with general relaxation of he muscles, and inability to walk. In poisoning by alcohol there is either reat excitement some time before the stupor, which comes on suddenly, or he person is found in a state of deep coma a few minutes after having aken the poison. In poisoning by opium the face is pale, and the pupils re contracted:—in poisoning by alcohol the face, under excitement, is nore commonly flushed, and the pupils are generally dilated. Another act to be noticed is, that while perfect remissions are rare in poisoning by pium, in poisoning by alcohol a person frequently recovers his senses and

dies subsequently. When coma has supervened, the patient may be roused by a loud noise or a violent shock in either case, and it is very difficult under these circumstances to draw a well-marked distinction. The odour of the breath, or an examination of the fluid drawn from the stomach by the pump, may then show which poison has been taken: but the treatment is the same in both cases. In poisoning by carbolic acid, there is the peculiar odour of the acid in the breath, a white furred or shrivelled tongue, and a white or brown stain about the angles of the mouth.

Appearances.—The stomach has been found intensely congested or inflamed, the mucous membrane presenting in one case a bright red, and in another a dark red-brown colour. When death has taken place rapidly, there may be the peculiar odour of some form of spirits in the contents; but this will not be perceived if the quantity taken was small, or many hours have elapsed before the inspection is made. The brain and its membranes are found congested, and, in some instances, there is effusion of blood or serum beneath the inner membrane. In a case in which a pint of spirits had been taken, and proved fatal in eight hours, black extravasation was found on the mucous membrane of the stomach; but no trace of alcohol could be detected in the contents. ('Dub. Med. Press,' i. 293.) The action of a strong alcoholic liquid on the mucous membrane of the stomach so closely resembles the effects produced by arsenic and other irritants, as easily to give rise to the suspicion of mineral irritant poisoning. A girl was found at four o'clock in the morning lying perfectly insensible on the floor. She had had access to some brandy which she had swallowed from a quartern measure found near her quite empty. She had spoken to her mother only ten minutes before, so that the symptoms must have come on very rapidly. She was seen by Adams four hours afterwards. She was then quite insensible, in a state of profound coma, the skin cold and covered with a clammy perspiration. There had been slight vomiting. The child died in twelve hours, without recovering consciousness from the time at which she was first found. On inspection, there was congestion of the brain and its membranes: the heart and lungs were quite healthy. The mucous membrane of the stomach presented patches of intense redness, and in some places it was thickened and softened; portions of it were detached and hanging loosely in the stomach; and there were patches of black extravasated blood about it. It contained a greenish-coloured liquid, but there was no smell of brandy in it, neither was this perceptible in the breath of the child, four hours after the alcoholic liquid had been taken. At first it was suspected that arsenic had been administered, but the symptoms were not those of arsenical poisoning, and neither arsenic nor any other metallic irritant was present in the contents of the stomach, but traces of alcohol were detected by the process described below.

Analysis.—When a large dose has been taken and the case has proved rapidly fatal, the contents of the stomach may have the odour of alcohol, or of the alcoholic liquid taken. The odour is not always perceptible, or it may be concealed by other odours. In a case of poisoning by gin, the liquid drawn from the stomach by the pump after seven hours had no odour. In the case of the child above related, the smell of brandy had entirely disappeared in twelve hours. The whole of the contents or of the suspected liquid should be distilled in a water-bath, with a proper condensing apparatus attached. If the liquid has an acid reaction, it should be first neutralized by a solution of sodium carbonate. The watery liquid obtained should be mixed with fused calcium chloride or anhydrous copper sulphate in sufficient quantity, and submitted to a second distillation in a smaller retort, by a water-bath. The liquid resulting from the second distillation should be agitated with rather more dry potassium carbonate than

will dissolve, in a small tube provided with a stopper, and allowed to and. A stratum of alcohol, if present, will, after a time, float on the rface, and may be drawn off by a pipette and examined. *Tests.*—1. lcohol has a hot pungent taste, a peculiar odour, and is very volatile. 2. bsorbed in asbestos, it burns with a pale blue flame, which deposits no rbon on white porcelain; and when burnt in the mouth of an inverted t-tube, containing a few drops of baryta water, it produces a well-arked white deposit of barium carbonate. Lime water may be substituted r baryta water in this experiment. Carbonic acid and water are the le products of its combustion. 3. The liquid becomes green when boiled th a few drops of a solution of potassium bichromate mixed with sulphuric id. 4. The alcoholic liquid is made alkaline with a solution of potash soda, warmed, and a solution of iodine in potassium iodide is added til the liquid is brownish yellow; potash is again added till the liquid ain becomes colourless. Sooner or later iodoform separates as a yellow ly precipitate; which, when examined under the microscope, is seen to nsist of six-sided stars and rosettes.

The following method will allow of the detection of a quantity of ohol too small for separation by the process above mentioned. Make a ixture of strong sulphuric acid and a saturated solution of potassium chromate: moisten with this mixture a few fibres of asbestos, and close them in a glass tube connected with the retort or flask in which stillation is carried on. For this purpose a flask or tube similar to those ed for detection of chloroform vapour will be found serviceable (see fig. 50, 406). The smallest portion of alcohol-vapour passing over the asbestos, mediately renders it green, by converting the chromic acid into chromic loride. This may serve as a trial test or for evidence, according to cir-mstances. The tube may be removed, and the condensed vapour llected for the application of the other tests. Ether and methyl alcohol oduce a similar result.

From lapse of time, the effects of treatment, or absorption and elimina-n, there may be no trace of alcohol in the stomach or intestines, never-eless the person may have died from the effects. In one case, fatal in ght hours, no alcohol was found in the stomach (p. 400). One cause of lure may sometimes be traced to the distillation being restricted to a rtion of the contents. It is advisable to distil the *whole*, as, if necessary, e distillate or the residue can be examined for other poisons.

Ether.

Symptoms and Effects.—Ether, in moderate doses, has a hot burning ste, and produces during swallowing a sense of heat and constriction in e throat. It causes great excitement and exhilaration, followed by in-ication, but persons may become habituated to it, and thus after a time may be taken in very large quantities with comparative impunity. It uses intoxication more rapidly than alcohol, but this state is of shorter ration. The effects produced on the system, when a large dose has been ten, are not unlike those occasioned by alcohol. Orfila found that about lf an ounce of ether, administered to a dog, caused, in a few minutes, disposition to vomit. This was followed by giddiness, and in ten nutes by an entire loss of power in the muscles. The breathing was nful and hurried, but there were no convulsions. After a slight abate-nt in the symptoms, the dog fell into a state of insensibility, and died three hours. The whole of the mucous membrane of the stomach was a blackish-red colour, and with the other coats intensely inflamed. ere was a slight inflammation of the duodenum; but the rest of the mentary canal was in a healthy condition. The heart contained partially

coagulated black blood: the lungs were gorged with fluid blood. (Op. cit. ii. 531.) Ether as a liquid has not, so far as is known, destroyed life; but when its vapour has been breathed, it has caused death in several instances. (See 'On Poisons,' 2nd ed. p. 731.)

Analysis.—When ether has been taken as a liquid and has caused death, it may be separated from the contents of the stomach by the process described for alcohol. The chromic acid process (p. 400) applied to the vapour during distillation will detect a minute quantity; and by its peculiar odour ether may be easily distinguished from alcohol or pyroxylic spirit. 1. Ether is highly inflammable, and burns with a yellow smoky flame, producing carbonic acid and water. 2. When shaken with its bulk of water, only a small portion is dissolved, the rest floats on the surface. If taken in a liquid form, it may be separated from the contents of the stomach by distillation, and the product rectified by redistillation with dry potassium carbonate at a temperature of about 120° F.

Chloral Hydrate, or Hydrate of Chloral.

This is a solid crystalline substance, produced by the reaction of chlorine on alcoholic liquids, and the subsequent addition of a small quantity of water. It is much used as a substitute for opium, and in doses of twenty to thirty grains it has been found to operate as a sedative and narcotic without producing any stage of excitement. It has been given in very large doses, often with benefit, but at other times causing dangerous symptoms, followed by death. Medical men who have taken it incautiously have died from its effects. Several instances of this kind are reported in the 'Med. Times and Gaz.' (1871, 1, 367). The deaths have been frequently sudden, and no remarkable symptoms have preceded dissolution. The person has passed from sleep into death. In 1880 there were eleven deaths in England from chloral hydrate.

Symptoms and Appearances.—According to Liebreich, who introduced this compound, it produces in proper doses, after a short interval, a deep sleep, and, when carried far enough, complete loss of consciousness and sensibility. A lady took six doses of thirty grains each. She fell into a sound sleep. Every attempt failed to arouse her, and she slept into death. The principal post-mortem appearance was great congestion of the cerebral vessels. ('Med. Times and Gaz.' 1871, 1, 132.) In another case a lady took in three doses at intervals of four hours, seventy grains of the hydrate. In two hours after the last dose, she suffered from severe cramps in the legs, a feeling of suffocation, swimming in the head, and inability to regulate her movements. Four hours after the last dose her face was flushed, the eyelids were closed, and the conjunctivæ were injected; the pulse was quick (120) and bounding. She was with difficulty roused either to speak or take food. She recovered in about sixteen hours. ('Med. Times and Gaz.' 1870, 2, 435.)

A patient took thirty grains of chloral hydrate at night. He became unconscious almost immediately after swallowing the draught—the face and hands turned livid and cold, and breathing took place only at long intervals, indeed for about five hours death seemed to be impending. He recovered next day. ('Lancet,' 1870, II. p. 402.) A case is reported in the same journal in which a dose of 160 grains was given by mistake to an hospital patient, a middle-aged man. The man slept well and recovered notwithstanding the large dose taken. In two cases sudden death followed ordinary doses, and in one instance ninety grains introduced into the rectum produced rapidly insensibility, and caused death in three hours. ('Lancet,' *1871, II.* 466.) It has been observed, in reference to this drug, that in the

produced by it the pupil is contracted, but that it immediately dilates
ıe person awaking. In other cases the pupil has been dilated and
sible to light. There appears to be considerable uncertainty in the
ı of this drug, even when similar doses are given. After an ordinary
of twenty or thirty grains a patient has slept for a quarter of an
and has then awakened with a sense of deadly faintness, the lips
the face pale, the pulse scarcely perceptible, and a feeling of intense
ıstion and impending dissolution, mingled with delirium, lasting for
r ten minutes. It appears to exert a depressing action on the heart,
n cases of heart-disease it may thus cause sudden death ('Lancet,'
II. p. 32). A case proved suddenly fatal by causing paralysis of
eart ('Lancet,' 1871, I. pp. 227, 440, 473).
ases of accidental poisoning by overdoses of chloral are very common.
ese cases the fatal dose is rarely known. The usual symptoms are
und sleep, passing into coma. Breathing becomes gradually slower,
ı the end it entirely ceases. The pulse becomes rapid, irregular, and
. There is complete loss of sensation, with great muscular prostra-
and the temperature falls much below the normal. It is probable
death usually takes place from paralysis of the heart. The editor
with a case in which a young man barely survived a dose of 70 grains:
ıcame idiotic, and never entirely recovered.
'atal dose.—A child, a year old, died from the effects of three grains
il. Med. and Surg. Rep.' 1871). Thirty grains caused the death of
man, æt. 30 ('Lancet,' 1871, I. p. 226). A dose of thirty grains also
ıd fatal in thirty-five hours to a young lady, æt. 20; while in a case
ioned above a man recovered from a dose of 160 grains taken at once.
r states that one of his patients took 150 grains and another 180
ıs without injury. ('Lancet,' 1871, I. p. 403. See also Husemann's
resber.' 1872, p. 509.) Richardson states that the largest dose which
as known to be taken was 120 grains. It produced prolonged and
erous coma, but recovery followed. He looks upon this as a safe
for an adult, distributed over twenty-four hours in divided quantities.
n at once it is a maximum dose for an adult, dangerous, but not
sarily fatal. Beyond 120 grains the danger increases, and 180 grains
be considered a dose that would prove, in the majority of cases,
ively fatal. ('Med. Times and Gaz.' 1871, 1, p. 169.)
'he presence of chloroform has been doubtfully demonstrated in
blood of dogs to which chloral had been administered (Wiggers'
resber.' 1871, p. 566.)
'atal period.—A patient may die in a few minutes, but more commonly
ives for a few hours. Death has ensued so late as ten and even
y-five hours.
ıalysis.—Chloral hydrate is a white, brittle, crystalline solid, of a
liar odour and a pungent bitter taste. When heated on platinum it
s and is entirely volatilized without combustion. It is not inflammable.
ted in a close tube it melts, and does not rapidly solidify. It is
lled over in a liquid form, and after a time it sets into groups of
tals. It is soluble in water, which retains it on cooling. The solution
ıt acid, has no bleaching properties, and gives only a faint milkiness on
ng with a solution of silver nitrate. It is dissolved by strong sulphuric
nitric acids, without any change of colour. Potash added to the
tion converts it into chloroform, which escapes in copious effervescence,
into formic acid, which combines with the alkali. On boiling it with
sh the solution, if the hydrate is pure, acquires only a slight yellow
ur. When boiled with auric chloride or silver nitrate, and potash is
d, gold or silver is immediately precipitated. It decomposes a copper

salt like grape-sugar, but in the cold potash does not redissolve the precipitated cupric hydrate.

One hundred parts will yield eighty-two parts of chloroform. It is by this conversion that chloral hydrate may be detected in the contents of the stomach. The liquid should be rendered alkaline with potash, and the mixture heated in a flask by a water-bath. The vapour which escapes may be tested for chloroform by the process described at p. 406. Procter thus detected it in a case of suicidal poisoning.

The quantity of chloral hydrate present in a strong solution, *e.g.* a draught, may be approximately determined by placing a measured quantity of the solution in a graduated and stoppered burette, and shaking with a solution of soda. On allowing the mixture to stand, the chloroform formed by the decomposition of the chloral hydrate will form a dense layer at the bottom. Approximately, each minim of chloroform separated represents two grains of chloral hydrate. By adding a solution of soda of known strength to a definite volume of a solution of chloral, and when the chloral is decomposed, titrating the uncombined soda, the percentage of chloral in a dilute solution may be determined with considerable accuracy.

Chloroform.

Symptoms and Appearances.—This liquid, when taken in a large dose, appears to affect the system like alcohol: but as a *liquid* it cannot be regarded as an active poison. A man swallowed *four ounces* of chloroform. He was able to walk for a considerable distance after taking this dose, but he subsequently fell into a state of coma—the pupils were dilated, the breathing was stertorous, the skin cold, the pulse imperceptible, and there were general convulsions. He recovered in five days. ('Med. Gaz.' vol. 47, p. 675.) A man swallowed nearly two ounces of chloroform. He was seen ten or fifteen minutes afterwards; he had already vomited, and was found insensible with stertorous breathing, and a pulse of about 60. The stomach-pump was employed, and some spirits of ammonia were injected. The pulse became more feeble, the breathing slower, and the pupils were insensible to light. The surface was cold, and for a time he continued to get worse, the face becoming purple, while the pulse was intermittent and hardly discernible. Two hours and a half after taking the poison, however, a gradual improvement commenced, but sensibility did not return until four hours later. For several days he continued to suffer from great irritability of the stomach, and eventually he had an attack of jaundice. ('Amer. Jour. Med. Sc.' Oct. p. 367; 'Med. Times and Gaz.' Nov. 28, 1857, p. 558.) A man, æt. 42, swallowed two ounces of chloroform, and he died in about six hours afterwards. In this case the pupils were fully dilated, the breathing was stertorous, and the skin covered with cold perspiration. He rallied for a short time and then sank again, his lips becoming dark purple and his face livid. On inspection the lungs were found much engorged with blood, and there were some apoplectic effusions in these organs. The stomach was slightly inflamed in patches, and the mucous membrane was softened. It contained a dark fluid smelling strongly of chloroform ('Brit. Med. Jour.' May, 1866, and 'Amer. Jour. Med. Sc.' Oct. 1866, p. 571.) In some cases, alarming symptoms have been produced by much smaller doses, and one of these proved fatal. In March, 1857, a lady swallowed half an ounce of chloroform. In five minutes she was quite insensible, generally convulsed, the jaws clenched, the face slightly flushed, the pulse full and rather oppressed, and she foamed at the mouth. She vomited, and in twenty minutes the convulsions had left her; soon afterwards she had a relapse, and did not recover for twenty-four hours. ('Med.

imes and Gaz.' Dec. 12, 1857, p. 615.) The symptoms in this case appear have been mixed with those of hysteria and epilepsy. In another case lady also took half an ounce of chloroform. An emetic was given, and a few minutes a large quantity of liquid was thrown off the stomach. about an hour the patient became suddenly livid and then blanched in e face. The pulse was thready and scarcely perceptible—the breathing w, and after a time stertorous; the hands and face became purple, the es were deeply suffused and the pupils were dilated. There was mucous miting at intervals. The patient was quite insensible—the eyes were ed and the face flushed. She appeared to be dying, but under treatmt these symptoms passed away, and in about two hours sensibility turned and she recovered. ('Lancet,' 1870, I. p. 290.) In 1854, a boy, 4, swallowed a *drachm* of chloroform, and soon afterwards laid his head his mother's lap and lost all consciousness. Thursfield saw him about enty minutes afterwards. He was then insensible, cold, and pulseless. ustard plasters were applied to the legs; they acted well, but produced impression on the sensibility. His breathing varied; it was sometimes tural, at other times stertorous. He became warmer, his pulse full and gular; and he continued *three hours* in this state, when he died quite dmly, without a struggle. This is the smallest dose of liquid chloroform at has destroyed life.


Chloroform-vapour.—The vapour, when respired in a concentrated m, is speedily fatal to life. If it is diluted with a certain proportion of ir, it produces insensibility, with entire loss of muscular power in from ght to ten minutes, and the patient rapidly recovers after the vapour is thdrawn. Cases of death from the inhalation of the vapour for surgical rposes are numerous, and the symptoms and post-mortem appearances e well-marked. (See 'On Poisons,' 2nd edit. p. 738; 'Lancet,' 1859, pp. 400, 425; also 'Lancet,' 1870, II. pp. 454, 886.) In some instances ath has taken place within two minutes from the commencement of halation. In one of these only thirty drops had been taken in vapour, t the patient died in one minute, and in another, so small a quantity as fteen or twenty drops proved speedily fatal. ('Table of Fatal Cases' y Warren, U.S. p. 23.) Simpson suggested that in some of the alleged tal cases death may have been really due to other causes of sudden ath. ('Med. Times and Gaz.' 1870, 1, p. 224.)

Its fatal operation is sometimes suddenly manifested after the withrawal of the vapour. In one case, the heart suddenly ceased to beat ur minutes after the vapour had been withdrawn. The digital arteries hich had been divided in the operation suddenly ceased to bleed. The an was dead. The fatal effects are generally ascribed to idiosyncrasy, or the unforeseen condition of a fatty or flabby heart. In cases of alleged bbery and rape, it has been sometimes stated that the person assaulted as rendered suddenly insensible by chloroform: but chloroform-vapour es not produce immediate insensibility, unless it also produces asphyxia d death. The editor found that in more than two hundred cases of its dministration at Guy's Hospital, adults were not commonly rendered ensible until after the lapse of eight minutes, the dose being three d a half drachms given in half drachms. In 1863, a woman, æt. 40, ok ten drachms in thirty-three minutes, in half-drachm doses, and was ill conscious and able to talk. According to the report of a committee, e average amount of the vapour to act safely as an anæsthetic is 3½ per nt., the maximum being 4½ per cent. It should be only slowly and never ddenly increased. It should not be given after a long fast, and never in e sitting or erect posture. ('Edin. Month. Jour.' 1864, p. 187.) It also stated, as the result *of observation*, that from two to ten minutes

are required to induce insensiblity. The time, however, varies w temperament, and habits.

Analysis.—Chloroform is a heavy colourless liquid (sp. gr. 1·5), in its reaction, sinking in water, and only to a slight extent d in that liquid. It has a fragrant odour; it is dissolved by alc ether. A solution in alcohol, in the proportion of one part by to nineteen parts of rectified spirit, forms the *Spiritus Chlor* Chloric Ether is a similar, but stronger, solution. Chloroform i volatile, but its vapour is not inflammable and not readily com Nitric and sulphuric acids produce no change in it. It boils at and evolves a vapour which at a red heat yields chlorine an chloric acid. On this effect a process has been suggested for se it from the *blood and tissues*, when it has proved fatal in the vapour. The substance supposed to contain chloroform is pla flask, like that shown in the annexed illustration. The neck of is fitted with a cork perforated to admit a hard glass tube, right angles, and having a length of from twelve to fifteen inch flask is gradually plunged into water at about 160° F., and at time the middle portion of the tube is heated to full redness by only one of which is represented in the annexed engraving (fig. a red heat chloroform vapour is decomposed, and chlorine and hyd acid are among the products of i position. Litmus paper applie mouth of the tube is reddened paper moistened with potassium rendered blue, and silver nitra cipitated white. Two drops of pu form were thus readily detected persistent was the vapour in t vessel, that it was detected after and even three weeks. Two dr to a quantity of putrefied blood tected by a similar process afte night, the flask being closed, but t of the tube remaining exposed t practice, however, it will be fou difficult matter to detect it, ev we know it has been administe author examined by this process of a boy who had died from the chloroform-vapour, but without any trace of it. There was no odour in the blood, and the r negative. The blood of three persons was taken while they were full operation of chloroform, and collected in closely-stopped gla One of the samples, examined within half an hour after rem the living body, had no odour of chloroform, and gave no ind its presence. The two other samples, kept in close bottles un forty-eight hours after removal, did not yield a trace of ch vapour.

Fig. 50.



Apparatus for the detection of the vapour of Chloroform.

As chloroform is much more volatile than ether, and its od so pungent, it is not so easily detected in the dead body by the sm body should be inspected as soon as possible, and any solids intended for examination should be kept in well-closed glass ve the smell can still be perceived in the blood or organs, the vapou *easily* detected by the method above described. Chloroform *eliminated* or lost by its volatility, may have been converte

blood into formic acid, and thus removed from the ordinary processes of chemistry.

The editor of this work has found no difficulty in detecting chloroform in the blood of a person killed by its inhalation, even when the body was not examined till twenty-four hours after death. The flask (fig. 50) is fitted with a second tube, open at one end to the air, whilst the other end passes beneath the liquid to the bottom of the flask. This serves as an inlet for air. The exit tube is heated through a length of at least eight inches by a series of lamps; and its further end is attached to a set of Liebig's bulbs, filled with a strong solution of silver nitrate. Air is aspirated through the apparatus during the course of the experiment; and the presence of the lightest trace of chloroform or other volatile compound of chlorine is immediately revealed by the formation of a white cloud of silver chloride in the solution of silver nitrate.

Bichloride of Methylene.

The vapour of this highly volatile liquid has been used as a substitute for the vapour of chloroform in surgical operations. It was thought to be less likely to cause death. Like all anæsthetic vapours, it has however destroyed life on several occasions, even when given with care. The history of these fatal cases is similar to that which chloroform vapour has furnished on numerous occasions.

Symptoms and Appearances.—An operation for artificial pupil was about to be performed on a man, æt. 40. The vapour of the bichloride was given, and five minutes afterwards, when the operation had just commenced, the face of the man became livid, the breathing difficult, and the heart suddenly ceased to beat. On inspection the principal appearance was congestion of the lungs. In another case, a man inhaled, for the purpose of a trivial operation, a drachm and a half of the bichloride. It was given in the usual way by an experienced person, and was stated to be not more than one-half of the usual dose. The deceased became insensible—the operation was completed in a minute—when it was noticed that the patient's head had fallen on one side, his eyes were upturned and breathing and pulsation had ceased. Animation could not be restored. On inspection all the organs of the body were found healthy. There was no cause for death but the vapour of the bichloride ('Pharm. Jour.' 1871, p. 875). This preparation has been sometimes used in hospitals under the name of chloroform. In 1869, a man to whom the vapour was administered at Charing Cross Hospital, died in two minutes from the effects—although administered with care, and by one experienced in the use of chloroform. The allegation, therefore, that this vapour possesses any greater degree of safety than chloroform in surgical practice is not supported by facts.

Analysis.—This liquid has a peculiar odour resembling that of chloroform. It is not inflammable, but burns in contact with flame with a smoky combustion. It is not very soluble in water, but sinks in it, the globules having an opaque appearance. It has no acid reaction. Silver nitrate gives no precipitate with it. In contact with sodium and a small quantity of water, it is rapidly decomposed without combustion; the liquid acquires a yellowish colour, and chlorine is then readily detected in it by silver nitrate.

A mixture of chloroform and ether has been sold as bichloride of methylene.

Iodoform.

This substance, which has been recently introduced, in the form of yellowish crystals or powder, into antiseptic surgery, is without doubt a

poison. Schede, Kocher, and others have published cases where severe and even fatal symptoms have followed its external application. Boyd has still more recently reported four cases where toxic symptoms were developed after its use as a surgical dressing. These symptoms were, in two cases, drowsiness and stupor; in one, those of meningitis; and delirium in a fourth case, which terminated fatally. ('Brit. Med. Jour.' 1882, I. pp. 903, 913).

Symptoms and Appearances.—The symptoms usually observed after poisonous doses are—faintness, headache, giddiness, confusion of ideas, burning pain in the stomach, delirium, convulsions, insensibility, general paralysis, a small pulse, sometimes quickened and sometimes slowed, and the skin cold, livid, and bathed in perspiration.

CHAPTER 29.

CAMPHOR—TOBACCO—NICOTINE—COCCULUS INDICUS—PICROTOXIN—DARNEL—CALABAR BEAN—FUNGI—HENBANE—SOLANUM—DEADLY NIGHTSHADE, OR ATROPA—BELLADONNA—ATROPINE—DATURA STRAMONIUM, OR THORNAPPLE.

Camphor.

There are a few instances recorded in which camphor has proved fatal in the human subject; but it has on several occasions produced alarming symptoms, and would probably have destroyed life, had it not been early removed from the stomach. In the cases that have been observed, its effects were varied, but as a rule were tolerably uniform.

A woman swallowed about *twenty grains* of camphor dissolved in rectified spirits of wine mixed with tincture of myrrh. In half an hour she was suddenly seized with languor, giddiness, partial loss of sight, delirium, numbness, and tingling and coldness of the extremities, so that she could hardly walk. The pulse was quick and respiration difficult, but she suffered no pain in any part. On the administration of an emetic, she vomited a yellowish liquid smelling strongly of camphor. In the evening the symptoms were much diminished, but she had slight convulsive fits during the night. The next day she was convalescent; the difficulty of breathing, however, continued more or less for several weeks. This is the smallest dose of camphor which appears to have been attended with serious symptoms in an adult. An infant of fifteen months died from the effects of some camphorated oil given to it by mistake. Convulsions ensued, and death took place in thirteen hours. Three cases of poisoning by camphor are reported by Schaaf, one of which proved fatal. A woman gave about thirty grains (half a teaspoonful) of powdered camphor to each of her three children as a vermifuge. Two of the children were respectively of the ages of three and five years; the third was an infant aged eighteen months. The first symptoms were paleness of the face with a fixed and stupid look. Delirium followed with a sense of burning in the throat, great thirst, vomiting, purging, and convulsions; and in one child the convulsions were most violent. The two elder children, after suffering thus for three hours, fell into a comatose sleep, and on awaking the symptoms passed off. The infant died in seven hours, not having manifested any return of consciousness from the first occurrence of convulsions. ('Jour. de Chim. Méd.' 1850, p. 507.) The severity of the symptoms is fully explained by the large quantity administered and the age of the children. In a dose of one drachm given in a clyster, camphor produced alarming

ı. ('Med. Gaz.' vol. 48, p. 552.) In one case ('Med. Gaz.' vol. 2), 120 grains were taken by a physician, and all that he ex- was lightness in the head with great exhilaration. There was ement of the stomach or bowels. He slept profoundly for some d awoke very weak and exhausted. He also perspired greatly s sleep. It is difficult to draw any conclusion from this case, as tity taken was conjectural, and the patient was not seen by any hile labouring under the effects of the poison. A soldier took a ntity of camphor daily. For three days it had no effect. On the ıe suffered from great pain and a burning sensation in the stomach. was painful: there was giddiness, with an incessant desire to ut, although, like a drunken man, he could hardly keep on his ı soon fell completely insensible—his limbs were cold, his face was body convulsed, and the pupils were dilated. These symptoms owed by an irresistible desire to sleep. In two or three days he . ('Med. Times and Gaz.' Dec. 1858, p. 645.)

32, a man was admitted into Guy's Hospital, after having swallowed e fluid ounces of soap liniment. This quantity would contain ıs of camphor. His skin was cold and clammy. The pupils ted, and did not respond to light. He was quite unconscious, and nctiva of the eye was insensitive to touch; the jaws were tightly limbs were relaxed, but became rigid when handled. Pulse 120. rations were stertorous, and 20 per minute. An emetic had been lly administered to the patient before his admission. The stomach- s then applied with difficulty, in consequence of the rigidity of and only a small quantity of mucus and a few scraps of food gnized in the fluid removed. The temperature was 2° F. below al. A subsequent attempt to administer castor oil failed, as he ıle to swallow. Five hours after his admission consciousness He vomited, had very little muscular power, and fell on attempt- ave his bed. Ten hours after admission the skin was hot and pupils were still dilated, pulse 108; respirations very rapid (38), gh conscious he was drowsy. The tongue was dry, brown, and s. Muscular rigidity had disappeared. He now made rapid

ı of poisoning by camphor would be recognized by the odour of the symptom which would attract the attention of a non-professional The presence of this substance in the stomach would be at once by its odour.

Tobacco.

toms.—The effects which this substance produces, when taken in ose, either in the form of powder or infusion, are well-marked. ıtoms are faintness, nausea, vomiting, giddiness, delirium, loss of the limbs, general relaxation of the muscular system, trembling, prostration of strength, coldness of the surface, with cold clammy ion, convulsive movements, paralysis, and death. In some cases purging, with violent pain in the abdomen; in others there is ense of sinking or depression in the region of the heart passing ope, or creating a feeling of impending dissolution. With the ntioned symptoms there is dilatation of the pupils, dimness of nfusion of ideas, a small, weak, and scarcely perceptible pulse, ılty of breathing. A woman applied some leaves of tobacco to on her legs. After some hours she suffered from sickness, dim- ision, and cramps in the legs, with great prostration; she also ed of a numb feeling. On the third day there was great sleepiness,

other remedies.

Poisoning by tobacco has not often given rise to medico-l
sion. This is the more remarkable, as it is an easily accessibl
and the possession of it would not, as in the case of other poi
surprise or suspicion. In 1854, a man was charged with the
infant, æt. 10 weeks, by poisoning it with tobacco. He placed
of tobacco in the mouth of the infant with the view, as h
making it sleep. The infant was completely narcotized, and
second day. It is probably more extensively used to aid the
robbers than is commonly believed; and there is reason to s
porter and other liquids sold in brothels are sometimes dru
with tobacco or with snuff prepared from it. Scotch snuff is
used for this purpose. Tobacco and snuff owe their poisonou
to the presence of a liquid volatile alkaloid, *Nicotine*.

NICOTINE.—This is a deadly poison, and like prussic acid
life in small doses with great rapidity. A rabbit was killed
drop in three minutes and a half. In fifteen seconds the an
power of standing, was violently convulsed in its fore and hir
its back was arched convulsively (opisthotonos). A frothy alk
escaped from its mouth, having the odour of nicotine. ('Guy's
1858, p. 355.) A case of poisoning by this alkaloid which
Belgium in 1851, was the subject of a trial for murder. ('A
1851, 2, pp. 167, 147). The *Count* and *Countess Bocarmé* w
with the murder of the Countess's brother, a *M. Fougnies*, by
ing to him nicotine while he was dining with them at the
Bitremont. The poison was forcibly administered. The decea
survive more than five minutes, and was not seen living by
attendants. The possession of the poison, as well as the mor
fixed the crime on the Count, and he was condemned and exe
appearances after death were to a great extent altered or destr
pouring of some strong acid (acetic) into the mouth and over

cotine resembles prussic acid in its rapidity of action. The quantity of cotine taken could not be determined. The deceased appears to have en rendered insensible immediately, and to have died in from three to e minutes after having taken the poison. The *appearances* observed re a general relaxation of the muscles, prominent and staring eyes, ated features, great fulness with lividity about the neck. There was odour resembling nicotine or tobacco perceptible about the body. When amined between two and three days after death, putrefaction had curred, especially in the course of the veins. The swelling of the neck as found to arise from an effusion of dark liquid blood. The scalp and e membranes of the brain were filled with dark-coloured blood. The ngs were engorged, and of a dark purple colour. The cavities of the art were empty, with the exception of the left auricle, which contained o drachms of dark-coloured blood. The stomach contained a chocolate-loured fluid: the mucous membrane was of a dark crimson red colour om the most intense congestion. There was no odour excepting that of trefaction. The liver was congested and of a purple black colour. The lood throughout the body was black and liquid, but in some parts it had e consistency of treacle. The author found nicotine in small quantity the contents of the stomach, also in the liver and lungs; but as these rgans had been placed in contact with the stomach, it could not be in-rred that the poison had been absorbed and deposited in them.

Analysis—Nicotine is a colourless liquid, becoming brown on exposure air, and evolving a peculiar acrid odour, affecting the nose and eyes, hich when diluted resembles that of stale tobacco-smoke. It has the con-istency of a thin oil, and gives a greasy stain to paper which soon dis-ppears, owing to its volatility. When heated it burns with a bright llow flame, emitting a thick black smoke. It is powerfully alkaline, and mparts a strongly alkaline reaction to water, in which it dissolves. The queous solution, even when much diluted, retains the peculiar odour. icotine is dissolved by alcohol and ether, and the latter liquid will remove from its aqueous solution. 1. Platinic chloride produces in the aqueous olution an orange-yellow crystalline precipitate. 2. Corrosive sublimate ives a white precipitate. 3. Arsenio-nitrate of silver gives a yellow recipitate. In all these characters nicotine resembles ammonia: the ifferences, apart from the odour, which is an important distinction, are —4. Iodine water gives a brown precipitate (in ammonia there is no pre-ipitate, the colour is discharged). 5. Tannic acid gives a whitish-yellow recipitate (in ammonia there is no precipitate, but a red colour is im-arted). 6. Chloride of potassium and mercury precipitates it copiously, ven when much diluted. 7. Gallic acid gives no precipitate (in ammonia produces a pinkish-red colour, rapidly changing to an olive green). 8. Sulphuric acid and potassium bichromate produce a green colour. (See 'Guy's Hosp. Rep.' 1858, p. 354.)

Organic mixtures.—To separate nicotine from the contents of the tomach, these should be digested in cold distilled water acidulated with artaric acid. This liquid is strained, filtered, and the residue pressed. It is then to be evaporated at a gentle heat, and the residue digested with lcohol, filtered, and the alcoholic liquid evaporated. The alkaloid is now issolved out of the residue by a small quantity of water, and the solution is rendered alkaline by potash and then shaken in a tube with its bulk of ther; the ethereal liquid is allowed to evaporate in a series of watch-lasses, and if nicotine be present the alkaloid will be left in small oily-ooking globules. The odour may not be perceptible until the residue is eated, when its peculiar acridity will be brought out. A few drops f water should be added *to the residue* in each glass—it will be found

to be strongly alkaline, and the different tests may then be a
It was by this process that the author discovered the poison in th
of the gentleman whose case is above related. In reference to the
killed by a single drop (p. 410), nicotine was found in the stomach
contents: there was a trace found in half an ounce of the blood
animal, and the poison was clearly detected after a week in the
and soft parts of the throat of the animal, but there was no t
nicotine in the liver, heart, or lungs.

Levant Nut (Cocculus Indicus).

Symptoms and Effects.—This is the fruit or berry of the A
Cocculus (*Levant Nut*), imported from the East Indies. The be
tains from one to two per cent. of a poisonous principle (*Picrotoxia*
shell or husk contains no picrotoxin, but a non-poisonous principl
menispermin. The seeds, in powder or decoction, give rise to
vomiting, and griping pains, followed by stupor and intoxication.
are only two well-authenticated instances of this substance having
fatal to man. Several men suffered from this poison in 182

Fig. 51.



a. Berry of Cocculus Indicus, natural size.
b. The same, seen in section with one-half of the semi-lunar kernel.
c. The kernel, containing picrotoxin.

Liverpool: each had a glass
strongly impregnated with cocc
dicus. One died that evening;
recovered. ('Traill's Outlines.')
second case, the following detai
been published. A boy, æt. 12,
suaded by his companions to swall
grains of a composition, used for
ing fish. It contained cocculus
In a few minutes he perceived
pleasant taste, with burning pain
gullet and stomach, not relieved by frequent vomiting, and pain ex
over the whole of the abdomen. In spite of treatment, a violent a
gastro-enteritis supervened, and there was much febrile excitem
lowed by delirium and purging, under which the patient sank
nineteenth day after taking the poison. On inspection, the vessel
pia mater were congested with dark-coloured liquid blood. Th
serous effusion in the ventricles of the brain, and the right lung
gested. In the abdomen there were all the marks of peritoniti
advanced stage. The stomach was discoloured, and its coats were
and softer than natural. (Canstatt's 'Jahresbericht,' 1844, 5, 298.


Porter, ale, and beer owe their intoxicating properties in some ir
to a decoction or extract of these berries. The fraud is perpetrat
low class of publicans. They reduce the strength of the beer b
and salt, and then give to it an intoxicating property by means
poisonous extract. A medical man consulted the author some yea
in reference to the similarity of cerebral symptoms suffered by se
his patients in a district in London. It was ascertained that th
supplied with porter by retail from the same house. The effects p
by this drug are remarkable: there is a strong disposition to sleep,
the same time wakefulness. There is a heavy lethargic stupor,
consciousness of passing events, but a complete loss of voluntary
It is a kind of nightmare feeling, altogether different from health
Cocculus indicus is sometimes used by robbers to intoxicate their
and to this form of intoxication the term 'hocussing' is applied
method of detecting this poison in alcoholic liquids consists in di
over the alcohol and then testing the extract by physiological or ch
processes. The extract containing cocculus indicus is intensely bitt

duces in an animal peculiar symptoms. One-twentieth of a grain oxin kills rabbits with peculiar opisthotonic convulsions. Fishes mersed in water containing this substance make strange sinuous nts, and fall powerless on the side. ('Brit. Med. Jour.' March 27, 875). Röber found that frogs are affected with tonic and clonic ons, and a peculiar inspiratory tetanus, which causes an inflated the abdomen. He thinks that this special condition is characteristic lministration of picrotoxin to these animals. For some remarks on teration of beer and other liquids, and a process for separating the s principle, picrotoxin, by amylic alcohol, see 'Chem. News,' 2, 1864, p. 123.

ılus indicus has been frequently used for the malicious destruction ıd game. In one instance referred to the author, there was reason e that 270 young pheasants had been poisoned by grain soaked ction of this substance. *Barber's poisoned wheat* for the destruc- irds owes its poisonous properties to cocculus indicus. (Horsley.)

TOXIN.—The poisonous principle of the berry of cocculus indicus es in slender hexahedral prisms, having a silky lustre. It is in 150 parts of cold water, but is uble in boiling water, and the solu- a very bitter taste. When heated e, picrotoxin, like digitalin, evolves vapour. Hydrochloric acid dissolves ıt change of colour. It is soluble in ether, chloroform, and in amylic Sulphuric acid imparts to it an ellow colour, which becomes of a low by dilution. When potassium ate is added to the sulphuric acid a green colour is produced. Strong id dissolves it without any change of Tannic acid and the chloriodide of m and mercury do not precipitate it solutions. When boiled with a solution of potash and copper , it reduces the solution like grape-sugar.

Fig. 52.



Crystals of Picrotoxin, magnified 124 diameters.

ley has shown that picrotoxin may be separated from many oisonous alkaloids by taking advantage of its peculiar chemical es. It does not combine with acids to form salts, but readily es. Thus water containing a small quantity of potash will dissolve ı or one-eighth part of its weight of picrotoxin. Water thus l will, it is well known, readily yield most of the alkaloids to ether, is liquid is shaken with the solution; but if the liquid is strongly ed, most of the alkaloids remain combined with the acid, while r shaken with the liquid entirely removes the picrotoxin. Thus, ining beer supposed to be adulterated with cocculus indicus, the ıould be acidulated with hydrochloric acid, and then shaken with ımes of ether. The ethereal solution thus obtained, when spon- y evaporated, leaves the picrotoxin in crystals. Langley states this process he has detected so small a quantity as 1–750th of a picrotoxin in a pint of ale. The stomach of a cat which had been l was treated with alcohol, and the solution evaporated to dryness. ed water was poured on the residue, and the picrotoxin with some matter was dissolved. The acid liquid was shaken with ether, and of picrotoxin were obtained by the evaporation of the ethereal ('Pharm. Jour.' Dec. 1862, p. 277.)

Bearded Darnel (Lolium Temulentum).

Symptoms and Effects.—Poisoning by darnel is generally the result of accident from the intermixture of the seeds of this grass with wheat or rye. The seeds are ground into flour and eaten with the bread.

In January, 1854, Dr. Kingsley, of Roscrea, furnished the author with the particulars of some cases in which several families (including about thirty persons) suffered severely from the effects of bread containing, by accidental admixture, the flour of darnel seeds. The persons who partook of this bread staggered about as if intoxicated: there was giddiness, with violent tremblings of the arms and legs, similar to those observed in delirium tremens, but of much greater intensity (the patients requesting those about them to hold them, and experiencing great comfort from this assistance being given to them); greatly impaired vision, every object appearing of a green colour to the sufferer; coldness of the skin, particularly of the hands and feet; great prostration of strength, and in several cases vomiting. Under the free use of stimulants and castor-oil the whole of the patients were convalescent on the following day, but much debilitated from the effects of the poison. Among the symptoms in other cases there has been noticed a sense of burning heat in the mouth and throat, with confusion in the head, trembling, and a small irregular pulse. (See 'Edinb. Month. Jour.' Aug. 1850, p. 180.)

Fig. 53.




Lolium Temulentum, or Bearded Darnel.

Analysis.—The plant is known by its botanical characters. Pfaff examined darnel, in order to discover a poisonous alkaloid; but there was no trace of such a substance. By distillation with water he obtained two kinds of ethereal oil, one lighter and the other heavier than water; they were colourless and had the odour of fusel-oil.

Ordeal or Calabar Bean (Physostigma Venenosum).

The Calabar bean is a large leguminous seed of a dark colour, resembling a garden bean, but much thicker and more rounded in its form. It is brought from the western coast of Africa, and is there employed by the natives as an ordeal bean when persons are suspected of witchcraft. The common belief is, that the innocent vomit and are safe, while the guilty retain the poison and die from its effects. So strong is popular confidence in this test, that those who are suspected voluntarily take an emulsion of this seed, and, as Christison remarks, many an innocent person thus pays the penalty of his rash reliance on this superstitious custom. It is a firm matter of faith that if a man dies he is guilty. Illustrations of this bean of its natural size are subjoined.

Fig. 54.



a. The bean of its natural size.
b. The same seen edgewise.

This bean owes its properties to the presence of an alkaloidal substance called *Physostigmine* or *Eserine*. It is found in the cotyledon, and the process adopted for its separation by Jobst and Hesse is described in the 'Chem. News,' March 5, 1864, p. 109.

The seed or bean has a thin, hard, dark-coloured, brittle covering: the kernel inside is white, and weighs from thirty-six to fifty grains; the whole seed about sixty-seven grains. Christison found that the active

nciple could be extracted by alcohol, which dissolves 2·7 per cent. of the d, including this substance. That alcohol will remove the poisonous nciple is proved by the fact that the exhausted residue is not always sonous. (Bouchardat, 'Ann. de Thérap.' 1864, p. 73. See also 'Pharm. r.' 1863, p. 561.) The greater part of the seed, as in nux vomica, sists of starchy and other inert matters, with a small quantity of oil. e kernel is yellowish-white, without bitterness, acrimony, aroma, or any er impression on the organ of taste. In fact it cannot be distinguished taste from a haricot-bean. The poison, according to Christison, pro-es a primary impression on the heart, causing paralysis of that organ, insensibility and coma being only apparent. The results appear to w that there is also paralysis of the voluntary and respiratory muscles, a retention of consciousness. ('Pharm. Jour.' 1855, p. 473.)

Desiring to try the effects of this seed on himself, Christison took the hth part of a seed, or six grains, one night before going to bed. There s a slight sense of numbness in the limbs during the night, but in the rning no urgent symptoms of any kind. He then chewed and swallowed fourth part of a seed (twelve grains). In twenty minutes he was ed with giddiness, and a general feeling of torpor over the whole frame. immediately swallowed an emetic, and thus emptied his stomach. The diness, weakness, and faintness increased to such a degree that he was iged to lie down in bed. In this state he was seen by two medical nds, who found him prostrate and pale, the heart and pulse extremely ble and tumultuously irregular, the mental faculties intact, extreme ntness threatening dissolution, but no apprehension of death on the part the patient. There was no uneasy feeling of any kind, no pains or mbness, no prickling, not even any sense of suffering from the great bleness of the heart's action. There was the will but not the power to mit; the limbs became chill with a vague feeling of discomfort. Stimu-nts were employed, and warmth and pulsation, with a power of moving, dually returned. Two hours after the poison had been taken he felt rwsy, and slept for two hours more, but with such activity of mind that had no consciousness of having been asleep. The tumultuous action of e heart continued. After this the symptoms gradually disappeared, and e next day he was quite well. ('Pharm. Jour.' 1855, p. 474.)

In 1864, fifty children were poisoned at Liverpool by reason of their having en these beans. The sweepings of a ship from the west coast of Africa d been thrown on a heap of rubbish; the children found the beans and e them. A boy, æt. 6, who ate six beans, died in a very short time. e principal symptoms were severe griping pains, constant vomiting, and ntracted pupils. In addition to these symptoms the face was pale, and e eyes were bright and protruding. In attempting to walk the children ggered about as if they were drunk. In 1864, two children, aged 6 and years respectively, chewed and ate the broken fragments of the kernel of e nut. In about forty minutes they complained of sickness. One child ld his head drooping, appeared sleepy, and his hands were powerless. e staggered and was scarcely able to walk. He complained of severe pain the stomach, and made ineffectual attempts to vomit. Milk was given, d he then vomited. The child became quite prostrated, the pulse was eble and slow, and the pupils were slightly contracted. Some pieces of e nut were thrown up by vomiting. The other child had pain in the bdomen, and was listless, sleepy, and depressed. He vomited freely, some rtions of nut being ejected. He could neither stand nor walk. His face as pale, the eyes were piercing, but the pupils and pulse were natural. n this case there was purging. The children recovered on the third day. 'Edin. Month. Jour.' 1864, p. 193.) In cases in which it has proved

fatal to animals it has caused much irritation and congestion of the stomach and bowels. (Dragendorff.)

Fraser relates the case of two maid-servants who were poisoned by tasting some of the embryos of the bean through curiosity. ('Edin. Med. Jour.' 1863, 2, p. 131.)

African travellers have described the symptoms resulting from the use of the beans as an ordeal, as consisting of violent thirst, inability to swallow, cramps and muscular twitchings. If vomiting takes place, as it often does early when a large dose is given, recovery ensues rapidly; otherwise consciousness remains till shortly before death, which occurs usually within half an hour.

A drop of the extract applied to the eye produces in from ten minutes to a quarter of an hour a remarkable contraction of the pupil. This has been observed to last in children for fifteen or twenty hours. In this respect, the poison is eminently distinguished from natural mydriatic alkaloids atropine, and the two hyoscyamine, which cause great dilatation of the pupil. It causes contraction of the pupil when taken internally, as well as when applied locally. It paralyzes the motor nerves, and leaves the intellect and muscular irritability unimpaired. It destroys life by paralyzing the respiratory muscles, and although it weakens the heart's power, it neither stops the circulation nor arrests the heart's action. It is not, according to Harley, a cardiac, but a respiratory poison. It is closely allied in its effects to curare and conia, but more to the latter. It differs from both in its tendency to produce muscular twitchings, and in its power of causing contraction of the pupil. Neither curare nor conia has any effect on the iris. ('Lancet,' 1863, I. 717.) Salts of the alkaloid (eserine), as well as an extract of Calabar bean, are now extensively used in the treatment of diseases of the eye; and hence accidents are likely to occur from the use of these preparations.

Von Boeck concludes that the special character of poisoning by Calabar bean consists mainly in a diminution of the excitability, complete paralysis of the locomotor centres situated in the spinal marrow, and paralysis of the excito-motor centres of the heart and their peripheral extremities; also in producing contraction of the vessels and of the unstriped muscles, especially those of the intestine and the sphincter muscles of the iris, as well as in promoting salivary and other secretions.

The editor has himself observed a very marked diminution of respiratory depth from the hypodermic use of salts of eserine (physostigmine).

Analysis.—Physostigmine (eserine) combines with acids to form salts. A solution of bromine in water acts in a characteristic manner on a solution of the sulphate, even when diluted to 1–10,000th part. It produces a red colour when less than 1–1000th of a grain is present. The chloriodide of potassium and mercury also precipitates physostigmine. The physiological test consists in the application of a solution or alcoholic extract to the eye. It produces strong contraction of the pupil when this liquid contains but a minute proportion of physiostigmine. It is rapidly eliminated by the saliva and other secretions. (Husemann's 'Jahresber.' 1872, p. 570.)

Poisonous Mushrooms (Fungi).

No branch of toxicology has given rise to greater differences of opinion than the study of poisoning by fungi. Some authors have considered nearly every kind of mushroom as unfit for food; whilst others, again, seem to regard nearly every species as edible with safety. In inquiring into the causes of these discrepancies of opinion, it will be found that whilst some species of fungi are undoubtedly to be regarded as poisonous,

since they contain an integral poisonous constituent or constituents which may be isolated in a greater or less state of purity, others produce injurious effects only under certain conditions, such as idiosyncracy of the individual, decomposition of the fungus, &c. Mushrooms contain a large quantity of water, and are very rich in albuminous constituents, and are hence prone to decomposition. They are also indigestible, and apt to produce catarrh of the stomach and intestines. In one or other of these various ways, the anomalies exhibited after the eating of mushrooms may be accounted for. The morel and *Hevella esculenta* are highly esteemed kinds of mushrooms, and yet Keber relates the history of six persons, who after partaking of these fungi were attacked with vomiting and diarrhœa which lasted for sixty hours. ('Preussische Vereinszeitung,' 1846, No. 32.) Poisonings by the common edible mushroom (*Agaricus campestris*) are rare, except when the mushrooms are decayed.

Symptoms and Appearances.—The noxious species of mushrooms act sometimes as narcotics, and on other occasions as irritants. It would appear, from the reports of several cases, that when the narcotic symptoms are excited, they come on soon after the meal at which the mushrooms have been eaten, and that they are chiefly manifested by giddiness, dimness of sight, and debility. The person appears as if intoxicated, and there are singular illusions of sense. Spasms and convulsions have been occasionally witnessed among the symptoms when the case has proved fatal. Peddie has related three instances of poisoning by mushrooms ('Edin. Med. and Surg. Jour.' vol. 49, p. 200), in which the poison acted as a pure narcotic; there was neither pain in the abdomen, nor irritation in the alimentary canal. The narcotic symptoms began in half an hour with giddiness and stupor: the first effect with one patient was, that every object appeared to him to be of a blue colour. The three patients recovered—two of them rapidly. When the drowsiness passes off, there is generally nausea and vomiting; but sometimes vomiting and purging precede the stupor. If the symptoms do not occur until many hours after the meal, they partake more of the characters of irritation; indicated by pain and swelling of the abdomen, vomiting, and purging. In a case of poisoning by mushrooms, there was slight vomiting about an hour and a half after the meal; but no violent symptoms until after the lapse of ten hours. Several cases, in which the symptoms did not appear until after the lapse of fourteen hours, are reported (Med. Gaz.' vol. 25, p. 110). In some instances the symptoms of poisoning have not commenced until thirty hours after the meal; and in these narcotism has followed the symptoms of irritation. It might be supposed that these variable effects were due to different properties in the mushrooms; but the same fungi have acted on members of the same family, in one case like irritants, and in another like narcotics. In most cases recovery takes place, especially if there is early vomiting. In the few instances which have proved fatal, there has been greater or less inflammation of the stomach and bowels, with congestion of the vessels of the brain. ('Méd. Gaz.' vol. 46, p. 307; vol. 47, p. 673; 'Jour. de Chim. Méd.' 1853, p. 694.)

A fatal case of poisoning by fungi was attended with symptoms of irritation resembling those caused by arsenic. There was no loss of consciousness or sensibility. A boy, æt. 13, fried and ate for breakfast at 8.30 A.M. two fungi which he had found growing under a tree. He returned to his work without complaint. At noon he had his dinner of pork and vegetables. At 1 P.M. he returned to work, where he remained until 6 P.M., working the whole time without any complaint. Soon after he reached home, he complained of feeling ill, and vomited violently. Purging then followed, with severe spasmodic pain in the abdomen. These symptoms continued throughout the *night* until 6 A.M. The bowels then ceased to

act. At 11.30 A.M. he was suffering from constant pain in the bowels, occasionally aggravated: there was tenderness over the abdomen generally, but especially over the course of the transverse colon, with vomiting every ten minutes—great thirst, skin warm and perspiring, pulse 90, and great depression. At 3 A.M. on this the second day he was again seen. Vomiting and purging had returned. There was great exhaustion; pulse imperceptible; the action of the heart feeble. He was lying in bed on his back, with the knees drawn up. Sensibility and consciousness were perfect. He complained of great pain in the stomach; there was tenderness over the abdomen, but no swelling of the cavity. In another hour he died, *i.e.* about forty-four hours after eating the fungi, and about thirty-four after the first setting-in of the symptoms. Others partook of the fungi, but in small quantity, and they did not suffer. On inspection, the heart on the right side contained a little fluid blood. The left ventricle was contracted and empty. The lungs were healthy, and there was only cadaveric congestion. The lining membrane of the stomach and small intestines was throughout injected, the blueish-red appearance diminishing in intensity as it approached the cæcum. There were a few ecchymosed patches near the intestinal end of the stomach. The organ contained six ounces of a brownish liquid resembling thin gruel. The large intestines were empty and pale, and the spleen was congested; the other organs were healthy. ('Med. Times and Gaz.' 1863, 2, p. 536.) In many of its features, and in the absence of narcotic symptoms, this case resembled a case of acute poisoning by arsenic. The fact that nearly ten hours elapsed before the symptoms of irritation commenced, and that there was no blood in the matters discharged by vomiting and purging, were the most marked differences.

In 1871, two children died from the effects produced by noxious fungi. Several other persons were placed in a precarious condition from the same cause. Some fowls died from eating portions of the mushrooms. Cases of poisoning by fungi are reported in Husemann's 'Jahresbericht,' 1872, p. 534. Two children, a boy, æt. 8, and a girl, æt. 10, cooked some mushrooms for breakfast. The boy ate greedily of them, but permitted the girl to take only one mushroom. The symptoms produced in both children were similar, except that the boy had them in a severer and fatal form, and the girl recovered. Three or four hours after the meal, the girl was seized with violent pains in the head and abdomen. She vomited several times in the course of the day, was restless, thirsty, and had occasional muscular twitchings of the hands. During the night the symptoms increased in severity, and she slept but little. Next day there was slight diarrhœa. When admitted into hospital fifty-four hours after the mushrooms were eaten, all the symptoms had nearly subsided. The boy was then collapsed, and died twenty minutes afterwards. His stomach was found empty and contracted; its mucous coat pink, with minute injection, and covered with a thick layer of dryish epithelium. The whole of the small intestines were empty and contracted; the coats thick and firm; and the mucous membrane intensely congested, more especially towards the lower part of the ileum, and covered with a thick layer of yellowish epithelium. The liver was fatty. ('Guy's Hosp. Rep.' 1872, p. 228.) A man, æt. 43, and his daughter, æt. 5, suffered severely from eating the *Amanita panthernia*. The earliest symptoms appeared in two hours and a half after the meal. They were thirst, faintness, delirium, nausea, paleness of the face, and cold extremities. After eleven hours, there was stupor with tenderness of the abdomen. In the child, there was *cyanosis* of the legs with contracted pupils. It was remarked that even *fourteen* hours after the fungi had been eaten, portions of them were dis-

arged by vomiting from the action of emetics. They both recovered. a period of four years (1865–8) six deaths were recorded to have taken ace from eating poisonous fungi. In the year 1880 no case of poisoning mushrooms was recorded in England.

An analysis of cases of mushroom poisoning shows that when the mptoms are referable to the presumably decayed state of the fungi, ese produce violent gastro-intestinal symptoms; and that, as a rule, ese symptoms appear only after the lapse of some hours, and then the urse of the case is not unlike one of cholera. The fly-fungus (*Amanita uscaria*) contains a definite alkaloid, *muscarine;* and when this fungus is ten, generally in mistake for the golden mushroom (*Amanita Cæsarea*), e symptoms appear within half an hour or an hour, though occasionally a much later period; and they are of a cerebral character—the gastro-estinal symptoms being either only secondary or altogether absent. Thus ere is a state of excitement and inebriation, trismus, &c. Ponfinck has ently made the extraordinary statement that an infusion of the ordinary ushroom is poisonous. This is contrary to common experience; and e children of rural districts often eat with impunity large quantities of cooked mushrooms.

Analysis.—The discovery of portions of the undigested mushrooms in e matter vomited, or a description of the food eaten, will commonly lead a recognition of this form of poisoning. One of the most poisonous in is country, *Amanita muscaria* or the fly-mushroom, renders the water in hich it is boiled so poisonous, that animals are killed by it, while the iled fungus itself has no effect upon them. The liquid procured from is used as a fly-poison, whence the name of the mushroom is derived. is an autumnal fungus, known by its rich orange-red colour.

Some fungi which were exposed for sale in open market have been operly seized and condemned as unfit for human food. An experienced ycologist (the Rev. J. Berkeley) says, 'No general rule can be given for e determination of the question whether fungi are or are not poisonous. olour is quite indecisive, and some of the most dangerous fungi, and mongst them the *Agaricus Phalloides*, are void of any unpleasant smell hen fresh, though the most wholesome may be extremely offensive when d. Experience is the only safe test, and no one should try species cautiously with whose characters he is not thoroughly acquainted.'

Henbane (Hyoscyamus niger).

Symptoms and Appearances.—The seeds, roots, and leaves of this plant e poisonous. When the dose is not sufficient to destroy life, the mptoms are—general excitement, fulness of the pulse, flushing of the ce, weight in the head, giddiness, loss of power and tremulous motion the limbs, somnolency, dilatation of the pupils, double vision, nausea, d vomiting. After a time these symptoms pass off, leaving the patient erely languid. When a large quantity of the *root* or *leaves* has been ten, an accident which has occurred from the plant having been mis-ken for other vegetables, more serious effects have been manifested. In ldition to the above symptoms in an aggravated form, there may be loss incoherency of speech, delirium, confusion of thought, insensibility, nia, and sometimes a state resembling insanity; the pupils are dilated d insensible to light, there is coldness of the surface, cold perspiration, s of power in the legs, alternating with tetanic rigidity and convulsive vements of the muscles; the pulse is small, frequent, and irregular, the spiration deep and laborious. ('Med. Gaz.' vol. 47, p. 640.) Occasionally ere is nausea with vomiting and purging. Death may take place in a few urs or days, according to the severity of the symptoms. The special

effect of this poisonous plant is manifested in its tendency to produce a general paralysis of the nervous system.

One fatal case of poisoning with the roots of henbane is quoted by Orfila, and another with the leaves is reported by Wibmer (op. cit. p. 147). The appearances consisted in a general congestion of dark-coloured liquid blood in the venous system. The lungs and brain especially manifested this condition. There are commonly no marks of irritation or inflammation in the stomach and bowels.

Fig. 55.



Small leaf of Henbane of its natural size and form.

Fig. 56.



Seeds of Henbane. *a*. Natural size. *b*. Magnified 30 diameters.

Analysis.—When the vegetable has been eaten, it can be identified only by its botanical characters. The seeds are very small and hard; they are furrowed on the surface, and may be easily confounded with those of belladonna. They are of an oblong, oval, or pyriform shape. We subjoin illustrations, in which they are represented magnified (*b*) and of their natural size (*a*) fig. 56. The leaves are peculiar in shape and other characters, by which they may be easily identified. The annexed illustration (fig. 55) is from a photograph of a fresh leaf of henbane. The poisonous properties of henbane are known to be owing to the presence of two crystalline alkaloids, which are called *Hyoscyamine* and *Hyoscine*. These, with atropine the alkaloid of belladonna, are, according to Ladenburg, the only three known natural mydriatic alkaloids, *i.e.* basic bodies which cause marked dilatation of the pupil of the eye. According to Ladenburg, hyoscyamine is identical with *duboisine*.

Nightshade (Solanum).

Symptoms and Effects.—There are two species of this plant—the *Solanum dulcamara*, *Bitter-sweet*, or *Woody-nightshade*, which has a purple flower and bears red berries; and the *Solanum nigrum*, or *Garden-nightshade*, with a white flower and black berries. The active principle *Solanine*, on which the poisonous properties of both species depend, varies in proportion at different seasons of the year. Solanine is an alkaloid which needs further investigation, and is perhaps a mixture of alkaloids. In one instance a decoction of the plant is said to have produced in a man dimness of sight, giddiness, and trembling of the limbs,—symptoms which soon disappeared under slight treatment. (For a case of poisoning by the decoction, see 'Med. Gaz.' vol. 46, p. 548.)

The berries of the Solanum nigrum, in one instance at least, produced serious effects in three children who had eaten them. They complained of headache, giddiness, sickness, colic, and tenesmus. There was copious vomiting of a greenish-coloured matter, with thirst, dilated pupils, stertorous breathing, convulsions, and tetanic stiffness of the limbs. One child died in the acute stage: the others died apparently from secondary consequences during treatment. (Orfila, op. cit. 4ème ed. 2, 273.) From three to four berries of this plant have been found to produce sleep. In 1853, the red berries of the *Woody-nightshade* are stated to have caused the death of a boy, æt. 4, under the following circumstances. He had eaten some of the berries, and at first did not appear to suffer from them;

at eleven hours afterwards he was attacked with vomiting, purging, and nvulsions, which continued throughout the day; the child being in-nsible in the intervals. He died convulsed in about twenty-four hours. he vomited matters were of a dark greenish colour and of a bilious cha-cter. Other children had partaken of the berries at the same time: but nong these, one only suffered slightly. ('Lancet,' June 28, 1856, p. 715.)

Deadly Nightshade (Atropa Belladonna).

Symptoms.—The symptoms which are produced by the leaves, berries, d root of the belladonna are of a uniform character, and may be thus scribed:—Heat and dryness of the mouth and throat, nausea, vomiting, ddiness, indistinct or double vision, delirium, great excitement and rest-ssness, convulsions followed by drowsiness, stupor, and lethargy. The pils are much dilated, and the eyes are insensible to light. In two cases, e pupils were contracted during sleep, although dilated in the waking ate. ('Dub. Med. Press,' Jan. 5, 1853; 'Jour. de Chim. Méd.' 1853, p. 5.) Several deaths from the poisonous effects of the *berries* occurred London in 1846. A boy, æt. 14, ate, soon after breakfast, about thirty the belladonna berries, which he had bought as fruit in the streets. about three hours he had the sensation of his face being swollen: his roat became hot and dry, his vision was impaired, objects appeared uble, and they seemed to revolve and run backwards. His hands d face were flushed, and the eyelids swollen; there were occasional shes of light before his eyes. He tried to eat, but could not swallow on count of the state of his throat. In endeavouring to walk home he mbled and staggered; and he felt giddy whenever he attempted to raise s head. His parents thought him intoxicated; he was incoherent,—equently counted his money, and did not know the silver from the copper ins. His eyes had a fixed, brilliant, and dazzling gaze; he could neither ar nor speak plainly, and there was great thirst; he caught at imaginary bjects in the air, and seemed to have lost all knowledge of distance. His ngers were in constant motion: there was headache, but neither vomiting or purging. He did not reach the hospital until nine hours had elapsed, nd the symptoms were then much the same as those above described. He ttempted to get out of bed with a reeling, drunken motion; his speech was hick and indistinct. The pupils were so strongly dilated that there was erely a ring of iris, and the eyes were quite insensible to light. The yelids did not close when the hand was passed suddenly before them. He ad evidently lost the power of vision, although he stared fixedly at objects s if he saw them. The nerves of common sensation were unaffected. When placed on his legs he could not stand. His pulse was 90, feeble and ompressible; his mouth was in constant motion, as if he were eating some-hing. His bladder was full of urine on admission. He continued in this tate for two days, being occasionally conscious, when by a free evacuation f the bowels, some small seeds were passed: these were examined and dentified as the seeds of belladonna. The boy gradually recovered, and ft the hospital on the sixth day after his admission:—the progress of ecovery was indicated by the state of the pupils, which had then only equired their natural size and power of contraction. In three other cases hich occurred at the same time, the berries having been baked in a pie, ains in the limbs, drowsiness, insensibility, and convulsions, were among he symptoms. In two instances of poisoning by the berries, the symptoms ore a strong resemblance to those of delirium tremens, but among them re heat and dryness of the throat, loss of power of swallowing, incoherent peech, double vision, and strange spectral illusions, with occasional fits of ild and *ungovernable laughter.* On the following morning both these

patients recovered, as if from a dream; but they suffered for some time from languor, thirst, and dryness of the throat: the pupils also continued dilated. (Casper's 'Wochenschr.' Jan. 10, 1846, p. 26.) Two cases, showing the poisonous effects of the berries on children, are quoted in the 'Edin. Med. and Surg. Jour.' (vol. 29, p. 452).

In 1880, a boy, æt. 12, was admitted into Guy's Hospital who on the previous day had eaten some ripe belladonna berries whilst on a country excursion. On returning home he went to bed as usual, but awoke at 2 A.M. in much the same condition as on his admission at 5 A.M. He was then delirious, and in such violent convulsions that he was unable to sit still a moment. He talked most incoherently. He apparently could not swallow, as he put water into his mouth and spat it out again, the effort throwing him into severe convulsions. At 10 A.M., the delirium and convulsions still continued; there was a marked flushing on the legs and face, and the latter was somewhat swollen. The throat was red, and he showed aversion to water. The pupils were widely dilated. The delirium continued, with convulsions, all day and during the next night, though occasionally he spoke rationally. He was flushed, and appeared like a child in the early stage of a scarlatina or rash. At noon—about forty-two hours after, as was supposed, the berries were eaten—one-third of a grain of morphia was injected hypodermically. The boy slept, and next day awoke well.

The *root* of the belladonna, administered in the form of decoction as an enema, has destroyed life. Eighty grains of the root were employed, and the liquid, strained and reduced by evaporation to four ounces, was injected. After a slight stage of excitement, the patient, a female, æt. 27, fell into a state of complete coma; the countenance appeared swollen, and of a reddish-brown colour; the pupils were excessively dilated; the pulse was at first full and hard, then small; death took place in five hours. (Casper's 'Wochenschr.' Feb. 8, 1845, p. 101.)

The *leaves* of belladonna have occasionally given rise to accidents. A young man swallowed an infusion of two drachms of the leaves. In about an hour he found great difficulty in swallowing, the salivary secretion was suppressed, and objects appeared to be in perpetual motion before him. He became delirious, repeatedly attempted to pass his urine in vain: and for an hour and a half he was in constant motion, although his gait was unsteady. The muscles of his face, jaws, and limbs were agitated by convulsive twitchings: the pupils were excessively dilated, and there were singular hallucinations. There was neither nausea, vomiting, nor purging. Emetics, injections, and bleeding were resorted to, and the next morning the patient awoke as if from a dream. ('Ann. d'Hyg.' Oct. 1847, p. 413.)

Fig. 57.




Small leaf of Belladonna, natural size.

Leaves of belladonna have been ignorantly supplied for ash-leaves, and half a wine-glassful of the decoction of the leaves produced on Garrod the usual symptoms of poisoning by this plant. His patient, who took half a pint, suffered severely. The chief symptoms were giddiness, difficulty in walking, dryness of the mouth and throat, perversion of taste, indistinctness of vision, dilatation of the pupils, bloodshot eyes, difficult articulation, delirium, insensibility, and a scarlet redness of the skin of the face and neck, followed by a peeling off of the cuticle. The leaves of belladonna are peculiar in shape. The annexed illustration (fig. 57) is from a photograph of a small leaf of the fresh plant. According to Luxton, 1,000

ı of leaves yield only five grains of atropine. ('Pharm. Jour.' p. 300.)

ıe *seeds* of belladonna are small, of a somewhat oval shape, and lark colour. Under a low magnifying power they have a honey-ɔd surface (fig. 58). In henbane the surface of ɔds presents more irregular depressions, resembling seen on certain corals or maderepores.

Fig. 58.



Seeds of Belladonna.
a. Natural size.
b. Magnified 30 diameters.

vo persons swallowed a small spoonful of the *t* of belladonna by mistake for that of juniper. was speedily indistinctness of vision, tottering lelirium, incoherency, hallucinations, and dilata-ıf the pupils. In one there was great cerebral ment. Under treatment, the symptoms of poison-sappeared in two days; but one of the patients n the seventh day from disease. The physical and ılogical properties of the extract indicated that it elladonna; but the attempt to procure atropine it entirely failed. A portion of the concentrated extract given to , caused dilatation of the pupil in a quarter of an hour. In a case npound poisoning by extract of belladonna and tincture of opium, was the violent excitement produced by belladonna, but the pupils strongly contracted as in poisoning by opium. ('Med. Times and 1870, 1, 564.) A lady suffered from severe symptoms of poisoning, early lost her life, owing to an injection containing one drachm of tract of belladonna, and one drachm of wine of opium having been istered to her. The pupils in this case were dilated, and the opium ɛntly did not counteract the effects of the belladonna.

ıe following case, which occurred in 1871, is remarkable for the ıat a woman recovered from a large dose of the extract. A nurse ɔy mistake to a lady whom she was attending a belladonna liniment ning three drachms of the extract mixed with soap liniment. She ɛd slightly, and suffered from dryness of the throat, difficulty of ɔwing, drowsiness, delirium, pupils dilated, fixed stare of the eyes, f power and difficulty of speech. Paralysis of the extremities came th great pain in the back. Emetics with brandy and cayenne pepper ɛmployed with success. The woman recovered, but not until after eeks from the time of swallowing the liniment.

ɒpearances.—The appearances observed in several cases of poisoning ɔ berries which proved fatal in London during the autumn of 1846, ıs follows: the vessels of the brain were congested with liquid blood; ɔmach and intestines were pale and flaccid; there were some red spots ls the cardiac end. In other fatal cases, of which the appearances ɔeen reported, the vessels of the brain and its membranes were found ded with thick black blood. Red spots have also been observed l the throat and gullet, and congested patches of a dark purple colour ɔ coats of the stomach. In some instances the mucous membrane has ɔompletely dyed by the juice of the berries. A boy, æt. 5, after ɾ eaten a quantity of belladonna berries, went to bed, was very ıs, vomited once, and died in convulsions about fifteen hours after ɾ taken the poison. On inspection, the eyes were half-open, with an e lustre; the pupils dilated; the mouth was spasmodically closed and hincter ani relaxed. The cerebral vessels were distended with dark-ed blood; the substance of the brain, cerebellum, and medulla oblon-ɒresented numerous bloody points. In the throat and gullet there everal patches of redness. In the stomach there was some fluid, with ɒpen berries; *the mucous membrane* was of a reddish-blue colour in

various parts. (Canstatt's 'Jahresber.' 1844, v. 295.) For another case showing the appearances, see Horn's 'Vierteljahrsschrift,' 1866, 2, 159. A woman, æt. 66, swallowed a teaspoonful of belladonna liniment, and after suffering the usual symptoms died in sixteen hours. On inspection the lungs were found full of blood,—the right side of the heart contained but little black blood, and the left side was firmly contracted. The brain was slightly congested. The stomach and other organs presented nothing unusual. The inspection was made thirty-four hours after death, and the pupils were then dilated. ('Lancet,' 1870, II. p. 83.)

Analysis.—The indigestible nature of the leaves, fruit, and seeds will commonly lead to their detection in the matters vomited or passed by the bowels, or in the contents of the viscera after death. The seeds of belladonna are very small—they can, however, be distinguished by the microscope from the seeds of other poisonous plants. The colouring matter of the berry is of a deep purple hue. The leaves are known by their botanical characters, and a decoction or infusion of them, by the liquid causing dilatation of the pupil. The urine, blood, or organic liquids containing this poison, applied to the eye of an animal, cause dilatation of the pupils.

Atropine.—Atropia, or atropine, is the name given to the alkaloidal principle of belladonna. This alkaloid is a powerful poison. In 1850, Sells, of Guildford, forwarded to the author for examination the stomach of a young man who had poisoned himself by taking *two grains* of atropine. He took the dose on going to bed. He was heard to snore heavily during the night, and was found dead about seven o'clock in the morning, lying on his right side, the surface livid, the limbs rigid and contracted, and with a little brown matter issuing from the mouth. The pupils were much dilated. The mucous membrane of the stomach presented a diffused redness, which might have arisen from some brandy which he had swallowed. No trace of the poison could be detected in the stomach or its contents. In the 'Assoc. Med. Jour.' (Sept. 16, 1853, p. 818) will be found the report of a case in which all the symptoms of poisoning by belladonna arose from the application of a weak solution of atropine in water to the conjunctiva. One-eighth of a grain injected into the skin for the relief of sciatica, produced the usual symptoms of poisoning. ('Pharm. Jour.' May, 1862, p. 583.)

Cases of atropine poisoning of a mild character are common in hospital practice, in consequence of atropine lotions, intended for the eye, being accidentally taken by children and others.

The criminal administration of atropine is a rare event in this country. A trial for murder by this alkaloid took place at the Manchester Lent Assizes, 1872 (*Reg.* v. *Steele*). The prisoner, who was a nurse in the workhouse, was charged with administering atropine to the senior surgeon, and thereby causing his death. The deceased was taken suddenly ill after his breakfast, and died under the usual symptoms of poisoning with atropine in about twelve hours. The poison was detected in the body, and also in a liquid found in the room—a solution of atropine in spirit. Milk was the vehicle through which it was taken. The milk as sent from the kitchen contained nothing injurious, but that found in deceased's room was tasted by two of the nurses and both suffered from poisoning by atropine. The prisoner had access to this room, and it was alleged that she had a strong motive for this criminal act, but there was no direct proof to show that she put the poison into the milk, and she was acquitted.

Analysis.—Atropine is a white crystalline substance, not very soluble in water, but easily dissolved by alcohol, ether, and diluted acids. It does not readily crystallize, but it forms crystallizable salts. The annexed illustration (fig. 59) shows the irregular crystalline form of sulphate of

opine, as it is deposited from an alcoholic solution. Ammonia added the solution of sulphate of atropine does not separate the alkaloid in tinct crystals. In this respect it differs from rphia and strychnine. When atropine is ted on platinum it melts, darkens in colour, l burns with a yellowish smoky flame. Sul- uric, hydrochloric, and nitric acids dissolve vithout any change of colour. Water added the mixture of sulphuric acid produces no nge: but a crystal of potassium bichromate duces a green colour. Tannic acid precipi- s the alkaloid from its solutions: but the st effectual precipitant is the chloriodide of assium and mercury, which throws down ense white precipitate even in very diluted itions. Atropine is also precipitated by ic chloride, but, unlike strychnine, it is not cipitated by potassium sulphocyanide or potassium chromate. It may letected in, and separated from, organic liquids by the process of Stas. ording to Winckler atropine is precipitated most completely from all solutions by the chloriodide of potassium and mercury. By the use of precipitant he was able to determine the proportion of atropine con- ed in the powder of the dry leaves and root. In the leaves the alkaloid ied from 0·41 to 0·49 per cent. and in the root it amounted to 0·48 cent. ('Pharm. Jour.' June, 1872, p. 1029.)

Fig. 59.



Imperfect crystals of Sulphate of Atropine, magnified 30 diameters.

A small quantity of a diluted solution of atropine applied to the eye duces dilatation of the pupil. This may be employed as a physiological for detecting the presence of atropine in an extract made from the tents of the stomach, or of any organic liquid. The introduction of a tion into the cellular membrane of an animal, besides producing the inary symptoms of poisoning, causes dilatation of the pupil. Atropine me of the three natural pupil-dilating alkaloids. It occurs not only in ladonna, but also in stramonium.

Thornapple (Datura stramonium).

All parts of this plant are poisonous; but the *seeds* and *fruit* are con- ered to be the most noxious.

Symptoms.—The usual effects produced by this poison will be under- od from the following cases. A woman, æt. 36, took two teacupfuls of sion of stramonium leaves by mistake for senna tea. In about ten nutes she was seized with giddiness, dimness of sight, and fainting. In hours she was quite insensible; the pupils were fixed and dilated, all muscles of the body convulsed, the countenance flushed, and the pulse s full and slow. The stomach-pump was applied, and in the course of few hours she recovered,—suffering, however, from indistinctness of ion and vertigo. ('Med. Gaz.' vol. 8, p. 605.) The *seeds* of this plant highly poisonous. A boy, æt. 5, ate some seeds, with a portion of the at. Soon afterwards it was observed that his face was flushed, and that staggered as if intoxicated. He vomited and threw up about thirty ds. His skin was hot and red, the countenance had a wild and staring pression, the pupils were nearly fully dilated and insensible to light. e child was restless, in a state of raging delirium, and biting with fury those who attempted to restrain him. He was unable to stand, and in tate resembling St. Vitus's dance. The pulse could not be counted. e breathing was hurried and gasping. He was incessantly talking, but hout articulating *distinctly*, and he appeared to be driving away from

him imaginary objects. Emetics produced the vomiting of more seeds, and in an hour he began to articulate. He slept restlessly for two hours. Some seeds were passed in the evacuations from the bowels. In four hours the symptoms had abated, and the boy gradually improved. The pupils did not recover their natural state until after three days. ('New York Jour. of Med.' 1856; and 'Brit. and For. Med. Rev.' 1857, 19, 497.)

Turner ('Amer. Jour. Med. Sci.' April, 1864, p. 552) describes five cases of poisoning by the seeds, in children under ten years of age. They had eaten them in the scarcely ripe state, when they are not very bitter. In one hour and a half two of the children were found to be fully under the influence of the poison. They were lying on their backs, the eyes bright, and the pupils widely dilated and insensible to light; the conjunctivæ were injected, the face deeply suffused and of a dark crimson colour; there was difficulty of breathing, inability to articulate, and a state of complete insensibility, broken occasionally by a paroxysm during which they would utter some indistinct sounds and throw their hands about, as if trying to ward off some threatening evil. They then fell into a comatose state, but were easily roused into a state of violent excitement: they grasped at imaginary objects; there was picking at the bed-clothes, with paroxysms of excessive laughter. They had no proper control over their limbs, walked with a staggering gait, and fell to the ground as if intoxicated or in a state of complete exhaustion. They recovered under treatment in about twenty-four hours. (See also other cases in the same journal, Jan. 7, 1862, p. 54.)

A girl, æt. 5, ate about half a dozen stramonium seeds, together with some of the pulpy matrix of the fruit. Symptoms came on within twenty minutes, beginning with dryness and burning of the throat, thirst, inability to swallow, nausea and retching, but no vomiting; pain in the stomach, flushed face, giddiness, and singing in the ears. Twitchings of the muscles of the forearm were next observed, and delirium set in. When seen an hour and a half after eating the seeds, the girl was lying on her back, delirious, apparently unconscious, and in convulsions. She caught at imaginary objects in the air. The eyes were bright and glistening, the conjunctivæ red and injected, and the pupils widely dilated. The delirium was of a busy kind—fits of laughter alternating with fits of crying and horror. The convulsions were general. The skin was hot, dry, and of a deep scarlet hue; temperature normal; the pulse small and rapid; respiration interrupted, but not rapid. She recovered. From six ounces of the urine voided five hours after the seeds were eaten, a substance was obtained by Stas's process which dilated the pupil when applied to the eye of a man; and this dilatation lasted for some hours. (Canada 'Lancet,' vol. 14, p. 161.)

Death may take place although the whole of the seeds are ejected. A child, æt. 2, swallowed about one hundred seeds of stramonium, weighing sixteen grains. The usual symptoms were manifested in an hour, and the child died in twenty-four hours, although twenty seeds had been ejected by vomiting and eighty by purging. ('Med. Gaz.' vol. 15, p. 194.) Sufficient daturine to destroy life had been absorbed from the entire seeds and carried into the blood. In a case which became the subject of a trial at Osnabrück, a woman administered to her mother a decoction of the bruised *seeds* of the thornapple, of which it was supposed there were about 125. She very soon became delirious, threw her arms about, and spoke incoherently: she died in seven hours. (Henke, 'Zeitsch. der S. A.' 1837, i. H.) The seeds retain their properties notwithstanding exposure to heat: thus the smoking of stramonium seeds is attended with danger. In the return of the Registrar-General for April, 1856, there is the record of one death from this cause.

One of the methods of poisoning adopted by the Hindoos, not so much ith the intention of destroying life as of facilitating the perpetration of obbery, consists in administering to persons either the powdered seeds, or strong decoction of them, in curry, or in some other highly-flavoured article f food. Delirium and insensibility soon follow, and sometimes death is ie result; but no suspicion of the real case appears to be excited.

Brown, of Lahore, states that out of ninety-two of these cases of oisoning no fewer than twenty-one proved fatal; but it is probable that any which result in death are never known, while those who survive ould naturally complain of any injury that might have been done to them hile insensible. The drug has a bitter taste, which it generally imparts o the food with which it is mixed, and which is sometimes recognized hen it is eaten. The symptoms usually occur in about ten minutes after he poison has been taken, although they may be delayed from half an our to an hour. There is at first a dryness in the throat, attended with feeling of faintness, headache, and giddiness, and the person has difficulty n walking straight, and appears as if intoxicated, while at the same time he is very restless. The pupils are dilated, and he will sometimes complain of indistinctness of vision, or drowsiness, and he almost always falls asleep. The sleep may either increase to complete insensibility with dilated pupils, flushed face, and muttering delirium, or the patient may awake and then become delirious. The delirium is characterized by great restlessness, the person affected frequently moving about, and there is a tendency to go naked and to pick at various objects. The pulse is generally slow, and here is great thirst. After a time the patient becomes again insensible, nd is greatly exhausted: sometimes convulsions occur, with low mutterng delirium, and at length he dies. If, as it more frequently happens, he ecovers, the insensibility persists for a day or more, and the patient emains occasionally in an idiotic state, able to speak, but not to underand for some time longer, and he has no recollection of what has occurred fter the poisonous meal. Sometimes vomiting is an early symptom, lthough this is rare. ('Poisons in the Punjab,' 1863, p. 57.)

Chevers has given a very complete account of the Hindoo system of oisoning by *dhatoora*. ('Med. Jur.' for India, 1856, pp. 121, 549, 591.) appears that the *Datura fastuosa* and *alba* are the principal sources of e poison in India. The Thugs employ this poison with the object of ndering their intended victims helpless. As it is administered by skilled ofessional poisoners in India, it causes a profound lethargy resembling ma. The symptoms may continue for two days, and yet recovery take ace. He also states that the cases rarely prove fatal. Out of fifty-one stances of poisoning by dhatoora, at the Bombay hospital in one year, corded by Giraud, one only proved fatal, and four presented very arming symptoms. Chevers notices the early occurrence of insensibility. man drank two mouthfuls of a poisoned liquid, complained of a bitter ste, and fell down insensible within forty yards of the spot where he had unk the liquid, and did not recover his senses until the third day after.)p. cit. p. 137.) In these cases, probably the seeds are given in a large se, either in solution or in very fine powder. The first stage of poisoning commonly marked by delirium, the patient is restless and wanders about if in search of something, but from giddiness or great muscular weakss he is soon unable to walk or even to stand; he talks incoherently, ughs wildly, moves about as if to avoid spectra, and picks or catches ceasantly at real or imaginary objects. He appears as if drawing out naginary threads from the ends of his fingers, and his antics are of the ost varied and ludicrous kind. The pupils are invariably dilated, and e spectra are illusions depending on disordered vision. Distant objects

appear near to him, and near objects as if highly magnified: he will attempt to grasp a distant object as if it were close at hand, and will start back on a person approaching, as if he thought the person was quite near to him. In the second stage of poisoning, there is either great drowsiness or complete stupor, sometimes passing into utter insensibilty, with stertorous breathing. The third stage of final delirium is similar to the first. (Op. cit. p. 593.) For some additional information respecting the employment of datura by the professional poisoners of India, see Irving's 'Cases of Food-Poisoning,' &c., 1864.) The effects are generally produced within a quarter of an hour, and those who have taken the poisoned food have had little or no recollection of anything that occurred afterwards. An extract of datura is probably used as one of the methods of 'hocussing' persons by thieves in this country. The dilatation of the pupil, with the peculiar train of symptoms above described, would distinguish this state from ordinary intoxication. The bitter taste of the liquid might excite suspicion; but if the person is already partially intoxicated, he may be incapable of making any observation of this kind.


Appearances.—In a well-marked case of poisoning by stramonium seeds, in which death took place in less than eight hours, the following appearances were noted:—great congestion of the vessels of the brain and its membranes, the brain firm and highly injected, the choroid plexus turgid, the ventricles containing serum, the substance of the lungs congested, and the heart flaccid. The stomach contained about four ounces of digested food mixed with eighty-nine seeds of stramonium. There were two patches of extravasation in the mucous coat—one on the larger curvature, and the other near the pylorus. Many seeds and fragments were also found in the intestines. ('Lancet,' Sept. 18, 1847, p. 298.) In the Osnabrück case (p. 426) there were marks of diffused inflammation about the cardiac end of the stomach.

Irving describes the appearances met with in the body of one of the professional Indian poisoners, Bassawur Singh, who, in order to lull suspicion, partook of the poisoned food himself. His intended victims became insensible; he robbed them and left them to their fate. After a time they recovered their senses, and gave information at the police-station. The poisoner was found under a tree, about a mile from the place, quite insensible. Remedies were unsuccessfully used, and he died shortly after being apprehended. On his person was found all the stolen property, besides a quantity of datura seeds. The following were the post-mortem appearances:—The pupils were widely dilated; the body was covered with dust, as if it had been rolled on the ground. The fingers of both hands were firmly clenched. There was great venous congestion of the brain and membranes: slight effusion of bloody serum under the membranes, chiefly on the right hemisphere. About an ounce of dark fluid blood was found at the base of the skull. The bloody points on a section of the brain were numerous. The ventricles contained a considerable quantity of serum. The choroid plexus was unusually full of blood. In the stomach there was a quantity of food, partly digested, in which were found seeds of datura as well as seeds of the *Solanum melongena*, which in form they somewhat resembled. ('Cases of Food-Poisoning,' &c., 1864. 'Ind. Annals of Med. Sci.' No. 17.)

Analysis.—The *seeds* of stramonium, from which accidents have most frequently occurred, are flattened, kidney-shaped, but half oval, rough, and of a dark-brown or black colour (fig. 60). The seeds are liable to be mistaken for those of capsicum. Brown thus describes the difference:—'The datura seeds present dots on their exterior, which on a microscopical examination are seen to be composed of convoluted ridges surrounding spaces. On the capsicum seed these convoluted ridges run nearly parallel

h other, and are joined at right angles by shorter ridges so that most spaces are of an oblong form, and are as lines curving round the seed: datura, the ridges are onvoluted and irregu- ining at acute angles cumscribing irregular . ('Poisons of the b,' 1863, p. 67.) Of y datura stramonium, eight seeds weigh one They are of an oblong -shape, and of a dark- or black colour. The of the datura fastuosa similar in size and l appearance, that a te illustration of them is quite unnecessary. The seeds of datura e larger, flatter, and much lighter-coloured, but have similar micro- l characters. These are the seeds which are chiefly used by the and the poisoning robbers of India.

Fig. 60.



Seeds of Datura stramonium.
a. Natural size.
b. Magnified 30 diameters.

Fig. 61.



Seeds of Datura alba (India).
a. Natural size.
b. Slightly magnified by a lens.

e *leaves* of the common datura stramonium are well characterized by eculiar shape. In the annexed illustration (fig. 62) is represented l leaf of the datura stramonium from a young plant. In the full- plant the leaves retain the same characters, but are much larger.


URINE.—The poisonous properties of thornapple are owing to the ce of an alkaloid, *daturine*, which forms about one per cent. of the vegetable. In its properties it resembles Atropine and Hyos- cyamine. This alkaloid crystal- lizes in long colour- less prisms or needles; it has a bitter taste, some- what acrid, and slightly resembling that of tobacco (fig. 63). It is poisonous. The eighth of a grain killed a sparrow in three hours. When placed on the eye, or introduced into the cellular membrane of an animal, it is observed, like atropine, to cause dilatation of the pupil. When heated in a tube it is de- composed, and ammonia is evolved, as with other alkaloids. It is soluble in water, and the solution has an alkaline reaction. It is pre- cipitated by tannic acid and by the chloriodide ssium and mercury. Nitric and hydrochloric acids dissolve it, without ing any change of colour. Sulphuric acid produces a pale rose-red with the crystals, which becomes paler when the acid mixture is . with water. Ladenburg asserts that daturine is a mixture of ie and hyoscyamine.

Fig. 62.



af of Stramonium, from a tograph; natural size.

Fig. 63.



Crystals of Daturine, magnified 30 diameters.

(SPINAL POISONS.)

CHAPTER 30.

NUX VOMICA—STRYCHNINE—SYMPTOMS AND APPEARANCES—TIME OF OCCURRENCE OF SYMPTOMS—FATAL DOSE—PERIOD OF DEATH—CHEMICAL AND MICROSCOPICAL ANALYSIS OF NUX VOMICA AND STRYCHNINE—TESTS—PROCESS FOR ORGANIC MIXTURES—DETECTION OF STRYCHNINE IN THE TISSUES—BRUCINE.

Nux Vomica. Strychnine.

Nux Vomica in powder has a bitter taste, and cannot therefore be easily administered in a poisonous dose without exciting suspicion. It owes its poisonous properties to the presence of the alkaloid *strychnine* or *strychnia* associated with another alkaloid named *brucine* or *brucia*, of similar but feebler poisonous properties, in the proportion of about one per cent. and sometimes less. Strychnine itself has a very bitter taste even in very small quantity; but as it destroys life in a small dose, and it may be given in the form of pills or professedly administered as quinine or other medicines, it offers every facility for criminal administration. The free sale of vermin-killers containing strychnine affords facilities for poisoning by this alkaloid. Strychnine is a constituent of at least one quack medicine. Fellow's Compound Syrup of Hypophosphites, a proprietary preparation, contains strychnine; and this dangerous substance is described on the wrappers in which the preparation is sold to the public merely as a tonic alkaloid. Each fluid drachm—the ordinary dose—is stated to contain one sixty-fourth of a grain of strychnine.

Symptoms.—At a variable interval after taking either nux vomica or strychnine in a poisonous dose, the patient experiences a sense of uneasiness and restlessness, accompanied by a feeling of impending suffocation, and not infrequently by a sense of impending calamity or death. There is a shuddering or a trembling of the whole frame, with twitchings and jerkings of the head and limbs. Tetanic convulsions then commence suddenly with great violence, and nearly all the muscles of the body are simultaneously affected. The limbs are stretched out involuntarily, the hands are clenched: the head after some convulsive jerkings is bent backwards, and the whole of the body becomes as stiff as a board. As the convulsions increase in frequency and severity, the body assumes a bow-like form (opisthotonos), being arched in the back and resting on the head and heels. The head is firmly bent backwards, and the soles of the feet are incurvated, or arched and everted, the legs sometimes separated. The abdomen is hard and tense, and the chest spasmodically fixed, so that respiration appears to be arrested. The face assumes a dusky, livid, or congested appearance, with a drawn, wild, or anxious aspect; the eyeballs are prominent and staring, and the lips are livid. The intellect is clear, and the sufferings during this violent spasm of the voluntary muscles are severe. The patient in vain seeks for relief in gasping for air, and in requiring to be turned over, moved, or held. The muscles of the lower jaw, which are the first to be affected in tetanus from disease, are generally the last to be effected by this poison. The jaw is not always fixed during a paroxysm. The patient can frequently speak and swallow, and great thirst has been observed among the symptoms. In some cases of poisoning by nux vomica, the jaw has been fixed by muscular spasm; but, unlike the lock-jaw of disease, this has come on suddenly in full intensity with tetanic spasms in other muscles, and there have been intermissions which are not witnessed in the tetanus

disease. The sudden and universal convulsion affecting the voluntary uscles has sometimes been so violent that the patient has been jerked off e bed. After an interval of half a minute to one or two minutes, the nvulsions subside, there is an intermission, the patient feels exhausted, id is sometimes bathed in perspiration. It has been noticed in some of ese cases that the pupils during the paroxysms are dilated, while in the ermission they are contracted. The pulse during the spasms is so quick at it can scarcely be counted. Slight causes, such as an attempt to ve, a sudden noise, a draught of air, or gently touching the patient, will quently bring on a recurrence of the convulsions. In cases likely to ve fatal, they rapidly succeed each other, and increase in severity and ation, until at length the patient dies utterly exhausted. The tetanic ptoms produced by strychnine when once clearly established, progress idly either to death or recovery. The patient is conscious, and the d is commonly clear to the last. He has a strong apprehension of th. The duration of the case, when the symptoms have set in, is coned by minutes; while in the tetanus of disease, when fatal, it is coned by hours, days, and even weeks. As a general statement of the rse of these cases of poisoning, within two hours from the commence- nt of the symptoms, the person either dies or recovers, according to severity of the paroxysms and the strength of his constitution. Death metimes takes place in a paroxysm. ('Lancet,' June, 1861, p. 572.) e temperature of the body often rises, even ten degrees above the nominal. The *time at which the symptoms commence* appears from the recorded es to be subject to great variation. In poisoning by nux vomica the ptoms are generally more slow in appearing than in poisoning by rchnine. Until they set in suddenly, the patient is capable of walking, king, and going through his or her usual occupations. In one, a man llowed about 300 grains of nux vomica and no symptoms appeared for hours. He then died rapidly in a violent convulsive fit. ('Ann. yg.' 1861, 2, 431.) On an average in poisoning by strychnine the ptoms appear in from five to twenty minutes. In one case convulsions e on in five minutes. ('Ann. d'Hyg.' 1861, 1, 133.) In two cases at t, an hour has elapsed. ('Lancet,' Aug. 31, 1850. 'On Poisoning by rchnia,' 1856, p. 139.) In a case which occurred to Lawrie and an, in 1853, an hour and a half elapsed. In 1848, Anderson met with nstance in which *two hours and a half* elapsed before the appearance ymptoms. ('Poisoning by Strychnia,' p. 42.) The longest interval rded was in the following case:—A boy, æt. 12, swallowed a pill aining three grains of strychnine. No symptoms appeared for *three s*; they then set in, in the usual way, and death took place in ten utes. It was proved that the pill taken contained three grains of chnine, with mucilage. The pills had been prepared eight months pre- sly for the purpose of poisoning dogs; hence they were hard, and would ergo only a slow solution in the stomach. ('Lancet,' 1861, II. p. 480.) The form in which the poison is administered or applied has a con- rable influence on the time at which the symptoms commence. Thus n strychnine is given in pills, especially if, as in the above case, they hard, the symptoms are much longer in appearing than when the on is taken in solution. Savory gave to a dog two bread pills, t containing one quarter of a grain of strychnine. No symptoms of oning had occurred at the end of *two hours*, but the animal was found l a short time afterwards. When strychnine was given in solution the ptoms soon appeared, and death took place rapidly. ('Lancet,' 1863, p. 515, 548.) This fact connected with the absorption of this poison been ignored (*Reg. v. Palmer*, C. C. C., 1856). Palmer gave to the

deceased, Cook, two pills supposed to contain strychnine. No symptoms were observed for an hour and a quarter. More than one expert deposed that this interval rendered it impossible that the symptoms could have been caused by strychnine. The above-mentioned cases will show that this opinion was in conflict with ascertained facts.

If the poison is applied hypodermically to the cellular membrane, to an ulcerated or diseased surface, or even a healthy mucous surface, absorption takes place rapidly, and the interval for the production of symptoms is proportionably short. Schuler relates a case of amaurosis in which about the 1–12th part of a grain of strychnine was introduced into the punctum lachrymale at the corner of the eye. Three or four minutes had not elapsed when symptoms of poisoning appeared. There was convulsive respiration, with violent tetanic shocks, and the patient appeared about to die: however, the symptoms passed off, and he recovered. ('Med. Times and Gaz.' July, 1861.)

Appearances after death. Externally.—In general the body is relaxed at the time of death, and stiffens afterwards: but the commencement and duration of the rigid state depend on various conditions. In the case of two children (*Reg.* v. *Vyse*, C. C. C. 1862), who died in less than an hour from the effects of Battle's Vermin Killer, administered by the mother, when the bodies were seen, soon after death, they were much discoloured, livid, and although quite warm, were perfectly rigid. The younger, aged five years, was rigid all over: the elder principally about the jaws and neighbouring parts. The rigidity gradually disappeared, and after twenty-four hours there was scarcely any remaining in the elder child. Decomposition had commenced, the front of the abdomen presenting a green discoloration. The body of a person poisoned by strychnine may therefore be found in a non-rigid state within the ordinary period after death; but in most recent cases it is not unusual to find the hands clenched and the feet arched or turned inwards,—incurvated. In the case of *Cook*, the rigidity of the limbs, including the hands and feet, is reported to have been well-marked when the body was disinterred about two months after burial. The great rise of temperature in strychnine poisoning may cause the body to be warm for an unusual length of time after death.

In other instances of strychnine poisoning no particular degree of rigidity has been found at any period after death. In rabbits poisoned by similar doses of strychnine, the author observed the body of one to remain perfectly rigid for a week, while another had lost all rigidity and had begun to putrefy after thirty-six hours. The circumstances which affect the commencement and duration of this condition of the dead body have been elsewhere described (see p. 59). The experiments of Brown-Séquard have shown that it is not any special influence of the poison on the muscles, but the mode in which it operates on the system, that determines the commencement and duration of rigidity in the dead body.

In an accurately observed case recorded by Casper, the body was examined forty-one hours after death. It presented the slight greenish tinge of incipient putrefaction in the loins: there was slight humidity; the expression of the face was that of one quietly sleeping—the eyes were closed, the pupils neither contracted nor dilated. Rigidity was present in its usual degree for the time of observation—well-marked, as it always is, in the masseter muscles by which the jaws were firmly closed, and more strongly marked in the limbs which were lying parallel with the trunk. The feet were not incurvated: the fingers as in other dead bodies were half flexed inwards, and the nails were blue. There was no evidence of tetanic, still less of opisthotonic stiffness or rigidity of the body. In short, this body was externally precisely like a thousand other bodies which had come

fore him; and any physician not informed of the mode of death, would ve had no suspicion whatever of death by strychnine from the external ppearances. (See report of this case revised by Casper within a few hours his own death, in Horn's 'Vierteljahrsschr. für gerichtl. Med.' Juli, 864, p. 7.)

Among the *internal* appearances which have been met with in different ses, is congestion of the membranes and substance of the brain, as also the upper part of the spinal marrow, with congestion of the lungs. The art is either contracted and empty; or its right cavities in some instances ve been distended with liquid blood. The blood has been found black d liquid throughout the body. The mucous membrane of the stomach s occasionally presented slight patches of ecchymosed congestion, pro-bly depending on extraneous causes; such as the process of digestion, e presence of food or alcoholic liquids. In most instances the stomach d intestines have been found quite healthy, and this poison neither flames nor irritates the mucous membrane. Of the appearances observed poisoning by strychnine, there are none which can be considered aracteristic. Congestion of the membranes of the brain and spinal arrow is probably the most common. A man who had taken strychnine edicinally, died in less than three hours from a dose of a grain and a lf. On inspection, there were extensive patches of extravasated blood neath the arachnoid membrane of the lower half of the spinal cord. 'Med. Times and Gaz.' March 21, 1857, p. 297.) With regard to the te of the heart and lungs, their condition, as to fulness or emptiness, pends rather on the mode of dying, than on the actual cause producing ath.

Casper states that out of nearly 1,200 medico-legal inspections made by im up to Dec. 10, 1863, no case of death from strychnine had come fore him. At that date he made a careful examination of the body of a an, who had destroyed himself with strychnine, with a view, if possible, f fixing the special appearances produced by this poison, and of isolating em from those casual conditions of the dead body which have been rongly described as characteristic of the effects of strychnine. A healthy an, æt. 30, swallowed from five to six grains of strychnine. For about an ur, he lay in his room quietly. At this time spasms commenced, and in s attempt to reach a window he fell and lost all power of moving his gs. He was not seen for another hour, when he was found on the floor, king for water. In attempting to raise himself, he was seized with tanic convulsions affecting the whole of his muscles: he had three of ese fits in a severe form, and died in the last, three hours and a quarter ter the poison was taken. During the spasms, as well as in the intervals, ere was complete consciousness.

The external appearances in this case have been already described (p. 432). The two outer membranes of the brain were filled with blood: which throughout the body was generally fluid as in death from asphyxia —it was of a light reddish colour, as in poisoning by carbonic oxide or russic acid. The brain and spinal marrow were healthy. The muscles f the throat and gullet were of a dark violet colour, unlike the other uscles of the body. The lungs were natural—not congested. The right vities of the heart were collapsed and empty, and the left cavities con-ined but little blood. The large vessels were also nearly empty. The leen was congested. The stomach was half full of a mass of partly gested food: the mucous membrane was pale, firm, and softened, and hen minutely examined by a lens, was found to be perfectly natural. The ucous membrane of the whole of the intestinal canal was in the same althy state. The *kidneys were healthy* and not congested. The spinal

marrow was especially examined throughout its whole extent, as well as the roots of the spinal nerves. It was cut into in various directions: and in no part did it present any appearance deviating from the healthy condition. So far as appearances went, there was no visible cause of death in this case of an adult, healthy man, dying in less than four hours from a large dose of this poison, and obviously from its immediate effects. In this respect, strychnine resembles some other alkaloidal poisons. (Horn's 'Vierteljahrsschr.' Juli, 1864, p. 28.)

Casper considers the peculiar colour of the muscles of the throat and gullet, as worthy of notice. This was the only deviation from the ordinary appearances which he had been accustomed to meet with in cases of violent death. If he had no previous experience of the condition of the body in death from strychnine, he had unsurpassed opportunities of observing the appearances in all other kinds of violent death. He was thus in a better condition than others to fix upon any that were really characteristic of poisoning by strychnine. Although the examination of a dead body is thus proved to throw but little light upon the question of death from strychnine, still a medical jurist has in the symptoms—their mode of occurrence and progress—sufficient data for a safe opinion.

Quantity required to destroy life.—The medicinal dose of strychnine for an adult ranges from 1–30th to 1–12th of a grain. The 1–16th of a grain is an average dose. This quantity has operated as a poison on a child. It caused the death of a child between two and three years of age in four hours. Three quarters of a grain killed a child, æt. 7½, in half an hour. ('Ann. d'Hyg.' 1861, 1, 133.) In two cases of adults, in each of which a quarter of a grain had been taken by mistake, the patients recovered only under early treatment. ('Lancet,' July 26, 1856, pp. 107, 117.) The smallest fatal dose in an adult was in the case of *Dr. Warner*. *Half a grain* of the sulphate of strychnine here destroyed life. ('On Poisoning by Strychnia,' pp. 138, 139.) So powerful are the effects of this drug in certain cases, that ordinary medicinal doses can scarcely be borne. A gentleman took 1–20th of a grain of strychnine in six doses during a period of two or three days. Severe fits of tetanus occurred, although half a grain had not been taken altogether. It is probable in such cases that elimination is either arrested or imperfectly performed. Tweedie prescribed pills for a gentleman, each containing 1–15th of a grain of strychnine. He took altogether five of them, or one-third of a grain, at intervals. The patient was seized with alarming tetanic convulsions, continuing for some time. There was also opisthotonos of a severe kind. He slowly recovered. A *fatal dose* of strychnine for an adult may be assigned at from half a grain to two grains.

As in other cases of poisoning, many recoveries have taken place, even after large doses of strychnine have been taken. There are at least three instances on record in which persons have recovered after taking one grain. A case of recovery from two to three grains is reported. ('Lancet' 1861, II. p. 169.) A girl recovered in six or seven hours from a dose of *four grains* of strychnine. (Ibid. 1863, I. p. 134.) When first seen, she was sensible, and while talking was suddenly seized with the usual tetanic symptoms—opisthotonos, concave contraction of the hands and feet, the muscles rigid, the eyes natural, the pulsations of the heart considerably increased, the respiration difficult, and great fear of death. She had only three paroxysms, and to this probably her recovery was due, as her system was not exhausted by severe and frequent convulsive attacks. There is one instance reported in which a person is said to have recovered from a dose of seven grains of strychnine ('Med. Gaz.' vol. 41, p. 305). In

erence to this alleged recovery from large doses, it may be a question ether the strychnine was not mixed with some other substance, whereby poisonous properties were weakened. Instances of recovery from doses above one or two grains must be regarded as exceptional.

With respect to *nux vomica*, three grains of the alcoholic extract have troyed life. The smallest fatal dose of the powder was in a case reported Hoffmann, and quoted by Christison, also by Trail ('Outlines,' p. 137). *irty grains* of the powder, given in two doses of fifteen grains each, ved fatal. The poison was given by mistake for bark to a patient ouring under quartan fever. This is about equivalent to the weight of full-sized seed, and to only one-third of a grain of strychnine. The e of nux vomica required to destroy life became of some importance *Reg.* v. *Wren* (Winchester Spring Ass. 1851). The prisoner was victed of an attempt to administer this poison in milk; the quantity arated from the milk amounted to forty-seven grains, which was above atal dose. The intense bitterness which the nux vomica gave to the k led to detection, and this would, in general, be a bar to the criminal ministration of this poison, except in the form of extract in pills. The tor has known strychnine to be administered, criminally, in cocoa; and in eggs, in tea, and on bread and butter. A female recovered after ing two drachms of nux vomica. ('Lancet,' Dec. 15, 1849.)

Period at which death takes place.—In fatal cases death generally takes ce within two hours after the taking of the strychnine. In the case of *rner* the symptoms commenced in five minutes, and he was dead in nty minutes. On the other hand, in the case of *J. P. Cook*, the symptoms not commence until fifty-five minutes after the poison was taken, but case terminated fatally in twenty minutes after their commencement. 1870, two deaths are reported to have occurred at Ypres in Belgium, which strychnine proved more rapidly fatal than in the cases of Warner l Cook. *M. Merghelynk* took in pills seven grains and a half of at he supposed to be hydrochlorate of quinine. Violent convulsions ne on, and he died in a quarter of an hour. His wife, not suspecting thing wrong, took a similar dose and died in *ten minutes*. A pill con- ing a grain and a half was given to a dog, which died under the usual nptoms of poisoning by strychnine. The supposed hydrochlorate of nine was then examined, and it was found to be largely mixed with strych- e. The case of *Madame Merghelynk* is, with one exception, the most id on record. Gray refers to a case which proved fatal in five minutes. TRYCHNINE,' 1872, p. 55.) One of the longest cases for duration was t of an adult, who died in *six hours* from a dose of three grains of chnine. ('Guy's Hosp. Rep.' 1857, p. 483.) In 1876, a case was tried g. v. *Silas Barlow*, alias *Silas Smith*, C. C. C. Nov. 1876), in which the oner was convicted for the murder of a woman with whom he cohabited means of strychnine. The poison was administered in the form of min killer, given in decoction of sarsaparilla. The woman lived about hours and three-quarters after taking the poison. No strychnine was nd in the body of the deceased. ('Pharm. Jour.' 1876, Dec. 2, p. 467.) poisoning by *nox vomica*, death usually occurs within two hours; Christison mentions a case in which a man died in *fifteen minutes* r taking a dose (op. cit. p. 898). This is probably the shortest period wn. There are several instances of recovery on record, even after ge doses.

Vermin and Insect Killers.—Although it is difficult to procure strych- e at a druggist's shop, it is extensively sold to the public under the ne of Vermin Killers, in threepenny and sixpenny packets. *Butler's min Killer* consists of a mixture of flour, soot, and strychnine. The

author found the sixpenny packet to weigh about a drachm, and to contain from two to three grains of strychnine. As the poison is mechanically mixed with the other ingredients, and is manufactured on a large scale, the proportion of strychnine is liable to variation. By the aid of a lens, the poison may be sometimes seen scattered in white particles through the coloured powder. The threepenny packet contains about half the quantity of strychnine, but, as it will be seen, quite sufficient to destroy the life of an adult. In place of soot, Prussian blue is sometimes used as a colouring substance. The editor finds that there are two kinds of Butler's Vermin Killer in commerce: in one the poisonous ingredient is barium carbonate (carbonate of baryta), and in the other strychnine. A sixpenny packet of the latter weighed (1882) forty-two grains, and yielded two grains and a quarter of strychnine. Another sixpenny packet weighed sixty-two grains, and contained one grain and three-quarters of strychnine. *Battle's Vermin Killer* is a powder similar to that of Butler, containing a fatal proportion of strychnine, as it is sold in packets. These powders are a fertile source of poisoning either through accident or design. In *Reg.* v. *Vamplew* (Lincoln Autumn Ass. 1862), it was proved that the prisoner, a girl under 13 years of age, had purchased one of these powders at a village shop and had destroyed her master's infant with it. There was also reason to believe that this girl had destroyed two infants by similar poisons in two other families where she had acted as nurse. They had all died suddenly in fits. A similar powder purchased for threepence at the same shop consisted of about thirteen grains of flour, coloured with Prussian blue and mixed with three-quarters of a grain of strychnine. Another Battle's powder, purchased in London for threepence, weighed like this about thirteen grains, and a sixpenny packet weighed twenty-three grains. The editor found (1882) a threepenny packet of Battle's Vermin Killer to weigh twelve grains, and to contain one grain and a quarter of strychnine; and a sixpenny packet weighed twenty-five grains, and contained two grains and a half of strychnine. These vermin killers have caused death in numberless instances. A few years ago the facility with which these poisons were sold to the public by grocers, oilmen, and others, led to their being scheduled under the Pharmacy Act, 1868; so that they can now only be legally procured from registered chemists and druggists, and with registration of the sale in a 'Poisons Book' kept for the purpose. It would be easy to add many fatal cases which have fallen within our own knowledge; but they present nothing out of the usual course. The persons have all died under the ordinary symptoms of poisoning by strychnine, in a well-marked form. The appearances in the body were similar to those seen in death from strychnine: but there is one caution to be given in reference to the examination of the stomach. As death is commonly rapid and there is no vomiting, the colouring matter, either soot or Prussian blue, should always be sought for in the stomach. Strychnine may or may not be found, according to the amount swallowed and the degree to which absorption has gone on during life. Some cases of recovery are reported. In 1859, a man recovered after taking a whole packet containing nearly three grains of strychnine ('Ed. Month. Jour.' 1859, vol. 2, p. 507); and in 1860, Part met with an instance of recovery in which a girl took half a packet. In these cases the favourable results were probably due to vomiting excited by emetics. In 1880 six deaths were registered in England and Wales from strychnine, and nineteen from vermin killers.


Analysis.—*Nux vomica* is well known as a flat round kernel, about the size of a shilling, covered with radiating silky fibres, and slightly raised in the centre (figs. 64 and 65). It is of a light brown colour. It is very hard, brittle, tough, and difficult to pulverize. The powder is of a

brown colour, like that of liquorice or jalap: it is sometimes met in a coarsely rasped state; it has an intensely bitter taste. It yields ter and alcohol, strychnine, ine, igasuric or strychnic and some common vege- principles. Heated on num-foil, it burns with a w smoky flame. Nitric acid s it of a dark orange-red ır, which is destroyed by ıous chloride. These pro- es are sufficient to distin- ı it from various medicinal lers which it resembles. In one case of poisoning by this substance ·. v. *Wren*) a quantity of guaiacum powder was mixed with the nux ica. This so completely changed the action of nitric acid, as in the instance to create some difficulty in identifying the substance. The ıst must be prepared for these admixtures or adulterations.

Fig. 64.




Fig. 65.



Seeds of Nux Vomica, natural size. *a*. convex surface; *b*. concave surface; *c*. hilum or umbilicus.


The aqueous *infusion* or *decoction* is reddened by nitric acid, and is y precipitated by tincture of galls. Ferric sulphate gives with it an -green tint. The fine silky fibres or hairs which cover the surface of seed may be obtained by washing the residue of the powder in the ach, or the sediment of any liquid with which the nux vomica may ı been mixed. They present a characteristic appearance under the oscope (fig. 67). As in other poisonous seeds or roots, the strychnine owly removed from the powder by the absorbent vessels of the stomach, carried into the blood, until that liquid is sufficiently impregnated with

Fig. 66.



Magnified view of a section of Nux Vomica, showing the hairs projecting from the surface (Pereira).

Fig. 67.



Hairs of Nux Vomica, magnified 124 diameters.


poison to produce symptoms. The powder itself remains, as it is unable by the fluids of the stomach. Strychnine may be extracted from vomica by Stas's process, described at p. 439.

Strychnine.—This alkaloid may be readily obtained crystallized from an nolic solution. The crystals are very small, and their form is subject reat variation, according to the strength of the solution, the rapidity lowness of evaporation, the presence of foreign matters, &c. It is monly seen in octahedra, sometimes lengthened into prisms, bevelled he ends, and crossing each other at angles of 60°. (See fig. 68, 38.) There are as many as six or eight varieties of crystals, so that nuch importance must not be attached to their form. When strych- is procured from the solutions of its salts by the addition of ammonia, usually deposited in long slender prisms. (Fig. 69, p. 438.)

. Strychnine *is white, of an intensely* bitter taste, even when it forms

only 1–30,000th part of a solution. 2. When strongly heated on platinum it melts, and burns like a resin with a black smoky flame; in a close tube it yields ammonia. 3. It is not perceptibly dissolved by cold water: requires 7000 parts for its solution. 4. It is easily dissolved by acids, and is precipitated from the concentrated solutions by potash or ammonia.

Fig. 68.



Various forms of Crystals of Strychnine, as they were obtained from an alcoholic solution, magnified 124 diameters.

Fig. 69.



Crystals of Strychnine, obtained by adding ammonia to the sulphate, magnified 124 diameters.

both of which it is insoluble. 5. Strong nitric acid imparts to commercial strychnine a pale reddish colour, owing to the presence of brucine. 6. Sulphuric acid produces no apparent change in it: but when to the mixture a small crystal of potassium bichromate, of potassium ferricyanide, or a small quantity of black oxide of manganese or of peroxide of lead is added, series of beautiful blue, violet, and purple colours appear, which pass rapidly to a light red tint. Among these substances black oxide of manganese will be found preferable. By reason of its insolubility, it imparts no colour to the liquid if strychnine is absent; and if the alkaloid is present it slowly brings out the colours, so that there is time to make full observation. The hydrated or precipitated oxide may be used in place of the anhydrous compound. Permanganate of potash has been recommended as a substitute for the oxide, but it is objectionable on account of its solubility, and of its being already coloured. Letheby suggested the use of a small galvanic battery for the production of the coloured reaction. In this case sulphuric acid only is required. It presents no practical advantage over the use of oxide of manganese. 7. Sulphomolybdic and iodic acids produce no change of colour in strychnine, and thus distinguish it from morphia.

The salts of strychnine are very soluble in water, and these solutions give crystalline precipitates, with a large number of substances. The alkalies and alkaline carbonates, if diluted, precipitate the alkaloid in slender prisms (see fig. 69). Potassium sulphocyanate, potassium ferricyanide, sodium nitroprusside, and potassium chromate furnish with it well-defined prismatic crystallizations. In the last case the crystals are stellated and of a yellow colour. Two of these groups will be found delineated in the annexed illustrations. (Figs. 70 and 71.) The chromate of strychnine may be also produced by adding red chromate of potash to a dialysed liquid containing strychnine. On draining the crystals, drying them, and adding sulphuric acid, the colour reactions are at once brought out. Picric (carbazotic) acid, is even a more delicate precipitant of a solution of strychnine. It gives small tufts or groups of stellated crystals. Sulphocyanate of strychnine in crystals may be produced in solutions containing not less than 1–7000th part of strychnine. Filhol recommends as delicate precipitants of solutions of strychnine, chlorine and auric chloride,


ing care that there is no alcohol in the liquid to be tested. Auric oride slowly precipitates in a crystalline form even the 1–650th part a grain of strychnine. When these precipitates, drained of water, treated with concentrated sulphuric acid, they are dissolved, and to

Fig. 70.



Crystals of Sulphocyanate of Strychnine, magnified 124 diameters.

Fig. 71.




Crystals of Chromate of Strychnine, magnified 124 diameters.

a mixture a crystal of red chromate of potash may be added to bring the blue colouration peculiar to strychnine.

Strychnine has been fatally mistaken for santonin ('Lancet,' 1870, I. 598), salicin, and jalapin, and has caused death on several occasions. apin does not crystallize, and the crystalline forms of santonin and cin are, as shown by the annexed illustrations (figs. 72 and 73), very erent from those of strychnine.


These two vegetable principles differ from strychnine in their pro-ties. When heated in close tubes, they give off *acid* vapours. Salicin

Fig. 72.



Crystals of Salicin, magnified 124 diameters.

Fig. 73.



Crystals of Santonin, magnified 124 diameters.

soluble in water. Santonin is not soluble in water, but is dissolved by ohol. Tannic acid and the chloriodide of potassium and mercury do not cipitate the solutions, while they readily precipitate those of strychnine. ric acid has no effect upon either, while sulphuric acid, which does not nge santonin, gives a pink colour to salicin. The crystals of santonin ely resemble, in microscopical appearance, those of salicin, but they are inguished from salicin and from alkaloids by acquiring a brilliant low colour on exposure to sunlight, without undergoing any change of n.

In *Organic mixtures* the process suggested by Stas, but somewhat modified, enerally preferred for the separation of this poison. The principle of its ration consists in dissolving the strychnine by a gentle heat out of the ue or organ *previously pulped or* finely cut up, by means of rectified spirit

of wine mixed with a small quantity of tartaric acid. The liquid is strained, and the residue well pressed and washed with alcohol: the acid solution of strychnine thus obtained is evaporated at a low temperature to dryness. The residue is exhausted with absolute alcohol, filtered, and the filtrate again evaporated to dryness at a low temperature. The residue is now taken up with water, filtered, and the liquid is neutralized by an alkali—potash or ammonia—the latter being in some respects preferable, and a slight excess of alkali is added. The alkaline liquid is then shaken in a long stoppered tube, with twice its volume of ether or chloroform, or a mixture consisting of four parts of ether and one of chloroform. These liquids dissolve the strychnine set free by the alkali. The ethereal solution is separated from the watery liquid by a pipette or by a stoppered tube, and submitted to spontaneous evaporation, when, if strychnine is present, the alkaloid will be obtained, but generally associated with oily and other organic matters, which interfere with the production of crystals. The impure residue left by the ether is heated in a water-bath, with a few drops of strong sulphuric acid: this destroys the organic matter without materially affecting the strychnine. Water is added, and the acid liquid is filtered through paper, neutralized by ammonia, and again treated with ether, when strychnine will be obtained in small and slender prisms. The crystals, after an examination by the microscope (see fig. 69, p. 438), are treated with sulphuric acid and black oxide of manganese, and the colour reactions of strychnine, if the alkaloid is present, will then appear. By this method strychnine has been detected in the liver of a person who died from this poison, although the organ was in a highly putrescent state. The process of dialysis (p. 216) will allow of the separation of strychnine when combined with acids and in a state of solution, from blood, mucus, and other viscid organic matters found in the stomach. The liquid containing the salt of strychnine may be tested by evaporating a few drops and applying the colour test. If thus found to be present, it may be neutralized by ammonia or potash and shaken with ether or chloroform in order to obtain pure strychnine. The dialytic process of separation has been successfully carried out by Gray. The reader will find in his essay on strychnine a full account of the method of employing this process for the detection of the poison in organic liquids and the best modes of applying the tests. ('STRYCHNIA,' by St. Clair Gray, Glasgow, 1872, p. 75.) In all cases the physiological test should be used to supplement the chemical tests for strychnine. A frog may be employed for this purpose.

The reader will find an account of the processes for strychnine in organic solids and liquids in some papers published by Wormley, in his 'Micro-Chemistry of Poisons,' New York, 1867, p. 534. He describes a case in which, from a misapplication of the process, strychnine was sworn to be present, when, from the chemical method pursued, the alkaloid could not possibly have been separated; and two instances fell within the author's own knowledge, where the colours produced by sulphuric acid and potassium bichromate, on the concentrated and dry organic contents of the stomach, were referred to strychnine, when they were really due to the decomposition of the salt employed in contact with organic matter. The detection of this poison in the stomach or the tissues, will depend on the same conditions as those observed in other cases of poisoning. If a person takes a large dose and dies quickly, a residuary portion may be readily found. In *Reg.* v. *Burke* (Clonmel Summer Ass. 1862), the prisoner administered strychnine to his wife in Epsom salts. She died in about half an hour under the usual symptoms. More than three grains of the poison was extracted from the contents of the stomach. If a small dose has been taken, and the person has survived some hours, it is possible that none

ll remain in the stomach. A decomposed state of the viscera and their ntents does not appear to interfere with the detection of this poison. It s been suggested that the presence of morphia counteracts the colour ts: but unless in admixture with the strychnine in large proportion, this not probable. Besides, in Stas's process, the morphia is scarcely dissolved the ether.

Persons have died from strychnine, and no trace of the poison has been nd in the body. In a case of poisoning by this alkaloid, which was the bject of a trial for murder in 1861, Reese made separate analysis of the ntents of the stomach and the contents of the intestines, as well as of e tissues, and each one of these was repeated to avoid error. Yet there as no evidence of the presence of strychnine by the bitter taste of the al extract, or by the colour tests. The witness, by a comparative experiment, satisfied himself that he could detect the half-millionth of a grain Amer. Jour. Med. Sci.' Oct. 1861), but in this power of detecting so small quantity of strychnine in a pure state he had already been anticipated by opney ('Pharm. Jour.' July, 1856. p. 24). In Reese's case, the quantity ken was unknown, the woman lived five or six hours, and the body was ot examined until six weeks after death. A small but fatal dose, and the uration of the case, will sufficiently account for the negative results with ut resorting to any other hypothesis. In the case of *Mrs. Salter*, who died om a dose of strychnine in 1869, death probably took place within two or hree hours, but the most careful examination made of the stomach and iver by Horsley, led to a negative result. Strychnine, in the opinion of ll the medical witnesses, was the cause of death, but no trace of strychnine ould be detected in the body by one well qualified to detect it. There was me reason to think that the poison had been taken in solution, but even nder these circumstances it must have been rapidly absorbed, diffused, nd eliminated. In the case of *Silas Barlow* (see p. 435) Bernays found o strychnine in the body. The woman had survived the administration f the poison nearly six hours.

When death has been caused by small doses applied under the skin, the oison may not be found in the tissues. The following experiment was erformed in May, 1864. One-eighth of a grain of acetate of strychnine n coarse powder was placed in the cellular membrane of the neck of a abbit. In nine minutes the animal was seized with a sudden convulsion nd fell on its side: its fore and hind legs were rigidly stretched out, and s body passed into a state of opisthotonos. It had a succession of fits, and ied in one of them in twenty minutes after the commencement of the ymptoms. One-half of the powdered acetate was still found in the wound, howing that the rabbit had been killed by the 1–16th of a grain. Of course he *residuary* strychnine was easily detected in the wound: it was plainly isible to the eye. On applying Stas's process to the heart, as well as the lood and the liver, the tests failed to indicate the slightest trace of the lkaloid. The ethereal liquid left no crystalline residue of any kind. This esult does not show that strychnine is not absorbed, but it proves that nder certain conditions it has not been detected in the organs of the body, n cases in which, beyond all doubt, it has destroyed life. In instances in hich death has been caused by nux vomica, which contains only one per ent. of he poisonous alkaloid, strychnine has not been found deposited in he tissues.

The following case shows the rapidity with which the poison may be iffused and deposited in the tissues, when a large dose has been taken. A trong healthy man, æt. 43, placed upon his dry tongue, at 10 P.M., a owder which contained six grains of Dover's powder and *five grains* of trychnine (*dispensed by mistake for* five grains of James's powder). He

complained of a bitter taste, asked for an orange, and he found, on sucking this, that it increased the bitterness—the acid juices of the orange dissolved the strychnine, and thus favoured its early absorption. In fifteen minutes he went to bed—twitchings of the muscles then came on, and the patient, from previous experience in taking strychnine as a medicine, was fully aware of the cause of the symptoms. He complained of his bowels being drawn up; he drew his knees up as if to his mouth, gave a yell, seized a friend who was standing by, and became apparently unconscious (exhausted) for about five minutes. He then revived, but in a few minutes was again seized with a violent convulsion of a tetanic character, and he died in two or three minutes afterwards, a little over half an hour after taking the powder. Owing to a spasmodic closure of the jaws, he was able to speak only for a few minutes at a time; he was rational, but seemed to be in great terror. An inspection was made thirty-six hours after death, when the body was found to be unusually warm. The back and lower parts were much discoloured, but the discolouration was easily removed by pressure, indicating a fluid state of the blood. The lower jaw was slightly drawn up, the body straight, not arched; the fingers slightly flexed, not clenched; the thumbs were fixed, but not bent into the palms of the hands. On opening the head, the scalp was found very much gorged with fluid blood. The membranes of the brain were also much congested, as well as the blood-vessels of the brain generally. There was no clot or coagulum, but a quantity of serous fluid escaped from the surface. There was no softening of the substance of the brain or spinal cord. The lungs were healthy, but dark-coloured from engorgement with blood; the heart was empty, and its structure was soft; the liver was healthy; the spleen was gorged with fluid blood; the kidneys were congested. The other organs presented no appearance calling for notice. Edwards found strychnine in the stomach, the quantity being estimated at about one grain. He also found the poison in the tongue and the liver. He sent to the author a portion of the liver, one kidney, and six ounces of blood. They were in a putrescent state, and when examined about three months after death, eight ounces of the liver yielded, by the process above described, prismatic crystals of strychnine, producing the usual colour-reactions with sulphuric acid and peroxide of manganese, as well as with potassium bichromate. The quantity of strychnine thus obtained was small. The kidney and the blood did not give results on which any reliance could be placed. This case shows that a large dose of strychnine rendered soluble will destroy life in half an hour—that within this short time four-fifths may be removed from the stomach, or at least not be discoverable there by careful chemical analysis after death—that in half an hour the poison may be distributed through the body and deposited in the soft organs, although no satisfactory evidence of its presence could be obtained from less than half a pound of animal matter. The strychnine found in the tongue was probably a portion of the powder swallowed, which still remained there. It may be further remarked that, although the deceased took in the powder 6–10ths of a grain of opium, no morphia was present in the crystalline residue obtained from the liver. (For additional facts and cases connected with this question, see 'Guy's Hosp. Rep.' Oct. 1856, p. 326, and 'On Poisons,' 2nd edit. 1859, pp. 70, 788.)

In Casper's case (p. 433) the deceased admitted that he had taken between five and six grains of strychnine. He lived three hours and a half, and on analysis Sonnenschein procured from the stomach three grains of the poison. He did not, however, succeed in extracting any from the blood or tissues.

In those inspections in which there has been such criminal interference, or culpable neglect, as in that of *J. P. Cook*, the only course for an analyst

to seek for the poison in the tissues. This case settled nothing in erence to the presence or absence of strychnine in the body of a person soned by this substance. Except the actual destruction of the stomach lf, everything had been done which could be done in order to render hemical analysis fruitless. It cannot therefore be taken as a fair cedent in any sense for the results of a proper medico-legal research oisoning by strychnine. In an analysis of this case by Casper (Horn's ierteljahrsch.' Juli, 1864, p. 26), not only are the chemical results arded as negative, by reason of the gross mismanagement of those o inspected the body, but the *post-mortem* appearances themselves, for imilar reason, are considered as throwing no light upon the effects of rchnine on the body. One of the medical witnesses for Palmer could in the whole case nothing but angina pectoris, another only epilepsy, h 'tetanic complications,' and a third admitted death from poison, but from strychnine. Assuming that there had not been a criminal inter- ence with the dead body on the part of the prisoner *Palmer*, the position amed—that strychnine, if a cause of death, must always, and under all cumstances, be found in the dead body, is incorrect. Its detection in body, properly verified, is a proof that it has been taken; the symptoms their commencement, progress, and termination will furnish irrefragable oof that it has acted as a poison; but its non-detection does not prove at it has not destroyed life, or, in the words of Casper, 'Das Nichtauffinden s Giftes allein kann, aber niemals einen Gegenbeweis abgehen.'

For a more complete history of the *medical* facts in the memorable se of *Cook*, the author referred the reader to a paper on 'Poisoning by rychnia,' 'Guy's Hosp. Rep.' 1856; 'Pharm. Jour.' July, 1856, p. 6 rom the pen of the late Jacob Bell). The most able legal analysis of it any English writer which the author saw, was published by Stephen, his 'General View of the Criminal Law of England,' 1863, p. 357. Of e foreign reports, one by Tardieu in the 'Ann. d'Hyg.' for 1856, 2, 1, and 1857, 1, 132, and the other by Casper in Horn's 'Viertel- hrsschr. für ger. Med.' &c., 1864, 2, p. 1, are the most correct in their edical and medico-legal details.

The editor of this (third) edition of this work believes that much smaller antities of strychnine may be detected when mixed with organic matters an the author (Dr. Taylor) admitted; and that, with improved methods analysis, which cannot here be given in detail, strychnine can hardly il to be detected in the body in any case of poisoning by this alkaloid roving fatal within a couple of hours. As a rule, it may be readily tected in the urine during the course of a case of strychnine poisoning; id also when the alkaloid is only being given in ordinary medicinal doses. hat strychnine is absorbed into the blood unchanged is incontestably roved by the experiments of Vulpian, who killed a dog by transfusing to its veins the blood of another strychnized animal.

Strychnine in Organic Solids.—From the vermin killers of Butler and attle, the strychnine may generally be readily separated by means of cohol, and procured in a crystalline form for the application of tests. If e vermin killer is coloured with Prussian blue, one or two drops of lphuric acid will remove the colour from the separated alkaloid, and ack oxide of manganese may be added. The colour reactions are then well marked as with pure strychnine.

The alkaloids strychnine and brucine may be detected in the powder of ix vomica by the following process:—Digest the powder in a small antity of diluted sulphuric acid by a water-bath heat. The substance ould be well stirred with the diluted acid, which, after a short time, mpletely *carbonizes it. The mass* is heated to dryness, then treated with


a small quantity of distilled water and filtered, by which an acid liquid of a pale sherry colour is obtained. On neutralizing this liquid with potash or ammonia, and agitating it with two volumes of ether, the strychnine is separated, and may be obtained crystallized by the evaporation of the ethereal solution. The strychnine may also be obtained by dialysis. Ten grains of nux vomica, equal to 1–10th grain of strychnine, gave satisfactory results. Prismatic crystals were procured which gave the appropriate reactions with the colour tests. Brucine was also detected by the action of nitric acid on the crystals.

In cases in which the poison is contained in pills or powders, having much organic matter soluble in alcohol, it will be advisable to employ either dilute or concentrated sulphuric acid. It is a remarkable fact that strychnine itself is not acted on in the same degree by sulphuric acid as ordinary organic matters, or even other poisonous alkaloids.

Brucine or Brucia.

Brucine is an alkaloid generally associated with strychnine. It is contained in the seeds of nux vomica, and more abundantly in the bark of the tree. It is not so powerful a poison as strychnine, but the symptoms which it produces are similar. It is considered to have from 1–12th to 1–40th the strength of strychnine. It is not affected by the colour-tests employed for the detection of strychnine, and it acquires an intense red colour on the addition of nitric acid, and this is changed to a violet on the addition of stannous chloride. It is more soluble in water than strychnine, and has a bitter taste. Hydrochloric and iodic acids produce in it no change, either in the cold or when heated. Sulphuric acid gives to it a pink red colour without carbonizing it, probably owing to the presence of a trace of nitric acid in the acid; sulphomolybdic acid does the same, but the red colour changes to greenish-brown and ultimately to blue-black. The sulphate of brucine crystallizes in well-defined prisms truncated at the ends. They are larger and longer than the prisms of strychnine.

Fig. 74.



Crystals of Sulphate of Brucine, magnified 124 diameters.

(CEREBRO-SPINAL AND CARDIAC POISONS.)

CHAPTER 31.

CONIUM MACULATUM. HEMLOCK—CONIA—CICUTA VIROSA—ŒNANTHE CROCATA —WATER-PARSNIP—ETHUSA CYNAPIUM—LOBELIA—FOXGLOVE—DIGITALIN. ACONITE, OR MONKSHOOD. ACONITINE.

Common or Spotted Hemlock (conium maculatum).

This is a well-known hedge-plant, which grows abundantly in most parts of Great Britain. Its poisonous properties reside in the seeds, leaves, and roots.

Symptoms and Effects.—The effects produced by hemlock have not been uniform; in some instances there have been stupor, coma, and slight convulsions; while in other cases, the action of the poison has been chiefly

ifested on the spinal marrow—*i.e.* it has produced paralysis of the cular system. The poisonous effects usually set in early and advance ewhat rapidly. A peculiar muscular debility sets in; the lower limbs me weak, and eventually paralyzed; the paralysis advances upwards, tually reaching the respiratory muscles. There is dyspnœa, anxiety ie region of the heart, and towards the close of life convulsions, con- isness being previously intact. The pupils are dilated, though not to same extent as when a solanaceous plant has been taken. When the iration is affected there is marked blueness of the surface of the body. an ate a large quantity of hemlock-plant, by mistake for parsley. In fifteen to twenty minutes there was loss of power in the lower ex- ities: but he apparently suffered no pain. In walking, he staggered f he was drunk; at length his limbs refused to support him, and he

On being raised, his legs dragged after him, and when his arms e lifted they fell like inert masses, and remained immovable. There complete paralysis of the upper and lower extremities within two hours r he had taken the poison. There was a loss of the power of swallow- and a partial paralysis of sensation, no convulsions, but only slight sional motions of the left leg; the pupils were fixed. Three hours r eating the hemlock, the respiratory movements had ceased. Death c place in three hours and a quarter; it was evidently caused by gradual hyxia from paralysis of the muscles of respiration; but the intellect perfectly clear until shortly before death. On inspection, there was ht serous effusion beneath the arachnoid membrane. The substance the brain was soft; on section there were numerous bloody points, the organ was otherwise healthy. The lungs were gorged with dark d blood; the heart was soft and flabby. The stomach contained a en-coloured pulpy mass resembling parsley. The mucous coat was ch congested, especially at its greater end. Here there were numerous ravasations of dark blood below the membrane, over a space of about size of the hand. The intestines were healthy, here and there present- patches of congestion in the mucous coat. The blood, throughout the ly, was fluid and of a dark colour. A portion of the green vegetable lp was identified as part of the leaves of the *Conium maculatum*. Some the leaves bruised in a mortar with a solution of potash, gave out the culiar odour of the alkaloid conia. ('Ed. Med. and S. J.' July, 1845, 169.)

In a case which was the subject of a trial for murder (*Reg.* v. *Bowyer*, swich Sum. Ass. 1848), the child died in one hour after swallowing part a teacupful of a decoction of hemlock, alleged to have been administered the mother. The child sipped the decoction, until it lost the power of lding the cup; it became insensible and paralyzed, and died in the chair a sitting posture. There were no morbid appearances, and no hemlock aves were found in the stomach, these having subsided in the cup. The ild had been poisoned by the upper stratum of clear liquid. The mother as acquitted for want of proof of administration, the death of the child aving taken place in secrecy.

A medical electrician suffering from facial spasm took, beginning four urs after the last of a previous series of divided doses of a fluid extract conium amounting in the aggregate to one hundred and eighty drops, at 10, 4.40, and 5.15 P.M., fifty minims (one hundred and fifty in all) of Squibb's Fluid Extract.' The first dose produced dizziness and muscular laxation; the second, great muscular weakness, inability to stand, and ickening of speech, without relief of the spasm; the third, immediately, me nausea, and tremors about the chest. At 6.10 P.M. there were nausea, tense muscular weakness, *partial* dropping of the eyelid (ptosis, a common

symptom), double vision, and great difficulty of speech. The pulse was 60. Shortly after this he became unable either to speak or to swallow. He made signs for electricity, and, on being asked whether the direct or the faradic current, indicated the latter, and also the place of application of the electrodes, but was unable to hold one of the latter. Shortly after this he dropped back dead. ('The Sanitarian,' June, 1875.)

Analysis.—Hemlock is known from most other plants which resemble it by its large round smooth stem, with dark purple spots. The leaves are of a dark-green colour, smooth and shining. Every portion of the plant has a peculiar and disagreeable smell when rubbed or bruised, resembling cat's urine, or, according to some, the odour of mice. It is strongly brought out when the stem, leaves, or seeds are rubbed with a solution of caustic potash. We subjoin an illustration of the *seeds* of hemlock, which are peculiar in their form, and are easily distinguished from the seeds of other umbelliferous plants (fig. 75). A person may be poisoned by decoction of *leaves* of hemlock, and no leaves be found in the stomach or bowels (case of *Bowyer*, p. 445), but the stomach had been emptied and the contents lost, and hence no trace of conia was found. The prisoner first gathered the *Anthriscus sylvestris* by mistake for *Conium maculatum*, but it was proved that she had afterwards gathered the leaves of hemlock. A leaf of each of these plants was copied by photography, and produced as evidence in Court.

As the determination of the presence of fragments of leaves in poisoned liquids, and in the contents of a stomach, may be of importance in evidence, an illustration of hemlock-leaves, engraved from a photograph of the living plant (fig. 76) is subjoined. The appearance and smell of the

Fig. 75.



a. Seed of Hemlock, natural size.
b. The same, magnified 20 diameters.
c. Group of seeds.

Fig. 76.



Leaf of Common Hemlock.

leaves, either when bruised or when rubbed with a solution of potash, will greatly aid a medical witness in forming a judgment, as there are many umbelliferæ which bear a close resemblance to hemlock in the form of their leaves. Among these is common parsley. It is hardly credible that a mistake of this kind should be made, yet through carelessness and ignorance accidents have occurred. In 1864, a lady and two of her children were seized with symptoms of poisoning soon after dinner. The medical men who were called in examined the remains of some soup which had been eaten, and they detected fragments of the leaves of hemlock

ongst the herbs which had been used to flavour the soup. Under atment, the symptoms abated in a few hours, but these persons did entirely recover until after two or three days. It turned out that hemlock had been gathered in the garden belonging to the family, ere it was growing side by side with parsley. As the parsley was ed from seed, it is probable that hemlock-seed had been accidentally ed with it by the seedsman, and thus the accident had occurred. subjoin an illustration from a photograph of a leaf of parsley; also strations of the seeds, by which the differences between hemlock and aley will be at once apparent (figs. 77 and 78).

CONIA.—The alkaloid of hemlock is known under the names of conia, niine, conine, conicine, and conicina. It resembles nicotine and ammonia its liquidity, alkalinity, volatile reaction, and in some of its chemical operties. It is a liquid of oily consistency, usually of a pale yellow lour, but is colourless when freshly prepared, powerfully alkaline, and s, when its vapour is diluted, a smell resembling that of mice, and an rid bitter taste. It gives a volatile greasy stain to paper, and burns ith a yellow flame and thick smoke. 1. It is not coloured or affected by itric, sulphuric, or hydrochloric acid; the last-mentioned acid produces

Fig. 77.



Leaves of Garden Parsley, from a photograph.

Fig. 78.



Seeds of Garden Parsley.
a. Natural size.
b. Magnified.

ith it dense white fumes of hydrochlorate of conia, and on heating the ixture, this salt remains in prismatic crystals. 2. It is not dissolved by ater, but floats on it in oily globules. 3. It is soluble in alcohol and ther, and this last-mentioned liquid removes it from its aqueous solution, nd leaves it in oily globules on evaporation. 4. It gives a white precipitate ith corrosive sublimate, and a yellow precipitate with arsenio-nitrate of ilver. 5. It precipitates brown oxide of silver from the nitrate; this is ot dissolved by an excess, but the oxide is blackened and reduced. Iodine water gives a reddish-brown precipitate, which is redissolved; n excess of iodine water causes a yellowish precipitate. 7. It gives a ellow crystalline precipitate with chloride of gold, but no precipitate with latinic chloride. 8. Tannic acid precipitates it of a dingy white. Gallic acid gives no precipitate, but slowly acquires a yellowish colour. s odour and insolubility in water, as well as several of the characters bove mentioned, serve to distinguish it from nicotine and ammonia; but may be readily separated from ammonia by the chloriodide of potassium nd mercury, which precipitates it even more completely than tannic acid. reference to its presence in *organic mixtures*, it may be detected by its culiar odour, or by distilling the liquid with a solution of potash and amining the distillate.

The reactions produced by *tests* on small quantities must be confirmed

by evidence of the action of the poison on the body from the symptoms. As in reference to strychnine, veratria, and other alkaloids, an incautious operator may readily come to the conclusion that he has found 'traces,' and ascribe death to the poison. The following case occurred in Germany a few years since. A man died two hours and a half after going to bed, and it was alleged that his wife had poisoned him. The persons commissioned to make the analysis deposed that they had found traces of conia in the stomach, intestines, and kidneys, and they came to the conclusion that the man had died from the effects of hemlock, which implicated his wife in a charge of murder. Some doubt appears to have arisen in the minds of the authorities on this point, and they submitted three questions for the consideration of a Medical College. 1. Is there any reason to doubt whether conia has really been found in the body of deceased? 2. existing in the body, may it have been spontaneously produced, or does it show administration from without? Does its detection in the body incontestably prove that the deceased died from poisoning by conia or hemlock? 3. Is it improbable that deceased poisoned himself with hemlock? The College decided that there was not sufficient evidence to show that death had been caused by hemlock. The matter was then referred to Mitscherlich and Casper, and they found that the chemical processes pursued failed to detect conia in the body—that there was nothing to indicate that deceased had taken hemlock in any form, and that the state of the windpipe sufficiently accounted for the sudden death of deceased. He had eaten and drunk freely, had vomited after going to bed; a portion of the food had entered the trachea and he had been suffocated. (See Casper's 'Vierteljahrsschr.' 1859, p. 194.)

In the year 1861, Dr. Jahn killed his mistress in a few minutes by a dose of ten or fifteen drops of conia. Violent palpitation of the heart was the most prominent symptom. (Husemann, 'Die Pflanzenstoffe,' p. 269.)

Water-Parsnip.


This plant (*Sium latifolium* and *S. angustifolium* or *S. nodiflorum*) is not unlike water-cress, for which it has been eaten by mistake. In 1882, two girls, aged five and three years respectively, died from eating the leaves. The day after these were eaten, the younger child became suddenly ill and died, while the other succumbed two days afterwards. ('Brit. Med. Times,' 1882, II. p. 26.)

Water-Hemlock (Cicuta virosa).

The water-hemlock, or cowbane, has given rise to several fatal accidents, its roots having been mistaken for parsnips. The whole of the plant is poisonous; but the roots are the most active, especially when gathered early or late in the year.

Symptoms and Effects.—The symptoms produced by the roots are giddiness, dimness of sight, headache, and difficulty of breathing. There is burning pain in the stomach, with vomiting, and these symptoms are accompanied by heat and dryness of the throat. Convulsions have been observed to precede death. In the cases of three children, who died in convulsions from this poison, Mertzdorff found an injected state of the mucous membrane of the stomach, with redness of the air-passages, as well as of the stomach at the cardia and pylorus. The vessels of the brain and the sinuses were filled with dark liquid blood. (Wibmer, 'Cicuta,' p. 119.) In a fatal case which occurred to Wepfer, the patient, a man, æt. 20, who had eaten a large quantity of the *root*, was

Fig. 79.



Seed of Cicuta virosa, magnified (Lindley).

and with his face swollen and his eyes projecting. He breathed with eat difficulty, and foamed at the mouth. He was seized with a severe ileptic fit: his limbs assumed a tetanic stiffness, and there was spasmodic eathing. He was quite unconscious, and soon died. The only marked pearances were fluidity of the blood, and patches of redness on the mucous mbrane of the stomach. (Wibmer, loc. cit.) A man ate a portion of s root of this plant in a cooked state. It had a sweetish taste, and was the colour of a parsnip. Half an hour after his dinner he felt giddiness, d great dryness of the throat. He walked home with great difficulty, his gs being very unsteady, and all surrounding objects appeared to him as if ey were advancing or receding. In about an hour and a half the legs were ralysed, the arms benumbed, and their movements weak; the face was xious and flushed, and he had an apprehension of death. The skin was arm and dry—the pulse 90. An emetic was given. In two hours he as able to stand, and with difficulty walked across the room. He passed uch urine, and had hallucinations. In seven hours the legs were cold, pils dilated, skin and throat dry, with occasional delirium. There was purging. In two days he recovered. ('Lancet,' 1871, II. p. 396.) In e 'Pharm. Jour.' for June, 1872, p. 1063, two fatal cases are reported. he boys ate the roots, supposing them to be wild celery. Symptoms of isoning soon came on. They suffered from severe convulsions, with ismus (lock-jaw) before death.

HEMLOCK WATER-DROPWORT (ŒNANTHE CROCATA).

This umbelliferous plant grows on the banks of rivers, streams, and litches. It is one of the most poisonous of the order, and is considered to e one of the most virulent of English vegetable poisons.

Symptoms and Appearances.—A number of convicts, while engaged at work, ate the leaves and roots of the œnanthe. In about twenty minutes ne man, without any apparent warning, fell down in strong convulsions, which soon ceased, but left a wild expression on his countenance. Soon afterwards, as many as nine fell into a state of convulsions and insensibility. The face of the man first seized became bloated and livid, there was bloody foam about the mouth and nostrils, the breathing was stertorous and convulsive, and there was great prostration of strength, with insensibility: he died five minutes after the symptoms had set in. A second died under similar symptoms in a quarter of an hour, although the stomach-pump was used, and some leaves were extracted with the fluids. A third, who had assisted in carrying the two former, was himself seized with convulsions, and died in about an hour; and soon after him, a fourth died, in spite of energetic remedial treatment by cold affusion, emetics, stimulants, stimulating frictions, as well as the use of the stomach-pump. Two other cases proved fatal, the one in nine and the other in eleven days; and in these two cases there was irritation of the alimentary canal. On inspecting the bodies of those who died quickly, there was congestion of the cerebral vessels; and, in one instance, a layer of extravasated blood was found beneath the inner membrane (pia mater). In the first case, which proved most quickly fatal, the cerebral vessels were not congested. The pharynx and gullet had a white appearance, and contained some mucus, with portions of the root. The lining membrane of the windpipe and air-tubes was intensely injected with dark blood. The lungs were gorged with fluid blood. The blood in the heart was black and fluid. The stomach and intestines were externally of a pink colour: the cavity of the stomach was lined with a thick viscid mucus, containing portions of the root. The mucous membrane was much corrugated, and the follicles were particularly enlarged. Similar appearances *were met with in* all. In the two protracted cases the

mucous membrane of the stomach and bowels was softened and th
It had a pink colour externally, but no red appearance internall
vessels of the brain were congested. In the others who partoo
roots the symptoms were not so severe. Under the free use of pu
a considerable quantity of the root was discharged, and in a f
the men recovered. ('Med. Gaz.' vol. 34, p. 288.) These cas
that the œnanthe is a powerful poison. It destroys life wit
rapidity; for it here proved fatal to a strong healthy man in l
one hour.

In 1857, two fatal cases occurred at West Bolden, in Durham
labourers ate some of the roots of the œnanthe. They were fou
afterwards lying insensible and speechless, with livid faces,
swollen and protruded, convulsive movements of their jaws, frothy
with blood about their mouths, eyes full and projecting, pupils
breathing stertorous and laboured, with occasional general conv
They both died in an hour and a half from the time at which th
first discovered. On *inspection* it was found that there had been l
from the ears; the abdomen was livid and swollen. The stomach co
a gruel-like liquid with some of the partly digested roots: on re
this liquid, the membrane was found congested and softened. Th
were engorged with dark liquid blood, and the blood contained in t
was in a similar state.


It is not often that attempts are made to destroy others by the adu
tion of these umbelliferous poisons; but a case occurred in France, i
a woman attempted to poison her husband by mixing slices of the
this plant with his soup. His suspicions were excited by the acrid
the soup. The woman was tried for the crime, and Toulmouche

Fig. 80.



Part of leaf of Œnanthe.

Fig. 81.



Seeds of Œnanthe crocata.
a. Natural size.
b. Magnified 30 diameters.
c. One half of a seed magni
d. One half natural size.
e. Group of seeds.

at the trial that the plant from which the root had been taken
œnanthe crocata—that it was a powerful poison, and might cause
two or three hours. The prisoner was convicted. ('Gaz. Med.'
1846, p. 18; also 'Jour. de Chim. Méd.' 1845, p. 533.) The œn
poisonous to animals.

Analysis.—The œnanthe crocata can be identified only by its b
characters. The leaves are of a dark green colour, with a reddish-
border. They have no unpleasant odour when rubbed. The plant

eater resemblance to celery than most of the other umbelliferæ. Its m is round, channelled, smooth, branched, of a yellowish-red colour, d grows to the height of two or three feet. The root, consisting of a ries of oblong tubercles with long slender fibres, is of a yellowish-white lour, and not unpleasant to the taste. It is the most active part of the ant. The leaves yield much tannic acid to water, and the chloriodide of tassium and mercury produces no precipitate in the decoction. The ots and stems of this plant are more frequently eaten than the leaves. evertheless, it may be occasionally necessary to identify the plant by the ves. The engraving (fig. 80, p. 450) is taken from a photograph of the rger leaves of the œnanthe crocata, grown from the roots of the plant ocured from the spot where the two labourers above mentioned had ken their fatal meal. The smaller leaves of this plant are much wider proportion to their length.

Fool's Parsley (Æthusa cynapium).

Fool's Parsley, or Lesser Hemlock, is very common in gardens and dgerows. The leaves so closely resemble those of parsley that they have ten been gathered for them by mistake.

Symptoms and Appearances.—That the root of this plant contains a ost energetic poison, and that it is capable of producing rapidly fatal ffects, is apparently shown by a case in which death took place in an hour. girl, aged five years, in good health, ate the bulbs of the æthusa by istake for young turnips. She was suddenly seized with pain in the bdomen, followed by sickness, but no vomiting. She complained of feeling ry ill. On trying to eat, she could not swallow. She was incapable of nswering questions, and her countenace bore a wild expression. The ower jaw was so fixed by spasm as to prevent anything being introduced nto the mouth. She then became insensible, and died in *an hour* from the ommencement of the symptoms: so far as could be ascertained, there

Fig. 82.



Portion of a leaf of Fool's Parsley, natural size.

Fig. 83.



Seeds of Fool's Parsley.
a. Natural size.
b. Magnified 30 diameters.
c. Group of seeds.

re no convulsions. A second child, aged three years, shortly after eating e same substance, was attacked with pain in the stomach, sickness, miting, and profuse perspiration. She soon recovered, with the exception suffering severe griping pains without purging, but these disappeared the following day. A third child, of the same age, suffered from similar mptoms. Recovery in the two last cases was due to the plant having en eaten on a full stomach, and to the effect of early and copious vomiting. Med. Times,' Aug. 23, p. 1845, 408.) Two ladies partook of some salad, to which the leaves of *this plant* had been put by mistake for parsley.

They soon experienced nausea, with occasional vomiting; oppressive headache, giddiness, and a strong propensity to sleep, at the same time that this was prevented by frequent startings and excessive agitation. There was a sensation of pungent heat in the mouth, throat, and stomach, with difficulty of swallowing, thirst, and loss of appetite. There was numbness, with tremors of the limbs. The two patients only slowly recovered from the effects of the poison. (Churchill's 'Botany.')

Dr. John Harley has published experiments ('St. Thomas Hosp. Rep.' 1873, p. 43) which show that fool's parsley is not a poison. Although the particular plants he experimented with were not poisonous, there is evidence to show that other specimens—if rightly named—are highly poisonous.

Analysis.—It is known from garden parsley by the smell of its leaves when rubbed, which is peculiar, disagreeable, and very different from that possessed by the leaves of parsley. The leaves of fool's parsley are finer, more acute, and of a darker green colour. They are represented in the illustration, from a photograph of the living plant (fig. 82, p. 457). *Its* flower-stem, which is striated, or slightly grooved, is easily known from all other umbelliferous plants by the beard, or three long pendulous leaves of the involucrum under the flower. The flowers are white: those of the garden parsley are of a pale yellow colour.

Indian Tobacco (Lobelia inflata).

The leaves of Indian tobacco contain an acrid principle which is capable of producing poisonous effects on the brain and spinal marrow, attended with irritation of the stomach and bowels. When administered in doses of from ten to twenty grains, lobelia operates as an emetic; but in larger quantity it acts deleteriously. It would also appear that even ordinary medicinal doses affect some persons with great severity. There is a notion that this is a useful medicine and not a poison, although, like arsenic and opium, it may be either, according to the mode in which it is employed.


In one case, a man lost his life by swallowing *one drachm* of the powdered *leaves*, prescribed by a quack. This person was seen by a medical practitioner soon after he had taken the poison: he was evidently suffering great pain, but he was quite unconscious; the pulse was small, and the pupils were strongly contracted and insensible to light. He had vomited the greater part of the poison. He suffered from spasmodic twitchings of the face, sank into a state of complete insensibility, and died in about thirty-six hours. On inspection, some fluid was found in the stomach, but none of the powder. The mucous membrane was intensely inflamed, and the vessels of the brain were strongly congested. ('Pharm. Times,' May 1, 1847, p. 182.) The *seeds* of lobelia are equally poisonous. In the 'Med. Times and Gaz.' Nov. 26, 1853, p. 568, two cases are reported in which the seeds proved fatal. In one, the mucous membrane of the stomach was highly inflamed. Another case is referred to in the same journal, March 12, 1853, p. 270.

There have been many inquests and trials for manslaughter in this country as the result of the improper administration of the powdered *leaves* of the *Lobelia inflata* by quacks and dealers in vegetable medicines. The medical evidence given on these trials has proved that in large doses lobelia is a most noxious drug. (See 'Med. Gaz.' vol. 44, pp. 383 and 433; vol. 46, p. 384; 'Lancet,' March 5, 1853, p. 237; 'Pharm. Jour.' Aug. 1851, p. 87; and for some remarks on the action of the poison see a paper by Curtis and Pearson, 'Med. Gaz.' 1850, vol. 46, p. 285. Those who profit by the sale of this drug among the ignorant poor, maintain the

octrine that it cannot kill, and never has been known to destroy life. In 856, one of these quacks was convicted on a charge of manslaughter for illing a woman with overdoses of lobelia. Severe pain, followed by loss f consciousness and congestion of the brain, were the chief symptoms receding death in this case. The admission that, in proper doses, it was useful remedy in spasmodic asthma, was of no avail on this occasion. he man was sentenced to three months' imprisonment. (*Reg.* v. *Boyden* : *Jackson*, Lincoln Sum. Ass. 1856.) A man named *Riley Drake* was onvicted in the United States of having caused the death of a woman by dministering lobelia in improper doses. (Wharton and Stille's 'Med. ur.' p. 522.) In 1882, a man suffering from heart disease, and who was a enormous eater, took as an emetic a medicine containing lobelia prepared rom one of Dr. Coffin's prescriptions. At the post-mortem examination, ade twelve hours after death, an aperture about the size of a goose-quill as found in the lesser curvature of the stomach, and about two pints of luid having a milky appearance in the peritoneal cavity. The stomach self contained lobelia seeds and cayenne pepper. The dictum of the so-alled Coffinites is that 'Heat is life; and the want of heat, disease and eath.' In accordance with their principles, their drugs are lobelia and ayenne. ('Brit. Med. Jour. 1882, 2, p. 24.)

Analysis.—Lobelia is seen in the form of a greenish-coloured powder (fragments of leaves). This powder acquires a reddish-brown colour with strong nitric acid, and is blackened by concentrated sulphuric acid. Iodine water has no effect upon the infusion. The ferrous and ferric sulphates produce with it a dark-green colour—the ferric sulphate very rapidly. The leaves and seeds contain a liquid volatile alkaloid, *lobeline*. It is poisonous, and acts somewhat like nicotine, the active alkaloid of tobacco. In small doses it acts as an expectorant, and in larger doses as an emetic. The leaves of lobelia are generally seen in fragments which do not readily admit of identification by the microscope. The *seeds* are very small, of a lengthened oval shape, reticulated on the surface with projecting hairs or fibres, and of a light brown colour (fig. 84). The discovery of them among the fragments of leaves would furnish a sufficient proof of the presence of lobelia.

Fig. 84.



Seeds of Lobelia.
a. Natural size.
b. Magnified 70 diameters.

Foxglove (Digitalis purpurea).


Purple foxglove is a well-known hedge-plant, growing abundantly in England. All parts of the plant—the seeds, leaves, and root—are poisonous, owing to the presence of the poisonous principle, *digitalin*. The leaves, whether in the form of powder, infusion, extract, or tincture, exert an action on the brain and spinal marrow, as well as on the stomach and bowels. They retain their noxious properties when dried.

Symptoms and Effects.—Cases of poisoning by foxglove are not very numerous. One was the subject of a criminal trial at the Cent. Crim. Ct., in Oct. 1826. A quack was indicted for the manslaughter of a boy under the following circumstances:—He prescribed for a trivial complaint six ounces of a strong decoction of the *leaves*. The boy was soon attacked with vomiting, purging, and severe pain in the abdomen. After some time he became lethargic, and slept for several hours; in the night he was seized with convulsions. The pupils were dilated and insensible, the pulse was slow, small, and irregular; coma followed, and the boy died twenty-two hours *after taking the poison*. On *inspection* the membranes of the

brain were found much injected, and the mucous lining of the stomach was partially inflamed. The prisoner was acquitted of the charge, because he had only given his fatal advice on the application of the friends of the deceased. ('Ed. Med. and Surg. Jour.' vol. 27, p. 233.) A young man swallowed a strong *decoction* of foxglove by mistake for purgative medicine. He was soon seized with vomiting, pain in the abdomen, and purging. In the afternoon he fell asleep. At midnight he awoke, was attacked with violent vomiting, colic, convulsions, and the pupils were dilated and insensible to light; his pulse was slow and irregular. He died twenty-two hours after taking the poison. (Wibmer, op. cit. *Digitalis.*) A few grains of the powdered leaves have been known to produce giddiness, languor, dimness of sight, and other nervous symptoms. A drachm, however, has been taken without causing death; but in this instance it produced the most violent vomiting. As an indication of the singular effect of this poison on the nerves of sensation, it may be stated that a coal-fire appeared to the patient to have a blue colour. One effect of this poison is to produce great depression and slowing of the heart's action. A woman made an infusion of digitalis, and swallowed it by mistake. The symptoms which followed were vomiting, paleness of the face, coldness of the skin, prostration, muscular feebleness, a persistent feeling of drunkenness, headache, giddiness, confusion of sight, dilatation of the pupils, and loss of sensibility. The vomiting was constant, and aggravated by anything that was taken. There was constipation of the bowels, with suppression of urine. There was thirst, with pains in the abdomen increased by pressure, and great restlessness at night. At first the pulse was 52. On the fourth day it was 41 to 42. On the fifth day it was 58, less irregular, and the symptoms had abated. During the night she got up, and on returning to her bed suddenly fainted, and died. A person labouring under symptoms of poisoning by digitalis should always be kept in the recumbent posture. ('Ed. Month. Jour.' 1864, p. 169.) The editor has seen a patient under the influence of digitalis die very suddenly on being raised by the nurse from the recumbent to the sitting posture.

Analysis.—When foxglove has been taken in substance, *i.e.* in the form

Fig. 85.



Leaves of Foxglove.

Fig. 86.



Seeds of Foxglove.
a. Natural size.
b. Magnified 30 diameters.

of seeds or leaves, or any portion of these has been swallowed in a decoction or infusion, fragments may be found in the stomach and bowels. In reference to the infusion, decoction, tincture, or extract, except there be

ient to allow of the separation of digitalin, there is no chemical
es known by which the poison may be recognized. If any fragments
ves or seeds are found in the contents of the stomach or in food, they
be identified by the aid of the microscope. The illustration (fig. 85,
4), taken from the living plant by photography, represents a small
nd a portion of a larger leaf of this plant.
; is calculated that digitalin constitutes only one per cent. of the dried
s. In reference to the *seeds* of the foxglove, they are of a reddish-
n colour, remarkably small, oblong, and somewhat angular in shape.
have peculiar markings (fig. 86, p. 454). By the aid of the microscope
may be easily distinguished from the seeds of hyoscyamus, datura,
lonna, and most other poisonous plants.

IGITALIN.—Digitalin is the active principle of foxglove: its physio-
al properties have been investigated by Homolle ('Jour. de Pharm.'
1845–57; also, Bouchardat, 'Ann. de Thérap.' 1864, p. 155). The
nercial article has a pale fawn colour, and no crystalline character.
French and German varieties are not identical. Nativelle has obtained
the aid of boiling 90 per cent. alcohol in fine white and shining
es ('Pharm. Jour.' 1872, April 27, p. 865). Alcohol is its best
nt. Boiling water takes it up in small quantity, acquiring a tea-like
r: its solutions are intensely bitter. It is a mixture of neutral
able principles, having neither alkaline nor acid reaction. In solution
precipitated by tannic acid, but not by the chloriodide of potassium
mercury; and by this property it may be distinguished from the
oids. When heated in a tube, it melts and is decomposed, evolving
id, and not an ammoniacal vapour. Strong nitric acid dissolves it, and
to it a deep orange-red colour unlike that of morphia or brucine. This
solution speedily acquires a pale yellow colour on standing. Iodic
is unchanged by it. Hydrochloric acid dissolves it, and when gently
d the solution becomes green. Strong sulphuric acid gives to it a
n colour, and after exposure for some time or by a gentle heat this
r changes to a purplish-black. If the sulphuric acid solution is diluted,
iquid immediately assumes a dingy green colour. Diluted sulphuric
heated with the powder gives a reddish-black colour. Grandeau has
ested another test. If the digitalin has been previously dissolved and
iquid evaporated, sulphuric acid imparts a rose colour to small quan-
, or a reddish-brown or even brown colour when the digitalin is in
r large quantity. If the digitalin, moistened with sulphuric acid, is
sed to the vapour of bromine, it immediately assumes a violet colour.
peculiar colour is observed even with the faintest trace of digitalin,
it is regarded by him as characteristic. Seventeen of the alkaloids and
iples thus tested did not acquire a violet colour. ('Chem. News,'
16, 1864, p. 26.) According to Grandeau, digitalin readily admits of
ation by dialysis from organic liquids. Tardieu and Roussin, and the
r, have not found this method so successful in practice as these experi-
s on pure digitalin would appear to indicate. ('Ann. d'Hyg.' 1864,
.) According to Brunner ('Deut. Chem. Ges. Ber.' 1873, p. 96) and
uist ('Arch. Pharm.' [3] V. p. 515), digitalin, when in a separate state,
be detected by the red colour produced when its solution is mixed with
ate watery solution of dried ox-bile, and then with a quantity of strong
nuric acid sufficient to raise the temperature to 158° F. The test is
plicable when sugar or several glucosides are present. Fagge and
ditor found the physiological test applied to a frog the best test for
resence of digitalin. ('Guy's Hosp. Rep.' 1866, p. 37.)

Digitalin operates powerfully on man and animals in very small doses,
it must be regarded as a deadly poison. 1–16th of a grain, which is

considered to be equal to eight grains of the well-prepared powder of the dried leaves, is sufficient to cause symptoms of poisoning. Doses of from 1–11th to 1–32nd part of a grain have lowered the pulse and caused nausea, vomiting, griping, purging, and an increased secretion of urine. (Pereira, 'Mat. Med.') Doses of from one-quarter to one-half of a grain would probably prove fatal to life. Homolle found in experiments on himself that small doses of digitalin taken at intervals lowered the pulse to about one-fourth or one-fifth of the normal standard: thus in himself it fell 17 in one minute, which represents a fourth of the normal pulsations. In doses of from 1–15th to 1–30th of a grain in twenty-four hours, digitalin slackened the circulation. In doses above 1–15th of a grain, it produced on adults emetic and purgative effects, sometimes suddenly, at others slowly and gradually. In doses of from one to two grains, unless speedily thrown off by vomiting, it killed dogs in a few hours. (Orfila, 'Toxicologie,' vol. 2, p. 350. See also a paper by Fagge and Stevenson, 'Guy's Hosp. Rep.' 1866, p. 37.)

Digitalin has acquired some notoriety by reason of the trial of *Dr. De la Pommerais*, at Paris, in 1864, for the murder of his mistress, a woman named Pauw. The deceased, who was about forty years of age, and in the enjoyment of good health, was suddenly seized with violent vomiting, and, after an illness of about twenty-four hours, died on the 17th Nov. 1863. The prisoner had just renewed his intimacy with her at the time of the occurrence of this fatal illness; and, after a long interval of absence, he had induced her to insure her life in various insurance offices for enormous sums of money, quite disproportioned to her circumstances. Immediately after her death he put in a claim for these large insurances. The body of the deceased was exhumed, and inspected for the first time thirteen days after death. The viscera throughout were healthy; they presented no unusual appearance, and revealed no natural cause of sudden death. The stomach and bowels, which were well preserved, bore no marks of the action of poison; and, on a chemical analysis, no poison of any kind could be detected in these organs by Tardieu and Roussin. The symptoms, during the illness, owing to there being no suspicion of poisoning, were not accurately observed. Repeated vomiting, with great depression and exhaustion, seem to have been the most prominent. Failing to detect any poison by chemistry and the microscope, the experts adopted the physiological test of administering prepared alcoholic and aqueous extracts of the stomach and intestines to animals. An attempt made to separate the active principle and remove the organic matter by dialysis, did not yield satisfactory results. ('Ann. d'Hyg.' 1864, 2, 105.) Seventy-five grains of the mixed extracts above mentioned were introduced into the cellular membrane of the thigh of a dog. The animal vomited twice; and in four hours the pulsations of the heart sank from 102 to 86: its action was irregular and intermittent, and the respiration was deep and painful. There were no narcotic symptoms; on the next day, the dog was better, and it completely recovered. Sixty grains of these extracts in water, administered to a rabbit by means of a funnel, caused death in a few minutes, probably from syncope (or asphyxia ?).

The deceased, during her fatal illness, had vomited on the floor of her room. An alcoholic extract was made of the scrapings of the floor and of the substances deposited between the planks. No mineral poison was found in it. Seventy-five grains of this extract were introduced into the cellular membrane of the thigh of a dog. The animal suffered from vomiting and depression of the action of the heart, and died in about twenty-two hours. There was no coma or insensibility at any time. Thirty-one grains of the same extract diffused in water were administered to a rabbit by

means of a funnel. In less than three hours after the injection the animal died, having suffered from irregular and depressed action of the heart. Sixty grains of an alcoholic extract from the scrapings of the floor, said to be free from vomited matters, had no effect upon an animal.

These two extracts of the floor had different chemical properties. The first, containing, as it was believed, a portion of the vomited matters, amounted to half an ounce. It was of a brown colour, had a rancid oily flavour, and a bitter taste. Its solution was precipitated by tannic acid: it was coloured purple-red by sulphuric, and green by hydrochloric acid. The second was coloured, had an oily aspect, but no bitterness. It was not precipitated by tannic acid, and was feebly coloured by sulphuric and hydrochloric acids; the results being different from those obtained with the first extract. It was objected to any inferences from the properties of these extracts, that deceased's room had been formerly occupied by a photographic artist: but it is expressly stated that no noxious mineral substances, such as are used in photography, were found in them. No attempt was made to procure digitalin from the extracts: the presence of this principle was a matter of inference, from the extracts produced: and the reason assigned for the extract derived from the stomach and bowels of deceased having no fatal effect upon animals, was that the quantity of the principle left in the body at the time of death was too small.

Tardieu and Roussin deposed at the trial that the deceased had died from a vegetable poison which produced no marked change in the body, which could not be revealed by chemical analysis, but only by its noxious effects on animals. The effects on animals were in this case similar to those caused by digitalin, and without positively affirming that the deceased woman, Pauw, had died from this poison, there was the strongest presumption that she fell a victim to it. The deceased was quite well the day before her death, and the post-mortem examination of the body proved the absence of any natural cause to account for this sudden death.

In reference to the accused, it was proved that he had in his possession a large number of poisons of a deadly kind, including digitalin; that he had at three different times purchased as much as fifty-two grains of this poison, of which much had been used, and that those quantities were inconsistent with any reasonable medical requirements. As the prisoner was a homœopathic practitioner, the purchase and actual use of such large quantities of so potent a drug were quite inexplicable on any theory consistent with his innocence. On the other hand, the case was equally against him in its moral aspects; it was clearly established that, by reason of the large insurances effected on her life, he had a strong motive in the death of the woman, that a long cessation of their intimacy had taken place by reason of his marriage with another person, that he had suddenly and without any reasonable grounds, renewed his intimacy with the deceased, and the date of her fatal illness was in accordance with these visits thus renewed. In short, De la Pommerais had the motive, means, and opportunity of destroying the life of this woman by poison, and no theory consistent with his innocence could be suggested, by those who defended him, to explain satisfactorily the mass of moral and medical circumstances which were clearly proved against him. Further, he over-acted his part, and by forged letters and correspondence had shown that he had fully anticipated the sudden death of the woman Pauw, and the explanations that might be required of him in order to account for this event. Apart from any questions respecting the speculative character of the medical evidence, there were circumstances proved in this case which were inconsistent with any theory of the innocence of the accused. The jury found him guilty of murder, and he was subsequently executed.

Monkshood (Aconitum napellus).

All parts of the common aconite (*Aconitum napellus*) are highly poisonous. The plant is commonly known by the names of monkshood, wolfsbane, or blue rocket. The root has frequently been eaten in mistake for horseradish, to which it bears a remote resemblance. The root of the horseradish is, however, long and almost cylindrical, and does not change colour when scraped and exposed to air; whilst, on the contrary, that of aconite is darker, distinctly conical, and becomes pink when scraped and exposed to the air for a short time. The root has twice been administered for homicidal purposes. In most cases it is the tincture, liniment, or the pharmaceutical preparation which is taken in poisonous dose by misadventure. Still more rarely the active alkaloid, *aconitine*, has been administered. This is perhaps the most deadly known poison, 1–16th of a grain having proved fatal, and 1–50th of a grain has, according to Pareira, produced alarming results. The roots, seeds, and leaves of the plant, when masticated, produce a cool numbing sensation, affecting the lips, tongue, and interior of the mouth generally. At first the root appears to be almost tasteless, as the effects are only manifested after the lapse of a few minutes. The sensation, once produced, lasts for several hours.

The roots of *Aconitum ferox*, the Indian bikh or bisch, and those of Japanese aconite from *A. Fischeri*, are also articles of commerce, and are as poisonous as the ordinary *A. napellus*. The official tincture, *Fleming's tincture*, the extract, the alcoholic extract (not official), and the liniment may all be productive of fatal results.

Symptoms and Appearances.—In from three to five minutes after chewing the root of aconite, or after contact of any of its preparations with the tongue, a hot, burning, astringent sensation is experienced on the tongue, extending to the fauces and to the lips, especially the lower. The sensation soon becomes very severe, and is accompanied by a certain amount of salivation, and a sensation of swelling of the fauces, and there may be difficulty in swallowing. The sensation is by some described as one of numbness, and there is decided loss of sensation locally. Later the feeling is one as if the tongue had been seared with a hot iron. Vomiting usually sets in in an hour or two at the latest; and is usually severe and spasmodic. The patient feels cold, especially in the extremities, and the skin is cold, clammy, and perspiring. There may be a feeling of numbness extending over the whole body, or a sensation of impending paralysis.

Poisoning by the *root* of aconite is by no means infrequent. In the spring or autumn, the root is liable to be mistaken for that of horseradish. It has been thus accidentally eaten on several occasions, and has caused death. A mistake of this kind led to fatal results in three hours in a case which occurred at Lambeth; and another set of cases occurred at Dingwall, in 1856. Here three persons were poisoned by reason of their having had sauce, made with the root of aconite, served at dinner with roast-beef in place of horseradish sauce. They were healthy adults; they all died within three hours and a half. Mistakes of this kind show deplorable ignorance, but there is always the risk of their occurrence when horseradish and aconite are grown near to each other in a garden, at that season of the year when the leaves have fallen. A trial for murder by poisoning with the root of this plant took place at the Monaghan Lent Assizes in 1841 (*Reg.* v. *McConkey*), in which Geoghegan conducted the medico-legal investigation. The medical evidence was beset with difficulties; for no trace of the poison could be discovered in the body, and it was only by a close analysis of symptoms and appearances that the charge was brought home to the prisoner. The deceased had eaten for his dinner some greens

ssed for him by the prisoner; he complained of their having a sharp te, and this was perceived also by another person present who tasted m. It was ascertained that soon after the meal the deceased had nited a greenish matter, and suffered from purging, restlessness, in- erence, lock-jaw, and clenching of the hands. He died in about three rs after having eaten the greens, but was not seen by a medical man ile living. The chief appearance met with was in the stomach, where mucous membrane was of a light reddish-brown colour. Traces of etable matter were found in the intestines: but no poison could be ected, either botanically or chemically. The symptoms suffered by a nd of the deceased, who had accidentally tasted the greens, were very aracteristic of poisoning by aconite. In *two* minutes he felt a burning t in the mouth, throat, gullet, and stomach; then a sensation of swelling the face, with a general feeling of numbness and creeping of the skin. stlessness, dimness of sight, and stupor almost amounting to insensibility, lowed; and in about an hour after the meal he was found speechless, thing at the nose and mouth, the hands and jaws clenched, appearing asionally as if dead, and then again reviving. Vomiting, purging, derness at the pit of the stomach, cramps, tingling of the flesh, and a rning taste in the mouth followed. This man did not entirely recover til after the lapse of five weeks. The prisoner was convicted of murder, d confessed before her execution that the powdered *root* of aconite had en mixed with pepper and sprinkled over the greens. ('Dub. Med. ur.' vol. 19, p. 403.)

In 1856, Hadfield forwarded to the author four small slices of aconite ot, taken from the stomach of a man who had died in three hours. e quantity which he had swallowed with suicidal intention was un- own: but none was thrown off by vomiting so far as could be ascer- ined. The *symptoms* within half an hour of death were burning pain the stomach, parched mouth, intense thirst, retching and vomiting a tenacious mucus, cold perspiring skin, imperceptible pulse, and a eling of deadly sickness. The patient was conscious: there were no nvulsions. On *inspection*, there was congestion of the brain as well as its membranes; the heart was flaccid, and there was some blood in the ght side. The stomach contained much half-digested food, with four ices of aconite root apparently unaltered. The mucous membrane resented a slight reddish-brown patch at the greater end, of the size of alf a crown. It was otherwise healthy, as well as the other organs. (For a account of the effects of this plant the reader is referred to a paper in e 'Dub. Jour. Med. Sci.' vol. 19, p. 403.)

The tincture of the root operates powerfully in small doses. Dr. Male ed from the effects of not more than *eighty drops* taken in ten doses, er a period of four days, the largest quantity taken at once being *ten* ops. ('Prov. Med. and Surg. Jour.' Aug. 20, 1845, p. 535; also 'Med. az.' vol. 36, p. 861.) Pereira had known tingling and general numbness the limbs produced in hysterical women by a dose of only *five minims* a carefully prepared tincture. Topham has published an account of the mptoms produced by *fifteen minims* of the tincture of the root of aconite. mediately after taking the poison in a mixture into which it was put by istake, the patient (a woman, æt. 27) felt a sensation of numbness in e tongue, with difficulty of swallowing. There were convulsive twitchings the muscles of the face, and she lost the power of walking. There was mplete unconsciousness, which continued for two hours, when she began recover. The pupils were observed to be slightly contracted. The tensity of the symptoms varied at intervals, and came on in paroxysms. ey indicated great *disorder of* the nervous system. The next day she

had numbness in both arms, but she rapidly and perfectly recovered. These tinctures were three times as strong as the pharmacopœial tincture. ('Lancet,' July 19, 1851, p. 56. See also the account of a case of recovery in 'Amer. Jour. of Med. Sci.' January, 1862, p. 285.)

In 1853, a woman took by mistake *seventy minims of Fleming's tincture* of the root mixed with one grain of acetate of morphia. Fleming's tincture is six times as strong as the ordinary tincture. In a few minutes she became very thirsty, complained of a burning sensation and pain in her stomach, to relieve which she swallowed a quantity of cold water. In fifteen minutes there was violent vomiting, which continued for two hours. She lost the power of standing, and was very restless. The pain in the stomach increased, and there were convulsive movements of the muscles. She was conscious until shortly before her death, which took place in about four hours after she had taken the poison. There were no general convulsions: the pain in the stomach was well marked throughout. On *inspection*, the membranes of the brain were found congested, but the brain itself was firm and healthy. The lungs were healthy: the heart was flaccid, and the uterus congested. The stomach contained some mucus, and the membrane at the larger curvature was injected (reddened) in patches, but otherwise natural. The mucous membrane of the duodenum was in a high state of inflammation, abraded in patches, softened, and broken down. Some spots were of a very dark colour, passing into mortification. In 1852, an excise officer lost his life by merely tasting Fleming's tincture of aconite, under the supposition that it was flavoured spirit. He was able to walk from the Custom House over London Bridge, but he died in about four hours after taking the poison. A liquid sold for external use under the name of NEURALINE appears to be a preparation of tincture of aconite mixed with chloroform and rose-water. According to Dr. George Harley there is one drop and a half of Fleming's tincture in half a bottle of the so-called neuraline. It operates by causing numbness or paralysis of the parts to which it is applied. The death of the *Hon. G. R. Vernon* was ascribed to the too frequent use of this preparation externally. But his death from this cause was doubtful. ('Pharm. Jour.' Jan. 1872, p. 618.) The same ignorance prevails respecting this as with regard to other poisonous substances dissolved in alcohol, namely, that it is harmless unless the skin is broken. Unless it were absorbed by the skin it could have no medicinal operation, and the effects of absorption must depend on the quantity applied and the frequency with which it is applied. Alcohol has been found to promote the absorption of poisonous agents through the unbroken skin. NERVINE is also a preparation of aconite.

The case of the man *Hunt* who, in 1863, destroyed his wife and children by prussic acid, presents some features of interest in reference to the symptoms and appearances produced by tincture of aconite. The quantity of tincture taken by him was not determined; but the man was soon afterwards seized with violent spasmodic retching, the face was pale, the skin cold and clammy, the pulse small and hardly perceptible, and the action of the heart feeble. The pupils were much dilated, and the eyes brilliant and sparkling; the breathing quiet and regular, except during the fits. He complained of pain in his heart. In attempting to walk, he staggered, and had no power to raise his arms. He was perfectly conscious, called for writing materials, and wrote a few lines. He then became suddenly worse, and a quarter of an hour before his death he lost all power and sensation in his limbs, the sharpest pinches producing no impression. The pulse was imperceptible. There were no convulsions, but complete relaxation of the limbs at death, which appeared to arise from syncope three-quarters of an hour after he had taken the poison. On *inspection*

forty-two hours after death, there was great rigidity of the muscles. The substance of the brain was firm and healthy: the vessels on the surface were filled with blood. The heart was healthy: the right side was greatly distended with dark fluid blood; the left side contracted and quite empty. The lungs were healthy. In the abdomen the viscera were healthy, with the exception of the stomach and duodenum. The mucous membrane of the stomach had a bright red colour at the larger end. There were marks of irritation, with softening and separation of the mucous lining, the whole of the membrane being in a highly corrugated condition. Traces of aconitine were found in the contents of the stomach. The deceased had provided himself with an ounce of the tincture of aconite, and had swallowed the greater part of this mixed with water.

The tincture varies much in strength. In the 'Lancet,' vol. II. 1861, p. 170, it is stated that a lady recovered who had swallowed two teaspoonfuls by mistake for laudanum. She had been in the habit of taking large doses of laudanum. After she had swallowed the aconite she could not rise from her seat, and exclaimed that she had lost the use of her legs. She complained of a burning sensation in the throat and constriction at the chest. Her mind was clear, and she had no feeling in her arms and legs. The symptoms subsided in two hours, and she recovered in eight hours. Vomiting had been early promoted by emetics. In 1862, a man died from the effects of two grains of extract of aconite taken in two pills. As in other cases in which active poisons have been administered in pills, the symptoms were a long time in appearing, but when they once commenced they proceeded rapidly to a fatal termination.

A case of poisoning by a *decoction* of this plant occurred to Sayle. A man, æt. 39, boiled the fresh stalks and leaves of aconite in half a pint of beer until it was reduced to a quarter of a pint: he then swallowed half of it as a medicine. An hour afterwards he was found in bed, rolling his arms about and foaming at the mouth:—the pupils were widely dilated, the legs were paralysed, the skin was cold and clammy, there was great nausea, the pulse was scarcely perceptible, and he was perfectly insensible. He soon afterwards died. The abdomen was examined, and the only appearance met with was a slight redness near the cardiac extremity of the stomach. ('Med. Times,' Oct. 18, 1845, p. 70.)

Fatal dose.—Of the *root* 60 grains has proved fatal; but it is probable that this is much in excess of the minimum fatal dose. Of the pharmacopœial tincture two or three drachms might probably be fatal. *Fleming's tincture* is six times as strong, and twenty-five minims have killed an adult. Four grains of *alcoholic extract* have proved fatal. Of the *official* (non-alcoholic) *extract* two grains has proved fatal (see above). It is very uncertain in its action; but is much less active than the alcoholic extract. The *liniment* is stronger than even Fleming's tincture, and eight times the strength of the pharmacopœial tincture; twenty minims would probably form a fatal dose.


Analysis.—The botanical characters of the root and leaves, when any portions can be obtained, will enable a medical witness to identify this vegetable poison. The root has been frequently and fatally mistaken for horseradish, but there are these striking differences:—1. Aconite-root (fig. 87, p. 462) is very short, conical, and tapers rapidly to a point. 2. It is externally of an earthy-brown colour,—internally white and of an earthy smell,—the cut surface is rapidly reddened by exposure to air. It has numerous long thin fibres proceeding from it. 3. It has at first a bitter taste, but after a quarter of an hour or twenty minutes it produces a disagreeable sense of tingling and numbness on the lips and tongue. 1. Horseradish root (fig. 88, p. 462) is long, cylindrical or nearly so, and of the same

thickness for many inches. 2. It is externally whitish-yellow, and has a pungent odour when scraped. 3. Its taste is sometimes bitter, but it produces an immediate hot or pungent sensation.

Fig. 87.



Fig. 88.



a. Root of Aconite. *b*. Root of Horseradish.

The leaves of aconite or monkshood are of dark-green colour, thick and of a peculiar shape. The illustration (fig. 89) is engraved from a photograph of a fresh leaf. When masticated the leaves slowly produce on the lips and tongue the persistent sensation of tingling and numbness, with the sense of coolness, observed in the root. They are less powerful than the root and seeds. The seeds differ in appearance from those of other poisonous plants. (See fig. 90.)


ACONITINE.—The chief alkaloid of *A. napellus*, is *aconitine*, *aconitia*, or *aconitina;* and is, perhaps, the most formidable known poison, the fatal dose being probably 1–20th of a grain. *A. ferox* contains a closely allied alkaloid, known as *pseudaconitine;* and Japanese aconite roots yield a third alkaloid, *japaconitine*. The editor has found that all these alkaloids are

Fig. 89.



Small leaf of Aconite, natural size, from a photograph.

Fig. 90.



a. Seed of Aconite, natural size.
b. The same, magnified 30 diameters.

toxic, producing similar effects when administered to animals, and that they are of almost equal physiological activities. Commercial samples of aconitine are of varying degrees of activity and purity; most of the German or

"exotic" varieties being comparatively inert. Pseudaconitine and japaconitine are not articles of commerce. The statement of some authors that the special preparation known as Morson's is pseudaconitine, prepared from the roots of the Indian plant, is incorrect. The inertness of the exotic preparations is due to admixture with other and inert alkaloids, partly existent in the plant, and partly the products of decomposition during the manufacture. Indeed, the active alkaloids aconitine, pseudaconitine, and japaconitine, are somewhat of the nature of glucosides, readily undergoing a kind of saponification and splitting up into an acid and a comparatively inert basic body. Thus aconitine in ammoniacal mixture speedily splits up into another base aconine, and benzoic acid. Duquesnel first, and subsequently Wright ('Year Book of Pharmacy,' 1880), have pointed out the conditions essential for success in the manufacture.

In 1880, three cases of poisoning by crystallized nitrate of aconitine occurred in Holland ('Schmidt's 'Jahresb.' 189, p. 122); 'Berl. Klin. Wochenschr.' 1880, p. 337); and one of them proved fatal. The first was the case of a weakly man, 61 years of age, suffering from chronic bronchitis and a febrile attack. For this there was prescribed a solution of nitrate of aconitine. The patient took five drops, containing ·006th of a grain of the nitrate at 7 P.M. This produced an astringent and burning taste in the mouth, extending to the stomach. At 9 P.M. the dose was increased to twenty drops (=·025th of a grain); and this dose was repeated at 8 A.M., 11 A.M., 4 P.M., 9 P.M.; next day at 10 P.M., a final dose of ten drops (=·012th of a grain) was taken. In all 1–7th of a grain of the nitrate was taken in seven doses. After every dose the patient was seriously indisposed, so that eventually his life was in jeopardy. The symptoms were a feeling of coldness, cold clammy perspiration, severe vomiting, difficult respiration, great lassitude, and the patient felt as if he were about to become paralysed. There were intermittent deafness and blindness, and spasmodic twitchings of the whole body, but more especially of the muscles of the face. At one time he felt that he was dying, and stated that he had been poisoned. The respiration became stertorous and quickened; then slow and gasping. There was no loss of consciousness. It is not stated that there was any loss of sensation, or any actual paralysis.

In the second case, a man, æt. 62, took an undetermined dose of the same medicine. When seen he had cold clammy perspiration, a weak, irregular, dicrotic pulse, and was conscious. The respirations were short, laboured, irregular, and superficial. The pupils were contracted, and responded feebly to light. There was no difficulty in swallowing. There was great precordial anxiety, and *facies hippocratica*. Suddenly the pulse entirely ceased, though the cardiac beats could still be feebly heard; and a deathly pallor supervened. The patient rolled from side to side of the bed. The pupils were now dilated. Tonic convulsions of the facial muscles set in, with trismus; then three hours after the dose general clonic convulsion, and the patient lost consciousness. In five or six minutes muscular relaxation ensued, but the convulsions returned in a quarter of an hour. An hour later death appeared imminent. Vomiting now set in, the pulse improved, and in twenty-one hours the man was convalescent.

The third case terminated fatally. Dr. Mayer, who had prescribed for the above patients, himself took from 50 to 60 drops of the solution of nitrate of aconitine prescribed for the first patient. This corresponds to 1–13th to 1–21st of a grain of the nitrate. It may be assumed that the dose was probably 1–16th of a grain. The symptoms commenced in an hour and a half; but they were not accurately noted till 8 P.M., four hours after the alkaloid had been *taken*. He was then found with a small, weak,

irregular but not slowed pulse, cold skin, and contracted pupils. He had an astringent and burning pain in the mouth, extending to the stomach, and difficulty in swallowing. The tongue was swollen. There was great precordial anxiety. He complained of burning pain, weakness, and heaviness of the limbs—especially the lower—which felt cold. Suddenly vision was lost, and the pupils became dilated. Soon, however, they again contracted, and vision was restored. Vomiting was procured by tickling the fauces. At 4.40 severe convulsions first set in, with stertorous respiration, singing in each ear alternately, and deafness. Ether was employed hypodermically, and its use was followed by renewed vomiting and convulsions. The pulse, nevertheless, improved, and ether was again injected. In a few minutes there was renewal of severe vomiting and convulsions, and the patient became unconscious; the pulse failed, and death ensued at 9 P.M., without return of consciousness, five hours after the administration of the fatal dose. On post-mortem examination the viscera were unusually charged with blood, and there was considerable hyperæmia of the stomach and small intestines, so that the colon and rectum appeared pale and bloodless by contrast. The intestines contained fæces, there having been no stool passed during the illness; and the bladder contained two and a half ounces of urine.

In these cases it was intended to give Friedländer's nitrate of aconitine, a weak German preparation. The dispenser used instead a crystallized preparation procured from Petit, in Paris. Plugge, to whom the analysis was referred, found that Petit's preparation was eight times more poisonous to animals than Merck's and 170 times stronger then Friedländer's nitrate. He failed to detect aconitine in a benzene extract of the viscera.

Alarming results have also been known to result from the administration of pills, each containing 1-250th of a grain of aconitine, four times a day. The symptoms were developed on the second day. ('Lancet,' 1880, II. p. 46.)

In 1882, a medical practitioner named Lamson was tried, convicted, and executed for the murder of his brother-in-law, Percy Malcolm John (*Reg.* v. *Lamson*, C. C. C. March, 1882). This is the only known case of the homicidal use of *aconitine;* and the only recorded case of fatal poisoning by English (Morson's) aconitine. On Dec. 3, 1881, Lamson, a medical practitioner, visited his brother-in-law, æt. 19, who was at a school in Wimbledon. John, though a cripple, and paralysed below the pelvic region, was at that time in good health. In the presence of the master, Lamson gave to John a gelatine capsule, which he pretended to fill with powdered sugar, but into which he no doubt introduced a fatal dose of aconitine—perhaps the whole of two grains which he had purchased a few days previously. This was done under the pretence of showing the youth how to use the capsules for taking nauseous medicines. Lamson then made a hasty departure. Twenty minutes or half an hour afterwards the poor victim was seized with pain in the stomach, which he at first called heartburn, and which he compared to pain which he had experienced on a former occasion when Lamson had given him what professed to be a quinine pill or powder. In a box belonging to John there was found, after his death, a packet of quinine powders, some of which were mixed with aconitine, whilst others were free from that poison; and also pills containing quinine and aconitine. There is no doubt that attempts had been made on John's life on two previous occasions by the administration of these articles furnished to his brother-in-law by Lamson. The boy was taken upstairs, and he vomited, and was in great pain. He said his skin felt all drawn up, and that his throat burned. When first seen by Dr. Berry one

our and forty minutes after the administration of the poison, he was ing on the bed, with great pain in the stomach. He complained of the in of his face being drawn, of a sense of constriction in the throat, and being unable to swallow. He retched violently, and vomited a small antity of dark brown fluid. Half an hour later he was also seen by r. Little, and two hours and three-quarters after the poison was swallowed quarter of a grain of morphia was injected beneath the skin. This mewhat eased the patient's agony; but the symptoms returned with creased severity. At one time he was with difficulty kept lying down the united force of two men. An hour later the morphia injection was peated—one-sixth of a grain being used. Twenty minutes later he died, wing been conscious almost to the last. Death occurred four hours and re minutes after the administration of the capsule, and not quite four urs after the commencement of symptoms. At the post-mortem exnination, the only unusual appearances were—redness and inflammation the cardiac end of the stomach, which had a blistered appearance; great ngestion of the first portion of the small intestine (duodenum), and tches of congestion in other portions of the intestine in a lesser degree. he brain was hyperæmic. The membranes of the spinal cord were conested. The lungs were much congested, more especially towards the osterior parts. The heart was very flaccid, and as if sodden, and stained ith blood-pigment.

From a portion of the first ejected vomit—from the urine drawn off om the bladder after death—and from the stomach, stomach contents, ver, spleen, and one kidney, taken together—the editor and Dupré exracted aconitine by a modification of Stas's process. The existence of his was proved by its general reactions as an alkaloid, by the peculiar nsation which it excited upon the tongue, and by comparison of its ital effects upon mice with those produced by Morson's aconitine. One wo-thousandth part of a grain of English aconitine may be recognized y the taste-test, and the same quantity will kill a mouse within a few inutes.

A solitary case of poisoning by German aconitine (Merck's) is very rudely recorded. An analytical chemist took eight grains of aconitine fter dinner, with suicidal intent. Half an hour later the first violent ymptoms appeared. A burning sensation in the mouth and throat first ade itself felt, and this became more intense every minute; intense ains in the stomach ensued after thirty minutes, and these became so iolent in a few seconds that the patient writhed, shrieking, in the most readful convulsions, and trying to strike the wall with his head. He was eld with difficulty, and milk and oil were given. Very soon he became ncapable of swallowing; he was seized with spasmodic cough, and wanted o vomit. In spite of emetics, he could not vomit, however, till an hour fter taking the poison, and then with great exertion a dark greenish fluid as ejected; but this afforded no relief to the pain in the stomach and the urning sensation in the throat, which rendered swallowing difficult. The pplication of the stomach-pump afforded no relief. Exhaustion ensued after iolent convulsions, and the symptoms reappeared with renewed force. At he beginning of the third hour, the pains and convulsions attained such iolence that death was expected every instant. In the fourth hour, after peated injections of morphia, the patient seemed somewhat better. revious to this he indicated that his skin was greatly irritated. This ritation of the skin, as of ants crawling, continued apparently the whole me, and whenever the intensity of the pains somewhat remitted, he ratched the skin of the face and breast in a convulsive manner till these ere sore. His *eyes glared wildly*, sometimes resting with a fixed stare

on one point. The convulsions were repeated at almost regular intervals, and the inclination to vomit continued, although vomiting did not continue after the second hour. At intervals of about forty minutes the patient seemed to lose consciousness, but only for a few minutes, and then the convulsions and the other symptoms reappeared with undiminished violence. Three hours after the onset of the symptoms he became incapable of intelligible utterance, but indicated that he felt giddiness; and soon after he appeared to lose sight. He threw himself wildly about on the couch, screamed, and uttered fearful groans. Exhaustion and apparent coma ensued, and then renewed attacks of the most violent description. Then difficulty of breathing set in, and he appeared to suffocate. At intervals he was conscious, indicated that he felt pain in the head and stomach, and was very thirsty. The pulse and body temperature fell considerably, and before death, which occurred at the end of twelve hours, exhaustion and unconsciousness set in, cold perspirations, and death-like pallor. Though death from asphyxia was all along expected, this occurred from syncope. The post-mortem appearances showed nothing unusual. The pupils were dilated, the interior of the mouth was pale, the brain and lungs were congested, the valves of the heart were very flaccid, the liver and kidneys were congested. There was inflammation of the stomach, and its mucous membrane was congested (*sic*). The alkaloid was found by chemical analysis in the contents of the stomach; but, very remarkably, none was found in the urine of the deceased. ('Med. Press.' May 24, 1882, p. 439.)

Analysis.—In any suspected case of poisoning by aconite, the vomited matters, or the stomach and intestines after death, should be carefully examined for portions of vegetable matter which may be compared with the structure of the undoubted aconite plant. Aconitine may be extracted from organic liquids by means of Stas's process for the separation of the alkaloids. In this way, and by applying the tests of taste and that of physiological action on animals (mice) to the substances thus extracted, a very minute trace of aconitine may be detected. No other alkaloid produces the same sensation upon the tongue as the alkaloid, or mixture of alkaloids, known as aconitine. Aconitine yields the general reactions of the alkaloids, and a colour test with sulphuric acid has been described. This colour reaction is, however, valueless, as it does not succeed with pure aconitine, and is due to the presence of impurity. Aconitine readily decomposes when in alkaline solution; and hence it speedily disappears from liquids which remain alkaline, and can no longer be detected. The editor finds that its presence can no longer be detected in viscera where it was known to exist, should these become and remain alkaline for some time from putrefactive decomposition.

CHAPTER 32.

LABURNUM—TAXUS BACCATA, OR YEW—LIGUSTRUM VULGARE, OR PRIVET—ILEX AQUIFOLIUM, OR HOLLY—VIBURNUM OPULUS, OR GUELDER ROSE.

Laburnum (Cytisus laburnum).

Symptoms and Effects.—The *bark* and *seeds* of the common Laburnum contain an active alkaloidal poison called *Cytisine*. A case of poisoning by the *bark*, was the subject of a trial at Inverness. ('Ed. Med. and Surg. Jour.' Oct. 1843.) A youth, with the intention of merely producing vomiting in one of his fellow-servants, a young woman, put some dry laburnum-bark into the

oth which was being prepared for their dinner. The cook, who remarked ' strong peculiar taste ' in the broth, soon became very ill, and in five inutes was attacked with violent vomiting. The account of the symptoms imperfect, for the cause of them was not even suspected until six months terwards. The vomiting continued thirty-six hours, was accompanied ' shivering, pain in the abdomen, especially in the stomach, great ebleness, and severe purging. These symptoms continued, more or less, r a period of eight months; and the woman fell off in flesh and strength. t this time she was seen by a physician, who had been called on to vestigate the case. She was then suffering from gastro-intestinal irrita-n, vomiting after food, pain in the abdomen increased by pressure, rging, tenesmus and bloody evacuations, with other serious symptoms. he medical opinion was that she was then in a highly dangerous state. he woman eventually recovered. There was no doubt, from the investi-ation made by Ross and Christison, that her protracted illness was ally due to the noxious effect of laburnum-bark. A girl, æt. 18, idly nd unthinkingly, put a small portion of a laburnum-branch into her outh, carrying it for some hours, and chewing it. It was described as f the thickness of the little finger, and two or three inches long. There ere some yellow flowers with it, but she was not aware that she had allowed any. In about half an hour she felt unwell, but she was not een by a medical man until the day following. The symptoms then were reat pain in the stomach, nausea and retching, but no vomiting; pulse 00, tongue white, great thirst, anxiety and pallor of countenance, dilated upils, sense of fainting even while lying down, and great exhaustion. here was no purging. Under treatment these symptoms disappeared, nd the girl recovered in about a fortnight. ('Lancet,' 1870, II. p. 182.)

In reference to poisoning by the *seeds* of laburnum, there are but few nstances recorded. Traill has described two cases, and Rake communi-ated to the author a case of poisoning by the pods and seeds. Two hildren, the one aged two and the other three years, had been playing ogether, and on returning home they appeared unwell, and soon afterwards omited. They had been seen with laburnum-pods in their hands, and ome seeds with portions of the pods were mixed with the vomited matter. Both children were pale and exhausted, with a slow and somewhat feeble ulse. The pupils were natural. An emetic was given, but no more seeds ere ejected: the pulse increased in volume and frequency, and the next ay the children had recovered their usual health. Twelve children, at Otley, were attacked with rigidity of the limbs and other symptoms of oisoning, in consequence of having swallowed laburnum seeds. They ecovered under the use of emetics. ('Lancet,' Nov. 1, 1856, p. 497.)

Two boys swallowed a quantity of laburnum-seeds in a cake. In about hree-quarters of an hour one was seized with vomiting and purging, eak and frequent pulse, severe rigors, muscular twitchings in the face nd neck, and great epigastric pain. The pupils were dilated, but there as no headache. Many seeds were vomited. There was a great disposi-ion to sleep, and coldness of the skin. Under treatment they recovered. ' Pharm. Jour.' Oct. 1862, p. 185.) A girl, æt. 9, died in consequence of aving eaten a few of the seeds. A boy, æt. 4, ate about ten of the seeds. n half an hour he began to vomit, the vomited matter consisting of food nd thick mucus. He afterwards became drowsy, and was seized with onvulsions, shaking violently, and drawing up his limbs at intervals. lthough drowsy, he was easily roused, but soon dozed off again. Both upils were widely dilated, pulse 85 and small, surface especially of the mbs cold. He fell into a calm sleep, and the next day he was well. 'Lancet,' 1871, *II. p. 396.)*

In 1882, two fatal cases of poisoning occurred by some undetermined portions of the laburnum tree. ('Brit. Med. Jour.' 1882, I. p. 199.) The victims were two children, aged respectively three and eight years. The elder child was seized with vomiting and diarrhœa, headache, and prostration. In six hours the vomiting and diarrhœa ceased. She then made noises in her breathing, and continued in much the same state till her death, fourteen hours after she was attacked. Next day the younger child became tired and sleepy, vomited, and complained of headache. She vomited freely, and passed two motions. Five and a half hours after the commencement of the symptoms she was convulsed, and the convulsions continued till her death, eight hours from the commencement of the attack. On post-mortem examinations being made, some signs of irritation of the stomach and intestines were observed in each case.

The contents of the stomachs of both children were examined by the eye and by the microscope, but no fragments of the structures of the laburnum were discovered. Good evidence was, however, obtained by Fairley, in both cases, of the presence of cytisine, the poisonous alkaloid present in the flowers, seeds, bark, leaves, and all parts of the common laburnum tree. A small portion of an alcoholic extract made from the stomach and contents of the elder child was administered to a mouse, which died in the course of a few hours.

The *flowers* of this plant are highly noxious. A child, between three and four years of age, ate twelve laburnum-flowers, and in about fifteen minutes it complained of sickness and severe pain in the stomach. The child vomited a quantity of mucus mixed with the yellow petals of the laburnum. An emetic was given: this cleared the stomach, and the child recovered. There was no purging. ('Guy's Hosp. Rep.' 1850, p. 219.) A case in which a child suffered from symptoms of a nervous kind, by reason of its having eaten laburnum-flowers, is described. ('Med. and Physical Jour.' vol. 62, p. 86.)

Analysis.—The poisonous principle of the laburnum is called *Cytisine*. It is difficult of separation, and at present has no well-defined chemical properties whereby it may be identified. Hence, when administered in powder, infusion, or decoction, there are no chemical processes known by which the poison may be detected. *Cytisine* is an alkaloid, having a bitter taste, and is distinguished from many other alkaloids by its insolubility in ether, chloroform, benzol, and carbon disulphide. Most of its salts are uncrystallizable, but the nitrate crystallizes readily. A decoction of the bark forms a clear light brown liquid, having an acid reaction. It strikes a dark olive-green colour with a ferric salt. Nitric acid renders this lighter. Lead acetate precipitates it, but the precipitate has none of the properties of lead meconate. The *leaves* of the laburnum are well known. An illustration of a leaf of its natural size, which is copied from a photograph, is annexed (fig. 92). The *seeds* are somewhat kidney-shaped, and slightly hooked at the hilum. They shrink in drying, become dark-coloured, and present irregular depressions on the surface. They have no markings, and are thus easily distinguished from most other poisonous seeds. They are larger than those of datura stramonium (fig. 91).

Fig. 92.



Leaf of Laburnum, natural size.

Fig. 91.



Seeds of Laburnum. *a*. Natural size. *b*. Slightly magnified by a lens.

Cytisine is said to be the poison contained in an insect powder, which is known by the name of Australian or Persian Insect Powder.

Yew (Taxus baccata).

The yew appears to be a cerebro-spinal poison. The symptoms produced by the *leaves* and *berries* are uniform in character: convulsions, insensibility, coma, dilated pupils, paleness of the countenance, small pulse, and cold extremities, are the most prominent. Vomiting and purging are also observed among the symptoms. In two cases, the subject of one—a girl about five years of age—died in a comatose state in four hours after she had eaten the *berries*, and the other a boy, æt. 4 years, died nineteen days after taking the berries, obviously from severe inflammation of the bowels. The immediate symptoms in the boy were vomiting, purging, coma, convulsions, dilated pupils, hurried respiration, a small pulse, and a cold skin. (See 'Prov. Jour.' Nov. 29, 1848, p. 662, and Dec. 27, p. 708.)

The *leaves* and *berries* of this tree have been long known to be poisonous to cattle, causing death in a few hours, sometimes without vomiting or purging. There is a vulgar but erroneous notion that the leaves are not poisonous when fresh, and that they act only mechanically. It is now well ascertained that yew-leaves and berries exert a specific poisonous action both on men and cattle. If animals recover from the primary effects, they are liable to die after several days from inflammation of the bowels. On one occasion the author examined the viscera of an ox which had died from the poisonous effects of yew-leaves. There was much inflammation, and in some parts of the intestines gangrene had taken place.

Symptoms and Appearances.—A tablespoonful of the fresh *leaves* was administered to three children of five, four, and three years of age, as a vermifuge. Yawning and listlessness soon succeeded; the eldest vomited a little, and complained of pain in the abdomen, but the two younger children suffered no pain. They all died within a few hours of each other.

A lunatic died from the poisonous effects of *yew-leaves*. The deceased was observed chewing the plant, and before the attendants had taken it from him he had succeeded in swallowing a portion of the masticated juice. He was soon afterwards suddenly seized with giddiness, prostration of strength, vomiting, coldness of the skin, spasms, and irregular action of the heart. He died in fourteen hours. On inspection, the stomach was found much distended; and it contained some yew-leaves. There was emphysema in the sub-mucous tissue, but no other abnormal change: there was some thickening with opacity of the arachnoid membrane, which might have been of old standing and due to the insanity. ('Dub. Hosp. Gaz.' May 15, 1845, p. 109.) A girl, æt. 19, took a strong decoction of the *leaves* to bring on the menses. The dose taken was a tumblerful for four successive mornings. Severe vomiting followed, and this was promoted by tepid water. Delirium came on, and the patient died eight hours after taking the last dose. It is stated that nothing of importance was revealed by an inspection of the body. ('Lancet,' 1870, II. p. 471.) In another case, a girl, æt. 13, took the leaves for a similar purpose. Death took place rapidly, without any other symptom of poisoning than vomiting. On inspection, there was congestion of the membranes of the brain, liver, and kidneys; a greenish colour of the contents of the stomach and intestines owing to the fragments of yew-leaves, and stellated inflammation of the mucous membrane of the stomach and bowels.

On these occasions it is difficult to obtain any knowledge of the quantity taken. The following case shows that the life of an adult may be destroyed by a very small quantity of the fresh leaves. A lunatic woman had been employed in preparing evergreen decorations. Nothing unusual was observed by the nurses in attendance until about 10.30 P.M.

She had had some bread and cheese with the other patients, when in about five minutes she slipped off her chair almost helpless. Her countenance turned of a dusky pallid hue, but there were no cerebral symptoms. She vomited a quantity of food mixed with a few bits of yew-leaves. She soon passed into a state of collapse, and died in less than three hours from her first seizure. She retained her consciousness until a few minutes before she died, and admitted that she had eaten some little bits of yew, but she did not think anything of it. The broken leaflets in the vomited matters and the portions found in the stomach and bowels after death, did not amount to a teaspoonful. Yew-leaves may thus prove in small quantity a rapidly fatal poison.

A child, aged three years and a half, ate a quantity of *yew-berries*. In an hour afterwards the child appeared ill, but did not complain of any pain. It vomited part of its dinner, mixed with some of the berries. A medical man was sent for, but the child died in convulsions before he arrived. On inspection, the stomach was found filled with mucus, and the half-digested pulp of the berries and seeds. There were patches of redness in the mucous membrane, and this was so much softened that it could be detached with the slightest friction. The small intestines were also inflamed.

A lunatic ate a quantity of the *berries*, and seven hours afterwards he was found dead sitting in a chair. On inspection of the body, the right cavities of the heart were distended with fluid blood of a dirty plum-colour. The mucous membrane of the stomach was reddened and softened with patches of black congestion. The duodenum was in a similar state. In the lower part of the small intestines there was a mass of the berries. The liver and other soft organs were much congested. ('Med. Times and Gaz.' 1870, 2, p. 446; see also 1871, 1, p. 386, for another fatal case.

Marmé obtained an alkaloid *taxine*, from the berries of the yew ('Med. Cent.' Bl. xiv. p. 97); and the poisonous nature of this alkaloid has been experimentally determined by Borchers ('Exper. Untersuch. u. Wirkung. des Taxin. Göttingen,' 1876). That the poisonous principle of the yew-berry is confined to the so-called stone of the berry is a matter of notoriety; for the pulp is eaten freely with impunity, and a highly esteemed jam is prepared from it. Infusion of yew-leaves, which is popularly called yew-tree tea, is sometimes used for the purpose of procuring abortion by ignorant midwives. A case of death from a person drinking this infusion is reported in the registration returns for 1838-9. In the returns for 1840 there is also one death of a female, æt. 34, referred to her having eaten the berries of the yew. The subject of poisoning by yew-leaves, in reference to their employment for purposes of abortion, has been investigated by Chevallier, Duchesne, and Reynal. ('Ann. d'Hyg.' 1855, vol. 2, pp. 94 and 335.)

Fig. 93.



Yew-leaves and fragments, natural size.

Analysis.—Fragments of the leaves or the berries may be found in the stomach. The yew and the savin are the only coniferous poisons which are indigenous to this country. The apex of the leaf of the yew is not so pointed as that of the savin, and the yew-leaf does not possess the peculiar odour of savin when rubbed. In the annexed illustration (fig. 93) the leaf is of the natural size, the engraving having been made from a photograph of the living leaf. Yew-berries are seen in autumn; they are about the size of a pea, of a light red colour, dull on the surface and translucent. They

e open at the top, allowing a hard brown kernel to be seen. This is an ovoid shape, and it forms the greater part of the berry. The fine d skin contains a colourless and remarkably viscid or adhesive juice, hich reddens litmus paper, and has a sweetish taste.

Privet (Ligustrum vulgare).

The privet is not commonly enumerated among vegetable poisons. No ference is made to this plant in the works of Wibmer, Orfila, Christison, d other writers on toxicology; and yet it would appear, from the sub-ined cases, that the *berries* may exert a poisonous action. In 1853, three ildren ate the *berries* of the privet; two of them, a boy of three years age and a girl of six, eating them rather freely. They suffered from olent purging, and when seen by a medical man the boy was found lseless and cold, and before death he was frequently and violently con-lsed. The girl was in a state of collapse, but rallied a little under eatment: soon afterwards she died convulsed. The surviving child, ho had only tasted the berries, did not suffer, and she was enabled to oint out the shrub, the berries of which they had gathered. In 1866, a hild, æt. 2, died thirty-seven days after eating these berries; symptoms f irritation continuing more or less throughout. After death there were he well-marked appearances of mesenteric disease. According to Loudon, hey are eaten by birds when other sources of food fail.

In May, 1872, two children, aged twelve and eight years respectively, te a quantity of leaves and shoots proved subsequently to have been hose of the privet. The symptoms in both cases were drowsiness, con-ulsive twitchings, difficulty in moving about, loss of muscular power, evere vomiting and purging, the evacuations being of a greenish colour. They both recovered.

The Holly (Ilex aquifolium).

From some published facts, the *berries* of this tree appear to produce he effects of narcotico-irritant poisoning. A boy, three years old, ate a umber of them. The symptoms which followed were sickness, pain in he head and abdomen, and much purging. Many of the berries of the ommon holly were passed in the motions; drowsiness supervened, and here was loss of consciousness. In twenty-four hours his face was pale; he skin pale and cool; pulse eighty, weak and small. The pupils were uch contracted, but were sensible to light. The vomiting had ceased, ut there was some purging. Castor oil and stimulants were given, and n the second day the child recovered ('Lancet,' 1870, I. p. 573). Wibmer peaks of these berries as having merely a purgative action.

Guelder Rose (Viburnum opulus).

The poisonous properties of this plant have received but little notice. Vibmer speaks of its flowers and berries having acrid properties, and indley describes the plant generally as emetic and purgative. This egetable is not, however, simply irritant to human beings; it has mani-ested an action on the brain and nervous system.

In 1870, five children in a family at Sudbury suffered from symptoms f poisoning as the result of eating the *berries* of this shrub, commonly alled snow-berries. One morning the five children were simultaneously ized with violent vomiting which lasted for many hours. Smith saw hem next morning. The vomited matters had then been thrown away. he girl, æt. 5, was in a state of profound coma and insensibility; the upils were not much dilated; pulse 40; legs rather rigid; the arms ot at all so. This girl died about thirty-six hours after eating the berries.

Another child suffered from similar symptoms, but in a less degree, and recovered in two or three days.

In the case of the child that died, the stomach and intestines were quite empty; and there were no marks of inflammation. The brain was slightly congested on its surface but not in its substance, and there was no effusion. This is the only instance of poisoning by this plant known to the author.

CHAPTER 33.

THE CADAVERIC ALKALOIDS, OR PTOMAINES.

UNDER the name of *Ptomaines*, a class of bodies has recently attracted the attention of toxicologists; and it will be well to summarize the observations which have led up to the discovery and recognition as a distinct class of these alkaloidal products of decay and putrefaction. A summary of the observations already published on this class of bodies is given by Th. Husemann in a recent number of the 'Arch. der Pharm.,' an abstract of which is contained in the 'Jour. of the Chem. Soc. of London,' 1881, p. 57. Panum first showed that by the putrefaction of albuminous substances, a soluble ferment is produced, insoluble in alcohol, withstanding the temperature of 100° F., and highly poisonous. Fagge and Stevenson also showed ('Proc. Royal Soc.' 1865; 'Guy's Hosp. Rep.' 1865) that the alcoholic extracts of many *post-mortem* liquids, even after exposure to the temperature of the water bath, are possessed of toxic properties. Bergmann confirmed Panum's observations, and described a definite body, *sepsine*, as a product of fermentation. The researches of Panum and Schweniger showed, further, that at different stages of decay, compounds varying in their physiological actions are generated. Sonnenschein and Zuelzer discovered in poisonous sausages, and also in an anatomical maceration fluid, a peculiar alkaloid resembling atropine in its physiological action; and they also noticed among the products of decay a substance which produced tetanic convulsions. The probable relation of these products of putrefaction to certain diseases is shown by the fact that Sonnenschein's aklaloid has been found in the bodies of patients dying from continued fever, and individuals who have eaten decomposed food and been poisoned thereby, often show typhoid symptoms. Lambroso and Erba showed that decomposed poisonous maize produced tetanic symptoms, and that the maize contained alkaloidal bodies. The tetanus is sometimes associated with or masked by narcosis; and with this may be associated the observation of Ranke—that the proper physiological action of impure strychnine extracted from putrefied corpses may be masked by ptomaines.

Ptomaines, discovered and named by Selmi, are alkaloids generated during decay, and closely resembling the vegetable alkaloids, not only in their physiological effects, but also in their chemical reactions. Some ptomaines appear to be poisonous, others to act counter to known poisons, as Ranke's observations show; whilst others, again, appear to possess no marked physiological activity. That the ptomaines are not exclusively *post-mortem* products has been shown by Spica, who obtained no less than four ptomaines from the fluid taken during life from a patient in a case of peritonitis; all were poisonous, though one only was so in minute doses, and the effects of this resembled curare. Lambroso thinks that the tetanic and narcotic action of extract of putrefied maize, and its beneficial action on several skin affections, point to the possible origin of pellagra in

diseased or putrid maize. This would explain the prevalence of pellagra in the South European maize-growing countries, and assigns the cause to ptomaines. It is undoubted, however, that non-alkaloidal, and probably more or less toxic bodies, are produced during putrefaction, besides ptomaines. Thus, lactic acid and alkaline lactates are formed during the putrefaction of maize; and Aebi and Schwazenbach detected a compound ethereal salt in the extract of dead bodies.

Ptomaines are usually produced in substances which, after brief exposure, have been excluded from access of air, as in buried corpses, the internal viscera, sausages, and tinned foods; and then chiefly in the interior of the article. Cases, however, are known where similar principles have been present in comparatively fresh substances, which have been constantly exposed to air; and hence we must include under the name 'ptomaines' all alkaloidal products of decay, whether formed in the presence or absence of air. It is interesting to note that all animals are apparently not equally susceptible to the action of ptomaines. Thus it is well known that putrefied flesh may be eaten by dogs with impunity. Hansen, who has described pretty fully the chemical and physiological properties of the poisonous ptomaines, states that the chief symptoms produced by them are contraction at first, followed by dilatation of the pupils; slowing of the heart, followed by irregularity in its beats; and convulsions. Selmi, and afterwards Brouardel and Boutmy, detected a ptomaine in the bodies of persons who had died from the effects of arsenious acid; and the latter observers have also found ptomaines in the organs of a person who had succumbed to carbonic oxide. They also state that each case of putrefaction does not give rise to a distinct ptomaine; for they found the same ptomaine after poisoning by prussic acid and carbonic oxide respectively. Since ptomaines present in general the leading properties, physical and chemical, of the vegetable alkaloids, such as veratrine, morphine, and codeine, they may readily be confounded with these. The proper mode of distinguishing between the two classes of bodies is to determine all the chief chemical and physical properties of the isolated base, and to compare these with those of the vegetable alkaloid whose presence is suggested. Unfortunately this can rarely be done, from lack of material to work upon. Hence Brouardel and Boutmy have endeavoured ('Comp. Rend.' 192, p. 1056; 'Ann. d'Hyg.' tome 5, p. 497) to find means sufficient in all cases to disclose the nature of the alkaloid extracted; and they think they have discovered such by making use of potassium ferricyanide and silver bromide as reagents. If a base is present, indicated by the formation of a precipitate with potassium iodo-mercurate, and this instantly changes potassium ferricyanide into ferrocyanide, giving a precipitate of Prussian blue on the addition of ferric chloride, a ptomaine is present; whereas precipitation by the iodo-mercurate, coupled with non-reduction of the ferri- to the ferrocyanide, shows that a vegetable alkaloid is being dealt with. Morphine and veratrine of the vegetable alkaloids are exceptions to the above reaction. Other vegetable alkaloids reduce the ferricyanide slowly; and certain artificial bases containing methyl and phenyl radicals also reduce the ferricyanide instantaneously. In applying the test, the alkaloid is converted into sulphate; and the solution is then tested with potassium iodo-mercurate to ascertain whether a basic substance is present. If so, a few drops of the solution of the sulphate are placed in a watch-glass containing a little solution of potassium ferricyanide, and a drop of solution of ferric chloride is then added, when, if a ptomaine be present, a precipitate of Prussian blue is produced. Gautier has confirmed the results of Brouardel and Boutmy; whereas Turet ('Comp. Rend.' 92, p. 1160) finds that ptomaines produce the above

results only slowly, and as vegetable alkaloids also reduce the ferricyanide slowly, the test is in a measure invalidated. Brouardel and Boutmy have, however, supplemented it by another—the reduction of silver bromide. If a piece of photographic paper imbued with the bromide be written upon with a quill pen dipped in a solution of the base, and the paper be placed in a dark room, and then washed successively with sodium hyposulphite and water, the characters traced upon the paper will be made manifest by reduction which has occurred if a ptomaine be present.

Gautier has also found that albuminous matters, when putrefying in contact with air, generate alkaloids; and states that these bases have physiological properties analogous to some poisonous vegetable alkaloids. Gianetti and Corona point out that most of those poisons act profoundly on the heart and muscles; so that after death the application of induced currents of electricity does not arouse contraction. This physiological reaction is said to be almost characteristic of these substances. Gautier is of opinion that, far from being substances exclusively of cadaveric origin, they are normal and necessary products of the disassimilation of animal tissues; and that he has found very poisonous alkaloids in normal urine. It is, however, entirely contrary to the editor's large experience to find any *poisonous* alkaloid in normal urine. (*Reg.* v. *Lamson*, C. C. C. March, 1882.) The fact that Gautier extracted from human saliva a substance having the same percentage composition as the venom of serpents, has been absurdly translated by an anonymous writer ('Lond. Med. Rec.' 1881, p. 496) into the statement that Gautier has extracted the venom of serpents from such saliva.

Th. Husemann has contributed a valuable article on 'The Significance of the Ptomaines in Toxicological Chemistry' ('Archiv. der Pharm.' No. XVI. 1881, p. 415).

The formation of ptomaines being frequent in corpses when undergoing slow decomposition, it might be presumed that they would be frequently observed in the bodies of persons who have died from acute arsenical poisoning. Selmi has succeeded in demonstrating that under these circumstances peculiar arsenical poisonous bases (arsines) are formed. In 1878, he reported two cases in which poisonous crystalline ptomaines were found in exhumed bodies containing arsenic. The first subject was the body of a person exhumed fourteen days after burial, in a good state of preservation, and containing much arsenic. In the search for alkaloids, a small quantity of an alkaline substance, having a sharp bitter taste, was found. It was crystallizable, yielded crystalline salts, reacted generally as an alkaloid, but gave no precipitate with platinic chloride. It afforded several colour reactions; but the amount of material did not suffice for a complete chemical and physiological examination. Shortly afterwards, Selmi obtained larger quantities of a more easily crystallizable ptomaine from an arsenical corpse exhumed a month after death. This base was alkaline in reaction, and had likewise a sharp bitter taste. Its chemical reactions differed somewhat from those of the previously described alkaloid. It was highly poisonous when administered to a frog.

An endeavour to destroy the base by means of nitro-hydrochloric acid, and then demonstrate the presence of arsenic, led to no definite result, although several milligrammes of the base were employed for the purpose.

Though in these two ptomaines the presence of arsenic was not proved, Selmi afterwards discovered organic arsenical bases (arsines) in the stomach of a pig which had been preserved in a solution of arsenic. The tissues were not destroyed, and there was no putrescent odour perceptible. The alkaline liquid yielded, on distillation in an atmosphere of hydrogen, an alkaline distillate which yielded white crystals with hydrochloric acid.

hese, when moistened with caustic soda, exhaled an odour somewhat sembling trimethylamine. The presence of arsenic was ascertained in ıe hydrochlorate of this volatile base, which yielded some alkaloidal actions. Experiments made with twenty-four milligrammes (0.36 ain) of the substance showed it to be highly poisonous, and that it sembled strychnine in its physiological action. From the solid matter, volatile alkaloid was further extracted, but its small quantity prevented ı accurate examination being made. From the residue of the distillation the ether used in extracting these bases, a third and non-volatile base as obtained, having an alkaline reaction, and of a cadaverous odour. On posure to air, this base became brown, and insoluble in water. Its ydrochloric solution had an offensive odour and a bitter taste. It caused ngling when placed on the tongue, followed by loss of sensibility. The ase yielded alkaloidal reactions, and contained arsenic. It was poisonous) frogs, but its action differed from that of the volatile arsine, and was mewhat similar to that observed as the ordinary action of the poisonous tomaines. Torpor, paralysis, and stoppage of the heart in systole, were he most prominent symptoms. The alleged existence of arsenical ptomaines ı highly important, not only to the medical jurist, but as affording a ossible explanation of chronic arsenical poisoning produced by arsenical all-papers, if Selmi is correct in his assertion, that a volatile arsine is roduced by the contact of arsenious acid and albuminous substances, pos-essing a highly poisonous action differing from that of arsenious acid. Iusemann thinks it likely that a similar product may be formed from the ise employed in affixing the arsenical paper to a room, the moisture of the ir playing a part in the formation of the arsine.

Selmi's researches may, as Husemann thinks, throw light upon an bscure page in the history of toxicology. It is asserted that the poisoners f the seventeenth and eighteenth centuries, Toffa and other professionals, nderstood how to make arsenic more potent. In Italy, the *acquetta di 'erugia* was, according to tradition, a secret compound prepared by rubbing hite arsenic into the flesh of a pig, and collecting the liquid which ropped from the flesh. It is possible that the activity of the arsenic was ncreased, both by the formation of readily-absorbable compounds of arsenic ith the inorganic alkalies, and by the formation of arsenical bases. The me object may have been in view in preparing *aqua Toffana*, with the ddition, as is known, of the juice of the ivy-leaved broad flax (*Linaria ymbalaria*). Selmi and Vella are of opinion that in the *acquetta di 'erugia*, the concealment of the action of the arsenic on the one hand, and lso of the tetanizing poisons on the other, was accomplished; but this pinion, which is based upon an observation of Vella, in a case of poisoning ith arsenic and strychnine, does not accord with observations made on arm-blooded animals with a mixture of potassium arsenite and strychnine, hereby the tetanizing action of strychnine was not prevented, provided he alkaloid was given in poisonous doses.

More recently Selmi ('R. Accord. dei Lancei,' 5, pp. 174, 243; 'Gazetta,' 881, p. 546; 'Jour. of Chem. Soc. of Lond.' 1882, p. 741), suspecting hat in various diseases there are formed in the tissues substances of oisonous nature, which, together with the alterations of the tissues or by eir sole action, determine the death of the patient, has analysed the rine of patients affected with progressive paralysis, miliary fever, eumatic tetanus, and other diseases; also the urine of the insane; and ads that in all these cases, as in the animal body after death, poisonous ses are formed. The urine of a patient affected with progressive paralysis, ccompanied by increasing imbecility, yielded two bases; one resembling at not identical *with nicotine*, having a specific poisonous action,

especially on the spinal marrow, destroying its activity, and diminishing the general sensibility, the respiration, and the pulsations of the heart. The other base resembled conia in odour. A base having the same odour was extracted from the urine of a patient affected with rheumatic tetanus. From the urine of other patients various other bases were extracted, of somewhat indefinite character, but all possessed of poisonous properties.

There is great indefiniteness attached to most of the descriptions of the ptomaines; and experimenters with them seldom commit themselves to statements of the quantities obtained or employed for physiological experiment. Obviously only very impure substances have been separated. The quantities of alkaloids obtained are, when stated, much greater than English experimenters have been able to extract from corresponding quantities of putrid viscera. Paterno and Spica's recent experiments ('Gazetta,' 1882, p. 63; 'Jour. of Chem. Soc. of Lond.' 1882, p. 741) also tend to throw doubts on the work of Selmi. These observers endeavoured to ascertain whether substances identical with, or similar to, cadaveric alkaloids can be extracted from animal fluids in their normal state, before they enter into putrefaction. The liquids experimented on were fresh blood and fresh egg-albumen, solutions of which were tested with various reagents commonly used for the detection of the alkaloids, *e.g.* phospho-molybdic acid, potassio-mercuric iodide, tannin, &c., with the result of showing that the reactions thus obtained are exactly similar to those produced by the same reagents in solutions of the so-called ptomaines extracted from the dead animal body. They also very properly point out, with reference to the search for poisonous alkaloids in a dead body by the hypodermic injection of fluids extracted therefrom into the body of a living animal, that it is necessary to ensure that the fluids injected are free from infective germs, as otherwise it would not be safe to infer that any poisonous effects that may result from the injection were really due to the presence of the alkaloids. By taking these necessary precautions, and by using extraordinary precautions in the separation and purification of the alkaloidal extracts obtained by Stas's process, the editor has convinced himself that the existence of poisonous cadaveric alkaloids in human viscera, even when putrid and diseased, is, to say the least, very rare.

Some observers state that ptomaines are not true alkaloids, but that they belong to the class of chemical compounds known as amides.

)UNDS AND PERSONAL INJURIES.

CHAPTER 34.

EFINITIONS OF A WOUND—INJURY TO THE SKIN—LEGAL DEFINITION—
IMMEDIATE AND NOT REMOTE INJURY TO THE SKIN—IS A DISLOCA-
, FRACTURE A WOUND ?—WOUNDS DANGEROUS TO LIFE—THE DANGER
IT — DYING DECLARATIONS — WOUNDS PRODUCING GRIEVOUS BODILY

erson is the subject of a wound or external injury, from the
hich he ultimately recovers, a medical witness is often rigorously
with respect to the precise nature of the injury, and how far it
risk of life. The answers to these questions may have an
influence on the defence of a prisoner, when the crime is charged
icular forms of indictment.

on of a wound.—We may look in vain in works on medicine and
r any consistent definition of a wound. A wound is commonly
be a 'recent solution of continuity in the soft parts, suddenly
by external causes.' Yet those who adopt this view do not
wounds ruptures of the liver or spleen, burns by heated bodies,
dislocations and fractures, although these injuries are strictly
ded in such a definition.

to the unsettled meaning of the word *wound*, medical witnesses
ly differed in their evidence, and some difficulty has arisen in
ation of charges for unlawful wounding. It has been asserted
der to constitute a wound, the *skin* should always be *broken* or
nd this, indeed, is the interpretation commonly put upon the
t those who adopt this definition do not regard *burns*, produced
eated metals or corrosive liquids, as wounds, although the skin
oken or destroyed. Technical difficulties of this kind, which can
to the embarrassment of witnesses and to the acquittal of
harged with serious offences, might be avoided if the medical
of England would adopt the comprehensive definition sanctioned
al tribunals of certain States on the Continent, namely, that
includes any personal injury, suddenly arising from any kind of
pplied externally, whether such injury is external or internal.'
pear contrary to surgical propriety to designate a burn or fracture
d; but the common surgical definitions will be found on exami-
e inconsistent with each other. The use of such vague defini-
edical evidence has frequently led to acquittals, not upon the
a case, but upon mere technicalities. It is desirable, therefore,
comprehensive definition should be generally adopted. In
o medical evidence we are bound to regard the wants of justice
n the strict rules of surgery. If medico-legal cases fail from
respecting the meaning of scientific terms among surgical writers,
that some fixed rule should be adopted. While the practice of
nnot possibly suffer by such an innovation, the administration
will be rendered more efficient. The statute 14 and 15 Vict.
s, however, supplied a remedy for some of the evils which
rose from a misdescription of personal injuries in indictments.

Legal definition.—It cannot be denied that an alteration in the use of medical terms must, in order to be attended with any good effects, receive the support of our legal authorities. This, probably, would not be long withheld, if good reasons for the change were afforded by medical witnesses. It was at one time held that no injury was a wound in law, unless the continuity of the skin was broken; so that in a case in which blows were inflicted with a hammer or iron instrument sufficient to break the collar-bone, and violently bruise but not break the skin, it was held not to be a wounding within the statute. (*Reg.* v. *Wood*, 'Matthews' Digest,' p. 415.) The Act 1 Vict. c. 85 provided for the punishment of persons guilty of inflicting such severe injuries, but left the legal signification of the word 'wound' unsettled. The 14 and 15 Vict. c. 100 is more precise, but this also avoids any legal definition of a wound.

In order to remove any difficulty in future cases, and to put an end to conflicting decisions, the Commissioners for codifying the Criminal Law suggested that *internal* breaches of continuity should be included under the term 'wound.' They have defined a wound to be '*that whereby the skin is divided either externally or internally*.' Talfourd, J., objected to this definition, because, in his opinion, the division of the skin internally without a division externally was impossible. The use of the word 'skin' leads to ambiguity. The skin consists of the cuticle and cutis. It has been held on more than one occasion that an abrasion of the *cuticle*, or outer skin only, is not a wound in a legal sense. A man was tried (C. C. C. Aug. 1838) on a charge of cutting and wounding the prosecutor. The prisoner struck the prosecutor a severe blow on the temple with a heavy stone bottle, which was thereby broken in pieces. The prosecutor fell senseless, and it was a long time before he recovered from the effects of the violence. The medical witnesses in this case underwent a vigorous cross-examination respecting the meaning of the word 'wound.' They said that there had been a separation of the *cuticle* or outer skin of the temple, but not of the cutis, and that there was no absolute wound in the usual acceptation of the word. They further deposed that the prosecutor had lost the sight of his left eye, and the hearing of his left ear; and he was for a considerable time in a state of great danger, from which he had scarcely recovered. The prisoner's counsel contended that the injuries were not such as to constitute cutting and *wounding* in law. The judges said, that in order that a wound, in law, should have been inflicted, it was necessary that the *whole skin*, and not the mere *cuticle*, should have been separated and divided; and as the evidence did not show distinctly that there was such a wound, those counts of the indictment could not be sustained. The prisoner was, therefore, found guilty of a common assault. A division of the *cutis* or true skin has always been regarded as a wound, whether blood is effused or not. The boundary of the cutis towards the inside of the body is not easily determined; since there is a gradual transition of the cutis into the subjacent fibrous tissue, in which the fat and sudatory glands are contained. The cutis measures in thickness from a quarter of a line to a line and a half (a line is one-twelfth of an inch). It is thicker in some parts than in others. Taking the true skin, or cutis, at the thickness usually assigned, it is impossible to conceive that such a very thin layer of membrane as this can be divided internally without an external division being produced. Allowing the maximum thickness of the eighth of an inch, it would be difficult for any medical man to affirm that only a fractional part of this membrane had been divided internally, when there was no evidence of external separation; and it would be impossible for him to prove it. What the Commissioners probably mean, is a division of the structures beneath the skin. Their definition is, however,

ague and unsatisfactory, because it does not reach an important class of ases in which wounds are inflicted not in the skin, but in the *mucous embrane* lining the outlets of the body. Thus cuts, punctures, or lacera- ons of the lining membrane of the nostrils, mouth, and throat, rectum id vagina, are undoubtedly wounds, although the skin may not be directly uched by the weapon. Injuries of a serious description have thus been equently inflicted on women by cutting and pointed instruments: they ave been regarded as wounds, but they would not be comprised under is term by a strict adherence to the proposed definition. Skin and ucous membrane are not one and the same structure. It is, how- rer, satisfactory to find that there is at least one legal case on record, in hich injuries to the mucous membrane, not involving the external skin, ave been judicially pronounced to be wounds. In Scotland the matter as never been contested. Under this head would fall injuries to the brain roduced by pointed instruments passed up the nostrils through the ethnoid one. Other cases, in which the vagina in females has been thus wounded, re given under the section of 'Wounds of the Genital Organs.' (See ase, post.)

Do all breaches of continuity involving the skin or mucous membrane, all under the head of wounds? Burns appear to constitute an exception; ut there is no reason why a burn producing a destruction of the skin, as y a red-hot poker, should not be regarded and treated in law as a wound. o definition of a wound, medically or legally, can be so contrived as to xclude such an injury. The question, however, mainly to be considered s this—May not a breach of continuity be regarded as a wound, although either the skin nor the mucous membrane is directly implicated in the njury? Is a simple dislocation or fracture a wound? Is a rupture of the ladder, liver, or other organ, suddenly caused by external violence with- ut implicating the skin, to be regarded as a wound? Is a compound islocation or fracture a wound? No definition yet constructed has xcluded these last-mentioned injuries, because the skin is always involved. In a case before the Queen's Bench in Nov. 1847, it was even held that a imple *dislocation* was a wound. An action was brought against a medical ractitioner for negligence in the treatment of a dislocation of the arm, nd a verdict was returned for the plaintiff. An application was made o the Court for a new trial, on the ground of a misdirection. The eclaration alleged that the plaintiff had employed the defendant, who as a surgeon, for the treatment and cure of certain *wounds*, fractures, ruises, complaints, and disorders; but the evidence showed that the efendant had been employed to cure the plaintiff of a *dislocated arm*. At the close of the plaintiff's case, it was submitted that there was no ord in the declaration which was applicable to the case, but this objection as overruled. A dislocation, it was argued, was neither a wound, bruise, or fracture; and the words 'complaint and disorder' were not at all pplicable to a surgical case, but to internal complaints which required to e treated medically. Denman, C.J., in delivering the judgment of the ourt, said, 'It is rather strange that the pleader should have omitted the ost appropriate word; but we think the Chief Baron was quite right.' —Rule refused.

In reference to simple *fractures*, it was held in *Rex.* v. *Wood* (4 'C. nd P.' p. 381), that a fracture of the collar-bone was not a wounding ithin the statute, because the *skin* was not broken. In more recent cases, owever, this decision has been overruled. Thus in *Reg.* v. *Smith* (8 'C. nd P.' p. 173) the prisoner struck the prosecutor with an iron hammer on he side of the face. A surgeon deposed that the lower jaw was broken n two places, and *that the skin* was broken *internally*, but not externally.

There was not a great deal of blood effused. On the objection being taken that this was a *fracture* and not a wound within the statute, Denman, C.J., observed, 'If it is the immediate effect of the injury, we think we cannot distinguish this from the cases already decided;' and Parke, B., said, 'We were of opinion that there was a wound, and upon consideration I am more strongly of that opinion than I was at the outset. There must be a wounding; but if there be a wound (whether there be an effusion of blood or not), it is within the statute whether the wound is *internal* or *external*.' The same point rose in *Reg.* v. *Warman* (1 'Denison, C. C.' p. 183). This was an indictment for inflicting a mortal *wound;* and a question arose whether it was supported by proof of a blow which caused an *internal* breach of the skin (although externally there was only the appearance of a bruise). The death of the deceased had been caused by a single blow on the head by a piece of wood; and the medical witness described the injury as follows:—'I found on examining the head no *external* breach of the skin. I found a collection of blood in the back part of the head: the deceased died from effusion of blood, which pressed on the brain. On examining the scalp, I found a collection of blood between the scalp and cranium, just above the spot where, within the cranium, I had found the pressure on the brain. I call that a contused wound with effusion of blood; that is the same thing as a bruise. The internal part of the skin was broken. Medically, we call the breaking of the skin, whether broken externally or internally, a wound.' This case was reserved for the opinion of twelve judges. All thought that this *internal* injury was a sufficient wound to support the allegation in the indictment.

In each of these cases the Court appears to have been misled by the medical witnesses affirming that the skin (cutis) was broken internally, but not externally. There is no doubt that they intended by this, not the cutis merely, but the connective tissue and soft part beneath. Their evidence has, however, served to mislead the Commissioners, and to induce them to propose a faulty and erroneous definition. There is no instance in which a rupture of the bladder or liver, without any external injury, has been called a wound, although the term might be applied with as much propriety to this kind of injury as to a simple fracture or dislocation. The brain is sometimes lacerated by a blow on the skull which does not break the scalp or the skin of the head. This must, however, be regarded as a wound of the brain; it admits of no other description. Archbold describes a wounding to be where 'the violence is so great as to draw blood, by striking or stabbing with a sword, knife, or other instrument, or by shooting or striking with a cudgel, the fist, or the like;' while 'a wound includes incised, punctured, lacerated, contused, or gun-shot wounds.' ('Pleading and Evidence in Criminal Cases,' 15th ed., by Welsby, 1862, pp. 567, 572.) In the first part of this quotation, the 'drawing of blood' is made a character of a wound. This is inconsistent with the further statement respecting lacerated, contused, and gun-shot wounds, for these injuries are not necessarily accompanied with effusion of blood: and in some of the most fatal wounds of this class no obvious appreciable quantity of blood is effused. From the legal decisions above given, it appears that simple fractures and dislocations, as well as injuries to the mucous membrane of the outlets, are considered to be wounds. No doubt when the question arises, ruptures of the bladder and other organs will be equally considered as wounds for all legal purposes, although the skin may not be involved. From this it appears that the best definition which we can give of the word 'wound,' whether in a medical or legal sense, is that it implies 'a breach of continuity in the structures of the body, whether external or internal, suddenly occasioned by mechanical violence.' This would include

juries to the skin or mucous membrane, dislocations, fractures whether mple or compound, and ruptures of the viscera. Fractures are, however, ɔt usually regarded as wounds.

Wounds dangerous to life.—A medical witness is sometimes asked, hether a wound is or is not dangerous to life. In reference to persons ıarged with an attempt to murder or maim, a written medical opinion, or deposition, may be demanded of a surgeon by a magistrate, in order to ıstify the detention of prisoners. The meaning of the words '*dangerous life*' is left entirely to the professional knowledge of a witness. It is not ıfficient on these occasions that he should make a naked declaration of ıe wound being dangerous to life; he must, if called upon, state to the ourt satisfactory reasons for this opinion; and these reasons are rigorously ıquired into by counsel for the defence. As a general principle, it would ot be proper to consider those wounds dangerous to life in a legal sense, n which the danger is not *imminent*. A wound of a great blood-vessel, of ny of the viscera, or a compound fracture with depression of the bones f the head, must in all instances be regarded as bodily injuries dangerous o life; because in such cases the danger is imminent. Unless timely ssistance be rendered, these injuries will most probably prove fatal, and, ndeed, they often destroy life in spite of the best surgical treatment. When, however, the danger is remote, as in a puncture or laceration of the ınd or foot, which may be followed by tetanus, or in a laceration of the calp, which may be followed by erysipelas, or in penetrating wounds of he orbit, which may be attended by fatal inflammation of the brain or its nembranes, the case is somewhat different. Such injuries as these are not lirectly dangerous to life—they are only liable to be attended with danger n certain cases, and under certain circumstances; hence the medical pinion must be qualified. The law, on these occasions, appears to contemplate the direct and not the future or possible occurrence of danger; f the last view were adopted, it is clear that the most trivial lacerations nd punctures might be pronounced dangerous to life; since tetanus or rysipelas, proving fatal, has been an occasional consequence of very slight injuries. A difference of opinion will often exist among medical witnesses, whether a particular wound is or is not dangerous to life. Unanimity can nly be expected when the judgment and experience of the witnesses are qual. The rules for forming an opinion in these cases, will, perhaps, e best deduced from the results of the observations of good surgical uthorities in relation to injuries of different parts of the body. This will orm a subject for consideration hereafter.

Dying declarations.—The wound may be of such a nature as to cause eath speedily, so that a practitioner may arrive only in time to see the ounded person die. In this case the dying person may make a declaration r statement as to the circumstances under which the wound was inflicted: e may also mention the names of the parties by whom he was assaulted. his *dying declaration* or statement, according to the circumstances under hich it is made, may become of material importance in the prosecution f a party charged with homicide. A practitioner should therefore bserve and make notes of the *exact condition* of the dying person: hether, at the time he makes the statement, he is under the conviction at he must soon die, either expressed in language or implied by his nduct. According to some authorities, it is not necessary that a man ould declare that he believes himself to be dying, in order to render his atement admissible; but there must be evidence that at the time of aking it he was under the full conviction of approaching or impending eath. When it is made clear to the Court, by medical or other testimony, at the person making the statement believed that he was about to die, it

will be received as evidence against the accused; for the law supposes that, under the sense of impending dissolution, all interest in this world is taken away, and that the near contemplation of death has the same powerful effect upon the mind as the solemn obligation of an oath. It is presumed that there can be no disposition on the part of a dying person to wilfully misrepresent facts, or to state what is false. Much, therefore, often depends on the conduct of a medical practitioner under such circumstances, for the usual method of testing the truth of a statement by cross-examination is, of course, out of the question: it must, if admitted at all, be received as it was made.

In *Reg.* v. *Bayley* ('Exch. Chamber,' Jan. 1857), in which it appeared that the surgeon had given some hope to the dying person before the declaration was made, while the declarant stated that he did not himself *believe* that he could recover ultimately, its reception was objected to on the part of the prisoners because the surgeon had given the man some hope. He died two days afterwards. Pollock, C.B., ruled that the real belief of the dying man was the question, and here he had said, notwithstanding the opinion of the surgeon, he believed he could not recover. In the case of *Reg.* v. *Harvey* (Exeter Sum. Ass. 1854) the chief evidence against the prisoner consisted of certain statements made by the deceased. They were admitted by Wightman, J., because it appeared clearly from the evidence that when they were made, deceased had expressed an opinion that she should die *shortly*, and had not changed that opinion. Her whole conduct intimated that she had no hope (or belief) of recovery. It was observed on this occasion that the medical and other witnesses were more desirous of telling the deceased her state, than of ascertaining what her own opinion was. In other cases (*Reg.* v. *Wanstall*, Leeds Aut. Ass. 1869, and *Reg.* v. *Pettingill*, C. C. C. April, 1872), Cleasby, B., held that before a declaration could be admitted as evidence, even when taken down by a magistrate, there must be clear proof that the person making it was in momentary expectation of death, or that death was imminent. In *Reg.* v. *Loudesborough* (York Lent Ass. 1871), Brett, J., declined to receive a statement because the evidence went no further than this—the dying youth said he thought he should not get better; and in *Reg.* v. *Barrett* (Leeds Lent Ass. 1869), Cleasby, B., rejected a statement in which the expression used by the deceased was—she thought she should not recover. This was also the opinion of the surgeon at the time the statement was made, but this did not prove that she believed her death to be impending. In the case of *Jenkins* (Crown Cases Reserved, April, 1869), a statement was rejected because the dying person, in using the expression 'I have no hope of my recovery,' requested that the words 'at present' should be added.

One test of the correctness of a statement is, that the dying person has given at different times and to different persons the same account, but in different language, and that the details are consistent with each other. Even if he recovers after making it, and lives some hours or days, the statement will be admissible provided it was made under the sense or impression of almost immediate death. It is the proof of the sense of impending dissolution which determines its admissibility. Erle, C.J., in Seton's case (*Reg.* v. *Pym*, Hants Lent Ass. 1846), said, 'The law admits these declarations, not because recovery is impossible, but because there is in the mind of the person making them the conviction of approaching death.'

It is no part of the duty of a medical witness to form a judgment on this important subject. He should give the statement as it was made, and leave the Court to decide upon its admissibility from the circumstances

observed by him with respect to the condition of the patient. He should not render himself officious in extracting information. He should receive that which is *voluntarily uttered*, and, either immediately or on the earliest possible opportunity, write down the statement in the *identical* words, carefully avoiding his own interpretation or any paraphrase of them. On no account should leading questions be put—and any question should be simply confined to the purpose of explaining what may appear ambiguous or contradictory in the declaration itself. It is well known that when death takes place from violence, especially when this proceeds from loss of blood or a wound of the head, delirium is apt to supervene, or the intellect of the dying person becomes confused. Hence great caution should be used in receiving a declaration in such cases, since it may lead to the implication of innocent persons. The identity of a person is also, under these circumstances, liable to be mistaken; and it is in general an injudicious proceeding to take a suspected party before one who is dying, in order that he may be identified. At this time there may be a half-delirious state of mind, not easily recognized by non-professional persons; and confessions or statements then made, should, when they implicate other persons and are not strongly corroborated by circumstances, be regarded with great suspicion. A fatal mistake of this kind was made many years since in London. A woman was maltreated by some men on Kennington Common. She was taken to St. Thomas's Hospital, and while dying from the effects of the violence, a suspected party was brought before her, as one of the supposed assailants. She stated that he was one of those who had assaulted her. The man was tried, upon her declaration respecting his identity—found guilty and executed; but a year after the execution, his innocence was satisfactorily established by the discovery of the real murderers.

In *Reg.* v. *Qualter* (Stafford Lent Ass. 1854), the escape of a criminal was attributed to the neglect of the medical attendant in reference to a dying declaration. The deceased was grossly ill-treated, as it was alleged, by the prisoner and others. He lingered from June 19th until Aug. 8th, 1853, when he died from the injuries received. On his death-bed he made certain statements implicating the prisoner, and upon these the case for the prosecution chiefly rested. Qualter was tried for the murder. The deceased told his wife that he knew he should not recover, but this was *after* he had made the statement against Qualter, and it was therefore inadmissible. A similar declaration affecting the prisoner was subsequently made by the deceased to the surgeon; and it seems that the surgeon had told the wife that her husband would not recover, but not in the presence or hearing of the deceased: hence the declaration made by deceased to him was inadmissible, and the prisoner was acquitted. There was a want of proof, in fact, that the statement to either had been made by the dying man while he was under the conviction of approaching death. Had the surgeon informed the deceased that he could not recover, or had he made the announcement to the wife in her husband's presence and hearing, the declaration might have been made under circumstances to render it admissible. It is advisable, in all cases when a medical man perceives that the recovery of a wounded person is impossible, that he should take the first opportunity of stating his opinion to the wounded person in the presence of others, so that the ends of justice may not be defeated by reason of the non-observance of these legal forms. (See *Reg.* v. *Harvey*, Exeter Sum. Ass. 1854.) His duty does not end here. In spite of the medical opinion thus expressed, the dying person may himself have some hope or belief that he shall recover. It is therefore his duty to elicit from the person wishing to make the statement what his opinion of his condition is

—whether he himself actually believes that he is dying, or has some expectation of recovery.

Wounds causing grievous bodily harm.—A wound may not be dangerous to life, but it may have produced '*grievous bodily harm.*' This question is sometimes put, although the usual practice is to leave it to be drawn by the jury as an inference from a professional description of the injury. These words have a vague signification; but it would perhaps be difficult to substitute for them others less open to criticism. They evidently refer to a minor description of offence, and are applied commonly to those injuries which, while they do not actually place life in danger, may be attended with considerable personal inconvenience, or be in some way detrimental to the health of the wounded party. Pollock, C.B., stated on one occasion that 'grievous bodily harm' would reasonably apply to such an injury as would render medical treatment necessary. It is always a question for a jury, whether the *intent* of the prisoner, in inflicting a wound, was or was not to produce grievous bodily harm. Sometimes the nature or the situation of a wound, as well as the kind of weapon used, will at once explain the intent: so far the medical witness may assist the Court, by giving a plain description of the injury, as well as of the consequences with which it is usually attended. It may happen either that the wound itself is not of a serious nature, and yet the intention of a prisoner may have been to do grievous bodily harm; or, as in the following case, the injury may be really serious, and yet the prisoner may not have intended to do grievous bodily harm. A man was indicted for feloniously wounding a girl, with intent to do grievous bodily harm. He kicked her in the lower part of her abdomen—the surgeon described the injury as of the most serious character, and said that at one time he considered the life of the prosecutrix in danger. She was still suffering, and would probably feel the effects of the injury for the rest of her life. The judge in summing up the case told the jury that the material question for them to consider was the *intent* of the prisoner. It was not because serious injury was the result of a prisoner's act, that they were therefore to infer his intention was to do that injury; and they were to judge, from all the circumstances, whether, at the time he kicked the prosecutrix, he intended to do her grievous bodily harm, as was imputed to him by the indictment, or whether he was merely guilty of a common assault. He was found guilty of a common assault. (*Reg.* v. *Haynes*, C. C. C. Sept. 1847.) In *Reg.* v. *Davis* (Chelmsford Aut. Ass. 1871) a man was charged with wounding with *intent* to do grievous bodily harm. It appeared from the evidence that the prisoner, half-drunk, and during a quarrel, suddenly stabbed the prosecutor, inflicting a dangerous wound, with which he was laid up for a month. For a fortnight he was in danger. It was contended that there was no intent to produce grievous bodily harm. Bramwell, B., said the jury might satisfy themselves on that point by looking to the circumstances of the case. Could a man inflict such a wound as this without having an intention to inflict grievous bodily injury? The prisoner was not so drunk but that he knew what he was doing, and all the circumstances showed premeditation and intention—the nature of the wound, the weapon used, and the part of the body struck where an injury was so likely to be dangerous. The prisoner was found guilty of the intent. In cases of this description, the intent with which a wound was inflicted is usually made out by evidence of a non-medical kind. (See also *Reg.* v. *Maslin*, Devizes Sum. Ass. 1838.)

These are the principal medico-legal questions connected with wounds when the wounded person is seen while *living*. We will suppose, however, that the wounded person is found dead, and an examination of the body is

required to be made. The most difficult part of the duty of a medical jurist now commences. Among the numerous questions which here present themselves, the first which demands examination is, whether the wound was inflicted on the body before or after death.

CHAPTER 35.

EXAMINATION OF WOUNDS IN THE DEAD BODY—ALL THE CAVITIES SHOULD BE INSPECTED—ACQUITTALS FROM THE NEGLECT OF THIS RULE—CHARACTERS OF A WOUND INFLICTED DURING LIFE—OF A WOUND MADE AFTER DEATH—EXPERIMENTS ON AMPUTATED LIMBS—CAUTION IN MEDICAL OPINIONS—WOUNDS OR INJURIES UNATTENDED WITH BLEEDING—ECCHYMOSIS FROM VIOLENCE—EVIDENCE FROM ECCHYMOSIS—ECCHYMOSIS FROM NATURAL CAUSES—IS ECCHYMOSIS A NECESSARY RESULT OF VIOLENCE?

Examination of Wounds.—In examining a wound on a dead body, it is proper to observe its situation, extent, length, breadth, depth, and direction:—whether there is about it effused blood, either liquid or coagulated; whether there is ecchymosis, *i.e.* a livid discoloration of the skin from the effused blood; whether the surrounding parts are swollen, whether adhesive matter or pus is effused, and whether the edges of the wound are gangrenous, or any foreign substances are present in it. Care must be taken that putrefaction is not mistaken for a gangrenous condition of the wound. The wound may be examined by gently introducing into it a bougie, and carrying on the dissection around this instrument, avoiding as much as possible any interference with the external appearances. The preservation of the external form will allow of a comparison being made at any future time between the edges of a wound and a weapon found on a suspected person. Of all these points *notes* should be taken, either on the spot or immediately afterwards. In the dissection every muscle, vessel, nerve, or organ involved in the injury, should be traced and described. This will enable a witness to answer many collateral questions that may unexpectedly arise during the inquiry. Another point should be especially attended to. A medical practitioner has frequently contented himself by confining his dissection to the injured part, thinking that on the trial of an accused party the questions of counsel would be limited to the situation and extent of the wound only, but this is a mistake. If the cause of death be obscure, on no account should the inspection be abandoned until all the important organs and cavities of the body have been closely examined; since it may be affirmed that a natural cause of death might have existed in that organ or cavity which the medical witness had neglected to examine. (*Reg.* v. *Holloway*, Abingdon Aut. Ass. 1860.) It rests with the practitioner to disprove the probability thus urged by counsel, but he has no facts on which he can base an opinion, and the prisoner, of whose guilt there may be but little doubt, will have the benefit of his inattention and be acquitted by the jury.

In the medical reports on the examination of the bodies of wounded persons, care should be taken to avoid the introduction of any remarks in the form of inferences from or comments on the facts of the case. At the trial of *McLachlan* (Glasgow Sept. Circ. 1862), Lord Deas objected to the statements in the medical report, 'that the body of deceased had been found under circumstances of great suspicion,' and 'that there were marks

of a severe conflict.' When the witness was cross-examined on the medical facts which had led him to the conclusion that there had been a 'severe conflict,' it resolved itself into the statement that there were marks of blood on the flags, which indicated that the body had been dragged along the floor *after death;* but he was unable to mention any medical facts by which this form of expression could be justified. Inferences of this kind should, as a rule, be excluded from medical evidence and reports.

In making an inspection of the body, the state of the *stomach* should not be overlooked. Death may have been apparently caused by violence, and yet really be due to poison. Wildberg was called upon to examine the body of a girl who had died, apparently from the effects of the violence, while her father was chastising her for stealing. On the arms, shoulders, and back many marks of blows were found; and under some of them blood was effused in large quantity. The injuries, although severe, did not, however, appear sufficient to account for sudden death. He therefore proceeded to examine the cavities, and on opening the stomach, he found it very much inflamed and lined with a white powder, which was proved to be arsenic. It turned out that on the theft being detected, the girl had taken arsenic for fear of her father's anger: she vomited during the flogging, and died in slight convulsions. Upon this Wildberg imputed death to the arsenic, and the man was discharged. A gentleman, having taken eleven grains of strychnine, threw himself out of a window and sustained great bodily injury. The surgeon finding so much more spasm than could be accounted for by the violence sustained, discovered the real state of the case from the patient's confession. There was also evidence of the purchase of the poison. The cause of death may be easily assigned in such cases when the circumstances are known; but it is evident that without proper inquiry and great care in conducting examinations after death, the apparent may be sometimes mistaken for the real cause. (For some interesting cases and good practical suggestions on this subject, see Belloc, 'Cours de Méd Lég.' 148.) In 1864, an inquest was held at Kilburn on a young man who committed suicide by throwing himself from the window. He lived sufficiently long to inform his medical attendant that he had first taken corrosive sublimate, then cut open his wrist that he might bleed to death, and finding this ineffectual, threw himself from the window. Even when there may be no suspicion of poisoning, it will be necessary to observe the state of the stomach and its contents—*i.e.* to determine whether it contains food, the nature of the food, and the degree to which it may have undergone digestion. In *Reg.* v. *Spicer* (Berks Lent Ass., 1846), the falsehood of one part of the prisoner's defence was made evident by an examination of the stomach. The deceased was found dead at the foot of a stair. The prisoner stated that *after* he and his wife had had their dinner, he heard a fall. The woman had died instantaneously, and the fall was heard by neighbours at or near the dinner-hour. The stomach was quite empty; there was no trace of food. It was therefore clear that this part of the prisoner's story was untrue, as, had the deceased died immediately after dinner, some portion of undigested food would have been found.

Description of wounds.—It is impossible to impress too strongly on the mind of a medical witness, that in describing the wounds which he has found on the examination of a body, he should employ plain and simple language, and avoid as much as possible the use of technical or professional terms. The natural desire of a good witness is to make himself understood: but this cannot be accomplished if he clothes his ideas in language which is incomprehensible to educated men of the legal profession, and *à fortiori* to the class of men who constitute juries. A medical witness

ould, for his own credit and for that of the profession to which he belongs, nploy plain and simple language in describing a wound, as well as in ving his evidence generally. (See p. 30.)

Characters of a wound inflicted during life.—If we find about a wound arks of gangrene, the effusion of adhesive or purulent matter, or if the lges are swollen, and cicatrization has commenced, it is not only certain at the injury must have been inflicted before death, but that the person ust have lived some time after it was inflicted. Marks of this description will not, however, be commonly found when death has taken place ithin ten or twelve hours from the infliction of the injury. A wound hich proves fatal within this period of time will present throughout much ie same characters. Thus, supposing it to have been *incised*, there will be aces of more or less bleeding, the blood having chiefly an arterial character, id it will be found coagulated where it has fallen on surrounding bodies. he edges of the wound are everted, and the muscular and cellular tissue round is deeply reddened by effused blood. Coagula or clots are found dhering to the wound, provided it has not been interfered with. The rincipal characters of a wound inflicted during life are, then, the following: . Eversion of the edges owing to vital elasticity of the skin. 2. Abundant leeding, often of an arterial character, with general diffusion of blood in ie surrounding parts. 3. The presence of coagula. The wound may not ave involved any vessel, and there may be no appearance of bleeding, still ie edges will be everted, and the muscles and skin retracted. By an bservation of this kind made on the body of a new-born child (case of *Ilphick*, March, 1848), Prince was enabled to state that the child was ving when it was inflicted, an opinion afterwards confirmed by the conession of the mother.

Characters of a wound made after death.—If the wound on a dead body i not made until twelve or fourteen hours have elapsed from the time of eath, it cannot be mistaken for one produced during life. Either no blood i effused, or it is of a venous character, *i.e.* it may have proceeded from ome divided vein. The blood is in small quantity, commonly liquid, and t does not coagulate as it falls on surrounding bodies, like that poured out f a wound in the living. The edges are soft, yielding, and destitute of lasticity; they are therefore in close approximation. The cellular and nuscular tissues around are either not infiltrated with blood, or only to a ery partial extent. There are no coagula within the wound. In experienting upon amputated limbs, the author found these characters in a ound produced two or three hours after death, although they are best seen hen the wound is not made until after the body has lost all its animal heat. i wounds on the dead body, divided arteries have no marks of blood about em, while in the living body the fatal bleeding commonly proceeds from ese vessels. Hence in a wound on the living, it will be found that the rrounding vessels are empty. The chief characters of a wound after ath are, therefore: 1. Absence of copious bleeding. 2. If there is bleeding is exclusively venous. 3. The edges of the wound are close, not everted. There is no diffusion of blood in the cellular tissue. 5. There is an sence of coagula. But it may happen that a wound has been inflicted on after death, and while the body is yet warm. The distinction between wound then made and one made during life is not so well marked as in unds inflicted at a later period after death. Observations of this kind the human subject must of course be purely accidental; and there e many obstacles to the performance of experiments on bodies recently ad.

In conjunction with Aston Key, the author performed some experiints on recently amputated limbs. *Two minutes* after a leg had been

amputated a deeply incised wound was made in the calf. It must be borne in mind that in the case of an amputated limb, blood will have drained from the severed member, and that the conditions are not precisely those of a wound inflicted after death upon the unsevered limb. At the moment that the wound was made the skin retracted considerably, causing a protrusion of the adipose substance beneath; the quantity of blood which escaped was small, and the cellular membrane, by its sudden protrusion forwards, seemed mechanically to prevent its exit. The wound was examined after the lapse of twenty-four hours: the edges were red, bloody, and everted; the skin was not in the least degree swollen, but merely somewhat flaccid. On separating the edges, a small quantity of fluid blood escaped, but no coagula were seen adhering to the muscles. At the bottom of the wound, however, there was a small quantity of coagulated blood; but the coagula were so loose as readily to break down under the finger. In a second experiment, *ten minutes* after the separation of the member from the body, a wound of similar extent was made on the outer side of the leg, penetrating to the deep-seated layer of muscles. In this case the skin appeared to have already lost its elasticity, for the edges of the wound became but slightly everted, and scarcely any blood escaped from it. On examining the leg twenty-four hours afterwards, the edges of the incision were pale, and perfectly collapsed, presenting none of the characters of a wound inflicted during life. At the bottom of the wound and inclosed by the divided muscular fibres, there were some coagula of blood; but these were fewer than in the former experiment. A portion of liquid blood had evidently escaped, owing to the leg having been moved. Other experiments were performed at a still later period after the removal of the limbs; and it was found that in proportion to the length of time suffered to elapse before the production of a wound, so were the appearances less distinctly marked; that is to say, the less likely were they to be confounded with similar injuries inflicted upon a *living* body. When the incised wound was not made until *two or three hours* after the removal of the limb, although a small quantity of liquid blood was effused, no coagula were found.

When an incised wound is the cause of death, the person dies either immediately, in which case there is copious bleeding from the wounded organ or some large vessel, or he dies after some time, in which case, as the wound continues to bleed during the time that he survives, the longer he lives the more copious will be the effusion of blood. In a wound inflicted after death, and while the body is warm, nothing of this kind is observed. Unless the weapon injure one of the large veins, the bleeding is generally slight, so that the *quantity of blood* lost may assist us in determining whether the wound was made during life or after death. When the body has been moved, and all marks of blood effaced by washing, rules of this kind cannot serve a medical witness, and the time at which the wound was actually inflicted must then be deduced from other circumstances. In the case of *Greenacre*, who was convicted in 1837 of the murder and mutilation of a female, this formed a material part of the medical evidence. The head of the deceased had been severed from the body, and the question was, whether this severance had taken place during life or after death. The prisoner alleged in his defence that it was after death: but the medical evidence went to establish that the head must have been cut off while the woman was living, but probably after she had been rendered insensible by a blow on that part, the marks of which were plainly visible. This medical opinion was founded on two circumstances. The muscles of the neck were retracted, and the head was completely drained of blood, showing that a copious and abundant flow must have

ıed at the time of separation, and therefore indicating that the ulation was probably going on at that time. On cutting off a head r death a small quantity of blood may escape from the jugular veins: this soon ceases, and the quantity lost is insufficient to affect materially contents of the vessels of the head. The chief medical witness, Gird-d, expressed himself with proper caution, by stating, in answer to a stion from the judge, that the wounds in the neck had been inflicted er during life or very shortly after death, while the body still preserved warmth. The circumstantial evidence tended to show that the deceased ı first stunned, and that her head was cut off while she was in a state stupor.

A post-mortem *lacerated* wound occurring as the result of accident, y be attended with such an effusion of blood as to deceive a medical n, unless all the facts of the case are known. In another part of s work (p. 92) is described a case communicated by Gibson, merly the surgeon of Newgate Prison, in which, except from the proof accident after death, a surgeon might have come to the conclusion that ı deceased had been maltreated during life. In any case in which it is ubtful whether a wound was inflicted on a living or dead body, it will be per to adopt the same cautious mode of expressing a medical opinion: ce it must be remembered there are no decisive characters by which unds of the kind referred to can be distinguished; and a medical witness s likely to be wrong as right in selecting either hypothesis. It is a siderable step in evidence, when we are able to assert that a particular und, found on a dead body, must have been inflicted either during life *immediately* after death; for it can scarcely be supposed that in a case ling for criminal investigation, any one but a murderer would think of licting upon a body immediately after death, a wound which would uredly have produced fatal effects had the same person received it while ing. So soon as such an opinion can be safely expressed by a witness, cumstantial evidence will often make up for that which may be, medically aking, a matter of uncertainty.

Wounds or injuries unattended with hæmorrhage.—The copious effusion blood has been set down as a well-marked character of a severe wound eived during life; but this observation applies chiefly to cuts and stabs. erated and contused wounds of a severe kind are not always accom-ied by much bleeding, even when a large blood-vessel is implicated. It rell known that a whole member has been torn from the body, and that le blood has been lost; but in such cases coagula or clots of blood are monly found adhering to the separated parts, a character which indi-es that the wound was inflicted either during life or soon after death, le the blood was warm and fluid. When a lacerated or contused wound olves a highly vascular part, although no large blood-vessels may be licated, it is liable to cause death by loss of blood. A prisoner was rged (*Reg.* v. *Cawley*, Liverpool Wint. Ass. 1847) with having caused death of his wife by kicking her in the lower part of the abdomen. ious bleeding followed, and in spite of medical assistance the woman l very shortly afterwards, evidently from exhaustion produced by the of blood. It was stated in evidence that there was no external lacera-, but an examination of the body showed that a contused wound of the itals had been produced *internally*, and had given rise to fatal bleeding. re is nothing at all remarkable in such a result, considering the abun-ce of small blood-vessels, in these parts of a woman.

Ecchymosis from violence.—Contusions and contused wounds are com-ıly accompanied by a discoloration of the surrounding skin, to which term ecchymosis (ἐκχύω, to pour out) is applied. The subject of

ecchymosis is of considerable importance in legal medicine, since it has often given rise to medical difficulties and complicated questions. It consists essentially in the effusion of blood, generally from small ruptured vessels, into the cellular membrane beneath the skin. An ecchymosis is commonly superficial, affecting only the layers of the skin, and showing itself externally, either immediately or in the course of a short time, in the form of a deep blue or livid red patch. According to Chowne, the former colour is met with in the ecchymosis slowly produced; while that which is the immediate result of violence is red or livid red. In some instances the ecchymosis is deep-seated, the blood being poured out among the muscles and beneath the membranes enclosing them: its extent cannot then be so readily determined by the amount of external discoloration, for this is commonly slight, and it may appear only after the lapse of some hours, or even two or three days. Sometimes the ecchymosis shows itself not over the immediate seat of injury or around it, but at some distance from it. Chowne met with an instance in which a young man received a severe bruise on the inner ankle. In two days ecchymosis appeared around the outer ankle. When blood has once escaped from the small vessels, it will sooner or later diffuse itself where it meets with the least resistance, and the layers of skin in the part struck may become so condensed by the blow, that the blood is diffused in the cellular membrane of the adjoining parts. Syme met with a case in which a compound fracture of the tibia about one-third down, was produced by the wheel of a carriage passing over the leg of a woman. There was no ecchymosis around the seat of injury, but after some days, the skin of the knee and lower part of the thigh became discoloured. ('Ed. Med. and Surg. Jour.' Oct. 1836.) Ecchymosis may sometimes proceed from causes irrespective of the direct application of violence to the skin. Strong muscular exertions, the act of vomiting, and many other conditions, may give rise to a rupture of the minute vessels, and to an effusion of blood in parts which have been stretched or compressed. It has been known to be produced to a great extent around the knee (without any blow), from the stretching of the ligament of the kneepan in a person who was trying to save himself from suddenly falling forwards with his knee bent under him. Such cases are commonly recognized by there being no mark of mechanical injury about the part: the skin is smooth and unabraded.

Ecchymosis signifies an effusion or a pouring out of blood; but the effusion may be so deep-seated (extravasation) as not to present any external discoloration. It is scarcely necessary to observe that the term *effusion* applies to internal as well as to external hæmorrhage, and unless this is borne in mind medical testimony may be wholly misunderstood. Some years ago, on a trial at Edinburgh, the public prosecutor attempted to prove that the person assailed had been wounded to the *effusion* of blood, which, according to the law of Scotland, is an aggravation of guilt in such cases. When the principal medical witness was examined as to the injuries inflicted, he was asked whether any blood had been effused; and he replied that a great deal must have been effused. But he meant effusion of blood under the skin, constituting the contusion or bruise described, while the Court at first received the answer as implying that there had been a considerable loss of blood from a wound externally. The ambiguity was, however, detected. ('Edin. Month. Jour.' Nov. 1851, p. 454.) This case shows the importance of medical evidence being given in language intelligible to all. At the same time the amount of personal injury inflicted is not at all dependent *on the external* effusion of blood. The assault may be of a most serious *kind, and yet* no blood be effused through a wound in the skin.

Violence inflicted on a living body may not show itself under the form f ecchymosis until *after death*. A man received several kicks on the ower part of the abdomen, which caused a rupture of the bladder, and eath from peritonitis. He died in about thirty-five hours; but there was no cchymosis in the seat of the blows, *i.e.* in the pubic and lumbar regions, ntil after death. Hinze met with a ase of suicidal hanging, in which t was observed that ecchymosis appeared in the course of the cord only fter death. (See 'HANGING.') A medical jurist must therefore guard gainst the error of supposing that when a blow has been inflicted on a iving person, it is necessary that the person who is maltreated should urvive for a long period in order that ecchymosis should be produced. hese facts simply prove that the cause producing the ecchymosis may perate during life, but there may be no appearance of it until after death. his disposes of a popular error that ecchymosis can only be produced in the living body, as well as of the theory that unless a person survives for ome time after being subjected to severe blows no ecchymosis will be found on the body. Among numerous cases proving that this statement is not in accordance with facts may be mentioned that of the *Duchess de Praslin*, Aug. 1847. This lady, who was assassinated by her husband, was attacked while asleep in bed. The number of wounds on her person (thirty) showed that there had been great resistance, but the struggle from first to last could not have lasted more than *half an hour*. Yet, on inspection, there were the marks of numerous ecchymoses, which had resulted from the violent use of a bruising instrument. ('Ann. d'Hyg.' 1847, t. 2, p. 377.) Casper considered that ecchymosis required a certain time for its production, and that if a person died speedily from the effects of violence, no ecchymosis would be found on the body, although the violence might have been of a bruising nature. ('Handb. der Gerichtl. Med.' vol. 1, p. 121.) The case of the Duchess de Praslin shows that this is not correct, and Casper himself has admitted that ecchymosis may be produced as the result of violence applied to a recently dead body (see 'STRANGULATION'), a result which is in accordance with other facts mentioned above. If ecchymosis can be produced by violence to the recently dead body, it is clear that a continuance of life is not necessary for its production. The following case shows how these facts may be misapplied. A man was seen to strike one of his companions. The person struck died suddenly. On a post-mortem examination the mark of a bruise was seen over the sixth and seventh ribs on the right side. About a fortnight before this blow was struck, he deceased had met with an accident: a heavy box fell on his right side, nocked him senseless, and nearly killed him. The question at issue was, hether the ecchymosed mark on the side was owing to the blow struck ortly before the man died, or to the fall of the box upon his body a rtnight previously. It was suggested, on the authority of Casper, that as e man died soon after the blow was struck, the ecchymosis could not ve arisen from the blow, but that it was most probably due to the fall of e box a fortnight before. ('Lancet,' 1870, II. 35.) Such a case does not esent much difficulty. If the ecchymosed mark is blue or livid, and ithout any marginal colours, it was probably the result of the blow struck st before death. If the blood is fluid at the time of the violence, and the all capillary vessels are torn through, a blow may cause effusion and the oduction of an ecchymosis on the skin. The warm liquid blood thus used will find its way into the cellular tissue, and produce the usual ternal appearance. If, in the case quoted, the ecchymosis had been proced a fortnight before, it would have shown some changes of colour at e margin, as described in the next paragraph.

Changes of colour in ecchymosis.—The changes which take place in

the colour of an ecchymosed spot will serve to aid the witness in giving an opinion on the probable time at which a contusion has been inflicted. After a certain period, commonly in eighteen or twenty-four hours, the blue or livid margin of the spot is observed to become lighter; it acquires a violet tint, and before its final disappearance it passes successively through shades of a green, yellow, and lemon colour. During this time the spot is much increased in extent, but the central portion of the ecchymosis which received the violence, is always darker than the circumference. These changes are due to changes in and absorption of the blood pigment. The colour is finally entirely removed by the absorption of the blood. The extent and situation of the ecchymosis, the degree of violence by which it has been produced, as well as the age and state of health of the person, are so many circumstances which may influence the progress of these changes. Thus an ecchymosis is longer in disappearing in the old than in the young. Watson found effused blood in an ecchymosis in an old person, five weeks after the infliction of the injury. Where the cellular membrane is dense, the ecchymosis, *cæteris paribus*, is not so rapidly formed; nor, when formed, do the above changes take place in it so speedily as when the blood is effused into a loose portion of membrane like that surrounding the eye or existing in the scrotum. In some instances an ecchymosis has been observed to disappear without undergoing changes of colour at its margin. On examining an ecchymosed portion of skin which has suffered from a severe contusion, we find that the discoloration affects more or less the whole substance of the true skin, as well as the cellular membrane beneath it.

Evidence from the form of an ecchymosis.—It not unfrequently happens that the ecchymosis produced by a contusion will assume a form indicative of the means by which the violence was offered. In hanging, the impression caused by the cord on the neck is sometimes ecchymosed, and indicates its course with precision; so also in strangulation, when the fingers have been violently applied to the fore part of the neck, the indentations produced may serve to point out the manner in which life was destroyed. A case is mentioned by Starkie, which shows that the form of an ecchymosis may occasionally furnish presumptive evidence against an accused party. In an attempt at murder, the prosecutor, in his own defence, struck the assailant violently in the face with the key of the house-door, this being the only weapon he had near at hand. The ecchymosis which followed this contusion corresponded in the impression produced on the face to the wards of the key; and it was chiefly through this very singular and unexpected source of evidence that the assailant was afterwards identified and brought to trial. ('Law of Evidence, vol. 1, art. Cir. Ev.)

Contusions on the dead.—For our knowledge of the effects of *contusions* on the recently *dead* body, we are greatly indebted to Christison. He found that blows inflicted on a dead body not more than *two hours* after death, gave rise to appearances on the skin similar to those which resulted from blows inflicted on a person recently before death. The livid discoloration thus produced generally arose from an effusion of the thinnest possible layer of the fluid part of the blood on the outer surface of the true skin, but sometimes also from an effusion of blood into a perceptible stratum of the true skin itself. He likewise found that dark fluid blood might even be effused into the subcutaneous cellular tissue in the seat of the discolorations, so as to blacken or redden the membranous partitions of the cells containing the fat; but this last effusion was never extensive. From this, then, it follows, that by trusting to external appearance only, contusions made soon after death may be easily confounded with those which have been produced by violence shortly before death.

a contusion has been caused some hours before death, there will be
ng of the part, and probably also certain changes of colour in the
mosed patch, in either of which cases there will be no difficulty in
ng an opinion. Although ecchymosis, or an appearance analogous
may be produced on a body after death, the changes in colour are
net with only under peculiar circumstances, to be presently mentioned.
blood found beneath an ecchymosed spot is clotted, this will afford a
mption of its having been effused during life, although, strictly speak-
t only proves that the effusion must have taken place either before
, or very soon after it. The experiments related, in speaking of incised
ds, show that blood effused from a wound ten minutes after death,
e found in a coagulated state. Again, the circumstance of the blood
d under a contused wound being *liquid*, is not a proof that the effusion
place after death; for sometimes, as in death from a sudden and
it shock to the nervous system, or in cases of rupture of the heart,
ffused blood does not coagulate. Blood effused into the spinal canal
g life is often fluid, and it is well known that blood may be found
ilated in some parts of the body, while it remains fluid in others.
l coagulates more slowly in the dead body than in a vessel into which
s been drawn during life or after death. The blood may remain fluid
dead body from four to eight, and, according to Donné, as long as
e hours after death. ('Cours de Microscopie,' 52.) It rarely begins
agulate until after the lapse of four hours; but if drawn from a blood-
l and exposed to air, it would coagulate in a few minutes after its
val. (See pp. 62, 63.)

n general, contusions which have been produced during life, and in
h the effused blood remains liquid, may be recognized by the *extent* of
ffusion. If, under the ecchymosed parts, we find a large quantity of
d blood, and the seat of injury is so situated that the blood could not
become infiltrated into it, and at the same time there is no ruptured
from which it might have flowed, we may confidently pronounce that
ffusion must have preceded death. In a dead body, a contusion would
but little extravasation, unless a vein of large size had been torn
igh. The sign which is most satisfactory as a criterion, in the opinion
hristison, is, however, the following:—In a contusion inflicted during
the ecchymosed portion of cutis (true skin) is generally dark and
s discoloured by the infiltration of blood throughout its whole thick-
; the skin at the same time is increased in firmness and tenacity.
is not, however, a uniform consequence of a contusion during life; for
w may cause effusion of blood beneath the skin without affecting the
in the manner stated. The state of the skin here described, cannot
roduced by a contusion on a dead body; although it is still an open
ion, whether it might not be produced if the contusion were inflicted
r minutes after death. As it is, the value of this sign is somewhat
mscribed,—it is not always produced on the living,—it might be
bly produced on the recently dead; so that when it does not exist,
nust look for other differential marks, and when it does exist, we
t to satisfy ourselves that the contusion was not inflicted recently
death.

he period at which such injuries cease to resemble each other has not
fixed with any degree of precision; but, as in the case of incised
ids, it would seem that there is little danger of confounding them,
s a contusion has not been inflicted on a *dead* body until after the
ppearance of animal heat and the commencement of cadaveric rigidity.
stison found that sometimes the appearance of contusion could hardly
oduced on a dead body two hours after death; on other occasions such

an appearance might be slightly caused after three hours and a quarter, but this period was near the extreme limit. Whenever the warmth of the body and the laxity of the muscles are not considerable at the time the blow is inflicted, the appearance of contusions during life cannot be distinctly produced. It is, therefore, only on the trunk that, even in the most favourable state of the body—namely, when warmth is retained and the blood remains altogether liquid—a mark resembling a contusion on the living body can be produced so late as *two hours* after death. ('Ed. Med. and Surg. Jour.' No. 99, p. 247 *et seq.*) Notwithstanding these satisfactory results, it will be seen that, from the moment of death until after a lapse of two hours, contusions may be followed by appearances on the dead almost identical with those observed on the living. The *earliest period* after death in which an experiment was tried on the human body was *one hour and three quarters:* in this case the similarity was so strong that we may infer, if the experiments had been performed within half an hour, or even an hour after death, it would have been difficult to say whether the blow producing the discoloration had been inflicted on a living or dead body. Christison's experiments lead to the conclusion that *severe* blows inflicted on a recently dead body produce no greater degree of ecchymosis, or cutaneous discoloration, than *slight* blows inflicted on the living. Assuming that the great extent of an ecchymosis would in all cases serve to show that the violence which produced it had been inflicted during life, it must be remembered that the importance of these facts in relation to medical evidence, is not affected by the extent of the discoloration. It may be just as necessary to have a positive opinion on the origin of a *slight*, as on the origin of an *extensive* bruise. Slight ecchymoses, as in cases of strangulation or suffocation, if they can be certainly pronounced vital, may make all the difference between the acquittal and conviction of a person charged with murder. Again, slight ecchymosis on the bodies of the drowned may excite a suspicion of strangulation and subsequent immersion of the body in water. So in reference to child-murder. An infant may be destroyed by violence, and only a few slight marks of ecchymosis be found upon its body. Irrespective of the *extent* of an ecchymosis, the great point for a medical witness to consider is, whether it occurred during life or after death. Cases in which a mistake might easily have arisen will be related in speaking of marks of violence on the drowned.

The practical inference is, that these discolorations of the skid caused after death, are liable to be mistaken for marks of violence on the living body. An instance occurred in which, for the sake of experiment, blows with a stick were inflicted on the recently dead body of a woman while still warm. The body was afterwards accidentally seen by non-professional persons, who were not aware of the performance of these experiments; and so strong was the impression from the appearances, that the deceased had been maltreated during life, that a judicial inquiry was instituted, when the circumstances were satisfactorily explained.

Ecchymosis from natural causes in the living.—There are certain conditions of the living body in which ecchymosed marks are found on the skin. A medical witness must be careful not to confound these marks with ecchymosis arising from violence. First with regard to the living body—in aged persons, it is not unusual to find the legs and feet covered with livid patches, sometimes of considerable uniformity of colour, and at others much mottled. These discolorations, which, after death, might be mistaken for ecchymosis from violence, arise from the languor of the capillary circulation in such persons: the blood finds its way with difficulty through the venous capillaries, and the marks are commonly observed on the lower parts of the body, because they are far removed from the

re of circulation, and the blood has to rise in opposition to gravitation. s is the condition which has been denominated by Andral, asthenic ræmia. (Andral, 'Anat. Pathol.' t. 1, p. 40.) Similar discolorations sometimes met with on the bodies of those who have died from scurvy, hus, and other adynamic diseases. In persons severely affected with rvy, it is well known that the slightest pressure on any part of the skin l suffice to produce a spot resembling the ecchymosis of violence, and ing like it from a rupture of minute cutaneous vessels; but the effusion blood, which causes the discoloration, is commonly confined to the erficial layers of the true skin. These patches, under certain states of system, occur spontaneously, and often cover the body to a great ent: when small, they take the name of *petechiæ*, but when extensive, which case they bear some resemblance to the ecchymosis of violence, y constitute the pathognomonic character of the disease termed *purpura*.

all these effusions of blood in the living body, the term *Sugillation gillatio*, a black mark) has been applied. Some medical jurists have empted to draw a distinction between ecchymosis and sugillation: thus is said, ecchymosis proceeds from external, sugillation from internal, ses; ecchymosis is confined to the marks which occur in the living dy, sugillation to those which occur in the dead:—in ecchymosis the sels are ruptured, in sugillation there is mere congestion; again, some ve considered that ecchymosis and sugillation might take place both in living and the dead. (Henke, 'Zeitschrift der S. A.' vol 1, p. 199, d 'Ann. d'Hyg.' 1838, 2, 383.) From this statement, it appears im- sible to give a consistent definition of the meaning of either of these ms: but it is altogether unnecessary to make the attempt, for the error, er all, consists in the introduction of a superfluity of words to express a ple condition of the body, depending on different causes. Why, according the view taken by Chaussier, an ecchymosis should not also be called sugillation, it is difficult to say: for the definitions above given create real distinction. A medical jurist should avoid the use of the term gillation, if by employing it he considers that he is speaking of a dition essentially different from ecchymosis. It may be occasionally cessary to distinguish ecchymoses in the living body arising from infirmity disease, from those which have their origin in violence. In regard to spots or patches on the legs of old persons, their great extent, envelop- g as they often do the whole circumference of a leg, is sufficient to ablish a clear distinction. In distinguishing the patches of *purpura*, difficulty may sometimes exist, but here also the appearance of the bject, the general diffusion of them over the whole of the body, and ir simultaneous existence on the mucous membrane of the throat and mentary canal, cannot fail to point out that they originate in some other se than violence. In the living, these spots have been observed to dergo the same changes of colour as the true ecchymosis of violence. has been alleged, on the authority of Zacchias, one of the early writers medical jurisprudence, that a distinction is obtained in these cases r death by a dissection of the part. According to this authority, in at is termed sugillation, *i.e.* the ecchymosis of disease, the blood is fluid, le in the ecchymosis of violence it is described as being in a thick and crete state. In the remarks already made respecting contusions, facts e been mentioned which show that such a distinction is inadmissible; her the state of the blood nor its situation will alone suffice to determine question. Although it has been usual to describe the ecchymosis of ase as being due to a superficial extravasation on the true skin, yet urpura and scurvy the discoloration may occasionally extend through whole substance of the skin to the fatty tissue beneath.

Ecchymosis in the dead body. Lividity.—Ecchymosis may present itself in various forms on the skin of a dead body. The first form when it occurs, is almost an immediate consequence of death, but it is not fully developed until the body has cooled. It is commonly called *cadaveric lividity.* It presents itself in diffused patches of great extent, sometimes covering the whole of the fore part of the chest and abdomen, at other times the lateral regions of the back. The upper or lower limbs, either on their internal or external surfaces, or on their whole circumference, are often thus completely ecchymosed. The appearance is wholly unlike the effects of external violence. Ecchymosis may be a result of putrefaction from the fluid blood escaping from a vessel. Effusions of blood beneath the skin from causes operating after death may produce appearances like those caused by violence, and in certain exceptional cases zones of colour somewhat resembling those of a disappearing ecchymosis may be produced. (See p. 88, *et seq.*)

Is Ecchymosis a necessary result of violence?—This medico-legal question has often created great difficulty to medical witnesses. It has been repeatedly asserted in courts of law, that no severe blow could have been inflicted on the body of a person found dead, in consequence of the absence of ecchymosis or other indication of violence from the part struck; but this assertion is opposed to well-ascertained facts. However true the statement may be that severe contusions are commonly followed by ecchymosis, it is open to numerous exceptions; and unless these are known to a practitioner, his evidence may mislead the Court. The presence of ecchymosis is commonly presumptive evidence of the infliction of violence, but its absence does not negative this presumption.

It was remarked by Portal, that the spleen had been found ruptured from blows or falls, without any ecchymosis or abrasion of the skin appearing in the region struck. This has been also observed in respect to ruptures of the stomach, intestines, and urinary bladder, from violence directly applied to the abdomen. Portal supposed that the mechanical impulse was simply transferred through the supple parietes of the abdomen to the viscera behind, as in the striking of a bladder filled with water. Whether this be the true explanation or not, it is certain that the small vessels of the skin often escape rupture from a sudden blow, so that their contents are not effused. Casper thought that under these severe injuries the non-production of ecchymosis in the skin was to be ascribed to the loss of blood from the ruptured liver or other organ ('Hand. der Gerichtl. Med.' 1, 121), but this explanation will not account for the facts. In some of the cases the part ruptured has been the intestines or the urinary bladder, from which a large quantity of blood would not flow. A case is reported by Henke, in which a labouring man died some hours after fighting with another, and on an inspection of the body the peritoneum was found extensively inflamed, owing to an escape of the contents of the small intestines, which had been ruptured to a considerable extent. There was, however, no ecchymosis or mark on the skin externally, and the medical inspectors were inclined to affirm, contrary to direct evidence, that no blow could have been struck; but others of greater experience were appealed to, who at once admitted that the laceration of the intestines might have been caused by a blow, even although there was no appearance of a bruise externally. Watson states that a girl, aged nine, received a smart blow upon the abdomen from a stone. She immediately complained of great pain, collapse ensued, and she died in twenty-one hours. On inspection there was no mark of injury externally, but the *ileum* (one of the small intestines) was found ruptured, its contents extravasated, and the peritoneum extensively inflamed. ('On Homicide.' p.

.) A man received a kick on the abdomen from a horse: he died in rty hours from peritonitis. The ileum was found to have been torn npletely across in its lower third. There was not the slightest trace of hymosis externally, a fact which is the more remarkable, since the blow s here struck by a somewhat angular or pointed body—the hoof of a rse. ('Med. Gaz.' May, 1840.) In a fatal railway accident which urred at Leicester in 1854, there were no marks of external violence on head, but Macaulay found a laceration of the left hemisphere of the ain, with effusion of a large quantity of blood which had coagulated.

Many cases might be adduced in support of the statement that ecchymosis is not a necessary or constant result of a severe blow or mechanical olence; but those above related sufficiently establish the fact. (See tuptures of the Heart, Liver, Spleen, and Kidneys,' post.) This medico-gal question frequently arises in cases in which the bladder or liver is ptured, as, owing to the general absence of marks of violence, it is often leged in defence that no blow or kick could have been inflicted on this rt of the abdomen. The incorrectness of this view will be apparent by a ference to cases of ruptured bladder related in another part of this work. ston observed a case of rupture of the liver, under circumstances in which chymosis would have been generally expected to take place as a result of olence. In 1852, a woman, aged 75, was run down by a cab in the streets of lasgow, and died in less than half an hour. No ecchymosis existed, although ur ribs on the right side of the chest at the lower part were broken, and e liver was ruptured longitudinally in two places, and throughout the entire ngth of its anterior and convex surface. The laceration of this organ had t been caused by the fractured ends of the ribs penetrating downwards, for these there was no displacement, but the organ seemed to have burst in nsequence of the heavy compression to which it had been subjected, which ld not, however, been sufficient to occasion any discoloration of the skin ternally. The following case was tried in Glasgow, in 1837. A woman as found dead in her house, and her husband was accused of having urdered her. There was no mark of violence externally; but on opening the abdomen, the liver was found extensively lacerated, and there was o doubt that this was the cause of death. A medical witness asserted, at as there was no appearance of injury externally, the rupture could not ve been caused by a fall or a blow. He attributed the absence of marks ecchymosis to the rupture having been occasioned by the forcible ssure of some heavy rounded smooth body on the abdomen. The isoner was acquitted on a verdict of not proven. The liver is seldom ptured except from violence directly applied, and it is observed that the pture is more commonly caused by a *sudden* than by a slow application violence. It may have been ruptured in this case either by a blow or a l—the absence of ecchymosis in the skin of the abdomen is consistent h either view. The explanation given by the witness would neither count for the rupture nor for the absence of ecchymosis; for these conions are more commonly met with under directly opposite circumstances. the same time, in cases where the facts are imperfectly known, a surgeon st not be too ready to assume, in the absence of ecchymosis or injury to skin, that violence has been directly applied and has caused the rupture an internal organ. That murderous violence may be produced by blows a body without leaving any external marks, is further proved by a case d in Scotland (*Cuming*, for the murder of his wife, Dec. 19th, 1853). e woman died from a severe injury to the head, but she chiefly comined of great pain in one of her breasts, and in her chest on that side. om her statement it appeared that the prisoner had used great violence this part of her body; yet on a careful examination, during life and

after death, there were no marks of ecchymosis or contusion. The case of *Slater and Vivian* (C. C. C. Sept. 1860), charged with the manslaughter of a lunatic at Colney Hatch Asylum, presents many points of importance in reference to this medico-legal question. (Winslow's 'Med. Critic, and Psych. Jour.' 1861, p. 91.)

CHAPTER 36.

EVIDENCE OF THE USE OF A WEAPON—CHARACTERS OF WOUNDS CAUSED BY WEAPONS—INCISED, PUNCTURED, LACERATED, AND CONTUSED WOUNDS—STABS AND CUTS—WHAT ARE WEAPONS?—EXAMINATION OF THE DRESS—WOUND PRODUCED THROUGH THE DRESS.

Evidence of the use of a weapon.—It is not necessary to prove that a weapon has been used for the production of a wound, for the words of the statute are:—'Whosoever shall, *by any means whatsoever*, wound or cause any grievous bodily harm to a person,' &c.; yet evidence of the use of a weapon in case of assault may materially affect the amount of punishment awarded on conviction. When, upon the clearest evidence, it is certain that a weapon has been used, it is not unusual for prisoners to declare that no weapon was employed by them, but that the wound had been occasioned by accidental circumstances. A witness should remember that he is seldom in a position to swear that a particular weapon produced at a trial must have been used by the prisoner:—he is only justified in saying, that the wound was caused either by it or by one similar to it. Schwörer relates the following case. A man was stabbed by another in the face, and a knife with the blade entire was brought forward as circumstantial evidence against him, the surgeon having stated that the wound had been caused by *this* knife. The wounded person recovered; but a year afterwards an abscess formed in his face, and the broken point of the real weapon was discharged from it. The wound could not therefore have been produced by the knife which was brought forward as evidence against the prisoner at the trial. ('Lehre von dem Kindermorde.') Although the criminality of an act is not lessened or impugned by an occurrence of this kind, it is advisable that such mistakes should be avoided by the use of proper caution on the part of a witness. On this question, see the case of *Renaud*, 'Ann. d'Hyg.' 1839, 2, 170. As to what is a weapon, see Henke, 'Zeitschrift der S. A.' 1844, 1, 67.

Characters of wounds produced by weapons.—Let us now suppose that no weapon is discovered, and that the opinion of a witness is to be founded only on an examination of the wound. It is right for him to know that on all criminal trials considerable importance is attached by the law to the fact of a wound having been caused by the use of a weapon; since this generally implies malice, and in most cases a greater desire to injure the party assailed than the mere employment of manual force. Some wounds, such as cuts and stabs, at once indicate that they must have been produced by weapons.

1. *Incised wounds.*—In incised wounds, the sharpness of the instrument may be inferred from the cleanness and regularity with which the edges are cut: in stabs, also, the form and depth of a wound will often, but not necessarily, indicate the kind of weapon employed. Stabs sometimes have the characters of incised punctures, and may be mistaken for such, one or *both* extremities of the wound being cleanly cut, according to whether the weapon was single or double-edged. Dupuytren has remarked that such

stabs, owing to the elasticity of the skin, are apparently smaller than the weapon—a point to be remembered in instituting a comparison between the size of a wound and the instrument. A lateral motion of the weapon may, however, cause a considerable enlargement of the wound. (See case, 'Ann. d'Hyg.' 1847, 1, 400.)

2. *Punctured wounds.*—It is necessary to notice whether the edges of a punctured wound are lacerated and irregular, or incised; because it may be alleged in defence, that the wound was produced by a fall on some substance capable of causing an injury somewhat resembling it. A case occurred in which a deeply penetrating wound on the genital organs of a woman, which had evidently caused her death, was ascribed by the prisoners charged with the murder to her having fallen on some broken glass; but it was proved that the edges of the wound were bounded everywhere by clean incisions, which rendered this defence inconsistent if not impossible. A similar defence was made on two other occasions, where the cases came to trial. In one, a man struck the prosecutor, and knocked him against a window. On examination, there were three deep cuts on the face of the prosecutor, but no weapon had been seen in the hands of the prisoner. He was charged with cutting and stabbing. The surgeon deposed that the wounds appeared to have been inflicted with a knife or razor-blade, and not with broken glass. If the wounds had been made with glass, particles of that substance would probably have been found in them, but there were none. The prisoner was acquitted, the infliction of the wounds by a weapon not being considered to have been sufficiently made out. In another case that occurred in 1841, the prosecutor was knocked down, and his throat was found severely cut, but there was no direct proof that a weapon had been used. In the defence it was urged that the wound had been produced by a broken pane of glass, but the surgeon described it as a clean cut, five inches in length and one inch in depth, laying bare the carotid artery. He considered that it must have been inflicted by a razor or knife, and that it was a cut made by one stroke of the instrument. In *Reg.* v. *Ankers* (Warwick Lent Ass. 1845), a clean cut as from a penknife, about two inches long and one deep, was proved to have existed on the person of the prosecutor, who had fallen during a quarrel with the prisoner. Some broken crockery was lying near the spot, and it was alleged in the defence that a fall upon this had caused the wound. This allegation was inconsistent with the clean and even appearance of the edges of the wound. The prisoner, in whose possession a penknife had been found, was convicted.

When a stab has traversed the body, the entrance-aperture is commonly larger than the aperture of exit; and its edges, contrary to what might be supposed, are sometimes everted, owing to the rapid withdrawal of the instrument. That facts of this kind should be available as evidence, it is necessary that the body should be seen soon after the infliction of a wound, and before there has been any interference with it.

In general, wounds made by *glass or earthenware* are characterized by their great irregularity and the unevenness of their edges. Cases of this kind show that, as it is not always possible to know when this sort of defence may be raised, a medical witness should never fail to make a minute examination of a wound which is suspected to have been criminally inflicted. A trial for murder took place (Worcester Sum. Ass. 1838) in which it appeared in evidence that the deceased had died from a small punctured wound in the chest. It was five inches and a half deep; it had completely traversed the right ventricle of the heart, and had led to death by loss of blood. The wound was supposed to have been produced by a small skewer, *which was found* near the spot, but in the defence it

was alleged that the deceased had fallen over a tub, and that the wound had been caused by a projecting nail. This allegation, however, was negatived by the surgeon, from the fact of its being a cleanly *cut* wound. Had it been produced in the manner alleged by the prisoners, this would have been indicated by an irregularity of margin. In the case of *Bryant* (Taunton Lent Ass. 1849), which involved a charge of maliciously stabbing the prosecutor, the defence was that many flints were lying about in the road, and as the assault took place in the dark the wound might have been inflicted accidentally during a fall. The medical witness could not say that the wounds had been positively caused by a weapon: they might have been produced by the flints. The prisoner was acquitted, as the statute then required proof that a wound had been inflicted by some instrument. A careful examination made at the time of the injury would most probably have enabled the witness to give a decided opinion, instead of leaving the case open to doubt. A puncture made by a flint during a fall is not likely to resemble a stab with a knife. The wound would present some marks of laceration and great irregularity. As the wound was under the ear, it was by no means probable, from the situation, that it could have been thus caused accidentally. A similar question has recently arisen in a case in which the prisoner was charged with inflicting a wound with a knife. In the defence it was urged that the wound was caused by the sharp edge of an oyster-shell. A careful examination made when a wounded person is first seen would enable a medical man to meet suggestions of this kind, which are often thrown out unexpectedly in the defence. The answer to such a question may materially affect the amount of punishment inflicted on the prisoner, as the use of knives or daggers is looked on with severity.

These medical difficulties are now for the most part removed by 24 and 25 Vict. c. 100. This must not, however, lead the witness to suppose that a personal injury is not to be carefully examined with a view to the determination of this question. In 1853, the careful examination of a wound disproved a charge of maliciously wounding made against innocent persons. A little girl was represented to have received, while sitting over an iron grating, a wound in the pudendum, by some person pushing a toasting-fork or pointed instrument between the bars of the grating from below. There were no marks of punctures, which would have been found had this statement been true, but a slight laceration of the parts, such as might have been produced by an accidental fall on the edge of the iron grating while the girl was in a sitting position. There were also marks of bruises on the thigh, such as might have occurred from an accident of this kind. The mother of the child had made a false charge for the sake of exciting public compassion and extorting money. A proper surgical examination of the injury clearly established that it had resulted from accident. The part of the body in which the injury existed in this case, is not usually exposed to laceration or punctures from accident; but the child, for a certain purpose, had placed herself voluntarily in this position, and had on her own admission slipped, and thus probably injured herself.

3. *Lacerated and Contused wounds.*—Lacerated wounds do not in general present greater difficulty with regard to their origin than those which are incised or punctured. The means which produced the laceration are commonly well indicated by the appearance of the wound. These injuries are generally the result of accident; they are, however, frequently met with on the bodies of new-born children, in which case they may give rise to a charge of infanticide. If it could be proved that they had arisen from the use of a weapon, this would, of course, go far to a conviction on a

harge of murder. *Contused* wounds and severe contusions present much reater difficulty to a medical jurist. It is not often in his power to say hether a contused wound has resulted from the use of a weapon, from *a ow of the fist*, or *a fall*, by reason of the deceased having accidentally llen against some hard surface. The question is frequently put to edical witnesses on those trials for manslaughter which arise out of the gilistic combats of half-drunken men. One of the combatants may be illed, either by a blow on the head, by a fall, or by both kinds of violence mbined. The skull may or may not be fractured; and the person may e of concussion, inflammation of the brain, or from effusion of blood. he general defence is that the deceased struck his head against some hard bstance in falling on the ground, and a surgeon is asked whether the rticular appearances might not be explained on the supposition of a fall. medical witness is rarely in a position to swear with certainty that a ntused wound of the head must have been produced by a weapon and t by a fall. Some circumstances, however, may occasionally enable him form an opinion on this point. If there are contused wounds on several rts of the head, with copious effusion of blood beneath the skin, the esumption is that a weapon must have been used. If the marks of olence are on the summit of the head, it is highly probable that they ve been caused by a weapon, since this is not commonly a part which can ceive injury from a fall. So if sand, gravel, grass, or other substances be und in a contused wound, this will render it highly probable that the jury was really caused by a fall. When the question is simply whether contused wound was produced by a blow of the fist or by a weapon, it ay admit of an answer from an examination of the wound, as in the llowing case. Two men were fighting, and one struck the other a severe ow on the head, felling him to the ground. The deceased was rendered sensible and soon died. There was a fracture of the skull six inches in ngth. The prisoner alleged that he struck the deceased only with his st. The medical opinion was that a blow of the fist could not have oduced such a severe injury. A weapon must have been used. While ll allowance is made for the effect of falls, it must be remembered that ere are injuries which from their nature are not likely to have been pro-uced by blows of the fist.

It matters not, under the statute on wounding, whether the wound as produced directly by a weapon employed by an assailant, or indirectly r any act of violence on his part. A man may fracture the skull of nother either by striking him with a brick, or by striking him with his st and thus causing him to fall against a brick. Acquittals formerly ok place upon technicalities of this kind; but in *Reg.* v. *Dodd* Shrewsbury Sum. Ass. 1853), Coleridge, J., expressed a strong opinion gainst the distinction thus made. The prisoner, it was alleged, threw stone at the deceased, who immediately fell on a stone floor. The ceased was able to go about for several days, but he died a week after had sustained the violence, from inflammation of the brain, as a sult of fracture of the skull. The medical witness ascribed the fracture a blow from a stone. In the defence it was urged that the fracture ight just as well have arisen from the fall on a stone floor. Coleridge, J., ld, if the prisoner knocked the deceased down, that it would make no fference whether the deceased died from the fall on a stone floor, or om injury directly produced by the stone which was thrown at him.

In *Reg.* v. *Howes* (Croydon Sum. Ass. 1863), the deceased, the wife the prisoner, was found dead with severe contusions on the head and ce, and a lacerated wound on the temple. She died from extravasa-on of blood *on the brain*. The defence was that deceased had fallen

cause of the violence, Channel, B., remarked—' If there were blows means of blows the prisoner caused the falls, then though the blow not themselves be the direct cause of death, he would be respon the result.' The prisoner was convicted of manslaughter. A simil tion arose in *Reg.* v. *Budd* (Kingston Lent Ass. 1868), where was charged with killing his wife by blows. It appeared that either kicked her, and produced the injury which caused her death she had fallen upon some wood as a result of his violence. Byles it was not material whether death was caused directly by the blow or whether the prisoner struck or pushed his wife and she fell so a duce the injury which caused her death; the prisoner would eq guilty of manslaughter. He was convicted. If it could be shown fall was the result of some accident, then it might be a good gr defence.

A doubt may occasionally arise whether a *weapon* has or has used in reference to lacerated or contused wounds. Contused wo bony surfaces, as on the head from a cricket-ball, sometimes pre appearance of incised wounds, the skin being evenly separated. wound is recent, a careful examination will generally enable a wi form a correct opinion, but if some time has elapsed before a w examined, great caution will be required in forming a judgm man, it was alleged, had been stabbed on the head with a knif prisoner struck the blow, and he certainly had a knife in his han time, but whether the wound was or was not produced by the kni not be determined from the evidence of eye-witnesses. In the d was urged that the prisoner had inflicted the wound with his knuc not with a knife. When a surgeon was called to examine the some time after its infliction, there was so much contusion and la about its edges, that it was impossible to ascertain, with the n precision, by what means it had been caused. There was suspic no medical proof, that a weapon had been employed.

A surgeon should be cautious in listening to the statements of

ollowed upon this evidence, and a respectable woman, charged as accessory, as sentenced to a severe punishment, not for having assaulted the prose-utrix, for it does not appear that she struck a blow, but for aiding another in the supposed act of stabbing. It was alleged that she handed a knife to the assailant, when it was extremely doubtful, medically speaking, whether any knife had been used in the assault. This case conveys a serious caution in respect to the medico-legal examination of wounds. A medical man is not justified in giving a hasty opinion of a weapon having been employed from mere hearsay; he may, in this way, lead to the infliction of a very severe and unmerited punishment.

There is no doubt that some means of discrimination between the effects of falls and blows affecting the same part of the body, would greatly aid the administration of justice; but as no two cases coming under this class of injuries are precisely alike, either in the part wounded or the amount of force employed, it is scarcely possible to introduce general rules or to make statistics practically available. It is commonly supposed that a mere fall is not sufficient to produce the same degree of injury that may be caused by a blunt weapon, applied suddenly to the head by human force; but a severe fracture may arise from a simple accident of this kind, and present nearly all the characters of homicidal violence. (See case, p. 508.) The difficulties at criminal trials will be found to proceed, not so much from want of rules to assign the violence to one condition or the other, as from a want of proper observation when the wounds are first examined. If minute attention were given to an examination of these injuries soon after their occurrence, circumstances would be noticed which would help the medical witness to a conclusion. The defence that they might have been produced by a fall, is not set up until a subsequent period, and the surgeon is then obliged to trust to his memory for the main points of distinction. Such improvised opinions usually fail in impressing a jury.

The case of *Mr. Briggs*, who was murderously assaulted in a carriage on the North London Railway in 1864, furnishes an illustration of the ease with which homicidal and accidental violence may be distinguished, pro-vided attention is directed to this question at the time. There were several wounds on the head of this gentleman which could not have proceeded from one cause. It appeared probable that some had been inflicted on the deceased by an instrument while he was in the carriage, and that he had then been thrown from it while the carriage was in rapid motion, and the fall had produced other bruises. The surgeon who examined the deceased found a transverse jagged wound across the left ear, and above his there was a scalp-tumour as well as two distinct wounds of the scalp with effusion of blood beneath and corresponding fractures in the bones. There had obviously been more than one distinct application of force to produce such injuries. The fractures in the skull in two distinct places indicated the use of a heavy blunt weapon, while the scalp-tumour was probably caused by the head coming in contact with the ground at that point. A large stone, with some blood and light grey hair resembling that of deceased, was found in the road near the spot where the body was lying. In this case the assassin, *Müller*, had no doubt intended that death should appear to be the result of an act of suicide—the fall from a train in motion necessarily producing severe injuries, which might reasonably account for death. The case of *Mr. Gould*, who was murdered on the Brighton Railway in 1881, in a similar manner, presented less difficulties; since Mr. Gould was first shot by his assailant, *Lefroy*, and then, probably whilst still living, was thrown out of the carriage. An assailant may select his opportunity of inflicting violence upon another while riding on horseback, and by

causing him to fall from his horse may thus give the appearance of accidental injuries. A proper medical examination, however, could not fail to reveal the real state of facts. In 1861, the *Baron de Vidil*, a French nobleman of high social position, was charged with attempting to murder his son, Alfred de Vidil, under the following circumstances. He invited his son, on false pretences, to take a ride on horseback, with him—he led him into a solitary lane near Twickenham—fell behind, and then suddenly struck his son several severe blows on the head with a heavy riding whip having a metal head. The young man, although severely wounded, was able to keep his seat, and soon procured assistance. The Baron alleged in defence that his son's horse had shied and had thrown him against a wall. The surgeon who examined the son soon after the occurrence found on the head two contused wounds of a star-shape cutting through the skin to the bone, one at the upper part of the forehead, near where the hair grew, and the other at the back of the head. There were no scratches or other injuries to the face. The medical witness very properly said that these two wounds in different parts of the head were inconsistent with their production by any fall or by such an accident as that assigned by the accused. They had the appearance of having been caused by separate blows from some heavy blunt instrument, the force being concentrated on each point. This medical view of the cause of the injuries was borne out by the direct evidence of an eye-witness who saw the prisoner strike the blows. It was proved that, by the death of his son, the prisoner would have come into the possession of a large sum of money. The Baron was tried at the Central Criminal Court, and although the son refused to be a witness against the father, he was convicted, upon the medical and general evidence, of an assault.

When it is a question which of two weapons produced certain contused wounds found on the head, the difficulties of medical evidence are increased. In *Reg.* v. *Teague* (Cornwall Sum. Ass. 1851) the prisoner was charged with the murder of his father-in-law. The deceased was found dead with a large wound in the centre of the forehead. According to the medical evidence, it had the appearance externally of being two, but was in reality only one wound, inflicted by more blows than one. The wound was nearly of a circular figure, with a band of skin passing vertically across it. The bone had been driven in to some depth. A large hammer was found near with white hair upon it, but no blood. It was alleged for the prosecution, that the contused wound had been produced by this hammer by the act of the accused, and it was stated by the medical witness that one end of the hammer corresponded to the shape and other physical characters of the wound. The defence was, that the injury had been caused either by a fall or by a kick from a horse. It was not at all probable that any fall could have produced such a wound, without greatly disfiguring the face, which presented no marks of injury; and in reference to its production by a kick, the witness compared the horse's shoes and found that the wound bore no resemblance whatever to them. One circumstance appeared to connect the hammer with the wound, namely, the presence of some white hairs upon it; but the evidence failed to fix the crime upon the prisoner, since it only went to prove that he had had the opportunity of committing the crime, but there was no apparent motive for its commission. ('Med. Gaz.' 1851, 48, 729.)

In most instances an accurate observation of the form of a contused wound, and an early comparison of it with the supposed weapon or the substance said to have produced it, will enable a witness to come to a *correct* conclusion on the subject. The situation, depth, and shape of the *wound, may* be such that no accidental fall could reasonably account for

s production. In *Reg.* v. *Skelton* (Carlisle Spring Ass. 1858) the evidence howed that deceased, an old man, had died from violence to the head. He as found insensible and bleeding in the road, not far from the prisoner's ouse. An angular stone was lying near to his head. There were no ruises on the body, but on the left side of the crown of the head, there as a square-shaped hole about the size of a half-crown, the bone being here driven in. Three inches below this, above the tip of the ear, there was another fracture of the skull under a narrow scalp wound about an inch in length. In the prisoner's house was found a hammer, which had a square face, with the corners rounded off; and on comparing this with the indented wound and fracture, it corresponded very nearly in shape and width. The other end, when compared with the smaller wound near the ear, also corresponded. The hammer, as it frequently happens with heavy bruising instruments, had no blood upon it, nor anything to indicate that it had been used for inflicting the injuries. The stone found near the deceased had upon it blood and mud at one corner, and a white human hair adhered to it. It was admitted by the medical witnesses that had the deceased fallen heavily upon this stone, it would have accounted for the lesser wound; and with respect to the indented wound, it was suggested that had he been knocked down by a horse and trampled on, the 'caulker,' or square piece of iron at the heel of a horse-shoe, might have produced it. They at the same time stated that the other part of the shoe would have left some mark, of which there was no trace. The hat worn by the deceased at the time presented no indentation or mark. It is probable from this description that the injury was produced by a weapon, but the evidence failed to connect the prisoner with the act.

In assaults on women, it is not unusual to find that the complainant herself endeavours to exculpate the assailant by ascribing the marks of violence, not to blows, but to some accidental fall. In 1864, a woman deposed before a magistrate that certain severe injuries which she had sustained had been caused by her falling on a fender. The medical man who examined her, found on the top of the head three distinct wounds which were bleeding. Two appeared as if they had been caused by a blunt instrument: the third, on the back of the head, was a cleanly cut wound. He considered that they had been produced by a chopper, and that none of them had been caused by a fall or a series of falls. The prisoner on this evidence was committed for trial.

4. *Stabs and Cuts.*—It has been remarked that the law in some cases attaches great importance to the clear proof of the use of a *weapon;* and a medical man has therefore a certain responsibility thrown upon him when, in the absence of a weapon and the denial of its use, he is called upon to say whether one has or has not been used. In reference to cuts and stabs there can in general be no difficulty, for these injuries carry with them distinct evidence of their mode of production. Formerly stabbing and cutting were treated as distinct from wounding, and very nice legal distinctions were drawn between these terms, which had the effect of procuring acquittals on mere legal technicalities. Under the Consolidated Act, the words 'stab' and 'cut' are omitted, and the word 'wound' only has been retained. Medical men would always agree upon a stab or cut being a wound, but they might reasonably differ upon the question whether in a given case a wound was really a stab or cut. It might be punctured, lacerated, or contused, and not fairly come under the professional description either of a cut or a stab. In the meantime, the only party who derived benefit from this confusion, was the assailant who had inflicted the undefined injury on another. A medical witness has now only to prove that the personal injury falls strictly within the

meaning of the term *wound:* he is not called upon to prove the precise variety of wounding to which the injury should be assigned. At the same time, he should always be prepared for a full description of the characters of an injury in case questions on the subject should be put to him.

What are Weapons?—Those legal doubts which formerly arose in reference to the true signification of the term *weapon* have been removed by statute. Thus the teeth, the hands or feet uncovered, were formerly held by the judges *not* to be weapons; and injuries produced by them, however severe, were not treated as wounds within the meaning of the statute. Parties were tried on charges of biting off fingers and noses, and although the medical evidence proved that wounds of a severe kind had been thus inflicted and that great disfigurement and mischief had been done to individuals, yet the nature of the injury produced was not so much regarded as the actual method by which it was accomplished. The persons charged were acquitted under an indictment for 'wounding,' since wounds in a legal sense could be produced only by weapons, while the teeth, hands, and feet were not weapons in law. On a trial which took place at the Nottingham Assizes in 1832, a strenuous effort was made by prisoner's counsel to claim for artificial arms and legs the same privilege of exemption that was accorded to natural arms and legs. In the case alluded to, it was argued in defence that a wooden arm with an iron hook at the end of it, with which an assault was committed, had become, by long use, part of the body of the prisoner, and that, like a natural arm, it ought not to be considered a weapon in law. The objection was overruled. Except in so far as the deliberate use of a weapon may indicate an intent to inflict a greater amount of personal injury, such questions as these cannot again arise. A man named *Benson* was tried for a felonious assault (C. C. C. Nov. 1871). The evidence showed that the prisoner, having no left hand, struck the prosecutor on the face with an iron hook which served as a substitute, and produced serious injuries. He conducted his own defence, but did not base it on the theory that the iron hook was a substitute for his natural means of defence. He was found guilty.

Examination of the dress.—This is a most important part of the duty of a medical man. In a case of severe wounding, of whatever kind, he should always require to see the dress of the wounded person. It may throw a material light upon the *mode* in which a wound has been produced: it may remove an erroneous suspicion of murder, and may sometimes serve to indicate that a wound has been self-inflicted for the concealment of other crimes, or falsely to impute its infliction to other persons. Marks of blood, dirt, grass, or other substances on the clothing, may also throw a light upon the mode of infliction. So again the use of a weapon, in reference to cuts and stabs, may be inferred from the dress presenting corresponding cuts or perforations. Contused wounds by bludgeons may, however, be readily produced through the dress, without tearing or injuring it. Considerable laceration of the skin and muscles, and even severe fractures, may be caused without necessarily penetrating the dress, supposing it to be at all of an elastic or yielding nature. In self-inflicted or imputed wounds, if of the nature of cuts or stabs, there is often a want of correspondence between the perforations of the dress and the wounds on the person: this is one of the characters by which the correctness of a statement may be tested. (See 'IMPUTED WOUNDS.') A severe wound may be indirectly produced by a bruising weapon, and medical witnesses have been often questioned on this point. Thus, the prosecutor may at the time have worn about his person some article of dress which received the blow, and this may have caused the wound. On a trial for

liciously wounding (Reading Spring Ass. 1837) it appeared in evidence at the prisoner, while poaching, assaulted a gamekeeper by inflicting on s head severe blows with a gun. At the time of the assault, the prose-tor wore a strong felt hat, which, it was contended in defence, had caused e wounds that formed the subject of the charge. The medical witness mitted that the wounds might have been produced either by the gun, by the hat through a blow from the gun. The prisoner was convicted; is was held to be a wounding, although the gun did not touch the skin. another case, a blow was struck with a bludgeon at the head of the osecutor, who wore spectacles. Wounds were produced, which, it was gued in the defence, had resulted from the glass of the spectacles and t from the bludgeon. The prisoner was acquitted. Every case of this nd must be determined by the circumstances which accompany it. One ct appears to me to be well established from the foregoing cases—namely, at a medical practitioner should always make a careful examination not ly of wounds which are likely to become the subject of criminal charges, t of the dress or clothing worn by the wounded person at the time of e assault. In performing his duties as a surgeon, he is bound, so far as consistently can, to notice as a medical jurist the characters of all rsonal injuries, so as to be able to give an opinion on the mode in which ey were inflicted.

When the question is simply, whether the contused wound resulted om accident or homicide, a careful examination of the dress may tend to move any medical or legal doubts. A man was found dead in a stable, t far from a vicious mare, and the traces (harness) of this animal were pon his arms and shoulders when the body was discovered. The brother the deceased was tried (Warwick Spring Ass. 1808) on the charge of aving killed him with a spade, which was found lying in the stable. This ade was stained with blood, but the evidence from this fact was wholly set side by the circumstance that the spade had been subsequently used in eaning out the stable. In the defence it was alleged that the deceased ad been kicked by the mare while attempting to put on the traces, and had ius been accidentally killed. There were two straight *incised* wounds, pparently caused by a blunt instrument, on the left side of the head, one bout five and the other about two inches long. On the right side of the ead there were three irregular wounds of a mixed lacerated and incised haracter, two of them about four inches in length. There was also a wound n the back part of the head, about two inches and a half long. There was o swelling round any of the wounds, and the skin adhered firmly to the bone. he right side of the skull was generally fractured—the fracture extending long the back of the head to the left side—a small portion of the temporal one having come away. The deceased was found with his hat on, which as bruised in the part corresponding to the seat of injury, but not cut; but ere were no wounds on any other part of the body. Two medical wit-sses expressed a strong opinion that the injuries could not have been oduced by kicks from a horse, grounding that opinion principally on the stinctness of the wounds, the absence of marks of contusion, the firm hesion of the skin, and the straight lateral direction and similarity of e wounds. They also thought that they could not have been inflicted thout cutting the hat, if this had been on the deceased's head at the time; d if the hat had been off, that he could not have had the power to put it after receiving the wounds. The case was not made out against the isoner, and he was acquitted. (Wills' 'Circ. Evidence,' p. 302.) Taking e facts as they are here reported, there seems to have been no good medical ason for assuming that the wounds on the head were homicidally inflicted. he fact that they had a somewhat incised character is not a positive proof

that the spade was used in producing them, since an instance has occurred where the skin of the scalp presented a similarly incised appearance from the kick of a horse; and this is not an unusual consequence of a severe and sudden blow on those parts of the body where the elastic skin is stretched over round surfaces of bone. In this case, however, another question arose, namely, whether wounds of this description could be inflicted on the head without necessarily cutting through the hat. Admitting it to be improbable that the deceased could have placed the hat on his head after being thus wounded, we must infer that it was on his head at the time, and assuming that the injury was produced by the bruising violence of a horse's hoof, it is easy to understand that the scalp might be wounded and the skin broken without causing more than an indentation in the hat. Had the spade been used, it is less probable that the hat would have escaped the effects of violence. Hence the witnesses who assumed that the deceased had been killed by the spade, were obliged to suppose that the hat must have been off, and put on afterwards, therefore that there must have been murderous interference. This, however, would not explain the fact that the hat was indented over the situation of the principal injury. On the whole, this seems to have been really a case of accidental violence, this theory being strongly supported by the condition in which the hat was found on the head of deceased. It is of some importance as a medico-legal fact, that the skin may be readily wounded through the dress, without the latter being necessarily cut or torn. Wood, B., who tried the above case, stated at the time that he remembered a trial at the Old Bailey, where it had been proved that a cut and a fracture had been received without having cut the hat of the wounded person, and evidence was then adduced of the infliction of a similar wound without cutting the hat.

An instructive case which occurred in Aug. 1853, shows the importance of comparing the article of dress with the injuries which may have proved fatal. A woman, æt. 60, was found dead in her bed. She had vomited slightly, and there was a small quantity of blood on the floor which had flowed from her nose. She had been seen in her usual health on the previous night. On inspection, there were found two indentations about the middle of the right parietal bone, and there was a large clot of blood in this situation beneath the skin. On removing this clot, the bone was found fractured to the extent of four inches. Nearly three ounces of dark clotted blood were found on the outer membrane of the brain (dura mater), between it and the skull. All the other viscera were healthy. This was the only injury, and quite sufficient to account for death; but a question arose respecting the mode in which this fracture was caused. It was in evidence that on the evening before her death, deceased had been suddenly knocked down, while she was walking in a public road, by a man accidentally running against her. One witness stated that she fell heavily on the back of her head, on which at the time she wore a bonnet. She appeared stunned, was raised up by the man, some brandy was given to her, and she recovered sufficiently to walk home and eat her supper as usual, after which no one saw her until she was found dead in bed on the following morning. Some suspicion arose that the violence done to the head was too great to be accounted for by a mere fall, and it was a question whether, with such an amount of injury, the deceased could have walked to her home, at the distance of a mile and a half, and have eaten her supper before going to bed. At first it was thought that this was a case of murder, and a man who lodged in the house with deceased was suspected. His room was searched, and a hammer with two claws was found. On comparing these claws with the two indentations and fracture, the medical witness thought

at this weapon would at once account for their production. Deceased and is man had been in the habit of quarrelling, and they were the only persons i the house on this occasion. The lodger said that he let the woman in bout nine o'clock (the fall in the road occurred about 7.30); her appearance resented nothing unusual, and he saw no more of her until called at seven ie next morning, when she was found dead and cold. It was only at the ljourned inquest that the bonnet worn by the deceased at the time of the ll was called for by the coroner. Two indentations were then found pon the back part of it, corresponding to those on the skull of deceased. he indentations on the bonnet contained dust and dirt, thereby confirming ie statements of the witnesses, and rendering it probable that the fall in ie road had caused the fatal injury to the head.

The examination of the dress, in this case, cleared up what might have een otherwise doubtful. It is probable that the large internal effusion of lood which caused death did not take place until deceased had reached ome, and perhaps as a result of the exertion made. She must have died ery soon after she went to bed, as her body was found cold at seven 'clock the next morning. In addition to the caution which this case onveys respecting medical opinions on the origin of wounds, it shows that ersons may walk and die at a considerable distance from the spot where erious injury to the head has been sustained.

The examination of the clothing in the *Waterloo Bridge* tragedy (p. 131) hrew some light upon the question of murder. An overcoat presented, a the collar behind and towards the left side, a cut or stab as from a double-dged knife. The undercoat as well as the waistcoat presented the mark f a similar stab corresponding in size, form, and direction to the cut in he collar of the overcoat. The shirt beneath was much stained with lood. The stab took a direction from above downwards, and must have enetrated into the chest. Its situation and direction precluded the idea f its having been self-inflicted. As there was no blood on the overcoat here cut, the weapon had not before been used for inflicting a wound, nd the deceased had obviously been stabbed from behind with all his lothes upon him. The theory that this was not a murder would involve he assumption that the overcoat, undercoat, and waistcoat had been placed pon some lay-figure for the purpose of imitating a fatal stab behind, and hat the undershirt had been covered with blood to add to the appearance. No reasonable motive could be assigned for such a proceeding.

CHAPTER 37.

WOUNDS INDICATIVE OF HOMICIDE, SUICIDE, OR ACCIDENT—EVIDENCE FROM THE SITUATION OF A WOUND—SUICIDAL WOUNDS IN UNUSUAL SITUATIONS—EVIDENCE FROM NATURE AND EXTENT—SHAPE—EVIDENCE FROM THE DIRECTION OF A WOUND—SUICIDAL AND ACCIDENTAL WOUNDS—WOUNDS INFLICTED BY THE RIGHT OR LEFT HAND—ACCIDENTAL AND HOMICIDAL STABS—EVIDENCE FROM THE PRESENCE OF SEVERAL WOUNDS—THE USE OF SEVERAL WEAPONS—TWO OR MORE MORTAL WOUNDS—WOUNDS PRODUCED SIMULTANEOUSLY OR AT DIFFERENT TIMES.

Wounds indicative of Homicide, Suicide, or Accident.—Supposing that the wound which is found on a dead body is proved to have been caused before death, it may be necessary to inquire whether it was the result of *suicide, homicide,* or *accident.* It might at first sight be considered that

the determination of a question of this nature was wholly out of the province of a medical jurist. In some instances it may be so, and the settlement of it is then left to the legal authorities; but in a large number of cases, it is so closely dependent for its elucidation on medical facts and opinions, that juries could never arrive at a satisfactory decision without medical evidence. Let us suppose, then, that a medical jurist is consulted in a doubtful case,—What are the points to which he should direct his attention? They are, with regard to the wound, 1, its *situation*: 2, its *nature* and *extent*; and 3, its *direction*.

1. *Evidence from the situation of a wound.*—It is a general principle in which most medical jurists agree, that wounds inflicted by a suicide, are usually confined to the fore or lateral parts of the body. The throat and chest are commonly selected when cutting instruments are employed; while the chest, especially in the region of the heart, the mouth, the orbit and the temples, are the spots generally chosen for the perpetration of suicide by fire-arms. But it is obvious that any of these parts may be also selected by a murderer, with the especial design of simulating a suicidal attempt; therefore the mere situation of a wound does not suffice to establish the fact of suicide. Smith considered, in reference to pistol-wounds, that if the weapon has been introduced into the deceased's mouth and there discharged, we may take it for granted that 'it has not been done by another' ('For. Med.' p. 302); but this inference has been too hastily drawn. because it is quite within the range of probability that a calculating assassin may purposely resort to this method of destroying a person in order to conceal the crime. In suicidal wounds from fire-arms, a discolouration by powder of the fingers of the hand which discharged the weapon is sometimes observed; this has also been looked upon as a source of evidence of suicide under doubtful circumstances, but a similar objection, although not with equal force, might be made to its admission. Some have regarded it as fully established in legal medicine, that when wounds exist at the back part of the body, it is a positive proof that they have not been self-inflicted. This situation is certainly unusual in cases of suicide; but, as Orfila observes, it is not the situation, so much as the direction of a wound, which furnishes evidence against the presumption of suicide. A wound, traversing the body from behind forwards in a direct line, is not likely to have resulted from a suicidal attempt: at least, it must be obvious that it would require more preparation and contrivance on the part of a self-murderer, so to arrange matters that such a wound should be produced, than we can believe him to possess at the moment of attempting his life. Besides, his object is to destroy himself as quickly and as surely as circumstances will permit: he is, therefore, not likely to adopt uncertain means for carrying this design into execution. Nevertheless, we must not always expect to find suicidal wounds in what an anatomist would pronounce to be the most appropriate situation to produce instant destruction. A want of knowledge, or a want of resolution, on the part of a suicide, or the accidental slipping of the hand, will often cause a wound in a part where we might least expect to find it.

Wounds which result from accident or suicide are generally in *exposed* parts of the body. An incised wound in a concealed or not easily accessible part is presumptive of homicide: because this kind of injury could have resulted only from the deliberate use of a weapon. Suicidal wounds are, however, sometimes found in the most unusual situations. In 1842, a surgeon destroyed himself by cutting through the brachial artery and the principal veins of his left arm with a penknife: and in another instance which occurred in 1839, a young man committed suicide by dividing the arteries of the fore-arm on both sides. It is rarely that we find suicidal

abs in the abdomen or throat, but an instance occurred a few years since, which a woman destroyed herself by a stab in the lower part of the domen; and several similar cases are recorded. In an attempt at suicide, hich fell under the author's observation, a stab was inflicted by a carving ife on the fore part of the neck traversing the parts from the windpipe the spinal column. In regard to situation, it has been remarked, that ere is no wound which a suicide is capable of inflicting upon himself, hich may not be produced by a murderer; but there are many wounds flicted by a murderer which, from their situation and other circumstances, suicide would be incapable of producing on his own person. We cannot ways obtain certainty in a question of this kind,—the facts will often low us to speak only with different degrees of probability. A remarkable stance of the singular situation selected for suicidal wounds is reported the 'Med. Gaz.' vol. 45, p. 439.

The situation of a wound sometimes serves to show whether it is of n *accidental* nature or not—a point often insisted on in the defence. ccidental wounds generally exist on those parts of the body which are xposed. Some wounds, however, forbid the supposition of accident even hen exposed; as deeply incised wounds of the throat, and gunshot wounds f the mouth and temples. For the report of a case in which an accidental ound on the head, by an axe, closely simulated a homicidal wound, see asper's 'Wochenschrift,' May 24, 1845.

2. *Evidence from the nature and extent of a wound.*—Generally speaking, the wound met with on the body of a suicide, when fire-arms have not een used, is either incised or punctured, *i.e.* a cut or a stab. Contused ounds are rarely seen in cases of suicide, because in producing them here is not that certainty of speedily destroying life to which a self-murderer commonly looks. There are of course exceptions to this remark; s where, for instance, a man precipitates himself from a considerable eight, and is wounded by the fall. Circumstantial evidence will, however, arely fail to clear up a case of this description. Greater difficulty may xist when life is destroyed by a contused wound, voluntarily inflicted. A ase is related in which a man first attempted to destroy himself by running with his head against a wall; and not having succeeded in the attempt, he struck himself repeatedly on the forehead with a cleaver. By this he roduced such violent injury to the brain, that death soon followed. The an was seen to commit the act by several witnesses: had not this been he case, the nature of the wound was such as to excite suspicion that it ad been inflicted by another, and that the man had been murdered.

A close attention to the *shape* of wounds in the throat made by cutting nstruments will sometimes lead to the development of cases rendered oubtful from the circumstances under which the dead body of a wounded erson is found. The body of a farmer was found lying on a high road. His throat was severely cut, and he had evidently died from the bleeding which had taken place. A bloody knife was discovered at some distance rom the body, and this, together with the circumstance of the pockets of he deceased having been rifled, led to a suspicion of murder. The suspicion as confirmed when the wound in the throat was examined by a surgeon. t was cut, not, as is usual in suicides, by carrying the cutting instrument rom before backwards, but as the throats of sheep are cut when slaughtered y a butcher. The knife had been passed in deeply under and below the ar, and had been brought out by a semi-circular sweep in front, all the reat vessels of the neck, with the gullet and windpipe, having been divided rom behind forwards. The nature of this wound rendered it at once mprobable that it could have been self-inflicted, and it further served to etect the murderer, *who was soon afterwards discovered.* The prisoner,

who had been a butcher, was subsequently tried and executed for the crime.

When persons labouring under insanity commit suicide, they often inflict upon themselves wounds of an extraordinary kind—such as would, at first view, lead to a suspicion that they had been produced by the hand of a murderer: and, therefore, the rules which are here laid down to distinguish homicidal from suicidal wounds, must be guardedly applied to the cases of those persons who are known to have been insane. In 1850, a case occurred at Guy's Hospital, in which a person in a fit of delirium tore away the whole of the abdominal muscles from the lower and fore part of the abdomen. Had the body of this person been found dead with such an unusual and serious personal injury, it is not improbable that it might have been pronounced homicidal, and not suicidal. A woman suffering from delirium tremens tore open her abdomen with her hands. The wound produced was eight inches long, and about eight feet of the small intestines protruded from it as well as a portion of the large intestines, which had been completely torn across. She lived twenty-seven hours after inflicting this injury. ('Lancet,' 1870, I. 863.) Such severe injuries as these, if found on a dead body, would perhaps not be described as self-inflicted, but as indicative of murderous violence. A pregnant woman under a delusion so ripped open her abdomen that a large wound was made, and the omentum and gravid uterus protruded. ('Lancet,' 1870, II. 258.) A gentleman was found lying in a state of insensibility in the kitchen of his house, with a cleaver by his side. On examining the head, upwards of thirty wounds were found over the back part of the skull. The wounds, many of which were superficial, had a horizontal direction from behind forwards. One, however, had removed a portion of the skull from the middle of the lambdoidal suture, so that some of the brain had escaped. This person died four days afterwards, but recovered so far as to admit that he had produced the wounds on himself, of which, from other circumstances, there could have been no doubt. He was a lunatic. This was a most unusual way of committing suicide. Had the deceased been found thus wounded, dead on a highway, the probability is, that a strong suspicion of murder would have arisen. A case of this kind should be borne in mind when we are called upon to speak to the possibility of certain wounds found on a dead body, having been self-inflicted. ('Med. Gaz.' vol. 24, p. 276.) Ryan met with a case in which a man contrived to cut his throat exactly between the hyoid bone and the larynx, having previously made two distinct cuts of the thyroid cartilage. The wound was of an unusual kind, reaching backwards through the pharynx to the spinal column. Ryan states that there were two cuts on the fourth cervical vertebra and another on the intervertebral cartilage. The carotids and jugulars had escaped, but some of the larger branches of these vessels were divided. The man survived about seven hours. ('Med. Times,' Jan. 17, 1852, p. 73; also 'Lancet,' June 1, 1844. For another case of extensive wounds in the throat by a lunatic, see 'Med. Times and Gaz.' Aug. 27, 1853, p. 219.)

Wounds of the throat, when inflicted by suicides, are commonly at the upper part, involving the hyoid bone and the thyroid or cricoid cartilages; the large vessels often escape, but the larynx is opened. The wound does not always cause death by hæmorrhage. A woman, æt. 68, attempted suicide by inflicting a wound on her throat. It was between four and five inches long, and extended nearly from ear to ear. It laid open the larynx between the hyoid bone and thyroid cartilage, and had taken off a portion of the epiglottis. There was no arterial hæmorrhage, only a few veins having been divided. The patient did well at first, but inflammation of the lungs

set in, and this carried her off on the sixth day. This was a secondary cause of death. ('Ed. Month. Jour.' Feb. 1863, p. 759.)

The *extent* of a wound, by which we are to understand the number and importance of the parts injured, must in these cases be always taken into consideration. It has been somewhat hastily laid down as a rule, that an extensive wound of the throat, involving all the vessels and soft parts of the neck to the spine, could not be inflicted by a suicide. Although in general suicidal wounds of this part of the body do not reach far back, or involve the vessels of more than one side, yet we find occasionally that all the soft parts are thus completely divided. These are cases in which, perhaps, with a firm hand, there is a most determined purpose of self-destruction. In a case of suicide, observed by Marc, the weapon had divided all the muscles of the neck, the windpipe, and gullet—had opened the jugular veins and both carotid arteries—and had even grazed the anterior ligaments of the spine. A wound so extensive as this is rarely seen in a case of suicide, but there is no ground for the assertion that extensive wounds in the throat are incompatible with self-destruction.

Incised wounds in the throat are generally set down as presumptive of suicide, but murderers sometimes wound this part for the more effectual concealment of crime. Circumstances connected with the form and direction of a wound, may in such cases lead to detection, for, unless the person attacked be asleep or intoxicated, resistance may be offered—evidence of which may be obtained by the presence of great irregularity in the wound, or the marks of other wounds on the hands and on the person of the deceased. In some instances, however, it is extremely difficult to say whether the wound is homicidal or suicidal—the medical facts being equally explicable on either hypothesis. (See case by Marc, 'Ann. d'Hyg.' 1830, 2, 408; another by Devergie, ib. 414; and a third by Ollivier, 'Ann. d'Hyg.' 1836, 1, 394.) *Regularity* in a wound of the throat has been considered to be presumptive of suicide. This was the publicly-expressed opinion of Sir Everard Home in the well-known case of *Sellis*. The deceased was found lying on a bed, with his throat extensively cut, and the edges of the incision were regular and even. This condition of the wound, it was inferred, repudiated the idea of homicide, but as a general principle this appears to be a fallacious criterion. A murderer, by surprising his victim from behind—by having others at hand to assist him, or by directing his attack against one who is asleep, intoxicated, or from age or infirmity incapable of offering resistance, may easily produce a regular and clean incision on the throat. This was observed in the case of *Lord William Russell*, who was murdered by Courvoisier in 1840 (p. 65). The wound in the throat possessed all that regularity which has been regarded as characteristic of suicide. Some have taken a contrary view to that of Home, and have contended that the chief character of a suicidal wound in the throat, is great irregularity from want of steadiness in the hand during the perpetration of suicide. It is by no means unusual in suicides to find the cut regular at its commencement, and irregular or uneven at its termination, from the loss of blood which attends the first incision; but it is obvious that a homicidal wound might possess these characters. In short, we are entitled to say, regularity or irregularity in an incision in the throat furnishes no presumptive evidence either of homicide or suicide.

The nature and extent of a wound, or of other injuries on the person, will sometimes allow us to distinguish *accident from homicide*. These personal injuries may be such, that they could not possibly have had a suicidal or accidental origin. In a case that occurred at Manchester, in 1836, it was *shown that seven* ribs were fractured on one side of the

chest of the deceased, and five on the other. The person charged with murder alleged in defence that he had merely struck the deceased a slight blow, and that the ribs were broken subsequently by an accidental fall. The medical witness, however, satisfied the Court that the fall, as described by the prisoner, was inadequate to the production of such extensive violence; and that even had the deceased fallen on *one* side, this would not account for the fracture of the ribs on the *other*. When, therefore, we find in a dead body severe injuries referred to a fall, we should search the whole of the body carefully for proofs of violence. The insides of the arms or thighs may present marks of injury, which could not possibly be explained on the supposition of an accidental fall. Severe contusions on both sides of the body, or anteriorly and posteriorly, commonly indicate homicidal violence. The body of a woman alleged to have been murdered by her husband, presented numerous marks of contusions; one arm was completely ecchymosed from the shoulder to the hand. The person charged with the murder ascribed these appearances to the fact of his wife having accidentally fallen out of bed; but on examining the bed, it was found to be only a foot from the floor. A fall from this height would not account for the presence of such extensive marks of violence; but irrespective of this, a severe contusion was found on the outer side of the opposite thigh, which, from the appearance, must have been produced about the same time as that on the arm. The existence of this second contusion rendered the defence still less probable: for the woman could not, if she had fallen at all, have fallen on both sides of her body at once; and it was not alleged that she had had more than one fall. In the case of *Reg.* v. *Wallis* (Cent. Crim. Court, 1839), a similar defence was set aside, by the fact that distinct and severe bruises were found on the back of the head and on the temples of the deceased.

3. *Evidence from the direction of a wound.*—The direction of a wound has been considered to afford presumptive evidence sufficiently strong to guide a medical jurist in this inquiry. It has been remarked that in most suicidal wounds which affect the throat, the direction of the cut is commonly from left to right, either transversely or more often passing obliquely from above downwards: in suicidal stabs and punctured wounds, the direction is commonly from right to left and from above downwards. In left-handed persons, the direction would, of course, be in the opposite transverse directions. Suicidal wounds are, however, subject to such variation in extent and direction, that it is scarcely possible to generalise with respect to them. Nevertheless, an attention to these points may sometimes be of real assistance to the inquirer, especially when the body has not been moved from its position. It is obvious, that if a murderer makes an incised wound in the front of the throat from behind, the direction may be the same as that commonly observed in cases of suicide. (See on this point the case of *Reg.* v. *Dalmas*, Cent. Crim. Court May, 1844.) Again, if the person attacked is powerless, the wound may be deliberately made, so as to simulate a suicidal act; indeed a murderer might attack the throat with the design of simulating an act of suicide. A homicidal stab may also take the same direction as one which is suicidal, but this would be confined to those cases in which the assailant was placed behind or aside. If in front of the person whom he attacks, the direction would probably be from left to right; but in suicide, when the right hand is commonly used, it is the reverse. Oblique wounds, passing from above downwards, are common to homicide and suicide, but those which take an oblique course from below upwards are generally indicative of homicide, for it is extremely rare, that a person bent on suicide, unless a lunatic, thus uses a weapon. Homicidal incisions, especially in the throat, are often

olonged below and behind the skin forming the angles of a wound, eply into the soft parts (case, p. 511). Those which are suicidal rarely ssess this character; they terminate gradually in a sharp angle, and the in itself is the furthest point wounded, the weapon is not carried either hind, below, or beneath it. Exceptions to these characters may exist; it in a dark and intricate subject of this nature, we have only these nited rules to guide us. The instrument with which a wound is supposed have been inflicted should be adapted to the edges of the incision: its arpness compared with the cleanness and evenness of the cut, and its ngth with the depth of the incision or stab. It is no uncommon occurnce for a murderer to substitute some instrument belonging to the ceased or another person for that which he has actually employed; and is by its size, shape, bluntness, or other peculiarities, may not account r the appearances presented by the wound.

Suicidal and Accidental wounds.—It is not often that any difficulty is perienced in distinguishing a *sucidal* from an *accidental* wound. When wound has really been suicidally inflicted, there are generally to be found bout it clear indications of design; and the whole of the circumstances are ldom reconcilable with the supposition of accident. But if the position f the deceased with respect to surrounding objects has been disturbed, if he weapon has been removed, and the body transported to a distance, then ; will not always be easy to distinguish a wound accidentally received rom one inflicted by a suicide or a murderer. The evidence of those who nd the body can alone clear up the case; and the medical witness may be equired to state how far this evidence is consistent with the situation, xtent, and direction of the wound by which the deceased has fallen. It is nnecessary to dwell further on this subject, since the observations already nade will suggest to a practitioner the course which he should pursue. Circumstantial evidence is commonly sufficient to show whether a wound as been accidentally received or not; but as an accidental wound may ometimes resemble one of homicidal or suicidal origin, so it follows that t is not always possible for a medical jurist to decide the question peremporily from a mere inspection of the wound.


It would not be difficult to produce instances in which murderers, in heir defence, have alleged that the wounds observed in the bodies of their ictims were of accidental origin, and the allegations have been clearly efuted by medical evidence. A witness must be prepared, therefore, in ll cases in which death has taken place in secrecy, and the nature of the round is such as to render its origin doubtful, to be closely examined by ounsel for a prisoner charged with homicide, on the question whether the round might not have been accidental. The law requires that it should be ndered evident to a jury, before such a charge can be sustained, that the tal wound could not have had an accidental or suicidal origin.

The death of a person from wounds has hitherto been considered as a ubject connected with a criminal charge; but an investigation of the ircumstances under which death ensues, is occasionally rendered necessary hen the decease has effected an insurance upon his life. A policy of lifesurance is in some cases rendered void by the act of self-destruction; and erefore a person bent on suicide might, for the sake of his family, take recautions to conceal the manner in which he intended to destroy himself. is body might be found wounded in a way which would render it unrtain whether he had been wounded accidentally, whether he had been urdered, or whether he had fallen by his own hand. In a disputed case is incumbent on the office to prove the act of suicide, while the relatives the deceased would attempt to show the contrary. Such litigation must, course, call forth a deep and searching investigation into all the circum-

stances connected with the death of the insured, and the whole case would, in some instances, rest almost exclusively on medical evidence. ('Med. Gaz.' vol. 36, p. 826.) Numerous cases have occurred in England, which will illustrate the importance of attending to the precise characters of wounds, and the circumstances under which the body of a wounded person is found. The following may serve as illustrations:—

Wounds of the throat.—The extent and direction of fatal wounds affecting this part of the body, if accurately observed, will frequently enable a medical jurist to express a strong opinion on the question whether the wound was self-inflicted or inflicted by the hand of another. The blood-vessels and nerves likely to be involved in such wounds will depend on their situation and depth. The annexed illustration (fig. 94) shows the relative position of the carotid artery, jugular vein, and their principal

Fig. 94.



View of the Blood-vessels and Nerves of the side of the neck, from a drawing by J. T. Nray.—5. Internal jugular vein. 8. Lingual artery. 9. Pneumogastric nerve. 11. Phrenic nerve. 12. Superior thyroid artery. 12. Sterno-mastoid muscle, turned back. 14. Common carotid artery. 15. Inner end of collar-bone, turned back. 16 and 18. Muscles covering the larynx and trachea (windpipe).

branches, as well as the nerves of the right side of the neck. Those parts only are made subjects of reference in the figures which may require description in medical evidence. The purely anatomical references are omitted.

In 1837, the body of a woman was found with the throat cut. The deceased, when seen, was lying on her back, and the razor with which the wound was inflicted was found under the left shoulder. On inquiry it was ascertained that when first seen, she was lying on her face, and the body *had* been turned round on the back. Blood had evidently run down the *fore part* of her person, rendering it probable that she had been wounded

le in the erect position. The incision in the throat was deep, and nded obliquely from the right side of the chin to within about an inch he left collar-bone. It had divided the windpipe, the gullet, all the cles of that side and the fore part of the neck, the carotid artery, the ılar vein, and the muscles on the fore part of the spine, penetrating ı into the bodies of the vertebræ of the neck. The incision was double— superficial, close under the chin, and the other a deeper one, appeared to ontinued from this. The deepest part of the right end of the incision nearly three inches in a direct line behind the right angle of the nd, so that it extended at that part behind and beneath the sound . The cut was four and a half inches long and two and a half deep. main question was, whether this could have been a suicidal wound, cted by a razor, the only weapon found near the body. Considering characters, Dodd inferred that it must have been inflicted by another on, and not by the deceased upon herself. The deceased was right- ded, which would have added to the difficulty of supposing the wound ave been suicidal. The inference drawn was precisely that which the lical circumstances appear to justify.

In 1860, a young woman was found dead in a farm-house, from a ınd in her throat. This wound was seven inches long and two inches lepth: it was situated on the left side of the neck, its direction was rly transverse, but passing slightly upwards from behind forwards. incision commenced a little in front of the spine on the left side osite to the second or third spinal process, and terminated about an ı and a half from the centre of the chin, the fore part of the incision ıg over the body of the lower jaw and quite superficial, dividing only skin, cellular tissue, and fat. The important parts involved on the left were, the external and internal carotids, which were cut into but not ss; the internal jugular vein, the pneumogastric nerve, and (at the erior part of the wound) the spinal cord, were completely severed. weapon nearly entered the joint between the second and third cervical ebra, about two-thirds of the intervertebral substance between these es having been divided. A portion of the second vertebra had been cut ugh, and was left adherent to the lower lip of the wound. The left ebral artery was also completely divided. The lower lip of the wound jagged and serrated, and the neck was slightly wounded lower down he same side, showing that several strokes had been made in this part ı the weapon. In the *left* hand of deceased a common dinner knife was ıd, loosely *held;* it was in a reversed position, with the back instead of blade towards the throat. The left hand presented three incised wounds the middle finger, one of considerable depth, and another reaching he bone over the outer side of the ring finger. The right hand had one slight wound upon it. The deceased was *right-handed.* Measured ny scientific rules, such a wound as this was inconsistent with an act ıicide. Assuming that it had commenced behind, the spinal marrow divided in such a situation that there would be instantaneous destruc- of all muscular power, so that the weapon could not be carried forward he division of the jugular vein and the two principal branches of the tid artery in front. Assuming that the wound had commenced in t, the division of these large vessels would have rendered it impossible, ason of the copious loss of blood, to have carried the weapon through intervertebral substance to the division of the spinal marrow and ebral artery behind. There could be no doubt that the wound com- ced behind on the left side, and that the weapon was used with great to cause a division of the bony process of the second vertebra. Its tion, extent, and direction were all inconsistent with suicide. A

suicide could have inflicted a wound in this situation and direction only with the right hand, but the weapon was lying loosely in the *left* hand of the deceased. There were deep recent cuts on the back of the left hand which admitted of explanation only on the supposition that the deceased had raised it to protect her throat. No suicide scores the backs of the hands before inflicting fatal wounds on the throat. A fellow-servant of the deceased, although not at first suspected, was tried (Carlisle Sum. Ass. 1860 *Reg.* v. *Cass*), and convicted of this act of murder upon his own confession. His clothes were examined, and it is worthy of observation that, with the exception of a few small spots on the shirt, they were free from any marks of blood. The knife found in the hand of the deceased was bent towards the end as if it had been used against some hard obstacle. It had been wiped; but it still contained in its depressions and irregularities, as well as between the layers of the handles, coagula of recent blood mixed with rust. One remarkable circumstance, brought out by the microscope, appeared to connect the prisoner with this weapon. In a small coagulum found on the knife, dried and fixed to the blade, were some woollen fibres of a peculiar purple-brown dye. These corresponded exactly to the fibres of the woollen jacket which the prisoner wore.

Another case, possessing some equally remarkable features, was referred to the author in 1862 (*Reg.* v. *Edmunds*, Swansea Lent Ass. 1863). A young woman named *Jane Lewis* was found dead with her throat cut, lying in a pathway not far from the house in which she resided as servant, and a razor taken from the house was lying near the body. She had left home perfectly well, about seven hours previously, to keep an appointment with the man who was charged with the murder. This man was a fellow-servant to whom she was about to be married. There were three distinct and deeply incised wounds in the neck made from left to right—the upper one four inches in length, commencing below the left ear and running parallel to the jawbone; the middle cut about seven inches in length, commencing at the same point and running across the middle of the neck to a spot behind and below the right ear; and the lower cut six inches in length, commencing above the middle of the left collar-bone going in a perpendicular direction, and terminating in the front of the neck by joining the middle incision. The middle cut divided the windpipe, the gullet, and all the great vessels and nerves in front of the neck to the cervical vertebra. There were two distinct cuts into the spinal column about the third cervical vertebra, one penetrating deeply into the upper edge of the bone, and the other a quarter of an inch below it, commencing on the body of the vertebra and running more deeply to the right side. This divided the transverse process of the vertebra, opened the joint between it and the bone, and severed the vertebral artery. There were deep cuts, which had bled, on the inside and outside of the left hand; and the pad of the middle finger of the right hand had been sliced off, and was found wedged in the joint of the razor. This was half open and lay a yard behind the body. There was no blood upon the handle, while the hands of the deceased were bloody. The deceased's bonnet was found covering a large patch of blood near the razor. A collar which she wore, as well as the strings of her bonnet, had been cut through, and these like the razor were at a distance from the body. It is scarcely necessary to adduce reasons for showing that these wounds could not have been inflicted by the deceased upon herself. Apart from all the surrounding circumstances, and looking at the medical description only of the situation, nature, extent, and direction, the surgeon was quite justified in saying that 'it was impossible for any person to inflict such wounds upon himself.' The hacking of the bones of the spinal column in two distinct places with

rce as to cut off a part of the bone, after both carotid arteries and r veins had been cut through, was alone sufficient to justify this ı. In order to produce these marks, the razor must have been sly twice used with great force through the same deep incision. could be no reasonable doubt that this was an act of deliberate r; but there was a failure of proof to trace it to the accused.

cides may graze the ligaments in front of the spinal column, but ıey should make deep incisions into the bones, cut off hard bony ıes, and divide the intervertebral substance and the vertebral arteries, oposition contrary to all experience and probability. The case of *ırl of Essex*, who was found dead in the Tower in July, 1683, bore hat on these points. The deceased was discovered with his throat d a razor lying near him. This razor was found to be much notched, he throat was smoothly and evenly cut from one side to the other, the vertebral column. Some considered this to have been an act of , others of murder. Those medical witnesses who supported the view ide were asked to explain how it was that such an even wound ıave been produced by a notched razor. They attempted to account is by asserting that the deceased had probably drawn the razor ards and forwards across the neck-bone; forgetting that before this have been done by the deceased, all the great vessels of the neck have been divided. In *Reg.* v. *Heywood* (Liverpool Wint. Ass. it was proved that deceased had died from a wound in the throat ing six inches from right to left, by which the upper portion of the pe was severed as well as the branches of the carotid artery. Her as concealed by a pillow, the arms were crossed, there was a razor in ght hand, and the back of the razor was towards the body. The were clean. A pillow on the other side of the bed was bloody ıeath. All these circumstances clearly indicated homicide and dal interference after death. The prisoner ınvicted. In a former part of this work 3, 83) the case of *Gardner* is referred to r. *Gardner*, C. C. C. 1862). Among various -legal questions to which this case gave ras that which we are now considering. the wounds in the throat inflicted by the ed on herself, or by another person? With- ing minutely into details, it may be stated ɔqueira, the surgeon who was called, found man dead and blood was copiously effused, ly on each side of the neck, not in front of rson. A large table-knife was loosely placed right hand; it was lying in the direction length of the body, the back of the blade ls the chest, and the sharp edge in front. was dry blood upon the blade and handle. lustration, fig. 95, made from a drawing spot, shows the exact position in which dy was found on the floor of the room. lying at full length in a corner by an open s if laid out, the right arm which held the ɔeing partly under a bed, as indicated by e which traverses it. The wound in the cut through the bone and thyroid cartilage larynx, dividing the thyroideal artery, causing a flow of blood and by suffocation. It commenced over the larynx as by a deep stab,

Fig. 95.




Position of the body of Mrs. Gardner (*Reg.* v. *Gardner*, Central Criminal Court, 1862).

and extended for about two inches downwards and backwards on the left side. It must have been inflicted while the deceased was lying down, and under the circumstances it was not such a wound, in the opinion of the medical men, as a woman could have inflicted on herself while in this position.

The knife was lying *loosely* in the right hand of deceased, and the small quantity of blood on the palms presented the appearance of smearing or wiping. On these facts being proved, it became simply a question which of two persons then in the house was guilty of this act of murder. The husband was convicted of the crime. In homicidal wounds of the throat, the hands of the deceased, either back or front, frequently present marks of recent cuts. These injuries arise from an instinctive effort to protect the throat under a sudden attack. It need hardly be said that a person contemplating self-destruction by wounding the throat would not begin by making cuts across the hands. Sometimes the weapon may be so grasped by the person attacked as to cause numerous cuts on the front of the hand. These will of course bear the characters of recent cuts. Their presence should admit of some reasonable explanation. In the case of *Gardner* (p. 519), this was one of those facts properly considered to be inconsistent with the innocence of the prisoner. The palms of the hands of the deceased presented numerous fresh cuts in the positions shown by the illustrations, fig. 96. The sharp blade of the knife had probably been grasped by deceased before her death, in resisting the attack. There were four cuts on the left hand and six on the right. Some of the cuts were across the fingers. Of two on the middle finger of the left hand one had gone completely through to the bone.

Fig. 96.



Case of Mrs. Gardner. The recent cuts on the palms of the two hands are here shown by the dark lines.

Another case of some importance in which a man was tried and convicted of the murder of a woman living with him as his wife, was the subject of a trial (*Reg.* v. *Wiggins*, C. C. C. Sept. 1867). The woman was found dead with a wound in her throat which divided the carotid artery, the internal jugular vein, and the windpipe. It commenced on the left side far back, penetrating as by a stab perpendicularly towards the spine, the bones of which had been indented by the violence of the blow. Death must have speedily followed. There was a wound on the neck of the prisoner commencing on the left side, going in a direction from left to right and from above downwards. It was quite superficial, involving only the skin and the external jugular vein. The prisoner alleged that the deceased had cut his throat while he was lying on the floor asleep, and that she had afterwards destroyed herself.

A close examination of these wounds showed that on the prisoner's neck there was a superficial cut such as a man might easily produce on himself, while the wounds on the neck of the woman were such as were not likely to have been self-inflicted. There were many circumstances in this case which only admitted of explanation on the theory that a murderous *assault* had been committed on the woman by the prisoner, and that he *had* subsequently inflicted the wound in his own neck, to give some

plausibility to the story that his wife had attempted to murder him while he was lying asleep. He gave two accounts of the transaction not consistent with each other, nor with any of the facts proved in the case. Among the circumstances which were inconsistent with his statement was the following:—He produced a neckerchief which he said he wore while lying down, and showed the constable a cut in the handkerchief which, according to him, was produced by the deceased while attempting to cut his throat. The neckerchief was of thin red cotton in sixteen folds. It was nearly transversely cut across the folds, the edges clean and sharply cut, and neither stained nor stiffened by blood. It could not be made to correspond in any way to the cut in the neck. It was nearly at right angles to it, and on the opposite side of the neck as it was worn. It was obvious, from a close examination, that the cut must have been made on this cotton-handkerchief when it was not upon the neck, and with a clean knife. For a full account of this singular case, which presented points of interest in reference to the probable time of death, the attitude of the body, the power of locomotion and exertion after a wound of the carotid artery, the jugular vein and trachea, and the medical inferences from blood-stains on clothing, the reader is referred to a paper in 'Guy's Hosp. Rep.' 1868, vol. 14, p. 112.

It is important on these occasions that there should be no disturbance of the body, of the weapon, articles of furniture, or other matters in its immediate vicinity. If the body or the weapon has been carelessly moved, or the arrangement of the clothes altered, this may materially affect a medical opinion. There is no case in medical jurisprudence, in which the rule *prius est de crimine quam de reo inquirendum*, is more rigidly enforced than in reference to these wounds of the throat, whether the wounded person survives or dies. Hence much consideration is required before we come to the conclusion that the act was certainly homicidal. It will greatly aid the effect of medical evidence in reference to the situation and direction of wounds in this part of the body, if at the time of inspection a rough diagram of the neck in its fore and back part is made, and lines are so carried as to indicate, by arrows, the direction which the weapon is supposed to have taken. A Court will thus be able to follow more completely the description given by a medical witness, and to appreciate more readily the reasons which he assigns for his opinion. It would be well if, before a body is moved, a photograph could be taken of the attitude and position of surrounding objects in relation to it. (See on this subject 'Ann. d'Hyg.' 1848, 1, 433.)

Wounds inflicted by the right or left hand.—Some remarks have been made in reference to the direction of a cut or a stab varying according to whether the right or the left hand has been used by a suicide. It is necessary for a medical jurist to be aware that there are many persons who are *ambidextrous*, *i.e.* who have equal facility in the use of the right and the left hand. This may not be generally known to the friends of the deceased; and such persons are often pronounced, even by those who had associated with them, to have been right-handed. A want of attention to this point is said to have been one of the circumstances which led to a suspicion of murder in the case of *Sellis*. (Wills' 'Cir. Evidence,' p. 97.) This man was found dead on his bed with his throat cut—the razor was discovered on the left side of the bed; whereas it was generally supposed and asserted that he was a right-handed man. The truth was, he was equally expert in the use of the razor with his left and right hand; and thus the suspicious circumstance of the razor being found on his left side was at once explained away. In 1865, a case of suicide by cut-throat occurred in London, which shows the necessity of caution in forming an opinion

in these cases. A man known to be right-handed was found dead with his throat cut; it proved to be what is called a 'left-handed cut,' *i.e.* done with the left hand. It appeared in evidence that deceased was brought up as a wood-carver, a trade which requires a man to use both hands equally well. Thus the cause of the wound being in an unusual direction for a right-handed man was satisfactorily explained. The direction in which a wound has been made may not infrequently be determined by the serrated character of the edges. The points of these serrations are directed towards the commencement of the wound. If after the wounding the person lives more than two or three days, these serrations disappeared by the absorption going on in the edges of the wound. In cases of cut-throat the existence of small tentative cuts near the commencement of the main cut affords aid in diagnosis. If these are fairly parallel with the chief wound, the presumption afforded by this evidence is that the wounds were suicidal; but if the tentative wounds be different in direction from the principal wound, this points rather to homicide than suicide, and may be referred to the attempts by struggling to evade the assassin's knife.

It is not uncommon to find one end of a wound, more especially in a case of cut-throat, digitated or palmated. This is probably due to the folding of the skin during the action of the weapon, and hence these digitations indicate the termination of the wound.

Accidental Stabs.—Severe incisions on vital parts do not often happen by accident, but severe punctures and stabs affecting vital organs have frequently an accidental origin. These stabs arise generally from falls while the person is in the act of running with a pointed instrument in his hand or his pocket. There is one character which, when thus produced, they are commonly observed to possess, namely, that their direction is from below upwards. In this way the truth of a defence may be sometimes tested, as when a prisoner alleges that the deceased threw himself or *fell* upon the weapon. Homicidal stabs may be likewise directed from below upwards; but this is somewhat rare, and not probable, unless the person is stabbed by an oblique blow, while in the recumbent posture. Rules of this kind may appear to be susceptible of but little practical application; yet cases occasionally present themselves wherein a close attention to situation and direction may materially assist in forming an opinion. In a case of alleged murder, which was tried in 1843, at the Cent. Crim. Court, a surgeon deposed that he found, on examining the body of the deceased, a stab on the left side of the chest, near the arm-pit, about six inches in depth. It had wounded the lung, and had penetrated obliquely into the right auricle of the heart, passing from left to right. He properly contended, that, considering the situation and direction of this wound, it was very improbable that the deceased could have inflicted it upon himself. The fact that there may be some instances in which rules of this kind will not be applicable, must not deter us from endeavouring to make a cautious application of them in doubtful cases.

The following cases show how acccidental may simulate homicidal stabs. A blacksmith, while forging a piece of rod-iron, was irritated at some observations made by a bystander. He made a rush at the offender with the heated iron in his hand, the end being red-hot; he stumbled and fell. In some way the piece of iron became accidentally reversed—he fell upon the red-hot point, which struck against a portion of the breast-bone, glanced from that, and penetrated the upper part of the left lung. He died in a few days, and the body was examined. Had only one person been present when this circumstance occurred, a charge of murder might easily have arisen, and the medical and circumstantial evidence might have appeared

o favour this view. ('Dublin Med. Press,' Jan. 1845.) How could such n occurrence have taken place by any conceivable accident? Cooper elated a case in which a man accidentally inflicted upon himself a stab nder very singular circumstances. ('Med. Gaz.' vol. 36, p. 264. See lso case, 'Ann. d'Hyg.' 1843, 2, 169.)

In 1843, a man was brought to Guy's Hospital with a punctured wound n the back, between his shoulders. It had been inflicted by a stonemason's hisel. The instrument had penetrated to its head, which had prevented t from going further, and had entered the chest, producing a severe wound s it was supposed of the lungs, attended with copious hæmorrhage. It ppeared that the man had been drinking and quarrelling with some com- anions. He had fallen from a blow, but did not complain of being stabbed, nd was conveyed home. His wife, on removing his coat, found that his waistcoat and shirt had been penetrated by the chisel, which was still sticking in his back, but the outer coat had not been cut or perforated by it. She withdrew the instrument, when copious bleeding came on, and he was sent to the hospital. The person with whom he had fought was charged with having stabbed him; and it was clear that such a stab must have been either homicidal or accidental. It was elicited from witnesses, however, that no weapon was seen in the hands of the accused—that the chisel belonged to the wounded man, and that he used it in his trade as a stonemason; there were no marks of blood on the floor where he fell, or on his clothes; that after leaving the public-house where the quarrel took place, he walked with a policeman, who said that the man exhibited no signs of having been wounded, and did not complain of having been struck by any weapon. These facts seemed to show that the stab must have taken place after the quarrel; it was further proved that the wounded man had the chisel in his pocket before the quarrel, and that as the outer coat had not been cut, a homicidal stab could only have been inflicted by the assailant raising this, which was altogether improbable: and then it would remain to be explained how the weapon could have penetrated up to its head.

From the whole of the facts, it was considered that this must have been an accidental stab; although its direction, as such, was remarkable, since, according to the wife's statement, the weapon had not entered the body in a slanting direction, but straightforward, and it required considerable force to remove it. The man recovered, and from the statement which he made, there could be no doubt that it was an accidental stab produced by a fall; but it was certainly extraordinary that it should have been found in such a situation, and taking such a direction. On these investigations, some egard must always be had to the helpless state of intoxication in which a wounded person may be. This may give an anomalous character to ccidental stabs or punctures, and render a man unconscious of a severe njury. The case further illustrates the importance of examining the dress. Had the act been homicidal, the coat would have been found perforated.

At the trial of a *Mrs. Mackinnon* for murder, 1823, a careful observa- ion of the direction of a stab in the chest clearly proved the falsehood of a efence. The deceased had been stabbed with a knife, and on an inspection f the body, it was found that the wound, which was situated over the artilage of the second left rib, penetrated towards the left, backwards, nd very much downwards, into the lungs. On the part of the prosecution was alleged that the prisoner held a long table-knife dagger-wise, and ruck the deceased in a direction downwards, forwards, and to her right de. The prisoner alleged in defence that she merely held the knife before er, sloping upwards to deter the deceased from attacking her; that he umbled forward and fell upon the point of the knife. This statement

was in some measure confirmed by the bystanders. As the witnesses on both sides were intoxicated, the important medical fact to guide the jury was the *direction* of the wound. This was wholly inconsistent with the statement of the prisoner, but in accordance with the evidence for the prosecution. ('Ed. Month. Jour.' Nov. 1851, p. 418.)

Foreign tribunals in questions of this nature have taken evidence on the stature of the assailant and deceased, as an aid to solve the question whether a stab was the result of accident or homicide. A trial took place in Rome (Case of *De Lucca*, Rome, Ap. 1872) in which during a quarrel between the Pope's guards and some soldiers, one of the former fell dead from a bayonet wound in his side between the sixth and seventh ribs. The medical evidence showed that the wound took a horizontal direction and caused death by dividing the vena cava. The medical witnesses who were called for the prosecution deposed that the deceased *De Lucca* was more than six feet in height, while the person alleged to have inflicted the stab was short, being under five feet. On this ground they alleged that if wilfully inflicted, a bayonet thrust from so short a man as the prisoner must have taken a decidedly upward direction instead of a horizontal one. They seem to have forgotten that by raising his musket with both hands, the prisoner might have inflicted a stab taking either a horizontal or even downward direction in spite of the difference of stature. The evidence rendered it probable that the deceased, in attempting to wrest the musket from the prisoner, accidentally drew it towards him and inflicted the bayonet wound on himself. The prisoner was acquitted. It may be here observed that accidental stabs when persons are standing upright are commonly horizontal. Watson describes the case of a man who, while performing in 'Rob Roy,' and when the stage was obscured by smoke, accidentally ran forward upon the bayonet of one of the soldiers and thus received a horizontal stab in the chest, from which he died in a few seconds. ('On Homicide,' p. 276.) In 1858, an inquest was held on the body of a man who had died from an accidental stab under the following circumstances. *Lieut. Clavering* and a friend were walking late at night near Acton, when they were attacked by the deceased who was intoxicated. In self-defence, Clavering raised a sword-stick which he carried; the deceased pulled at it, and thus unsheathed it, the lieutenant keeping the sword pointed outwards. The deceased fell, but it was not known at the time that he had been stabbed, as he was helplessly intoxicated. At the first place where there was a light on the road, the lieutenant and his friend examined the sword, and they saw no blood upon it. The drunken man was picked up dead; and on examination it was found that he had died from a penetrating wound in the chest, involving the heart. It commenced on the outer side of the right nipple, was seven or eight inches long, going straight across the chest to the heart. It must have been given or received when the deceased was standing sideways. The medical witness properly admitted that this direction was quite consistent with accident, and with the mode in which the lieutenant and his friend had stated that the wound had been inflicted. The only unintelligible part of the case is that the lieutenant holding a sword, point outwards, should not have been aware, either by its entrance or withdrawal, that it had penetrated a human body, when the circumstances were such as to render such an accident highly probable.

In *Reg.* v. *Carver* (Guildford Aut. Ass. 1870) prisoner was charged with the murder of his wife by stabbing her in the chest with a knife. The wound was between the fourth and fifth ribs of the left side. It was *four* inches deep, and had penetrated to the heart. It caused death in *two or three* minutes. The defence was that the deceased rushed at the

soner while he was holding the knife in his hand. The direction of wound was described as straight or transverse, and the surgeon thought might have been caused by the woman rushing on the knife in the nner described. As to the precise direction of the wound, the witness d it was rather upwards towards the heart. There were other marks of lence about the deceased, showing that she had been ill-treated, and :re was evidence of the prisoner having been seen to strike her about) time at which she was wounded. Upon this evidence he was convicted.

A remarkable case involving a similar question was tried at the Cent. im. Court (*Reg.* v. *Davy*, July, 1871). The prisoner was charged th the manslaughter of Mr. Moon under the following circumstances. fall was heard in the dining-room, and on persons going in they found e deceased on the floor, dying from a wound in his chest. The prisoner id in answer to an inquiry: 'I am afraid I did it, but I don't know how; must have been done in the scuffle.' The knife—a large table-knife, ken from the knife-box on the sideboard—had been removed from the ound, and was lying within the fender. There was evidence of threats d quarrelling between the parties, but the defence at the trial turned ainly on this medical question: 'Was the wound such as might have sulted from accident during a scuffle, or did it carry with it clear id undoubted proofs of design?' The wound penetrated the left side of e chest between the sixth and seventh ribs, reaching and wounding the ex of the heart, and was downwards, forwards, and inwards in one iiform direction—straight from end to end, never changing its course. he obliquity of the ribs al-wed of its reaching the apex the heart. There was not e slightest upward tendency the direction of the wound. he opinion of Savory was hat the wound must have en inflicted by another per-n stabbing the deceased, d that it was caused by one ow given with considerable rce.' He could not suggest y theory satisfactory to him-lf by which the wound could ve been caused accidentally. ther surgeons gave evidence the same effect.

Fig. 97.



Side view of the ribs, showing the direction of a stab traversing the heart. (*Reg.* v. *Davy.*)

The engraving (fig. 97), duced from a photograph, ows where the knife entered tween the ribs, and the rection which it took from e lower margin of the sixth) at the side to the lower argin of the seventh rib in nt. The wound in the in, which is here removed, s about two inches further ck. Its exact situation is licated by a pin projecting m the under edge of the sixth rib.

The counsel who defended the prisoner made the suggestion that 'two

medical men might come to different conclusions as to the *course* such a wound took.' Savory believed it was impossible that the body of Moon had fallen on the knife and so inflicted the wound. He could not account for the wound in that way. He would not swear unconditionally that it was impossible, because his judgment might err, but he believed it to be impossible; and, he said, the wound being from above downwards, the pressure must have come from above, whereas in the case of a falling body the pressure would come from below.

For the defence four surgeons were called, who thought the wound might have been caused by the deceased in pulling down the knife upon himself during a struggle with the prisoner. One believed that the knife might have been driven into the apex of the heart by a fall. An appeal to the jury to acquit the prisoner on the ground of the conflicting opinions expressed in the case, and the difficulty which the jury must necessarily experience in seeing their way to a verdict of guilty, failed.

There is every reason to think that the view of this case expressed by Savory, namely, that this wound from its situation, direction, and depth, was the result of an act of deliberate stabbing, and that no accident could reasonably explain it, is a correct one. The firmness and decision with which he gave his evidence is worthy of imitation on all similar occasions. No case of this kind is ever likely to come before a Court of Law in which there will not be conflicting medical opinions, and if such a conflict is to be made a ground for the discharge of persons accused of these serious crimes, there will be no convictions.

In *Reg.* v. *Malony* (C. C. C. Sept. 1861), in which a man was convicted of the murder of his wife by stabbing her in the neck, the direction of the wound was not consistent with the testimony of a witness upon whose evidence the case chiefly rested. The medical witness stated that the stab followed the line of the axis of the shoulder, commencing above the collar-bone on the left side, and passed perpendicularly downwards into the chest. It caused almost immediate death. The prisoner stated that his wife had inflicted the wound on herself and had then thrown the knife away (it was found sticking by the blade upright in the floor). There was blood upon the hands of the prisoner and upon his clothes. The medical witness admitted it was possible that the deceased might have produced this wound on herself, and in answer to a question by the judge (Byles, J.), he thought it *probable*. At the trial, a witness came forward and swore that he saw the prisoner stab the woman, but he gave no information to the police, nor said anything about the matter. He was asked what sort of stab it was that he saw the man give to the woman. 'The witness made a *forward thrust* with his right arm;' but a wound, such as that described by the surgeon, could have been produced only by a downward thrust, the hand and arm being considerably raised. The medical witness was not further examined on this point, and on the direct testimony the prisoner was convicted of murder. It is a new feature in cases of this kind to have the question of *probability* introduced. When a medical witness has admitted that the wound may have been self-inflicted, he has gone as far as professional knowledge will admit. The question of probability must be solved, if at all, by the other circumstances of the case. In *Reg.* v. *Cogan* (C. C. C. Sept. 1861), a case in which a man was charged with the murder of his wife by cutting her throat, the wound was eight inches long. It commenced at the centre of the back of the neck on the right side, passed downwards and forwards on this side of the neck across the throat to the middle of the left collar-bone. It was a very deep wound; it divided the windpipe, all the principal arteries of the neck, as well as the muscles, and even went into the cervical vertebræ. The deceased probably did

move after receiving it. A bloody razor was found six feet from the ly, and there was a pool of blood near this spot, while there were marks the window-shutter, produced by the spurting of blood from the blood- sels, in the position in which deceased's body was lying. There were sh cuts upon the left hand of the deceased, such as would be caused by r grasping some sharp instrument. The medical witness would not say was impossible, but he thought it highly improbable that deceased could ve produced this wound on herself. The prisoner, who had a slight ound in his throat, stated that this had been caused by his wife, who had erwards destroyed herself. It was proved, however, that no blood had en effused at the spot where he said this wound had been inflicted by r. He was convicted. Such a wound as this could have been produced, at all, only by the left hand of the deceased; its situation, direction, d extent, were more consistent with homicide than suicide, and the tter appears to have been clearly negatived by the facts—1, that the ceased had bled in two places, while death must have been almost stantaneous; 2, that the weapon was found at a distance from the body; d 3, that the left hand of deceased was much cut, which could be plained only by the theory that she had endeavoured to protect her roat when attacked.

The presence of several wounds.—In suicides, commonly one wound only seen, namely, that which has destroyed life, and the presence of several ounds on the body, or the marks of several attempts around the principal ound, have been considered to furnish presumptive evidence of murder. ut any inferences of this kind must be cautiously drawn, since not only ay a murderer destroy his victim by one wound, but a suicide may inflict any, or leave the marks of several attempts before he succeeds in his urpose. A case is reported in which a gentleman, labouring under mania, ttempted to destroy himself. Besides many wounds on the forearm, neck, nd face, which disfigured him, there were twenty-two in front of his hest. One of these had traversed the heart, producing death after some ours, by causing effusion of blood. ('Lancet,' July, 1839.) In wounds f the throat, owing either to ignorance of the situation of vital parts, or o tremulousness of the hand, a suicide often produces one or more incisions f greater or less extent near that which has destroyed life. This is espe- ially the case when the instrument happens to lodge in the first instance a the cartilages of the larynx. The same remark applies to suicidal stabs hen the point of a weapon, in being directed against the chest, comes first a contact with the ribs or their cartilages. With respect to the throat, any cases might be cited in which two, three, and even six or more cisions have been made in this part by suicides before they have succeeded destroying themselves. A case occurred to Handyside ('Ed. Med. nd Surg. Jour.' Jan. 1838), in which a medical man destroyed himself by flicting several wounds on his throat. An incision was found on each de of the neck, just below the angle of the jaw, and in the hollow behind . They were irregular in form, and bore the character of deep stabs. he only important vessel divided was the internal jugular vein on the ght side; but nevertheless, a large quantity of blood was lost, and this as no doubt the cause of death. The case is in many points of view ngular, for such wounds have perhaps never before been described in cases suicide. It would appear that the deceased was ambidextrous, and that e wound on each side of the neck was inflicted by the hand of the posite side. The following case occurred in London in 1839. A lady, ho had been for several days in a desponding state, was found one morning ead in her bed in a sitting posture. On examination, two very deep and tensive wounds, which had divided the principal blood-vessels, were

perceived on the right side of the neck. There were two penknives on the bed covered with blood. From the situation and other characters of the wounds, it was inferred that they must have been inflicted with the left hand, although nothing satisfactory could be ascertained on this point. The husband and son slept in the adjoining room. There was no doubt that this was a case of suicide, although it is singular that two deep wounds should have been found thus inflicted by two different weapons on the right side of the neck, in the case of a person who was not known to be left-handed.

The *number* and *nature* of the wounds on these occasions generally lead to a strong suspicion of murder. In 1859, a woman, æt. 60, was one morning found dead with severe wounds on the back and front of her neck, apparently made as if in an attempt at decapitation. She was seen alive three-quarters of an hour before, and the only person in the house was her husband, an aged, feeble man. A large table-knife newly sharpened was found near the body. When examined by Lucas, the following injuries were observed. In front there was an incised wound across the throat, four inches long, from about half an inch on the right side of the middle line towards the left ear, dividing the large muscles on the left side of the neck, and the left internal jugular vein, which was gaping. The mark of the cutting instrument was very distinct on the cartilages of the neck, extending rather obliquely down from right to left. On the back of the neck there was a deep gaping wound, extending horizontally from the right ear to the angle of the jaw on the left side, passing down between the third and fourth vertebræ, laying the spinal marrow bare; there was a slight abrasion on the surface of the cord, which might have been accidentally produced during the examination. A second cut was found passing between the second and third vertebræ, also extending to the spinal cord. The skin showed marks of several incisions, the muscles being mangled by repeated cuttings; the edges of the bones were rough, and one slice of bone about the size of a shilling lay almost detached in the wound. The wound in front was separated from the one behind by about half an inch of skin. There were no marks of violence on the hands or on any other part of the body. The evidence at the inquest proved that the son had left the house before the time of the woman's death, and that she had spoken to the neighbours and her husband in a desponding manner a few days before the event. The evidence was generally in favour of the deed being suicidal. It was satisfactorily established that the husband and wife had lived on good terms, and no motive for his perpetrating such an act could be suggested. A verdict of 'wilful murder against some person unknown' was returned. These wounds might have been inflicted by the deceased on herself with her left hand, probably in her attempt to cut off her head. The wounds at the back of the neck were inflicted first, while the principal wound—that which proved fatal by the division of the jugular vein—was inflicted last. The woman had been for some time in a desponding state, and on the evening before the event she had been observed by her husband to pass a knife with her left hand across the back of her neck as if she was contemplating suicide. There was not the slightest proof of homicide.

The number, situation, and direction of the wounds found on a dead body may be inconsistent with the theory of a suicidal origin. A woman was found dead at New York in 1839, and there were many wounds upon her body. The husband was suspected of having killed his wife, but he asserted that she had destroyed herself. This defence, however, was *shown to* be inconsistent with the medical facts. Three physicians who examined the body deposed that there were eleven stabs, eight on and

out the left side of the thorax, one of which had penetrated the peri-
rdium, and divided the trunk of the pulmonary artery at its origin; and
s others were on the back, near the left scapula. It was considered to
quite impossible that these last-mentioned wounds could have been pro-
ced by the deceased, and there was every reason to suppose that the
bs in front and at the back had been inflicted at the same time by an
ssassin. In acts of murder perpetrated by lunatics or persons labouring
der delirium tremens, it is usual to find a large number of wounds on
e body of the person attacked. In a case at York, in 1871, a man in
fit of delirium tremens killed his wife by cutting and stabbing her.
rocter found on the body of deceased fifty-six wounds, of which some
ere of a nature inconsistent with the theory of self-infliction. The object
ith such criminals is apparently not merely to kill, but to mangle the body
f the victim.

The use of several weapons.—In general, suicides, when foiled in a first
ttempt, continue to use the same weapon; but sometimes, after having
ade a severe incision in the throat, they will shoot themselves, or adopt
me other method of self-destruction. These cases can only appear com-
licated to those who are unacquainted with the facts relative to self-
urder. Neither the presence of several wounds by the same kind of
eapon, nor of different wounds by different weapons, can be considered of
self to furnish any proof of the act having been homicidal. One instance
as been already related, in which a lunatic, in committing suicide, inflicted
irty wounds upon his head (p. 512). In a case of murder, when many
ounds are found on a dead body, it may happen that the situation or
irection of some will be incompatible with the idea of a suicidal origin.
hus a stab or cut may be close to a contusion or contused wound, and
lthough a fall or other accident might account for the latter, the former
ould indicate violence separately inflicted.

Two or more mortal wounds.—When we find several wounds on the body
f a suicide, it generally happens that one only bears about it a *mortal*
haracter, namely that which has caused death. On this account it has
een asserted by some medical jurists, that when two mortal wounds are
ound upon a body, and particularly if one of them is of a stunning or
tupefying tendency (*i.e.* affecting the head), they must be considered in-
ompatible with suicide. An inference of this kind can be applied to those
ases only in which the two wounds, existing on different parts of the body,
ere likely to prove immediately fatal. It must, however, be borne in
ind, that all suicides do not *immediately* perish from wounds which are
ommonly termed mortal: on the contrary, they have often the power to
erform acts of volition and locomotion, which might by some be deemed
holly incompatible with their condition. It is difficult to say whether one
ound was likely to destroy life so rapidly as to render it impossible for
he person to have inflicted another upon himself; but when there are
everal distinct incisions on the throat, each involving important blood-
essels, there is good reason to infer that they have resulted from an act
f murder. There are no rules by which, in unknown cases, the in-
antaneous mortality of wounds can be accurately determined—a fact
hich will be apparent hereafter, from a description of wounds of the
ead, heart, and throat.

It is not possible to say, from the mere discovery of marks of contusion
injury on the head, that the deceased must have necessarily laboured
nder insensibility or concussion, and have therefore been afterwards
nable to inflict any other wound upon himself. Injuries of the head
e attended with most singular anomalies in this respect. One person
ill be rendered insensible and powerless by a blow which may leave

scarcely any appreciable marks, while another will be able to walk and exert himself when the skull has been fractured and depressed, blood effused, and even when a portion of brain has been lost: in short, the appearances may be such as to induce many surgeons to express an opinion that death must have taken place instantaneously. It is quite right that a medical jurist should be fully prepared for the occurrence of such anomalous cases; but a strong suspicion of homicide may fairly exist when, besides marks of great injury to the head, a severe cut or stab is found on the body. A man is not likely to cut or stab himself after having sustained severe violence to the head; but he may retain the power of precipitating himself from an elevated spot, and thereby of producing great injury to the head, after having previously attempted to cut his throat or stab himself. ('Vierteljahrsschrift,' 1871, 2, 216.)

A man was found lying dead in a street in a low quarter of London, with his skull severely fractured, and his throat cut. The evidence adduced at the inquest satisfactorily showed that the deceased had attempted suicide by cutting his throat in his bedroom, and had then thrown himself out of the window, by which the fracture and other severe contusions had been produced. Had his body been thus discovered in a lonely and sequestered spot, the medical presumption would certainly have been in favour of murder. A similar remark may be made in reference to the following case, which occurred in 1872. A man stabbed himself in the chest with a sharp instrument like a dagger, and then threw himself from a window forty feet from the ground. On examining his body the weapon was still sticking in the wound. It had penetrated the chest to the depth of six inches. Cases of this description are usually determined by circumstantial evidence. In the following instance there could be no doubt of homicide. A woman was found dead nearly twelve months after she was first missed. Her body was clearly identified. A handkerchief was drawn tightly round the neck, and a wound from a pistol-ball was traced through the left side of the chest, passing out at the right orbit; and three other wounds were found, one of which had entered the heart, and all of which had been made by a sharp instrument. The prisoner charged with the crime alleged that the deceased had committed suicide—but the variety of the means and the instruments employed to produce death, as well as the fact that the gun-shot wound in the head, the stab in the heart, and the act of strangulation were individually sufficient to account for speedy death, left no doubt that this was an act of murder. (*Rex* v. *Corder*, Bury Sum. Ass. 1828. Will's 'Circ. Evidence,' p. 237.)

Wounds produced simultaneously or at different times.—When several wounds are found on a dead body, the question is frequently asked.—*Which was first received?* If one is what is commonly termed mortal, and the others not, it is probable that the latter were first inflicted. This remark applies both to cases of homicide and suicide; but it is apparent that when, in a murderous assault, a person has been attacked by several assailants at once, the wounds may have been simultaneously produced. This is, however, a question to which it is not easy to give a specific answer. Each case must be decided from the special circumstances attending it; and in most instances, unless some direct evidence is forthcoming, a medical opinion can be little more than conjectural. This question is almost always put in a Court of law; and a witness should at least prepare himself to meet it, by a proper examination of the medical circumstances of the case.

The case of *Reg.* v. *Spicer* (Berks Lent Ass. 1846) affords an illustration of the importance of examining wounds minutely, as well as the locality where a dead body is found, when it is suggested that death has

been caused by accident. The prisoner was charged with the murder of his wife, and the evidence against him was chiefly circumstantial. The deceased was found dead at the foot of a stair, as if she had accidentally fallen backwards. The parietal bone was fractured, and the fracture had extended to the base of the skull. The brain was lacerated, and there was great effusion of blood. The second vertebra of the neck was fractured, and the spinal marrow torn through. These injuries were quite sufficient to account for death, and had they existed alone, there might have been no reason to charge the husband with the murder. But there was a recent wound on each side of the temple, partly lacerated and partly bruised, and a branch of the right temporal artery had been divided—this injury having been inflicted, apparently, with a pointed blunt instrument. There were marks of blood on the wall at the top of the staircase, and a pointed stone, covered with blood, was found near to the body. It was therefore obvious, as the deceased had fallen on the summit of the head, that the injuries to the two temples *laterally*, could not have been accidentally produced during the fall, for there was no projecting body against which she could have struck in her descent to produce them; and when the force of the fall had been spent on the head, her body could not have rolled over so as to produce punctured and lacerated wounds on both temples. All the facts tended to show that a murderous assault had been made upon her at the top of the stair, and that she had afterwards fallen or had been pitched headlong backwards. The injuries received previously to the fall might have stunned her, and might not have sufficed to account for death; but their nature and situation furnished strong proof that they could not have arisen from any accidental causes operating simultaneously, and that they were neither of accidental nor suicidal origin. The prisoner was convicted. ('Med. Gaz.' vol. 37, p. 610.)

If several wounds have been inflicted through the *dress*, an examination of this may sometimes suffice to show which was first received. A man, in struggling with an assailant, received three stabs with a knife—two on the left elbow, and the third in the back. The latter was at about the level of the eighth rib;—it was vertical to the chest, and had clean edges. The lower margin was obtuse—the upper acute; hence it was evident that the cutting edge of the weapon had been directed upwards. It had traversed the left lung and the heart, and had caused immediate death. It was obvious, on examination, that this mortal wound had been first received, and the stabs at the elbow inflicted subsequently. These two stabs, which were slight, had divided the cloth coat and shirt, and had only grazed the skin, so that no blood had been effused. But the edges of the cuts in the cloth coat and shirt were stained with blood; hence it was evident that they must have been produced by a weapon already rendered bloody by a previous wound. The fact was of some importance in the case, and the correctness of the medical opinion was confirmed by the evidence at the judicial inquiry. ('Ann. d'Hyg.' 1847, 1, 461.)

CHAPTER 38.

EVIDENCE FROM CIRCUMSTANCES—MEDICAL QUESTIONS—VALUE OF CIRCUMSTANTIAL EVIDENCE—THE POSITION OF THE BODY—OF THE WEAPON—THE WEAPON OR OTHER ARTICLE FOUND IN THE HAND OF THE DECEASED—EVIDENCE FROM BLOOD, HAIR, AND OTHER SUBSTANCES ON WEAPONS—HUMAN AND ANIMAL HAIR—MARKS OF BLOOD ON CLOTHING AND FURNITURE—NO BLOOD ON THE ASSAILANT—EVIDENCE FROM WADDING AND PROJECTILES—EXAMINATION OF FIRE-ARMS—BLOOD ON THE DECEASED—BLOOD ON THE ASSAILANT—EVIDENCE FROM THE FORM AND DIRECTION OF SPOTS OF BLOOD.

Evidence from circumstances.—In pursuing the examination of the question respecting the homicidal or suicidal origin of wounds, the attention of the reader may be called to the force of evidence which is sometimes derived from the circumstances under which the body of a person, dead from wounds, is discovered. It may be said that this is a subject wholly foreign to the duties of a medical jurist, but the author cannot adopt this view. There are few in the profession who, when summoned to aid justice in the detection of crime, do not seek for circumstances by which to support the medical evidence required of them. A practitioner would certainly be wrong to base his professional opinion exclusively on these circumstances, but it is scarcely possible for him to avoid drawing an inference from them as they fall under his observation. His evidence may be of itself weak and insufficient to support the charge against an accused party; in such a case if any suspicious circumstances have come to his knowledge, he may be often unconsciously induced to attach greater importance to the medical facts than he is justified in doing. In short, he may, through a feeling of prejudice, which it is not always easy to avoid, give an undue force to the medical evidence. But if a proper degree of caution is used in drawing inferences, and the circumstances are not allowed to create a prejudice in his mind against the accused, a practitioner is bound to observe and record them; for, being commonly the first person called to the deceased, many facts capable of throwing an important light on the case would remain unnoticed or unknown, but for his attention to them. The position of a dead body—the distance at which a knife or pistol is found—the direction of the instrument—whether situated to the right or left of the deceased—the marks of blood or wounds about the person, or of blood on the clothes or furniture of the apartment, are facts which may assist materially in developing the real nature of a case, and in giving force to a medical opinion. Many of these circumstances can fall under the notice of him only who is first called to the deceased; and, indeed, if observed by another, no advantage could be taken of them, except from the interpretation of a medical man.

In the case of *Davidson*, who was tried for murder (Aberdeen Spring Court of Just. April, 1855), the origin of certain wounds on the head of the deceased turned on the question of the presence or absence of nails at the head of a bed. On this occasion Lord Deas, the judge, remarked: 'A medical man when he sees a dead body should notice everything.' There was reason to believe that some nails had been driven into the head of the bed subsequently to the infliction of the violence, so as to give the appearance of the wounds having resulted from accident. There was some medical evidence in support of the view of their accidental origin: but according to Ogston there was no blood on the bedstock where the nails were represented to have been: and as the woman had died from

bleeding, this was not likely to have escaped being stained with blood, if the wounds, as alleged for the defence, had really been produced by the nails. In his opinion, too, the nails would not have accounted for the wounds on the temple as the result of any accident. The whole of the difficulty in this case appears to have arisen from want of proof that there were no nails in the bedstock when the woman was found dead. The prisoner was discharged on a verdict of 'not proven.'

Among the questions which present themselves on these occasions are the following:—Is the position of a wounded body *that* which a suicide could have assumed? Is the distance of a weapon from the body such as to render it improbable that it could have been placed there by the deceased? —In answering either of these questions, it is necessary to take into consideration the extent of the wound, and the time at which it probably proved fatal. Again, it may be inquired—Has the deceased bled in more places than one? Are the streams of blood all connected? Are there any marks of blood on his person or clothes, which he could not well have produced himself? Are there any projecting nails or other articles which might account for wounds on the body as the result of accident? These are questions, the answers to which may materially affect the case: hence a practitioner, in noticing and recording the circumstances involved in them, ought to exercise due caution. 'The consideration of the nature of circumstantial evidence,' observes Starkie, 'and of the principles on which it is founded, merits the most profound attention. It is essential to the well-being at least, if not to the very existence of civil society, that it should be understood that the secrecy with which crimes are committed will not insure impunity to the offender. At the same time it is to be emphatically remarked that, in no case and upon no principle, can the policy of preventing crime and protecting society warrant any inference which is not founded on the most full and certain conviction of the truth of the fact, independently of the nature of the offence and of all extrinsic considerations whatever. Circumstantial evidence is allowed to prevail to the conviction of an offender, not because it is necessary and politic that it should be resorted to, but because it is in its own nature capable of producing the highest moral degree of certainty in its application. Fortunately for the interests of society, crimes, especially those of great enormity and violence, can rarely be committed without affording vestiges by which the offender may be traced and ascertained. The very measures which he adopts for his security not unfrequently turn out to be the most cogent arguments of guilt. On the other hand, it is to be recollected that this is a species of evidence which requires the utmost degree of caution and vigilance in its application. Several of the above questions arose on the occasion of the trial of the brothers Peltzer at Brussels, in 1882, for the murder of M. Bernays.

The rule respecting the admissibility of this kind of evidence applies to circumstances of a *medical*, as well as those which are of a physical or moral kind. Medical circumstances, when properly observed and interpreted, are often of the highest importance. In order to convict an accused person on circumstantial evidence, the facts proved in the case should be consistent with his guilt, and be utterly inconsistent with his innocence; or, in the language of a judge, a certain number of material facts should be incontestably proved in the case, which are quite inconsistent with the innocence of the prisoner. These facts should be such as to render it impossible in the minds of the jury that any one but the prisoner could have committed the murder. Alderson, B., in charging a jury to this effect, made an observation which should be remembered by medical witnesses, in reference to circumstantial evidence. He pointed out to

them the 'proneness of the human mind to distort the facts in order to establish such a proposition (the guilt of the prisoner), forgetting that a *single circumstance* which is inconsistent with such a conclusion is of more importance than all the rest, inasmuch as it at once destroys the hypothesis of guilt.'

There are many cases on record in which an observation of slight and unexpected circumstances by medical men, has led to the detection of offenders. In the life of Sir Astley Cooper, it is mentioned, that when called to see *Mr. Blight*, of Deptford, who had been mortally wounded by a pistol-shot in the year 1806, he inferred from an examination of the localities that the shot must have been fired by a *left-handed* man. The only left-handed man near the premises at the time was one Patch, a particular friend of the deceased, who was not in the least suspected. This man was, however, subsequently tried and convicted of the crime, and he made a full confession of his guilt.

The rules for investigating a case of poisoning (see p. 203) may be equally observed in cases of death from violence. Among the circumstances to which a medical witness should specially direct his attention on these occasions are the following:—

1. *The position of the body.*—The body may be found in a position which the deceased could not have assumed on the supposition of the wound or injury having been accidental or suicidal. The position of a dead wounded body is often only compatible with homicidal interference, either at the time of death or afterwards (case of Bernays, 1882). In order to determine the probable time of death, we should always notice whether there is any warmth about the body—whether it is rigid, or in a state of decomposition, and to what degree this may have advanced. The importance of such observations in a case of alleged murder has been elsewhere considered (pp. 70, *et seq.*)

2. *The position of the weapon.*—If a person has died from an accidental or self-inflicted wound, likely to cause death either immediately or within a few minutes, the weapon is commonly found either near the body or within a short distance of it. If found near, we must notice on which side of the body it is lying; and if at a short distance, consider whether it might have fallen to the spot, or have been thrown or placed there by the deceased. If there has been any interference with the body, evidence from the relative position of it and the weapon will be inadmissible. In one case, a woman had evidently died from a severe wound in the throat, which was homicidally inflicted; the weapon, a razor, was found under the left shoulder, a most unusual situation, but which, it appears, it had taken owing to the body having been carelessly turned over before it was seen by the surgeon who was first called.

It is compatible with suicide that a weapon may be found at some distance, or in a concealed situation; but it is much more frequently either grasped in the hand, or lying by the side of the deceased. In one instance, the deceased was discovered in bed with his throat cut, and the razor lying *closed* or shut by his side. In another case, the bloody razor closed was found in the deceased's pocket. In the case of a *Captain Wright*, who was found dead in one of the French prisons during the war with France, it is stated on good authority that the *shut razor* was held in the hand of the deceased. In a wound involving the great blood-vessels of the neck, it is most improbable that there should be any power to close or shut the razor with which the wound was inflicted; and there are fair grounds to suspect interference when a razor is thus found closed in the hand. There is, however, one circumstance in relation to a weapon strongly confirmatory of *suicide*. If the instrument is firmly grasped in the hand of

he deceased, no better circumstantial evidence of suicide can be offered. t is so common to find knives, razors, and pistols grasped in the hands of uicides, that it is unnecessary to produce cases illustrative of this state- ent. The grasping of a weapon appears to be owing to muscular spasm rsisting after death, and manifesting itself under the form of what has en called cadaveric spasm. It does not seem possible that any murderer uld imitate this state, since the relaxed hand of a dead person cannot be ade to grasp or retain a weapon, like the hand which has firmly held it y powerful muscular contraction at the last moment of life. Of this the ses of *Reg.* v. *Saville* (Nottingham Sum. Ass. 1844) and *Reg.* v. *Hey- ood* (Liverpool Wint. Ass. 1855), furnish illustrations. See pp. 67, 519.

In reference to the weapon being found at a distance from the body, all he circumstances of the case should be taken into consideration before ny opinion is expressed. If the weapon cannot be discovered or it is ound concealed in a distant place, this is strongly presumptive of homicide, rovided the wound is of such a nature as to prove speedily fatal. In the se of *Lord W. Russell*, 1840, no weapon could be found; and although he wound in the throat bore somewhat of the characters of a suicidal in- ision, the absence of the weapon was sufficient to show that a wound hich was certain to be rapidly fatal must have been the act of a murderer. he assassin had used a carving-knife, which he had afterwards washed nd then replaced in the tray with the other knives.

It should be noticed whether the weapon is sharp or blunt, straight r bent, also whether the edge is or is not notched. These circumstances ay throw a light on the question of suicide or murder. In *Reg.* v. *Gill* Dublin Commis. Court, Nov. 1860), the prisoner, an old man, was harged with the murder of his wife. The woman was found dead with wound in her throat, dividing the larynx as well as the thyroideal rteries and gullet at the thyroid cartilage. It penetrated to the front of he spine, which was hacked and notched apparently with some violence. everal pieces of bone were detached. The right hand of the deceased as turned back, and a blunt knife was lying in it loosely, and not rasped. The cut through the skin and muscles of the throat was clean nd had evidently been made by a sharp instrument. On the left side he cut had two extremities presenting an appearance as if the weapon ad been twice used in cutting. The knife found in the hand of deceased as not only blunt, but turned at the point, and it had no handle. There as a mark of a bloody finger on the dress over the left shoulder of eceased. From this state of facts, Porter and Geoghegan drew the nclusion that deceased had not inflicted this wound on herself. Among her circumstances, the hacking of the spinal column and the evidence two separate cuts were adverse to the theory of suicide. Further, e wound had not been made with the knife found in the hand. If this apon had been used for the purposes of suicide, it would either have en grasped in or have altogether fallen out of the hand. The deceased d not produced the bloody mark of a finger found upon her dress. These nclusions were fairly justified by the facts. A blunt knife had been bstituted for a sharp razor; the placing the knife in the hand had failed give the appearance presented in suicide, and the nature of the wound s inconsistent with the idea of self-infliction. The prisoner was never- less acquitted.

3. *Blood on weapons.*—The weapon with which a wound has been licted is not necessarily covered with blood. The popular view is that if ch blood is found about a dead body, the weapon ought always to be re or less bloody. In reference to heavy blunt instruments applied with ce to the head, severe contusions and fractures may be produced without

immediate effusion of blood. Unless the bludgeon is used in a subsequent struggle or handled by a bloody hand, no blood whatever may be found on the end which produced the injuries. In reference to stabs, the knife is frequently without any stains of blood upon it, or there is only a slight film, which on drying gives to the surface a yellowish-brown colour. The explanation of these facts appears to be that in a rapid blow or plunge the vessels are compressed, so that bleeding takes place only after the sudden withdrawal, when the pressure is removed. Even if blood should be effused, the weapon, in being withdrawn, is sometimes cleanly wiped against the edges of the wound, owing to the elasticity of the skin. Thus the first stab through the dress may not present any appearance of blood on the outside, but in a second stab with the same weapon the outside of the dress should present a bloody mark, unless the weapon had previously been wiped (p. 53). The blood may have been removed by washing from the blade of a knife or dagger. The handle and inner portions should therefore be closely examined. In a case of alleged murder in 1857, no blood was found on the blade of a knife or in the notch for opening it; but on removing the buckhorn handle a coagulum of blood was found between this and the plate of iron to which it was riveted.

When a weapon is bloody, particular attention should be given to the manner in which the blood is spread over it. In cases of imputed wounds or in the attempted concealment of murder, it is not unusual for a criminal to besmear with blood a knife or other weapon which has probably not been used, and to place it near the body. A young man alleged that he had received a cut on the forehead by a blow from a cutlass, which he produced. It was observed by Marc that the weapon was smeared with blood on both surfaces, but the layers were thicker towards the handle than at the point. The wound on the forehead was a clean incision; a cap, which the complainant wore, had been cut through. It was obvious, therefore, that the blood on the weapon could not have proceeded from this cut, for it would have been wiped, or only left in thin streaks, and more towards the point than the handle, by the act of drawing it through the clothes in producing the wound. There was no doubt that blood had been intentionally applied to this blade. ('Ann. d'Hyg.' 1829, 1, 263.) In the case of *Doidge* (Cornish Sum. Ass. 1862), the weapon, a large cleaver, had been wiped on the smock of the deceased, but although the blood had been thus in great part removed from the surface of the blade, it had been wiped into the recesses of the letters of the maker's name, which were found to contain dry coagulated blood.

The blood on a weapon may be wet or dry, in a partly coagulated state, or spread out as a mere film. If coagulated, this would render it probable that it had issued from the body of a living person or animal, or from a body recently dead. The blood of a *dead* animal dried in small spots on the blade of a knife may sometimes present a similar appearance, and thus lead to a mistake in evidence. This question arose in the case of *Reg.* v. *Nation* (Taunton Spring Ass. 1857). The deceased was found dead in a cart, with his throat cut, and there could be no doubt that this was an act of murder. The prisoner, who had been last seen in his company, was arrested, and a knife was found in his possession, on the blade of which there were marks of blood. On the part of the prosecution, it was contended that the knife had been used for cutting the throat of the deceased, while, according to evidence given for the defence, it had been used for cutting raw beef. A chemical witness, who was called for the prosecution, stated that the knife had been immersed in *living* blood up to the hilt—that it was *not* the blood of an ox or a sheep, and that there were on the blade of the knife certain scales or empty cells, such as are found in

the mucous membranes of the throat (epithelial scales ?). They were much larger than the globules of the blood, and were perfectly distinguishable by the microscope. From the appearance he thought the knife had passed through the mucous membrane which forms the lining of the throat. If this evidence was trustworthy, there was an end of the defence; with the admission of the statement that there were scales of the mucous membrane of the *throat* (the gullet ?) upon the blade, no further proof was required that the weapon had been used for cutting a throat. Fortunately, however, for the ends of justice, there were other circumstances which brought the crime home to the prisoner, and he was convicted. ('Med. Times and Gaz.' April 11, 1857.) Cockburn, C.J., in commenting on these microscopic subtleties, said, 'In admitting the advantages of science, they were coming to great niceties indeed when they speculated upon things almost beyond perception, and he would advise the jury not to convict upon this scientific speculation alone.'

4. *Hair and other substances on weapons.*—In some instances no blood may exist on a weapon, but a few hairs or fibres may be found adhering to it if the weapon is of a bruising or cutting kind. The main question may be in such a case whether the fibres are of cotton, linen, silk, or woollen, and whether the hair is that of a human being or of an animal. The importance of examining closely the hair found on weapons is shown in a case in which a hatchet having clotted blood and hair adherent to it was produced as evidence against an accused person, under whose bed this weapon had been found. This, with other circumstantial evidence, had turned public opinion strongly against the prisoner; but when the hair was examined it was found not to be human, but to have been taken from the body of some animal. This circumstance led to a more complete sifting of the evidence, and the accused was acquitted. It turned out that the accused had killed an animal with the hatchet, and had carelessly thrown the weapon under the bed. ('Apology for the Microscope,' p. 24.) In *Reg.* v. *Hansen* (Bodmin Lent Ass. 1856), the weapon by which the deceased lost his life was a heavy stone found near the dead body. The base of the skull was fractured, and there were upon the stone marks of blood with some hair similar to that of the deceased. The prisoner was connected with the act by his having been seen with the stone, or one closely resembling it, in his possession. On these and other circumstances he was convicted.


Before any coagulated blood is removed from a weapon, it should be carefully examined by the microscope. Hairs or fibres of linen, woollen, silk, or cotton may be found imbedded in the solidified blood, either on the edge or on the blade; and evidence of this kind may occasionally be of great importance. In *Reg.* v. *Harrington* (Essex Lent Ass. 1852), a razor was produced in evidence, with which it was alleged the throat of the deceased had been cut. The edge was examined microscopically, and some small fibres were separated from a coagulum of blood, which, under a high magnifying power, turned out to be cotton fibres. It was proved at the trial that the assassin, in cutting the throat of the deceased while lying asleep, had cut through one of the strings of her cotton nightcap. This was a strong circumstance to show that the razor produced was the weapon with which the fatal wound had been inflicted.

In *Reg.* v. *Steed* (Maidstone Sum. Ass. 1863), Pavy and the author examined the boots of the prisoner who was charged with the murder of the deceased. The marks of violence about the head showed that the assailant had trampled on the deceased after he was on the ground, producing severe wounds which led to his death. Some hairs were found firmly wedged *beneath the large* hobnails of the boots, and in certain dark

stains of coagulated blood on the leather there were some red woollen fibres. The hair was compared with a portion cut from the head of the deceased, and corresponded in colour and size. On inquiry, it was found that at the time of his death the deceased wore round his neck a red woollen comforter, of which the wool corresponded in colour and appearance with that taken from the prisoner's boots. The case was brought home to the prisoner by a variety of circumstances, all inconsistent with his innocence. A case is elsewhere referred to (*Reg.* v. *Cass*, p. 518), in which the dried blood upon a knife lying near the body of deceased was found, on a microscopical examination, to lock up within it certain fibres of woollen of a peculiar dark dye, resembling the fibres taken from a coat worn by the prisoner.

Fibres found upon weapons should, if adherent to coagula, be removed by careful digestion of the clot of blood in water, otherwise they may be at once examined in the dry state. A magnifying power of about 300 diameters may be employed. Under these circumstances *cotton* presents itself as a flattened band, assuming more or less a spiral form (fig. 98).

Fig. 98.




Fibres of Cotton, magnified 300 diameters.

Fig. 99.



Fibres of Linen, magnified 300 diameters.

Fig. 100.



Fibres of Silk, magnified 300 diameters.

The fibre of *linen* derived from flax is of a rectilinear form, with jointed markings at unequal distances, the fibre tapering to a point (fig. 99). Silk and woollen have other characters by which they may be indentified. *Silk* presents a regular cylindrical form, and there are no markings upon the surface. It has a strong refracting power on light, which gives to the fibre a well-defined boundary (fig. 100). The fibre of *woollen* is irregular, contorted, of unequal thickness, and it has peculiar markings of an imbricated character on the surface (fig. 101, p. 539). This may be taken as the type of cloth, shoddy, alpaca, merino, and a variety of other fabrics worn as clothing. The microscopical characters of these fibres under certain circumstances are long retained, so that they may be identified after many centuries. Fig. 102, p. 539, represents the woollen fibre from the shroud of a monk buried in an ancient priory in the fourteenth century, and exhumed within a recent period, after the lapse of five hundred years. The markings are simply less defined than in the recent sample of wool. The fibres are also of a coarser and larger kind. The fibre of linen appears to be equally indestructible. Fig. 103, p. 539, represents fibres from the linen cerements of a mummy, of the dynasty of the Shepherd Kings. It was unrolled in 1832. This fibre was well preserved, and was still tough. The ancient woollen was rotten, and broke into small fragments. The linen had the characters of the fibre of modern flax. It was of a very coarse fabric, and was strongly

mpregnated with a brown bituminous matter used in embalming. Its reservation was no doubt in great part owing to the presence of this sub-

Fig. 101.




Fibres of Woollen, magni- 300 diameters.'

Fig. 102.



Fibres of ancient Woollen, magnified 300 diameters.

Fig. 103.




Fibres of ancient Linen, from an Egyptian Mummy, magnified 300 diameters.

stance. These illustrations have been drawn from average specimens, nder the same microscopical power, so that they are calculated to give an dea of the relative size of the fibres. (See on this subject Linde's Beiträge zur gerichtl. Chemie,' p. 45, 1853.)

Other fibres are frequently found upon weapons, boots, and articles of ress. These are common vegetable fibres from roots, leaves, and other ubstances. They cannot be confounded either with hair or with the four orts of fibres just described. The editor was once called upon to examine he boots of a man who was supposed to have murdered a woman by kick- ng her on the head. The woman had very grey hair; and on the front of he prisoner's boot was a small dark spot, which was supposed to be blood; nd imbedded in this were a couple of white hair-like bodies. The brown ot was composed of vegetable matter, and the white 'hairs' were the own of a thistle. The discovery of *hairs* upon weapons or clothing may ave an important bearing on medical circumstantial evidence. The haracter of human hair is pretty well marked at all ages. In the young nd in females it is long and fine. The hair of the head presents itself in ransparent cylinders, variously coloured, ith markings resembling those of wool, ut hair is more uniform in width. It has cortical and medullary portion. In the lustration, fig. 104, No. 1 represents the air of a child, magnified 300 diameters, ith the linear markings on the cortical ortion. No. 2 represents the hair of an lult, magnified 300 diameters. The lines e equally seen on the cortical portion -the dark shading in the centre represents e situation of cells which traverse the ntre of the medullary portion. The letter represents the transverse section of the

Fig. 104.



air, showing the cortical and medullary portion, and the air-cells in the ntre of the cylinder. These hairs were found on measurement to have diameter of 1-360th of an inch. Human hairs vary much in size— me do not exceed the 1-600th of an inch. No. 3 represents the pointed tremity of the hair of the eyebrow. These hairs, like those of the eye-


lashes, are coarser and thicker than those of the head, and are opaque, except near the point, where they become transparent. In examining hairs microscopically it will be well to observe whether they are of the same or of different colours or sizes, whether they are pointed at one end or cut at both ends, and whether they have still attached to them the bulb or sheath in which they grew. The engraving, fig. 105, No. 4, represents the sheath of the hair with the hair issuing from it. This condition of the hair will be found when it has been violently torn from the skin. The microscope will sometimes enable a medical jurist to state whether a hair has been indented, cut, or bruised, at either or both ends—the medullary structure frequently retains these marks of violent treatment. (See Casper's 'Vierteljahrsschrift,' Jan. 1863, p. 76.) The hairs of animals are frequently found on weapons and clothing: they must not be confounded with human hair. They are generally speaking coarser, shorter, thicker, and less transparent than those of a human being. The hair of some animals may be at once distinguished by the eye or by a pocket lens, as that of the cow, the horse, and the deer; but the hair of some dogs, such as the Skye-terrier and spaniel, being long and silky, closely resembles that of man. The linear markings on the cortical portion are not so numerous or fine. Fig. 106, No. 5, is the hair of a spaniel magnified 300 diameters. By measurement it had a diameter of the 1-1125th of an inch. No. 6 is the hair or fur of the rabbit, 1-1125th of an inch. No. 7 the hair of the hare. These hairs have a remarkable structure, in the form of dark transverse cells. This kind of hair is found in all rodents, *e.g.* the rat, the mouse, and the squirrel. No. 8, is the hair of the horse, 1-340th of an inch; no. 9, of the goat, 1-500th of an inch; no. 10, of the fox, 1-600th; no. 11, of the cow, 1-600th of an inch; no. 12, the hair of the fallow-deer, 1-250th of an inch in diameter. The mere difference in size among these hairs is not to be regarded as a marked distinction, for in the same animal hairs of very different sizes may be found. The engravings above given have been copied from actual measured specimens. They are all represented under the same magnifying power, *i.e.* 300 diameters. The cells and linear markings on the cortical portion furnish the most striking differences. The necessity for an acquaintance with the characters of hair will be apparent from the case of Teague (*Reg.* v. *Teague*, Cornwall Sum. Ass. 1851, p. 504), and of Watson (*Reg.* v. *Watson*, see below).

Fig. 105.



Human Hair, with tubular Sheath, as torn out by force, magnified 70 diameters.

Fig. 106.



gue's case it was alleged that the fatal wounds to the head of the d, involving both eyebrows, had been produced by a hammer m a hedge. There was no blood on the hammer, but there were rt white stiff hairs at the smaller end. It was suggested that these ave been the hairs of a white goat, the hammer having been used ting out portions of goat-skin which were hanging on the same Two medical witnesses, however, deposed that they were hairs human eyebrow, and having compared them with the deceased's r, they found they agreed. The hair of the eyebrow was described idal or pyramidal: and the hair on the hammer had this character. ared as if it had been bruised or squeezed between two blunt sub- but this appearance might have been equally presented on the f the defence, that it was goat's, and not human hair. The medical e pointed to the weapon, and not to any act on the part of the r. The witnesses were severely cross-examined upon the structural ces of the hair of man and animals. ('Med. Gaz.' 1851, 48, 731.) ill easily occur to a medical jurist that, on some occasions, this kind nce may be of importance in showing that the hair is similar to or t from that of the assailant or deceased. An opinion of identity n a similarity of hairs found on a weapon or on a person who has m violence, should be expressed with caution. The hair of a woman ally longer and finer than that of a man, and the hair in children and more silky-looking than that of an adult. But there are ersons who have hair similar in colour, size, and length; hence ss may be able to say that there was similarity, but he can rarely be sition to swear that there is absolute identity. In *Reg.* v. *Devine*, 1864, the deceased was killed by blows with a poker. On the end weapon, which was traced to the prisoner, some grey hairs were corresponding to those of the deceased. In a case of murder and which occurred at Somers Town in July, 1864, Harley found tchet certain hairs from one to three-and-a-half inches long, which ribed as human hairs from the head of a fair person who was g grey. From their fineness he considered them to be hairs from d of a woman, and when compared with those taken from the head deceased woman (*Rosetta Bishop*), they presented so great a ty as to leave no doubt that the hair had belonged to the same and that the wounds on the head had been inflicted with this . As in other cases of contused wounds on the head, there was no pon the hatchet. The presence of hairs on a weapon under these tances proves that it has not been washed, or they would not be and if with the hairs there is no blood, then it follows that these ot have been stained with blood from the wound. This absence of , however, quite consistent with the production of contused wounds hich blood may have subsequently escaped in large quantity. (See 6).

discovery of the hair of animals may sometimes have an important on a case, as in *Reg.* v. *Watson and wife* (Notts Lent Ass. 1867). soners were charged with the murder of a man named *Raynor*. He n going into the prisoners' house, and about two hours afterwards d body was found lying across a line of railway below it. Twenty s before the body was discovered, a person had passed the spot, and y was not there. The medical evidence showed that death had been by manual strangulation. There were marks of bruises about the The face was smeared with blood, and blood had escaped from the t there was no wound by cutting and no great blood-vessel had jured. No *hat could be* found. There were marks of dragging

between the cottage and the line of railway, and at one part in the soft clay there were the impressions of footmarks corresponding to the boots of the male prisoner. On the top bar of a gate there were marks of blood. On searching the house an iron-rake was found concealed on a shelf, with a cindery substance adhering to one end of it, looking as if it had undergone fusion. On heating a portion of it the smell of burnt shellac was emitted, and on acting on it with alcohol a resinous solution like that of shellac was obtained. The alcohol caused the separation of some fibres which under the microscope proved to be the hair of some animal of the rodent order. The engraving (fig. 107) represents the appearance presented. The short fibres were mixed with irregular flakes of shellac only partially destroyed. On being questioned respecting the rake the male prisoner said he himself had used it on the Friday (the day before the murder) for cleaning out a cesspool.

Fig. 107.



Portions of Rabbit's Fur and flakes of Resin, separated from an iron rake, magnified 124 diameters. Case of Raynor (*Reg.* v. *Watson*).

A hat similar to that worn by the deceased, and purchased at the same shop, was burnt. The cindery ash was collected, and submitted to examination with precisely similar results. These hats are made of felt chiefly from rabbit's and hare's fur, and this is combined with shellac.

The theory of the prosecution was that deceased had been killed by the prisoners in their house; that they had afterwards taken an opportunity of dragging the dead body from the cottage to the railway, and had laid it across the rail, with a view of its being run over by an expected train, and concealing the murder. The train then due was late that day, and the body was discovered and removed by the porter before it had passed. Where was the hat of the deceased? It was a worthless article which no one perpetrating murder would have stolen, to be perhaps a proof against him, and yet no hat was found with the body. It was suggested for the prosecution that in dragging down the body, the hat was accidentally left in the cottage. To have returned with it to the railway might have led to detection. It was assumed that the prisoners had burnt it under the grate in order that it might not be evidence against them, and that they used the rake in the process by pressing it together, and thus some portion of the half-burnt felt still adhered to the flat end of the rake.

It was suggested in the defence that the rake might have been used for the burning of a hat a long time previously, and that the burnt shellac or resin adhering to the rake, might have been used by somebody for making varnish. According to the statement of one of the prisoners, the substance found on the rake could not have been there more than twenty-four hours, *i.e.* within the time which included the murder of Raynor. Admitting that shellac or resin is used in making varnish, rabbit's fur is not so employed, and it was necessary to account for the presence of both of these substances on the cottage-rake. There was no evidence to show that there had been varnish-making and the burning of rabbit-skins in this cottage within twenty-four hours of the death of Raynor. The only conclusion to be drawn from the facts was that some one for some purpose or other had within the time mentioned burnt in the prisoners' cottage a hat similar to that worn by the deceased, and that the prisoners knew nothing of the proceeding.

Foreign substances in wounds.—In gunshot wounds, the examination dding or paper found in a wound or near a dead body, has in more ɔne instance led to the detection of the person who had committed a . His handwriting has been traced on the paper used as wadding, or ɜ been found to have been part of a printed page, of which the nder has been discovered in his possession. When a gun is dis- ed near to the body, a portion of the wadding is generally carried he large irregular wound which is produced. This was part of the nce in the case of *Reg.* v. *Blagg* (Chester Sum. Ass. 1857). The iar character of the wadding found in the body connected the prisoner the act. Whether the wadding is found in or near the body, it d be equally preserved. In *Reg.* v. *Richardson* (Lincoln Ass. Dec. , the accused was convicted of murdering a policeman under the fol- g circumstances. He shot at the deceased, who was able before to identify the prisoner; but as the deceased was weak from loss of and failing in consciousness at the time, there was some difficulty in ıg upon this dying declaration, especially as no other person witnessed ɔt. Some paper-wadding had been picked up on the spot where the sed fell; and a gun which had one barrel loaded, and one empty from ɔnt discharge, was found in the prisoner's house within twenty-four ı of the murder. The wadding in the loaded barrel consisted of a ıent of *The Times* newspaper of March 27th, 1854, and the charred ɜulphurous pieces of wadding picked up on the spot were proved ıe publisher of that journal, who was summoned on the trial, to formed a portion of the same impression. The prisoner's counsel, ɔt, could not deny that the act had been brought home to the instru- if not to the agent, and though the explanation of the crime remained ıre to the last, and the motive unassignable, the aggregate evidence ɔd sufficient to convince the jury. Any projectiles found in a gunshot d should always be preserved for evidence. In the case of *Rush*, who tried by a remarkable train of circumstantial evidence and convicted e murder of *Mr. Jermy* (Norwich Lent Ass. 1849), it was proved the projectiles removed from the body of the deceased consisted of ılar pieces of lead (slugs). Similar masses were taken from the body ɜ son, who was killed at the same time. They were described by the cal witness as being angular, and quite unlike the shot used in killing . Each piece weighed from eleven to thirteen grains, and there were n pieces in all. As the judge remarked, this demonstrated that wo acts of murder were committed by the same person, or by this n acting in concert with others. In the *Queen* v. *Lloyd* (Shrewsbury Ass. 1854), it was proved that the deceased had been killed by the arge of a gun through a window. He was struck on the head by ; thirty shots, one of which had penetrated the brain and caused . The assailant was not seen, but the charge was brought home to ɔy numerous circumstances: among others by the discovery in one of ockets of shot of the same sizes as those removed from the head of leceased (Nos. 3 and 4). The surgeon had removed and preserved hot, so that they were afterwards available as evidence against the ner. Facts of this kind may sometimes establish the innocence of ɔcted persons. In August, 1859, a man was shot at Sheffield while g in a room. He was wounded in the left temple, and the ball d behind the left eye. A man was arrested on suspicion, and on hing his house two pistols were found, one a small one, and the several sizes larger. As the ball could not be removed, and the ıded man survived, no comparison could be made. In the meantime ɔrisoner was remanded. The wounded person died in March, 1860,

from the effects of the injury. The ball was then extracted from the body and compared with the pistols. It was too small for one and too large for the other, so that it could not have been fired out of either. The man was discharged.

The chemical analysis of a projectile may be occasionally necessary. A common bullet is entirely formed of lead. Cast bullets are commonly found to have a void space in the interior when cut through the centre, owing to the exterior cooling more rapidly than the interior, and to the greater bulk of the metal when in a liquid state. In large bullets this cavity is frequently of the size of a barleycorn. Bullets obtained by compression have no such space, and are of greater specific gravity. Small-shot consist of lead with 1-200th part of arsenic. If the arsenic is in large proportion the shot is lenticular; if absent or in small proportion, pyriform (Ure). In the case of *Rush*, type-metal was found in the house. This consists of lead with one-fourth part of antimony, the latter being left by digestion in nitric acid. It was therefore considered advisable to examine the slugs chemically, and they were found to consist chiefly of lead, and to contain no antimony.

Examination of Fire-arms.—An attempt has been made by French medical jurists to determine for how long a period a gun or pistol found lying near a dead body may have been discharged; but it is out of our power to lay down any precise rules on such a subject. All that we can say is, a quantity of potassium sulphide, mixed with charcoal, is left adhering to the barrel of the piece when *recently* discharged; and this is indicated by forming a strong alkaline solution with water, evolving an odour of sulphuretted hydrogen, and giving a deep-brown precipitate with a solution of lead acetate. After some hours or days, according to the degree of exposure to air or moisture, the saline residue becomes converted into white potassium sulphate, forming a neutral solution with water, and giving a white precipitate with lead acetate. If a considerable time has elapsed since the piece was discharged, oxides of iron with traces of sulphate may be found. (See 'Ann. d'Hyg.' 1834, 1, p. 458; 1839, 1, p. 197; 1842, 1, p. 368.) This subject excited some attention at a trial which took place in France in reference to the death of *M. Dujarrier*. It was considered here of some importance to determine whether, by the mere discharge of powder, such a deposit of charcoal or powder took place at the mouth of the pistol as to soil the finger when introduced three hours after the alleged discharge. Boutigny conducted the investigation, and found in his experiments that the finger was not blackened under the circumstances. He considers that sulphate and carbonate of potash are rapidly formed, and that the charcoal is entirely consumed. The facts proved at the trial were, however, adverse to the view thus taken. The result produced by a discharge of powder in the way supposed, must depend on the quantity of powder employed, its perfect or imperfect combustion, and the proportion of charcoal contained in it. ('Ann. d'Hyg.' 1848, 1, 392.)

Foreign substances are sometimes discovered in contused or lacerated wounds: and these may throw an important light on the circumstances under which a crime has been perpetrated. In *Reg.* v. *Hazell* (Taunton Lent Ass. 1848), the body of the deceased was found in a well. When examined, there were on the head several severe wounds sufficient to account for death. There was much blood on the clothes and face, and in the blood were sticking a quantity of hay-seeds, which led the medical witnesses to consider that the wound must have been inflicted in a stable, or in some place where there was hay. On examining a neighbouring stable, the spot where the murder was committed was rendered evident by the discovery of marks of blood. There may be found in the wound a portion of the

weapon itself. The preservation of this is necessary, as it may serve to connect the prisoner with the act, should his criminality be otherwise doubtful. In *Reg.* v. *De Salvi* (C. C. C. Oct. 1857), it was proved that the deceased died from a stab inflicted on him by the prisoner. Two inches of the pointed portion of the blade of a knife were found imbedded in one of the vertebræ. The spinal cord had been divided, and paralysis, ending fatally, was a result of the wound. The identity of the weapon was not only established, but the force by which it had been used by the prisoner was thus clearly indicated.

In the case of a man named *Moore*, charged with murdering his wife in Finsbury, in 1859, it was proved that the woman's throat had been cut through to the spinal column. The surgeon in making a minute examination of deceased's neck, found small particles of steel, which had formed part of the edge of a cutting instrument, broken off and imbedded in the muscles and bones. These were examined microscopically and their nature verified. They were covered with blood. In a box in the prisoner's room two razors were found. The blade of one of these, stained with blood from end to end, had been partly wiped. The edge of this razor presented several notches, corresponding to the portions of steel found on the vertebra of deceased. The handle of the razor was also partly unriveted, showing that it had been used with very great force. Suicide was not only thus disproved, but the act of murder was fixed upon the accused.

Marks of blood on clothing or furniture.—It is proper to notice all marks of blood on the clothes of the deceased or in the apartment, and to observe where the greatest quantity of blood has been effused; this is generally found on the spot where the deceased has died. The deceased may have bled in more places than one; if so, it should be noticed whether there is any communication in blood between these different places. Blood on distant clothes or furniture will show whether the deceased has moved, or has been moved about, and whether he has struggled much after receiving the wound. Acts of locomotion by a wounded person who has died from loss of blood, or by a criminal whose hands and feet may be bloody, are generally indicated by tracks or marks of blood. The observation of these marks is of medical importance, if made at the time that a dead body is found. They may be so situated as to show that the body has been moved or been interfered with after death, and thus throw a light upon the question whether the act has been one of homicide or suicide. In *Reg.* v. *Hatto* (Bucks Lent Ass. 1854), a mark of blood, as from the smear of a hand, was traced along the passage of the house in which the body of the deceased was found. The mark was continued over the door-post into a back-room, which was found locked and bolted on the inside. The crime was thus fixed upon the prisoner; for no one breaking into the house in front could have had access to this room. The evidence thus brought against him was derived from his feeling his way with a bloody hand in the darkness after the murder. He was not at the time aware that he was thus leaving impressions which would show that no one but himself could have perpetrated the crime. It is a fair subject of medico-legal inquiry on these occasions, whether there are any marks of blood about the apartment or the spot where a murder is alleged to have been perpetrated, which no one but the assassin could have produced.

In the case of Mr. Briggs (*Reg.* v. *Müller*, Cent. Crim. Court, Oct. 1864), it was proved that the outside handle of the carriage-door in which the fatal assault was made was marked with blood, while there was no blood upon the hands of the deceased, which were examined soon after the occurrence. This was adverse to the theory that deceased had opened the door, and had fallen out, while it proved that a hand stained with fresh blood had been in contact with it.

In the case of Mrs. McPherson (the *Queen against Jessie McLachlan*, Glasgow Circ. Court, Sept. 1862), Macleod observed footprints in blood in the bedroom of deceased, who was found dead from wounds obviously homicidal. There were three imprints of a naked left foot, one of them particularly well marked. There was the impression of a small well-formed foot at rest. Before any suspicion was attached to any one, the medical witness expressed an opinion that they were made by a woman's foot with a high instep. At the time of this act of murder there were only three persons in the house—the prisoner, the deceased, and a man aged 87, James Fleming. Macleod observed, when he made an inspection of the body, that there was no blood on the feet of the deceased—further, he made a careful outline of her left foot, and found that it did not in any way correspond to the footprints on the floor of the room. The foot of deceased was larger in all dimensions, it was longer and broader, and had a large bunion. In his opinion the left foot of the deceased could not have produced these marks. He compared the foot of James Fleming with the footprints, and they were obviously quite different. He had a flat foot, in contradistinction to a high sole by which the marks had been produced. He was quite satisfied that the old man's foot could not have caused them. He also compared the feet of the prisoner with these marks, especially the left foot, and the marks in his judgment might have been produced by her foot. The accused made no objection to tread with her left foot in a thin layer of bullock's blood and then step on a plank of wood. When all the conditions of the floor were imitated, two impressions were obtained which corresponded with a marvellous degree of accuracy with the marks taken from the house. In the minutest detail of measurement and outline they tallied with the original. ('Report of Medical Evidence,' by Dr. Macleod, 1862, p. 13.) This was one among the numerous circumstances which tended to fix the act upon the prisoner.

In *Gardner's* case (p. 519) it was remarked by the surgeon that there was no blood on the wainscot or part of the bed-furniture of a room where, had the woman Humbler perpetrated or participated in the act, it was supposed it would be found. On the following day, the fourth day after the murder, some blood was pointed out in this situation by the prisoner; it had the appearance of having been recently splashed or smeared, and one patch was still wet. This had been obviously done to furnish that evidence against the woman by which the prisoner hoped to avert suspicion from himself. Fortunately the room had been well examined on the previous day by the surgeon and a policeman, and they were able to depose that the marks of blood in the room had been caused after their examination.

In reference to clothing, it is advisable, if it be possible, to have some clear proof that the clothes sent for examination were actually worn by the accused, or that they had belonged to the deceased and were really taken from the body. Serious mistakes are sometimes made, and opinions should therefore be expressed with caution. In the case of *Hatto* (Bucks Lent Ass. 1854), the clothes said to have been worn by the prisoner on the night of the murder were examined. On the shirt there were no marks of blood: on the trowsers and cap there were a few stains of blood: but it was admitted that, from the appearance of these, they might have been on the clothes five or six weeks, and therefore several weeks prior to the date of the murder. Owing to this want of certainty respecting date, these clothes were not produced in evidence; and it subsequently turned out by the confession of the prisoner, and the discovery of other articles of dress in places where he admitted he had concealed them, that the clothes *which* had been examined were not worn by him when he perpetrated the *murder*. In the case of Munro (Cumberland Spring Ass. 1855), the

es supposed to have been worn by the prisoner were sent for examina-
There was no blood on the trowsers, and it appeared, from the
nce at the trial, that the prisoner had changed this article of dress
e he was apprehended. In a case of suspected murder, we should
ine for blood not only articles of dress produced by the police, but any
s that might have been worn by the accused at the time of the occur-
. In the Road murder (*Reg.* v. *Constance Kent*, Wilts Sum. Ass.
), the omission to inquire minutely in the first instance into all the
les of dress led to the defeat of justice. The prisoner, a girl only
en years of age, showed an amount of cunning, in the perpetration
concealment of this act of murder, rarely met with among old and
ienced criminals. From the nature of the wounds on the body of the
t, her step-brother, it was not probable that the dress of the person
ting them could have escaped being stained. It appears that she
hree night-dresses, but only two were produced. When asked for an
nation, she said one had been lost at the wash a week after the murder.
was proved to be a falsehood by the laundress and her daughter.
other facts proved in the case, there was no doubt that the prisoner
ecreted, soon after the murder, one of her night-dresses stained with
; she then put out a clean one for the wash to avoid suspicion, but
wards clandestinely took this back again to her bedroom. This gave
ground to her statement that the missing one of the three had been
t the wash. Within twenty-four hours of the murder, a chemise
ped in brown paper and stained with blood was found by a policeman
fire-hole in the scullery; this was most probably the missing night-
. She stated in her confession that she burnt the dress worn on the
; of the murder five or six days afterwards. The three night-dresses
ld have been produced or accounted for at once; and had this been
ly carried out, a heavy load of suspicion would have been removed
several innocent persons, and a crime like this would not have
ined concealed for five years.

. medical man should observe on these occasions whether the blood is
ited in large patches on clothing, or whether it is sprinkled, and also
a note of the quantity. The sprinkling may have proceeded from a
ded artery or from a splashing of blood as a result of continued
nce. We should likewise notice whether, if the wound is in the
t or chest, blood has flowed down in front of the clothes or person, or
her it has flowed so as to collect in the armpits, on each side of the
, or under the back; for these appearances will sometimes show whether
round was inflicted when the person was standing, sitting, or lying
. If the throat is cut while a person is lying down, it is obvious that
lood will be found chiefly on either side of the neck, and not extend-
lown the front of the body. Few suicides cut the throat while in a
nbent posture, and the course which the blood has taken may, there-
sometimes serve to distinguish a homicidal from a suicidal wound.
position of the body when a wound was inflicted, is a frequent question
quests and criminal trials. In the case of *Lord William Russell* (*Reg.*
urvoisier, C. C. C. 1840), the throat had evidently been cut while the
sed was lying in bed; the blood was effused on each side of the neck
There was also found a wound on the thumb of the right hand of
leceased, which was probably inflicted at the time the hand was put
defend the throat. The case of *Mrs. Gardner* (*Reg.* v. *Gardner*,
. C. Oct. 1862), already referred to as illustrating other important
o-legal points (see p. 519), bears a strong resemblance to that of
W. Russell, but the proofs of murderous interference with the
sed were still stronger. Her throat had been cut while she was in

the recumbent position. Sequeira found an impression made by sooty fingers on the inside of the left wrist, and a similar sooty impression on the left elbow, as if it had been forcibly grasped. On the inside of the right thigh there was the impression of the palm of a bloody hand of full size, pointing downwards. He noticed these marks before the prisoner, who was a chimney-sweep, had entered the room, and he also observed that there was no soot on the hands of the deceased, and no blood sufficient to produce such an impression of blood as that existing on the right thigh. The impression was also larger than the hand of the deceased.

In a case of fratricide referred to Dupuytren, the deceased had received a severe wound at the lower part of the neck, and another in the front of the chest, which had led to his death. As the blood had run down the front of the person from both of the wounds, and one of them was so deep that the deceased, unless supported, would probably have immediately fallen, Dupuytren inferred that two persons had been engaged in the murder, and that one held the deceased by the arms while the other struck him in front. This suspicion was corroborated by there being no marks of wounds upon the hands. The opinion thus expressed was singularly confirmed by the evidence adduced at the trial of the murderer. ('Ann. d'Hyg.' 1829, 1, 465.) If the deceased has been wounded with his clothes on, we should notice whether any part of his dress has or has not been cut or injured over the situation of the wound, whether the cut portions of dress are bloody, and whether the blood has been effused or applied on the *inside* or *outside*. When, together with a wound in the throat, we find the cravat and the shirt, or in a female the collar or bonnet or cap-ribbons cut through, this, all other circumstances being equal, is strongly presumptive of homicide. A person intending suicide, unless labouring under confirmed insanity, would not allow any mechanical obstacles of this kind to remain as an obstruction to the use of the weapon. In one case of homicidal wound of the throat, inflicted in the recumbent posture, the cravat of the deceased had been lifted up, and afterwards allowed to drop over the wound, in order to conceal it. The importance of examining the dress, and comparing it with the marks of violence on the body, has already been pointed out.

Inference from the quantity of blood.—When the blood-vessels of the neck have been divided to the vertebral column, and the amount of blood on the spot where the body is found is small, there is reason to infer that the act is homicidal, and that the wound has been produced soon after death from some other cause. The Road murder, already referred to (*Rex* v. *Constance Kent*, p. 547), furnishes an illustration of this kind. In reference to young children, the question of self-infliction cannot be raised to embarrass the case: nevertheless, from such a wound as that inflicted on the deceased, there should be evidence of spurting and copious loss of blood; but the quantity of blood on the spot where the body of the child was found was so small (about two tablespoonfuls) compared with the severe wounds on the neck, that the medical man properly drew the conclusion either that the wounds had been inflicted elsewhere, or that they had been produced on the body after active circulation had ceased. There was reason to believe that the child had been first suffocated, and the severe wound dividing the blood-vessels of the neck inflicted soon afterwards, although this is not in accordance with the prisoner's confession. A case [illegible] similar, involving the death of a lady of good social position [illegible] the United States a few years since. This lady was found [illegible] her throat cut, and the bed-clothes smoothly arranged [illegible] although the soft parts of the neck, including the [illegible] and the gullet, were cut through to the

l column, there was no appearance whatever of a jet or spurt of blood, s if blood had been poured out from the divided vessels. There was lood on the fore part of the neck above or below the cut, nor on the s, with the exception of a small stain on the inside of the fingers of ight hand. The blood effused is said not to have exceeded a quart: had evidently escaped from the wound in the neck, and had flowed behind the body. Besides these marks, there was a spot of blood on heet in front of the body, entirely removed from the wound and other on the bed-clothes. The blood continued to ooze freely from the d for twenty-four hours after death, in spite of the efforts made to ss it. Was this a case of murder or suicide? Apart from all moral mstances, the medical facts were such as to justify the inference that vound was homicidal. The attitude of the body, as if laid out; the partly closed, found under the right arm, the hand not bloody; the ce of blood from the front of the person, showing that this deep and sive wound, if suicidal, must have been inflicted while deceased was down; and, above all, the small quantity of blood (one quart) which lowed from a wound involving all the great vessels of the neck to the l column—were facts presumptive of homicidal interference. Had hroat been cut while the deceased was living, there would have been eat flow or spurt of blood, but as there was no evidence of this, burne and others who investigated the case came to the conclusion the woman had been first suffocated or strangled, and her throat cut she was lying down.

bservations made in carrying out sentences of execution by decapita- show that on a division of the great blood-vessels of the neck during e life the flow of blood is copious and instantaneous. In the case of *Gardner* (p. 519), the body was straight on the floor, as if laid out, lthough the carotid artery had escaped division, there was a pool of on the floor on each side of the throat, and this had run down the

A quantity of blood escaping from the thyroideal artery, had ed the windpipe and caused death by suffocation.

hen spots of blood are found upon articles of dress or furniture, their and *direction* may occasionally serve to furnish an indication of the ion of the person with respect to them when the wound was inflicted. , if the form of a spot is oval and elongated, the presumption is the person was placed obliquely with respect to the stained article g the hæmorrhage. ('Ann. d'Hyg.' 1840, 1, p. 397.) The force which the blood has been thrown out will be in some measure indi- by the degree of obliquity and length of the spot. This is in general and rounded at the upper part, but narrow and pointed below. The of *Spicer* furnishes some suggestions on the importance of evidence ionally derived from an examination of the form and direction taken ots of blood. At the top of the stair, and at the height of four or eet above its level, several spots of blood were observed upon a brick

(See fig. 109, p. 565.) These were rendered evident by the wall ig been recently whitewashed. The spots took an oblique direction above downwards, were of a pale red colour at the upper part, but red below, terminating in a point consisting of the fibrin and the er part of the red colouring matter. Their form and regularity id that they had proceeded from a small artery, and that the wounded idual could not have been very distant from the wall, while their ng lustre rendered it probable that they were of recent origin, and well-defined termination in a firm coagulum showed that they had ably proceeded from a living blood-vessel. The deceased had died fracture of the skull and spinal column by a fall from the top

stair; one branch of the right temporal artery was found divided, and this wound could not have been produced by the fall. It was therefore evident that a murderous assault had been made upon the deceased at the top of the stair, and this had led to the spurting of the arterial blood on the brick. The height at which the spots existed, and their appearance, proved that the jet of blood had been from above downwards, thereby rendering it probable that deceased was standing up, or that her head was raised at the time the wound was inflicted. Further, as the brick with the spots was on the left hand in the descent, and the wounded artery was on the right side, it is probable that deceased was face to face with her assailant in the act of ascending the stairs, and that she was killed by being precipitated backwards to the bottom. The position in which the body was found in the cellar corroborated this view. ('Med. Gaz.' vol. 37, p. 612.)

In examining a dead body, attention should be paid to the state of the *mouth* and *throat*. Assailants who make their attack during sleep sometimes endeavour to close the mouth, or to compress the throat, so as to prevent an alarm being given. In the case of the *Duchess de Praslin*, there were the marks of finger-nails around the mouth. In another case, ecchymosed impressions, as if produced by a hand, were found upon the throat of the deceased. The *hands* of the dead person should always be examined; many cuts, excoriations, or incisions found upon them, especially if on the dorsal surfaces (backs), will indicate that there has been a mortal struggle with the assailant. In the inspection, the examination of the *stomach* should not be omitted. The presence or absence of food, mucus, or blood, may furnish evidence of considerable importance in the elucidation of the case. Thus, in the stomach of the *Duchess de Praslin*, a quantity of bloody froth was discovered. This rendered it certain that she had lived sufficiently long to swallow a quantity of saliva mixed with blood, and that probably she had made some attempts to give an alarm. The fact that several days have elapsed since death will not prevent the discovery of food in the stomach, provided it has been taken within one or two hours before death: since the digestion of food does not appear to go on to any perceptible extent after death. We have thus discovered food in the stomach twenty-eight days after interment. This question connected with the digested or undigested state of the food found in the stomach, frequently arises on criminal trials.

The nature of the dried spots of *mud* on clothing may occasionally serve to connect an accused person with an act of murder. In the case of *Reg.* v. *Snipe and others* (York Wint. Ass. 1852), evidence was adduced to show that some spots of mud on the boots and clothes of the prisoner, when examined microscopically, presented infusorial shells, and some rare aquatic vegetables, particles of soap, confervæ, and hairs from the seeds of groundsel. The mud of a ditch close to which the body of the deceased was found presented the same microscopic appearances as the mud from the prisoner's boots: and the witness who gave this evidence deposed that in his opinion the mud-spots were derived from this ditch. He had examined the mud of all the other ditches in the locality, and found it to be different. Admitting the opinion to have been correct, this circumstance clearly connected the prisoner with the act; and it was borne out by the fact that he had been seen near the spot on the night of the murder. In a case which occurred in Nov. 1857, the author found granules of wheat-starch mixed with the blood-stains on the gaiters of a man charged with murder. He had been just before the occurrence engaged in sowing seed-corn. So in *Reg.* v. *Steed* (Maidstone Sum. Ass. 1863), on the soles of the boots belonging to the prisoner, portions of farinaceous matter were discovered adhering to the nails, in addition to blood, hair, and woollen

fibres. It was proved in evidence that after the murder the prisoner had gone into a country baker and flour-dealer's shop, and trodden on the floor on which there was flour. The above facts tended to corroborate the evidence that the prisoner was the man who had been seen in the shop.

Marks of blood or other substances on the deceased.—All marks or stains of blood or dirt on a dead body require special observation. The impression of a hand, or of some of the fingers, may be found on the skin in a situation where it would have been improbable or impossible for the deceased to have produced it, even supposing that one or both of his hands were covered with blood. In one case of murder there was found the bloody impression of a left hand upon the back of the *left hand* of the deceased, in such a position that it was quite impossible the deceased himself could have made the mark. In all cases it should be noticed whether the *inside* or *outside* of the hand or whether one or both hands are marked with blood, and the size and position of the marks should be described. Stains of blood on the dress of a wounded person or dead body may often furnish important circumstantial evidence. If there are several stabs or cuts on the body involving the dress, it should be observed whether the edges of one or more of them are stained with blood, as if from the wiping of a weapon, and whether the stain is on the outside or inside of the article of dress. In simulated personal injuries, the stain of blood may be, through inadvertence, applied to the outside of the dress—a fact which might, in some instances, lead to the detection of the imposture. (See case by Bayard, 'Ann. d'Hyg.' 1847, 2, 219.) In judging from marks of blood in the *apartment*, we must take care that we are not unconsciously misled by the accidental diffusion of this liquid by persons going in and out or touching the body. The following case, which occurred in France, will show the necessity of extreme caution. A young man was found dead in his bed-chamber, with three wounds on the front of his neck. The physician who was first called to see the deceased had, unknowingly, stamped in the blood with which the floor was covered, and had then walked into an adjoining room, passing and repassing several times; he had thus left a number of bloody foot-prints on the floor. No notice was taken of this at the time; but on the following day, when the examination was resumed, the circumstance of the foot-prints was particularly attended to, and excited a suspicion that the young man had been murdered. The suspected person was arrested, and would have undergone a trial on the charge of murder, had not Marc been called in to examine all the particulars of the case. A similar circumstance occurred in the case of *Eliza Grimwood*, who was murdered at Lambeth in 1838.

Marks of blood or wounds on the assailant.—It is a very common, but erroneous, idea that no person can commit a murder in which blood is effused without having his person and clothes more or less covered with blood. On several occasions articles of clothing have been examined which had been worn by persons subsequently convicted of murder by wounding, and either no blood has been found on any part of the dress, or only small spots wholly out of proportion to the quantity of blood which must have flowed from the deceased. (See *Reg.* v. *Harrington*, Chelmsford Ass. 1852; *Reg.* v. *Flack*, Ipswich Ass. 1853; *Reg.* v. *Cass*, Carlisle Ass. 1860; *Reg.* v. *Rowlands*, Beaumaris Ass. 1861; *Reg.* v. *Edmonds*, Swansea Ass. 1862.) In the case of *Gardner* (C. C. C. 1862, p. 519), in which there had been a large effusion of blood from a severe wound in the throat, no blood-stains were found on the clothing of the man who was convicted of the murder. It is obvious that the throat of a person while standing, sitting, or kneeling, may be cut by a murderer from behind, and thus in appearance simulate suicide. Under these circumstances the

clothes of the assassin would escape being stained with blood. The flowing or spurting of blood upon his clothes will depend upon his position in relation to the deceased at the time of inflicting the wound, and this must always be a matter of pure speculation. In entire violation of this simple principle, the fact of a prisoner's clothes not being marked with blood, has been on more than one occasion urged as a proof of his innocence. (*Reg.* v. *Dalmas*, C. C. C. June, 1844.) In this case the counsel for the prisoner wished to impress the jury that no person could cut the throat of another without having his clothes covered with blood; and as it was not proved that there was any blood on the clothes, the prisoner could not have been guilty of the crime. The throat of the woman was cut while she was walking across Battersea bridge, the prisoner having inflicted the wound from behind. In the case of *Lord W. Russell*, pp. 513 and 535, the act of murder was committed by Courvoisier while in a state of nudity. In *Reg.* v. *Müller* (C. C. C. Oct. 1864), this line of defence was carried to a still greater length. Although the clothes of the prisoner were not produced, and the evidence showed that he had had time to change them, the counsel for the defence said, 'Blood spurted out from the deceased, and there is no doubt his assailant, whoever he was, must have been covered with blood, or have been considerably stained with it.' It should be observed, however, that the wounds were of a contused character, from which much blood was not likely to have flowed at the time of their infliction. The clothes worn by the assailant need not, therefore, from this state of facts, have been 'covered with blood,' or 'considerably stained.' No artery was cut through, and there was no evidence of spurting. Setting aside these erroneous assumptions, the evidence tended to show that had blood fallen upon his clothes, the prisoner had had ample time to dispose of them, and thus prevent a chemical examination of them. In one case (*Reg.* v. *Smith*, Liverpool Aut. Ass. 1867), too great a reliance upon the absence of blood-stains on the dress of the accused, as adverse to the theory of guilt, appears to have led to a failure of justice. The deceased was found dead, with his throat cut. The wounds in the throat were of such a nature that they could not have been inflicted by the deceased himself, and might have been made by another person from behind. The accused was traced to the spot, and a cap belonging to him, and saturated with blood, was found under the dying man. In his charge to the jury the judge is reported to have said: 'There were very slight, if any, traces of blood upon his clothes, and it appeared to him impossible that the person who committed this deed should not have been deluged with blood from the wound, &c.' The medical evidence was to the effect that there were some stains of blood on the clothes, which were damp. They had been washed. The jury acquitted the prisoner. In another case, commonly known as the Eltham murder case (*Reg.* v. *Pook*, C. C. C. July, 1871), a young woman was found dead, with severe injury about her head inflicted with a plasterer's hammer. One of the wounds divided the temporal artery. The prisoner's clothes were examined by Letheby, and he found upon them numerous small spots of blood, apparently recent. The judge, in charging the jury said, 'Was it likely that the person who inflicted all that violence, dividing arteries as it did in some places, could have done it without considerable marks of blood being afterwards found upon his clothes?' This question, if addressed to a medical witness who had had experience in examining such cases, would have been answered in a very different manner from that suggested. The spots were such as might have arisen from the use of a plasterer's hammer in inflicting these wounds. The effect of spurting on the clothes by the divided temporal artery would have depended on the position of the assailant at the time. By a bruising instrument of this kind 'consider-

able marks of blood' were not likely to have been produced. In a trial in Ireland, in 1872, the non-discovery of blood on the clothes of the accused was advanced as a strong proof that he could not have committed the act of murder with which he was charged. There is no doubt that policemen are often misled in searching for criminals, by relying upon blood on clothing as a necessary accompaniment of an act of murder. This also leads them to magnify stains of red paint, iron rust, and fruit-stains, on the dress of an accused person, into marks of blood.

The presence of spots of blood on articles of clothing, knives, &c., taken from the persons of those who are accused of murder, may be quite consistent with innocence. Small spots or stains have often an undue importance attached to them. Minute spots of blood on the shirt of a man tried for murder by wounding, have been regarded as furnishing proof of criminality, until it was explained that they were probably derived from flea-bites, and that some were on one side and some on the other, showing that the shirt had been worn on the two sides. The coarse clothing worn by labourers may acquire blood-spots from a variety of accidental circumstances which the accused may not always be able to explain. When an attempt has been made to wash out the stains, or the accused admits that they are there, and shows great anxiety to give some explanation of their presence, as that he has assisted in killing a pig, rabbits, or rats, or that he was carrying game about him, there may be some ground for suspicion. Due allowance should always be made for the accidental presence of blood. In *Reg.* v. *Cass* (Carlisle Sum. Ass. 1860), among twelve different articles sent for examination for blood, was a sovereign, which it was supposed had been taken from a purse belonging to the deceased at the time of the murder and had been touched by a bloody hand. Although the reddish-coloured spot, which was in the letters near the rim, presented the appearance of dried blood, yet a chemical examination showed that it was not blood. A few days after, a number of sovereigns received from a public bank were examined. Some of these presented spots similar to that on the sovereign above mentioned, and one among them had a spot of dried blood upon it. A knife, coin, or purse, handled with a cut finger, might, if found in the possession of an accused person, be thus inadvertently set down as a proof of guilt.

If no blood is found on the clothing of a person charged with murder, any wounds or marks of violence upon him should be specially examined. These may have been produced in a struggle with the deceased, and the accused may not be able to give any consistent account of the time or mode of their production. A case has been related (p. 492) in which the identity of an assailant was in some manner established by the form of an ecchymosis on his face. So a wound may be found on the accused which he may pretend to account for by some accident, or in order to evade suspicion. His statement may, however, be wholly irreconcilable with the appearances of the injury. The kind of weapon used, and the period at which it was inflicted, may sometimes be inferred from a simple examination, and prove that the prisoner's story is false. A case of this kind was tried, in which an assailant was identified by the peculiarity of a wound on the knee. He had broken into a house at night with some others, and discharged his gun at the prosecutrix, while he was in the act of kneeling or stooping. The gun burst, and the recoil of the breech produced a mixed laceration and contused wound on the knee of the assailant. When the prisoner was called upon to account for this wound, he referred it to an accidental blow from a mandril some time before. The appearance of the injury was, however, inconsistent both with the time of its alleged accidental infliction, and with the instrument said to have produced it;

while, on the other hand, it was proved to correspond to such an injury as the broken breech of the gun would have produced at the date of the burglary. This led to the identification of the prisoner and his subsequent conviction.

In 1834, two men were charged with having assaulted with intent to rob the prosecutor, a surgeon. It appears that the prosecutor, while walking late at night along a lonely road in the country, overtook three men who were strangers to him. One knocked him down by a severe blow on the face, and held him, while another put his hand upon his mouth to prevent him giving alarm. The prisoner contrived to get his finger into the prosecutor's mouth, and during the struggle the latter bit off the end completely between the nail and the first joint. The men then ran away. The piece of finger was given to a constable, and in the course of about eight hours he found one of the prisoners with his hand bandaged. On examining the hand, it was ascertained that the tip of one finger was missing. The prisoner accounted for this by saying that he accidentally cut it off. This statement was found to be false, and he made several other inconsistent statements. On comparing the piece of finger with the injured finger of the prisoner's hand, they were found closely to correspond. The portion of finger was preserved in alcohol for the trial, and upon this clear evidence of identity he and his companion were convicted. These cases may be taken as types of many others of a similar description.

Cerebral matter.—Under severe injuries to the head, a portion of the brain may escape and be deposited with blood on articles of clothing or furniture. Orfila first directed the attention of medical jurists to this subject, and suggested the application of certain tests to the dried spots of brain-matter. ('Ann. d'Hyg.' 1850, 2, 143.) He found that strong sulphuric acid applied to dry cerebral substance dissolved it and gave to it a violet colour. He also observed that hydrochloric acid operated in a somewhat similar manner, but much more slowly. Orfila did not find that albumen or albuminous tissues were similarly changed by acids. Lassaigne, who has more recently examined this question, advises the use of sulphuric acid only in its highest state of concentration. ('Ann. d'Hyg.' 1855, 1, 442.) He found that a drop of this acid placed on a dry stain of cerebral matter produced almost immediately a yellowish colour. In twelve seconds it acquired an orange tint, in twenty-five seconds a vermilion red, and in two minutes a violet colour which gradually disappeared in about an hour, as a result of the absorption of moisture from the air. He thinks the colouring effect is owing to the action of the acid on the cerebral cholesterin and not on the cerebrin. His observations apply equally to the action of the acid on the substance of the spinal marrow.

If an examination of stains of supposed cerebral matter were required in practice, the application of the microscope by a competent observer, using a power of from 500 to 600 diameters, would be preferable to the chemical methods above described. Sulphuric acid produces a variety of colours with organic substances, and a chemist might be easily deceived. In a case of murder which occurred some years since, in which the deceased had sustained severe injuries to the head, an expert professed to have discovered with the stains of blood on cloth a quantity of brain substance; but on the post-mortem examination of the body, it was found, that although there was fracture of the skull, the cavity had not been opened and no brain had escaped.

CHAPTER 39.

F BLOOD-STAINS—CHEMICAL, OPTICAL, AND MICROSCOPICAL EVI-
INS OF BLOOD ON LINEN AND OTHER STUFFS—AGE OR DATE OF
—INSOLUBLE STAINS RESEMBLING BLOOD—STAINS OF FRUITS,
OTS, AND EXTRACTS—STAINS OF BLOOD ON WEAPONS—STAINS
UST—ARTERIAL AND VENOUS BLOOD—THE GUAIACUM PROCESS—
ALYSIS—VARIETIES OF BLOOD—BLOOD OF MAN AND ANIMALS—
ALS.

Blood-stains.—It may appear at first sight an easy matter certain suspected spots or stains on articles of clothing, eapons are or are not owing to blood; but, in practice, great en experienced in answering the question. If the stains are it, most persons may be competent to form an opinion; but aracters of blood are soon changed, even when the stuff is rwise favourable for an examination. If the stains, whether l standing, are upon dark-dyed woollen stuffs, as blue, black, or if they appear in the form of small or detached spots, or dark clothing or rusty weapons, no one but a competent ould be allowed to give an opinion. Before proceeding to an be occasionally necessary to show the exact size and posi-ains when found on articles For this purpose photo- employed. In the case of . *Watson and wife*, Notts), the position of certain ood on the flap of a vas of some importance The engraving (fig. 108) ograph, taken to a scale ing the relative position two streaks of blood. A photograph thus made etter idea of quantity han any verbal descrip- ains on dark cloth are perceptible by artificial rdinary daylight. There ods of examining blood hemical processes; 2, by); and 3, by spectrum ome cases it is necessary se processes in order to lusive result.

Fig. 108.



Stains of blood on the flap of a table. Case of *Raynor, Reg.* v. *Watson and wife* (Notts Lent Assizes, 1867).

alysis.—There is no direct is by which blood can be e presumptively establish letermining the presence f the red colouring matter The chemical properties ring matter of blood are as readily dissolves in cold *distilled water*, forming, if recent, a tion. 2. The red colour of this solution is not changed to a

crimson, blue, or green tint by a few drops of a weak solution of *ammonia*. If the ammonia is concentrated, or added in large quantity, the red liquid will acquire a brownish tint. 3. The red solution when heated to about 170° F. is coagulated, the colour is entirely destroyed, and a muddy brown flocculent precipitate is formed, the quantity of which will depend on the quantity of colouring matter and albumen present. The red colouring matter of blood is always more or less mixed with albumen, and it is this substance which gives to a dried blood-stain on linen or cloth a well-marked stiffness. Stains from cochineal, and the red colours of wine, flowers, and fruit, do not cause any stiffening of the fibre of the stained stuff, nor any appearance under the microscope at all resembling a dried coagulum of blood. 4. A solution of the red colouring matter of blood in water produces with tincture of *guaiacum*, a reddish-white precipitate of the resin. On adding to this a solution of *peroxide* of *hydrogen*, a beautiful blue colour is more or less rapidly brought out. If a sufficient quantity of alcohol or ether is added, the precipitate will be dissolved and a deep sapphire blue solution will result (p. 566). Cochineal, and other red colouring matters, when thus treated give a reddish colour to the resin of the tincture of guaiacum, but undergo no change on the addition of peroxide of hydrogen. They are thus well marked and distinguished from blood. Whether the blood is new or old, whether concentrated or exceedingly diluted, the test produces the blue colouration. It produces the change better in a diluted than in a concentrated state. A drop of blood diffused through six ounces of water may be thus detected in one or two drachms of the mixture. Such are the chemical properties of blood, whether taken from the human body or from that of any warm red-blooded (mammalian) animal.

Blood-stains on linen or other stuffs. Their age or date.—Supposing the stuff to be white or nearly colourless, the spot of blood, if *recent*, is of a red colour; but sooner or later it becomes of a reddish-brown, or of a deep red-brown colour. The change of colour to a reddish-brown takes place in warm weather in less than twenty-four hours. After a period of five or six days, it is scarcely possible to determine, from the appearance, the *date* of a stain even conjecturally. In a large stain of blood on linen, no further obvious change took place during a period of fifteen years. It had a reddish-brown colour at the end of six weeks, which it retained for the long period mentioned. Indeed, it is very difficult in any case, after the lapse of a week, to give an opinion as to the actual date of a stain. The stain may not be so readily dissolved by water, but no chemical test applied to the solution can enable a chemist to fix the date. Blood of one week's, and blood of six weeks' date may present the same chemical properties. This question arose in the Eltham murder case (*Reg.* v. *Pook*, C. C. C. July, 1871). Letheby, who examined the prisoner's clothing, very properly declined to assign a date to the small stains which he had found upon it. Spectrum analysis as applied to blood furnishes no precise information as to date. It allows us to make a distinction between fresh blood and that which has undergone chemical changes, but not to fix the date. If a recent blood-stain has been exposed to smoke, or has been dried in an impure atmosphere containing acid vapours, its chemical and optical properties are changed as well as its physical appearance. Heat also affects the appearance of a blood-stain. Blood dried in a pure atmosphere and kept from air may retain its chemical character of freshness for a long time. Pfaff performed numerous experiments on fresh and old blood-stains, with a view of determining their age or the date at which they were produced. (Casper's 'Vierteljahrsschrift,' 1862, 1, 266.) He considers that the rapidity with which the red colouring matter dissolves in water

d other liquids, may constitute a safe basis for a medical opinion. It s been long known that the fresher the blood the more easily is the d colour imparted to water. It has also been pointed out that in fresh ains the colour is crimson red, while in old stains it is brown or red-own. The novelty of Pfaff's suggestion consisted simply in fixing the e of the stain on linen and other stuffs by the time required for the com-encement and completion of the solution of the red colouring matter. he solvent employed by him is a solution of arsenious acid in distilled ater, in the proportion of one grain to two drachms of water. This is a od solvent for the red colouring matter. In operating on stains on linen d other stuffs, the rapidity of solution must, however, depend on so any contingencies irrespective of age, *e.g.* the quantity of the blood, the ture of the stuff, its thickness, and its permeability to liquid, that no finite rules can be safely laid down for determining the precise date. dy has endeavoured to establish the age of blood-stains by means of e spectroscope. Upon coloured stuffs, or dirty clothes, it is of course possible to trace any physical changes in stains of blood; on red-dyed ffs the stain appears simply darker from the first, but in all cases the re of the stuff is more or less stiffened, as a result of the drying of the umen with the red colouring matter. In examining an article of clothing, ention should be paid to the side of the stuff which has first received the in: sometimes both sides are stained. The evidence derived from an ervation of this kind may be of importance.

Of the various red colouring matters extracted from vegetable and imal substances, there are none which, to the experienced eye, present e peculiar crimson-red tint of dry blood, especially when the substance examined in a good light by a low power of the microscope. When utions of these red colouring matters are heated with ammonia, some—ch as cochineal, logwood, and the colours of roots and woods—acquire a ep crimson tint; while others, such as the red colours of flowers and uits, are changed to a blue or green. These red colours are not destroyed a boiling temperature, and even when mixed with albumen this is agulated, but the red colouring matter remains unchanged. In the case blood, the effect of heat is to destroy the colour entirely. Another tinction has been already pointed out (p. 556). Guaiacum tincture and roxide of hydrogen produce no change of colour in these red colouring atters, while the red colour of blood is changed to blue. The test, wever, has only a limited value, since a few other organic substances, not cessarily pigmentary, may yield a similar reaction with guaiacum alone.

Suspected stains on clothing.—The suspected stain, if in a dry state, ould be first examined in a strong light, with a low power of the micro-pe. If caused by blood, it will not be a mere colouring of the fibres, t it will have a shining glossy appearance, and each fibre will be observed be invested with a portion of dried coagulum or clot. In other cases, nute coagula or clots presenting the appearance of dried jelly, will be n in the meshes of the stained article of clothing. In certain lights the ts may appear of a dark red colour, but by changing the light, bright nslucent portions of a peculiar crimson tint will come into view. The mson colour of a blood-stain is unlike that of any other red colouring atter, and when the stained portion presents the character of a dry agulum, the stain cannot be easily mistaken by a practised eye for that used by any other red colour. In fact, the microscope puts the observer a small stain in the same position as a non-professional person, who hesitatingly forms his judgment from a large quantity of dried blood. rtions of kino over a dress may present occasionally the appearance of agulated blood; but kino differs in colour and in chemical properties

from blood. The microscopical observation of a suspected stain on linen, cotton, or woollen, however small, is generally sufficient to enable an expert to form an opinion either in the affirmative or negative. When the stain is on black or dark-coloured cloth, no colour will be visible. If owing to blood, the fibre will, however, be stiffened, and when viewed by reflected light it may appear glossy from the drying of the albumen or serum. The suspected spot should be wetted with distilled water, and when the cloth is thoroughly softened two or three layers of white blotting paper may be pressed upon it. If blood is present reddish coloured stains will be produced, sometimes extending through three or four folds of paper. Any one of these presenting colour may be tested by adding tincture of guaiacum followed by peroxide of hydrogen, and subsequently alcohol. The blue colouration produced by blood will then be apparent. If no red colour is thus obtained on applying the filtering paper to wetted cloth, it is not probable that recent blood will be detected by any other test. If the stain is of sufficient size, a slip of the article of dress, whether cloth or linen, should be suspended in distilled water contained in a small test-tube or in a watch-glass. In the case of blood-stains of a certain age, a cold saturated solution of borax may be substituted with advantage for distilled water; and the solution may be raised to a temperature of 100° F. If the stain is owing to blood in a soluble form, a red or red-brown liquid will be seen to fall to the bottom of the tube. When a sufficient quantity has been thus collected, the clear water may be drawn off by a pipette, and the coloured liquid tested by ammonia, by heat, and by guaiacum, as already described (p. 556). Old stains are very slowly dissolved by water, and those which have been exposed to a heat of 170° F. or upwards, or to the influence of certain gases, are rendered more or less insoluble in water. Oil or grease in the stained article will also interfere with the solubility of the red colouring matter of blood. If the quantity of blood is small, the substance may be cut up and macerated in a porcelain capsule, with just enough water to keep it well moistened. After an hour the stained substance may be pressed, and a red-coloured liquid, in a state for testing, will be thus obtained. It may be objected that red stains resembling blood are occasionally found on linen and other stuffs, and may give rise to error. If the stains are insoluble in water, they cannot be easily mistaken for blood-stains: if soluble, no mistake can arise provided the red liquid so obtained is submitted to the chemical tests above described. Blood-stains rendered insoluble in water by heat or some other cause must be tested by other methods.

The effect of *heat* in rendering the red colouring matter of blood insoluble, has been already described as a test for its presence (p. 556). In the case of a dead body found burnt, with stains resembling those of blood upon the clothing or furniture, due allowance must be made for a change of this kind. The insolubility of the matter forming the stain merely affects the chemical tests, namely, the application of heat and ammonia. That the substance is blood may be proved not only by the guaiacum process, but by the spectrum. An insoluble coagulum of blood may be dissolved in ammonia by the aid of heat, and thus examined.

The changes produced by heat on blood became a subject of inquiry in the case of Raynor (*Reg.* v. *Watson and wife*, Notts Lent Ass. 1857, pp. 541, 555.) Stains suspected to be those of blood were found on various articles of clothing belonging to the female prisoner. The woman had been making black-puddings with pig's blood a few days before the murder, and it was alleged in defence that the stains found on her dress were produced with pig's blood while so occupied. The blood-marks on the dress, as well as the streak on the flap of the table (fig. 108, p. 555), had the

ppearance of coagulated blood as effused from a living body. They formed reddish-coloured solution in water like recent blood, and there was no ore salt in them than would be contained in a like quantity of blood. art of the dress was, for the sake of experiment, sprinkled with some of e black-pudding mixture, with the result that when dry, the stains were fferent in colour as well as in chemical and other properties. This ixture is made by heating blood and adding to it a quantity of salt. The ains thus made with the mixture were of a brown colour, insoluble in ater, and contained much salt. It was clear from these results that the ains on the woman's dress could not have been caused by the black-dding compound. On the other hand, it was admitted that pig's blood uld not be distinguished from human blood either chemically or micro-opically, and it was suggested that all the blood-marks would be accounted r and explained by the pig's blood being used or accidentally spilled fore it was heated and mixed with salt.

Red stains resembling blood.—There are certain red stains bearing a semblance to blood, some of which are insoluble in water. These may be entified by their special characters. Among them are:—1. *Red dyes*, ch as madder, red inks made from cochineal, a colouring matter in the thers of the banana-eater, and purpurin-sulphuric acid. Madder, when ordanted, is quite insoluble in water. Cochineal red ink is discoloured y chlorine without the production of a precipitate. The red pigment of e banana-eater is a substance not likely to be met with in practice. hough it yields a similar spectrum to blood, it may be distinguished from lood-pigment by its not yielding the spectrum of reduced hæmoglobin hen treated with reducing agents. Purpurin-sulphuric acid only yields spectrum when hot; but this spectrum might be mistaken for that of lood. 2. *Iron-moulds.* These are of a reddish-brown colour, sometimes of light or orange-red. They are quite insoluble in water, but are easily issolved by diluted hydrochloric acid, and on adding potassium ferro-yanide to the hydrochloric solution, the presence of iron will be at once pparent. Care should be taken that the acid used for this purpose con-ains no iron. A more satisfactory method of testing is to apply to the pot glacial acetic acid, followed in a few minutes by a solution of tannic cid. A blueish purple stain of ink is produced, thus indicating that the pot is owing to oxide of iron. Tannic acid alone has no action on iron-oulds. Iron-moulds are generally distinguished by their brown colour, nd by the absence of all stiffening of the fibre, on the stained spot. Not-ithstanding these well-marked distinctions, mistakes are sometimes made, s in the following case. Some years since a man was found drowned in he Seine at Paris, under suspicious circumstances. The body had vidently lain a long time in the water. On examining the shirt of the eceased, a number of red-brown stains were observed on the collar and ody—resulting, as it was supposed, from spots of blood, which had become hanged by time. On a chemical examination, however, they were found be iron-moulds, produced by the rusting of a steel chain which the eceased had worn round his neck. 3. *Red paint.* Stains made with red aint containing ferric oxide have been mistaken for blood. They may be asily known by digesting them in diluted hydrochloric acid, and applying the solution the tests for iron. Like those produced by iron-moulds, they e insoluble in water, and therefore cannot be confounded with ordinary ood-stains. The same may be said of spots of the ammonio-nitrate of lver changed by light, which the author has known to be mistaken for d stains of blood. The stuff on which the spots of blood are found may itself stained with a red dye or colour, or it may be dyed with iron: in is case it will be necessary to test by the same process a piece of the

the recumbent position. Sequeira found an impression made by sooty fingers on the inside of the left wrist, and a similar sooty impression on the left elbow, as if it had been forcibly grasped. On the inside of the right thigh there was the impression of the palm of a bloody hand of full size, pointing downwards. He noticed these marks before the prisoner, who was a chimney-sweep, had entered the room, and he also observed that there was no soot on the hands of the deceased, and no blood sufficient to produce such an impression of blood as that existing on the right thigh. The impression was also larger than the hand of the deceased.

In a case of fratricide referred to Dupuytren, the deceased had received a severe wound at the lower part of the neck, and another in the front of the chest, which had led to his death. As the blood had run down the front of the person from both of the wounds, and one of them was so deep that the deceased, unless supported, would probably have immediately fallen, Dupuytren inferred that two persons had been engaged in the murder, and that one held the deceased by the arms while the other struck him in front. This suspicion was corroborated by there being no marks of wounds upon the hands. The opinion thus expressed was singularly confirmed by the evidence adduced at the trial of the murderer. ('Ann. d'Hyg.' 1829, 1, 465.) If the deceased has been wounded with his clothes on, we should notice whether any part of his dress has or has not been cut or injured over the situation of the wound, whether the cut portions of dress are bloody, and whether the blood has been effused or applied on the *inside* or *outside*. When, together with a wound in the throat, we find the cravat and the shirt, or in a female the collar or bonnet or cap-ribbons cut through, this, all other circumstances being equal, is strongly presumptive of homicide. A person intending suicide, unless labouring under confirmed insanity, would not allow any mechanical obstacles of this kind to remain as an obstruction to the use of the weapon. In one case of homicidal wound of the throat, inflicted in the recumbent posture, the cravat of the deceased had been lifted up, and afterwards allowed to drop over the wound, in order to conceal it. The importance of examining the dress, and comparing it with the marks of violence on the body, has already been pointed out.

Inference from the quantity of blood.—When the blood-vessels of the neck have been divided to the vertebral column, and the amount of blood on the spot where the body is found is small, there is reason to infer that the act is homicidal, and that the wound has been produced soon after death from some other cause. The Road murder, already referred to (*Reg.* v. *Constance Kent*, p. 547), furnishes an illustration of this kind. In reference to young children, the question of self-infliction cannot be raised to embarrass the case: nevertheless, from such a wound as that inflicted on the deceased, there should be evidence of spurting and copious loss of blood; but the quantity of blood on the spot where the body of the child was found was so small (about two tablespoonfuls) compared with the severe wounds on the neck, that the medical man properly drew the conclusion either that the wounds had been inflicted elsewhere, or that they had been produced on the body after active circulation had ceased. There was reason to believe that the child had been first suffocated, and the severe wound dividing the blood-vessels of the neck inflicted soon afterwards, although this is not in accordance with the prisoner's confession. A case somewhat similar, involving the death of a lady of good social position, occurred in the United States a few years since. This lady was found dead in bed with her throat cut, and the bed-clothes smoothly arranged about her person. Although the soft parts of the neck, including the carotid arteries, the windpipe, and the gullet, were cut through to the

f hydrogen indicated blood over a square foot of the calico lining, and eyond this, these liquids produced no change. The degree of the diffusion f the blood, as it had been washed from the front of the trousers into the ning, was thus clearly defined.

On a trial for murder (*Reg.* v. *Misters*, Shrewsbury Lent Ass. 1841), his question as to the power of certain chemical reagents to remove tains of blood, was raised. Alum was traced to the possession of the risoner: it was found dissolved in a vessel in his bedroom, and it was upposed that he had removed the blood-stains from his shirt by the se of this salt. Two medical witnesses deposed that they had made exeriments, and had found that alum would take the stains of blood out of nen: according to one, sooner than soap and water. The results of the uthor's experiments did not correspond with these. It was not found hat alum removes stains of blood so readily as common water; and when lum is added to a solution of blood-pigment in water, so far from the olour being discharged, it is slowly converted to a deep greenish-brown quid. In one experiment a slip of linen, having upon it a stain of dried lood of old standing, was left in a solution of alum for twenty-four hours, ut not a particle of the red colouring matter had been extracted, although t was changed in colour. The effect of the alkali contained in yellow oap, as well as of potash, soda, and their carbonates, is to change the red olour of blood to a deep greenish-brown, like many other reagents, but hey do not exert on it any discharging or bleaching power. Combined ith friction, fresh blood-stains may of course be easily effaced by any *cold* lkaline or soapy liquid.

Detection of blood on weapons.—When recent, and on a polished instruent, stains of blood are easily recognized; but when of old standing, or n a rusty piece of metal, it is a matter of some difficulty to distinguish hem from the stains produced by rust or other causes. If the stain is rge, a portion may be easily scraped off on drying. This may be placed n a watch-glass with some distilled water, or saturated solution of borax, he solution filtered to separate any oxide of iron, and then tested. If the ater by simple maceration acquires a red colour, the solution may be sted by the methods already described (pp. 555, 556). Sometimes the tain appears on a dagger or knife, either in the form of a thin yellowish or ddish film, or in streaks, and is so superficial that it cannot be mechanically tached. We should then pour a thin stratum of water on a piece of late-glass, and lay the stained part of the weapon upon the surface. The ater slowly dissolves the colouring matter of blood, and the coloured quid may be examined by the chemical processes above recommended. f the weapon has been exposed to heat, so as to destroy the blood-pigment, nis mode of testing will fail. A very dilute solution of ammonia may also e advantageously used for the solution of blood stains on iron.

There is often a remarkable resemblance to the stains of blood on etal, produced by the *oxide or certain salts of iron with vegetable acids.* f the juice or pulp of lemon or orange is spread upon a steel blade, and is xposed to the air for a few days, the resemblance to blood produced by he formation of *citrate of iron* is occasionally so strong that well-inormed surgeons have been completely deceived: they have pronounced he spurious stain to be blood, while the real blood-stain on a similar eapon was pronounced to be artificial. The difficulty of distinguishing uch stains by the eye is illustrated by the following case which occurred n Paris. A man was accused of having murdered his uncle. A knife as found in his possession, having upon it dark-coloured stains, prounced by those who saw them to be stains of blood. Barruel and nother medical jurist were required to determine the nature of the stains,

and the examination was made before a magistrate in the presence of the accused. They were clearly proved, by these and other experiments, to be spots produced by the citrate of iron. It appeared on inquiry that the knife had been used by some person, a short time previously, for the purpose of cutting a lemon; and not having been wiped before it was put aside, chemical action had gone on between the acid and the metal which had given rise to the appearance. This case certainly shows that physical characters alone cannot be trusted in the examination of these suspected stains. Stains of the *citrate of iron* may be thus distinguished:—The substance is soluble in water, forming, when filtered, a yellowish solution, different from the red colour of blood under the same circumstances. The solution undergoes no change of colour on the addition of ammonia. If in the state of persalt, it is rendered blue by tincture of guaiacum alone. It is unchanged in colour, but may be partially precipitated at a boiling temperature, and it is at once identified as a ferric salt by giving a blue colour with the potassium ferrocyanide. Spots of the citrate of iron on knives are often soft and deliquescent, while those of blood are commonly dry and brittle.

It is not always easy to distinguish by sight a stain of blood on a weapon from a mark produced by common *iron-rust*. When suspicion exists, marks are pronounced to be due to blood, which under other circumstances would have passed unnoticed. One source of difficulty is this: the iron-rust on an old knife is often mixed with some article of food, or even with blood itself. We must here pursue the same mode of examination as if the stain were of blood, and macerate the weapon, or a portion of the coloured deposit scraped from the surface, in a small quantity of distilled water, and filter the liquid. If the stain is due to iron-rust alone, this will be separated by filtration, and the liquid will pass through colourless. If we now digest the brown undissolved residue left on the filter in hydrochloric acid, free from iron, we shall obtain a yellowish solution, which will give with the potassium ferrocyanide a blue colour—Prussian blue.

In old blood-stains on rusty weapons, blood and oxide of iron are necessarily intermixed. In order to detect and separate them the following plan may be adopted. Scrape off portions of the supposed dry blood and rust into a porcelain capsule. Moisten the substance with water and let it stand covered. If blood is present the water will acquire a reddish-brown hue, and the addition of tincture of guaiacum and peroxide of hydrogen will produce a red colour if blood be present. The effect is strongly marked when the water is allowed to evaporate to dryness and leave a reddish stain on the white porcelain. The guaiacum and peroxide of hydrogen have no action upon iron-rust, but the particles of dried blood acquire a blueish colouration around them, and are thereby clearly distinguished from the particles of rust. The guaiacum and peroxide applied to a film of water on which the rusted weapon has been placed will give a blue colour if blood is present, otherwise not. By this process, blood was readily detected on a rusty knife used in an act of murder committed ten years previously. (*Case of Gardner*, p. 519.) No blood could be seen on the blade with the aid of a lens.

A man was suspected of murder, and there were on his shirt some stains, which were supposed to have been produced by blood. Around the collar and upper part of the shirt there was a large and somewhat deep pinkish-red stain, in some respects resembling washed blood. This appeared to be an unusual situation for blood to be found sprinkled; and upon testing the stained linen, the colouring matter entirely resisted separation by water, and was turned of a faint crimson tint by ammonia. The stain was thus

roved not to be due to soluble blood. On inquiry, it was ascertained that
ie man had worn round his neck a common red handkerchief during a wet
ight, and while taking violent exercise. The reddish-coloured stain was
ius accounted for. There were, however, some other marks on the shirt
hich required examination, as there was a very strong suspicion against
is man. These were on the sleeves, at those parts which would be likely
) receive stains of blood if they had been rolled or turned up at the wrists;
id it was ascertained that the murderer in this case had used a quantity
! yellow soap in washing his hands. The stains were of a brownish
lour, without any shade of red; they were faint in parts, and diffused,
i if an attempt had been made to wash them out. So far as external
iaracters were concerned, it was difficult to say whether they had
en produced by blood or not. On examining the parts of the shirt
rresponding to the armpits, stains precisely similar were there seen,
ridently resulting from cutaneous perspiration, since the suspicion
! blood being effused on these parts of the shirt, under the circum-
ances, could not be entertained. Slips of linen from the stained portions
! the sleeves were digested in water. In twenty-four hours the stains
ere entirely removed, and the lower stratum of water in each tube had
xquired a straw-yellow colour. There was not the least shade of a red or
rown colour. The solution was wholly unlike that produced by blood
nder any circumstances; it was not changed in colour by ammonia, or by
heat of 212° F.; but it acquired a faint opalescence on the addition of
itric acid. These results not only indicated the absence of blood, but
iowed that the stains were due to cutaneous perspiration issuing from
dirty skin through a dirty dress. The stains on the parts corresponding
) the armpits could not be ascribed to blood, and from the similarity in
hysical and chemical properties it was impossible to attribute those on
ie sleeves to blood. It happened, however, that a large pocket-knife,
ith numerous dark-red stains on the blade and between the layers of the
andle, was found upon this man. Several persons who saw the knife
ronounced that the marks were due to blood. The stains were com-
osed of some soft viscid matter, which gave out ammonia when heated,
id left a residue of ferric oxide. On digesting the matter in water no
ortion was dissolved; and it was, therefore, evident that they were due
ot to recent blood, but to a mixture of some animal matter, probably
od, with iron-rust. The man was tried for the murder, and acquitted on
i alibi.

In the case of Mr. Briggs (*Reg.* v. *Müller*, Cent. Crim. Court, Oct. 1864), question arose whether there was dried coagulated blood upon a life-preserver, which the prisoner might have employed. The weapon consisted of a heavy mass of lead, enclosed in a network of string, and secured to a whalebone handle. There was a substance on the network resembling dried blood. When this was removed and placed in contact with water, it was not dissolved, and, under the microscope, presented the appearance of brown flakes, which gave no colour to the surrounding liquid. On applying a red-hot platinum wire to the supposed coagulum, it melted, and gave off the smell of resin. It was part of a resinous composition which had been used for securing the lead to the network; it had become softened by heat, and had oozed out between the meshes. No blood could be detected in any part.

The chemical analysis of suspected spots or stains on weapons and clothing is by no means an unimportant duty. If we cannot always obtain from these experiments affirmative evidence, they often furnish good negative proof, and thus tend to remove unjust suspicions against accused parties. Evidence should not be received on matters of this kind from

police-constables or other non-professional persons. No confidence should be placed in an opinion derived from physical characters only. On the occasion of the murder of *Eliza Grimwood*, in 1838, committed as it was under circumstances of the greatest mystery, and the perpetrator of which was never discovered, the examination of suspected marks resembling blood, became an important part of the inquiry, but it was improperly conducted. The finger-plates of the door of the room, in which the murder was perpetrated, presented some dark stains, supposed to have been produced by the bloody hand of the murderer in the act of escaping. The only test to which these were submitted was, that the magistrate, before whom the case was heard, tried to rub off some of the stains with a piece of blotting-paper, but did not succeed; and he expressed his opinion, that, if they were blood-stains, they had been wiped. It is easy to perceive to what results superficial examinations of this kind may lead.

Detection of fibrin.—Fibrin forms about 1-500th part of human blood; it exists in the blood of all warm-blooded animals. The other animal liquids in which it is found are the chyle and lymph. It is the chief constituent of muscular fibre. When the blood is in sufficient quantity, a pale film of fibrin may be left upon the stained substance, after the colouring matter has been removed by digestion in water. Small quantities of fibrin are not easily identified by chemical properties. Animal fibrin so closely resembles coagulated albumen and gluten, that it cannot be distinguished from them by chemical tests. Hence, unless evidence of the existence of red colouring matter is obtained, the presence of fibrin cannot be relied on: and if this is obtained the demonstration of the properties of fibrin is unnecessary, for there is no red colouring matter which, under due precautions, can be mistaken for that of blood. Evidence on this subject was tendered in the case of *Reg.* v. *Reed* (York Wint. Ass. 1847), but it was not well received by the Court. It has been supposed that the demonstration of the presence of fibrin in a blood-stain would enable us to say whether the blood had been effused from a living or dead body; but, admitting that the existence of fibrin in a small quantity of dried blood upon an article of dress could be indisputably established, this fact would not enable us to give a conclusive answer to the important question above suggested. If the quantity of blood examined be comparatively great, and no fibrin can be procured from it after complete digestion in cold water, it is probable that this blood has not come from a living body, and that it is merely a mixture of red colouring matter and serum, like that found in the vessels of the dead body after perfect coagulation. But the experimentalist must bear in mind that small stains of blood will commonly leave no appreciable quantity of fibrin. A well-marked stain of blood will not weigh when dry more than one-tenth of a grain. According to the average proportion the stain would not contain more than a mere trace of fibrin. On the other hand, if fibrin were clearly obtained, it would be by no means proved that the blood yielding it had issued from a *living* body. Until the blood has coagulated, there is no fibrin; and coagulation seldom commences in the dead body until after the lapse of three or four hours, although, if removed from the body, it speedily becomes solid.

Arterial and Venous blood.—It is not possible to distinguish *arterial* from *venous* blood by any physical or chemical characters, when it has been for some days effused, and is in a dry state upon articles of dress, furniture, or weapons; but this, in medico-legal practice, is not often a subject of much importance, since there are few cases of severe wounds, either in the throat or other parts of the body, in which the two kinds of blood do not escape simultaneously. The most striking and apparent difference between

them, when recently effused, is the *colour;* the arterial being of a bright scarlet, while the venous is of a dark-red hue; but it is well known that the latter, when exposed to air for a short time, acquires a florid red or arterial colour; and the two kinds of blood when dried, cannot be distinguished chemically by any known criterion. If a coat, or other stuff, stained with blood, were of a dark colour, the liquid would be absorbed and speedily lose its physical characters. The microscope shows no appreciable difference in the blood-corpuscles of arterial and venous blood, and chemistry does not enable us to apply any test so as to make a satisfactory distinction between them. In this deficiency of microscopical and chemical evidence an attempt has been made to establish a distinction by noticing the physical appearance of the blood-stain. Thus, it is alleged, the arterial blood will be indicated by its being *sprinkled* over surfaces upon which it has fallen, while the venous blood is always poured out in a full stream. In most wounds which prove fatal by hæmorrhage, the blood is poured out simultaneously from arteries and veins. The sprinkled appearance of the blood, when it exists, will, cæteris paribus, create a strong presumption that it was poured out from a *living* body, for after the heart has ceased to act the arteries lose the power of throwing out the blood in jets. This mode of distinguishing arterial from venous blood was adduced as evidence in the case of *Sellis*, who destroyed himself after having attempted to assassinate the Duke of Cumberland. There was the appearance of sprinkled blood on the coat-sleeve of Sellis, and it is stated that the temporal artery of the Duke had been wounded. Sir Everard Home thence inferred that Sellis had attacked the Duke, and wounded the artery, which had led to the sprinkling of the sleeve. ('Will's Circ. Evid.' 89.) This method of distinguishing the two kinds of blood, therefore, may be occasionally available for practical purposes; but it must be remembered that accident may lead to the sprinkling of blood from a small vein which has been wounded, while blood may be poured out in considerable quantity from an artery, especially if large; and if it fall on one spot at a short distance, it may produce a soaked appearance. The sprinkling may be expected only when the wounded artery is small, and the blood is effused at a distance. This is a fact which a medical jurist should not overlook, although, for the reasons stated, too great a reliance must not be placed on it. The spots of blood, if thrown out from a living blood-vessel, speedily consolidate, and the fibrin, with the greater portion of the colouring matter, is found of a deep red colour at the lower part of the spot, the upper portion being of a pale red. The lower and thicker part has commonly a shining lustre, as if gummed, when the spot is recent, and when it has been effused upon a non-absorbent surface. This glazed appearance is, probably, given by the evaporation of the aqueous, and the rapid desiccation of the albuminous portions. In *Reg.* v. *Spicer* (p. 549), there was a wound of the temporal artery of the deceased woman. A brick in the wall, opposite to the spot where the wound was inflicted, presented the appearance shown in fig. 109. The size and direction of the spots vary according to the distance of the person wounded, and the direction in which the spurting has taken place against the surface. When blood falls upon porous articles of

Fig. 109.



Spots of arterial blood sprinkled on the surface of a brick from a wound of the temporal artery (*Reg.* v *Spicer*, Berks Lent Assizes, 1846).

clothing, as linen or cotton, it is absorbed, and produces a dull stain. In dark-coloured articles of dress, it is sometimes difficult by daylight to perceive these stains. The part appears stiffened, and has a dull red-brown colour, which is sometimes more perceptible when seen by the reflection of the light of a candle.

In trusting to the coagulation of the sprinkled blood as evidence of its escape from a living vessel, it must be remembered that three or four hours may elapse before it coagulates in the healthy body after death. Hence blood which has escaped from a recently dead body, although it would not be found diffused as if by spurting, might, in so far as coagulation is concerned, assume the appearance of having been effused from a living body. The mere fact of the blood in blood-stains being found coagulated, does not prove that the person was actually living when the blood was effused. It merely shows that he was either living or but recently dead. Some states of the living body appear to favour and others to prevent the coagulation of the blood after death.

There is no method known by which the blood of a man can be distinguished from that of a woman, or the blood of a child from that of an adult. The blood of a child at birth forms a thinner and softer coagulum than that of the adult. A medico-legal question has arisen, on more than one occasion, whether there were any means of distinguishing *menstrual* blood from that of the body generally. This liquid yields fibrin, and contains red colouring matter and the other constituents of blood. The only differences noticed are of an accidental kind: 1st, that it is acid (fresh blood is alkaline), owing to its admixture with vaginal mucus; and 2nd, that under the microscope it is mixed with epithelial scales, which it has derived from the mucous membrane in its passage through the vagina. In the bodies of women who had died suddenly while menstrating, Webber found coagulated blood upon the uterine mucous membrane. If, therefore, menstrual blood does not coagulate, it is simply because it has already coagulated within the uterine cavity, and cannot do so again; it is more fluid than ordinary blood, because, during its trickling descent, it becomes mixed with watery uterine and vaginal mucus. ('Schmidt's Jahrb.' 1847, 7, 139.) A case occurred in France, which induced the Minister of Justice to refer the consideration of this question to the Academy of Medicine. The reporters, Adelon, Moreau, and Lecanu, came to the conclusion that there were no means of distinguishing menstrual blood dried on clothing, from that which might be met with in a case of infanticide or abortion. ('Ann. d'Hyg.' 1846, 1, 181.)

The Guaiacum Test.—The guaiacum test may be repeated with a small quantity of the solution of the stain either in distilled water or in a saturated solution of borax. Although it is alleged that several organic substances have the property of turning guaiacum blue, or of rendering a mixture of guaiacum and peroxide of hydrogen blue, there are few cases occurring in actual practice where the test is not available, and of considerable probative value. The tincture of guaiacum employed should be dilute, freshly prepared, and made by dissolving a fragment taken from the centre of a lump of the resin, in rectified spirit of wine. The tincture should be first added to the liquid to be tested. If a blue colour be produced, as will be the case should a ferric salt, or many other substances, be present, the test cannot be applied; but if no blue colour results from the addition of the tincture a small quantity of a solution of peroxide of hydrogen should be added. At once, or in the course of a few seconds, if a trace only of blood-pigment be present, a perceptible blueness of the liquid will be observed, which becomes more manifest if enough rectified spirit be added to redissolve the precipitated resin. Some experimenters

prefer to use the ethereal solution of the peroxide commonly sold as ozonic ether; whilst others, again, prefer oil of turpentine which has been freely exposed to the air. If either of these two liquids be employed in place of the aqueous solution of the peroxide, they will rise to the surface of the liquid, carrying with them most of the blue compound. Whatever oxidizing agent be employed—the aqueous or the ethereal solution of peroxide of hydrogen, or oil of turpentine—its fitness for testing must be determined by adding to it a small quantity of red chromate of potash strongly acidulated with dilute sulphuric acid, when a rich blue colour should be produced if the test liquid is fit for use.

Lefort has objected to this process on the ground that the resin of guaiacum is blued by an 'unlimited' number of substances ('Ann. d'Hyg.' 1870, 2, 432); but this objection is irrelevant and misleading. Schönbein and Day have both proved clearly that the colouring matter of blood does not cause a blueing of guaiacum resin, and therefore it could not possibly be mistaken for any one of the 'unlimited' number of substances, having nothing in common with blood, which change the colour of this resin. It is always advisable in practice to add the guaiacum first. If this is blued, then other methods of detecting blood should be resorted to.

Lefort, in dealing with this subject, forgets that in medico-legal researches the problem is to distinguish the *red* colouring matter of blood from other *red* colouring matters. He thinks that *colourless* saliva and colourless mucus may be mistaken for blood, because, according to him, they are turned blue by the guaiacum and peroxide, like blood. Assuming that he is correct (although his results are not in accordance with the author's experiments), no medical jurist could mistake colourless stains of these liquids for stains of *red* blood.


The same remarks apply to the colouring matter of bile, which, according to Jamieson ('Australian Med. Jour.' Oct. 1869), produces slowly a blueing of the guaiacum resin in contact with peroxide of hydrogen. In practice, stains of bile are so strongly marked by their peculiar yellow colour and special tests, that no one competent to undertake such investigations could fall into an error of confounding them with stains of blood. The mistakes which have arisen respecting blood on clothes have been chiefly traceable to the presence of stains derived from red fruits and flowers, artificial red dyes, and some red mineral substances, such as red ferric oxide. Lefort states that stains produced by the red colouring matter of wine gave a blue colour on the addition of a mixture of guaiacum and peroxide, but this was only after *some hours' exposure.* (Op. cit. p. 438.) It is the very essence of this mode of testing, that the effect on blood is immediate, or that it takes place within a few seconds. No reliance can or ought to be placed upon any change of colour which requires hours for its production, since the resin alone, or in mixture with peroxide, is slowly blued under long exposure to air.

The test operates equally well on fresh and old blood, and on concentrated as well as very diluted blood, even on blood which has been boiled. In conjunction with the spectroscope, it is the only certain method of discovering washed blood (p. 560). Provided some small portion of red colouring matter remains, the change to blue is perceptible. If the stain on the material gives no indication of a red colour, or the spectroscopic test —whatever might be the effect of this or any other tests—it would be unsafe to affirm that blood was present. On the other hand, the proper precautions being observed in the use of this test, if there is no blueing of the guaiacum resin in the presence of the peroxide, it will be safe to say that the mark or stain is *not* owing to blood. Every prudent witness

would avoid relying upon one test, and therefore, as so small a quantity of blood is required for the action of guaiacum, it will be always easy to reserve a portion for the spectroscope and chemical tests, so that no objection could be fairly raised against the results.

Spectrum analysis. Spectral test.—The great advantage of this optical process is that it admits of the examination of blood without in any way interfering with the subsequent application of the chemical tests already described. We simply analyse the light as it traverses a solution of the red colouring matter, and with a spectroscope attached to a microscope we notice whether the coloured spectrum has undergone any change. If the red liquid owes its colour to recent or oxidized blood, two dark absorption-bands will be seen breaking the continuity of the coloured spectrum (No. 1, fig. 110). These are situated between the *D* and *E* lines of the solar spectrum. The less refrangible of the two bands is the sharper and better defined of the two. Yet if the blood is quite recent and of a

Fig. 110.



1. Spectrum of oxyhæmoglobin.
2. Spectrum of hæmoglobin (reduced hæmoglobin).
3. Spectrum of methæmogolobin.
4. Spectrum of blood with acetic acid (acid hæmatin).
5. Spectrum of hæmochromogen (reduced hæmatin).

(*Drawn to a scale of wave-lengths.*)

bright red colour (oxyhæmoglobin) the two absorption-bands are both distinct and well defined. A good light—either artificial or daylight—is required; the coloured liquid should be clear and of sufficient intensity, and the spectrum apparatus properly adjusted. The blood may be placed in a narrow glass tube, or in a glass cell contrived for the purpose. The spectroscope should allow of two tubes being examined at once, and it is desirable to have a specimen of blood mounted for comparing the actual spectrum of blood with that of the suspected liquid.

In the course of an hour, in warm weather, and after a day or two in cold weather, the blood in the tube undergoes a change. It loses its scarlet and acquires a purple colour (hæmoglobin or reduced hæmoglobin). In this state the two bands appear blended, and one broad black band only is seen (No. 2, fig. 110). The blood appears to undergo deoxidation, for on removing it and shaking it with air in the tube, it becomes again bright, and the two bands reappear. The same change from a two-banded to a one-banded spectrum is effected by the addition of an ammoniacal solution of ferrous tartrate (Stokes's solution). This solution is made by dissolving a fragment of ferrous sulphate in water, adding an excess of potassium tartrate, and then enough of a dilute solution of ammonia to dissolve any precipitate which may have formed. The solution must be freshly prepared for use.

When a solution containing blood is exposed to the air for some time it loses its blood-red colour, and assumes a brownish tint. If it be now

amined by the spectroscope it will be found that a new absorption-band as made its appearance between the *C* and *D* solar lines; but somewhat arer to *C* than to *D* (No. 3, fig. 110, p. 568). This is the band of -called methæmoglobin.

If a solution containing hæmoglobin is acidified with acetic acid, the gment is destroyed, the solution acquires the brown-red hue of an old ood-stain, and hæmatin is formed. The same change is effected by pronged exposure of blood to air. Hæmatin in acid solution affords spectrum the number of bands in which varies according to the solvent nployed. Its acid solution in water has a very marked absorption-band, as picted (No. 4, fig. 110, p. 568) extending from about midway between e *C* and *D* solar lines up to *C* at the red end of the spectrum. If the lution be now made alkaline with dilute ammonia, the band shifts wards the blue end of the spectrum: it is indistinct and just touches the line at its most refrangible border. The addition of Stokes's solution, of other alkaline reducing agent, now results in the production of the o magnificent bands (No. 5, fig. 110, p. 568) of hæmochromogen (reduced matin). These are more refrangible than those of oxyhæmoglobin with ich they might possibly be confounded, the broader and more refrangible extending beyond the *F* solar line towards the blue; and the narrower already deep and sharply outlined before a concentration is reached reveals the more refrangible band.

-stain, however minute, may, if more or less recent, be made to ively all the spectra depicted in fig. 110, p. 568; but old blood- ich have become insoluble may yield the spectra only of hæmatin and -called reduced hæmatin (hæmochromogen). The stain is macerated or in a saturated solution of borax; and the reddish solution thus tained is examined spectroscopically side by side with a drop of fresh lood diffused through water. Spectroscopes proper for the purpose are rovided with an arrangement for comparing the two spectra side by side; nd the coincidence of the absorption-bands under examination with those f blood can be ascertained. A drop of ammonio-ferrous sulphate solution Stokes's) is then added to the two liquids; and in the event of blood being esent, the one-banded spectrum of hæmoglobin (reduced hæmoglobin) can compared with that produced from the liquid which is known to contain lood. The original solution may now be precipitated with a five per cent. lution of zinc acetate, and the reddish precipitate containing the blood- gment slightly washed on a filter with water, and redissolved whilst still oist in a few drops of glacial acetic acid. This solution will afford the ectrum of acid hæmatin (No. 4, fig. 110, p. 568). Old blood-stains may at once boiled with glacial acetic acid, or dissolved in a cold solution of rtaric acid or in dilute ammonia. The hæmatin solution when treated ith ammoniacal ferrous sulphate exhibits the two-banded spectrum of duced hæmatin (hæmochromogen). (See No. 5, fig. 110, p. 568.)

There can be no doubt that in the hands of a competent person, and e skilled in micro-spectral observations, this optical method will enable m to discover the minutest traces of blood, provided any red colouring atter remains. Thus Sorby states that a spot of blood only one-tenth an inch in diameter, or a quantity of the red colouring matter amounting no more than the 1000th part of a grain, is sufficient to give conclusive idence of its presence by spectrum analysis. Sorby thus detected blood the rusty blade of a knife with which the murder of Mrs. Gardner as committed in 1862, after the lapse of ten years (p. 519). Blood-stains hich have been washed in water, and blood which has even been boiled heated to 212° F., may be thus detected. In the latter case ammonia, ith the aid of a *gentle heat*, should be employed to dissolve the matters


rendered insoluble by boiling. Spectral analysis does not enable us to make any distinction beyond that of recent and old blood, and this distinction cannot be so drawn as to enable us to fix a specific or even an approximate date. Certain accidental conditions may rapidly produce on blood the same effect as exposure to air for a long period of time. It indicates no distinction in the blood of the sexes, of the fœtus and adult, or in the blood of man and animals. As a corroborative process it furnishes most valuable and trustworthy evidence, and there is no case in which blood admits of a chemical examination in which spectral analysis does not admit of a safe application before the chemical tests are applied. Falk describes it as the most certain, satisfactory, and simple process for detecting blood in medico-legal cases. (Horn's 'Vierteljahrsschrift,' 1867, 1, 354.)

The question here arises, Are there no objections to this optical test? Are there no red colours which, when traversed by light and sent through a prism, will produce absorption-bands similar to those of blood. Having tried all the ordinary red colours, animal, vegetable, and mineral, the author found none which produce the absorption-bands of blood; and this also is the result of Sorby's more extensive experience. A decoction of cochineal with ammonia has been said to possess similar optical properties, but in this liquid one broad black band obliterates entirely the yellow and orange rays of the spectrum. A solution of alkanet in alum gives two absorption-bands which might be mistaken for those of blood, but there is a third band at the end of the green rays where joining the blue. Even if this were overlooked, the properties of such a solution are wholly different from those of blood, and the liquid could not be mistaken for it. No prudent witness would rely upon a spectral examination only, and thus any difficulty on this ground would be removed. This answer equally applies to another objection, namely, that a prepared solution of *turacine*, a red colouring principle in the feathers of the Cape Lory (*Turacus albocristatus*), presents two absorption-bands, similar to those of blood in form and position. ('Student's Intellectual Observer,' April, 1863, p. 165.) A summary of this subject is given by Preyer ('Blutkrystalle.' 'Untersuch.' von W. Preyer, Jena, 1871). This work includes thirty-two coloured spectra of blood under its different conditions, showing how the absorption-bands vary in size, position, and number, according to the proportion of red colouring matter present, or according to the nature of the substance with which the red colouring matter is mixed.

Preyer makes a distinction in the use of the spectroscope, which it will be well for a medical witness to bear in mind. The absence of the absorption-bands in a red-coloured liquid, however much it may resemble blood, proves that it is *not* blood, but some other red colouring matter. If spectra of an artificial kind produced by chemical agents, are relied upon as proof of the presence of blood, the witness must be prepared to state from personal observation, the effect of these chemicals when employed with other red colouring matters.

Microscopical evidence. Blood-corpuscles.—Hitherto the microscope has been described as an aid to the examiner in drawing a distinction between the appearances presented by blood-stains in the dry state, and those caused by other substances. Its use, however, extends much beyond this. The spots or stains may be so small as not to admit of removal for the purpose of applying chemical tests. If an examination of a dry stain with a low power (20 or 30 diameters) justifies further proceedings, we may then employ the microscope for the purpose of detecting those peculiar bodies on which the colour of red blood is known to depend. The red colouring matter of blood consists of minute coloured corpuscles, float-

ı a clear liquid (serum). The engravings (fig. 111, 112) show the in the class Mammalia. *a* represents the circular form, when seen mt, the shaded portion being a depression which under a certain ition of the light assumes the appearance of a solid paque nucleus; *b* represents a corpuscle seen edge-in which case it presents somewhat the shape of a ave lens. It owes this form to the central de-on on each face. Other red colouring matters, is madder, cochineal, or lac, do not owe their colour ependent cells or corpuscles. Hence, if corpuscles, form and size of those found in mammalian are visible under the microscope, there can be ıbt that the liquid is blood. Such evidence can, however, be safely ed only from one who has been accustomed to the use of this instru- and to the examination of blood. In order to examine the suspected ınce for corpuscles, the best plan of proceeding, when the particles of lum are very small, is to breathe several times on a glass-slide, then the small fragments of coagulum on the slide, and again breathe over



Blood corpuscle highly magnified.

A slip of thin glass may then be laid upon them. If they consist od a red margin will soon appear, and in the fluid portion, by the a magnifying power of from 300 to 500 diameters, some of the ıcles of the blood may be recognized. They are seldom so perfectly cal as in the fresh state, and they appear small, and frequently ĸ or corrugated. In some cases only fragments of the envelopes can m. The condensed moisture of the breath serves the purpose of in breaking up the particles of dried blood, without destroying the ıcles by too much dilution. The red colour of blood is well brought ıder these circumstances. In thus treating cochineal, extract of log-kino, and other colouring matters, the appearances observed will be wholly different.

the suspected clot is in larger quantity, it may be removed from the nd placed to macerate in one or two drops of water on a glass slide. uld be covered with thin glass, in order to prevent rapid evaporation. nethod of extracting the corpuscles has frequently failed, owing to antity of water employed having been too large. Under these circum-s, the corpuscles are distended and rapidly destroyed, while the water becomes coloured. It is by no means easy in all cases to obtain dry coagula clear and distinct evidence of the presence of these ıcles, especially when the blood is old. In drying, the blood-cells ıeir form, and they do not readily resume it when again moistened. ı they are seen after a short maceration in a very small quantity of it is probable they will not be seen at all. To accelerate their tion various chemical liquids have been employed. Thus solutions ium sulphate and common salt, as well as liquid albumen and serum, ɔeen employed as fluid media for breaking up the dried clots of but there are disadvantages attending the use of these solvents. ture of glycerine and water in the proportion of one part by measure cerine, to nine or ten parts by measure of distilled water, will be preferable. The above quantity of distilled water is such as to the mixture to the specific gravity of serum, 1·028. A solution of ɔus acid, in the proportion of four grains to an ounce of distilled is also a rapid solvent of the coagula. When this is used the ıation should take place as soon as the liquid begins to be coloured margin, or the corpuscles may be destroyed, and only fragments of ɛnvelopes seen. Lesueur and Robin have adopted the following vhich they affirm to be successful for the detection of mammalian

blood. A portion of the suspected coagulum is scraped off the stained substance into a solution of sodium sulphate, made slightly alkaline by the addition of a little caustic soda, and it is then examined under the microscope, with a power of 520 diameters. At first the substance appears entirely homogeneous, but in half an hour it swells, and in another half-hour globules are formed, which can be separated by gently rubbing the glass slides one upon the other. These observers thus identified globules as those of mammalian blood, *i.e.* of animals which suckle their young. ('Chem. News,' 1850, 2, 295.)

In reference to stains on clothing, if they present any appearance of dry coagula, these should be carefully scraped off, and treated in the manner above described. If no portions of solid coagula can be procured, there will be but little hope of obtaining evidence of the presence of corpuscles in the suspected stain. The stained portion may be cut out and macerated in a small quantity of water. Under these circumstances the corpuscles may be sometimes seen aggregated, or in groups, in the fibres of the stuff, as in the engraving, fig. 113, in which the stain of blood was on a shirt. (Briand's 'Manuel de Méd. Lég.' 1863, p. 747.)

Fig. 113.




a, Corpuscles of blood in linen fibre; *b*, a group detached.

The illustrations below show the appearances presented by blood corpuscles, when examined with a power of about 300 diameters, and under different methods of treatment. The first illustration (fig. 114) is from an engraving in Lehmann's 'Physiological Chemistry.' It represents the appearance of a drop of healthy human blood. The red blood-cells are partly detached, partly united in rolls, and partly in irregular clusters. In the vacant spaces between them there are delicate threads of fibrin. The outlines of the blood-cells are rendered in some instances indistinct, by reason of this web of fibrin about them.


In fig. 115 the corpuscles are seen free from fibrin. Only a small portion of those which were in the field have been engraved. They are seen detached and in groups; those which are shaded are the white corpuscles of the blood. They are not so well-defined in form, and present an irregularity of surface, by which they may be distinguished from the coloured blood-cells.

Fig. 114.



Human blood-corpuscles with fibrin.

Fig. 115.




Human blood-corpuscles from a dried specimen, magnified 319 diameters.

Fig. 116, p. 573, represents the appearance of the corpuscles as they are seen in water, and fig. 117, p. 573, their appearance when examined after treatment with a concentrated solution of sodium sulphate. The effect of water is to alter the shape and render them spherical or globular. Water also renders them paler, and finally destroys them. In fig. 117, those

s which are seen edgewise have a lenticular shape. The shaded the depression elsewhere described (p. 571) and represented on a ale. These are taken from engravings in 'Lehmann's Physiological y.'


of Man and Animals.—When marks of blood have been detected ess of an accused person, it is by no means unusual to find these

Fig. 116.



nan blood-corpuscles, as seen in water.

Fig. 117.



Human blood-corpuscles, as seen in a solution of sodium sulphate, which does not dissolve them.

counted for by his having been engaged in killing a pig, bullock, , or in handling fish or dead game. Of course every allowance made for a statement like this, which can be proved or disproved circumstances; but the question here arises, whether we possess *in* means of distinguishing the blood of a human being from that imal. Barruel and other French medical jurists have affirmed nixing fresh blood with one-third or one-half of its bulk of strong c acid, and agitating the mixture with a glass rod, a *peculiar odour* ved, which differed in the blood of man and animals, and also in d of the sexes. This odour, it was said, resembled that of the s exhalation of the animal the blood of which was made the of experiment. Others, endowed with a more acute sense of , asserted that they had succeeded, by this process, in identifying d of frogs and fleas. (Devergie, 'Méd. Lég.' vol. 2, p. 907.) It that strong sulphuric acid does give rise to a particular odour xed with fresh blood; and it is possible that some persons may a difference in the odour, if not according to the sex, at least g to the animal. But, assuming this to be true, there is probably ndividual among a thousand whose sense of smelling would allow tate, with undeniable certainty, from what animal the unknown d really been taken. Any evidence short of this should not be ; for it is better not to decide at all, than to decide on principles e exposed to unavoidable fallacy. Besides, it must be remembered general, the operator has not before him fresh blood, or blood in antity, but merely a diluted solution of the dried colouring matter, ith a small quantity of serum, and sometimes only a few small elding no perceptible quantity of solution. In a case of some im- , which occurred in Paris, the testing of blood by odour completely the hands of Barruel, Tardieu, and Chevalier. The mistakes these experts are admitted by themselves to have been of so nature as to render this mode of obtaining evidence in any ase inadmissible. ('Ann. d'Hyg.' 1853, 1, 413; 'Guy's Hosp. ct. 1851.) Possibly, hairs, fish-scales, &c., imbedded in a blood- y indicate its origin.

In a few cases, the situation of the stains on different and remote parts of the dress, back and front, as well as in concealed or covered parts, may show that the defence is inconsistent with the facts; but, in the large majority, a medical witness will be pressed to state whether the blood is or is not human. It has been already observed that there are no *chemical* differences between the blood of man and animals. The red colouring matter, the albumen, and the fibrin are the same, and chemical tests produce on them precisely similar results. Thus, neither the guaiacum process nor spectrum analysis will enable us to distinguish human from animal blood. These methods of research simply allow us to speak to the presence or absence of the red colouring matter of blood; but on the question whether the blood has been taken from a human being, or from any warm or cold-blooded animal, they throw no light. The microscope alone, in the present state of science, can assist the inquirer in solving this question, and only under certain conditions. The microscope shows physical differences in reference to the shape of the blood-corpuscles in animals of different classes; and in reference to *size* in animals of the same class. 1. In respect to *shape*. In all animals with red blood, the corpuscles have a disk-like or flattened form. (See fig. 111, 112, p. 571.) In the mammalia, excepting the camel tribe, the outline of the disk is *circular*. In this tribe, and in birds, fishes, and reptiles, the corpuscles have the form of a lengthened ellipse or *oval*. In the three last-mentioned classes of animals they have a central nucleus, which gives to them an apparent prominence in the centre. The blood-corpuscles of all the mammalia, including those of the camel-tribe, have no central nucleus, and they appear depressed in the centre.

The microscope, therefore, enables an observer to distinguish the blood of birds, fishes, and reptiles, from that of a human being; and this may be of great importance as evidence. In *Reg.* v. *Drory* (Essex Lent Ass. 1851), it was suggested in the defence, that the blood-stains on the clothes of the prisoner had been caused by his having killed some chickens. The shape of the corpuscles negatived this part of the defence. In another case, the blood was alleged to be that of a fish; this was also disproved by the shape. Bennet on one occasion was called to see a patient who was spitting florid blood. On examining the sputum with a microscope, he found that the coloured blood-corpuscles were those of a bird. On his telling the patient that she had mixed a bird's blood with the expectoration, she was astounded, and confessed that she had done so for the purpose of imposition. ('The Microscope as a Means of Diagnosis,' p. 185.)

The chief microscopical distinction between the *blood of man and domestic animals*, consists in a minute difference in the *size* of the corpuscles. This, however, is only an average difference; for the corpuscles are found of different sizes in the blood of the same animal. In making use of this criterion, it would be necessary to rely upon the size of the majority of the corpuscles seen in a given area, and under the same power of the microscope. Their size bears no relation to the size of the animal. Thus, in the horse, ox, ass, cat, mouse, pig, and bat, they are, on an average, nearly of the same size; the difference is so slight as to be practically inappreciable. In these animals they are smaller than in man and in several of the mammalia. The corpuscles in man, the dog, the rabbit, and the hare, are of nearly the same size. In the blood of the sheep and goat, they are smaller than in other mammalia. The size of the corpuscle bears no proportion to the age of the animal: thus in the blood of the human fœtus they are found to be as large as in that of the adult.


The measured diameter of the corpuscles in *human blood* varies, according to Gulliver, from 1-2000th to 1-4000th of an inch (0·00050—0.00025 inch), the average size in both sexes being 1-3200th (0·00031) of

an inch. In fresh human blood the author found the average diameter of the corpuscles to be the 1-3500th (0·00029) of an inch, the maximum size being 1-3000th (0·00033), and the minimum 1-5000th (0·00020) of an inch. The corpuscles of human blood are larger than those of domestic animals. The subjoined measurements, in fractions of an inch, are those given by Gulliver, excepting those given in italics, which are from the author's own observations. The average diameter is, in the dog 1-3540th (0·00029)—*maximum 1-4000th (0·00025)*, *minimum 1-6000th (0·00017)*; in the hare, 1-3607th (0·00028)—*max. 1-2000th (0·00050)*, *min. 1-8000th (0·00012)*, *average 1-4000th (0·00025)*; *in the rabbit, 1-4000th (0·00025)*; in the mouse, 1-3814th (0·00023); in the ass, 1-4000th (0·00025); in the pig, 1-4230th (0·00022), which accords with *the author's measurements, 1-4250th*; in the ox, 1-4267th (0·00022); *in the cow, 1-4000th (0·00025) to 1-4200th (0·00022)*; in the cat, 1-4400th (0·00023); in the horse, 1-4600th (0·00022), *or 1-5000th (0·00020)*; in the sheep, 1-5300th (0.00019), *or 1-5333rd to 1-6000th (0·00019 to 0·00016)*; in the goat, 1-6366th (0·00016). These measurements apply to *recent* blood, which has not been allowed to become dry on animal and vegetable stuffs. In this case a distinction might be made between the blood of a human being and a sheep or goat. With respect to the dog, hare, and rabbit, it would be, even under these favourable circumstances, a matter of some difficulty. When blood is dried on clothing, and it is necessary to extract the corpuscles by means of a liquid of a different nature from the serum, we cannot rely on slight fractional differences, since we cannot be sure that the corpuscles, after having been once dried, will ever reacquire in foreign liquid the exact size which they had in serum. (See 'Guy's Hosp. Rep.' vol. 7, pt. 2, 1851.)

The illustrations figs. 118, 119, represent, in the dry state, the blood-corpuscles of twelve animals—ten taken from the mammalia, or warm-blooded sucking animals—one from a bird, and one from a reptile. All are represented under the same magnifying power in quadrants of circles, so as to allow of a comparison.


On comparing the ten samples of mammalian blood in these illustrations, with that representing human blood (in fig. 114, 115, p. 572) prepared under precisely similar circumstances and magnified in the same degree, it will be perceived that the only difference consists in the human corpuscles being somewhat larger. The difference in size, however, from the corpuscles

Fig. 118.



Blood-corpuscles, magnified 319 diameters.
a. Of the dog. *b.* Of the mouse.
c. Of the rabbit. *d.* Of the ass.

Fig. 119.




Blood-corpuscles, magnified 319 diameters.
a. Of the cow. *b.* Of the pig.
c. Of the ox. *d.* Of the cat.

the dog and the rabbit is so small as to be scarcely appreciable. The corpuscles of the bird and the reptile are well characterized by their size,

the oval shape, and the presence of a nucleus in the centre of each. The length of the corpuscle of the fowl's blood, was found by measurement to be the 1-2250th part of an inch, and its width the 1-4500th of an inch. The length of the corpuscles in the salamander was the 1-750th of an inch. and the width the 1-1125th of an inch. In reference to the scientific question proposed, it must be regarded as still unsolved. There are no *certain* methods of distinguishing, microscopically or chemically, the blood of a human being from that of an animal, when it has been once dried on an article of clothing, notwithstanding statements to the contrary.

Fig. 120.



Blood-corpuscles, magnified 319 diameters.
a. Of the horse.
b. Of the sheep.
c. Of the common fowl.
d. Of the salamander.

The extent to which a medical witness is justified in going on trials for murder, on which this important question frequently arises, appears to be this: the size and shape of the corpuscles are or are not consistent with their being the corpuscles of human blood; but it is impossible, in the present state of science, to affirm that the corpuscles extracted from stains dried on clothing or weapons are not those of some domestic animal belonging to the class mammalia. This was the substance of the evidence which the author gave in the case of *Reg.* v. *Munro* (Cumberland Lent Ass. 1855)—a case in which everything turned on circumstantial evidence of a medical and moral kind. He declined to say absolutely that the stains were caused by human blood, although the corpuscles coincided in measurement with them. In one instance a medical witness professed to make a distinction between certain spots on a man's clothes—assigning some to the blood of a horse, and others to human blood; and on another occasion scientific evidence was so strained by a witness upon this question as to elicit a sharp rebuke from the judge who tried the case. (*Reg.* v. *Nation*, Taunton Spring Ass. 1857, see p. 536; also 'Med. Times and Gaz.' April 11, 1857, p. 365.) Evidence based upon such varying averages as those above given must be treated as speculative and unsafe.

Blood Crystals. Hæmatin.—Another process for the microscopical detection of blood consists in procuring crystal from the dry red colouring matter of blood. Lehmann and Kunze ascertained that all red blood is capable of crystallization or of breaking up into crystalline forms, from whatever animal or organ it may have been taken. A drop of blood which has been kept a day is allowed to evaporate on a glass slide; a drop of distilled water is then added, and the whole is covered with a slip of thin glass. After a time, when the water has to some extent evaporated, regular red-coloured crystals, of various sizes and forms, such as those represented in the quadrant *a* of fig. 121, are visible. Some are columnar and prismatic, while others are in the form of rhombic plates. The second quadrant, *b*, represents the crystals procured, by a similar process, from the heart-blood of a cat. The third, *c*, crystals from the venous blood of a guinea-pig, which appear in regular tetrahedra; and the fourth, *d*, crystals from the venous blood of a squirrel; some of which are prismatic, and others in the form of rhombic

Fig. 121.



Blood-crystals.

xahedral plates. The crystals are represented in this and the other rings as transparent. They are, in fact, translucent, and under a ight, of a well-marked red or red-brown colour.

Fig. 122.




Blood-crystals.

fig. 122 the first quadrant, *a*, shows risms and rhombic plates obtained by ann from human venous blood; *b*, blood- ls from human blood in rhombic plates, neated by Robin and Verdeil ('Chimie mique'), and *c*, crystals obtained from ı blood, by Kunze, by a process de- l below. Some of these have a ic form; others are shaped like a hemp- and a few, being double at one ex- y, have the appearance of a swallow's In the quadrant *d* are represented ls as obtained by Lehmann from the ood of a fish. It is to be observed of crystals that they are all coloured, having more or less the red of the blood.

applying Lehmann's process to a fragment of a dried clot of human which had been kept for six months, prismatic crystals were seen, with bodies of an ovoid shape. A number of these are delineated in ıgraving fig. 123. They have the characters of the phosphates ther salts of the blood. No rhombic , or tetrahedra, such as those described ehmann, were seen. The prismatic ls had the characters of triple magnesium ıate. They were colourless on a red l.


Fig. 123.



Blood-crystals.

e production of crystals from the colour- atter of blood, as contained in a dry um, may be effected by evaporating to s a fragment of the blood-clot or stained with an excess of glacial acetic acid. id liquid is poured off, and a particle of n salt may then be added; more acetic nd the evaporation repeated. The e is examined by a microscopical power of 300 to 500 diameters. lood-crystals, if present, appear in groups, as small dark specks. re somewhat irregular in shape—have lly a prismatic form, some with rhombic ations, while others assume a spindle and others again are joined at an so as to resemble a bird's tail, or they ach other like the letter X. Hæmin- s, from human blood, were found to n average length of 1-2250th of an and a width of 1-9000th of an inch. obtained from sheep's blood were than those obtained from the blood ı and of the bullock. A fragment of bullock's blood, which had been on for about six years, gave, when ly treated, the group of red-coloured s seen in *b*, fig. 124; and blood of the sheep, of old date, gave the form *c*. The crystals in the latter are smaller than those produced from

Fig. 124.




Hæmin-crystals, magnified 517 diameters.

human and bullock's blood, but the resemblance is so great, that it would be obviously impossible to base any distinction between human and animal blood upon these observations.

Gwosdew adopts another method, which embraces the use of the spectroscope, as well as the production of crystals. The dry clot is treated with alcohol and carbonate of potash. The red colour is extracted, and this gives a single band in the spectroscope between *C* and *D* on the spectrum. The colouring matter is thrown down by dilution with water and the addition of acetic acid. To procure crystals the precipitate is dried, mixed with common salt and glacial acetic acid, and evaporated at 212° F. ('Ueber die Darstellung der Hämin,' 1866.) By Gwosdew's method three distinct processes for the detection of blood may be thus applied to the colouring matter extracted from a small stain. The colouring matter of blood so treated may be converted into quasi-crystalline forms, still preserving its red colour; and microscopical evidence of blood may be thus obtained, in cases in which the blood-corpuscles have not been successfully extracted by liquids. A very small quantity of dry coagulum will suffice to yield this corroborative evidence.

Fig. 125.



Hæmin-crystals, as obtained from human blood (Neumann).

Bug and flea spots differ in appearance from blood. The residue is free from fibrin and from blood-corpuscles. For further information on the subject of blood-stains, the reader is referred to the following works:—'Blutkrystalle Untersuchungen,' von W. Preyer, Jena, 1871; Neumann, 'Erkennung des Blutes,' Leipzig, 1869; 'Ann. d'Hyg.' 1865, 1, 139; 1868, 1, 130; 1870, 2, 432; Henke's 'Zeitschrift der S. A.' 1844, b. 2, p. 273; 'Guy's Hosp. Rep.' 1851; 1867, p. 432; 1870, p. 274; Casper's 'Vierteljahrsschrift,' 1862, vol. 1, pp. 15, 250, 256; 1863, vol. 2, p. 193; 1867, 1, 354; 'Chemical News,' 1868, p. 124; 'Lond. Med. Rec.' 1882, p. 83; and 'Pharm. Jour.' xii. p. 586.

CHAPTER 40.

IMPUTED OR SELF-INFLICTED WOUNDS—MOTIVES FOR THEIR PRODUCTION—MEDICO-LEGAL INVESTIGATION OF THESE CASES.

Imputed or self-inflicted Wounds.—The question whether a wound was or was not self-inflicted, may refer to the living as well as to the dead. Thus, a man may produce wounds upon himself for the purpose of simulating a homicidal assault, which, for various motives, he may allege to have been committed upon him. With the motives for the self-infliction of wounds, a medical jurist is not concerned—it is of the fact only that he can take cognizance. One of the most remarkable cases of this kind which have occurred in England, was that of *Bolam*, who was tried for the murder of a man named Millie, at the Newcastle Autumn Assizes, 1839. Bolam was found lying in an apartment which had been fired by himself, or, as he alleged, by some incendiary, and near him was the body of the deceased, who had evidently been killed by violence—the skull having been extensively

ractured by a poker lying near. The prisoner, when found, was either nsensible or pretended to be so. He stated that he had been suddenly ttacked by a man, and knocked down by a blow on the right temple. fter attempting to escape, he was again knocked down. He then felt a nife at his throat, but admitted that he did not put up his hands to rotect it. His hands were not cut. He said he remembered receiving ome blows on his body, but he became insensible, and recollected nothing nore. On examining his throat, there was a wound an inch and a half in ength on the left side of the neck, a quarter of an inch below the jaw. It ad penetrated nearly through the true skin, and was of inconsiderable xtent. A small quantity of blood, which had flowed down on the inside of is cravat, had escaped from this wound. There were many cuts on his oat at the back and sides, through his waistcoat, shirt, and flannel-shirt; ut there were no corresponding cuts or stabs, nor, indeed, any mark of njury upon the skin. The question was whether these wounds were nflicted by the unknown person, who was alleged to have fired the premises nd murdered the deceased, or whether the prisoner had inflicted them on imself, in order to divert attention, and conceal the crime which he was ccused of having committed. No motive for the imputed crime was dis-overed: but the medical facts relative to the self-infliction of wounds were o strong, that he was convicted of manslaughter. There was no doubt hat the prisoner had produced the wounds upon himself in order to remove he suspicion that he had caused the death of the deceased. They were uperficial, involved no important organs, and bore the characters which hose wounds only would have, which had not been produced with a uicidal intention.

Soon after Bolam's case, one somewhat similar occurred in London. The steward of a club-house was found one morning in bed wounded, and he cash-box of the club was missing. Circumstances led the police to uspect that no one could have broken into the house; but the man him-elf was considered so trustworthy, that no suspicion was entertained of is having been concerned in the robbery. Bransby Cooper, who xamined him, found the wounds on his person of a trivial character; and here was no doubt, from what subsequently transpired, that he had pro-uced them on himself, for the purpose of averting suspicion.

It is not always easy to trace a motive for the production of these njuries; and when a reasonable motive is not immediately discovered, ersons are apt to be misled and to credit the story. When a person ttending to commit suicide fails in the attempt, he has sometimes, under sense of shame, attributed the infliction of a wound in his throat to nother; but facts of this kind may without difficulty be cleared up by ircumstantial evidence. Imputed wounds, if we except the case of an actual ttempt at suicide, in which the injury is commonly severe, are generally f a *superficial* character, consisting of cuts or incisions not extending elow the true skin; deep stabs are seldom resorted to where the purpose i not suicide, but merely to conceal other crimes. Further, these wounds re in *front* of the person, and may be on the right or left side, according) whether the person is right or left-handed. They have also been enerally *numerous*, and widely scattered; sometimes they have had a mplete parallelism, unlike those which must have been inflicted by an dversary during a mortal conflict with a weapon. The *hands* are seldom ounded, although in the resistance to real homicidal attempts, these parts mmonly suffer most severely. The injuries are not usually situated over ose parts of the body in which wounds are by common repute considered *ortal*, and there is in general an entire want of correspondence between e situation of the wounds on the person, and the cuts or other marks on

the *dress;* or the cuts in the dress are not reconcilable with the articles of dress having been worn when they were produced. Facts of this kind require special attention. In a case which occurred to Marc, a young man alleged that he had received a sword-cut on the forehead from some assailants who had escaped. He stated that he wore at the time a handkerchief round his head, a cotton cap, and a common cap with an elastic front, which he alleged had been cut through. There was a longitudinal wound, quite superficial and about an inch long, at the upper and right part of the frontal bone, passing downwards from *left to right*. The cut in the felt of the cap, which was very soft, passed obliquely from *right to left*, and was about three inches in length. The cut was not so clean or regular as if it had been produced by a sword; there was very little blood upon the cap, and only on the edge of the incision. The silk handkerchief was cut in an irregular manner. When the person was requested to place the cap and other articles upon his head in the position in which he stated they were when he was attacked, it was found to be impossible to adjust them so as to make the incisions correspond, and the cap could not be worn over the folded handkerchief. This rendered it certain that the wound had not been inflicted in the manner described. Besides, a blow of a sword which would have divided the felt and silk handkerchief, would at the same time have produced a much deeper wound on the forehead than that which was found. In a case reported by Bayard, the falsehood of a similar charge was demonstrated by the want of correspondence between the cuts in the clothes and those found on the person. ('Ann. d'Hyg.' 1847, 2, 222. See also case of *Wiggins*, p. 520.) In comparing cuts on the *dress* with wounds on the person, there are several circumstances to be attended to. What articles of dress were worn at the time of the assault? In a case of stabbing all ought to present marks of perforation, corresponding in direction, form, size, sharpness of the edges of the weapon, &c. In imputed wounds the marks on several layers of dress may not correspond with each other in the characters above mentioned. It is very difficult for a man simulating such injuries so to arrange his clothes when off his person, as to deceive a careful examiner. There will be some inconsistency or want of adjustment. Apart from the fact that several stabs or cuts cannot exist on the same part of the clothes, without one or more being stained with blood on the outside or inside, an impostor may either do too much or too little, and thus lead to his detection. (Case of *Wiggins*, p. 520.) In a case of alleged arson to defraud a fire insurance company, which excited much public discussion in London many years since, a simple circumstance led to the inference that certain stabs or cuts through a shirt had not been produced while the shirt was on, but while it was off the body. There were two cuts in the shirt near to each other, precisely similar in size, form, and direction; in fact, the knife or dagger producing them must have gone through a fold of the shirt to produce them, so accurate was the correspondence. Then, however, it followed that the shirt could not have been upon the body of the wounded person as he alleged, because a stab through a shirt when worn over the skin must, in order to reach the body, traverse not only a fold (producing two cuts), but another layer in contact with the skin, and thus produce *three cuts*, or in the event of traversing two folds, *five cuts*. In simulating the wounds by cuts on the shirt, the person is supposed to have forgotten this, and have merely stabbed a fold of the shirt while lying on a table, or in some situation convenient for the purpose. This, among other facts, rendered it probable that the slight wounds on the chest were self-inflicted. A case occurred at Nottingham in 1872, which shows how persons who inflict wounds and at the same time cut the dress covering the wounded

part, may furnish evidence against themselves. A youth charged a man with unlawfully wounding him on the highway. He stated that the man had stabbed him in the arm, cutting through his shirt and coat-sleeve. There was no attempt at robbery, and no motive for such an act. On examining the coat and shirt-sleeve, it was found that they had been cut, but there was no corresponding cut in the lining of the coat-sleeve. The prosecutor could give no explanation of this. It was clear that the charge was false, that there had been no cutting or stabbing by another, but that the wound was self-inflicted, when the coat was not worn.

It has been contended that no rules can be laid down for the detection of such cases; each must be decided by the facts which accompany it. Nevertheless, the details of those above mentioned will serve to direct the inquiries of a practitioner. The facts which he must endeavour to ascertain are the following:—1. The relative positions of the assailant and the assailed person at the time of the alleged attack. 2. The situation, direction, and depth of the wound or wounds. 3. The situation or direction of marks of blood or wounds on the person or dress of either, or of both the assailant and assailed. 4. The marks of blood, and the quantity effused at the spot where the mortal struggle is alleged to have taken place. The importance of these inquiries cannot be over-estimated. A strong suspicion was raised against the late Duke of Cumberland, in the year 1810, in reference to the death of *Sellis*, when a proper examination of the wounds on the deceased would have shown that they might have been self-inflicted.

Imputed wounds are generally *cuts* or *stabs*. They are seldom of the contused kind: the impostor cannot, in reference to contusions, so easily calculate upon the amount of mischief which is likely to ensue. Bergeret, however, has related some cases in which females labouring under hysterical attacks have inflicted upon themselves severe contusions, and have charged innocent persons with attempts to murder. ('Ann. d'Hyg.' 1863, 1, 463.) In general the inconsistency of the story is so palpable as to betray the imposture at once. The case of *M. Armand*, a merchant of Montpellier, who was tried at the Assizes at Aix, in March, 1864, for an alleged murderous assault upon his servant, Maurice Roux, shows the readiness with which inconsistent stories are sometimes accepted by the public. This case was rather one of imputed homicidal strangulation than imputed wounding; nevertheless a foundation was laid for medical opinions by the presence, as it was alleged, of a slight excoriation of the skin on the nape of the neck. The injury was so slight that it escaped the observation of some medical men who examined the complainant, and there could be no doubt from the facts that it had been produced either accidentally or designedly by the complainant on himself. Several medical gentlemen, taking the man's story as true, asserted without any qualification, 1. That a blow on the nape of the neck might produce cerebral concussion and syncope. 2. That a blow to produce such effects need not be violent; and 3. That such a blow so inflicted would not always leave upon the skin marks of contusion or ecchymosis. These admissions were taken by the Court to support the man's story—that his master struck a severe blow on the back of his neck; and this had produced concussion of the brain, and that he had been rendered insensible for many hours. ('Ann. d'Hyg.' 1864, 1, 451.) The evidence for the defence, and chiefly that given by Tardieu, removed the effect produced by such loose medical answers as these, and satisfied the jury that the statement of the complainant was a pure fabrication. The accused was justly acquitted of the charge. Although it has been elsewhere stated that severe blows are not always attended with external marks *of violence* (p. 496), it by no means follows that such

blows have been struck in all cases in which the skin presents a slight abrasion.

Pistol-shot wounds are sometimes voluntarily inflicted for the purpose of imputing murder, or extorting charity. A man intending to commit suicide by fire-arms, and failing in the attempt, may also from shame or a desire to conceal his act, attribute the wound to the hand of an assassin. In examining such imputed wounds they will not be found to involve vital parts, except in cases of attempted suicide, and they will possess all the characters of near-wounds produced by gunpowder, wadding, or a bullet. (See GUN-SHOT WOUNDS.) The skin around will be more or less lacerated and bruised; there will be much ecchymosis, and the hand holding the weapon, as well as the dress and the wounded skin, may be blackened or burnt by the exploded gunpowder. A pistol-shot wound from an assassin may be produced from a distance, while an imputed wound which is produced by a person on himself must always partake of the characters of a near-wound. If the weapon has been charged with gun-cotton, there will be no marks of blackening on the person or dress, but there may be marks of burning.

CHAPTER 41.

THE CAUSE OF DEATH IN WOUNDS—CAUTION ON ASSIGNING TOO MANY CAUSES—WOUNDS DIRECTLY OR INDIRECTLY FATAL—DEATH FROM HÆMORRHAGE—AMOUNT OF LOSS OF BLOOD PROVING FATAL—MODIFIED BY AGE AND OTHER CIRCUMSTANCES—FATAL WOUNDS OF SMALL ARTERIES—INTERNAL HÆMORRHAGE—DEATH FROM MECHANICAL INJURY TO A VITAL ORGAN—DEATH FROM SHOCK—BLOWS ON THE ABDOMEN—FLAGELLATION—DEATH FROM NUMEROUS INJURIES WITHOUT ANY MORTAL WOUND.

Cause of Death.—It is important for a medical witness to bear in mind that in all cases of wounds criminally inflicted, the cause of death must be reasonably *certain*. No man ought to be convicted upon mere medical probability. In general, there is only *one* real cause of death, although other circumstances may have assisted in bringing about a fatal result. Hence it is our duty, when several apparent causes for death exist, to determine which was the *real* cause; and in stating it to the Court, to be prepared to offer our reasons for this opinion. In most cases of local injury, when a person dies speedily, there will be no great trouble in settling whether disease or the wound was the cause. A difficulty may, however, exist when a person has recovered from the first effects of a wound, and has subsequently died. Besides, there may be cases in which the cause of death, in spite of the most careful deliberation, will be still obscure; or sometimes it may happen that the death of a person appears to be as much dependent on bodily disease as on an injury proved to have been received at the time he was labouring under disease. How is an opinion to be expressed in such a case? The course which a medical witness ought to pursue, provided he has duly deliberated on the circumstances before he appears in court, and his mind is equally balanced between the two causes, is to state at once his doubt to the jury without circumlocution, and not allow it to be extracted from him in cross-examination. Occasionally many causes of death are assigned by a witness, and in a case of this kind an acquittal is commonly directed.

Wounds directly or indirectly fatal.—A wound may cause death either *directly* or *indirectly*. A wound operates as a *direct cause of death* when

the wounded person dies either immediately, or very soon after its infliction; and there is no other cause, internally or externally, to account for death. In wounds which cause death *indirectly*, it is assumed that the deceased survives for a certain period, and that the wound is followed by inflammation, pyæmia, tetanus, or some other mortal disease, which is a direct, and not an unusual consequence of the injury. Under this head may be also arranged all those cases which prove fatal by reason of surgical operations rendered imperatively necessary for the treatment of injuries—presuming that these operations have been performed with ordinary skill and care. We shall for the present consider only the direct causes of death in cases of wounds. They are three in number:—1. *Hæmorrhage*, or loss of blood. 2. *Great mechanical injury* done to an organ important to life. 3. *Shock*, or concussion, affecting the brain or spinal marrow, whereby the functions of one or more vital organs are arrested, sometimes with but slight injury to the part struck or wounded. From either of these causes, a wounded person may die immediately or within a few minutes.

1. *Death from hæmorrhage*—Loss of blood operates by producing fatal syncope (p. 163). A quantity of blood escaping from a vessel, although insufficient to cause death by affecting the heart and circulation, may readily destroy life by disturbing the functions of the organ or part into which it is effused. Thus, a small quantity effused in or upon the substance of the brain, or at its base, may prove fatal by inducing fatal compression; and again, if, in a case of wounded throat, blood should flow into the windpipe, it may cause death by asphyxia—*i.e.* by stopping the respiratory process (p. 164). In these cases it is obvious that the blood acts mechanically; and in respect to the last condition, a medical man, unless circumspection is used, may involve himself in a charge of malapraxis. In wounds of the chest, involving the heart and lungs, death is frequently due not so much to the actual quantity of blood effused, as to the pressure which it produces upon these organs. A few ounces effused into the bag of the heart (pericardial sac), will entirely arrest the action of this organ. ('Friedreich's Blätter f. Gerichtl. Med.' 1882, p. 163.)

The absolute *quantity of blood* required to be lost in order to prove fatal, will, of course, vary according to numerous circumstances. The young, the aged, they who are labouring under infirmity or disease, will perish sooner from loss of blood than others who are healthy and vigorous. Females, cæteris paribus, are more speedily destroyed by bleeding than males. Infants are liable to die from this cause, as a result of slight wounds. An infant has been known to bleed to death from the bite of a single leech, or from the simple operation of lancing the gums. Even the healthy and vigorous, when their vital powers have been depressed by maltreatment or by brutal violence, will sink under the loss of a comparatively small quantity of blood. (See 'Watson on Homicide,' p. 90.) A medical jurist must not forget that some persons have a predisposition to excessive bleeding from slight injuries; and this condition is often hereditary. The slightest wound or puncture—the bite of a leech or the extraction of a tooth—will be attended with a loss of blood which cannot be arrested, and which will slowly lead to death by exhaustion. Cases have been frequently recorded of fatal hæmorrhage following the extraction of teeth, when there had been previously nothing to indicate the probable occurrence of death from so trivial a cause. (For striking instances of this remarkable tendency to hæmorrhage in a family, see 'Brit. and For. Med. Rev.' vol. 17, p. 247; also, 'Med. Gaz.' May, 1842.) In the thirty-ninth volume of the latter journal, p. 86, a case is reported, in which an unusual *degree of bleeding* followed a compound fracture of the leg

Such cases are detected without difficulty; since a surgeon may always infer, from the part injured and the extent of the injury, whether the bleeding is likely to be copious or not. When a person bleeds to death from what would, under common circumstances, be a simple wound, the admission of this fact may in certain cases lessen the responsibility of an accused person.

A *sudden loss* of blood has a much more serious effect than the same quantity lost slowly. A person may fall into a fatal syncope from a quantity of blood lost in a few seconds, which he would have been able to bear without sinking had it escaped slowly. This is the reason why the wound of an artery proves so much more rapidly fatal than that of a vein. Death speedily follows the wound of a large artery like the carotid; but it takes place with equal certainty, although more slowly, from wounds of smaller arteries. In a case in which one of the intercostal arteries was wounded by a small shot, hæmorrhage caused death in thirty-eight hours (see *post*). The loss of blood which follows the division of the smaller branches of the external carotid artery, is often sufficient to destroy life, unless timely assistance be rendered. A case was tried (Berkshire Spring Ass. 1832), in which it was proved that the prisoner had killed his wife by stabbing her in the leg; a small artery (the anterior tibial) was divided, and the woman died from hæmorrhage half an hour afterwards. Wounds of arteries, even smaller than these, might in some subjects prove fatal, if no assistance were at hand. Watson mentions a case in which the internal mammary artery on the left side was divided by a stab in the chest. The woman died on the ninth day, and four pounds of blood were found effused on that side. In another case in which an intercostal artery was divided, six pounds of blood were effused. ('Watson on Homicide,' p. 101.) In both cases, as in most wounds of the chest, the blood not only affected the system by its loss, but by its compressing the lungs and impeding respiration. Wounds of large veins, such as the jugular, may, from the quantity of blood suddenly lost, speedily destroy life. If a wound is in a vascular part, although no vessel of any importance be divided, the person may die from bleeding. It is difficult to say what quantity of blood should be lost, in order that a wound may prove fatal. The whole quantity contained in the body of an adult is calculated at about one-thirteenth of its weight—*i.e.* about twelve pounds. According to Watson, the loss of from five to eight pounds is sufficient to prove fatal to adults. But while this may be near the truth, many persons will die from a much smaller quantity; the *rapidity* with which the effusion takes place having a considerable influence.

Internal hæmorrhage.—Hæmorrhage may prove fatal, although the blood does not visibly escape from the body. In incised wounds, the flow externally is commonly abundant; but in contused, punctured, and gunshot wounds, the effusion may take place internally and rapidly cause death. In severe contusions or contused wounds, involving highly vascular parts, the effusion may go on to an extent to prove fatal, either in the cavities of the body or throughout the cellular membrane and parts adjacent: many pounds of blood may thus be slowly or rapidly effused. The most fatal internal hæmorrhages are those which follow ruptures of the organs from violence or disease. Ruptures of the heart, lungs, liver, and kidneys, have thus caused death. In 1864, a man who had been run over was brought to Guy's Hospital. He complained of pain in the back, but there were no symptoms of severe injury, and no marks of violence were seen on the skin of the back. He left the [redacted] with some assistance to his house. A few ho[redacted] in bed. On inspection there was p[redacted] abdomen. This had

proceeded from one kidney, which had been ruptured transversely through its whole substance. In these cases the hæmorrhage is not immediate. Slight muscular exertion may accelerate it and cause death. In death from severe flagellation, blood may be effused in large quantity beneath the skin and among the muscles; this effusion will operate as fatally as if it had flowed from an open wound.

The means of ascertaining whether a person has died from bleeding by an open wound are these:—Unless the wound is situated in a vascular part we shall find the vessel or vessels from which the blood has issued, divided —the neighbouring vessels empty, and the body more or less pallid; although this last condition is of course liable to be met with in certain cases of disease, as also under copious venesection—points easily determined by an examination. The blood will commonly be found more or less clotted or coagulated on those surfaces on which it has fallen. If, with these signs, there is an absence of disease likely to prove rapidly fatal, and no other probable cause of death is apparent, it may be fairly referred to loss of blood. This opinion may, however, be materially modified in reference to open wounds, by the fact of the body not being seen on the spot where the injury was actually inflicted—by the wound having been sponged—the blood removed by washing, and all traces of bleeding destroyed. Under these circumstances, the case must in a great measure be made out by presumptive proof; and here a medical witness may have the duty thrown upon him of examining articles of dress, furniture, or weapons, for marks or stains of blood.

It must not be supposed that all the blood met with round a wounded dead body, or in a cavity of the body, was actually effused during life. As soon as the heart's action ceases, the arteries pour out no more; but the blood, so long as it remains liquid, *i.e.* from four to eight or ten hours, and the warmth of the body is retained, continues to drain from the divided vessels. The quantity thus lost, however, is not considerable, unless the veins implicated are large, or the part is highly vascular, *i.e.* full of small vessels. In wounds involving the great vessels of the neck the blood which drains from the wounded part after death may be large.

2. *Death from great mechanical injury done to a vital organ.*—We have instances of this becoming a direct cause of death in the crushing of the heart, lungs, or brain, by any heavy body passing over or falling on the cavities, as in railway accidents. The severe mechanical injury is sometimes accompanied by a considerable effusion of blood, so that the person really dies from hæmorrhage; but in other instances the quantity of blood lost is inconsiderable, and the fatal effects may be referred to shock. Sometimes a slight amount of violence may prove fatal. These are, however, to be regarded as exceptional instances. (See 'Med. Times and Gaz.' Aug. 1854.)

3. *Death from shock.*—This is sometimes a direct cause of death under the infliction of external violence; and in this case life is destroyed without the injury being to all appearance sufficient to account for so speedily fatal a result. Savory has suggested that death from shock is nothing more than death from temporary exhaustion of nerve-force, the result of a violent, sudden, and excessive expenditure of it. ('Lect. on Life and Death,' p. 171.) Whatever theory may be adopted to explain it, there is no doubt that a person may die from what is termed shock, without any marks of severe injury being discovered on his body after death. We have examples of this mode of death in accidents from lightning, or from severe burns or scalds, in which the local injury is often far from sufficient to explain the rapidly fatal consequences. As instances of this form of death from violence, may be also cited those cases in which a person has been

suddenly killed by a blow upon the upper part of the abdomen or on the pit of the stomach, which is supposed to operate by producing a fatal impression on the nerves and nerve-ganglia. Whether this be or be not the true explanation, it is admitted that a person may die from so simple a cause without any mark of a bruise externally, or physical injury internally, to account for death. On the skin there may be some abrasion or slight discoloration; but as it has been elsewhere stated (p. 496), these are neither constant nor necessary accompaniments of a blow. ('Med. Gaz.' vol. 44, p. 213.) Convictions for manslaughter have taken place, when death has been produced under these circumstances. ('Travers on Constitut. Irritation,' p. 432; and Bransby Cooper's 'Lect. on Surgery,' p. 443; Wounds of the Abdomen, *post;* 'Watson on Homicide,' p. 75.) Concussion of the brain, unattended by visible mechanical injury, furnishes another example of this kind of death. A man receives a severe blow on the head; he falls dead on the spot, or becomes senseless and dies in a few hours. On an inspection, there may be merely the mark of a slight bruise on the scalp; in the brain there may be no rupture of vessels or laceration of substance, and all the other organs of the body are found healthy. In certain railway accidents persons have died under somewhat similar circumstances. There has been no physical indication of a mortal injury, and no cause apparent to account for death. This can be referred only to the shock or violent impression which the nervous system has sustained from the blow or violence. A medical witness must give his evidence with caution in such cases; since it is the custom to rely in the defence upon the absence of any visible *mortal* wound or physical injury to account for death, as a proof that no injury was done. A trial took place (Liverpool Aut. Ass. 1837), wherein several persons were charged with the manslaughter of the deceased, by kicking him behind the right ear. The medical witness deposed that there was in this spot the mark of a severe bruise, but there was no injury whatever to the brain, and the body was otherwise healthy. He very properly ascribed death to the violent shock given to the nervous system, and the Court admitted that the cause of death was satisfactorily made out. The person who inflicted the wound was convicted.

There is another form of shock, which is of some importance in medical jurisprudence. A person may have received *many injuries*, as by blows or stripes, not one of which, taken alone, could, in medical language, be termed mortal; and yet he may die directly from the effects of the violence, either on the spot, or very soon afterwards. In the absence of any large effusion of blood beneath the skin, death is commonly referred to exhaustion, but this is only another mode of expression; the exhaustion is itself dependent on a fatal influence or impression produced on the nervous system. A prize-fighter, after having during many rounds sustained numerous blows on the body, may, either at or after the fight, sink and die exhausted. His body may present marks of bruises, or even lacerated wounds, but there may be no internal changes to account for death. In common language, there is not a single injury which can be termed *mortal*; and yet, supposing him to have had good health previously to the fight, and all marks of disease indicative of sudden death to be absent, it is impossible not to refer his death to the direct effect of the violence. It is a well-ascertained medical fact, that a number of injuries, each comparatively slight, are as capable of operating fatally as any single wound whereby some blood-vessel or organ important to life is directly affected. Age, sex, constitution, and a previous state of health or disease, may accelerate or retard the fatal consequences.

A case of a somewhat similar kind may present itself in the punishment

of flagellation, which is occasionally followed by death, either as a direct consequence of shock, or from indirect causes, such as inflammation and its consequences. At the trial of *Governor Wall*, the judge directed the jury that the long continuance and severity of pain (in flagellation) may be productive of as fatal consequences as if instruments or weapons of a destructive kind were used. It is not often that scholastic flagellation is a cause of death in this country. One case, however, which excited public attention from the atrocity of the circumstances attending it, was the subject of a trial for manslaughter (*Reg.* v. *Hopley*, Lewes Aut. Ass. 1860). The evidence showed that the prisoner had beaten a youth of sixteen most severely for nearly two hours with a rope and stick. The external wounds were slight, but an inspection showed that the muscles as well as all the soft parts beneath the skin had been considerably bruised and lacerated, and that there were extensive effusions of blood in the cellular membrane of the arms and legs. There was no mortal wound in the common sense of the term, but there was no reasonable doubt that the boy had died from the violence inflicted on him by the prisoner. His guilt was established by the fact that he had endeavoured to conceal the effects of his violence by removing the marks of blood—that he had covered the body of the deceased with clothing so as to conceal the bruises—that he had procured a coroner's inquest to be held in haste, and, while concealing from the jury the fact that he had beaten the youth on the night of his death, stated that he had found him dead, and suggested that he might have died of disease of the heart. There can be no doubt that the youth died either while the prisoner was inflicting the violence or soon afterwards. No attempt was made to dispute the cause of death. Apart from the depressing effects on the nervous system of long-continued and severe pain, there was, in this instance, such an effusion of blood internally as would account for the production of fatal syncope.

On a trial for murder, which took place in Germany, it was proved that the deceased had been attacked with sticks, and that he had been afterwards flogged on the back with willow switches. He died in about an hour. On inspection, there was no mortal wound, nor any injury to a vital organ; there were simply the marks of lacerations and bruises on the skin, apparently not sufficient to account for death; but this was, nevertheless, very properly ascribed to the violence. (Henke, 'Zeitschr. der S. A.' 1836; also 'Brit. and For. Med. Rev.' Jan. 1837, p. 249.) The case of the *Duchess of Praslin*, who was murdered by her husband in Paris, in 1847, furnishes an additional proof of the fatal effect produced by numerous injuries. On an inspection of the body, it was found that on the head, neck, and both of the hands, there were no fewer than *thirty* distinct wounds, some contused, and others incised and punctured. There were also the marks of many bruises, and the impressions produced by the nails of the assailant's hand over the mouth. For the most part these injuries were slight, and not one could be said to be necessarily mortal. The most serious wound was situated on the right side of the neck; but even here the carotid artery and internal jugular vein had escaped injury. Death was referred to the loss of blood which had taken place from the numerous wounds inflicted during the struggle with the assassin. ('Ann. d'Hyg.' 1847, 2, 377.) From these considerations, it cannot be expected that in every case of death from violence or maltreatment, there must be some specific and visible *mortal injury* to account for that event. When the circumstances accompanying death are unknown, a medical opinion should be expressed with caution; but if we are informed that the deceased was in ordinary *health and vigour* previous to the infliction of the violence,

and there is no morbid cause to account for his *sudden* illness and death, there is no reason why we should hesitate in referring death to the effects of a number of injuries. Among non-professional persons a prejudice exists that no person can die from violence unless there be some distinctly *mortal* wound actually inflicted on the body; *i.e.* a *visible* mechanical injury to some organ or blood-vessel important to life. This is an erroneous notion, since death may take place from the disturbance of the functions of an organ important to life without this being necessarily accompanied by a perceptible alteration of structure.

It is sometimes a difficult question to decide on the relative degree of mortality of several wounds, and on the share which they have had respectively in causing death. (See p. 591.) By a wound being of itself *mortal*, we are to understand that it is capable of causing death directly or indirectly, in spite of the best medical assistance. It is presumed that the body is healthy, and that no cause has intervened to bring about or even accelerate a fatal result. The circumstance of a person labouring under disease when wounded in a vital part, will not, of course, throw any doubt upon the fact of such a wound being necessarily mortal, and of its having caused death. If there should be more wounds than one, it is easy to say, from the nature of the parts involved, which was likely to have led to a fatal result. In order to determine, on medical grounds, whether a wound was or was not mortal, we may propose to ourselves this question: Would the deceased have been likely to die at the same time, and under the same circumstances, had he not received the wound? There can obviously be no general rule for determining the mortal nature of wounds. Each case must be judged by the circumstances which attend it. The *effect* of the wound, and the *intent* with which it was inflicted, are looked to: its anatomical relations, which must depend on pure accident, are never interpreted in the prisoner's favour. Some extenuation may, perhaps, be occasionally admitted when a wound proves mortal through an indirect cause, as inflammation or fever, and medical advice was obtainable, but not obtained until every hope of recovery had disappeared. It appears, however, from the case of the *Queen* v. *Thomas and others* (Gloucester Aut. Ass. 1841), that the mere neglect to call in medical assistance is not allowed in law to be a mitigatory circumstance in the event of death ensuing. The deceased died from the effects of a severe injury to the head, inflicted by the prisoners, but had had no medical assistance. The judge said it was possible that, 'if he had had medical advice, he might not have died; but whoever did a wrongful act must take the whole consequences of it. It never could make any difference whether the party injured had or had not the means or the mind to apply for medical advice.' The prisoners were convicted. According to Lord Hale, if a man be wounded, and the wound, although not in itself mortal, turn to a gangrene or fever for want of proper applications, or from neglect, and the man die of gangrene or fever, this is homicide in the aggressor; for though the fever or gangrene be the immediate cause of death, yet the wound being the cause of the gangrene or fever is held the cause of death, *causa causati*. These nice questions relative to the shades of responsibility for personal injuries, occasionally arise in cases in which persons have been wounded at sea on board of a ship in which there was no surgeon.

CHAPTER 42.

DEATH OF WOUNDED PERSONS FROM NATURAL CAUSES—DISTINCTION BETWEEN REAL AND APPARENT CAUSE—DEATH FROM WOUNDS OR LATENT DISEASE—ACCELERATING CAUSES—WHICH OF TWO WOUNDS CAUSED DEATH?—DEATH FOLLOWING SLIGHT PERSONAL INJURIES.

Death of wounded persons from natural causes.—It is by no means unusual for individuals who have received a wound, or sustained some personal injury, to die from latent natural causes; and as, in the minds of non-professional persons, death may appear to be a direct result of the injury, the case can only be cleared up by the assistance of a medical practitioner. Such a coincidence has been witnessed in many instances of attempted suicide. A man has inflicted a severe wound on himself while labouring under disease; or some morbid change, tending to destroy life, has occurred subsequently to the infliction of a wound, and death has followed. Without a careful examination of the body, it is impossible to refer death to the real cause. The importance of an accurate discrimination in a case in which wounds or personal injuries have been caused by another, must be obvious. A hasty opinion may involve the accused in a charge of manslaughter; and although it might be possible to show on the trial that death was probably attributable not to the wound, but to coexisting disease, yet it must be remembered, that the evidence of a surgeon before a coroner or magistrate may be the means of causing the person charged, to be imprisoned for some months previously to the trial. In 'Guy's Hosp. Rep.' 1850, p. 230, will be found two cases in which death from natural causes was wrongly assigned to violence. In one case ('Lancet,' Feb. 15, 1845, p. 185), the deceased, a boy, died from an internal strangulation of the intestine from morbid causes, after wrestling with another boy, who might, but for a careful inspection of the body, have been erroneously charged with having caused his death. (For a similar case, see 'Med. Gaz.' vol. 37, p. 702; also Casper's 'Wochenschrift,' May 24, 1845.)

Deaths from wounds or latent disease.—A natural cause of death may be lurking within the body at the time that a wound is criminally inflicted, and a close attention to the symptoms preceding and the appearances after death can alone enable a surgeon to distinguish the real cause. A man may be severely wounded, and yet death may take place from rupture of the heart, the bursting of an aneurism, from apoplexy, phthisis, or other morbid causes which it is here unnecessary to specify. ('Cormack's Ed. Jour.' May, 1846, p. 343.) If death can be clearly traced to any one of these diseases, the prisoner cannot be convicted of manslaughter; for the medical witness may give his opinion that death would have taken place about the same time and under the same circumstances whether the wound had been inflicted or not. The case of *Colonel Gordon* proves that very slight causes may lead to death, when there is latent disease of the heart or any other important organ. This case was the subject of a trial at the Chester Lent Assizes, 1854 (*Reg.* v. *Sandars*). It appeared from the evidence, that the accused, who was the conductor of a railway train in which the deceased was travelling, attempted to eject him from a carriage. The deceased resisted, and in the struggle the prisoner struck him on the left arm. The deceased made no further resistance, but sat quietly in his seat. It was soon afterwards perceived that he was dead. The medical evidence showed that there was ossification of the valves of the heart and aorta, that this disease had been of long standing, that the life of the

deceased was at all times in great peril, and that his death might have arisen from the excitement which took place previous to the prisoner laying hands upon him. As it was thus admitted that excitement alone would account for the fatal result, the prisoner was acquitted. There was no *corporeal* injury done to the deceased which could account for death. In 1867, a woman, æt. 73, was charged with causing the death of a pauper, by striking her on the cheek. The deceased became insensible, and died in ten minutes. On inspection, it was found that death had been caused by the rupture of an aneurism of the aorta. The medical opinion was that, although the blow was not of itself sufficient to cause death, it had accelerated a fatal result of the disease.

In another case, which was the subject of a trial (*Reg.* v. *Champlonier*, C. C. C. June, 1854), appearances sufficient to account for death existed in the part which sustained the violence; but the medical witness could not with certainty refer them to the violence. An old man passing along a road was struck on the forehead with a stone thrown by the prisoner. The surgeon stated that there was a contused wound, and that his nose bled profusely. The bleeding was arrested, and on the following day he considered the deceased to be out of danger. At a later period of the day, however, the deceased was seized with an apoplectic fit, from which he did not recover. The appearances in the brain were quite sufficient to account for death; but he could not undertake to say that the injury by the stone had in any way produced these appearances. Upon this evidence the supposed connection of the death with the violence was at once set aside as too remote, and the prisoner was discharged.

On these occasions, one of the following questions may arise:—Was the death of the person *accelerated* by the wound, or was the disease under which he was labouring so aggravated by the wound as to produce a more speedily fatal termination? The answer to either of these questions must depend on the circumstances of each case, and the witness's ability to draw a proper conclusion from these circumstances. The maliciously accelerating of the death of another already labouring under disease by an act of unlawful wounding is criminal; for in a legal sense that which accelerates, causes. In *Reg.* v. *Timms* (Oxford Lent Ass. 1870), it was proved that the prisoner had struck deceased some blows on the head with a hatchet. In twelve days, under treatment, he had partly recovered from the effects, but in six weeks afterwards he was seized with inflammation of the brain with convulsions, and died. On inspection, disease of the kidneys was found, of which there had been no symptoms. Death was referred to this disease, and inflammation of the brain as the result of the blows. The judge directed the jury, that if they believed the blows conduced in part to the death of the deceased, it was manslaughter, notwithstanding that other causes combined with the blows to account for death. The prisoner was convicted.

Lord Hale, in remarking upon the necessity of proving that the *act* of a prisoner caused the death of a person, says:—'It is necessary that the death should have been occasioned by some corporeal injury done to the party by force, or by poison, or by some mechanical means which occasion death; for although a person may, *in foro conscientiæ*, be as guilty of murder by working on the passions or fears of another, and as certainly occasion death by such means, as if he had used a sword or pistol for the purpose, he is not the object of temporal punishment.' (I. 247.) Several acquittals have taken place in cases in which the deaths of parties have been occasioned by terror, or dread of impending danger, produced by acts of violence on the part of the prisoners; not, however, giving rise to bodily injury in the deceased. Conformably to Lord Hale's view, the Criminal

nmissioners, in their report on the subject of homicide, state :—
The law takes no cognizance of homicide unless death result from
jury occasioned by some act or *unlawful omission*, as contradis-
ed from death occasioned by an influence on the mind, or by any
occasioned from such influence.' 'Art. 2. The terms "unlawful
ı" comprehend every case where any one being under legal obliga-
ıpply food, clothing, or other aid and support, or to do any other
nake any other provision for the sustentation of life, is guilty of
ach of such duty.' Under the statute (1 Vict. c. 85, s. 2) it
from the following case that physical injury only is intended. In
Grey (Huntingdon Lent Ass. 1857), the prisoner was indicted for
a bodily injury dangerous to life—to wit, a congestion of the lungs
ırt, with intent to murder. It appeared that she had exposed her
cold and wet, and that congestion or inflammation of the lungs
ɜsult of such exposure. Erle, J., held that the statute under which
ictment was laid contemplated the infliction of some wound or
njury to the person. The woman was found guilty; but the point
been reserved, the conviction was quashed by the Court for Crown
eserved, on the ground that, looking to the other offences provided
his statute, this case did not come within it. In *Reg* v. *Percival*
d Circ. March, 1857), a man was charged with the manslaughter
leceased by causing his death by fright, *i.e.* by personating a ghost.
dence showed that the boy had sustained no physical injury, but
received a shock from which he did not recover. Wightman, J.,
at in his view the case would fall within the definition of man-
er. Under the 14 and 15 Vict. c. 100, the necessity for tracing
ɔ some *corporeal* injury appears to be practically abolished. Accord-
he fourth section, in any further indictment for murder or man-
er it shall not be necessary to set forth the *manner* or the *means* by
he death of the deceased was caused.

ich of two wounds caused death.—It is possible that a man may
two wounds at different times, and from different persons, and die
ceiving the second: in such a case, the course of justice may require
medical witness should state which wound was the cause of death.
. 588.) Let us take the following illustration :—A man receives
a quarrel a gunshot wound in the shoulder. He is going on well
prospect of recovery, when in another quarrel he receives a severe
ting wound in the chest or abdomen from another person, and after
ıg under the effects of these wounds for a longer or shorter period,
. If the gunshot wound was clearly shown to have been the cause
h, the second prisoner could not be convicted of manslaughter: or
ıtab were evidently the cause of death, the first prisoner would be
ed on a similar charge. It might be possible for a surgeon to decide
estion summarily, when, for instance, death speedily followed the
wound; and on inspection of the body, the heart or a large vessel is
ɾred to have been penetrated; or, on the other hand, extensive slough-
ıfficient to account for death, might take place from the gunshot
, and on inspection, the stab might be found to be of a slight nature,
ıt involving any vital parts. In either of these cases, all would
. upon the judgment of the medical practitioner; his evidence would
mportant that no correct decision could be arrived at without it; he
be, in fact, called upon substantially to distinguish the guilty from
ıocent. On some occasions death may appear to be equally a con-
ce of either or both of the wounds; in which case, probably both
would be liable to a charge of manslaughter. (See 'Ann. d'Hyg.'
2, 432.) The second wound, which is here supposed to have been

the act of another, may be inflicted by a wounded person on himself, in an attempt at suicide, or it may have had an accidental origin. The witness would then have to determine whether the wounded person died from the wound inflicted by himself or from that which he had previously received. (See *Tetanus*, p. 603.)

It may happen that the wounded person has taken *poison*, and has actually died from its effects, and not from the injuries or maltreatment. Again, a wounded person may have been the subject of subsequent ill-treatment, and the question will arise—to which of the two causes his death was really due. It is to be observed of these cases, that the supervening disease, the poison, or the subsequent ill-treatment, should be of such a nature as to account for *sudden or rapid death;* since it would be no answer to a charge of death from violence, to say that there were marks of chronic disease in the body, unless it was of such a nature as to account for the sudden destruction of life under the symptoms which actually preceded death. In the medical jurisprudence of wounds there is probably no question which so frequently presents itself as this: it is admitted that the violence was inflicted, but it is asserted that death was due to some other cause, and the onus of proof lies on the medical evidence. Among numerous cases which have occurred in England during twenty years, the author found that the *latent causes of death* in wounded persons were chiefly inflammation of the thoracic or abdominal viscera, apoplexy, diseases of the heart and large blood-vessels, phthisis, ruptures of the stomach and bowels from disease, internal strangulation, and the rupture of deep-seated abscesses. In some of these cases the person was in a good state of health up to the time of the violence, and in others there was a slight indisposition. The history was nearly the same in all: it was only by careful conduct on the part of the medical witnesses that the true cause of death was ascertained.

Death following slight personal injuries.—An imputation has occasionally been thrown on the master of a school, when a boy has died soon after he has been punished in an ordinary way, and when there has been no suggestion that an undue amount of violence was used. In such cases there has been commonly some unhealthy state of the body to explain the result. When the disease which gives rise to doubt is seated in a part which is remote from that which sustained the violence, all that is required is, that the examination of the body should be conducted with ordinary care. If the disease should happen to be in the part injured (the head or chest), the case is more perplexing. The difficulty can then be removed only by attentively considering the ordinary consequences of such injuries. The violence may have been too slight to account for the diseased appearance; and the disease itself, although situated in the part injured, may be regarded as an unusual consequence of such an injury. On the other hand, the presence of chronic disease will form no exculpation of acts of violence of this nature. In *Reg.* v. *Hopley* (p. 587), there was chronic disease of long standing in the brain of deceased, who was of defective intellect, but it was proved that he was quite well and suffered from no unusual symptoms up to the time that a violent flogging was inflicted, and that this was followed by death in less than three hours from the commencement of the violence. It was not here a question even of acceleration, for the deceased might have lived for years in spite of the existence of this chronic disease.

In some cases slight blows have been followed by fatal consequences, even when no disease existed to account for the result.

The following cases furnish additional illustrations of death after slight personal injuries, in which the medico-legal question requiring solution was simply, whether the death was a sequence or consequence of the violence:—

r was struck two blows on the face, but it did not appear that they very severe. The boy went to his work on the following day, but lained of pain in his head: he continued to work for two days, when ıs seized with such severe pain that he was obliged to keep to his He became worse, and died fourteen days after the injury. A e inspection of the body was made, but the only morbid appearance was a small tumour on the outer membrane of the brain, corre- ing to the posterior face of the petrous portion of the right temporal This satisfactorily accounted for death; but the examiners very rly denied that it had proceeded from the violence, because—1, the ır had evidently been for a long time forming, and many months) he was struck, the deceased had complained of his head; 2, it was bable that the slight blows had, under any circumstances, given) the formation of this deep-seated fungous excrescence. (Henke, schrift der S. A.' 1837.) A case illustrative of these singular dences was the subject of a criminal trial in the United States in A man was stabbed by his wife, and he died in about ten minutes. s supposed that the deceased had died from his wounds, which con- of two stabs on the right arm, and one in the region of the stomach; he prisoner, who believed that she had caused her husband's death, harged with the murder. From the medical evidence given at the it appeared that there was a large quantity of blood effused in the nen, and that the weapon had only perforated the stomach, without ng any considerable blood-vessel to account for such copious hæmor- . It was found that this had proceeded from the rupture of an ism of the aorta, the walls of which were so much thinned that the excitement was, in the opinion of the witness, sufficient to cause cident. The aneurismal tumour was out of the reach of the knife, ı had not penetrated in the direction in which it was lying. The ss admitted that wounds of the stomach were always dangerous, but udden death was not a usual consequence of a slight puncture. The ıer was acquitted. In other instances the case may be of a very ful character. A good illustration of this will be found in a case l. Gaz.' vol. 20, p. 503), where a boy died apparently from the ; of a blow on the side; and after death, peritonitis, ulceration of the s, an aperture in the diaphragm, and gangrene of the lungs were . The following case, related by Morgagni, is remarkable in this of view. An old man was caught in the act of robbing an orchard: empted to escape, but while running away the owner struck him a on the back. The old man went on a few yards, and then fell dead. ıspecting the body, there were no external marks of violence. There large effusion of blood in the chest, which was traced to a rupture) aorta, probably from the vessel being in an aneurismal state. The appeared to have been slight, and would probably have produced no ous consequences in a healthy person. (Barzellotti, 'Questioni di ina Legale.')

CHAPTER 43.

WOUNDS INDIRECTLY FATAL—DEATH FROM WOUNDS AFTER LONG PERIODS—SECONDARY CAUSES OF DEATH—THE CAUSE UNAVOIDABLE—THE CAUSE AVOIDABLE BY GOOD MEDICAL TREATMENT—COMPARATIVE SKILL IN TREATMENT—CAUSE AVOIDABLE BUT FOR IMPRUDENCE ON THE PART OF THE WOUNDED PERSON—ABNORMAL OR UNHEALTHY STATE OF THE BODY—ACCELERATION OF DEATH.

Wounds indirectly fatal.—Certain kinds of injuries are not immediately followed by serious consequences, but a wounded person may die after a longer or shorter period, and his death may be as much a consequence of the injury as if it had taken place on the spot. The aggressor is as responsible as if the deceased had been directly killed by his violence, provided the fatal result can be traced to the usual and probable consequences of the injury. Wounds of the head are especially liable to cause death insidiously,—the wounded person may in the first instance recover,—he may appear to be going on well, when, without any obvious cause, he will suddenly expire. In general an examination of the body will suffice to determine whether death is to be ascribed to the wound or not. In severe injuries affecting the spinal marrow, death is not an immediate consequence, unless that part of the organ which is above the origin of the phrenic nerves (supplying the diaphragm) is wounded. Injuries affecting the lower portion of the spinal column do not commonly prove fatal until after some days or weeks; but the symptoms manifested by the patient during life, as well as the appearances observed in the body after death, will sufficiently connect the injury with that event. Death may follow a wound, and be a consequence of that wound, at almost any period after its infliction. It is necessary, however, in order to maintain a charge of homicide that death should be strictly and clearly traceable to the injury, and not be dependent on any other cause. A doubt on this point must, of course, lead to an acquittal of the accused.

Death from wounds after long periods.—Many cases might be quoted in illustration of the length of time which may elapse before death takes place from certain kinds of injuries,—the injured person having ultimately fallen a victim to their indirect consequences. A case is related by Astley Cooper, of a man who died from the effects of an injury to the head received about *two years* previously. The connection of death with the wound was clearly made out by the continuance of the symptoms of cerebral disturbance during the long period which he survived. Another case is mentioned by Hoffbauer, in which a person died from the effects of concussion of the brain as the result of an injury received eleven years before. ('Ueber die Kopfverletzungen,' 1842, p. 57.) A man received a musket-shot in the left side of the chest, and the ball remained lodged in the left lung during a period of *twenty-five years*. The ball, in penetrating, had fractured the humerus at its neck, in consequence of which the upper extremity had been amputated at the shoulder-joint. The wound of the chest soon healed, but the patient remained during life subject to fits of suffocation and hæmoptysis, under the effects of which he at length sank. On an examination of his body, the ball was found lying behind the third intercostal space in the midst of the pulmonary tissue, but lodged in a kind of cyst which communicated with the large air-tubes. In one case a person died fifty years after the receipt of a wound. ('Lancet,' Jan. 16, 1847.) Alison quotes several cases in which persons have been found guilty of homicide—the injured persons having died from the indirect

esults of the wounds after the lapse of three and five months, and longer. 'Criminal Law,' p. 151.) In the case of *Mr. Smith* who was shot by *Bois Touchet*, July, 1844, death did not take place until after the lapse of leven months from the time at which the wound was inflicted. In 1839, boy was admitted into Guy's Hospital for an injury to the spine, which roved fatal only after the lapse of eleven months. Among reported edico-legal cases, the *longest* interval at which a conviction has taken ace from indirectly fatal consequences, was *nine months*. (*Reg.* v. *Valus*, evizes Sum. Ass. 1847.) It was proved that the prisoner had maltreated e deceased in Sept. 1846. After this she suffered in her health, and in ec. she was found labouring under phthisis. She died of the disease in e following May. Two medical men deposed that three ribs had been oken on the left side—and the injury had evidently not been attended . They thought that the irritation caused by the fracture in Sept. ight have led to the development of phthisis, although the seeds of the sease might have been long lurking in the system. The judge left it the jury as a question depending on medical evidence, and they had consider whether the consumption was caused, or the death of the ceased hastened, by the violence of the prisoner. They returned a rdict of guilty.

It is the law that when a person dies from a wound, the assailant shall t be adjudged guilty of homicide, unless death takes place *within a year d a day* after the infliction of the wound. ('Archbold,' p. 345.) In actice, the existence of this rule is usually of little importance. Most unds leading to death generally destroy life within two or three months ter their infliction: sometimes the person does not die for five or six onths, and, in more rare instances, death does not ensue until after the pse of twelve months, or even several years. These protracted cases cur especially in respect to injuries of the head and chest. A man was mitted into the Edinburgh Infirmary, labouring under vomiting and ficulty of breathing, with severe pain on the left side of his chest. e died in four hours, and on inspection it was found that part of the ge intestines (colon) and the omentum had passed into the chest ough an aperture in the diaphragm. There was a cicatrix in the scle with which the intestine was incorporated, showing that the ury was of very old date. The man had died from phrenic, or diaragmatic hernia, and it turned out that he had received a wound ut *fifteen months* previously, in the lower part of the left side of the st, with a shoemaker's knife. This took place during a quarrel with a man with whom he cohabited, but she was liberated on his apparent overy. It seems that he had been attacked with severe pain in the lomen (ileus), and had been in the infirmary on two different occasions sequently to the wound, but had been dismissed each time apparently ed. (Reid's 'Physiol. Researches,' p. 523.) There was no doubt, hough more than a year and a day had elapsed, that the stab was irectly the cause of the man's death. In *Reg.* v. *Hynes* (Winchester m. Ass. 1860), it was proved that the prisoner had inflicted severe unds on the head of the deceased, and that death took place two months erwards. The medical witnesses were perfectly agreed that death was used by an abscess in the brain as a result of these wounds. The y had great difficulty in finding a verdict of guilty, because in their nion too long a time had elapsed for the injuries to have been the cause death.

Secondary causes of death.—A person who recovers from the immediate ects of a wound may die from fever, inflammation or its consequences, emia, erysipelas, delirium tremens, tetanus, or gangrene; or an opera-

tion required during the treatment of a wound may prove fatal. These are what may be called secondary causes of death, or secondary consequences of a wound. The power of deciding on the responsibility of an accused person for an event which depends only in an indirect manner on an injury originally inflicted by him, rests of course with the authorities of the law. But it is impossible that they can decide so difficult and nice a question in the absence of satisfactory medical evidence; and on the other hand, it is right that a medical witness should fully understand the importance of the duty here required of him. *Surgical fever* or *erysipelas* may follow many kinds of serious wounds, and in some few instances be distinctly traceable to them; but in others, the constitution of a person may be so broken by dissipated habits as to render fatal a wound which in a healthy subject might have run through its course mildly, and have healed. When the fever or erysipelas can be traced to a wound, or there is no other apparent cause of aggravation to which either of these disordered states of the body can be attributed, they can scarcely be regarded by a medical practitioner as unexpected and unusual consequences, especially when the injury is extensive, and seated in certain parts of the body, as in the scalp. If death takes place under these circumstances, the prisoner will be held as much responsible for the result as if the wound had proved directly mortal. This principle has been frequently admitted by our law, and, indeed, were it otherwise, many reckless offenders would escape, and many lives would be sacrificed with impunity. It is, however, difficult to lay down general rules upon a subject which is liable to vary in its relations in every case; but when a wound is not serious, and the secondary cause of death is evidently due to constitutional peculiarities from acquired habits of dissipation, the ends of justice are probably fully answered by an acquittal; in fact, such cases do not often pass beyond a coroner's inquest.

The secondary causes of death may be arranged under the following heads:—

1. *The cause is unavoidable.*—Of this kind are tetanus following laceration of tendinous and nervous structures; erysipelas following lacerated wounds of the scalp; peritoneal inflammation following blows on the abdomen with or without rupture of the bladder or intestines, and effusion of their contents; strangulation of the intestines (phrenic hernia), following rupture or wounds of the diaphragm, and others of a like nature. Here, supposing proper medical treatment and regimen to have been pursued, the secondary cause of death was unavoidable, and the fatal result certain.

2. *The cause avoidable by good medical treatment.*—There are many kinds of wounds which, if properly treated in the first instance, may be healed and the patient recover, but when improperly treated they prove fatal. In the latter case, it will be a question for a witness to determine how far the treatment aggravated the effects of the violence, and from his answer to this, the jury may have to decide on the degree of criminality which attaches to a prisoner. For instance, an ignorant person has removed a clot of blood, which sealed up the extremity of a blood-vessel, in consequence of which fatal bleeding has ensued, or he has caused death by unnecessarily interfering with a penetrating wound of the chest or abdomen. It would not be just to hold the aggressor responsible, since, but for the gross ignorance and unskilfulness of his attendant, the wounded person might have recovered from the effects of the wound. When death is really traceable to the negligence or unskilfulness of a surgeon who is called to attend on a wounded person, this circumstance ought to be, and commonly is, admitted in mitigation, supposing that the wound was not

originally of a mortal nature. Lord Hale drew a very nice distinction between death as it results from a wound rendered mortal by improper treatment, and death as it results from improper treatment, irrespective of the wound. In the majority of cases such a distinction could scarcely be established, except upon speculative grounds, and in no case, probably, would there be any accordance in the opinions of medical witnesses. In slight and unimportant wounds, it might not be difficult to distinguish the effects resulting from bad treatment from those connected with the wound, but there can be few cases of severe injury to the person, wherein a distinction of this nature could be safely made; and the probability is, that no conviction for murder would now take place, if the medical evidence showed that the injury was not originally mortal, but only became so by unskilful or improper treatment. In such a case, it would be impossible to ascribe death to the wound, or to its usual or probable consequences (see below).

3. *Comparative skill in treatment.*—If death has been caused by a wound, it signifies not that, under more favourable circumstances, and with *more skilful treatment*, a fatal result might have been averted. As an illustration, the following case, reported by Alison, may be quoted:—The prisoner was one of a party of smugglers who fired at an officer of excise. The wounded man was carried to the nearest village, where he was attended by a surgeon of the country, who was not deficient in attention. A great collection of matter formed in the leg, fever ensued, and the patient died at the end of three weeks. In defence, it was urged that by *skilful* treatment the man might have recovered; but the Court held that it was incumbent to prove that death arose *ex malo regimine*. The true distinction in all such cases is, that if the death was evidently occasioned by grossly erroneous medical treatment, the original author of the violence will not be answerable; but if it arise from the want merely of the higher skill which can be commanded only in great towns, he will be responsible, because he has wilfully exposed the deceased to a risk from which he had practically no means of escaping. ('Crim. Law of Scotland,' p. 150.) In the case of *Macewan* (Perth, Sept. Circ. 1830), the prisoner was indicted for the manslaughter of a boy, by striking him a blow on the shoulder, which dislocated the arm. Two days after the blow, an ignorant bone-setter was consulted, and owing to his manipulations inflammation took place, and the boy being of a sickly and scrofulous habit, this proved fatal. The prisoner was acquitted. In charging the grand jury, in reference to *Mr. Seton's* case (Winchester Aut. Ass. 1845), Platt, B., is reported to have observed, that if a man inflict a wound likely to produce death, and the wounded party should fall into the hands of an unskilful practitioner, whereby death was hastened, the aggressor would still be responsible for the result. If the wound had not been likely to produce death, but by unskilful treatment death ensued, then that would not be murder. A man in a quarrel received a bite on his thumb. He went to a quack, who applied some irritating ointment, which led to severe inflammation, and this rendered amputation of the arm necessary. He died from the effects of the operation. There was evidence that the original injury was slight, and would probably have healed but for the improper applications. On this evidence the prisoner was acquitted. (*Reg.* v. *Kingshott*, Lewes Sum. Ass. 1858.)

It will be obvious that a serious responsibility is thrown on practitioners who undertake the management of cases of criminal wounding. Any deviation from common practice should therefore be made with the greatest caution, since novelties in practice will, in the event of a fatal result, form one of the best grounds of defence. On these occasions every point connected with *the surgical* treatment will be the subject of rigorous

inquiry and professional criticism. In the case of a severe lacerated wound in the hand or foot followed by fatal tetanus, it may be said that the wounded person would not have died had amputation been at once performed. In this instance, however, a practitioner may justify himself by showing either that the injury was too slight to require amputation, or that the health or other circumstances connected with the deceased would not allow of its being performed with any reasonable hope of success. On the other hand, if the practitioner performed amputation, and the patient died, then it might be urged that the operation was premature, unjustifiable, and that it had caused death. Here the surgeon is bound to show that the operation was necessary, according to the ordinary rules of practice. The treatment of severe incised wounds of the throat, when the windpipe is involved, sometimes places a practitioner in an embarrassing position. If the wound is left open, death may take place from bleeding; if it be prematurely closed, blood may be effused into the windpipe and cause death by suffocation.

The following case occurred a few years since in London:—A man inflicted a transverse wound on his throat; it was about four inches in length, and passed across the middle of the larynx. The bleeding was not considerable, as the carotid arteries had escaped being wounded. The external orifice had, in the first instance, been closed, and the patient was almost suffocated, partly by the occurrence of emphysema, and partly by the blood flowing into the windpipe. On opening the wound the patient's breathing was relieved, and a quantity of mucus mixed with blood was thrown out at each expiration. After waiting some time, the pieces of divided cartilage were brought together by sutures, and the wound carefully closed. In a short time the breathing became difficult, the countenance livid, and the man died, apparently suffocated. In 1841, a woman was found in bed one morning with her throat severely cut, and a man was charged with the crime of murder. The wound had divided the wind-pipe and the superficial vessels. Although medical assistance was called in, it appears that nothing was done to arrest the bleeding for three-quarters of an hour. The wound was then closed by ligatures, and the woman died immediately —most probably from suffocation. The accused was tried and acquitted. because it appeared that this was an act of suicide. The first object of the surgeon, in all such cases, is to save life; therefore the bleeding should be immediately arrested by securing the divided vessels. When this is done, the wound may be closed, but if the closure takes place before this, death from suffocation will commonly follow.

4. *The cause avoidable but for imprudence or neglect on the part of the wounded person.*—A man who has been severely wounded in a quarrel may obstinately refuse medical assistance, or he may insist upon taking exercise, or using an improper diet, contrary to the advice of his medical attendant; or, by other imprudent practices, he may thwart the best conceived plans for his recovery. Let us take a common case as an illustration. A man receives a blow on the head in a pugilistic combat, from the first effects of which he recovers, but after having received surgical assistance he indulges in excessive drinking, and dies. The aggressor is tried on a charge of manslaughter, and found guilty. Death under these circumstances is commonly attributed by the medical witness to effusion of blood on the brain; but it cannot be denied that the excitement produced by intoxicating liquors will sometimes satisfactorily account for the fatal symptoms. In the case which we are here supposing, such an admission might be made, and the prisoner receive the benefit of it; for the imprudence or negligence of a wounded person ought not, morally speaking, to be considered as adding weight to the offence of the aggressor. If the symptoms were from the first

ifavourable, or the wound likely to prove mortal, circumstances of this kind uld not be received in mitigation. Judges are at all times unwilling admit them. In the case of the notorious *Governor Wall*, who was con-ted for causing the death of a man by excessive punishment, it was empted to be shown in evidence that the deceased had destroyed nself by the immoderate use of spirits while under treatment in the spital. The Lord Chief Baron, in charging the jury, observed that no n was authorized to place another in so perilous a predicament as to ke the preservation of his life depend merely on his own prudence. e more clearly the medical witness is able to trace death to imprudence excess on the part of the deceased, in the case of a *slight* wound, the re obviously would the responsibility of a prisoner be diminished; and nce the necessity for attending carefully to the progress of a wound, nich, if it prove fatal, may involve another in a criminal charge. In e case of *Christian Paterson* (1823), referred to by Alison (op. cit. 147), it appeared in evidence that the deceased was struck on the head th a smoothing-iron, which fractured her skull; some days afterwards e drank a quantity of whisky, and was ultimately taken to the Royal firmary, where erysipelas shortly appeared in the wound, of which she ed. Under these circumstances the charge of murder was abandoned, d the accused was found guilty of assault. The legal responsibility of e assailant is the same, whether the deceased die on the spot, or some ys, weeks, or months afterwards, unless it can be distinctly proved that s death was immediately connected with the imprudence or excess of nich he was guilty, and wholly independent of the wound. But although prisoner should be found guilty of manslaughter under these circum-nces, the punishment is so adjusted by our law as to leave a consider-le discretionary power in the hands of a judge. The neglect to call in medical practitioner, or the refusal to receive medical advice, will not, wever, according to the decision in *Reg.* v. *Thomas* (Gloucester Aut. s. 1841), be considered as a mitigatory circumstance in favour of the soner, even although the wound was susceptible of being cured. A man y receive a lacerated wound of a limb, followed by tetanus or gangrene, d thus proving fatal; he may decline receiving medical advice, or stinately refuse amputation, although proposed by his medical attendant. is would not operate as a mitigatory circumstance on the part of an ailant, because a wounded person is not compelled to call for medical istance, or to submit to an operation, and a medical witness could not ays be in a condition to swear that the operation would have saved life; he can merely affirm that it might have afforded him a better nce of recovery. In the case of *The Queen* v. *Hulme* (Liverpool Aut. s. 1843), it was proved that the deceased had died from tetanus used by an injury to a finger some time before. Amputation was ised by the surgeon, but the deceased would not consent to the ration. The prisoner was convicted of manslaughter, and sentenced the severest punishment prescribed by the law for that crime. In the e of *Mackenzie* (1827), the prisoner seized his victim by the throat, l bruised him severely in several parts of the body, in consequence which fatal tetanus supervened. Skilful medical advice was not led in until near the end of the illness, when tetanus had already ne on, and in the interval deceased had acted imprudently and had gravated the symptoms. The medical evidence proved that the tetanus s owing to the injury, and was a frequent result of it. The prisoner, der the direction of the Court, was convicted. Again, a person may eive a blow on the head, producing fracture, with great depression bone, and symptoms of compression of the brain: a surgeon may

propose an operation to elevate or remove the depressed bone, but the friends of the wounded man may not permit the operation to be performed. In such a case his line of duty will be to state the facts to the Court, and it is probable that in the event of conviction there would be some mitigation of punishment; because such an injury, if left to itself, must in general prove mortal, and no doubt could exist in the mind of any surgeon as to the absolute necessity for the operation. But the neglect or improper conduct of a person who receives a wound thus rendered fatal, does not exculpate the aggressor.

5. *The cause avoidable but for an abnormal or unhealthy state of the body of the wounded person.*—Comparatively slight wounds sometimes prove indirectly fatal, owing to the person being in an unhealthy condition at the time of their infliction; and compound fractures, or slight wounds, which in a healthy person would have a favourable termination, are followed by gangrene, fever, or erysipelas, proving fatal. Here the responsibility of an assailant for the death may become reduced, so that, although found guilty of manslaughter, a mild punishment might be inflicted. The consequence may be, medically speaking, unusual or unexpected, and, but for circumstances wholly independent of the act of the accused, would not have been likely to destroy life. In general, in the absence of malice, this appears to be the point to which the law closely looks, in order to make out the responsibility of the accused, namely, that the fatal secondary cause must be something not unusual or unexpected as a consequence of this particular injury. The medico-legal question presents itself under this form:—Would the same amount of injury have been likely to cause death in a person of ordinary health and vigour? Men who have suddenly changed their habits of living, and have passed from a full diet to abstemiousness, are sometimes unable to bear up against comparatively slight injuries, and often sink from the secondary consequences. So a man, otherwise healthy, labouring under rupture may receive a blow on the groin, attended with laceration of the intestine, gangrene, and death; another with a calculus in the kidney may be struck in the loins, and die, in consequence of the calculus perforating the blood-vessels, and causing fatal bleeding, or subsequent inflammation. Crosse reported to the Medico-Chirurgical Society the case of a boy, aged ten, who received a slight blow on the abdomen, and died in an unexpected manner on the second day after the injury. On inspection, a cyst, capable of holding ten or twelve ounces of liquid, was found connected with the under surface of the liver. The cyst had been ruptured by the blow, and its contents had escaped into the abdomen. But for the cyst existing in this situation, the blow would not have been attended with dangerous consequences. In these cases the effects of the violence must be regarded as something unexpected: it would not have produced serious mischief in an ordinarily healthy person, and hence the responsibility of an assailant becomes much diminished. The crime is undoubtedly manslaughter, but the punishment may be of a lenient description. A defence of this kind will, however, be limited by circumstances. A case is reported, in which a *Dr. Fabricius* was tried at the Old Bailey for the murder of his servant by striking her a blow behind the ear, whereby a large abscess, situated at that part, was ruptured, and this ultimately caused her death. The chief question on the trial was, whether the deceased had died from the effects of the violence, or from the disease under which she was at that time labouring. The doctor ingeniously urged in his defence that he had struck the blow merely for the purpose of opening the abscess. The jury, however, found him guilty of manslaughter. In the case of *The Queen* v. *Bell* and others (Notts Aut. Ass. 1841), it was proved that the deceased

had died from the effects of a blow received in a prize-fight, which had ruptured an abscess in the kidney, evidently of long standing. The prisoners were convicted. In the case of *Bennett* v. *Gredley* (Exch. Sittings, Hilary Term, 1854), which was a suit for compensation by reason of injuries inflicted on a boy's arm, it was argued in defence that the state of the arm was partly owing to a former injury; in reference to which the Chief Baron remarked, that a man was not bound to have his body in so sound and healthy a state as to warrant an unauthorized assault upon him. A man, therefore, who commits an unauthorized assault upon his fellow-man must take his chance of the effects which such an assault may produce. In the case of *The Queen* v. *Wallis*, for murder (Cambridge Sum. Ass. 1864), the medical evidence showed that the deceased, an aged lady, had received several wounds and bruises on her face and head, and a severe contusion on the right side of her chest. There was a fracture of the ulna near the wrist, and she had lost much blood. After lying in danger for some days her condition improved, but she again got worse, and died nineteen days after the infliction of the injuries. On inspection it was found that beneath the contusion of the chest, three ribs were broken but not displaced. There was disease of the valves of the heart of long standing, and it was proved that she had suffered from spasms in this region before the assault. The cause of death assigned by the witnesses was spasmodic seizure affecting the organs of the chest, principally the heart. The injuries which the deceased had received had lowered her system, and had rendered it less likely that she could recover from a spasmodic attack. In defence it was urged, that if in any case the cause of death be partly traceable to injuries and partly to natural or other causes, a prisoner is entitled to an acquittal. In support of this view he quoted the case of *Johnson*, from Lewis's C. C. vol. 1, p. 164. The objection was overruled by Channell, B., who held that it was bad law in the face of recent decisions. There can be no doubt, that but for the injuries inflicted, the woman would not have died; therefore, the act of the prisoner was the moving cause of her death. In cases of a mixed character this is probably the best test to determine the share which the alleged violence, when not strictly of a mortal nature, had in the death of a wounded person. By adopting such a course as was taken on this occasion, the cause will be sufficiently defined for the guidance of a jury. As a rule, cases of this description are determined by the question, whether the violence, although not the immediate, was the accelerating cause of death.

Numerous internal diseases exist, such as aneurism and various morbid affections of the heart and brain, which are liable to be rendered fatal by *slight* external violence. In *Reg.* v. *Marris* (Swansea Lent Ass. 1872), the prisoner was convicted of manslaughter under the following circumstances. He struck the deceased a blow on the side of the head, which caused him to stagger and fall. On inspection the heart was found to be in an advanced state of fatty degeneration. It was admitted by counsel for the prosecution that the blow would not of itself have produced any serious injury to a healthy man, but that in the case of the deceased it had accelerated his death, and would be likely to do so with a man suffering from heart disease. In the case of a *Mr. Wyld*, April, 1872, the evidence showed that deceased had received a blow on the head, producing a slight wound, but insufficient to cause, or even, in the opinion of the medical witness, to accelerate the death of deceased. An inspection showed that there was fatty degeneration of the heart, and that this was the sole cause of death. The law, as applied to these cases, is thus stated by Lord Hale:— It is sufficient to prove that the death of a person was accelerated by the malicious act of the prisoner, although the former laboured under a mortal

disease at the time of the act' (vol. 1, p. 428). In those cases in which a slight degree of violence has been followed by fatal consequences, it is for a jury to decide, under all the circumstances, upon the actual and specific intention of the prisoner at the time of the act which occasioned death. In most of these cases there is an absence of intention to destroy life, but the nature of the wound, as well as the means by which it was inflicted, will often suffice to develop the intention of the prisoner. An accurate description of the injury, if slight, may afford strong evidence in favour of the accused, since the law does not so much regard the means used by him to perpetrate the violence, as the actual intention to kill, or to do great bodily harm. Serious injury, causing death by secondary consequences, will admit of no exculpation when an assailant was aware, or ought to have been aware, of the condition of the person whom he struck. Thus, if a person notoriously ill, or a woman while pregnant, be maltreated, and death ensue from a secondary cause, the assailant will be held responsible; because he ought to have known that violence of any kind to a person so situated must be attended with dangerous consequences. So, if the person maltreated be an infant or a decrepit old man, or one labouring under a mortal disease, it is notorious that a comparatively slight degree of violence will destroy life in these cases, and the prisoner would properly be held responsible. (Case of *Reg.* v. *Louisa J. Taylor*, C. C. C., Dec. 1882.) A wound which *accelerates* death, *causes* death, and may therefore render the aggressor responsible for murder or manslaughter, according to the circumstances. The Commissioners appointed to define the criminal law on the subject of homicide thus express themselves:—'Art. 3. It is homicide, although the effect of the injury *be merely to accelerate the death* of one labouring under some previous injury or infirmity, or although, if timely remedies or skilful treatment had been applied, death might have been prevented.' This is conformable to the decisions of our judges. According to Lord Hale, if a man has a disease which in all likelihood would terminate his life in a short time, and another give him a wound or hurt which hastens his death, this is such a killing as constitutes murder. (Archbold, p. 345.) The case of *Reg.* v. *Murton* (Maidstone Wint. Ass. 1862) presents many points of interest in reference to the medico-legal question of the acceleration of death by violence. There was no mortal wound, and the deceased was in an unhealthy state of body. Nevertheless the prisoner was convicted of manslaughter.

6. *Abnormal conditions.*—When an assailant could not have been aware of the existence of a diseased or an abnormal condition of parts in the wounded person, the question is somewhat different. In many persons the skull is preternaturally thin, and in most persons it is so in those places corresponding to the Pacchionian bodies. In a case of this kind a moderate blow on the head might cause fracture, accompanied by effusion of blood, depression of bone, or subsequent inflammation of the brain and its membranes, any of which causes might prove fatal. In a trial involving this question (*The Queen* v. *Dowde*, Norwich Sum. Ass. 1842), the prisoner, a policeman, was charged with manslaughter. The deceased, it appears, attempted to escape from the custody of the prisoner; and the latter, in endeavouring to prevent his escape, struck the deceased a blow on the head. The deceased spoke of the blow as trifling, and, with the exception of a slight headache, he made no complaint. There was a slight cut, with a small effusion of blood. The deceased was placed in a cell, and some hours afterwards was found dead. On inspection, the skull was found fractured for an inch and a half beneath the seat of violence, and a quantity of blood had been effused and had caused death. The medical evidence on the trial was to the effect, that the blow did not appear to have been violent, that

he skull of the deceased was preternaturally thin, not being more than ne-twelfth of an inch in thickness at the fractured part. All agreed that fracture might in this case have been caused by a blow, which, under rdinary circumstances, would have been attended with no serious mischief. n some persons, all the bones of the body are unusually *brittle*, so that they re fractured by the slightest force. Inflammation, gangrene, and death ıay follow, when no considerable violence has been used; but these being nexpected consequences, and depending on an abnormal condition of parts nknown to the assailant, his responsibility may not, *cæteris paribus*, be so reat as under other circumstances. This condition of the bones can be etermined only by a medical practitioner. Facts of this kind show that he degree of violence used in an assault cannot always be measured by he effects, unless a careful examination of the injured part is previously ıade.

7. *Difficulty of proof in death from secondary causes.*—When a person is harged with having caused the death of another through violence termiating in some fatal disease, the case often admits of a skilful defence, and his in proportion to the length of time after the violence of which the leceased dies. The disease, it may be urged, is liable to appear in all ersons, even the most healthy; or it may arise from causes unconnected rith the violence. In admitting these points, it must be remembered that leath may be proved to have been indirectly a consequence of the wound y the facts: 1, that the supervention of the secondary cause, although ıot a common event, lay in the natural course of things; 2, that there did ıot exist any accidental circumstances which were likely to have given ise to this secondary cause independently of the wound. The proof of the irst point amounts to nothing, unless the evidence on the second point is onclusive.

CHAPTER 44.

'OUNDS INDIRECTLY FATAL—TETANUS FOLLOWING WOUNDS—ERYSIPELAS—PYÆMIA—DELIRIUM TREMENS—DEATH FROM SURGICAL OPERATIONS—PRIMARY AND SECONDARY CAUSES OF DEATH—UNSKILFULNESS IN OPERATIONS—NECESSITY FOR OPERATIONS—USE OF CHLOROFORM IN OPERATIONS—REFUSAL TO SUBMIT TO AN OPERATION—OPERATIONS UNDER MISTAKEN OPINIONS—FATAL DISEASES FOLLOWING OPERATIONS—CHARGES OF MALAPRAXIS.

'etanus following wounds.—This disease frequently presents itself as a :condary fatal consequence of wounds, especially of those which are cerated or contused, and affect nervous or tendinous structures. It has ften occurred as a result of slight bruises or lacerations, when the injury as so superficial as to excite no alarm; and it is a disease which may ive no warning of its appearance. Brady met with a case in which a man ipped in walking, and fell flat on his back. He was stunned, but able to alk home. He apparently recovered from this simple accident, but on ıe following day he was attacked with tetanus, and died in seventy ours. ('Lancet,' May 15, 1847, p. 516.) In the case of *Reg.* v. *Butcher* Warwick Lent Ass. 1848), it was proved that the deceased had received blow on the nose, which caused severe bleeding. In spite of good ırgical treatment, the man was attacked with tetanus on the fifteenth ıy, under which he sank. On inspection, it was found that one of the nall bones of the nose had been broken, and this had given rise to the ıtal attack. Tetanus may come on spontaneously, *i.e.* independently of

the existence of any wound on the body. Cases have been brought into the London hospitals, in which the only cause of this disease appeared to be exposure to cold or wet, or, in some instances, exposure to a current of air. ('Lancet,' Dec. 14, 1844, p. 351.) Watson met with an instance in which tetanus appeared in a severe form in a man who had received no wound, but who had been simply exposed to cold and wet. (Cormack's 'Month. Jour.' Dec. 1845, p. 902.) It has sometimes come on without any apparent cause. It is scarcely possible to distinguish, by the symptoms, tetanus from wounds (traumatic) from that rarer disease which occurs spontaneously as a result of natural causes (idiopathic). In endeavouring to connect its appearance with a particular wound or personal injury, it will be proper to observe—1, whether there were any symptoms indicative of it before the maltreatment; 2, whether any probable cause could have intervened to produce it, between the time of its appearance and the time at which the violence was inflicted; 3, whether deceased ever rallied from the effects of the violence. The time at which tetanus usually makes its appearance, when it is the result of a wound (traumatic), is from about the third to the sixth day; but it may not appear until three or four weeks after the injury, and the exciting cause may still be traced to the wound which may have healed. When resulting from a wound it is generally fatal.

A medical practitioner is bound to exercise great caution before he pronounces an opinion that a fatal attack of tetanus has arisen either from spontaneous causes or from slight blows or personal injuries. A case occurred in St. Bartholomew's Hospital, in 1853, which exemplifies the necessity of making a rigorous inquiry into all the attendant circumstances. A boy, æt. 15, while quarrelling with another, received a blow in the back from his companion's fist, and this was followed by a kick, but not of a severe character. He was able to get up and walk home; but in about two hours he complained of stiffness of the lower jaw. He passed a restless night—the stiffness increased, there was great pain, and subsequently difficulty in swallowing. On the second day he was admitted into the hospital, the pain and stiffness gradually increased, and the jaw became partially fixed. Spasm of the muscles of the back supervened, occurring in paroxysms, and there was confirmed tetanus. He died on the fourth day after he had received the blow on the back, and apparently from tetanus, as a result of that violence. It turned out, however, on inquiry, that six days previously to the first appearance of the tetanic symptoms, the boy had accidentally driven a rusty nail into his foot, and that the suppurating wound which resulted from this injury had only closed on the day on which the blow was inflicted. On an examination of the body a small puckered cicatrix, such as would result from the healing of a punctured wound, was found on the ball of the great toe, and there could be no doubt from the circumstances, that this, and not the slight blows struck by the assailant, had been the cause of the fatal attack of tetanus. ('Lancet,' Dec. 10, 1853, p. 550.) This case has an important bearing on the question considered at p. 589. It is probable that many cases have been set down as idiopathic tetanus in which, by proper inquiry, the disease might have been traced to a concealed wound or some personal injury. In one instance the tetanus was at first considered to be idiopathic, but shortly before death a small black mark was observed on the thumb-nail. On making inquiry, it was found that a few days previously to the attack a splinter of wood had accidentally penetrated the thumb. The patient attached so little importance to the accident that he did not mention the circumstance to his medical attendant. Two similar cases are reported. ('Brit. Med. Jour.' 1872, II. p. 594.)

Many trials for wounding have occurred in this country in which tetanus was the immediate cause of death; and the defence has generally rested upon the probable origin of the disease from accidental causes. Among these, that of *Capt. Moir*, who was tried at the Chelmsford Assizes in 1830 for the murder of a fisherman, is one of the most interesting, as it develops the rule of law in respect to criminal responsibility, when death takes place from a secondary cause. The deceased had frequently trespassed on the grounds of the prisoner, notwithstanding warnings. One day the prisoner met the deceased crossing his grounds, in order to pursue his usual occupation of fishing. An altercation took place, and the prisoner, in a state of irritation, rode back to his house, procured his pistols, rode after the deceased, and overtook him in the act of continuing the trespass. Words again ensued between them, and the prisoner then fired at the deceased, and wounded him severely in the arm. The muscles, vessels, and nerves were extensively lacerated, but no question seems to have been raised respecting the propriety of immediate amputation. The deceased lingered a short time; and tetanus supervened, from which he died. On the trial, the medical evidence went to show that death was caused by tetanus, brought on by the severe gunshot wound inflicted by the prisoner. In his defence, it was alleged that he shot the deceased under provocation, and that he had not intended to kill him, for he had purposely aimed at his arm. With regard to the first point, it was considered that the fact of his returning to his house, to fetch a weapon capable of inflicting a mortal wound, was evidence of deliberate malice; while, with regard to the second point, there could be no extenuation, since a serious wound inflicted on arm or leg may destroy life as certainly as a wound inflicted on the trunk. The prisoner was found guilty and executed. In this case, the connection of the secondary cause of death with the original wound appeared to be so clear, that not a doubt existed in the minds of the professional witnesses; and the law held the prisoner to be as much responsible for the fatal result as if he had killed the deceased on the spot.

Erysipelas, like tetanus, may be a fatal result of slight injuries. Wounds affecting the scalp are liable to be followed by this disease. Burns and scalds may prove fatal either through tetanus or erysipelas as a secondary cause. Some persons are particularly prone to erysipelatous inflammation, and thus wounds, comparatively slight, may have a fatal termination. In *Reg.* v. *Littlewood* (York Sum. Ass. 1858), it was proved that deceased had died from erysipelas consequent on a burn which he had received from an explosion of gas. The cause of death was clearly proved, but the evidence failed to show criminal negligence, and the prisoner was acquitted. On these occasions, in order to make an assailant responsible for the fatal result, the erysipelas must be clearly traced to the injury. The medical facts that the person assaulted has never recovered from the effects of the violence, and that the inflammation set up has suddenly assumed an erysipelatous character, are sufficient to establish this connection. If there has been recovery, and an interval of some days has elapsed, a doubt may arise respecting the connection of the erysipelas with the violence inflicted. This disease is occasionally idiopathic, *i.e.* it appears like tetanus without any assignable cause. In the following case, which was the subject of a trial at the Cent. Crim. Court in July, 1859, the erysipelas did not show itself until thirteen days after the injury, and it proved fatal on the seventeenth day.

A potman, stated to be of temperate habits, was struck on the left cheek with a quart pot. There was a contusion, but no injury to the skin. The man was slightly stunned by the blow, but was able, in less than an hour,

to prefer a charge against the aggressor. From this time he did not appear to suffer any ill effects from the blow, and continued as usual at his work for a period of thirteen days after the receipt of the injury, when erysipelas of the ordinary character made its appearance. It commenced on the bridge of the nose and both eyes. Towards the close of the same day the man had an attack of delirium tremens, and on the sixteenth day, the erysipelas began to assume an unhealthy aspect, and he was then taken into hospital. The erysipelas was now general over the face and head, and delirium tremens was strongly marked. Death took place on the following afternoon, and at the post-mortem examination twenty hours after death, only slight congestion of the brain was found. At the coroner's inquest Clapton was asked whether it was probable (as far as was currently known), that erysipelas could supervene upon a contused wound *thirteen days* after a blow. His reply was in the negative, and he expressed an opinion that the erysipelas could not be attributed to the blow. Hence the death of the man did not result indirectly from the blow, as was sought to be proved. The coroner and the jury disregarded the medical evidence, and committed the man for trial. At the trial the same medical evidence of the cause of death having been given, the Recorder immediately directed the jury to acquit the prisoner, stating that there was no evidence to prove that the death had been in any way caused or hastened by the injury inflicted.

Reid ('Physiol. Researches,' p. 512) has pointed out a singular appearance in death from erysipelas which, unless the facts had been known, might have given rise to a serious mistake. A man died from erysipelas in the left leg. On uncovering the body twenty-four hours afterwards, for the purpose of inspection, it was observed that the skin over the fore and middle part of the leg affected with the erysipelas, had assumed a dark purple colour, resembling so strongly the appearance of ecchymosed blood consequent upon injury, that all who were present confessed that if they had not been aware of the previous history of the case, the appearance might have been attributed to some injury received during life. When, however, the apparently ecchymosed part had been cut into, it was found that no blood had been effused into the cellular tissue, but the skin was increased in thickness, and its vessels were loaded with dark blood.

It is sometimes difficult to establish the connection of *erysipelas* with a wound, especially when the disease occurs in a remote part of the body not implicated in the wound. When this cannot be distinctly made out, there will be an acquittal. The following case was tried before the Justiciary Court at Glasgow, in 1822. A gamekeeper was indicted for the murder of a poacher, whom he shot so severely in the left arm, that it was found necessary to perform amputation above the elbow. The man died of erysipelas in the right leg; and the question on the trial was, whether the erysipelas was brought on by the gunshot wound or not. Upon this question there was great difference of opinion among the medical witnesses. One gave it as his opinion that the debility caused by the wound brought on the disease of which the deceased died. Another thought that the tendency to erysipelas had existed long before the man received the wound. It appeared in evidence that the deceased had been out two nights in the exercise of his vocation, and had slept without shelter; that during this time he had eaten but little; and that he had an ulcer in his leg, the absorption of matter from which, in the opinion of some of the witnesses, had laid the foundation of the disease before the injury was received. As he had received what was thought to be the best mode of treatment in such a case, supposing the deceased had

ceived no wound at all, the prisoner was acquitted of the charge. (Beck's
led. Jur.': Wounds.) Taking the circumstances as they are above
ported, it certainly did not appear that erysipelas was directly connected
ith the wound, and unless this had been clearly and satisfactorily proved,
would have been unjust to make the prisoner responsible for the fatal
nsequences. The bad habit of body and the actual existence of disease
the leg, were facts in themselves sufficient to render such an opinion
probable. But in addition to this, it is stated by Alison, that erysipelas
as at the time prevalent in the Glasgow Infirmary, and that deceased was
t into a bed formerly occupied by a patient labouring under this disorder.
ntil then the wound had presented no peculiarly dangerous symptoms.

A question of a similar kind arose in *Master* v. *The Blackpool Railway*
mpany (Liverpool Lent Ass. 1868). It was an action for recovery of
mpensation for the death of the Archdeacon of Manchester. In a
llision on the line he received a bruise on the shin. He complained of
e injury at the time, and walked lame. In a few days phlegmonous
ysipelas set in, and he soon afterwards died of pyæmia. It appeared that
s wife was at the time suffering from phlegmonous erysipelas with
oughing sores on the leg, and for two or three days after the injury, the
rchdeacon slept in his wife's room, and his leg was dressed by the servant
ho attended the wife. The injury itself appeared at first to be very
ight, but after this it assumed a more serious character. On the part of
e plaintiff it was urged that the erysipelas which had caused death, had
pervened naturally on the injury to the leg, while it was contended for
e Company that the erysipelas was induced by contagion or infection
om sitting in the wife's bedroom with the wife, and did not naturally
sult from the injury. It was left to the jury to say whether or not the
rchdeacon's sitting in the bedroom was a want of due care, or whether
e disease which proved fatal had followed as a natural consequence from
e blow. The jury found for the Company, on the ground that the
laintiff had sustained no pecuniary loss.

Delirium tremens is a disease which frequently presents itself as a
condary consequence of injuries to persons of intemperate habits. The
jury may be slight or severe; the disease will equally supervene and
ay prove fatal. It is observed occasionally as a consequence of operations
quired for the treatment of wounded persons. The remarks already
ade (p. 600) upon the influence of unhealthy constitutions on wounds,
pply with especial force to cases of this description. In the case of
eg. v. *Heywood*, C. C. C. Oct. 29, 1846, it was proved that the deceased
ad been assaulted by the prisoner, but had not sustained any personal
jury likely to be followed by serious consequences. Nevertheless, symp-
ms of delirium tremens came on, and he died in the course of a few
ays. It was alleged that the disease of which the deceased died was
rought on by the violence, and the evidence of Coulson was adduced in
pport of this view. He deposed that he was called upon to attend the
eceased on the day after the assault. His face was swollen and black,
articularly on the right side, and there were two wounds on that side of
e face. He did what was necessary at the time, and the wounds were
early healed. The deceased appeared to suffer from great tremulousness
nd weakness, and these constitutional symptoms continued to increase,
lthough the wounds were rapidly healing, and the swelling had nearly
bsided. Two days before his death the ordinary symptoms of delirium
remens came on, and of this he died. In his opinion death was
ttributable to a shock of the nervous system, causing delirium tremens;
nd he accounted for that shock by the attack made upon the deceased,
nd by the blows he had received. On a post-mortem examination he

could not discover any fracture of the skull or of the bones of the face, or a rupture of any blood-vessel. The right lung was much congested, and there were some old adhesions to the chest. The left lung was also congested. The heart was large and flabby, but he did not discover anything in the examination of the body to account for death. He considered that the delirium tremens arose from the attack made upon the deceased, but he was certainly surprised to see so fatal a result from such slight injuries. The blows the deceased had received were the exciting cause of delirium tremens. It was generally the result of violent injury, but he had known it to follow from slight blows. He should say, from the appearances he observed on the post-mortem examination, that the deceased was a 'bad subject.' The injuries the deceased had received were certainly not sufficient to account for the death of a healthy man. The shock to the system might have been produced by the deceased's excited condition, and delirium tremens might be occasioned by excitement alone; but, as there had been blows in this case, he thought it more natural to ascribe it to them than to mere excitement. The skull of the deceased was remarkably thin, and if there had been any great violence, he should have expected to find the bones fractured. If the system had not been in a bad state, the result would not have been so serious; but he considered the blows to have been the exciting cause of death. The witness alluded to the moral effect of the blows, and to the excitement they occasioned, rather than to the actual result that might reasonably be expected from injuries of such a character. He would not undertake to say that the deceased would not have died from the excitement alone, even if he had not received any blows. The blows and the excitement together were, no doubt, the cause of death. A second medical witness said, that in his opinion, the deceased's death was the result of his excited state, and that delirium tremens was thereby occasioned, and not by the blows he received. He described the liver and kidneys of the deceased as presenting the appearance of those of a person addicted to drinking spirits or beer. It was contended that there was no distinct proof of the actual cause of death, or that the disease of which the deceased died had been brought on by the wounds, and the prisoner was acquitted. ('Med. Gaz.' vol. 38, p. 811.)

Death from surgical operations.—In the treatment of wounds, surgical operations are frequently resorted to, and a wounded person may die either during the performance of an operation, or from its consequences. A question may thence arise, whether the person who inflicted the wound shall be held responsible for the fatal result. The law of England regards a surgical operation as part of the treatment, and if undertaken *bonâ fide*, and performed with reasonable care and skill, the aggressor will be held responsible, whatever may be the result. The necessity for an operation, and the mode of performing it, will be left to the operator's judgment. As the defence may turn upon the operation having been performed unnecessarily, and in an unskilful manner, it will be right for a practitioner, if possible, to defer it until he has had the advice and assistance of other practitioners. According to Lord Hale, if death takes place from an *unskilful operation*, performed for the cure of a wound, and not from the wound, the responsibility of the prisoner ceases.

Death is by no means an unusual result of severe operations, the secondary consequences under which the patient may die being very numerous, even when the case is most skilfully managed. Sometimes the patient will die on the table, although but little blood may have been lost. Fear, pain, and sudden shock to the nervous system have caused death under these circumstances. The most common indirect causes of death after severe operations are secondary hæmorrhage, erysipelas, tetanus,

lelirium tremens, pyæmia, and hectic fever with gangrene of the stump. nspection of the body after death frequently explains the unfavourable esult of operations that promise well, by discovering one or more organs in a state of chronic disease, which had not previously deranged the health in a degree sufficient to give notice of its existence, and which might, therefore, have remained quiet for years to come, had no extraordinary call been made upon the powers of the system.

Should an operation be unnecessarily or unskilfully performed, the responsibility of an aggressor would, it is presumed, cease, if the death of a wounded party could be clearly traced to it. Thus, if in carelessly bleeding a wounded person, the brachial artery should be laid open ('Ann. d'Hyg.' 1834, 2, 445), or if, in performing amputation, a large artery be improperly secured, so that the patient in either case dies from the loss of blood, the prisoner could not be equitably held responsible; because it would be punishing him for an event depending on the unskilfulness of a medical practitioner. According to Platt, B. (see p. 597), a prisoner will be held responsible if the original wound were likely to produce death, although unskilfully treated. Supposing the bleeding or amputation to be performed with ordinary care or skill, and yet, in the one case inflammation of the veins, and in the other erysipelas, tetanus, gangrene, pyæmia, or fever should destroy life, the prisoner will be liable for the consequences. The practice of the law is strictly consistent with justice. Should the operation be considered to be *absolutely* required for the treatment of a dangerous wound, which according to all probability would prove mortal without it, should it be performed with ordinary skill, and still death ensue as a direct or indirect consequence, it is only just that the person who inflicted the injury should be held responsible for the result. It is presumed in these cases, that were the patient left to himself, he would, in all probability, die from the effects of the wound. If, therefore, a surgeon, knowing that an operation would give him a chance of saving life on such an occasion, did not perform it, it might be fairly contended in the defence that the deceased had died, not from the wound, but from the incompetency and neglect of his medical attendant. Hence it follows that if, during his necessary treatment, unforeseen though not unusual causes cut short life, no exculpation should be admitted, if it went to attack the best-directed efforts made for the preservation of life. (See 'Ann. d'Hyg.' 1835, 1, 231.)

In another part of this work (p. 26), the author has referred to the case of *Kelly*, who was tried for the murder of police-constable Talbot (*Reg.* v. *Kelly*, Dublin Commis. Court, Nov. 1871). The facts of this case, although made a subject of the most violent contention in a medical, legal, and political view, were really of a very simple kind. On July 12th, the deceased received a pistol-shot wound at the back of his neck, and died from the effects on July 16th. The bullet fractured and splintered the atlas, wounding and crushing the soft parts of the neck, and leading to the formation of an abscess in this part. The actual cause of death was inflammation of the spinal cord and its membranes. Stokes considered it necessary to enlarge the wound for the purpose of removing the bullet, which was then supposed to be lying within reach. In this operation a small artery (the occipital) was divided, but the quantity of blood lost was small; the bleeding was stopped by compression, and this bleeding had no influence in causing death. The defence was that the wound would not have proved fatal but for the bad surgical treatment; that the probing of the wound was unnecessary, and that it was unskilfully performed. There was the evidence of experts on both sides; but the facts proved, apart from the opinions expressed, could leave no reasonable doubt

that the case had been treated with *bonâ fides* and with competent skill. The prisoner was positively identified by deceased and others, and yet upon this evidence the jury returned a verdict of not guilty. ('Brit. Med. Jour.' 1871, II. p. 716.)

The evidence of Tuffnell and other surgical experts showed that the probing operation performed on the deceased, which was made the subject of harsh and unjust comments by the counsel for the defence, was in strict accordance with the rules of surgery, and that the wound was of such a nature as from the first to be likely to prove mortal in spite of treatment. If any proof were required of the correctness of this opinion, it will be found in a public declaration, made subsequently to the trial, by nine eminent London surgeons, who one and all agreed 'that the bullet-wound in the neck of police-constable Talbot was the direct and sole cause of his death, and that no blame can be justly assigned to any of those by whom the wound was treated.'

Longmore thus expressed himself on this case:—'It would have been acting wrongly had every effort not been made to extract the bullet from the situation in which it was supposed and reasonably inferred to be lodging. It is of immense importance that foreign bodies lodging in the walls of cavities should be got away if possible. No one acquainted with such subjects—at least, no one who respects truth more than some other ulterior object—can really believe that the man's death in this case was due to anything else but the direct effect of the gunshot wound which had been inflicted upon him.' ('Brit. Med. Jour.' 1871, II. p. 717.)

The failure of justice in this case appears to have been chiefly owing to the fact that the jury were allowed to form their opinions on the surgical treatment pursued, whereas the rule of law is clear as to responsibility. The English practice, as already quoted above, is, that if a man unlawfully inflicts a dangerous wound on another, and the wounded person, after being treated by qualified practitioners, acting *bonâ fide*, and applying themselves with the best of their ability to the case, dies of the wound, the man inflicting it is really guilty of murder, even although an erroneous treatment of the case by the practitioner may have been the cause of death.

Medical responsibility in reference to the administration of anæsthetics.—In a large number of operations it is the general practice among surgeons to administer chloroform vapour or other anæsthetic, not only to allay pain but to prevent the exhaustion on the patient likely to arise from protracted surgical proceedings. In spite of care on the part of the operator, these vapours are liable to destroy life in an unexpected manner, and the patient may die either before the operation is commenced or during its performance. The facts may leave no doubt that the wounded person died from the anæsthetics, and not from the wound or operation. On inspection of the body, the heart may be found in an unhealthy state—a fact which was formerly considered sufficient to account for the fatal effects of the anæsthetic. In a case of this kind, what becomes of the responsibility of the person who inflicted the original wound? No decision has ever been given on this point. Was the use of the anæsthetic in a professional view a *necessary* part of the treatment? Was it skilfully and *properly* administered? Could the diseased condition of the heart, which rendered the effects of the vapour more fatal than usual, have been detected by the operator, so as to show the impropriety of administering it in this case? These questions should receive satisfactory answers before the aggressor is rendered responsible for death under such peculiar circumstances. In *Absolom* v. *Statham* (Q. B. Nov. 1867), an action was brought against a medical man for forcibly administering chloroform to the plaintiff against her will, and extracting six of her teeth; also for careless and unskilful treat-

ient, whereby her health was injured. The medical evidence showed that he woman had consented to the operation, and that it had been properly erformed; also that her health had sustained no injury by the chloroform r the operation, and that most of her symptoms were due to hysteria. ockburn, C.J., in summing up the case, said, that the two charges or mplaints were entirely distinct and different—one being for an assault, id the other for malpractice. The law was clear as to both. No surgeon id a right to perform any operation against the will of the patient, *so long s the patient preserved consciousness and will;* and if, therefore, the jury elieved the plaintiff's story, then she was entitled to a verdict, although ie amount of the damages would depend upon their impression as to the ctent of the injury. Then, as to the other ground of complaint, the law as equally clear, that every medical practitioner was bound to bring a asonable amount of skill and care to the performance of the duty he ndertook. The jury found for the defendant on both grounds. This ows the present state of the law in reference to the responsibility of edical men who undertake operations under chloroform.

Necessity for Operations.—When an operation is rendered necessary for e maltreatment of an injury, the responsibility of an assailant, if the se proves fatal, ceases. In *Reg.* v. *Kingshott* (Lewes Sum. Ass. 1858), was proved that prisoner and deceased fought, and that the prisoner bit e deceased severely on the thumb. According to the medical evidence e wound would, in all probability, have healed of itself, or with some ght applications, but it seemed that the deceased went to a corn-leech the neighbourhood, and he applied a salve to the wound, the consequence which was that severe inflammation ensued. The deceased then applied a regular practitioner, who did all that was possible under the circumances, but the whole arm was in such a condition that it was deemed visable to remove him to the hospital, where his arm was amputated, d he died from the effects of the operation. For the defence it was ntended that the prisoner ought not to be convicted of causing the death the deceased, inasmuch as it was proved that the original injury was of slight character, and not at all calculated to produce a fatal result, and at the deceased had conduced to his own death by suffering himself to treated by an ignorant and unskilful person. The judge held that the arge of manslaughter could not be supported upon the evidence, and he erefore directed the jury to acquit the prisoner.

By an operation being *absolutely required*, are we to understand that it ould be necessary to preserve life, *i.e.* that the wound would probably ove fatal without it? Bleeding and cupping may be necessary as part the treatment of a wounded person; but unless it could be sworn that is treatment was required, in the judgment of the surgeon, for the *prevation of life* from the injury inflicted, it is doubtful whether, in the ent of death occurring from these simple operations, the assailant would held responsible for the fatal result. In 1827, two persons were tried Edinburgh, for capitally assaulting another by throwing sulphuric acid er him. (*Rex* v. *Macmillan.*) The death of the deceased was clearly e to inflammation of a vein and concomitant fever, following the operan of bleeding, which was considered necessary in the treatment of the se. It did not appear that this bleeding was absolutely necessary for e preservation of life, but merely for the prevention of severe ophthalmia. e charge of murder was therefore abandoned, this question of responsility for the fatal result being considered to involve too nice a point to sure conviction. ('Ed. Med. and Surg. Jour.' April, 1829, 230.)

From cases hitherto decided, it would appear that the law regards three cumstances in death following surgical operations:—1st, the necessity

for the operation itself; 2nd, the competency of the operator; and 3rd, the fact that the wound was dangerous and would be likely to prove mortal without it. A few cases will serve to illustrate the view taken by our judges of this most important question. In *King* v. *Quain* and others (Limerick Spring Ass. 1836), Dillon (the deceased) received a comminuted fracture of the leg, produced by blows with a stick. He was taken to an hospital, and it was proposed to amputate the injured leg, but he would not consent. After some days symptoms of approaching mortification made their appearance. All the surgeons agreed that the only chance of saving life was the immediate removal of the leg. The deceased then gave his consent, and the operation was skilfully performed. The injury was inflicted on Oct. 10th; the operation was not performed until Nov. 9th, and Dillon died on the 19th (*i.e.* ten days after the operation) from tetanus, which, it was admitted, had resulted from the amputation, and not from the wounds inflicted by the prisoners. For the prisoners it was argued that the deceased did not die of the wounds as alleged in the indictment, but from the medical treatment. On the other side, it was contended that the injury to the leg was *causa causans*, as the recovery of the patient would have been utterly hopeless without amputation. The judge held (the amputation being considered a necessary part of the patient's treatment) that the death of Dillon, although not proximately, was actually caused by fracture of the leg, and so directed the jury, who returned a verdict of guilty. The disputed point was reserved, and argued before the twelve judges. In addition to the arguments in support of the conviction above given, it was represented as being laid down in the books, that if one give a wound to another, who neglects the cure, or is disorderly, and doth not keep that rule which a wounded man should do, yet if he die it is murder or manslaughter; because if the wounds had not been given the man had not died. (See case *Reg.* v. *Thomas*, *ante*, pp. 588, 599.) The exceptional cases are where death results from the medical treatment: but these are reducible to two classes:—1. When the wound is *not* in itself *mortal*, and the treatment causes the death. (*Rex* v. *Macmillan*, p. 611.) And 2ndly, when the death is clearly caused by the *treatment*, either by reason of its being *unskilful*, or not being necessary to save life in the opinion of skilful persons. (*Rex* v. *Macewan*, p. 597.) The judges, with one dissentient, ruled the point against the prisoner. In this case, the three conditions requisite for responsibility clearly existed: the operation was absolutely necessary to save life—there was no question as to the competency of the operator—and the wound would, according to all surgical experience, have proved fatal without it. The wounded person may, as in the preceding case, have refused to submit to an operation when in the judgment of a medical man it was necessary to save life, or he may have submitted to it when too late. In *Reg.* v. *Draper* (C. C. C. Aug. 1872), the prisoner, while carelessly driving a waggon, knocked down the deceased, and a wheel passed over his left arm just above the elbow. The deceased was taken to the Royal Free Hospital, when it was proposed at once to amputate the arm, but he, after consulting with his friends, refused to submit to the operation. The arm was then dressed and put into splints, and the man was told that his life would be endangered if he did not permit his arm to be amputated. A week later he consented to the operation. The arm was removed, but he died of pyæmia, one of the secondary consequences of the operation. In the opinion of the medical officers of the hospital the man's life would have been saved if he had allowed immediate amputation. Quain, J., told the jury to put out of their minds the question whether death had ensued from the determination of the deceased not to have his arm amputated, as that was a matter of law, upon which,

if necessary, he would reserve a case. The question for them to consider was whether, owing to the negligence of the prisoner, the deceased sustained the injury which led to his death. The jury found the prisoner guilty.

In *Reg.* v. *Perrell* (Taunton Lent Ass. 1847), it was proved that the prisoner had thrown a stone at the deceased, and caused a fracture of the skull. On a consultation, the medical practitioner performed the operation of trephining. The deceased rallied, but he died on the 19th day after the injury; and it was found that there was an abscess in the brain. The medical witnesses referred death to the blow, but admitted that it might have been accelerated by the operation. It was contended in the defence, that although the injury without the operation might have proved mortal, yet that the deceased had really died from the medical treatment. Cresswell, J., observed, that it was admitted the wound was mortal, and that the deceased might have died in a month, but that he had died in less than a week in consequence of the operation. The wound being mortal, if that which was done by the surgeon was what he considered right to be adopted, there would be no question raised upon this point. The prisoners were convicted. Competency for forming a judgment, or for undertaking an operation, implies on these occasions only that average skill and experience which every legally qualified practitioner is presumed by law to possess; and although it is difficult to say whether a man would or would not have died under a particular injury without an operation, yet the law allows a free exercise of judgment, and would not act upon extraordinary exceptions.

Operations under a mistaken opinion.—It may happen that the wound is not mortal, and that, although skilfully performed, the operation was *not* necessary to save life; in other words, the wounded person may have died from the immediate results of a serious operation, performed under a mistaken view of the case. It may be alleged by a prisoner's counsel that the operation was not necessary to save life, and that the wounded man might have recovered without it. A *Lieut. Seton* was killed in the Gosport duel case (June, 1845.) (*Reg.* v. *Pym*, Hants Lent Ass. 1846.) A tumour formed in the course of the pistol-shot wound received by the deceased at the lower part of the abdomen; and this was supposed by the three surgeons in attendance on the deceased, to be an aneurismal enlargement from a wound in, or injury to, the femoral artery, for which it was considered necessary to tie the external iliac artery. The patient died from peritoneal inflammation following the operation; and on inspection, it was found that the tumour was formed by a mass of coagulated blood poured out, not from the femoral artery, but from one of its superficial and anomalous branches, which was divided about an inch below Poupart's ligament, and an inch from the main body of the artery. There was some difference of opinion about the necessity for the operation, both as to the time selected for its performance, and as to its being absolutely requisite for the preservation of life. One witness thought that it was absolutely necessary to perform it at the time; while another thought it absolutely necessary, under the circumstances, to save life. In his evidence at the trial, Liston stated that 'the tying of the iliac artery was necessary, and that no other operation would have been prudent.' It was proposed to cross-examine the medical witnesses in order to show that the wound was not dangerous to life, and the operation not absolutely necessary; but Erle, J., interposed:—'I presume you propose to call counter-evidence, and impeach the propriety of the operation, but I am clearly of opinion that if a dangerous wound is given, and the best advice is taken, and under that advice an operation *is performed*, which is the *immediate* cause of death,

the party giving the wound is criminally responsible.' Cockburn—'I proposed to show that the opinion formed by the medical men was grounded upon erroneous premises, and that no operation was necessary at all, or, at least, that an easier and much less dangerous operation might and ought to have been adopted. I may therefore cross-examine the witnesses as to the grounds of their opinion. I shall submit that a person is not criminally responsible where the death is caused by consequences which are not physically the consequences of the wound, but can only be connected with the first wound by moral reasonings, as here that which occasioned death was the operation which supervened upon the wound because the medical men thought it necessary. The point has never been solemnly decided in this country. The cause of death is a question for the jury.' Erle, J. —'I am clearly of opinion, and so is Rolfe, B., that where a wound is given which, in the opinion of competent medical advisers, is dangerous, and the treatment which they *bonâ fide* adopt is the immediate cause of death, the party who inflicted the wound is criminally responsible, and of course those who aided and abetted him in it. I so rule on the present occasion; but it may be taken, for the purpose of future consideration, that it having been proved that there was a gun-shot wound, and a pulsating tumour arising therefrom, which, in the *bonâ fide* opinion of competent medical men, was dangerous to life, and that they considered a certain operation necessary, which was skilfully performed, and was the immediate and proximate cause of death,—the counsel for the prisoner tendered evidence to show this opinion was wrong, and that the wound would not inevitably have caused death, and that by other treatment the operation might have been avoided, and was therefore unnecessary. I will reserve this point for the consideration of the judges, although, as I have already stated, I have no doubt upon the subject. To admit this evidence would be to raise a collateral issue in every case as to the degree of skill which the medical men possessed.'

The point was reserved, but as the prisoner was acquitted of the charge, the opinion of the judges was not taken. ('Law Times,' March 21, 1846, p. 500.) The question was subsequently raised at the trial of the principal in the duel (*Reg.* v. *Hawkey*, Hants Sum. Ass. 1846), but Platt, B., decided in accordance with the opinion of Erle, J., and Rolfe, B. The prisoner was acquitted. ('Law Times,' July 25, 1846, p. 370.) This decision stops all inquiry respecting the necessity of an operation, leaving this to the *bonâ fide* judgment of the operator—and it leaves undecided, as in *Macmillan's* case (*ante*, p. 611), the question whether the operation was or was not necessary to save life. It was decided in the case of *Rex* v. *Quain* and *Reg.* v. *Pym*, that although the indictment alleged that the deceased died of the wound, while in fact he died from the results of an operation, yet it was good in point of law.

A case tried at the Cent. Crim. Court (*Reg.* v. *Fueling*, 1872), involved some of the points here raised. The prisoner severely kicked the deceased on the right knee. He was able to walk home with much difficulty. Disease set in, and about ten months after the violence amputation of the leg was performed. Ulceration of the stump took place, and the deceased died from secondary hæmorrhage. There was much disease about the leg. It was contended that notwithstanding the long period which had elapsed, the deceased had died from the unlawful act of the prisoner. For the defence it was suggested that deceased had died from an operation which was not necessary to the treatment. In addressing the jury, Channel, B., said, if a man attack another and certain results ensued, in the course of which the qualified and competent medical adviser who might be called in took in his discretion a step the termination of

which was unsuccessful, and which, perhaps, in the exercise of superior skill would not have been adopted, that termination would not save the man by whom the injury was inflicted from the consequences of his act. He added that in this case they had nothing to do with the question whether or not the offender contemplated the result of his act. The prisoner was acquitted.

Fatal diseases following operations.—When a wounded person is taken to an hospital in which gangrene or erysipelas is prevalent, and he is attacked by one of these diseases before or after the performance of an operation, and dies, a prisoner may be held responsible for the fatal result. It might be contended that the transportation of the wounded man to such a locality was not absolutely necessary to the preservation of his life, and that he would not then have died, but for the accidental presence of an infectious disease. This question was raised in a trial which took place at the Maidstone Lent Assizes, 1839. (*The Queen* v. *Connel* and others.) The deceased was assaulted by a number of soldiers, and received two blows on his head with a stick. The wound was not of any great extent, and the deceased did not appear to suffer much from it. Two days afterwards, he was attacked by *erysipelas* in the head and face, and he died in about a week. On inspection, there was no appearance of organic disease. The surgeon referred death to erysipelas, which was prevalent in the hospital at the time the deceased was brought in. The man would probably have recovered but for the attack of erysipelas, and he did not think that he would have been attacked by this disease but for the wound. Erysipelas was an infectious disease, and a common consequence of wounds of the head. Upon this evidence the prisoners were convicted. In *Reg.* v. *Norris* (Wells Sum. Ass. 1860), the deceased, a gamekeeper, died from tetanus following amputation of the leg, rendered necessary by a gun-shot wound inflicted by the prisoner. No attempt was made to deny the responsibility of the prisoner for the fatal result.

Pyæmia, or the introduction of pus into the blood by absorption or by the mouths of divided blood-vessels, is another cause of death which is liable to follow personal injuries and operations. The purulent matter acts as a poison. Pyæmia occurs frequently when a bone is involved either in the injury or as the result of an operation. Inflammation of the cellular membrane surrounding bone is a condition highly favourable to its occurrence. In *Reg.* v. *Maynard* (Maidstone Lent Ass. 1862), involving a charge of manslaughter by wounding, the medical evidence was to the effect that death was caused by pyæmia. The medical witness must remember that pyæmia may arise from causes totally irrespective of wounds or personal injuries. ('Guy's Hosp. Rep.' 1859, p. 179.)

Questions relative to responsibility in death following operations would come more frequently before Courts of law, were it not that the cases are stopped in the Coroners' courts by verdicts of accidental death. (See 'Med. Gaz.' vol. 19, p. 157.)

Medical Responsibility in Operations. Malapraxis.—This is a very wide subject, but it can here be only glanced at in a few of its leading features. It was held by Lord Ellenborough, that if a person acting in a medical capacity be guilty of misconduct arising either from gross ignorance or criminal inattention, by which a patient dies, he is guilty of manslaughter. Faults, such as omissions, or errors in judgment, to which all are liable, are not visited with this amount of criminality. The same rule applies to the licensed as to the unlicensed practitioner; but it would appear, from the charge of Williams, J. (Winchester Spring Ass. 1847), that a degree of unskilfulness which might lead to the conviction of a licensed, would justify the acquittal of an unlicensed midwife. This was in the case of a midwife,

æt. 72, alleged to have caused the death of a woman on whom she had been called to attend. 'The charge,' he said, 'appeared to be, that by want of skill or attention to her duties, she had caused the death of the woman upon whom she was attending. In order to constitute this offence, it must be shown that the party was guilty of criminal misconduct, either arising from gross ignorance, want of skill, or gross inattention. With respect to the degree of want of skill, he must say, that it was not to be expected that a midwife who was called in to attend a person in the humble class of the deceased, a soldier's wife, should exhibit what a medical practitioner would call competent skill. It was enough if she applied that humble skill which in ordinary cases would lead to a safe delivery. She was not bound to have skill sufficient to meet peculiar and extraordinary exigencies, although in the case of a regular medical man such skill might be required. The class of this humble practitioner was absolutely necessary for the poorer classes, and, although on the one hand it was fit the law should protect the patient by punishment for gross want of skill, yet he thought there would be much to be lamented if it was applied with such severity as to render a party not possessing skill of this kind, liable to punishment for manslaughter.'

Charges of manslaughter have been brought against medical practitioners in cases of midwifery. In some instances gross mismanagement has been proved; the uterus, and even parts of the viscera, have been torn away, and in such cases convictions have followed. It is well known, however, that much difference of opinion exists among the most eminent practitioners of midwifery respecting the treatment to be pursued in certain cases of difficulty. The case of *Reg.* v. *Dickinson* (Stafford Lent Ass. 1846) is in this respect of interest. A medical practitioner was charged with having caused the death of the deceased in her confinement. This appears to have been a case of placenta prævia: the placenta (after-birth) was removed, but the female sank under the bleeding which followed. Platt, B., after consulting several medical works, charged the jury, that if, in a particular case, there are two modes of treatment respecting the adoption of either of which men of learning are equally divided, then no man can be said to be 'grossly ignorant' in adopting a course which has received the approbation of eminent writers, and which his own judgment sanctions and approves. The accused was immediately acquitted. ('Med. Gaz.' vol. 37, p. 875.) When death is not a result of the medical treatment, an action for damages may be brought against the practitioner for *malapraxis*.

It has been a question whether slight deviations from the ordinary mode of performing operations should involve a practitioner in a charge of malapraxis. This question has not been raised in England.

The case of *Gibbs* v. *Tunaley* (Norfolk Lent Ass. 1845), is interesting in relation to this subject. An action was brought against a surgeon for alleged negligence and want of skill in treating an injury to the foot, which the plaintiff had sustained. Mortification took place, and amputation was necessarily performed. The plaintiff and his witnesses alleged that the mortification was caused by tight bandaging, but the defendant brought good medical evidence to show that it was most probably due to the extensive violence from the accident (a railway accident). Parke, B., observed in his charge, that they (the jury) were not to expect from a country practitioner the same amount of eminent skill to be met with in large towns; but they had a right to expect from him the usual and ordinary amount of skill, care, and attention which it was only reasonable to suppose he would possess; and if, in the discharge of his duty, he applied his professional skill and knowledge to the best of his ability,

then, however unfortunate the termination of the case, he was not to be visited with an action to mulct him for damages. Such a step would be most unjust, and have an injurious tendency, as it would check that independence of action so necessary for medical men to possess. Damages one farthing.

In the case of *Baker* v. *Lowe* (Queen's Bench, Feb. 1845), a medical man brought an action against the defendant for the amount of his bill, and the defence was that he had been unskilfully and improperly treated. The defendant had been attacked with senile gangrene in the toe; the toe was removed, but the disease involved the foot, and amputation was again performed. The plaintiff had adopted a plan of treatment in the first instance, which it was alleged was improper. The medical evidence was very conflicting. The plaintiff brought two experienced witnesses who approved of his treatment, and the jury returned a verdict for the greater part of the amount claimed. ('Med. Gaz.' vol. 36, p. 126.) When there is such a division of opinion among men of equal experience, a practitioner has a right to expect that a verdict will be returned in his favour; since it is not to be supposed that a man's practice should receive the unanimous approval of the *whole* of his professional brethren. All that appears to be expected is a reasonable accordance in treatment with received professional doctrines.

CHAPTER 45.

CICATRIZATION OF WOUNDS—EVIDENCE FROM CICATRICES—CHANGES IN AN INCISED WOUND—IS A CICATRIX ALWAYS A CONSEQUENCE OF A WOUND?—ARE CICATRICES WHEN ONCE FORMED INDELIBLE?—CHARACTERS OF CICATRICES—IDENTITY PROVED OR DISPROVED BY CICATRICES—COLOURED CICATRICES—TATTOO MARKS—THE TICHBORNE CASE—CICATRICES FROM DISEASE DISTINGUISHED FROM THOSE OF WOUNDS—WHEN WAS THE WOUND INFLICTED?—GANGRENE AND PUTREFACTION—CHANGES IN CONTUSIONS—HOW LONG DID THE DECEASED SURVIVE THE WOUND?

Cicatrization of wounds.—The period of time at which a particular wound was inflicted may become a medico-legal question, both in relation to the living and the dead. The identity of a person, and the correctness of a statement made by an accused party, may be sometimes determined by an examination of a wound or its cicatrix (scar). So, if a dead body be found with marks of violence upon it, and evidence be adduced that the deceased was maltreated at some particular period before his death, it will be necessary for a practitioner to state whether, from the appearance of the injuries, they could or could not have been inflicted at or about the time assigned. A case was tried (*The Queen* v. *Raynon*, Taunton Spring Ass. 1841), wherein evidence of this kind served to disprove the statement made by the accused. He was charged with maliciously cutting and wounding the prosecutrix. There was a cut upon his thumb, which he accounted for by saying it was from an accident that had occurred three weeks before. The medical witness declared, on examining it, that it could not have been done more than two or three days, which brought the period of its infliction to about the time of the murderous assault. This with other circumstances led to a conviction.

An *incised* wound inflicted on the living body gradually heals by adhesion, when no circumstances interfere to prevent the union of the

edges. For eight or ten hours the edges remain bloody—they then begin to swell, showing the access of inflammation. If the parts are not kept well in contact, a secretion of a serous liquid is poured out for about thirty-six or forty-eight hours. On the third day this secretion acquires a purulent character. On the fourth and fifth days, suppuration is fully established, and it lasts five, six, or eight days. A fibrous layer, which is at first soft and easily broken down, then makes its appearance between the edges of the wound: this causes them gradually to unite, and thus is produced what is termed a *cicatrix*. Cicatrization is complete about the twelfth or fifteenth day if the wound is simple, of little depth and width, and affecting only parts endowed with great vitality. The length of time required for these changes to ensue will depend—1. On the situation of the wound:—wounds on the legs are longer in healing than those on the upper part of the body. If a wound is situated near a joint, so that the edges are continually separated by the motion of the parts, cicatrization is retarded. 2. On the extent:—a deep or wide wound is long in undergoing cicatrization. Wounds involving many and different structures are also longer in healing than those simply affecting skin and muscles. 3. On the age and health of the wounded person:—the process of cicatrization is slow in old persons as well as in those who are diseased and infirm. In an incised wound the cicatrix is generally straight and regular; but it is semilunar if the cut is oblique. It is soft, red, and tender if cicatrization is recent; it is hard, white, and firm if of long standing. On compressing the skin around an old cicatrix, its situation and form are well marked by the blood not readily entering into it on removing the pressure. It has been said that the cicatrices of incised wounds are rectilinear, but this is not always the case; in general, they are more or less elliptical, being wider in the centre than at the two ends—this appears to be due principally to the elasticity of the skin and the convexity of the subjacent parts; thus it is well known that in every wound on the living body, the edges are more separated in the centre than at the ends, and this physical condition influences the process of cicatrization. When the wound is in a concave surface, or over a part where the skin is not stretched, as in the armpit or groin, then the cicatrix may be rectilinear, or of equal width throughout. If there is any loss of substance in an incised wound, or if the wound is lacerated or contused, the cicatrix will be irregular, and the healing will proceed by granulation. The process might then occupy five, six, or eight weeks, according to circumstances. When healed, the cicatrix would be white, and if there had been a loss of substance it would be depressed and present a puckered appearance; the surface of the skin would be uneven. (See Krugelstein in Henke's 'Zeitschrift der S. A.' 1844, b. 2, s. 75.)

Is a cicatrix always a consequence of a wound?—Assuming that the term wound implies a breach of continuity affecting the substance of the true skin (cutis), a cicatrix is always produced in the process of healing. Slight punctures or incisions with a lancet, and even leech-bites affecting only the surface of the cutis, may leave no trace after a few weeks or months. In an even cut made by a very sharp instrument, especially if it is in the direction of the fibres of subjacent muscles and the parts are kept in close contact, the cicatrix is even, linear, and sometimes so small as to be scarcely perceptible; and if the skin is white, it may be easily overlooked. Wounds of this kind are not, however, commonly the subject of medico-legal inquiry. If, on examining a part, where at some previous time a stab, cut, or burn involving the cutis, is alleged to have been inflicted, we find no mark or cicatrix, it is fair to assume that the allegation is false, and that no wound has been inflicted, making due allowance

for the fact that mere abrasions of the cuticle, or very slight punctures and incisions, often heal without leaving any well-marked cicatrices.

Is a cicatrix, when once formed, ever removed or so altered by time as to be no longer recognizable?—This is a question which sometimes presents itself to a medical jurist both in civil and criminal proceedings. When a cicatrix has been produced by the healing of a wound involving a loss of substance in the cutis or true skin, it is permanent. In wounds involving the whole substance of the skin, the cicatrix which is once formed does not disappear, although it may undergo some changes and become less distinct in after-life. Wounds which heal by suppuration and granulation generally leave behind them cicatrices which remain for life. The marks arising from the pustules of vaccination, small-pox, herpes zoster, and those produced by setons and issues, leave cicatrices usually recognizable at any period. In an early stage a cicatrix is soft and redder than the surrounding skin, but after some months or years it becomes white, hard, smooth, and shining. The time required for these changes to take place cannot be defined. In one person they make take place in a few months, and in another only after some years. The tissue of which an old cicatrix is formed, is different from that of the skin; it is harder, contains less blood, and is destitute of any coloured pigment, so that its whiteness, which is remarkable on the cicatrized skin of a negro, is retained through life. If any cicatrices were easily obliterated, it would be those which are even and regular—the results of incised wounds by sharp instruments; but small cicatrices of this kind may retain their characters unchanged for twenty-five years. According to the observations of Dupuytren and Delpech, the substance of a cicatrix is not converted into true skin—it never acquires a rete mucosum, *i.e.* the membrane which gives colour to the skin. Although this is generally true of incised and punctured wounds, yet contused and lacerated wounds on the legs of persons advanced in life, frequently present a brown discolouration—from the deposit of a brown pigment. In the cicatrices of lacerated and contused wounds, the form of the weapon with which the wound was inflicted is sometimes indicated. It is not, however, easy to distinguish the cicatrix of a stab of old date from that produced by a pistol-bullet fired from a distance. In both cases the edges may be rounded and irregular, and the cicatrix puckered, unless the stab has been produced by a broad-bladed weapon. If no mark of cutting can be perceived within a few months of the period at which a severe wound is alleged to have been inflicted, it is reasonable to infer that there has been some mistake, or that the circumstances have been greatly exaggerated.

A case in which this question was raised, was referred to the author under the following circumstances. (*Reg.* v. *Reed* and *Donelan*, Chelmsford Spring Ass. 1842.) The medical evidence was to the effect, that 'there was a wound on the nose of the prosecutrix, apparently inflicted by some sharp instrument, and the bridge of the nose was broken down. The weapon had entered half an inch, and had caused profuse bleeding. The wound was so deep that if it had entered a little higher up in the eye, it might have caused death.' In the defence it was urged that no weapon had been used; and that although the male prisoner had struck the prosecutrix a blow, the female prisoner had taken no share in the assault. It does not appear that any medical evidence was called to show in what state the prosecutrix was at the time of the trial. It was assumed that a weapon must have been used, and the prisoners were convicted, the one of stabbing, and the other of aiding and abetting. About six months after the alleged stabbing, and some weeks after the prisoners had been convicted and sentenced to punishment, the face of the prosecutrix was examined by two

surgeons (one of them a practitioner of twenty-eight years' standing), and they both deposed that there was no mark of a cicatrix from a stab, of fracture of the nose, or of any personal injury whatever. Other surgeons were requested to examine the face of the prosecutrix, but this she declined to permit; and as there was no power to compel her, the medical facts of the case were referred to Quain, Guthrie, Key, and the author. The evidence of the surgeons at the trial was laid before them, with the statements of the two surgeons who subsequently examined the prosecutrix. They all agreed that if such a wound as that described in the medical evidence had been inflicted, there would have been a visible scar and a ridge or prominence indicative of the situation where the bridge of the nose was stated to have been broken; and as no such marks could be perceived by two well-informed surgeons, they considered it improbable either that such a wound as that described could have been inflicted, or that a weapon could have been used in the assault. The medical question really to be decided was—could all traces of the cicatrix of such a wound as that above described be effaced in a period of six months, or even during the life of a person? Either the wound must have been misdescribed, or some marks of its past existence in the form of a cicatrix would have been found.

Characters of cicatrices. Their age or date.—It is important to observe that all cicatrices are of smaller size than the original wound, for there is a contraction of the skin during the process of healing. This is especially noticed with regard to the cicatrix of a *stab*, which is frequently of a triangular form. A recent stab, owing to the elasticity of the skin, is smaller than the weapon; and the resulting cicatrix is always smaller than the wound. Hence it is difficult to judge of the size of the stabbing instrument from an examination of an old cicatrix. Cicatrices arising from a loss of substance in the cutis, or true skin, are usually indicated by a depression. In gun-shot wounds, if the projectile has been fired from a distance, the cicatrix is of smaller dimensions than the ball. It represents a disk depressed in the centre, and attached to the parts beneath, while the skin is in a state of tension from the centre to the circumference. The amount of depression is great in proportion to the quantity of loose cellular membrane beneath. If the bullet has been fired near to the body, the cicatrix is large, deep, and very irregular. In this case there may be the blueish marks of tattooing from the gunpowder carried into the skin. If the projectile has made two apertures, the aperture of exit is usually known by the greater size and irregularity of the cicatrix. (See 'Ed. Month. Jour.' 1854, 10, 370.) As the age of a cicatrix increases, it becomes smaller, thicker, whiter, more shining and less sensitive. It is fibrous in structure, dense, and without sebaceous follicles, adipose cells, or hairs.

There are no appearances in an old cicatrix which will allow us to fix the *date* at which the wound leading to its production was inflicted, and it is often very difficult to say how or by what means it was inflicted. If the person is living, he may give a description of the injury and the date of its production, consistent or inconsistent with the appearances presented. As Casper remarks ('Gerichtl. Med.' 1, 115), it requires more than two, three, or four weeks to produce the hard white shining appearance of an old citatrix; but when it has once acquired these characters, there are no medical data for enabling us to determine whether the injury was inflicted two, three, or even ten years before. After the lapse of six weeks, during which a cicatrix usually has a blueish hue, the scar acquires its permanent characters; and it is then quite impossible to say how long a period has elapsed since the infliction of the wound. A proper attention to the number, situation, and appearances presented by cicatrices on the living or

ad body, will, however, sometimes enable a medical witness to establish
disprove the identity of persons.

Cicatrices from wounds or disease. Imputed.—Cicatrices may be im-
ted. It is rare to hear of frauds of this description: the wound must be
de in anticipation at a long date in order to give the appearance of an
l cicatrix. It is likely that an impostor may seek to gain his object by
tributing the cicatrices of wounds accidentally received to other causes,
by ascribing cicatrices which have resulted from disease, to some par-
ular cause occurring in early life. By a remarkable coincidence two
rsons may have cicatrices on or about the same part of the body, produced
cuts, punctures, or abscesses in early life; and serious mistakes may
made under these circumstances. A case is reported to have occurred
France in 1794, in which a man named *Lesurgues* was tried, convicted,
d executed for robbery and murder. There were some doubts at the
ne as to his identity, and strong exertions were made to save his life.
on after his execution the real murderer was discovered, between whom
d Lesurgues, who had had no hand or part in the crime, there existed a
onderful resemblance in stature, complexion, and features. But the most
traordinary part of the case was that Lesurgues, like the real criminal,
d a cicatrix or scar on the forehead, and another on the hand; and there
no doubt that these points of resemblance, which upon a proper scientific
amination might have been proved to be really different, became the
rning-point of the case and led to the conviction of an innocent person.

On the other hand, an impostor, with old scars upon his person, may
ake use of them as proofs of identity. Such scars may exist: they may
clearly proved to be of old date, and they may be assigned to causes
hich cannot be disproved except by a close medical examination. The
ars may have arisen from scrofulous ulcers or abscesses, in which case it
ould not be difficult to distinguish them from the cicatrices of wounds.
the case of *Smyth* v. *Smyth* (Gloucester Sum. Ass. 1853), the plaintiff
aimed to be the rightful heir to certain estates held by the defendants.
e based his claim upon certain deeds (alleged by the defendants to have
en forged), in which it was stated that the lost heir to these estates
ould be known by certain marks on his right hand and wrist, suggested
have been received at the time of his birth, in 1797, by reason of his
aving been brought into the world with instruments. It was one of the
rious features of this extraordinary case of imposture that no medical
inion was taken or required by the claimant on the probable nature and
igin of these marks. When requested at the trial to show his hand to
e jury, the mark had the appearance of a puckered cicatrix from a
rofulous ulcer near the wrist. Similar marks from scrofulous sores were
en upon his neck. His statements regarding himself, and the circum-
ances on which he based his claim, were so improbable and contradictory
at the case speedily broke down. A question of this kind may occa-
onally present some difficulty, but a close examination of the cicatrix,
ith a consideration of the statement of the person on its mode of produc-
on, will enable a practitioner to arrive at a satisfactory conclusion respect-
g its origin. *Scrofulous* ulcers are generally observed to leave irregular
d deeply furrowed cicatrices, with smooth depressions, surrounded by
ard and uneven margins. According to Schneider, the *scorbutic* cicatrix
dark, blueish-red in colour, soft to the touch, somewhat raised, and rather
inful; in the course of time it becomes flatter, of a reddish-brown colour,
ry thin, and easily injured. *Syphilitic* cicatrices are usually character-
ed by great loss of substance: they approximate the margins of deep
lcers before their granulations have had time to reach the surface. *Glan-
ular* cicatrices are irregularly tumefied, generally deep, hard, and of a

reddish-brown colour. These varieties cannot easily be mistaken for the cicatrices of wounds; but it is not so easy to distinguish them from each other. The form and shape of the cicatrix depend less on the cause producing it than on its anatomical position. The elasticity of the skin, the looseness or density of the cellular tissue beneath, the depression or convexity of the surface and the tension of the muscles, are conditions which will modify the form of the ulcer as well as the cicatrix proceeding from it. ('Ann d'Hyg.' 1840, 1, 430.) An expert can seldom do more than distinguish the cicatrices of ulcers arising from morbid causes, from those which have resulted from violence. Cicatrices in the inguinal regions raise a presumption that they are of *syphilitic* origin, but it is impossible to say that they may not have been derived from simple abscesses. The old cicatrices of *scrofulous* ulcers have some resemblance to those produced by fire-arms, but it may be presumed that they are of scrofulous origin when they are situated in the region of the neck, below the jaw, or in the course of the parotid gland, especially when there is any enlargement of the neighbouring glands. A puckered and folded state of the skin around the cicatrix would confirm this opinion.

Evidence from cicatrices.—The identity of a person may depend on the presence or absence of cicatrices. At the celebrated second Tichborne trial (*Reg.* v. *Castro*, Q. B. 1873), the possibility of the disappearance of scars was made a matter of great importance as bearing upon identity. Roger Tichborne, the missing baronet, whilst on board the ship *Pauline* met with an accident by which a fish-hook passed clean through one eyelid, and had to be pulled through and out; and it was truly alleged that such a wound would leave a scar, and that this would probably be indelible. He had also been bled, an operation which usually leaves indelible scars. It was also certain that, when a lad, Roger had either an issue or seton on his left arm. According to the prosecution it was an issue, and was kept open by a pea. According to the defence, it was a seton. On the defendant's arm there was the mark neither of an issue nor of a seton. Moreover, there was no scar on the eyelid such as would have been produced by the fish-hook. Further, Roger had his temporal vein opened when a young man; and there was no scar on the defendant's temples. Although it must be admitted that a venesection mark may disappear in the course of time, it is in the highest degree improbable that several cicatrices such as have been described would all disappear. The defendant was convicted of the attempted imposture; or rather of perjury, in swearing at the first (civil) trial that he was the veritable Sir Roger Tichborne. In the former case a medical jurist may be required to give an opinion on the cause and date of their production, and in the latter he may be required to say whether, assuming them to have once existed, they could have disappeared, either from natural causes or from chemical or other means employed to obliterate them. In some countries it is the custom to brand convicts, and the cicatrix from the brand-mark—a letter burnt into the skin—is regarded as the strongest proof of identity. In 1828 a man, D., was convicted of forgery and condemned to the galleys for ten years by the Criminal Court of Brabant. After a short imprisonment he was set free, on the condition that he left the country and never returned. Before his liberation he was examined by Vandelaer, a medical jurist, and he observed that there was upon his arm a cicatrix, or 'indelible' mark like that produced by branding. D. went to France, and in 1846 committed forgery and fled the country. The French Government, having reason to suspect that the accused had escaped, and was then living at Brussels under the name of H. B., demanded his extradition. H. B. was arrested, but he denied that he was the person sought for (D.), who had received the con-

itional pardon in Belgium in 1828. The question of his identity was rought before the Court of Assizes at Brabant. The accused persisted in s denial that he was the man who had been condemned by the Brabant ourt for forgery eighteen years before. Several officials of the prison in hich D. had been confined at that date came forward, and deposed that ere was a strong resemblance in the person now charged to the former isoner, but they declined to testify on oath that he was the same man. andelaer was then required to state whether he could detect on the arm the accused H. B. the mark, or scar, which he had seen on the m of D. in 1828. He deposed that there was no mark of a brand on e accused, but at the same time he gave his opinion that the absence such a mark was not a proof of the non-identity of the accused with . He assigned as sufficient reasons for its disappearance the length of me which had elapsed, and the probable use of some artificial means to use its removal. Vandelaer admitted that the mark which he saw on e arm in 1828 had been produced by a red-hot iron, and he thought at such a mark might be partially obliterated by time. Lebeau and manges, who were also called as experts, denied the accuracy of this conusion. Owing to this difference of opinion, the Court required reports om the physicians of the prisons of Vilvorde and Gand. They agreed ith Vandelaer that a scar, or cicatrix made on the shoulder with redot iron might disappear after a certain lapse of time, and by the aid of ertain means known to convicts. They were therefore not surprised to arn that such a mark, seen in 1828, was no longer visible in 1846. Upon his the Court decided that the identity of the prisoner was proved, and entenced him accordingly. ('Gaz. Méd.' Mars, 1847.)

It will be seen that the medical evidence of identity was here made to est upon the possible disappearance of a mark from branding with a redot iron, after the lapse of eighteen years, without leaving the slightest race of its existence. This is contrary to experience, and the reasons ssigned by the assessors are unsatisfactory. Instead of furnishing any acts to show that such cicatrices from red-hot iron had disappeared within heir knowledge, they relied upon the statement of one convict that he had een branded on both shoulders, and the marks had disappeared, and upon he averment of another that he had caused the cicatrix to disappear by the pplication of a red-herring to the burnt part. It would have been a more rudent course to state that there was a want of proof of identity from hysical marks. The man, D., may have been the same as H. B., but this as certainly not proved by this negative medical evidence.

The cicatrix left by an *issue* ought not to be mistaken for a cicatrix aused by a *seton*. In the first place, it is single, depressed below the level f the skin, and rounded in its margin; and, as in all cases in which the utis is destroyed, it remains indelible. It is impossible by any process to estore to the skin its uniformity of surface. A *seton* leaves two cicatrices nd a hard band of lymph between the two.

The cicatrices left as a result of the application of the true *vaccine* ymph have an irregular honeycombed appearance with white streaks, and s slightly depressed below the level of the surrounding skin. The spurious accine mark is of a reddish colour, not depressed, and not presenting the oneycombed appearance and white streaks of the cicatrix of the true ustule. The scars produced by *small-pox* are in the form of deep depresions, showing a complete destruction of the cutis.

The cicatrices of wounds from the performance of *surgical operations* are ommonly well indicated by their regular form and their situation. They nay present the characters of punctured or incised wounds, or of a division f parts for the removal of tumours. The cicatrices are commonly marked

by great regularity. The identity of a living person, or of a dead body, may be proved by the existence of a cicatrix which has been the result of a surgical operation. Such cicatrices, when they have involved the true skin, do not disappear.

A trial took place at the Cent. Crim. Court in 1834, in which Carpue was able to rescue a man, who was wrongly charged with being a convict and with having unlawfully returned from transportation. A certificate was produced, dated in 1817, of the conviction of a person, alleged to be the prisoner, under the name of *Stuart*. The governor of the gaol in which Stuart was confined believed the prisoner to be the person who was then in his custody. The guard of the hulks to which Stuart was consigned from the gaol, swore most positively that the prisoner was the man. On the cross-examination of this witness, he admitted that the prisoner Stuart, who was in his custody in 1817, had a wen on his left hand; and so well marked was this, that it formed a part of his description in the books of the convict hulk. The prisoner said his name was *Stipler:* he denied that he was the person named Stuart, but from the lapse of years he was unable to bring forward any evidence. The counsel for the defence requested to be permitted to put a question to an eminent surgeon, Carpue, who happened accidentally to be present in court. He deposed that it was impossible to *remove such a wen as had been described without leaving a mark or cicatrix.* Both hands of the prisoner were then examined, but no wen, nor any mark of a wen having been removed by a surgical operation, was found. Upon this the jury acquitted the prisoner.

A man may allege, in proof of his identity, that at a former period of his life he was bled in the arm, foot, or temporal artery, that he had undergone cupping, or that he had had a seton or issue in his arm. The simple questions for a medical witness will then be—are the marks of bleeding or cupping present? Are they visible in the situations in which such operations are usually performed? And if present, are they such cicatrices as would be likely to result from the alleged operations? If not visible at the time of examination, is it, or is it not, probable that they may have spontaneously disappeared by lapse of time? These simple questions may carry with them momentous issues, either in a civil or a criminal case. With regard to *cupping*, when the operation is properly performed, the numerous small and slightly elliptical cicatrices are well indicated by their whiteness and symmetrical position. The cicatrix left by the use of the lancet in *bleeding* from a vein in the arm or foot, is similar to that of cupping, white, linear, slightly elliptical, with its length in the direction of the vessel, and not across it. Fifty years ago, bleeding was a frequent operation, the same person requiring to be bled at spring and fall. The cicatrix that resulted was always perceptible; in some instances, when the person had been bled in or near the same part of the vein, a hard or knotted white cicatrix was produced, raised above the level of the skin. There is reason to believe that such a mark, involving as it does the whole cutis, very rarely disappears. Beck quotes the case of a child, which had been bled in the right arm when sixteen months old. When nearly four years old the child was lost, and two years subsequently, the godmother, seeing two boys pass, was struck with the voice of one of them; she called him to her, and was convinced that it was her lost godson. The identity was also considered to be proved by the discovery of a cicatrix from bleeding in the right arm, and a cicatrix from [illegible] abscess in the left knee, both of which were present in the lost child [illegible] in the one that was found. The latter, however, had [illegible] of the small-pox, while no marks of this kind were [illegible] former. The child was claimed by a widow (*Table*[illegible] deposed that

it was really her son. The Court decided in her favour, chiefly on the ground that the lost child was not marked with the small-pox ('Med. Jour.' vol. i. p. 655).

It was admitted that this child had, on the arm and knee, cicatrices similar to those which were known to exist in the one that was missing; and had the medical witnesses agreed about the causes of them, it is probable that the decision would have been different. The cicatrix at the knee was ascribed to the use of caustics by some of the surgeons, and to a slight tumour or abrasion by others. The widow Labrie admitted that her child had never been bled in the arm, while the missing child had certainly undergone this operation; but on the question of the presence of a cicatrix from bleeding, there was a conflict of medical opinion. Three surgeons examined the cicatrix, and declared that it had been made with a sharp instrument. Others deposed that it was not a cicatrix from bleeding, but from the opening of an abscess. As the child had been missing two years, it might have had small-pox in the meantime.

According to Casper, the cicatrix left by venesection may sometimes disappear, although he adduces no fact in proof of this ('Ger. Med.' vol. 1, p. 113): *ordinary* surgical experience is against it. Devergie states that every wound which involves the thickness of the skin, leaves a cicatrix which is indelible. ('Méd. Lég.' vol. ii. p. 217.) According to him, it may become less distinct by time, but it never disappears. (See *Reg.* v. *Castro*, p. 622.)

Independently of cicatrices from local injury, these cases of identity may present other physical signs, such as *moles*, *nævi materni*, and other congenital defects to which ordinary witnesses may be able to testify. There can be no fallacy of memory touching the form, size, and position of such marks, and they differ from cicatrices in this, that they cannot be artificially imitated. They may, it is true, be removed, but only by actual cautery or caustic applications. If thus removed, a cicatrix is left which is indelible. A case is reported by Beck in which a girl, *Salomé Muller*, had been sold as a slave, but her identity as the child of German parents, was proved after fifteen years, by two marks resembling moles about the size of coffee-grains, on the inside of the thighs. They were proved to have existed in the child, and they were proved to exist in the same parts of the body of the girl eighteen years afterwards. After much litigation she was, upon this evidence, pronounced to be a free woman. ('Med. Jur.' vol. i. pp. 662.)

Coloured cicatrices. Tattoo marks.—Small punctured wounds made into the true skin with needles dipped in colouring matter, leave marks which may or may not be indelible, according to the mode in which the operation is performed. The subject of tattooing has been noticed by medical jurists. It has been made use of as evidence in cases of disputed identity. (Tardieu, 'Ann. d'Hyg.' 1855, 1, 171; Horteloup, Ibid. 1870, vol. 2, p. 440; and Casper's 'Ger. Med.' vol. 1, p. 115.) The colours commonly employed in tattooing are indigo, charcoal (gunpowder), China-ink, and vermilion. Although China-ink and charcoal are black, the effect when introduced into a white skin is to produce, with either, a blue or blueish-coloured mark. The foreign matter thus introduced mechanically into these minute punctured wounds causes inflammation, but this soon passes off, and the colouring matter then remains permanently encysted in the substance of the cutis, or below it. It has been there found after death.

These coloured marks are not necessarily indelible. They have, however, been observed to remain for fifty years and upwards, when the colouring matter was carbonaceous; and for forty years in a case in which red

cinnabar was used; but it is not so much from the lapse of time as from other accidental causes, that the marks may become faint and ultimately disappear. The depth in the cutis to which the needles have been carried, and the nature of the colouring matter employed, are the chief circumstances on which the durability of these marks will depend. The red colours are the most disposed to fade, while the black, especially that of China-ink, is among the most persistent. The thinner the skin, and the less the depth to which the needles have penetrated, the more readily do these marks fade and disappear. Something also must be set down to the skill and experience of the operator. Casper states that while he has seen the tattoo-marks remaining in some cases after forty years and upwards, in two instances they had entirely disappeared after thirty-six and thirty-eight years respectively. (Op. cit. p. 116.) It is possible to remove these marks by caustic applications, or by the actual cautery, but such an act is necessarily indicated by the production of cicatrices; for if the tattooing is complete, the removal can be effected only by the destruction of the cutis. In one instance of attempted removal, a fatal result followed. ('Ann. d'Hyg.' 1855, 1, 199.)

On the occasion of the second trial of the claimant of the Tichborne estates (*Reg.* v. *Castro*, Q. B. 1873), the possibility of the effacement of tattoo-marks became a prominent question. It was well known that the missing baronet had been tattooed along the whole length of the forearm. The claimant had no tattoo-marks, nor any signs of tattooing; but above the left wrist there was a large scar, as if a piece of the skin had been cut or burned out. Ferguson and Holt stated that nothing will remove a tattoo-mark short of the knife or a cautery. The man, Orton, with whom the claimant was endeavoured to be identified, was said to have had the letters 'A. O' tattooed on his arm. Evidently a clumsy attempt had been made to obliterate the implicating letters 'A. O.' on the wrist.

When was the wound inflicted?—In bodies long dead, there may be some difficulty in distinguishing the effects of gangrene in a wound from those of putrefaction. Gangrene implies the death of a part in the living body, and putrefactive changes take place in the dead part, as in the entire dead body. If changes resembling those of gangrene are found in a wounded limb, while the rest of the body is not in a putrescent state, there may be some reason for the opinion that there was gangrene during life. In this case, however, due allowance should be made for the more rapid decomposition of wounded parts. The best evidence will be that which shows the actual condition of the injured part in the living body. If putrefaction is advanced, the opinion of a person who has not seen the deceased while living can be little more than a conjecture.

The time at which a severe *contusion* has been produced may be commonly determined by noting the changes of colour which take place around it. It is rarely until after the lapse of twenty-four or thirty-six hours that these changes of colour appear. (See Ecchymosis, *ante*, p. 491.) The livid circumference passes into a green circle, which is gradually diffused into a wide straw-yellow band, bounding the ecchymosis on every side, if it be in a loose part of the skin. In four, five, or six days, the dark livid colour slowly disappears from the circumference to the centre, while the coloured bands spread more widely around. A central dark spot may be perceived after ten days or a fortnight, and in an extensive ecchymosis it is some weeks before all traces of colour are lost. The rapidity of these changes will be modified by circumstances elsewhere stated. Observations of this kind often lead to useful results when proper caution has been taken. The appearances presented by a contusion inflicted recently before death, and of another inflicted some days before, are of course different.

By the aid of these facts we may have it in our power to determine whether two wounds found on a dead body were or were not inflicted at or about the same time. The law in these cases seldom requires a precise medical opinion; indeed, it would be scarcely possible to give this under any circumstances. If a medical witness can only state *about* what time the injury was inflicted, circumstantial evidence will make up for the want of great medical precision or accuracy on the point.

How long did the wounded person survive?—This question is indirectly connected with the preceding, although sometimes put with an entirely different object. Supposing the wound not to have been such as to prove rapidly fatal, the length of time which a person has survived its infliction may be determined by noting whether it has undergone any reparative changes, and in what degree. As a wound remains unchanged in appearance for eight or ten hours after its production, it is not possible to say within this period how long the person may have survived. It has been supposed that a medical opinion might be formed from the nature of the injury and the parts which it has involved. Thus, a wound may have involved large blood-vessels, or organs important to life; in this case it is pretty certain that the wounded person must have died speedily. Yet these so-pronounced rapidly mortal wounds sometimes do not prove fatal until after the lapse of some hours or days—a fact which has been much overlooked.

CHAPTER 46.

FACTS INDICATIVE OF VOLITION AND LOCOMOTION—INJURIES TO THE HEAD NOT IMMEDIATELY FATAL—WOUNDS OF THE HEART NOT IMMEDIATELY FATAL—WOUNDS OF THE CAROTID ARTERIES—LOCOMOTION AFTER RUPTURES OF THE DIAPHRAGM AND BLADDER—SUMMARY.

Facts indicative of volition and locomotion.—In cases of death from wounds criminally inflicted, it is often a matter of inquiry, whether a person could have performed certain actions, or have moved after receiving an injury which is commonly regarded as necessarily mortal, and likely to destroy life speedily. In respect to wounds of a less grave description, if we except those affecting the limbs directly, which will be hereafter considered, the power of willing and moving in the person who has received them cannot be disputed. A few cases of severe injuries to important parts or organs, which are usually considered to destroy life rapidly, will be treated of. The question relative to the power of exercising volition and locomotion, has been chiefly confined to those cases in which there were injuries to the heart, wounds of the head, the large blood-vessels, the diaphragm, and bladder.

Cases frequently occur, where a patient who had received a blow on the head has survived several hours or days; and after death, such injury to the cranium has been found as would, if the person had been seen only when dead, have probably given rise to a medical opinion that he must have died instantly. On the other hand, a person may fall lifeless from a blow which would produce no appreciable physical changes in the cranium or its contents; yet in this case, if the facts had been unknown, it would have been said the person might have survived some hours or days. Thus we see that it is by no means easy to determine, from an examination of a wound in a dead body, how long the person lived after its infliction. But

it must not be understood that an opinion on this subject is never to be expressed from the nature and extent of an injury, but what should be impressed upon a medical jurist is, that it must not be hastily given. A wound may be mortal, but it by no means follows that it should have destroyed life instantaneously. A man is found dead in his chamber with his throat cut, and the incision is proved to involve one or both carotid arteries. The medical inference is that he must have fallen dead on the spot, and that he could not have survived an instant. If this be true, the weapon ought, of course, to be found either in the hand of the deceased or close to his body; but it is lying in another room, and there are marks of blood between the two rooms. What, then, is the conclusion? Either that the medical opinion is erroneous, and the deceased could not have dropped down dead *instantly*, or that he must have been murdered. Unless circumstances tend to expose the error of the medical statement, irreparable injury may be done to an innocent person. The medical opinion has always given way when circumstances refuting it appeared: but it is the duty of a medical jurist to profit by such errors, and to apply his opinions with greater caution to similar cases.

Injuries to the head not immediately fatal.—A boy, owing to the bursting of a gun, had the breech-pin lodged in his forehead. He got out of a cart, in which he had been brought four or five miles, and walked into the hospital without assistance. The pin was firmly impacted in the frontal bone about the situation of the longitudinal sinus. On its removal, a portion of brain came away with several pieces of bone, and the aperture in the cranium was nearly an inch in diameter. Symptoms of coma then came on, and the boy died in forty-eight hours. The brain was found to be considerably injured. ('Med. Gaz.' vol. 18, p. 458.) Watson mentions a similar case. During a quarrel between father and son, the latter threw a poker at the former with such violence that the head of the poker stuck fast in his forehead, and was with some difficulty withdrawn. The father asked those who were near him to withdraw the weapon, and he was afterwards able to walk to the infirmary. He died from inflammation of the brain. ('On Homicide,' 62.) A case occurred to Wallace in which a man fell from a scaffold on the summit of his head. He was stunned by the fall, but on reaching the hospital, dismounted from the car which conveyed him, and walked upstairs with very little assistance. He died in three days, but he remained perfectly rational, and was enabled to get up and go to the water-closet the day before his death. On inspection, there was only a slight abrasion on the summit of the head, but the skull was found split into two nearly equal halves from the frontal bone backwards, and the longitudinal sinus was laid open throughout. In the hemispheres of the brain there was a large quantity of effused blood in a semi-coagulated state, and more than two ounces were found at the base of the skull. ('Lancet,' April, 1836.) Supposing this person to have been found dead with such extensive injuries, the medical opinion would probably have been that he was not likely to have lived or moved afterwards; and yet the power of volition and locomotion remained with him for two entire days. (See case, p. 508.)

A boy met with an accident while firing a pistol. The pistol burst, and there was no doubt that the breech had entered the brain, although it could be nowhere perceived. The boy remained sensible for two days; and although some amendment took place, he died twenty-four days after the accident. The breech of the pistol, weighing nine drachms, was found lying on the tentorium, and the brain was much disorganized. ('Lancet,' July, 1838.) In this case the boy was shot completely through the brain, a heavy mass of iron having traversed that organ, but he was not even

rendered insensible by so serious a wound. (See also 'Med. Gaz.' vol. 36, p. 38.) The medical opinion, in an abstract question of this kind, is commonly based on individual experience; but the real question is, not whether the witness himself has seen such a case, but whether such a condition of things is medically possible. A witness is allowed to express an opinion from general professional knowledge and experience.

A man was found dead in a stable with a severe fracture of the temporal bone, which had caused a rupture of the middle artery of the brain. A companion was accused of having murdered him, but he alleged that the deceased had fallen from his horse the day before, and had thus met with the accident. It appeared, however, that after the fall, the deceased had gone into a public-house before he returned to the stables, and had remained there some time drinking. The question respecting the guilt of the accused party rested upon the fact whether, after such an extensive fracture of the skull with extravasation of blood, it was possible for a man to do what the prisoner had represented the deceased to have done. Wallace gave, very properly, a qualified opinion; he said it was improbable, but not impossible, that the deceased could, after receiving such an injury, have walked into and drunk at a public-house. The extravasation was here the immediate cause of death, and probably this did not take place to the full extent, except as a consequence of the excitement from drink.

A man may fall from a height, and produce a severe compound fracture of the skull. He may, nevertheless, be able to rise and walk some distance before he falls dead. The discovery, after death, of severe injury to the head, with great effusion of blood on the brain, must not lead a surgeon to suppose that the person who sustained the violence had been immediately incapacitated. In *Reg.* v. *Milner* and others (Derby Sum. Ass. 1854), in which a Mr. Bagshawe had been assaulted by the prisoners and had died from the injuries sustained, it was proved that the temporal bone was beaten in, the base of the skull fractured, and there was a large coagulum of blood effused on the left side of the brain, which by its pressure had flattened this organ. Notwithstanding these injuries, the deceased walked a considerable distance, and he survived about twelve hours.

Wounds of the heart not immediately fatal.—Every penetrating wound of the heart was formerly considered to be instantaneously mortal, and the usual medical opinion at coroners' inquests was that a person so wounded must have dropped down dead on the spot. More accurate observations have, however, shown that this is an erroneous doctrine. The *Duc de Berri*, who was murdered in Paris in 1820, survived eight hours after having received a wound in the left ventricle of the heart. When the cavities of the heart are extensively laid open, death is likely to be an immediate result; but persons who have sustained wounds of this organ have frequently lived sufficiently long to exercise the power of volition and locomotion. Watson met with a case in which a man who had been stabbed in the right ventricle ran *eighteen yards* after having received the wound. He then fell, but was not again able to rise; he died in six hours. On dissection, it was found that a punctured wound had extended into the right ventricle in an obliquely transverse direction, dividing in its course the coronary artery. The pericardium was nearly filled with blood, and about four pounds were effused on the left side of the chest. ('On Homicide,' p. 98.) A remarkable case of the preservation of volition and locomotion after a severe wound of the heart will be found reported in the 'Med. Gaz.' (vol. 14, p. 334). In this case the patient, a boy, survived five weeks, and employed himself during that period in various occupations. *After death* a mass of wood was found lodged in the substance

of the heart. Had this boy been found dead with such an injury, it is most probable the opinion would have been that his death was instantaneous. Darling, of New York, had a case which occurred in 1855, in which a man survived for a period of *eleven days* a bullet-wound of the heart. Soon after receiving the wound he became senseless, cold, and pulseless, and remained in this collapsed state for four hours. He then rallied, but died on the eleventh day. On inspection, there was no effusion of blood: the pericardium was much distended with serum, the result of inflammation. A bullet, one-third of an inch in diameter, was found lodged in the fleshy partition between the right and left ventricles, about midway between the apex of the heart and base of the ventricles. There was no communication with the cavities—the wound had entirely cicatrized; and inflammation of the pericardium was obviously the cause of death. Some years ago, a man was admitted into Guy's Hospital who survived twenty-four hours after the infliction of a penetrating wound of the left ventricle.

The keeper of a brothel was tried in Glasgow, in the year 1819, for the murder of a sailor, by shooting him through the chest. The auricles and part of the aorta next to the heart were 'shattered to atoms,' by the slugs and brass nails with which the piece was charged; and in the opinion of the medical witnesses, the deceased must have dropped down dead on the moment that he received the shot. The body was found in the street, and the door of the prisoner's house was *eighteen feet* up an entry; so that it followed, if the medical opinion was correct, that the prisoner must have run after the deceased, and shot him in the street. For the prisoner it was urged, and proved, that he had shot the deceased through the door of his own house, which the latter was attempting to enter by force. Besides direct testimony to this effect from those within the house, and from a lad who was with the deceased at the time, it was proved that there was a stream of blood from the door of the house to the spot where the body lay, which could not have flowed from the body towards the house, as the threshold of the door was on a higher level than the pavement of the street. On this evidence, the prisoner was acquitted. If, by the heart 'being shattered to atoms,' we are to understand that its cavities were entirely laid open, and its substance destroyed, we have a description of wound which most professional men would not hesitate to pronounce instantaneously mortal. Although nothing is stated on the point, yet we must suppose it was proved before the question of survivorship was raised, that the body of the deceased could not have been dragged after death from the door of the prisoner's house to the spot where it was found; a circumstance which would have sufficed to account for the presence of a stream of blood, notwithstanding the difference of level between the street and the door of the house. The jury found that, in spite of the severe wound, the deceased had had the power to run into the street, after having been shot through the door of the prisoner's house.

In 1854, an Italian, æt. 38, discharged a brace of pistols into his chest on the left side. The man was brought into Guy's Hospital, and was able to converse on his condition, and lived one hour and fifteen minutes after the infliction of the wound. After death it was found that one bullet had perforated the pericardium, entered the right ventricle, and, after traversing the septum of the ventricles, made its exit from the heart at the junction of the left auricle with the ventricle. It traversed the upper lobe of the left lung, and was found fixed in one of the vertebræ of the back. The second bullet perforated the left ventricle, and then traversed the left lung. This wound was of such a nature that, at every contraction of the ventricle, the opening must have been closed so as to arrest the flow

of blood. This man, owing to severe suffering, rolled about the floor, and was with difficulty kept quiet. It will be seen that in this case there were bullet-wounds traversing completely the cavities of the heart; yet the man could talk and exert himself, and he actually survived their infliction *one hour and a quarter*. Had the body been found dead in a suspicious locality, the discovery of such wounds in the ventricles of the heart might probably have led to a hasty medical opinion that the death of the man must have been instantaneous. In these cases, little or no blood probably escapes from the heart in the first instance, but it may afterwards continue to ooze gently, or suddenly burst out in fatal quantity. It must not, therefore, be supposed, when a person is found dead with a wound of the heart, attended with abundant hæmorrhage, either that the flow of blood took place in an instant, or that the person died immediately and was utterly incapable of exercising any voluntary power. Only one condition will justify a supposition of this kind; namely, when the cavities of the organ are largely laid open. This remark applies especially to wounds of the auricles, which have but little contractile power.

Wound of the carotid arteries not immediately fatal.—Questions relative to the power of locomotion perhaps more frequently occur with respect to wounds of the great blood-vessels of the neck than of the heart—suicide and murder being more commonly perpetrated by the infliction of such wounds. Wounds of the carotid arteries are often pronounced *instantaneously* mortal. It occasionally comes out on inquiry that, if such a wound had been instantaneously mortal, then, in defiance of rational probability, or of the strongest presumptive evidence to the contrary, the deceased must have been murdered. An opinion of this kind has not only been refuted by circumstances, but by the evidence of eye-witnesses. A medical witness is then compelled to admit that his rules for judging of the mortality of wounds are wrong, and that the person may have survived for a longer or shorter period. There are several cases on record which show that wounds involving the common carotid artery and its branches, as well as the internal jugular vein, do not prevent a person from exercising voluntary power, and even running a certain distance. In 1863, a man committed suicide by cutting his throat. The external carotid artery and the jugular vein on the right side were cut through, and a large quantity of blood was lost. The wound extended from the front of the angle of the right jaw to near the windpipe, which was not wounded. The man survived half an hour, but he was speechless and insensible. The bleeding had been partly stopped by a cloth thrust into the wound. It was left doubtful by the evidence whether this wound was inflicted by himself or by another. In a case of murder, perpetrated at Kingston in 1831, it was proved by medical evidence that the deceased had died from a wound in the throat, involving the right carotid artery, jugular vein, and windpipe. The wound had been inflicted while the woman was lying in bed. Her body was found in an adjoining room, and the circumstances showed that, after receiving the wound, she had been able to rise from her bed, and to stagger or run to the distance of about six feet. In the case of *Rex* v. *Danks* (Warwick Lent Ass. 1832), it was proved that the deceased had died from a wound in the throat inflicted by the prisoner, which divided the trunk of the carotid artery, the principal branches of the external carotid, and the jugular veins. The evidence rendered it probable, if not certain, that, after the infliction of this wound, the deceased had been able to run twenty-three yards and to climb over a gate—the time required for the performance of such acts being at least from fifteen to twenty seconds. Most medical witnesses would have probably given an opinion that the deceased could not have moved from the spot where *such* a wound had been inflicted; but it was clear that she

of the heart. Had this boy been found dead with such an injury, it is most probable the opinion would have been that his death was instantaneous. Darling, of New York, had a case which occurred in 1855, in which a man survived for a period of *eleven days* a bullet-wound of the heart. Soon after receiving the wound he became senseless, cold, and pulseless, and remained in this collapsed state for four hours. He then rallied, but died on the eleventh day. On inspection, there was no effusion of blood: the pericardium was much distended with serum, the result of inflammation. A bullet, one-third of an inch in diameter, was found lodged in the fleshy partition between the right and left ventricles, about midway between the apex of the heart and base of the ventricles. There was no communication with the cavities—the wound had entirely cicatrized; and inflammation of the pericardium was obviously the cause of death. Some years ago, a man was admitted into Guy's Hospital who survived twenty-four hours after the infliction of a penetrating wound of the left ventricle.

The keeper of a brothel was tried in Glasgow, in the year 1819, for the murder of a sailor, by shooting him through the chest. The auricles and part of the aorta next to the heart were 'shattered to atoms,' by the slugs and brass nails with which the piece was charged; and in the opinion of the medical witnesses, the deceased must have dropped down dead on the moment that he received the shot. The body was found in the street, and the door of the prisoner's house was *eighteen feet* up an entry; so that it followed, if the medical opinion was correct, that the prisoner must have run after the deceased, and shot him in the street. For the prisoner it was urged, and proved, that he had shot the deceased through the door of his own house, which the latter was attempting to enter by force. Besides direct testimony to this effect from those within the house, and from a lad who was with the deceased at the time, it was proved that there was a stream of blood from the door of the house to the spot where the body lay, which could not have flowed from the body towards the house, as the threshold of the door was on a higher level than the pavement of the street. On this evidence, the prisoner was acquitted. If, by the heart 'being shattered to atoms,' we are to understand that its cavities were entirely laid open, and its substance destroyed, we have a description of wound which most professional men would not hesitate to pronounce instantaneously mortal. Although nothing is stated on the point, yet we must suppose it was proved before the question of survivorship was raised, that the body of the deceased could not have been dragged after death from the door of the prisoner's house to the spot where it was found; a circumstance which would have sufficed to account for the presence of a stream of blood, notwithstanding the difference of level between the street and the door of the house. The jury found that, in spite of the severe wound, the deceased had had the power to run into the street, after having been shot through the door of the prisoner's house.

In 1854, an Italian, æt. 38, discharged a brace of pistols into his chest on the left side. The man was brought into Guy's Hospital, and was able to converse on his condition, and lived one hour and fifteen minutes after the infliction of the wound. After death it was found that one bullet had perforated the pericardium, entered the right ventricle, and, after traversing the septum of the ventricles, made its exit from the heart at the junction of the left auricle with the ventricle. It traversed the upper lobe of the left lung, and was found fixed in one of the vertebræ of the back. The second bullet perforated the left ventricle, and then traversed the left lung. This wound was of such a nature that, at every contraction of the ventricle, the opening must have been closed so as to arrest the flow

ing, as the aperture was cicatrized and the omentum adhered to it. The existence of this injury was quite unexpected, and, at the time of admission, there was nothing to interfere with locomotion and exertion except the injury to the ankle. ('Guy's Hosp. Rep.' 1838, p. 368.)

Ruptures of the liver, spleen, or kidneys, unless attended at once with great loss of blood, do not prevent a person from exercising muscular power. In the case of *Gordon* (Glasgow Spring Circ. 1856), it was proved that the deceased had died from ruptured liver; but, after sustaining the violence, he had been able to reach home on foot, although with some difficulty. This question of survivorship in reference to ruptured liver, and the time required for fatal effusion of blood to take place, may often have an important bearing in a charge of murder. (See post, *Reg. v. Phillips*, Liverpool Wint. Ass. 1863.)

Ruptures of the bladder.—In ruptures of the *bladder*, attended with extravasation of urine, a question may arise respecting the retention of the power of locomotion. The following cases will show that this power does sometimes exist, although the general result is, perhaps, to incapacitate the person from moving. A man, æt. 31, while intoxicated, received a blow on the lower part of his abdomen. He was sobered by the accident, and walked home, a distance of a quarter of a mile, although suffering severe pain. When seen in the evening, twelve ounces of bloody urine were drawn off by a catheter, and he complained of having felt cold immediately after he had received the blow. He died four days after the accident. On inspection there was no mark or ecchymosis on any part of the abdomen. The bladder was ruptured in its upper and back portions for about an inch. ('Lancet,' May 14, 1842.) A gentleman who had been compelled to retain his urine, fell accidentally, in descending a staircase, with the lower part of his abdomen against the edge of one of the steps. The sense of fulness in his bladder immediately ceased, and he walked to a friend's house to dinner. The nature of the accident was mentioned to a surgeon there present, who immediately suspected that the bladder must have been ruptured. The case terminated fatally in twenty-four hours. A case is reported, in which a man walked a distance of two miles after having sustained a rupture of the bladder; and in another, the man, who sustained the injury in a scuffle, was able to walk between two and three hours after the occurrence. (See also 'Lancet,' Oct. 31, 1846, p. 480.) Thus, then, from these various instances, it is evident that locomotion and muscular exertion may take place after an accident of this description. The medico-legal relations of this subject will be apparent from the following case, reported by Syme. A man passed some hours convivially with a few friends, after which a quarrel ensued, blows were exchanged, and the parties wrestled with each other. The deceased then walked home, a distance of more than a mile; and in crossing the threshold of his own door he fell forwards on his abdomen. When lifted up he complained of great pain, and was put to bed, being quite unable to exert himself. He died in two days, and upon dissection the bladder was found ruptured at its upper part (fundus) to the extent of between two and three inches. Under these circumstances, it became a question whether the rupture was caused by the violence of his companions, or by the accidental fall at the door of his own house. If by his companions, he must have walked more than a mile with his bladder ruptured; but two medical witnesses declared that he could not have walked this distance after the rupture, and consequently that it must have been occasioned by the subsequent fall. The symptoms of rupture and extravasation of urine occurring immediately after the fall rendered it highly probable that this accident was really the cause. At

the same time it is obvious that the power of locomotion may be exerted under such circumstances to a much greater extent than is commonly supposed.

The question is sometimes restricted to the mere possibility of *survivorship for a given period* without active exertion. If the power of locomotion is retained under severe injuries to important organs, there can be no difficulty in supposing that life may continue for a longer or shorter time when the person remains in a quiescent state. Tardieu reported a case in which, under attempted abortion, the uterus was excessively lacerated, and the greater part of the small intestines had been torn away. These injuries had caused a great loss of blood, but the woman is stated to have lived three-quarters of an hour, and to have cried out during that time. Some medical witnesses thought that such violence could not have been sustained without leading to immediate death. A review of the facts, however, and an examination of parallel cases, satisfied Tardieu that the deceased might have survived and cried out in the manner deposed to by the witnesses. ('Ann. d'Hyg.' 1848, 1, 157.) The cases contained in this chapter fully corroborate the opinion formed by Tardieu. A witness must always be prepared to make full allowance for acts indicative of life in persons severely wounded.

Under survivorship from severe accidents or personal injuries, this power of moving, if not exerted to a large extent, may take place in a small degree; and this may become occasionally a material question in legal medicine. Thus it must not be lost sight of when we are drawing inferences as to the relative position of an assailant and a murdered person from the situation in which a body is found. A dead man, with a mortal injury to the head or heart, may be found lying on his face, when he actually fell upon his back, but still he might have retained sufficient power to turn over before death; or he may have fallen on his face, and have afterwards moved, so that his body may be found lying on the back. A slight motion of this kind is very easily executed; it does not always depend on volition. Individuals suffering from severe concussion have been frequently known to perform acts unconsciously and automatically. The cases above related may perhaps be considered rare, and as exceptions to the general rule. The medical jurist must bear in mind, however, that he is not required to state in how many, out of a given number of persons similarly wounded, this power of performing acts indicative of volition and locomotion may remain, but simply whether the performance of these acts is or is not *possible*. It is on this point only that the law requires information. The hypothesis of guilt, when we are compelled to judge from circumstances in an unknown case, can only be received on the exclusion of every other reasonable explanation of the facts. On surgical opinions or treatment, such cases, from their rare occurrence, may have little influence; but in legal medicine the question is widely different. Medical facts, however rare, here admit of a very important and unexpected application.

Struggling after severe wounds.—Although, in cases of severe wounds, we may allow that persons may survive for a sufficiently long period to perform various acts of volition and locomotion, yet the presence of a mortal wound, especially when of a nature to be accompanied by a great loss of blood, must prevent all *struggling* or violent exertion on the part of the wounded person; such exertion we must consider to be quite incompatible with his condition. A medical jurist may thus have it in his power to determine whether a mortal wound found on the deceased has been inflicted for the purpose of murder, or in self-defence. A man was tried (Lancaster Ass. in 1834), for the murder of a woman at Liverpool, by

ıbbing her in the chest. The prisoner and the deceased, with two other ımen, were quarrelling in the passage of a house. A struggle ensued tween the prisoner and the deceased, which one of the witnesses said lasted · *ten minutes*. When the prisoner had reached the door, he pulled out a ife and stabbed the deceased in the chest. She fell, and died almost mediately. The prisoner alleged that he was attacked by several persons, d that he stabbed the woman in self-defence. The judge said if the blow d been struck with premeditation before the struggle, the crime would murder—if during the struggle, it would be manslaughter. The ıdical evidence showed that the blow could not have been struck before › struggle, because it was of a speedily mortal nature; and the deceased uld not then have been able, as it was deposed to by the witnesses, to uggle and exert her strength with the prisoner for *ten minutes* after-rds. This being the case, it followed that, in all probability, the ceased had received the wound towards the conclusion of the quarrel; d therefore it might have been inflicted while the prisoner was attempt-ş to defend himself. The jury returned a verdict of manslaughter.

A case involving this question was tried at the Gloucester Lent sizes, 1843 (*Reg.* v. *Hobbs*). The prisoner was indicted for the wilful urder of a man with whom he had been drinking and quarrelling. It pears that in the early part of the quarrel the deceased threw the soner down and struck him. The deceased was told by the landlord of › inn to go home. He replied 'Very well,' and then, leaving the soner, went through the entrance-arch of the inn up the yard. In ut *seven minutes* the deceased, who had complained to the landlord of › maltreatment which he had undergone, returned into the inn-yard, l was seen, on entering it, to pull down his waistcoat and button his t. A witness advised him to go home, and he left the spot. A short ıe afterwards he was found at the back of the yard, lying dead on his e. On examining the body it was ascertained that the deceased had m stabbed in two places, one of the stabs having penetrated a ventricle the heart. On apprehending the prisoner, a large clasp-knife was found his pocket stained with blood. The prisoner admitted that he had bbed the deceased, but said it was *during the quarrel*, and that he had d the knife in self-defence while they were on the ground. This was › defence. For the prosecution it was contended that the deceased had m stabbed by the prisoner subsequently to the quarrel—that he had ıe through the gate into the yard to meet the deceased, had there bbed him, and had caused his instant death. A medical witness who s called, stated at first that from such a wound death must have been *tantaneous*. In cross-examination, however, he admitted that the ceased might have lived some time after he had been stabbed; and on s evidence the prisoner was convicted of manslaughter, and sentenced six months' imprisonment. The medical facts of this case are imperfectly ıorted: hence it is difficult to give a decided opinion respecting the ıe at which the deceased was stabbed in the heart. The size of the b in the ventricle is not stated; nor is it in evidence whether any od was found on the spot where the deceased was struggling with the soner. That the deceased should have struggled with the prisoner for › minute after he had been stabbed in a ventricle of the heart, is contrary medical experience and probability. It is also irreconcilable with › existence of such a wound, that the deceased should have been stabbed the heart without knowing it, or without being aware of his condition—t he should have been able thereafter to walk away through the inn-d to the house, and survive seven minutes while thus walking. Taking › facts as *reported, it appears* that it is probable that the deceased was

stabbed by the prisoner subsequently to the quarrel, while he was walking in the inn-yard. The only circumstances in favour of the defence were the prisoner's statement, and that, in some rare cases, certain wounds of the heart do not prove immediately fatal.

In the case of *Reg.* v. *E. M. Brown* (Dorchester Sum. Ass. 1856), the prisoner was charged with the murder of her husband by blows on the head while in her room. Her statement was that the violence on the head was produced by the kick of a horse. The medical evidence showed that the bones of the nose were broken: there was a triangular wound exposing the bone above the left eyebrow, another triangular wound exposing the bone at the top of the head, and a third wound at the back of the head. The left ear was perforated; and behind it was a long wound divided into two. The frontal bone was fractured from the orbit through the parietal into the occipital bone. Seven pieces of bone, varying in size from half an inch to three inches, had been driven into the brain, and a large quantity of blood was effused. The prisoner's account was that she found her husband thus wounded and bleeding outside the house, that she dragged his body into an inner room, and, further, that, though thus wounded, he held her tightly by the clothes for two hours afterwards. It was proved that there was no blood over the front of the person or dress of the deceased, and that there was no blood in the passage or in any part of the house, except in the room where the body was found lying. Further, the injuries were not such as a kick from a horse would explain; and the medical witness properly stated that a man thus injured could not have held the prisoner by the clothes for two hours, so as to prevent her from seeking earlier for assistance. These facts showed that the deceased had been killed by blows where the body was actually found. The prisoner was convicted.

CHAPTER 47.

WOUNDS AS THEY AFFECT DIFFERENT PARTS OF THE BODY—WOUNDS OF THE HEAD—OF THE SCALP—CONCUSSION—HOW DISTINGUISHED FROM INTOXICATION—EXTRAVASATION OF BLOOD—SEAT OF—AS A RESULT OF VIOLENCE, DISEASE, OR MENTAL EXCITEMENT—WOUNDS OF THE FACE—OF THE ORBIT—OF THE NOSE—DEFORMITY AS A CONSEQUENCE OF WOUNDS OF THE FACE—INJURIES TO THE SPINE—FRACTURES OF THE VERTEBRÆ—DEATH FROM INJURIES TO THE SPINAL MARROW.

THE *danger* of wounds, and their *influence in causing death*, are the two principal points to which the attention of a medical jurist must be directed.

WOUNDS OF THE HEAD.

Incised wounds, affecting the scalp, unless of great extent, rarely produce any serious effects. When the wound is contused, or accompanied by much laceration of the skin, it is dangerous in consequence of the tendency which the inflammatory process has to assume an erysipelatous character. The results of these wounds are, however, such as to set all general rules of prognosis at defiance. Slight punctured wounds will sometimes terminate fatally in consequence of inflammation, followed by extensive suppuration; while, on the other hand, a man may recover from a lacerated wound by which the greater part of the skin may have been stripped from the bone. There are two sources of danger in *wounds of the scalp*:—1.

The access of erysipelatous inflammation. 2. Inflammation of the tendinous structures, followed or not by a process of suppuration. Either of these secondary effects may be a consequence of slight or severe wounds, and prove fatal. Neither can be regarded as an unusual result of a severe wound of the scalp; but when one or other follows a slight injury, there is reason to suspect that the patient may have been constitutionally predisposed to the attack. Bad treatment may likewise lead to a fatal result from a wound not serious in the first instance, but the question how far the responsibility of an aggressor would be affected by a circumstance of this nature has been considered in another place (*ante*, pp. 608–610). Wounds of the head are dangerous in proportion as they affect the brain; and it is rare that a severe contused wound is unaccompanied by some injury to this organ. There is, however, a difficulty which a practitioner has here to contend with—namely, that it is scarcely possible to predict, from *external* appearances, the degree of mischief which has been produced within. The slightest contusions may be attended with fatal consequences, while fractures, accompanied by great depression of bone, and an absolute loss of substance of the brain, are sometimes followed by perfect recovery. ('Cormack's Jour.' Sept. 1845, p. 653; 'Med. Gaz.' vol. 39, p. 40; and 'Phil. Med. Exam.' Nov. 1845, p. 696.) Another difficulty in the way of forming a correct opinion consists in the fact, that a person may recover from the first effects of an injury, but after some days or weeks he will suddenly die; and on examination of the body, the greater part of the brain will be found destroyed by suppuration, although no symptoms of mischief may have manifested themselves until within a few hours of death. The abscess in the brain must be directly traceable to the violence inflicted. In some cases it may be formed independently of such violence. See case in 'Vierteljahrsschrift,' 1870, 2, 237. (For a medico-legal account of injuries to the head, see papers by Toulmouche, 'Ann d'Hyg.' 1859, 2, 395; 1860, 1, 143; and 1867, 1, 121.)

Concussion.—The common effect of a violent blow on the head is to produce concussion or effusion of blood, or both. Concussion is usually indicated by fainting, insensibility, or sudden death occurring immediately after the application of external violence. In concussion the symptoms come on *at once*, and the patient sometimes dies without any tendency to reaction manifesting itself. In the most severe form, the person drops at the very moment when struck, and dies on the spot. (Chelius's 'Surgery,' vol. 1, p. 408.) In other cases, he may linger in a state of insensibility for several days or weeks, and then die. In concussion there is generally more or less vomiting. It is important to remember, that neither compression nor obvious physical injury to the brain is necessary to render concussion fatal. (See p. 470; also Travers's 'Constitutional Irritation,' p. 438; Chelius's 'Surgery,' vol. 1, p. 410.) This may be entirely dependent on shock to the nervous system. After death, no particular morbid change may be discovered in the body, or there may be merely the mark of a light bruise on the head. In *Reg.* v. *Burgess* (Liverpool Lent Ass. 1845), the deceased, who was the subject of violence, fell and died on the spot, and there was no appearance of injury externally or internally. The state of insensibility observed in concussion may be only apparent. Some consciousness may be retained.

Inflammation may follow the primary shock from concussion—suppuration may take place, and the patient die after the lapse of several weeks, or even months. (See case 'Med. Times and Gaz.' June 30, 1860, p. 645.) It is important in a medico-legal point of view to notice that a person may move about and occupy himself, while apparently convalescent, for a week or ten days after recovery from the first shock, and then

suddenly be seized with fatal symptoms, and die. This apparent recovery leads to the common supposition that death must have been produced by some intervening cause, and not by the original violence to the head—a point generally urged in the defence of such cases. (See *Reg.* v. *Kelpes*, Lewes Sum. Ass. 1871.) When the inflammation that follows concussion is of a chronic character, the person may suffer from pain in the head and vomiting, and die after the lapse of weeks, months, or even years. (See p. 586; Travers op. cit. p. 445; also Hoffbauer, 'Ueber die Kopfverletzungen,' 1842, p. 57.) Concussion may sometimes take place as a consequence of a violent fall on the feet, in which case the head receives a shock through the medium of the spinal column. The skull may be thereby extensively fractured at the base, and the brain may be even shattered by such a fall. This was the cause of death in the case of the *Duke of Orleans*. ('Med Gaz.' vol. 36, p. 368.)

In *Allen* v. *the Chester Railway Comp.* (Court of Common Pleas, Feb. 1857), the plaintiff claimed damages for an injury caused by a railway collision. The evidence showed that the plaintiff received a blow on the head. There were no immediate effects; but in two days he suffered from lightness of the head and other symptoms, attributed by his medical attendant to *concussion* of the brain, as a result of the accident. Subsequently there were symptoms of injury to the spine. There was pain in the course of the spine, and partial paralysis of the bladder, rectum, and lower extremities, with loss of memory. The medical witnesses for the plaintiff attributed these symptoms to a blow received by him at the base of the skull. The defendants contended that if these were the results of concussion of the brain, they ought to have manifested themselves immediately on the occurrence of the accident; and this view was to some extent supported by the evidence of experienced surgeons. In substance, however, the medical evidence on the two sides was not conflicting. Concussion of the brain, as it is ordinarily known to surgeons, is generally attended with some *immediate* symptoms; but the witnesses for the defence properly admitted that 'a concussion of the brain (and spine?), attended with apparently slight symptoms at first, might, under peculiar circumstances, be followed by serious symptoms.' As no other cause could be assigned for the symptoms, this was practically admitting that the plaintiff had suffered from the injury, the degree being simply a question for the jury. They returned a verdict for the plaintiff.

Concussion distinguished from Intoxication.—The symptoms under which a wounded person is labouring may be sometimes attributed to *alcoholic intoxication*, and a medical witness may be asked what difference exists between this state and that of concussion. The history of the case will, in general, suffice to establish a distinction, but this cannot always be obtained. It is commonly said that the odour of the breath will enable a surgeon to detect intoxication; but it is obvious that a man may meet with concussion after having drunk liquor insufficient to cause intoxication, or concussion may take place while he is intoxicated—a combination which frequently occurs. Under such circumstances we must wait for time to develop the real nature of the case. Concussion may be so slight as sometimes closely to resemble intoxication, and from the absence of all marks of violence to the head and the existence of a spirituous odour in the breath, the medical examiner might be easily deceived. If there be no perceptible odour in the breath, the presumption is that the symptoms are *not* due to intoxication. On the other hand, intoxication may be so great as to give rise to the apprehension of fatal consequences, and the co-existence of a mark of violence on the head might lead to error in the formation of an opinion. What is the line of conduct to be pursued on such occasions?

The examiner should weigh all the circumstances, and if there be one cause for the symptoms more probable than another, he should adopt it: if there be any doubt, this should be stated to the Court.

There is nothing in the state of the brain in a dead body, which will enable a practitioner to distinguish whether concussion or intoxication had existed and had been the cause of the symptoms. The vessels may be congested in both cases. The discovery of alcoholic liquid in the stomach may lead to a presumption that deceased had been intoxicated, while marks of violence on the head may favour the view that he had suffered from concussion. When both conditions are found, the examination of the body cannot lead to a solution of the question. The answer must then depend on the special circumstances proved, and, if procurable, on the nature of the symptoms preceding death.

It is to be feared that medical witnesses are not sufficiently careful on these occasions to determine whether there are signs of intoxication about an injured person. Subsequent proceedings may render this a material part of the inquiry. Many a house-surgeon of a hospital has been severely blamed for an omission to inquire and satisfy himself whether, in addition to the results of violence, a man who has been brought into hospital has or has not been intoxicated when admitted. The question is of importance; the injuries to the head may have arisen from a fall, and a drunken man may readily meet with such injuries from accident. There can be no excuse for not making a full inquiry into the precise condition of an injured person, and arriving at the best judgment of which the case admits. A state of intoxication often renders it difficult to form an accurate opinion in a case of alleged criminal wounding; but it is always in the power of a witness to satisfy himself by close examination, the use of the stomach-pump, or simply watching the patient, whether he is in a state of drunkenness or whether he is labouring under the effects of disease or violence. In more than one instance within a recent period persons who have been struck with incipient symptoms of apoplexy in the street have been seized and locked up as drunk, and have soon afterwards been found dead or dying. Others, who have suffered from violence, have perished from neglect under a similar mistake made by a medical man or by the police. Disease of the brain, as well as injuries to the brain from violence, may give to a man a staggering gait and render him helpless: they are also commonly accompanied by stupefaction and vomiting. If it should happen that shortly before such an attack, the person has taken beer, wine, or spirits, sufficient to give an alcoholic odour either to the breath or the matter vomited, it is at once treated as a case of drunkenness, and the unfortunate person is left to his fate. The death of a *Mr. King*, in London, Oct. 1864, furnishes an instance of the necessity of a more rigorous examination of the facts on these occasions. He was pronounced by a medical man to be labouring under drunkenness, and handed over to the police. When examined by another surgeon the next morning, it was found that his skull was fractured, and that he was otherwise severely injured. He died from the effects. Two other cases of a similar kind occurred in London in the spring of 1872; and several cases have since occurred. A man who was stupified from the effects of accidental violence to the head, was sent away from a public hospital as drunk and unfit for admission. The man died the next day, and on inspection it was found that there was a fracture of the base of the skull, with great effusion of blood. It appeared that some brandy had been given to deceased soon after the accident to rouse him, and the smell of this in the breath had probably thrown the house-surgeon off his guard. It was alleged in explanation that there was no mark of external violence, and the man appeared only stupified and unable to stand.

Medical diagnosis was here greatly at fault from causes easily to be appreciated. This is by no means a solitary case.

The distinction of apoplexy from drunkenness involves greater difficulties. In these cases we have to deal with the true diagnosis of alcoholic or narcotic poisoning (p. 399). Jackson has directed attention to this medical question in a case reported in the 'Med. Times and Gaz.' 1871, 1, 360. Some instructive cases, in reference to this complication of wounds, have been published by Tardieu. (See 'Med. Gaz.' vol. 44, p. 347.)

Extravasation or effusion of blood.—A blow on the head may destroy life by causing an effusion of blood either on the surface or in the substance of the brain. In pugilistic combats, when a person is thus struck, he commonly falls, and death may take place in a few minutes. On inspection, blood may be found effused either at the base or in the ventricles of the brain, and the question will present itself—Did the injury which caused death arise from *a blow or a fall?* Two cases of this description are reported. The men were knocked down by blows with the fist, and they were taken up dead. (Cormack's 'Month. Jour.' Feb. 1846, p. 117.) It is not easy to give an answer to this question, and its relevancy in a legal view is not apparent; for as it is presumed the blow was the cause of the fall, the assailant would be responsible for the effects of either or both. In a case of this kind (*Reg.* v. *Williams*, Denbigh Lent Ass. 1856), in which deceased had received a blow and sustained a fall, and his death was clearly proved to have resulted from the violence, the judge directed the jury, if the death was caused by 'the fighting,' to return a verdict against the prisoners. They, however, persisted in returning a verdict of not guilty, assuming that the fatal injury was caused by the fall and not by the blow. A heavy blow on the head may cause at once fatal effusion of blood, but in these instances the effusion commonly arises from the violent concussion which the injured person sustains by the fall. A medical witness will therefore in general be compelled to admit that the fatal effusion might have taken place either from a blow or a fall. If the fall has resulted from accident and not from a blow, this will, of course, absolve the accused from responsibility for the fatal results.

This subject has important applications in legal medicine, for there are many cases of this description tried at the assizes. Effusion may occur from violence, with or without fracture, and it may take place without being accompanied by any external marks of injury. In the case of *The Queen* v. *Phelps* and others (Gloucester Aut. Ass. 1841), it was proved that there was great effusion of blood, and even laceration of the brain, without corresponding external injuries on the deceased. (See also at the same Assizes, the case of *The Queen* v. *Thomas.*) A person received a blow from a small stone, and died in ten minutes. On examination there was no external bruise or fracture of the bones: the ventricles of the brain were filled with coagulated blood, and all the vessels were gorged with blood. It was observed that the skull was in this instance unusually thin. The chief source of the effusion in violence to the head arises from a rupture of the meningeal artery, and this may occur from a mere shock or concussion, with or without a fracture of its bony canal. The blood thus effused acts by compressing the brain; this compression does not always cause death unless the blood is in large quantity, or unless it is effused in or around the base of the brain (medulla oblongata.) Thus the hemispheres will bear a degree of compression from blood which, if it affected that portion of the base of the brain from which the spinal marrow proceeds, would instantly destroy life. The most fatal effusions, therefore, are those which take place in a fracture of the base of the skull, whereby one or both lateral sinuses are commonly ruptured. There may, however,

be laceration of the brain, with effusion of blood to some extent at the base, and yet the person may survive some days. A woman survived for severe injuries to the head for a period of twelve days. She was insensible during the whole of this time; some of the external marks of violence had nearly disappeared, and undergone the usual changes of colour. A severe blow had obviously been inflicted on the summit of the head. On inspection after death it was found that there had been laceration of the brain by counter-stroke, and a large clot of blood was observed to occupy the lacerated part, extending over the surface of the base of the brain and into the ventricles. In this instance the woman survived a severe injury for an unusually long period. In the case of *Cuming* (Edinburgh, Dec. 1853), the deceased died on Nov. 8th, from laceration of the brain produced by blows on the head, inflicted by the prisoner on Oct. 26th. The woman lay in a state of insensibility during the whole period of thirteen days. In another case, as a result of effusion of blood from injury to the head, death did not take place until the twelfth day. The patient, æt. 18, received a blow on the head during a fight. He did not suffer much in consequence, and continued his employment during the next ten days, but on the eleventh day, owing to his having headache, he went to the hospital. He walked to his bed, and appeared quite rational, but he was depressed, and there were febrile symptoms. He died during the night. On inspection bruises were found on the arms, but the head presented no outward sign of injury, and the bones were not fractured. On removing the outer membrane (dura mater), the right half of the brain was surrounded by effused blood which had compressed it. It was contained in the cavity of the arachnoid membrane. The brain presented no breach of surface or laceration from which the blood could have issued, and its substance was healthy. Four ounces of blood in a fluid state were collected. There was a loose coagulum of slightly brown hue, and under this there were other coagula of a light ochreous colour adherent to the brain and dura mater, showing that the blood had been effused some days. These coagula were in membranous layers, and under the microscope presented a fibrous texture. ('Guy's Hosp. Rep.' 1859, p. 123.) This case shows the insidious nature of injuries to the head, and that an injury may prove fatal without leaving any marks of violence externally, or appearance of laceration of vessels or brain-substance internally. A man while intoxicated was thrown down, and struck his head against the pavement. He was taken up insensible, the wound was dressed, and he partially recovered his senses. Three days afterwards he was brought into Guy's Hospital in a state resembling that of concussion. There was a scalp-wound at the back of the head on the left side. He remained in a lethargic state, being occasionally affected with convulsions. About a week after his admission he sank into a half comatose state, and occasionally screamed out. The pupils became finally contracted (as in narcotic poisoning), and he died *twenty-five days* after the infliction of the violence. On inspection, a layer of blood an inch thick was found covering the right hemisphere of the brain. The clot was thready, of a dull red colour, and in some parts of a yellow or ochreous tint, showing from these changes in the red colouring matter that the blood had been effused for a considerable time. On two portions of the base this yellow clot was closely adherent to the brain, and on removing it this was found to be bruised and softened. The source of the blood was traced to some ruptured vessels of the inner membrane (pia mater) at this spot. None of the larger arteries or venous sinuses were found injured, and there were no inflammatory products. ('Guy's Hosp. Rep.' 1859, p. 122.)

In cases of injuries to the head proving fatal by effusion of blood on the

brain, a person may recover from the first effects of the violence, and apparently be going on well, when he will suddenly become worse, and die. Effusion takes place slowly at first,—it may be arrested by the effects of stupor from concussion, by a portion of the blood coagulating around the ruptured orifices of the vessels, or by some other mechanical impediment to its escape; but after a longer or shorter period, especially if the person be excited or disturbed, the bleeding will recur and destroy life by producing compression. How may hours or days are required in order that such an increased effusion should take place after an accident, it is impossible to say; but in severe cases, it is generally observed to follow the injury within a short time. Astley Cooper has related the case of a gentleman who was thrown out of a chaise, and fell upon his head with such violence as to stun him in the first instance. After a short time he recovered his senses, and felt so much better that he entered the chaise again, and was driven to his father's house by a companion. He attempted to pass off the accident as of a trivial nature, but he soon began to feel heavy and drowsy, so that he was obliged to go to bed. His symptoms became more alarming, and he died in about an hour from effusion of blood on the brain. When the brain has sustained laceration from violence, in addition to insensibility, convulsions are frequently observed.

Effusion of blood from disease or violence.—Blood may be found effused in various situations within the interior of the skull, and the cause of the effusion may be either disease or violence. The skill of a medical jurist is often required to determine which of these causes is the more probable, as where, for instance, a pugilist has died after having received severe injuries to the head, and his adversary is tried on a charge of manslaughter. On these occasions it is often urged in the defence, that the bleeding might have arisen either from a diseased state of the vessels of the brain, or—if the evidence render it probable that the blow was the cause—that the effects of the blow were aggravated by a diseased condition of the vessels, or by the excitement into which the deceased was thrown, either from the effects of intoxication or passion. When the brain is not lacerated by violence, the blood is effused either on the surface of the hemispheres, between the membranes, or at the base. When the effusion is caused by violence, the effused blood is not always found under the spot where the blow was inflicted, but occasionally by counter-stroke on the surface of the brain, directly opposite to it—a case which a medical witness has frequently been required to explain on trials, and depending on the same cause as fracture by counter-stroke, *i.e.* on a separation of parts (laceration of the brain, effusion of blood, or even fracture of the bones) at the point of the skull directly opposite to that which sustains the violence. The case related (p. 641) furnishes a good instance of extensive injury by counter-stroke. A severe blow had been inflicted on the summit of the head, as the mark was plainly visible, but the fatal injury was found in the base of the brain, *i.e.* on the part opposite to that which received the blow. Hence the brain was lacerated and blood effused. Again, fracture of the base of the skull is frequently the result of severe violence applied to the top of the head (vertex). (See case 'Med. Gaz.' vol. 36, p. 368.) Effusions of blood from a diseased state of the vessels more commonly take place in the substance of the brain, but they sometimes occur on the surface of the organ as a result of mere excitement or over-exertion of the muscular powers. A diseased condition of the vessels, and probably a softening of the substance of the brain, may on these occasions be apparent on inspection.

A boy, aged twelve, died suddenly with comatose symptoms, after

violent exertion. On inspection, half a pint of blood was found effused on the surface of the brain. ('Lancet,' Nov. 1840.) This case is the more remarkable, because it is rare that a spontaneous effusion from disease should occur in so young a person. Then again it must be remembered that, under the effects of violence when the brain participates in the injury, blood may be effused in its substance so as to resemble cerebral hæmorrhage from disease. Thus when the skull has sustained violent blows without fracture, the extravasated blood has been observed to proceed from the minute vessels of the pia mater and choroid plexus. A case is reported ('Lancet,' Jan. 11, 1845, p. 51), where a blow on the neck over the jugular vein caused instantaneous death, apparently from effusion of blood in the brain. Another fatal case from the same cause is referred to, in which a large quantity of blood was found effused in the lateral ventricles. Traill mentions an instance which occurred at Liverpool in 1838, in which a blow with the naked fist entirely divided the external carotid artery in a healthy man, who died very speedily. ('Outlines,' p. 89.)

If the effusion depend on *disease*, the arteries around may be found in a diseased condition, or the brain itself may be found softened and disorganized. The state of the brain and its vessels should be closely examined in all cases of alleged violence, since hæmorrhage may take place either from excitement or slight blows, whenever this diseased condition exists. It has occasionally happened, especially in old persons, that the person has dropped down dead without a blow being struck, and that death has been wrongly imputed to violence. Cerebral hæmorrhage from disease rarely occurs in persons under forty years of age. Frequent intemperance and violent passion may, however, easily create a tendency to it in younger subjects. As an effect of violence it may take place in persons of all ages, but when the marks of violence are slight, a witness must exercise great caution before he alleges that the extravasation was produced by a blow, especially when it is found that the deceased was of intemperate habits. For a full account of the circumstances accompanying extravasation from violence, see Brach's 'Chirurg. Foren. Spec.' p. 63, Köln, 1843.

Another condition, besides intoxication and passion, has been said to favour a rupture of vessels and an effusion of blood on the brain—namely an alleged thickened state of the substance of the left ventricle of the heart. According to some pathologists, this morbid condition favours the occurrence of cerebral hæmorrhage by the force with which the ventricle propels the blood to the brain. Unless the brain is softened and the vessels are diseased, it is, however, doubtful whether this condition of the heart, if it really exists during life, would have any influence. A case was tried (C. C. C. Aug. 1836, *Reg.* v. *Brown*), in which the prisoner owed his acquittal entirely to the deposition of the medical witness as to the condition of the heart. It was proved that the deceased had been much maltreated by the prisoner about the face and head, and that he speedily died, to all appearance, from the violence. On inspection, the medical witness stated that he found the left ventricle of the heart considerably thickened and dilated, and that under excitement this morbid condition had probably led to the effusion of blood on the brain, and death. Upon this evidence Gurney, B., directed an acquittal.

As a summary of these remarks, we may say that in effusions of blood from violence, the blood generally issues from a vessel which is plainly seen to be torn, as the middle artery of the brain, or the lateral sinus; and it is commonly found on the surface of the brain, and not in its substance, unless the organ is lacerated. When the blood is effused between the dura mater and skull, *more* especially when immediately below the seat of

violence or directly opposite to it by counter-stroke, this is strong evidence, *cæteris paribus*, that it has proceeded from a blow. When there is a fracture of the skull, the presumption of the extravasation being due to violence is great; because this is not only a sufficient but a very obvious cause, while the idea of its having proceeded from disease only is remote and speculative. When, besides these conditions, there is no remarkable congestion of the brain in other spots, the substance of the organ is firm, and the vessels are to all appearance free from disease, we have the strongest reason to believe that the effusion must have been due to violence, and to no other cause whatever. At the trial of *Edey* (High Court of Just. Edinburgh, Nov. 1847), it was proved that the deceased had died from effusion of blood on the brain, and the question was, whether this had arisen from a blow or from disease. The medical witness deposed that he found no marks of disease in the blood-vessels of the brain, and his opinion was that it had resulted from violence. The prisoner was convicted. A case of some interest in relation to this question was communicated to the 'Lancet' (Nov. 13, 1847, p. 521). An effusion of blood which led to sudden death after a blow on the mouth during a pugilistic encounter, was, however, in this instance considered to have arisen from excitement. (See case of *Reg.* v. *Baker*, p. 645.)

The evidence given on some trials, when the main question has turned upon the *cause* of an effusion of blood in the case of a person who has sustained violent injuries to the head, has not been satisfactory. It has been made to appear that no sort of mechanical violence applied to the head of a man in a state of drunkenness or passion—of one whose cerebral vessels were probably diseased—could have had any effect in producing a fatal extravasation found in the head after death. In spite of an individual having received a violent blow with a bludgeon, sufficient to have killed a vigorous man, or of his having been thrown with considerable force with his head against a stone-floor, an unqualified admission is often made, that excitement alone, or drunkenness alone, would account for the extravasation without reference to the blow. In putting the most favourable construction upon these cases, when we have clear evidence of great violence having been used to the head, with the presence of the usual post-mortem appearances, our opinion should be that the excitement or drunkenness might have predisposed to, but was not the immediate cause of, the cerebral hæmorrhage.

A mere inspection of the body does not always lead to the discovery of the cause of an effusion on the brain. The violence causing an effusion of blood may have been slight, and unless attention is particularly directed to the subject, it may be overlooked. In the case of a woman who died in a London hospital in 1857, there was no fracture of the skull or external injury to account for effusion of blood on the brain. The brain was not injured, and in fact there was no apparent cause of death but the effusion, and this was somewhat precipitately assigned to disease. A certificate of death from 'apoplexy' was given, and the deceased was buried. It subsequently transpired that she had been maltreated by her husband, and that the effusion of blood was owing to this maltreatment. The condition of the effused blood should be accurately noticed, in order to determine whether it presents any marks indicative of its being recent or of old standing.

Spontaneous effusions, or effusions from disease, are not easily distinguished from those which are the result of violence to the head. Wilks has pointed out that in most instances of *severe* injury attended with effusions of blood, the structure of the brain is found bruised. In meningeal apoplexy (apoplexy of the membranes) the source of the blood is a

vein of the pia mater or inner membrane, and sometimes a large arterial trunk. The difficulty chiefly arises in those cases in which effusion is found after slight violence, and there is, at the same time, disease of the vessels of the brain. (See 'Guy's Hosp. Rep.' 1859, p. 120.)

Effusion of blood from excitement.—When engaged in the investigation of these cases, it is always a fair matter of inquiry whether the *violence* upon the evidence was not of itself sufficiently great to account for the effusion without the supposition of coexisting disease or excitement. Admitting that the rupture of a blood-vessel, and the effusion of blood on the brain, may take place from simple excitement and passion, yet this is an event comparatively rare, at least in the young and healthy, while nothing is more common than that these results should follow violent injuries to the head, whatever the age or condition of the person. When the person assaulted is of intemperate habits and advanced in life, and the violence is not adequate to account for the effusion in a healthy person, it may be fairly assigned to excitement or disease. In *Reg.* v. *Portbury* (C. C. C. March, 1872) a woman was charged with the murder of her mother. The woman died ten days after a quarrel with the prisoner. On inspection there was congestion of the membranes of the brain, with slight effusion. There was nothing to indicate that this had been caused by violence, and the effusion, which was the cause of death, might have arisen from excitement, considering the age and habits of the deceased. This view was adopted by the jury, and the prisoner was discharged. A case occurred in London, in 1865, of a similar kind, but death was more rapid. The deceased, æt. 55, had presided at a meeting, and was engaged in an angry altercation, when he received a sharp blow on the cheek. He leaned over on his right side, but did not speak. He died in ten minutes. Both the deceased and the assailant were greatly excited. On inspection blood was found effused on the brain. The medical man properly referred death to apoplexy, as the result of excitement and not of the blow which was struck. In the trial of *Baker* for the murder of *Casey* (*Reg.* v. *Baker*, C. C. C. May, 1882), several interesting points arose with respect to wounds, and the cause of death. There were altogether nineteen wounds upon the body of the deceased. Three of these were mortal wounds, viz. one on the left side of the chest penetrating the right ventricle of the heart, the bag of the heart being filled with blood; a second wound at the lower part of the right side of the chest passed through the liver into the inferior vena cava, and had caused copious hæmorrhage; a third wound had opened the left internal jugular vein. The other wounds were of a minor character. All must have been produced by some sharp instrument. There were also abrasions on the head, neck, hands, &c., made during life. There was no existing disease. Over the surface of the brain was a considerable effusion of blood extending into the ventricles. This was ascribed by Pepper to apoplexy, probably the result of a violent struggle; and he assigned apoplexy rather than the mortal wounds on the body as the cause of death. Considering the copious hæmorrhage from the mortal wounds—hæmorrhage which probably went on for some time after death—the presence of an effusion of blood upon the brain was remarkable. Probably the mortal wounds were inflicted after the apoplectic seizure, and whilst the man was in the act of dying.

If on these occasions a medical witness is unable to state positively whether the effusion was due to the excitement or the blows, he will satisfy the Court if he only states clearly that which is, in his own mind, the more probable cause of death; and by weighing all the circumstances of the case beforehand, he will rarely fail to find that one cause was more probable than the other. Thus, if a man, excited by passion and intoxica-

tion, is struck on the head, and the blow is slight—such as an unaffected person would probably have sustained without injury—yet in this case insensibility and death follow, and, on examination, a quantity of blood is found effused in the substance of the brain, can it be a matter of doubt, medically speaking, that the effusion was chiefly due to the excitement under which the deceased was labouring? To take a converse instance—a man engaged in a personal conflict with another, is struck most violently on the head, or falls with great force on that part of his body: on inspection it is found that death has arisen from effusion of blood on the surface of the brain, and it would be no unexpected consequence of the violence inflicted that a similar appearance should be met with in an individual calm and unexcited. Could a practitioner hesitate to say, under these circumstances, that the blow would satisfactorily account for the effusion, without reference to any coexisting causes of excitement? These may be allowed to have their influence, in giving an increased tendency to cerebral hæmorrhage, or in aggravating the consequences of the blow, but no further.

A witness asserts, perhaps, that the extravasation of blood was owing to a blow inflicted on the head. He is then asked whether vessels may not be ruptured by excitement: he answers, without any qualification, in the affirmative, and thus produces an impression on the minds of the jury that excitement may have caused the rupture of the vessel in the particular case on which he is being examined. The effect produced by it on the Court is not always removed, even by a careful re-examination. A medical witness has to state the *whole* truth. A qualified answer should be given to what is really a general question; and supposing his opinion to be already formed on the subject on which his evidence is required, he should not, unless it be strictly consistent with his own views, allow his answer to a *general* question to be made applicable to a *particular* case. If asked whether vessels might not be ruptured, and blood extravasated by mere *excitement*, he should answer that such an effect might undoubtedly follow; but that it was his opinion—and it is here supposed that his opinion has been founded upon a deliberate examination of all the *medical* facts—that excitement was not the cause of rupture and extravasation in the case in question. A witness has a right to insist that his evidence shall pass to the jury without having any designed ambiguity attached to it. In a trial for manslaughter it was proved that the prisoner and deceased had been wrestling. The prisoner had thrown the deceased with his head on a stone floor; he then seized him by the throat, and beat his head several times against the floor. The deceased died nineteen hours afterwards. On inspecting the body, a great quantity of coagulated blood was found beneath the scalp. There was a wound over the right parietal bone, an inch and a half in length, penetrating through the scalp, but no fracture of the skull. There was a quantity of extravasated blood on the opposite or left side of the head, and a rupture of some branches of the carotid artery on the inside of the skull. On the neck were two discolourations to the left of the windpipe, apparently occasioned by the pressure of two fingers. The laying hold of the neck might, in the opinion of the witness, have more readily caused a rupture of the cerebral vessels, by preventing the return of blood. The surgeon, after giving this description of the post-mortem appearances, was asked whether, in his opinion, death was occasioned by the injury proved in evidence. He said death might or might not have been occasioned by it. Death might have arisen from other causes—an apoplectic fit might have caused it. The effusion of blood was the immediate cause of death, and he had seen blood in the heads of many persons dying from apoplexy. He was not able to speak

to the cause of the rupture of the vessels. He thought it highly probable that the injury received was the cause of death—it was certainly sufficient to account for it. It is not mentioned whether the man was found guilty, or whether the jury acquitted him. ('Med. Gaz.' vol. 7, p. 382.)

A case was tried (Gloucester Sum. Ass. 1845, *Reg.* v. *Phipps*), in which a strong opinion was expressed by Patteson, J., in relation to this defence. During a fight, the prisoner struck the deceased a severe blow under the left ear. He fell and died in a few minutes. After death, blood was found extravasated on the part corresponding to the seat of violence, and this, in the opinion of the medical witness, satisfactorily accounted for death. The defence was, that the effusion might have proceeded from over-excitement; but the judge is reported to have said that if it were proved two people were fighting together—blows were struck—one fell to the ground and died, and afterwards internal injuries were found corresponding with the external marks of violence, no power on earth could persuade him that such blows were not the cause of death. The prisoner was found guilty.

Effusion of blood causing death after a long period of time.—Admitting that blood has been effused on the brain as a result of violence, the person injured may survive the effects for so long a period as to create a doubt whether death can be strictly assigned to the violence. In this respect the case of *Reg.* v. *Sullivan* (C. C. C. Sept. 1853) is of some interest. A healthy man was knocked down by the prisoner, and fell with his head upon the ground. He appeared as if he was stunned, and staggered in attempting to walk: he complained of pain in the head and general weakness. This was on April 11th, 1853. Although he suffered from pain in the head, he had no medical advice until May 12th, and had in the meantime performed his duties as an officer of the Customs. After this he suffered from dimness of sight, and became delirious. On the 29th he came under the care of M'William. There were marks of bruises on the head; there was impairment of vision, a faltering gait, and other symptoms indicative of pressure on the brain. He improved under treatment, but the symptoms returned in an aggravated form about June 12th; he became insane, and was transferred to St. Luke's Hospital. He had delusions, and was evidently suffering from pressure on the brain. He recovered so far that he was about to be discharged, when the symptoms of pressure became aggravated, and death took place on Aug. 17th, *i.e.* *four months* after the infliction of the violence. On inspection, a shot was found imbedded in the frontal bone, not penetrating the skull. A large clot of blood existed between the layers of the arachnoid membrane, occupying the whole surface of the left hemisphere; the clot had evidently been there for some time, because it was partially invested with a false membrane. No large vessel was ruptured; there had probably been an escape of blood at different times, and this would explain the intermittent nature of the symptoms. The clot amounted to at least two fluid ounces, and the surface of the brain had been obviously indented by its pressure. Another clot of old standing was found in the Pons Varolii. The witnesses concurred in attributing death to the effusion of blood on the brain, and the effusion to the violence inflicted by the prisoner, although it was admitted to be probable that some additional effusion had taken place just before the last recurrence of symptoms. The prisoner was convicted of manslaughter. The fact that the deceased had been healthy previous to the violence, and that after this he had constantly suffered more or less from symptoms of pressure on the brain, fully justified the medical opinion, in spite of the protracted nature of the case. There was no other cause but the violence to account for the effusion and death.

Date of effusions.—Recent effusions of blood are recognized by their red colour, and the consistency and appearance of the clot or coagulum. After some days the clots acquire a chocolate or brown colour, and this passes gradually into an ochreous tint, which may be met with in from twelve to twenty-five days after the violence (see cases, *ante*, p. 641). Clots of effused blood also undergo changes in structure and consistency; when old they are firmer, and there is much lymph, which is sometimes disposed in membranous layers of a fibrous structure, and these are adherent to the dura mater and the brain. The surface of this organ sometimes presents a mark indicative of pressure.

The influence of time and surface in altering the appearance of effused blood, will be evident from the following case reported by Reid ('Physiol. Researches,' p. 513). A woman, æt. 70, threw herself from a window. The fall produced a severe lacerated wound of the scalp, laying bare the skull, and causing a simple fracture of the sternum and tibia. She died thirty-one days after the injury, in a state of exhaustion. On inspection there was a fracture of the left parietal bone, and between the dura mater and inner surface of the skull, near the left temple, there was a layer of coagulated blood, one-sixth of an inch in thickness and about two inches in breadth. In one place the clot had a *brownish* hue, but the greater part of it was still rather dark-coloured. On the right side there was a similar effusion of coagulated blood, but this was inside the dura mater and on the arachnoid covering of the brain (see fig. 126. p 650), or within the cavity of the arachnoid. This coagulum was everywhere of a *chocolate-brown* colour, showing that the process of absorption was much more advanced than on the left side. A large quantity of coagulated blood had been effused into the cellular tissue near the fracture of the tibia. This was still black, and had the appearance of a recent effusion. A small quantity of black blood was also found near the sternum, which had been fractured. The fractured ends of the bones had been firmly united. There is no doubt that all these effusions had taken place at the same time from the same accident, *i.e.* thirty-one days before death, yet they presented very different appearances; and but for the facts being known, it might have been contended that the effusion on the arachnoid from the great change of colour was of much older date than the others. The difference, however, was probably owing to absorption being more active on the inner surface of the serous membrane than in the other structures in which blood was effused. In estimating time, as indicated by change of colour in the clot, we must therefore always consider the seat of the effusion and the absorbing power of the tissues. Reid also mentions a remarkable case of effusion of serum in the ventricles of the brain in the case of a young man, who died about a week after he had received a blow on the right side of the face. It appeared, however, that he had sustained a severe injury to the head eighteen months before, and certain changes in the brain, as well as the appearance of the effusion, rendered it probable that it was really of old date, and that it had been caused by the first accident and not by the blow on the face. (Op. cit. p. 517.)

When a medical man is required to give an opinion of the *date* of an effusion found on the brain, great caution is required. A surgeon may not be able to fix the precise date, but it may be in his power to say whether the blood has been effused for a few days, weeks, or months. A case was tried (Derby Lent Ass. 1859), in which this question was material. On January 25th, a man was kicked violently on the head by two companions. He was attended by a surgeon for fourteen days, and he was then pronounced to be convalescent. On March 6th, six weeks after the assault, the man became seriously ill, and he died on March 11th.

The two men were tried for manslaughter; and at the trial a medical man deposed that the deceased died from the effects of the injuries inflicted by the prisoners on Jan. 25th. The post-mortem appearances were, congestion of the brain, with effusion of a large clot of blood on the surface of the left hemisphere, immediately below the situation of the most serious external wound, this clot being surrounded by a considerable quantity of coagulable lymph. The prisoner's counsel then put the question to the witness: 'I can produce evidence to show that deceased fell down some steps into a cellar, upon his head, three weeks before his death—do you not think it more likely that death was the result of this fall, rather than of the beating three weeks prior to the fall?' The surgeon said: 'Certainly not;' and, 'there could not have been the effusion of lymph I describe after an accident within so short a space of time as three weeks. There must have been a longer space of time between the injury and the death to have produced this appearance.' The reasons for so strong an opinion were not given. So far as the description goes, there was nothing to show that the effusion had been there more than three weeks. Coagulable lymph may be found in these effusions within a much shorter period than three weeks. A man fell from a height upon his head, was ill for three days, and then so far recovered that he sat up and dressed himself; on the next day he became insensible, and died on the eighth day after the accident. On inspection the base of the skull, including both orbits, was found fractured; there was effusion with much lymph at the base of the brain. In the case which was the subject of trial, the situation of the effusion beneath the seat of violence was in favour of its being caused by that violence, but there was nothing in the appearance of the effusion to enable a medical man to say whether it had taken place either six weeks or three weeks before death. The perfect intermediate recovery was somewhat adverse to the theory that the clot was produced by the violence of the prisoners.

When the force is of a bruising kind, the whole substance of the skull may be fractured without a division of the skin. (*The Queen* v. *Ward*, C. C. C. 1841.) There is one remarkable circumstance connected with fractures accompanied by depression of bone which here requires to be mentioned—namely, that the person has been sensible so long as the foreign substance which produced the fracture and depression remained wedged in the brain, and that insensibility and other fatal symptoms began to manifest themselves only after its removal. This being admitted, it may be urged in defence, that death was really caused by medical interference. But it is a sufficient answer to state, that the wounded person must have died from inflammation of the brain if the foreign body had been allowed to remain; and that it is consistent with the soundest principles of practice to remove all such foreign substances without delay. In fractures of the skull, with depression, it may become a question whether the surgeon raised the depressed portion of bone so soon as he ought to have done. A blow on the head may produce a fracture of the inner table of the skull, and cause death by compression as a result of the fracture or of the effusion of blood. In *Reg.* v. *Hadwen* (Lancaster Aut. Ass. 1871), the prisoner struck a boy a severe blow on the head. He became sick and unconscious, fell into a state of collapse, and died the next day. On inspection the inner table of the skull (fig. 126, *a*, p. 650) was found to be fractured, and there was effusion of blood on the brain.


Wounds of the brain.—Wounds of the brain sometimes prove instantaneously mortal, even when slight, while in other cases recoveries take place from contused or punctured wounds of this organ, contrary to all expectation. When a person survives the first effects of the injury, there

are two sources of danger which await him: 1. Fungoid growths from the exposed portion of the brain; and 2. Inflammation and its consequences. The process of inflammation, it must be remembered, is very slowly established in this organ; it may not manifest itself until from three to ten weeks after the injury. In one remarkable case, where a child was accidentally shot through the brain, the ball having traversed both hemispheres, no symptoms of cerebral inflammation manifested themselves for twenty-six days. The child died on the twenty-ninth day. ('Med. Gaz.' vol. 39, p. 41.)

In the description of injuries of the head, it is impossible to avoid the use of terms with which members of the legal profession are not likely to be acquainted. In giving evidence upon the situation of wounds, of the effusion of blood, and the effects of fractures, medical witnesses are often compelled to make use of anatomical terms, and are not always successful in explaining them.


Fig. 126 represents a section of the bones of the skull, with the three membranes which cover the brain. (*a*) Section of the skull-bones, with the outer and inner tables, and the intermediate cellular structure, or diploe, indicated by the dark shading; the scalp, or skin of the skull, which covers the outer table, is not represented. (*b*) The dura mater, or outer membrane of the brain; it is thick and fibrous, closely adherent to the inside of the inner table of the skull, but smooth on the side towards the brain. (*c*) The arachnoid membrane, so named from its delicate web-like structure, smooth towards the dura mater, but closely covering the pia mater beneath. (*d*) The pia mater—the membrane which immediately invests the substance of the brain and dips into all the convolutions. It contains the blood-vessels which nourish the hemispheres of the brain. These membranes are, for distinctness, represented as being separated from each other, but they are naturally in close proximity, and the rough side of the dura mater is closely adherent to the inside of the skull (calvarium). The ordinary seats of the effusion of blood from violence are between the dura mater and inner table of the skull, and between the pia mater and the surface, or in the substance of the brain.

Fig. 126.



The skull, with its outer and inner table, and the three coverings of the brain (membranes), seen in section.

Fig. 127.




A section of the brain, showing the centrum ovale and ventricles or cavities.

Fig. 127 represents a horizontal section of the brain. 1, 1, the two *hemispheres* cut down, forming what is called the *centrum ovale*. The greater part of this consists of white medullary or brain substances, studded with small red points (the sections of small blood-vessels) called *puncta cruenta* or *vasculosa*. It is surrounded by a narrow margin, darkly shaded, which represents the grey or cineritious substance, from its having a darker colour than the mass of the brain. The depth to which the *convolutions* of the brain extend into its substance is here seen, and it is into these that the pia

er or investing membrane dips. 2 and 3 represent in section the and back parts of the *corpus callosum*, or the body by which the two ispheres are united. The removal of this has exposed the two great ties of the brain, one in each hemisphere, called the *lateral ventricles*. se are here seen with their contents. 4. Part of the *septum lucidum*, wing a slight space between its layers, which is called the fifth tricle. 5, 6, 7, are prolongations of the cavities or ventricles, front back, which from their shape are called cornua (horns). 8. The *us striatum* of one ventricle. 9. A dark fringe-like looking body ed the *choroid plexus;* it consists of a fold of membrane (pia mater) osing numerous blood-vessels. This plexus communicates with that he opposite ventricle through the foramen of Monro. A bristle is sed through the opening under 4, and its extremities are seen resting he corpus striatum on each side. 10. A portion of the *thalamus opticus* ne ventricle. 11. The fornix. 12. The hippocampus major, descend- into the middle cornu.

Fig. 128.



Vertical longitudinal section of the brain, cerebellum, Pons Varolii, and the upper part of the spinal marrow (Hirschfeld and Leveillé).

1. Convolutions of longitudinal fissures.
4. Corpus callosum.
9. Pineal gland.
13. Corpora quadrigemina.
17. Fourth ventricle.
18. Optic nerve.
19. Arbor vitæ cerebelli.
21. Section of Medulla oblongata.
26. Section of Pons Varolii.

Wounds of the face.—When wounds of the face are of any extent they usually followed by great deformity; and when they penetrate the ties in which the organs of the senses are situated, they often prove l, either by involving the brain and its membranes, or by giving rise to mmation of this organ. Wounds of the eyebrows are not of so simple ture as might at first sight be supposed. Besides being attended with rmity when they heal, they are liable to give rise, during the process ealing, to serious disorders of the neighbouring parts. Amaurosis and algia are recorded among the secondary and not unusual consequences uch wounds, when the supra-orbital nerve has become implicated. ler certain conditions of the body, there may be inflammation of the s within the orbit, extending by contiguity to the membranes of the n, and proving fatal by leading to the formation of pus within that n. Amaurosis in the right eye has been known to occur from a con-

tused wound, not of a violent nature, to the right eyebrow. ('Med. Gaz.' vol. 31, p. 931.) Wounds apparently confined to the external parts of the face frequently conceal deep-seated mischief. A sharp instrument penetrating the eyelid, and passing upwards with any force, will produce fracture of the orbital plate of the frontal bone, which is known to be extremely thin, and even injure the brain beyond.

Wounds of the orbit.—Astley Cooper relates, that a girl accidentally fell, while playing with a pair of scissors, and the point of the scissors passed upwards under the upper eyelid. It was found difficult to extract them; the eye became inflamed, but for some days after the accident the child was in the habit of walking a considerable distance daily to receive medical advice. In about ten days she suffered violent pain, with symptoms of inflammation of the brain, under which she died. On inspection, it was found that the orbital plate of the frontal bone had been fractured, the dura mater torn, and one of the anterior lobes of the brain lacerated. (For a similar case, see 'Med. Gaz.' vol. 41, p. 553.) In several instances in this country, trials for murder or manslaughter have taken place, in which death has been caused by a penetrating wound of the orbit, leading to fracture of the bone and injuring the brain. In the year 1735, the celebrated *Macklin*, the comedian, was tried for having caused the death of Thomas Hallam, by thrusting a stick into his eye. On inspecting the body of the deceased, it was ascertained that the stick had entered the brain through the orbit; and the prisoner was found guilty of manslaughter. A somewhat similar case occurred at Liverpool, in 1843, where a boy killed another by wounding him with a gimlet in the eye. The brain was perforated, and he died in two days. It is necessary for a witness to bear in mind that, owing to the thinness of the orbital plate, an injury of this kind may be produced by the application, comparatively speaking, of only a moderate force. The following instance, reported by Watson, will show that a simple cause may produce a serious wound of the orbit. A boy, aged ten, had the birch end of a common broom thrust several times into his face by one of his companions. He became stunned, and was carried home in a state of stupor. He afterwards complained of violent pain in the eye-ball and forehead. Symptoms of inflammation and fever supervened, followed by coma, convulsions, and insensibility. He died in about sixteen days after the accident. On dissection, the orbital plate was found perforated, and pus and lymph were effused at the base of the brain. The left ventricle contained three ounces of pus; it communicated with a wound in the orbit. A small portion of bone was partially separated from the orbital plate, and projected upwards. For many similar cases, and one in which death took place in six hours, from a wound made by a tobacco-pipe, see 'Hoffbauer über die Kopfverletzungen,' 1842, p. 49. In infants and children, the partition between the orbit and the brain is membranous, and it may therefore be perforated by the slightest causes. A man was tried in Scotland, in 1827, for killing a girl, by shooting her. The prisoner had inadvertently discharged a gun towards the high road, where the deceased was standing; she received the shot in her face, but the wounds appeared quite superficial. She died in three days, and it was found that one small pellet had penetrated the orbital plate and perforated the brain. The orbital plate need not always be perforated, in order that fatal inflammation of the brain should be set up. A deeply penetrating wound of the orbit only, has caused death under the usual symptoms of cerebral disturbance. ('Ed. Med. and Surg. Jour.' vol. 43, p. 263.) (See also Casper's 'Wochenschrift,' May, 1845.)

Wounds of the nose.—These wounds are, generally speaking, of a simple

nature, rarely giving rise to serious symptoms; but they are often attended with great deformity. If the injury is contused and, at the same time, extensive, a loss of the sense of smelling will probably result. A penetrating wound of the nose, produced by passing a sharp-pointed instrument up the nostril, may destroy life by perforating the cribriform plate of the ethmoid bone, and injuring the brain. Such a wound, it is obvious, might be produced without leaving any external marks of injury. A man died in nine weeks from the effects of a wound of the nose, whereby the nasal bones were fractured. On inspection, there was a copious inflammatory effusion at the surface of the brain, particularly at the part corresponding to the seat of the violence. An injury to the bones of the nose may prove fatal by giving rise to an attack of tetanus. A case of this kind has been elsewhere related (*ante*, p. 603).

Deformity as a consequence of wounds of the face.—Wounds of the face, when at all extensive, are always followed, in healing, by greater or less *deformity*. A medical witness may, perhaps, find these questions put to him in relation to them: Is the wound likely to be attended with deformity? Could such a wound of the face heal without deformity?—or, Could the deformity, if it exist, have been produced by any other cause than the wound? These questions are of some importance. A person may allege that he was severely wounded in the face, when the medical witness, on examination, may find no trace of such a wound as that described. Again, a person may seek damages from another in a civil action, by alleging that a particular deformity was produced by a wound, when the medical witness may be able to trace its origin to disease, or to some accidental cause.

INJURIES TO THE SPINE.

Injuries to the spine and spinal marrow seldom require medico-legal investigation; but this organ is liable to *concussion* from blows, to compression from fracture of the vertebræ or the effusion of blood, with all the secondary consequences attending such accidents. Concussion of the spinal marrow commonly produces paralysis, affecting the bladder, rectum, or lower extremities. These symptoms may not appear at once, but come on after some hours or days. (*Bowling* v. *S. E. Ry. Co.* Exch. Feb. 1859; also *Williamson* v. *L. B. and S. C. Ry. Co.* Guildford Sum. Ass. 1862.) After death no traces of mechanical injury may be discovered. Blows on the spine, unattended with fracture or dislocation, may be followed by inflammation and softening of the spinal marrow. A slight injury has been known to cause death, by giving rise to inflammation of the spinal marrow. (Henke's 'Zeitschrift der S. A.' 1840, 2, 407.) This organ is also liable to compression from slight causes. A man was tried on a charge of manslaughter. It appeared in evidence that he had thrown the deceased on the ground, and while he was attempting to rise, he caught him by the throat, forced him backwards, and brought his head violently in contact with the ground. The deceased died after a few convulsive gasps. On inspection, the spinal cord was found to be compressed between the body of the fourth and the arch of the third vertebra, but on removing it, no indentation or laceration of its substance was perceptible. Death had ensued from paralysis of the phrenic nerves. This case shows the necessity of inspecting the vertebral column, when death is alleged to have been caused by violence, and no traces of it are perceptible in other parts of the body. Indeed, it is not improbable that in many cases of sudden death from alleged or suspected violence, where the cause is obscure, if the spinal marrow were examined, the fatal result might be explained by the discovery of some mechanical injury or morbid change in this organ. This

part of a medico-legal inspection is too commonly neglected. (See 'Ann. d'Hyg.' 1871, 1, 138; and 2, 116.)

Fractures of the vertebræ.—These fractures are generally attended by displacement, and thus produce compression of the spinal marrow. They are the more rapidly fatal in proportion as the injury is high up in the vertebral column. The whole of the body becomes paralyzed below the seat of injury, by the compression of the spinal marrow. If the seat of compression is above the fourth cervical vertebra death is commonly immediate: asphyxia results from paralysis of the nerves which supply the diaphragm, and are necessary to respiration. In falls on the top of the head from a height, it sometimes happens, not only that the skull is extensively fractured, but that the dentiform process of the second vertebra is broken off, owing to the head being doubled under the body. This injury to the second vertebra may be the cause of death. This accident is not always attended with fatal compression of the spinal marrow. ('Ed. Med. and Surg. Jour.' Jan. 1838.) In one instance the person survived fifteen months (Ib. Oct. 1845, p. 527); and in another, in which the fracture was caused by the patient turning in bed while his head was pressed on the pillow, death did not take place for *sixteen* months. (Copland, 'Dict. Pr. Med.' Paralysis.) On several criminal trials, this injury was proved to have been the cause of death; and in a case tried at Glasgow (*The King* v. *Reid*, p. 71), it became a material question, how far such a fracture might result from disease. It may happen that caries of the bone, or disease of the transverse ligament, will cause a separation of the dentiform process from the second cervical vertebra. The state of the bone in these alleged fatal accidents should therefore be closely examined. In Reid's case an acquittal took place, partly because the deceased had laboured under disease of the spine, and the exact state of the parts had not been noticed. Disease of the ligaments may also lead to a separation, followed by slow or rapid death, according to the degree of pressure. A slight cause may sometimes produce severe and fatal injury to the neck. A lunatic in a private asylum suddenly threw her head back, in order to avoid taking some food that was offered to her; and she died evidently from the compression produced by the displacement of the dentiform process of the second vertebra. A woman died suddenly a month after her confinement: she had been suckling her child at one o'clock in the morning, and at four she was found dead. The viscera of the abdomen, chest, and head were carefully examined, without the discovery of any morbid appearance to account for her death—when, as the brain was being returned into the skull, one of the inspectors noticed a projection at the foramen magnum. On further examination, the dentiform process of the second vertebra was found to have been displaced, and this had so injured the spinal marrow as to destroy life. ('Med. Gaz.' vol. 3, p. 582.) It is not stated whether the bone was in a healthy or diseased condition. The following case shows that the rapidity of death will depend on the degree of compression:—A girl had a stiff neck, as it was supposed, from cold: her head was continually twisted to the left side, but she possessed the power of moving it in the opposite direction. While in this state, a man suddenly seized her and gave her head a violent twist; she felt immediately severe pain, lost the power of turning her head to the right, and had difficulty of swallowing. These symptoms continued to increase for a month, and she ultimately died from paralysis. On inspection, the ligaments of the first and second vertebræ were found ruptured, but there was no mark of suppuration [illegible] bone were healthy. The dentiform process had compressed the [illegible] of the spinal marrow, which were softened; it was ob[illegible] that she had lost more of the powe[illegible]ation than [illegible]

léd.' Nov. 1842.) A displacement of the dentiform process may take lace from very slight causes. In a case which occurred to Petit, a child as instantaneously killed in consequence of its having been lifted up by he head. (See also Cormack's 'Edin. Jour.' April, 1845, p. 314.) A an while holding his head in a butting position during a struggle with a riend died suddenly. The friend had forcibly rotated or twisted the eceased's head a few times from side to side by the brim of his hat. On nspection, it was found that the first four cervical vertebræ were fractured —the ligaments were bruised and torn, and blood was effused on the overings of the spinal cord. ('Med. Times and Gaz.' May 17, 1856.) t is not stated whether there was any disease of the bones. Compression f the spinal marrow sometimes arises, though rarely, from *effusion* of lood from a fall. It is important to remember, that an effusion of blood nay also take place from spontaneous causes. In one case, which proved atal from an accidental fall, a coagulum of blood was found effused into he substance of the spinal marrow, exactly opposite a fracture of the body f the sixth cervical vertebra.

Injuries to the spine and its contents are generally the result of falls or lows, either on the head or the lower part of the column. The secondary onsequences of these injuries are sometimes so insidious as to disarm uspicion, and death may take place quite unexpectedly some weeks after he accident. Splinters of bone, separated by fractures may remain adherent or some time; and, by a sudden turn of the head, be forced off, and lestroy life by penetrating the spinal marrow, at a long period after the nfliction of the injury. This has been known to happen in fractures nvolving the margin of the foramen magnum, and in such cases death is mmediate.

The spinal marrow has been in some instances wounded in its upper art by sharp-pointed instruments introduced between the vertebræ. Death s an instantaneous result when the wound is above the third cervical ertebra:—there is no part of the spine where a weapon can so easily enetrate as this, especially if the neck be slightly bent forward. The xternal wound thus made may be very small, and if produced with any bliquity by drawing aside the integuments, it might be easily overlooked, r it might be set down as superficial. For an account of a case in which leath occurred from a stab in the back of the neck, causing a division f the spinal marrow, see Henke, 'Zeitschrift der S. A.' 1836, H. 2; and or another case of homicidal injury to the spine, see 'Lancet,' May, 1855, . 520.

In fractures of the vertebræ, a person is generally so disabled, whatever nay be the situation of the fracture, that he cannot walk or exert himself. We must be prepared, however, for exceptions to this. In 1861, a man, et. 35, was admitted into the Northampton Infirmary suffering from aralysis of the legs and great pain in the back and in the abdomen. He ould give no intelligible account of the cause of his illness. He soon died; nd on a post-mortem examination, the tenth dorsal vertebra was found roken in its body and arch. There was slight displacement, but it was ot such as to press upon the spinal cord. A large clot of blood was ituated on the sheath of the cord; this had caused the paralysis. It was roved at the inquest that deceased met with a heavy fall, but that he had walked some distance afterwards, visited several public-houses, went home ntoxicated, and lay down to sleep in a yard. He awoke in the morning ober, but was unable to move his legs. In addition to paralysis, the man when admitted was labouring under peritonitis. There was no evidence hat he had sustained any injury subsequently to the fall twelve days efore his admission; hence there was reason to believe that, in spite of the

fractured vertebra, he had not been rendered incapable of motion. There is no doubt that the effusion of blood was the cause of the paralysis, and this did not occur until some time after the fracture, as the result of slow oozing. (See for a case somewhat similar, *Reg.* v. *Slater* and *Vivian*, C. C. C. Sept. 1860. INSANITY.)

CHAPTER 48.

WOUNDS OF THE CHEST—OF THE LUNGS—RUPTURES FROM ACCIDENTS—WOUNDS AND RUPTURES OF THE HEART—WOUNDS OF THE AORTA AND VENÆ CAVÆ—WOUNDS AND RUPTURES OF THE DIAPHRAGM—DIRECTION OF WOUNDS OF THE CHEST—WOUNDS OF THE ABDOMEN—DEATH FROM BLOWS ON THE CAVITY—RUPTURES OF THE LIVER, GALL-BLADDER, SPLEEN, KIDNEYS, INTESTINES, STOMACH, AND URINARY BLADDER—MEDICO-LEGAL QUESTIONS CONNECTED WITH RUPTURED BLADDER—WOUNDS OF THE GENITAL ORGANS—MUTILATION.

Wounds of the chest.—Wounds of the chest have been divided into those which are confined to the walls and those which penetrate the cavity. Incised or punctured wounds of the chest-walls are rarely followed by dangerous consequences. The bleeding is not considerable, and is generally arrested without much difficulty. They heal either by adhesion or suppuration, and unless their effects are aggravated by incidental circumstances, the person recovers. Contusions or contused wounds of the chest are, however, far more dangerous, and the danger is in a ratio to the degree of violence used. Such injuries, when severe, are ordinarily accompanied by fractures of the ribs or sternum—by a rupture of the viscera within the cavity, including the diaphragm—by profuse bleeding—or, as an after effect, by inflammation of the lungs, with or without suppuration. Fractures of the ribs are dangerous for several reasons: the bones may be splintered and driven inwards, thereby wounding the lungs and causing hæmorrhage or leading to inflammation of the pleura or lungs. In fractures of the upper ribs the prognosis is less favourable than in those of the lower, because commonly a much greater degree of violence is required to produce the fracture. A simple fracture of the sternum or chest-bone without displacement of the bone, is rarely attended with danger, unless the concussion has at the same time produced mischief internally, which will be known by the symptoms. When, however, the bone is depressed as well as fractured, the viscera behind may be mortally injured. In a case of depressed fracture of the sternum, the person died after the lapse of thirteen days; and on inspection, it was found that the fractured portion of bone had produced a transverse wound of the heart about an inch in length. The cavities of the organ had not been penetrated, but the piece of bone was exactly adapted to the depression produced by it on the parietes. (Devergie, 'Méd. Lég.' vol. 2, p. 243.) A witness will frequently be required to take into consideration the effects of contusions on the chest, with or without fracture, in cases of death from pugilistic combats, which formerly gave rise to numerous trials on charges of manslaughter. Wounds penetrating into the cavity of the chest are generally dangerous, even when slight, in consequence of the numerous accidents with which they are liable to be complicated. In these wounds, the lungs are most commonly injured; but, according to the direction of the weapon, the heart, or the great vessels connected with it, as well as the œsophagus (gullet) and the thoracic duct, may share in the mischief.


Wounds of the lungs.—The immediate cause of danger from wounds of

these organs is the consequent hæmorrhage, which is profuse in proportion to the depth of the wound and the size of the vessels wounded. Should the weapon divide any of the trunks of the pulmonary veins, the individual may speedily sink. The degree of hæmorrhage cannot be determined by the quantity of blood which escapes from the wound; for it may flow internally, and collect within the cavity of the pleura, impeding respiration. This is especially to be apprehended when the external orifice of the wound is small and oblique, and one of the intercostal arteries has been touched by the weapon. A wound of the lung is generally known, among other symptoms, by the frothiness and florid colour of the blood which issues from the orifice, as well as by the expectoration of blood. The lungs may sustain serious injury from a blow or fall, and yet there may be no external marks of violence or symptoms indicative of danger for some hours. A young man, while riding, fell from his horse on his left arm. He complained of no pain for five hours, but in twelve hours he was seized with an alarming flow of blood from the mouth. He died in the course of a few days. After death there was no external mark of injury to the chest, but the right lung was ruptured posteriorly throughout its length, and much blood had been effused. ('Lancet,' Nov. 1842.) A boy, aged fourteen, fell to the ground from a height of about twenty feet, and he died in about three hours after the accident. On examination of the body, there was no mark of external injury. The collar-bone was fractured, but the ribs had escaped injury. The right lung was ruptured to the depth of four inches into its substance, and from this rupture a large quantity of blood had escaped, causing death. This case furnishes another illustration of the production of fatal internal injuries without any corresponding marks of violence externally. ('Med. Times and Gaz.' Dec. 31, 1853.) For a case of laceration of the lung without fracture of the ribs from a carriage passing over the chest, see 'Med. Times and Gaz.' Jan. 19, 1861. The surgeon should observe whether death, when it occurs during the convalescence of a person who has survived the first effects of a penetrating wound of the chest, may not have been caused either by imprudence on the part of the patient, or by abuse of regimen or other misconduct; for circumstances of this nature may be occasionally treated as mitigatory on the trial of the assailant. It is properly recommended, that in all cases where a person is progressing to recovery, any alteration in the treatment should be made with great circumspection. A soldier died instantly from internal hæmorrhage, brought on by throwing a bowl at some nine-pins, two months after he had been apparently cured of a wound of the lungs. ('Med. Times and Gaz.' July 24, 1851, p. 98.)

Wounds of the heart.—Wounds of the heart are among the most fatal of penetrating wounds of the chest. It was formerly considered that all wounds of this organ were necessarily and instantly mortal. (See *ante*, p. 529.) When the wound is small, and the weapon penetrates into the cavities of the heart obliquely, life may be prolonged for a considerable period; and cases are on record in which it is probable that such wounds would have healed and the patients have finally recovered, but for the supervention of other diseases which destroyed life. Dupuytren has reported the case of a man who received a stab on the left side of the chest. He was brought to the Hôtel Dieu, but the symptoms under which he laboured did not lead to the suspicion that he had received a wound of the heart. The man died in eight days, of cerebral disease. On an inspection of his body, it was found that the left ventricle was wounded about the middle and a little to the right, its cavity having been penetrated in a transverse direction. The wound was three lines and a half across,

and one line from above downwards. The external fibres of the organ were most separated; the openings diminished gradually, so that the internal fibres were in contact and closed the wound. A boy, in pulling a knife from a companion with the point towards him, accidentally stabbed himself in the chest. A small quantity of florid red blood escaped; he vomited, and fell to the ground. He died in eight days. The left ventricle had been perforated, and one pound and a half of blood was effused in the chest. This case shows that fatal hæmorrhage is not always immediate. ('Med. Gaz.' vol. 2, p. 721.) In another instance, reported by Dupuytren, five or six wounds were made by means of a saddler's needle —most of them penetrating into the left ventricle of the heart. The man died of cerebral disease, twenty-five days after the wounds could have been possibly inflicted; for the needle was taken from him twenty-five days before his death, without any suspicion being entertained of his having wounded himself with it. The cicatrices were visible on an inspection of the body. The quantity of blood found in the chest amounted to about three ounces, and this appeared to have proceeded from the substance of the heart. ('Med. Gaz.' vol. 13, p. 662.) For a case of sudden death as the result of an accidental wound by a fish-bone, see 'Med. Times and Gaz.' May 12, 1860, p. 667; and for cases in illustration of the fact that wounds of the heart are not instantaneously mortal, see 'Med. Gaz.' vol. 2, p. 721.

Fig. 129.



Right side of the heart, with its cavities laid open (Wilson).

1. Cavity of right auricle.
3. Superior vena cava, opening into the upper part of right auricle.
4. Inferior vena cava.
a. Right ventricle.
b. Cavity of right ventricle.
d. Pulmonary artery.
e. f. Tricuspid valve.
o. Left ventricle.
p. Ascending aorta.
r. Descending aorta.

It was the opinion of Dupuytren, that these injuries were not necessarily fatal, although, with one exception (p. 659), there is no case on record in which a person has recovered from a penetrating wound of the cavities of the heart. ('Ed. Med. and Surg. Jour.' Oct. 1844, 557; also 'Ann. d'Hyg.' 1846, 1, 212.) There are few, probably, who will be inclined to consider them curable. From a series of cases collected by Ollivier and Sanson, it appears that out of twenty-nine instances of penetrating wounds of the heart, only two proved fatal within forty-eight hours. In the others death took place at the varied periods of from four to twenty-eight days after the infliction of the wound. (Devergie, 'Méd. Lég.' vol. 2, p. 253.) These differences in the time at which death occurs, as well as the fact that wounds of the heart do not instantly destroy life, have been ascribed to the peculiar disposition of the muscular fibres of the organ, and to the manner in which they are penetrated by a weapon. Thus, as a general principle, it is stated that wounds which are parallel to the axis of the heart are, *cæteris paribus*, less rapidly fatal than those which are transverse to its axis. In a wound which divides the fibres transversely, the opening will be larger, and the hæmorrhage greater, than in one that is parallel to these fibres; and as the heart is composed of different layers, of which the fibres pass in different directions, so, in a penetrating wound of its cavities, while one set tends to separate the edges, another tends to bring them together, and thereby to restrain the flow of blood. It is this action of


the fibres which renders wounds of the ventricles less rapidly fatal than those of the auricles, all other circumstances being equal; but a man has been known to survive a laceration of the left auricle eleven hours. In this case the chest was crushed, and after death it was found that the left auricle was lacerated to the extent of an inch; nevertheless this patient survived the injury for the long period mentioned. ('Lancet,' Jan. 30, 1841, p. 655.) In another instance, where a man was stabbed through the left auricle during a quarrel, death did not take place until after the lapse of seventy-eight hours. ('Med. Gaz.' 40, 520.) A case is reported in which a person is stated to have recovered from a punctured wound of the heart ('Med. Gaz.' vol. 17, p. 82,); and Trugien met with a case in which a man who had been stabbed in the left ventricle survived *five* days. The wound in the heart had partly cicatrized. (Ibid. vol. 47, p. 42.)

The presence of a weapon in the wound, by mechanically obstructing the effusion of blood, also retards the fatal result. A lunatic wounded himself with a very long sharp instrument on the left side of the chest. Two days afterwards he was admitted into the Bicêtre Hospital, labouring under oppressed breathing, intermittent pulse, and other serious symptoms. The wounded man stated that he had plunged the instrument into his chest, and had not been able to withdraw it. His symptoms became more aggravated, and he died on the twentieth day after the infliction of the wound. The pericardium and the surrounding parts were found inflamed; and on opening the heart an iron stiletto was discovered, firmly imbedded in the substance of the left ventricle, which it had entirely traversed, so that its point projected a few lines into the cavity of the right ventricle. The man had obviously died from effusion of blood; but this had taken place slowly, and only after the period of time mentioned had the bleeding sufficed to destroy life. It appears that the right cavities of the heart are more frequently wounded than the left, and of these the right ventricle is most commonly the seat of injury. Out of sixty-four cases of wounds of this organ, twenty-nine were situated in the right ventricle, twelve in the left ventricle, nine in the two ventricles, three in the right auricle, and one in the left auricle. These differences are readily accounted for by the relative situation of the cavities. It appears also that wounds of the right ventricle are not only the most frequent, but of all others they are the most rapidly mortal. It is considered that the suddenness of death in severe wounds of the cavities of this organ, is to be ascribed not merely to the loss of blood, but to the degree of compression which the heart experiences from that which escapes into the pericardial sac. A singular case of accidental wound of the heart, causing death, is reported ('Med. Times and Gaz.' 1860, I. p. 467.) A woman died suddenly under suspicious circumstances. On inspection, it was found that a large fish-bone had protruded through the stomach and had perforated the heart, causing death by hæmorrhage. In reference to the *direction* of penetrating wounds of the chest, it may be stated that the base of the heart corresponds to the upper margin of the third rib on the left side, and the apex to the lower margin of the fifth rib on the same side. (See fig. 97, p. 525.)

Ruptures of the heart.—The heart is liable to be *ruptured* either from disease or accident. In the latter case, the organ generally gives way towards the base, and through one of its cavities on the right side. (For cases, see 'Med.-Chir. Rev.' vol. 31, p. 532.) Hope asserts that in ruptures from natural causes, it is the left side of the heart, and particularly the left ventricle, in which a rupture is most frequently found. The symptoms are sudden pain, collapse, cramps, cold extremities, and rapid

death. According to the circumstances under which they occur, cases of rupture from disease may excite a suspicion of death from violence. Sometimes the substance of the heart appears to have undergone fatty degeneration. A case occurred in which, under this diseased condition, the left ventricle had become ruptured during slight muscular exertion ('Med. Gaz.' vol. 38, pp. 774 and 857); and a case is reported of rupture of the right ventricle under similar circumstances. ('Lancet,' Feb. 16, 1857.) In other instances there has been no apparent alteration of structure. A young man, aged twenty-nine, died in ten hours after his first seizure; on inspection, there was a small aperture in the right auricle near the vena cava. This did not appear to be connected with any morbid condition of the heart. ('Med. Gaz.' vol. 26, p. 518; 'Lancet,' Nov. 1843.) It is worthy of note that when this alarming accident proceeds from blows or falls, it is not always accompanied by marks of external violence, or any fracture or other injury to the exterior of the chest. A girl was knocked down and run over by a cart. When brought to the hospital she was dead, and there was no mark of injury upon any part of the body. On inspection, the pericardium was found to be full of blood, which had issued from a transverse rent across the apex of the heart. Both ventricles were laid open: the muscular substance was torn to a greater extent than the pericardium. The spine and ribs were unbroken, and there was no injury to any other organ. It was obvious that the injury to the heart had been occasioned by the accident. ('Mem. of Path. Soc.' Jan. 1863.) 'A case is recorded by Gairdner in which a cart-wheel passed over the chest of a child, and occasioned instant death by causing rupture of the heart. Christison met with two similar instances, one caused by a fall, the other by a blow. A child was killed, as was supposed, by the wheel of a carriage going over its chest. On inspection, the skin, muscles, and ribs were free from any marks of injury. The pericardium was lacerated, and a pint of blood was effused into the right pleural cavity. The heart was found ruptured throughout its entire length. In another case, a man fell from a cliff the height of one hundred feet. There were a few slight bruises about the body, but no serious wound or fracture. On opening the chest, the pericardium was found to be distended with fluid blood, which had escaped [illegible] an irregular [illegible]

Fig. 130.



Front view of the Viscera of the Chest (Wilson).

1. Right ventricle of the heart. 2. Left ventricle. 3. Right auricle. 4. Left auricle. 5. Pulmonary artery. 6. Right pulmonary artery. 7. Left pulmonary artery. 8. Ligament of the ductus arteriosus. 9. Arch of the aorta. 10. Superior vena cava. 11. Arteria innominata, and in front of it, the right vena innominata. 12. Right subclavian vein, and behind it, its corresponding artery. 13. Right common carotid artery and vein. 14. Left vena innominata. 15. Left carotid artery and vein. 16. Left subclavian vein and artery. 17. Trachea, or windpipe. 18. Right bronchus. 19. Left bronchus. 20. Pulmonary veins: 18, 20, form the root of the right lung; and 7, 19, 20, the root of the left. 21. Superior lobe of the right lung. 22. Middle lobe. 23. Inferior lobe. 24. Superior lobe of the left lung. 25. Inferior lobe.

The heart is here represented without the pericardium, the membraneous covering or bag in which it is contained.

quarters of an inch in diameter, situated in the anterior portion of the right auricle. For another case see 'Cyc. Pr. Med.' vol. 4, p. 557. A boy was run over by a heavy waggon, two wheels of which passed over his chest. He arose apparently not much injured, but on reaching the side of the street, fell dead. On dissection, the heart was found ruptured. The ribs were not fractured, nor was there any laceration of the walls of the chest.

The *natural* causes of rupture of the heart are violent mental emotions, such as anger, fright, terror, paroxysms of passion, sudden or excessive muscular efforts, or violent physical exertions in constrained positions. The heart, like any other muscle, may also give way from its own powerful contractions. The left auricle of the heart has been ruptured as a result of great physical exertion. ('Med. Gaz.' vol. 47, p. 1063.) Rupture of the heart from any of these natural causes is, however, a rare occurrence. ('Med.-Chir. Rev.' Oct. 1847, p. 460; 'Lancet,' Jan. 23, 1860, p. 88; and Gamgee's 'Pathol. Anat.' p. 7.) It is of importance for the medical jurist to be aware that rupture of the heart may prove suddenly and rapidly fatal to life, although the lesion may not involve the cavities. A lady, *æt.* 75, was suddenly seized with faintness and occasional fits of hurried respiration: she died in about an hour. On inspection, the pericardium was found to be distended with twelve ounces of blood, one-third of which was in a coagulated state. A fissure was found in the superficial fibres about one-third of an inch in length, over the left ventricle and near the septum. There was another and smaller laceration a little higher up. The larger rent communicated with one of the coronary veins, and from this, and some of the smaller arteries in the substance of the heart, the hæmorrhage had proceeded: the lining membrane of the left ventricle was quite sound. Death had been caused by the mechanical effect of the blood in interrupting the heart's action. (Cormack's 'Month. Jour.' June, 1845, p. 421.)

When the heart is in a diseased condition, as in fatty degeneration, any slight causes of excitement are sufficient to produce rupture and sudden death. The mere exercise of walking may thus give rise to fatal consequences. A man was found dead upon a high road. The right auricle was found ruptured near the superior vena cava: its substance was thin, soft, and very easily torn. (Cormack's 'Month. Jour.' May, 1864, p. 343.) A man died suddenly after a struggle with an adversary. No blows had been exchanged. In this instance the walls of the left ventricle were found much thickened, and the aortic valves were ossified; there was no rupture. (Loc. cit.)

Wounds of arteries and veins.—Wounds of the large arterial and venous trunks, around the heart, must be considered as decidedly mortal: death is generally instantaneous from the sudden and profuse bleeding which attends them. Heil reported a case which proves in his view that a person may recover from a penetrating wound of the *ascending aorta.* (Henke's 'Zeitschrift,' 1837, b. 2, s. 459.) With regard to these fatal effusions of blood within the chest, as well as in the other great cavities, from whatever vessel or vessels the blood may have issued, the greater part of it generally preserves the liquid state: and it is rare that so much as one-half of the quantity effused is met with in the form of coagulum. These effusions of blood in the chest may be sometimes traced to wounds of the intercostal and the internal mammary arteries, or of the azygos vein. Wounds of the *carotid arteries* have been fully considered in the section on wounds of the throat (*ante*, pp. 517, 631). On wounds of the other blood-vessels, whether arteries or veins, it is unnecessary to make any further remark. *Death is generally* owing to loss of blood, and the bleeding from

a comparatively small vessel may prove fatal, according to its situation and the state of the person wounded.

Death from the entrance of air into wounded veins.—In wounds of *veins* there is an occasional and a peculiar cause of death which requires notice, namely, the entrance of air by the open mouth of the divided vessel. A man was labouring under chronic laryngitis, and a seton was introduced at the fore part of the neck. The skin was raised, and the seton-needle was passed horizontally through the skin, about two inches and a half above the breast-bone, and not at all near to the jugular vein or any other important blood-vessel. At the instant of its entrance there was a momentary hissing sound—the man became pale—his features were set—he fainted, and he subsequently became rigid and convulsed. The man did not recover his consciousness, was attacked with lockjaw, and died in seven hours. The medical evidence given at the inquest proved that death had not arisen from loss of blood, but from air penetrating through a small vein which had been accidentally divided. A verdict was returned accordingly. After the inquest the body was inspected, and it was then found that the jugular veins and the large vessels of the neck were uninjured. The right auricle and pulmonary artery were distended with frothy blood, and the lungs were emphysematous, distended with much air. ('Med. Gaz.' vol. 41, p. 608.) For another case of sudden death from this cause, see 'Med. Gaz.' vol. 43, p. 1098; and vol. 45, p. 926. Claude Bernard has shown that the air thus introduced into veins does not act by paralysing and obstructing the action of the heart: the obstacle which it creates to the circulation is in the lungs. ('Leçons,' p. 163.)

Air injected into the jugular vein destroys life by interfering with the functions of the heart. According to some, the air rushes into the cavity of the vessel owing to atmospheric pressure during the expansion of the heart, while others believe it to be dependent on the act of inspiration. In some alleged cases of this kind, death has been probably due to loss of blood. When the bleeding is slight, and the hissing sound is heard at the time of the incision, it may fairly be ascribed to the entrance of air. This opinion would be confirmed by the discovery of a frothy state of the blood in the right cavities of the heart. Death may take place from this cause, although a person may recover from the first symptoms. A case has been reported in which a man died under these circumstances in thirteen hours, although in the meantime he had so far recovered, that the functions of the lungs and heart were completely restored. ('Assoc. Jour.' Jan. 28, 1853, p. 91.)

Wounds and ruptures of the diaphragm.—The diaphragm, or muscular partition between the chest and abdomen, is liable to be wounded either by weapons which penetrate the cavity of the chest or abdomen, or by the ribs when fractured by violent blows or falls; but, under any circumstances, wounds of this muscle are not likely to occur without implicating the important organs that are in contact with it. It is scarcely possible, therefore, to estimate the danger of these injuries abstractedly, as the medical opinion must materially depend on the concomitant mischief to the adjoining viscera. The engraving, fig. 131, p. 663, represents a view of the diaphragm, or the muscular partition between the chest and abdomen.

Slight penetrating wounds of the diaphragm may heal like those of other muscular parts; and cases of this kind are on record. There is, however, especially when the wound is of a lacerated kind, a consecutive source of mischief which no remedial means can avert—namely, that after the wound has, to all appearance, healed, the life of a person may be cut short by the strangulation of a portion of the stomach or bowels in the half-cicatrized aperture. An instance affords an illustration of this. A sharp-

pointed weapon had penetrated the diaphragm, notwithstanding which the patient apparently made a rapid and perfect recovery. At the end of about three months, however, the man died from a strangulated hernia or rupture involving the stomach, which had passed through the wound of the diaphragm into the thorax. In a case of this description, when death occurs at a long period after the infliction of the wound, the witness may probably be required to say—Whether the wound was the cause of death; or whether there were any other circumstances which would have caused or facilitated the production of a hernia? The degree of culpability of an aggressor may materially depend upon the answers returned to these questions. *Phrenic hernia*, as this form of internal rupture is termed, is not by any means an unusual or unexpected fatal consequence of a wound of the diaphragm; and therefore it would appear, at first sight, that death, at whatever period this event may occur, should be referred to the original wound. But the case may present some difficulties, as it is possible that a slight blow on the stomach, received subsequently to the wound, or even any violent exertion on the part of the deceased, might have produced fatal strangulation. A person may survive with a large phrenic hernia for a considerable period, and die from some other cause. A case of this kind has already been related, in which the stomach and part of the intestines were found in the left cavity of the chest, and the person lived for nine months (*ante*, p. 632). The fact of a person surviving will, however, depend on the freedom of communication between the chest and the abdomen. If the aperture is small and unyielding, strangulation may occur, followed by death within the usual period of time. A man fractured two of his ribs by a fall. It was not until twelve months afterwards that he was admitted into hospital, where he died two days after his admission. On inspection, it was found that about fourteen inches of the colon protruded into the chest through an aperture in the diaphragm, so small as only to admit the point of a finger. The intestine had become strangulated, and this had led to death. There was no doubt that the injury to the diaphragm had been occasioned by the same accident which had caused the fracture of the ribs. The hernia, judging from the symptoms, had taken place only a few days before death. ('Med. Gaz.' vol. 40, p. 584.) Another case has been elsewhere related in which a man, who was stabbed in a quarrel, died from phrenic hernia fifteen months afterwards. These two cases are of importance, inasmuch as they show that death may unexpectedly occur from the effects of an injury to the chest received a long time previously. They also prove the absurdity of that principle of the English law which makes the aggressor responsible for a fatal result only when the death happens within a year and a day after the receipt of a wound. (See Reid's 'Physiolog. Researches,' p. 521.)

Fig. 131.



Under or abdominal surface of the diaphragm looking upwards—the abdominal viscera being removed (Wilson).

8. Right crus.
9. Lumbar vertebræ.
10. Left crus.
11. Opening for aorta.
12. Opening for œsophagus or gullet.
13. Opening for inferior vena cava.

The most serious injuries to the diaphragm are unquestionably those which are produced by violent contusions or falls on the abdomen, at a time when the stomach and intestines are distended. On these occasions the muscular fibres may be ruptured to a greater or less extent; but the bleeding is not considerable, rarely exceeding two, three, or four ounces. A uniform result of such *ruptures*, when extensive, is a protrusion of the stomach into the chest, with sometimes a rupture of the coats of this organ and extravasation of its contents. Severe lacerations of the diaphragm are more readily produced during the act of inspiration than during expiration —the fibres of the muscle being then stretched, and receiving, while in this state of tension, the whole of the force. According to Devergie, the rupture most frequently takes place in the central tendinous structure, where it is united with the left muscular portion above the crura. He has remarked that it occurs more commonly on the left side than on the right. (Op. cit. vol. 2, p. 250.) It has been supposed that death was an immediate consequence of this accident, but this view is not supported by facts. In a case of extensive rupture of the diaphragm related by Devergie, in which the stomach and colon were found in the chest, the person lived nine months after the only accident which could have produced it, and then died from another cause. Besides the stomach, it sometimes happens that the liver, spleen, or intestines pass through the opening, and these organs are then liable to become strangulated: the lungs are at the same time so compressed that respiration is stopped, and asphyxia or suffocation may be an immediate result.

Direction of wounds in the chest.—In judging of the *direction* taken by wounds which traverse the chest from front to back, it is necessary to remember the great difference that exists in the level of the same rib anteriorly and posteriorly. This must be especially attended to when we are called upon to state the direction of a traversing wound from the description of it given by another. The point here referred to had an important bearing in the case of a fatal gun-shot wound, which was the subject of a criminal charge some years since. (Henke's 'Zeitschrift,' 1836.) A reference to fig. 97, p. 525, will show that, owing to the great obliquity of the ribs, a straight line touching the upper edge of the sixth rib behind would be on a level with the upper edge of the third rib in front.

A person died from a single pellet of small-shot traversing the chest from before backwards. The pellet entered between the first and second rib anteriorly, and traversing the lung, caused death by lacerating the sixth intercostal artery, near its origin at the lower edge of the sixth rib, posteriorly. In giving an opinion on the direction of this wound, one medical witness described the wound behind as being six inches below the level of that in front. As the small canal through the lungs could not be discovered, he was inclined to think that the two wounds could not be connected, because the gun had been discharged from the shoulder when the party firing was nearly on a level with the deceased. This opinion, however, was soon corrected by a reference to the anatomical relations of the parietes of the thorax. Indeed, it will be found that a straight line carried backwards from between the first and second ribs in front will, in a well-formed skeleton, touch the upper border of the fifth rib posteriorly; therefore this wound was nearly *horizontal*—being only one inch and a quarter lower posteriorly, than anteriorly. In the case of *Colonel Fawcett*, killed in a duel, the bullet entered on the right side of the chest, fracturing the *seventh* rib, and after traversing the posterior part of the lungs lodged in the *ninth* dorsal vertebra. These parts are in a line with each other, and the wound was horizontal. It must not be forgotten that a wound imme-

iately below the sternum, will in its fore part involve the viscera of the bdomen—in the back part those of the chest, and in its central part it will raverse the diaphragm.

For the better understanding of medical evidence in reference to 'ounds of the chest, an engraving is given at p. 660 (fig. 130), which epresents the relative position of the lungs, heart, and blood-vessels. The ibs and diaphragm are removed.

Wounds of the walls of the abdomen.—Incised and punctured wounds, 'hich affect the walls of the abdomen, without penetrating the cavity, re not of so simple a nature as might at first sight be imagined. f the epigastric artery is wounded, the danger is immediate; or a fatal æmorrhage will, in some instances, take place from a wound of this mall vessel. A carpenter who had a chisel in his pocket stumbled in 'alking, and received a wound in the abdomen with the edge of the tool. Vhen brought to the hospital, the man appeared exhausted from loss of lood, and the skin was cold and pallid; he gradually became weaker, the ulse imperceptible, and he died a few hours after his admission. On an xamination of the body, the epigastric artery was found divided, and the avity of the peritoneum distended with blood. It is true that in this case he abdomen was penetrated, but the real cause of death was the blood lost rom the wounded artery. A man was brought to St. Thomas's Hospital, 'ho had been stabbed in the direction of the epigastric artery on the left ide of the abdomen, with a case-knife. He died in eighteen hours, appaently owing to bleeding from this vessel. Among the other sources of anger from these superficial wounds, is inflammation followed by suppuraion beneath the tendinous membrane which covers the abdominal muscles. 'he matter formed is very liable to accumulate within the sheath of the nuscles, and this may prove fatal unless proper treatment be adopted. The nflammation will sometimes extend to the peritoneum, and thus rapidly estroy life. As improper medical treatment may, in either of these cases, ause a superficial wound of the abdomen to take a fatal termination, so 'hen a person stands charged with having inflicted such a wound, it will e necessary for a medical witness to consider how far the consequences of he act of the prisoner have been aggravated by negligence or unskilfulness. But when these wounds take a favourable course and heal, there is n after-effect to be dreaded, namely, a protrusion of the viscera at the icatrized spot, constituting ventral hernia. When the wound has involved he muscular fibres transversely to their course, the cicatrix which follows s commonly far less capable of resisting the pressure of the viscera within, han other parts of the parietes. A hernia may take place, and this, like ther herniæ, if neglected, is liable to become strangulated and lead to the estruction of life. The walls of the abdomen, owing to the protrusion of his cavity, are easily penetrated by pointed instruments, and it requires ut a slight force to traverse them completely and wound the intestines. A light wound may thus prove fatal by leading to peritoneal inflammation. n 1861, *Mrs. Cuthrey* died from the effects of a penetrating wound, proluced by a table-knife being thrown across a dinner-table at her. The oint of the knife penetrated the abdomen for about three-quarters of an nch. The deceased died from peritonitis. There was a slight opening in he small intestines.

Contusions are attended generally with far more serious effects on the avity of the abdomen than on the chest. This arises from the coverings f the abdomen having less power to resist external shocks. In the first lace, death may be the immediate result of a blow in the upper and central ortions; no *particular* morbid changes may be apparent on inspection,

and the violence may have been so slight as not to have produced any ecchymosed mark on the skin. Death has been ascribed in these cases to a fatal shock transmitted to the system through a violent impression produced on the nerve-centre—called the solar or cœliac plexus. Some remarks have already been made on sudden death from blows on this part of the abdomen (see p. 586). Cases of this kind are of not unfrequent occurrence, and in the absence of marks of physical injury in the part struck, a jury might be led to doubt whether the blow could have been the cause of death. In *Rex* v. *Jones* (Warwick Sum. Ass. 1831) the prisoner was charged with having struck the deceased several blows on the breast, and one on the pit of the stomach, by which he instantly fell down senseless and expired. No morbid appearances were found. The prisoner was convicted of manslaughter. ('Watson on Homicide,' p. 75.) In another case (*The Queen* v. *Sayers*, C. C. C. Aug. 1841) death was thus caused by violence during a pugilistic combat. A man received a blow in the stomach, and fell dead. As there were no marks of external injury, the surgeon thought the deceased had died of apoplexy. The prisoner was acquitted. A similar case was the subject of a trial (*Reg.* v. *Laws*, Norwich Lent Assizes, 1854). The deceased, a powerful man, received during a pugilistic encounter a blow on the abdomen, and he instantly fell backwards, dead. On an examination of the body there were no marks of injury, either externally or internally. The surgeon attributed death to sudden shock. The judge left it to the jury to say whether they thought the death of the deceased was caused by a blow; but if they could not say what was the cause of death, or if they should think that death was attributable to excitement and that it was independent of the blow, the prisoner would be entitled to an acquittal. A verdict of Not Guilty was returned. Although the blow was seen to be struck, and was a sufficient cause of death under the circumstances, the jury probably thought that there should be some *visible* injury to the body. Some surgeons have thought that these cases have not been accurately observed, and that in those which terminate fatally a more careful inspection would probably have shown visible changes in the organic structures. This fact, however, remains: persons have died soon after receiving severe blows on the upper part of the abdomen, and medical men of experience who have examined the bodies for the express purpose of detecting physical injuries, have not found any to record. Moreover, they have not found in any part of the body a natural cause of sudden death.

Blows on the abdomen, when they do not destroy life by shock, may cause death by inducing peritoneal inflammation. (*Reg.* v. *Martin*, C. C. C. 1839; also *Reg.* v. *Smith*, Manchester Lent Ass. 1871.) For two other medico-legal cases in which death arose from this cause, see Cormack's 'Month. Jour.' May, 1846, p. 340. Peritonitis thus induced, is apt to be accompanied by inflammation of serous membranes in other cavities: thus, it is said, a person may be cut off by pleurisy depending on an attack of peritonitis produced by violence, while the former disease would probably be referred to some other cause. A woman received some severe blows on the abdomen from her husband. She died in five days. There were marks of pleurisy and peritonitis on dissection, the former much more decided. The medical witness, while he allowed that the peritonitis might have been caused by blows, thought that death had been produced by an attack of pleurisy from cold. The jury acquitted the husband. The reporter of the case considers that the attack of pleurisy was immediately dependent on the peritoneal inflammation produced by the violence. ('Med. Gaz.' vol. 25, p. 13.) This doctrine requires confirmation, before it can be safely applied to medico-legal practice. Such a sympathetic connection

between the two diseases must not only be rendered probable, but actually proved. Peritonitis thus produced by violence to the abdomen, is not always fatal. ('Lancet,' Jan. 24, 1846, p. 104; also 'Med. Gaz.' vol. 37, p. 460.) For an instructive case of this kind, in which fatal peritonitis followed a slight amount of violence, see 'Lancet,' Jan. 5, 1850, p. 29. At the Swansea Lent Assizes, 1863, a man was convicted of manslaughter, by giving to the deceased a kick in the lower part of the abdomen. No organ was ruptured, but peritonitis was set up, and death took place in two or three days. A soldier, during an action, was struck by a spent ball on the abdomen, over the region of the bladder. The ball fell on the ground at his feet, without either injuring his clothes or even marking his skin. He did not feel much pain at the time, and walked to the hospital, a distance of two miles, with the ball in his pocket, but he died shortly afterwards from peritonitis and inflammation of the bladder. The entire surface of the abdomen presented the appearance of a severe bruise in a few hours after he was struck. (Ed. 'Med. Jour.' March, 1863, p. 793.) Violence applied to the abdomen is not, however, always indicated by ecchymosis or injury to the skin. Effusions of blood in the sheaths or tendinous coverings of the muscles, may or may not be indicative of violence. One fact must here be borne in mind, to prevent mistakes in examining a body after death, namely, that blood may be found copiously effused in and round the abdominal muscles, quite irrespective of the application of violence. Reid met with four cases of this description in about five hundred inspections. A man, æt. 39, died of disease of the kidneys four weeks after his admission to the hospital. On inspection, a considerable quantity of dark coagulated blood was found effused in the recti muscles of the abdomen around the navel, without any external appearance to indicate its presence. A man, æt. 40, died of fever three days after his admission into hospital. On inspection, twenty-four hours after death, a large quantity of dark-coloured coagulated blood was found in the muscles round the navel. The skin had its natural appearance. In two other cases the effusions were in and around the muscles of the chest. ('Physiolog. Researches,' p. 511.)

Blows adequate to produce a laceration of the vessels and hæmorrhage would most probably be attended with ecchymosis, or some visible injury to the skin. At any rate, when such marks of violence are not visible, and there is no evidence of a blow having been struck, a witness would act wisely in declining to attribute the mere effusion of blood to the act of another person. Deeply penetrating wounds of the abdomen are generally fatal by reason of the injury done to the intestines and other organs. A soldier by accident so fell upon his bayonet that, although the weapon traversed the whole cavity of the abdomen (entering at the back and coming out in front below the navel), the man recovered in about six weeks. ('Med. Times and Gaz.' March 30, 1861, p. 329.) This case is of importance in reference to the situation and direction of wounds. Had there been no knowledge of the facts, this accidental wound might have been pronounced homicidal.

Ruptures of the liver.—Blows on the abdomen may prove fatal by causing a rupture of the liver or other viscera, with extravasation of blood; and as it has been elsewhere stated, these serious injuries may occur without being attended with any marks of external violence. Of all the internal organs, the liver and spleen are the most exposed to rupture, owing to their compact structure, which prevents them from yielding to a sudden shock, like the stomach and intestines. Ruptures of the liver may occur from falls or blows; but this organ may be ruptured merely by a sudden *action of the abdominal* muscles. An accident of this kind hap-

pened to a person who was endeavouring to avoid a fall from his horse. ('Male's Med. Jur.' p. 119.) A fall on the feet from an elevated spot may also produce laceration of this organ. ('Ann. d'Hyg.' 1846, 1, 133.) Ruptures of the liver are generally seen on the convex surface and anterior margin, seldom extending through the whole substance of the organ, but consisting of fissures, varying from one to two inches in depth. The right lobe from its size is more commonly affected than the left. Their usual direction is from before backwards, with a slight obliquity; they rarely intersect the liver transversely. The lacerated edges are not much separated, while the surfaces present a granular appearance. But little blood is met with in the laceration; it is commonly found effused in the lower part of the cavity of the peritoneum, or in the hollow of the pelvis, and is only in part coagulated. Ruptures of the liver, unless they run far backwards and involve the vena cava or portal vein, are not in general attended with any considerable hæmorrhage; but the bleeding, should this vessel be implicated, is sufficient to cause speedy destruction of life. Under other circumstances, a person may survive some hours, as the blood may escape only slowly, or it may be suddenly effused in fatal quantity after some hours or days, as a result of violent exertion or of fresh violence applied to the abdomen. A man went to hospital, in whom there were no immediate or urgent symptoms. He was sent away, and a few hours afterwards was found dead in a cell at a police-station. On inspection, the liver was lacerated nearly through its diameter, and a basinful of blood was found in the cavity of the abdomen. ('Med. Times and Gaz.' 1864, 2, 527.) This effusion must have taken place after the man had left the hospital. On the other hand, death may be a slow result of this injury. In one case, a man is reported to have died from a rupture of the liver, which had occurred from an accident eight days before. ('Med. Chir. Rev.' Jan. 1836, p. 296.)

In 1841, a drunken man was admitted into Guy's Hospital. There was no mark of violence about him, but he appeared helpless from intoxication. He died in nine hours, and on inspection two quarts of blood were found effused in the abdomen. This had flowed from a large rupture in the right lobe of the liver. It had probably escaped slowly, for the man was able to move about just before he died. Another case was admitted in 1861. There was an extensive laceration of the liver, but there were no symptoms of this severe injury, and its existence was not even suspected until the man died suddenly on the day after his admission. (See also 'Cormack's Jour.' May, 1846, p. 341.) In 1862, a man, who had been in good health half an hour before, was found dead upon the high road, and there was reason to believe that he had been run over by his own dray. The abdomen was found full of effused blood, which had proceeded from a large rupture on the under surface of the right lobe of the liver. It was T-shaped, five inches in the transverse, and about two inches in the longitudinal direction. The diaphragm was ruptured on the right side for about four inches from before backwards, and the liver protruded through the aperture into the chest. On opening the head, about two table-spoonfuls of blood were found effused between the membranes; and the substance of the brain was unhealthy. There were no marks of external violence. There was not the slightest scratch, abrasion, or discoloration, but the sixth and seventh ribs were broken transversely near their extremities. From the state of the brain it was thought that the man had had an apoplectic seizure, and had fallen [illegible] dray.

Ruptures of the liver generally prove [illegible]

One case has been related (su[illegible]

and a case occurred in which a patient in Guy's Hospital survived this accident ten days. On inspection, it was found that the diaphragm had been ruptured as well as the liver, and that the two had united, an abscess having been formed between them. The liver had been lacerated on its right side. ('Lancet,' 1864, Dec. p. 716.) In another case, in which the patient survived ten days, death took place from internal hæmorrhage. On inspection there was a rupture of the right border, involving the entire thickness of the liver. It arose from a fall from a three-storey window. There were no external marks of injury. ('Amer. Jour. Med. Sci.' April, 1870, p. 415.) Another case proved fatal in twenty-four hours. (*Ibid.* July, 1870, p. 145.) In a case in which the liver was found adhering to the false ribs, a fatal rupture was caused as a result of violent muscular action. The liver was large and its substance brittle ('Vierteljahrsschrift,' April, 1872, p. 324).

Ruptures of this organ may take place from violence applied to the *chest*, and there may be no marks of injury in the region of the liver. ('Med. Times,' Aug. 30, 1851, p. 234; 'Med. Gaz.' vol. 47, p. 156.) In the case of *Reg.* v. *Cuffery* (Liverpool Wint. Ass. 1863), a question presented itself in reference to these ruptures, as to the time required for the effusion of a large quantity of blood into the abdomen when none of the large vessels are involved in the laceration. A police-constable was charged with having caused the death of a man. The deceased was drunk, had fallen three times, and had been kicked and maltreated by a mob. The prisoner took or dragged him to the station, and in an attempt to escape, he knocked down the deceased and fell on him, his knee striking the abdomen. The deceased appeared to suffer great pain when he was lifted up, but he was able to walk to the station with assistance: when there he soon became insensible, breathed heavily, and died fifteen or twenty minutes afterwards. On inspection, the liver was found to be ruptured in three places, but none of the large blood-vessels were involved. Upwards of three pints of blood were effused in the abdomen, and the medical witnesses agreed that death was owing to internal hæmorrhage as a result of the ruptures. The question, however, arose whether the ruptures were caused by the violence of the prisoner about twenty minutes before death, or by any of the falls and ill-treatment which the deceased had previously sustained. It was contended in favour of the prisoner, that so large a quantity of blood could not be effused in so short a period as a quarter of an hour or twenty minutes, when the rupture involved only the substance of the liver and not the large blood-vessels. Hence it was alleged the rupture must have been caused by the previous violence. One medical witness thought it possible that this quantity of blood might have escaped from the smaller vessels within the time mentioned; another thought that it would have taken at least half an hour for such an extensive effusion to be produced. The prisoner was acquitted.


The question here raised was based on a refined speculation, and it is not surprising that the witnesses differed. The violence received before the prisoner took the deceased into custody, was admitted to have been quite sufficient to account for the ruptures of the liver and the fatal hæmorrhage, and there was nothing to fix it on the act of the prisoner. We have no means of measuring the rapidity with which blood flows on these occasions. It is stated that the liver was ruptured in three places; hence an extensive bleeding surface must have been exposed. The man was able to walk after the violence; and this exertion may have added to the hæmorrhage. Lastly, the bleeding would probably continue after death, so long as the blood retained its warmth and fluidity. The prisoner was acquitted, not because the amount of effusion was inconsistent

with the time assigned, but because there was a failure of evidence to show that the rupture was caused by his violence. Assuming that the rupture existed when the deceased was struck by the prisoner, it might have been a question whether his violence had not accelerated death by increasing the hæmorrhage.

Wounds of the gall-bladder.—Wounds and ruptures of the gall-bladder are necessarily attended with the effusion of bile. This irritant fluid finds its way into the cavity of the abdomen, and the person dies from peritonitis. In a fatal case of this description, an old man, while getting out of bed, fell with great violence on the floor. He died from peritonitis in forty-eight hours. The gall-bladder was ruptured, and a large stone was found impacted in the cystic duct. ('Med. Gaz.' vol. 37, p. 968.)

For the better comprehension of medical evidence in reference to ruptures and wounds of the liver and gall-bladder, an engraving is subjoined, fig. 132, representing the under surface of the liver, with the relative position of the larger blood-vessels. 1. The right or large lobe. 2. The left lobe. 3. The lobus quadratus, so named from its shape. 4. The lobus Spigelii. 5. The lobus caudatus. 6. The longitudinal fissure; the numeral is placed on the rounded cord, the remains of the umbilical vein. 7. The pons hepatis. 8. The fissure of the ductus or canalis venosus. The obliterated cord of the duct is seen passing backwards to be attached to the coats of the inferior vena cava (9). 10. The gall-bladder with its widest part or fundus projecting slightly beyond the anterior margin. 11. The transverse fissure containing from before backwards the hepatic duct, the hepatic artery, and the portal vein. 12. The vena cava. 13, 14. Depression produced by viscera covered by the liver. 15. The posterior border of the liver; the notch 17 corresponding with the spine. 16. The notch in the anterior border separating the two lobes. It is in this border that ruptures most commonly take place, and in the edge of the right or large lobe.

Fig. 132.



View of the under surface of the Liver, with its lobes and vessels.

Ruptures of the spleen.—Ruptures of the spleen may occur either from violence or disease, and it would appear from the following case ('Med.-Chir. Rev.' Oct. 1839), that a slight degree of violence is sufficient to rupture this organ, while there may be no marks of injury externally. A middle-aged man was observed fighting with a boy about fourteen years of age, who in stature scarcely reached to his waist. When the fight had terminated the boy ran away: the deceased was observed to become weak and faint, and he complained of uneasiness in his left side. He expired a few minutes afterwards. On inspection, no marks of violence could be detected externally; but the cavity of the abdomen contained a large quantity of blood. The spleen was found enlarged, and so softened that its structure was broken down by the slightest pressure. There was a laceration across its surface, about half an inch in depth, from which the fatal bleeding had proceeded. A similar case, in which death occurred in fifteen minutes, is reported in the 'Med. Gaz.' vol. 35, p. 942. The rupture was caused by a blow, but there was no mark externally to indicate that a

blow had been struck. A case of spontaneous rupture of the spleen, which was enlarged and in a diseased condition, is reported in the same journal for June, 1842. A little girl died in fourteen hours from rupture of the spleen. The rupture had arisen from the wheel of a cart passing over her body. There was no mark of external violence. It is highly probable that, when the liver and spleen are ruptured from slight causes, the structure of these organs will be found to be in a diseased condition—a circumstance which might in some cases be regarded as mitigatory of the act of an assailant. ('Med. Gaz.' vol. 35, p. 942.) A man, æt. 24, fell from a mast-head, twenty-five feet in height, and it was thought that he had fallen on his back. He was rowed ashore and walked to the hospital, where he arrived about an hour after the accident. He died in a quarter of an hour, apparently from internal hæmorrhage. On inspection, there were no external signs of injury. The abdomen contained several pints of blood. The spleen was torn transversely through its middle, and the splenic vein was lacerated in a longitudinal direction. This organ was about twice its natural size, soft, and had the appearance of a large ague spleen. ('Lancet,' 1864, II. p. 716.) The exertion of walking probably led to the fatal effusion, and accelerated death.

Ruptures of the kidneys.—The *kidneys* are occasionally ruptured from violence; but this appears to be a rare accident. Two cases were reported to the Med.-Chir. Soc. ('Lancet,' Nov. 1843.) In one, the person recovered; in the other, death did not take place for a considerable time. In another case, the injury occurred during a scuffle: its existence was not suspected during life. A rupture of the kidney may be produced without any prominent symptoms, and cause death in a few hours. A man, æt. 60, was run over by a light cart. He walked to the house of a friend at a short distance, and went with him to the hospital in a cab. It was found that three ribs were fractured, but there was no urgent symptom or sign of collapse. He was treated for fractured ribs, and then walked home with his friend and went to bed. Between five and six hours after the accident he was observed to sit up in bed and suddenly fall back dead. On inspection, no bruise or wound of any kind was found on the injured side. There was a large quantity of fluid and coagulated blood in the abdomen. This had evidently proceeded from the right kidney, which was torn in half transversely through the pelvis. The ninth, tenth, and eleventh ribs were fractured. It is probable that the blood had escaped slowly from the ruptured organ. The case proves that a kidney may be torn in halves and yet the person possess a power of locomotion and muscular exertion.

Ruptures and wounds of the intestines.—Ruptures of the intestines sometimes occur from disease; and, in a case of rupture alleged to have been produced by violence, we must always take this possible objection into account. The ruptured part of the bowel should be carefully examined, in order to see whether there are any signs of ulceration or softening about it. If not, and there is clear evidence of violence having been used, it is impossible to admit this speculative objection. If with the proof of violence there should also be a diseased condition of the bowel, we may be required to say whether this did not create a greater liability to rupture—a point which must be admitted. (See 'Watson on Homicide, p. 159; Henke's 'Zeitschrift der S. A.' 1836; 'Erg. H.' vol. 22; and 'Brit. and For. Rev.' vol. 4, p. 519.) The intestines may be ruptured by an accidental fall. ('Med. Times and Gaz.' 1861, I. p. 403.) Rupture of the intestines may sometimes occur from very slight causes. Any force, as a smart shock *suddenly* applied to the abdomen, will sometimes suffice to cause it. A case has already been related where the blow of a pebble ruptured the jejunum of a young girl by striking the abdomen. A case is reported, in


which there was no doubt that the ileum had been ruptured by a kick on the abdomen, leading to death by peritonitis. The coroner and jury appear to have thought that, as there was no mark of contusion or ecchymosis on the abdomen, the blow could not have been the cause of the mischief; hence they came to a verdict that the deceased had died from inflammation of the bowels depending on some unknown causes. ('Lancet,' Aug. 9, 1846, p. 15.) It is worthy of remark, that a rupture of the intestines does not necessarily deprive a person of the power of locomotion. A boy, æt. 13, had his duodenum completely ruptured across by a blow: he walked a mile with but little assistance, but he died in thirteen hours. ('Med. Gaz.' vol. 12, p. 766.) A boy of 13 was struck by a cricket-ball in the right groin, in spite of which injury he remained on the ground more than an hour and a half, and then walked more than a mile to his home. He died on the fifth day from peritonitis, as a result of rupture of the intestines and escape of the contents. ('Amer. Jour. Med. Sci.' April, 1870, p. 485.) A kick in the same part led to rupture of the small intestines, and death in twelve hours. ('Vierteljahrsschr. d. ger. Med.' April, 1872, p. 235.) That rupture of the intestines is not incompatible with the power of locomotion is also proved by a case where the cæcum was ruptured: the man was able to walk after the accident, but he died in twenty-four hours. Other instances of this kind are reported by Henke. The ileum is observed to be most liable to rupture from accident. In 1861, a man was brought into Guy's Hospital. He was able to walk to his bed, and he did not appear to be seriously injured, although it was stated that a bale of wool had fallen on him. In the evening he became collapsed, and he died twelve hours after his admission. On inspection, about a pound of blood was effused in the abdomen, and a portion of the ileum was found lacerated—the laceration extending into the mesentery and including the blood-vessels. The laceration was about an inch and a half long, and the bowel was divided not quite through. The intestines were much matted together by lymph and blood, the result of peritoneal inflammation. There had been only slight extravasation of the contents. ('Med. Times and Gaz.' Sept. 1861.) In two fatal cases of ruptured jejunum, one arising from a kick on the abdomen and the other from an accidental fall, it was observed that the power of locomotion and muscular exertion was retained.

Punctured wounds, which merely touch the bowels without laying open the cavity, are liable to cause death by peritonitis. These injuries to the intestines sometimes destroy life by shock; there is but little blood effused, and the wounded person dies before peritonitis can be set up. Severe wounds to the intestines may, however, be inflicted almost without the consciousness of the individual, and the wounded person may be able to walk a considerable distance. ('Med. Gaz.' vol. 46, p. 24.)

Wounds and ruptures of the stomach.—Wounds and ruptures of the stomach may cause death by shock; ruptures commonly give rise to severe pain, sufficient of itself to bring about speedy death. The stomach may be ruptured from spontaneous causes, as in ulceration from disease; but sometimes there is no morbid cause apparent. In 1828, a man, æt. 34, was brought into hospital, complaining of severe pain in the abdomen. Ten hours afterwards he was seized with violent vomiting, the pain ceased, the vomiting also ceased, and he died in five hours more. The posterior surface of the stomach was found lacerated to the extent of three inches, and its contents had escaped through the aperture: the mucous membrane was reddened, but there was no thickening, ulceration, or any apparent disease. ('Med. Gaz.' vol. 2, p. 182; also 'Dub. Med. Jour.' May, 1845; and 'Ed. Med. and Surg. Jour.' Oct. 1845, p. 522.) In a similar case, a boy, æt. 10, had great pain in the abdomen, which was much swollen,

and he died in a few hours, in a state of collapse. After death, the cardiac extremity of the stomach, which was softened, but not otherwise diseased, was found ruptured. ' (Lancet,' Jan. 3, 1846, p. 15.) A man, æt. 30, labouring under intermittent fever, died suddenly, after having been to the water-closet. On inspection, the stomach was found ruptured on its anterior surface, to the extent of about two inches, and the contents had escaped into the abdomen. There was no softening or morbid change in the coats, with the exception that the mucous membrane was dotted with redness for a slight distance around the aperture. ('Phil. Med. Exam.' Nov. 1845, p. 695.) A case occurred in which the stomach was ruptured at its pyloric end. The spleen was also ruptured by the same accident—a fall of about twenty feet. The man died in about fourteen hours, evidently from internal hæmorrhage. The rupture was about five inches in length, and extended from the pyloric end of the stomach into the duodenum. ('Amer. Jour. Med. Sci.' Oct. 1870, p. 575.) A remarkable feature of this case was that there was no indication of bruise or other external injury. Such an injury is not inconsistent with the power of locomotion, although it may be doubted whether in the case reported the large rent in the stomach took place until just before death. ('Brit. Med. Jour.' 1870, II. p. 617.) It is obvious that, in alleged lacerations from violence, this liability to spontaneous rupture must not be forgotten. Penetrating wounds of the stomach generally prove rapidly mortal; but they seldom form a subject for medico-legal investigation. A case was tried at the Norwich Assizes in 1832, in which a man was charged with the murder of his wife, by throwing at her a red-hot poker. The weapon completely perforated her stomach, and the woman died in six hours.

Fig. 133.



Vertical and longitudinal section of the stomach and duodenum (Wilson).

1. Œsophagus or gullet.
2. Cardiac orifice of the stomach.
3. Cardiac or greater end.
4. Pyloric or lesser end.
5. Lesser curvature.
6. Greater curvature.
8. Rugæ (folds) of the stomach formed by the mucous membrane; their longitudinal direction is shown.
9. Pylorus.
10. Ascending portion of duodenum.
11. Descending portion of duodenum.
12. Ducts of the pancreas and liver.
14. Transverse portion of duodenum.
15. Commencement of jejunum. The transverse striæ or folds in the interior of the duodenum and jejunum represent the valvulæ conniventes.

The illustration, fig. 134, p. 674, represents the stomach, and the small and large intestines. The stomach is seen in section, with its cavity laid open. *a*. The stomach, with its cavity seen in section. *b*. The œsophagus, or gullet, opening into *c*, the cardiac, or larger end of the stomach (on the left of the body). *d*. The pyloric, intestinal, or right end of the stomach. *e*. The situation of the pylorus, or valve which separates the cavity of the stomach from that of the intestines. *f*. The duodenum, or first portion of the small intestines seen in section. *g*. The convolutions of the jejunum, or second portion of the small intestines. *h*. The convolutions of the ileum, or the third and lowest portion of the small intestines. *i*. The cæcum, or blind-bowel, the first portion of the large intestines. *k*. The vermiform appendix of the cæcum. *l m n*. The ascending, transverse, and descending colon, or second portion of the large intestines. o. The

sigmoid flexure of the descending colon. *p*. The rectum, or lower bowel, the third and last portion of the large intestines.

Fig. 134.




The stomach, in connection with the small and large intestines.

Fig. 135 represents, in outline, the stomach and duodenum, with the liver, spleen, and pancreas. 1. The liver, of which the under surface is here seen, is raised and turned back, so as to expose the other viscera covered by it. It is divided into two unequal parts by a longitudinal fissure—seen in the upper margin—the right or large lobe being on the left of the engraving, and the left or small lobe being on the right. 2. The transverse fissure of the liver. 3. The gall-bladder, of a pyriform shape, of which the neck is towards the centre of the liver and the thickest part or fundus is towards the anterior margin. 4. Represents the stomach. 5. The entrance of the gullet or œsophagus—the cardiac opening; and 6. The situation of the pylorus, or intestinal opening. 7, 8. The duodenum, or first part of the small intestines, in its descending and transverse portions. 9. The pancreas. 10. The spleen. 11 and 12. The aorta.

Ruptures of the bladder.—This injury is frequently the result of blows on the lower part of the abdomen. The principal questions in reference to the accident are:—Was the rupture the result of wilful violence, or of an accidental fall?—or, Did it proceed from spontaneous causes, as from over-distension? The spot in which rupture commonly takes place is in the upper and back part, where the bladder is covered by the peritoneum. The aperture is sometimes large, at others small; but the effect is that the urine is effused, and death takes place sooner or later from inflammation. Ruptures, when attended with extravasation of urine into the peritoneal cavity, are almost uniformly fatal; but if the rupture occurs in the under part of the bladder, and the urine finds its way into the cellular tissue, the medical opinion is not so unfavourable. Syme has reported a case of recovery under these circumstances. ('Surg. Contributions,' p. 332.) Some observers have even met with cases of recovery where it was asserted that the peritoneum was involved in the rupture. A case of this description was reported

Fig. 135.



The liver, stomach, and duodenum, in their relative position with the pancreas and spleen.

('Lancet,' Nov. 1843); and another in which the patient, while his bladder was full, struck the lower part of his abdomen against a post. He fell, but was afterwards able to reach his home with some difficulty, at a distance of one hundred yards. He suffered under all the usual symptoms, and in eighteen hours peritonitis appeared. This was subdued, but again supervened, apparently from rupture of the adhesions. In two months, however, the patient had wholly recovered. ('Lancet,' July 25, 1846, p. 112.) Another case of recovery from this injury is reported. ('Amer. Jour. Med. Sci.' Oct. 1872, p. 579.)

The usual period at which death occurs from this accident is in from three to seven days; but in one case the person did not die until the fifteenth day. The cause of death is obviously peritoneal inflammation; but a person may die suddenly from this injury as a result of shock. ('Assoc. Jour.' Jan. 28, 1853, p. 88.) A man, while struggling with another, received a severe kick on the lower part of the abdomen. He fell backwards, and died immediately. On inspection, the brain was congested, but otherwise healthy; the heart was free from disease, but much distended with black coagulated blood. The bladder presented, on the left side of the body, a rent of about two inches; but this organ was in other respects healthy, as well as the urethra. There was some bloody effusion in the cellular tissue. The peritoneum and viscera of the abdomen were uninjured. There were no marks of violence on the body.

When these ruptures are produced by blows, they are rarely accompanied by marks of ecchymosis, or of injury to the skin. Thus, then, there may be no means of distinguishing, by external examination, whether a rupture was really due to violence or to spontaneous causes. During a quarrel one man struck another a severe blow on the lower part of the abdomen. The latter was carried home, confined to his bed, and died in seven days. There were only a few superficial excoriations on the skin of the abdomen. The bladder was found ruptured to the extent of two inches in its upper and back part; it was highly inflamed. Throughout the abdomen there were the marks of general peritoneal inflammation, of which the man had died. There was a sanguineous fluid effused, exhaling a strong ammoniacal odour. ('Ann. d'Hyg.' 1836, 207.) Some doubt was thrown on the correctness of the medical opinion, that the rupture had been caused by a blow, because there was no ecchymosis or other mark indicative of a severe blow over the region of the bladder. The witnesses properly answered, that ruptures of the viscera of the abdomen from violence were not necessarily attended with the marks of violence found in injuries to other parts, owing to the yielding and elastic nature of the parietes. One of them mentioned a case that had occurred to him, where a soldier had received in the abdomen a kick from a horse, which had ruptured the small intestines, and caused death; but there was not the slightest trace of violence externally.

In another case (*Reg.* v. *Eccles*, Lancaster Lent Ass. 1836), the prisoner, who was half-intoxicated, met the deceased on the high road, and without receiving any provocation gave him a violent kick on the lower part of his abdomen. The deceased turned sick; he attempted to pass his urine, but could not; he was conveyed home, and died from peritonitis in five days. There was no ecchymosis, or other injury to the skin indicative of external violence; but the bladder was found ruptured, and the contents extravasated. The rupture was attributed to the blow inflicted by the prisoner. In the defence, it was urged that as there was no mark of a blow, the rupture might have occurred spontaneously from simple over-distension. The judge observed that if the rupture was thus occasioned, it was extraordinary that it should have happened immediately

after a violent blow had been struck on the part. The distension of the organ might, however, have rendered the blow *more dangerous* than it otherwise would have been. The prisoner was convicted.

As an attempt may be made, in cases in which death has resulted from this injury, to refer rupture of this organ to natural causes, it may be observed that this is an unusual occurrence; a rupture is almost always the result of violence directly applied to the part, while the organ is in a *distended* state. A *spontaneous rupture* may, however, occur: 1. When there is paralysis, with a want of power to expel the urine. 2. When the bladder is ulcerated, or otherwise diseased. 3. When there is an obstruction in the urethra from stricture or other causes. For a fatal case of rupture of the bladder arising from obstruction as a result of disease, see 'Med. Times and Gaz.' Dec. 13, 1856, p. 590. The causes of spontaneous rupture are recognizable by ascertaining the previous condition of the deceased, or examining the bladder and urethra after death. If a man were in good health prior to being struck; if he suddenly felt intense pain, could not pass his urine afterwards, and died from an attack of peritonitis in five or six days; if, after death, the bladder was found lacerated, but this organ and the urethra were otherwise in a healthy condition, there can be no doubt that the blow must have been the sole cause of rupture and death. A diseased state of the bladder might probably diminish the responsibility of an accused person for the consequences; therefore the state of this organ should be closely looked to on these occasions. From the case mentioned above, it might be inferred, that the fact of the bladder being *distended* at the time of the blow, would be held an extenuating circumstance; but we can hardly suppose that such would be the deliberate opinion of our judges. (See p. 675.) The fact is, this most serious injury is never liable to occur from violence, except when the bladder is distended. If a pregnant woman be killed by a blow on the abdomen, which causes rupture of the uterus, the act cannot be regarded as admitting of mitigation because the uterus is only occasionally in this distended state.

The bladder ruptured by an accidental fall.—The following case shows that this accident may readily occur. A woman, æt. 26, fell forwards over the edge of a tub, and fainted immediately. On recovering herself, she complained of intense pain in the abdomen, with inability to pass the urine. Peritonitis came on, and she died in a week. On inspection, a small aperture was found in the upper part of the bladder; the peritoneum was extensively inflamed owing to the urine which had become effused. The ruptured surfaces had become partly glued together. ('Ed. Med. and Surg. Jour.' Oct. 1836.) Rupture of the bladder may take place from an accidental fall, and cause death without necessarily laying open the peritoneal cavity. For two cases of this kind see 'Med. Gaz.' vol. 36, p. 621. The patients were sailors who fell from their hammocks while in a state of intoxication. The usual symptoms followed; one died in five, and the other in eight days, from peritonitis; and after death it was found, in one instance at least, that the bladder had been ruptured in the usual situation, but the peritoneum was entire, although in a state of intense inflammation. Another case of this kind, which was the subject of a trial (*Reg.* v. *Dixon*, Durham Lent Ass. 1846). The prisoner kicked the deceased in the pubic region from behind. The man died from peritonitis in thirty-five hours. On inspection, the bl[redacted] found ruptured near its neck for about half an inch, immedi[redacted] to the left of the prostate gland. The urine was ext[redacted]lar tissue of the scrotum: but although there was [redacted], the peritoneum was not lacerated. A remar[redacted] a man died on the sixth day from

rupture of the bladder; and after death, although the peritoneum was lacerated, and the cavity of the abdomen was filled with dark-coloured urine, there was no sign of peritoneal inflammation. ('Lancet,' Dec. 19, 1846, p. 660.) This accident is liable to occur in women during parturition, owing to the pressure of the child's head; an occurrence which may throw a charge of malapraxis on the medical attendant. He is expected to know the probability of such an accident occurring, and to guard against it, if necessary, by the use of the catheter. In *Reg.* v. *Balsoner* (Liverpool Lent Ass. 1838), a surgeon was tried on a charge of this kind. It is important to remember, that although rupture of the bladder is commonly attended, at the time of its occurrence, with intense pain, sickness, and prostration of strength, yet persons may occasionally retain the power of exerting and moving themselves after the accident.

In punctured and incised wounds of the bladder, the urine is immediately extravasated, but in gunshot wounds the extravasation does not commonly take place until the sloughs have separated. Thus, life may be protracted longer in cases of gunshot than under other wounds of the bladder. Barzellotti relates the case of a man, shot through the bladder in a duel, who did not die until the *twentieth day* from peritonitis which supervened on the extravasation. ('Questioni di Med. Leg.' t. 3, p. 174.) One instance of a person recovering from a gunshot wound perforating the bladder, is reported in the 'Ed. Med. and Surg. Jour.' vol. 13. For the discovery of effused liquids or blood, in wounds and other injuries to the abdominal viscera, we must look to the cavity of the pelvis, as it is here that, for obvious reasons, such liquids have a tendency to collect.

Wounds of the genital organs.—Wounds of these organs, whether in the male or female, may prove fatal to life by excessive hæmorrhage. Self-castration or mutilation is not unfrequent among male lunatics and idiots. The practice of circumcision on infants is sometimes followed by fatal results. Schwartz met with two cases of boys eight days old, who were submitted to this rite, and both died of phlegmonous inflammation, one five days and the other twenty-five days after the operation. ('Lancet,' 1870, II. 471.)

Incised, lacerated, or even contused wounds of the female genitals, may prove fatal by loss of blood, not from the wound involving any large vessel, but from the numerous small vessels which are divided. Two women were in this way murdered in Edinburgh some years since. The wounds were inflicted by razors, and the women bled to death. (See Watson, 'On Homicide,' p. 104.) This crime appears to have been at one time frequent in Scotland. When deeply *incised* wounds are inflicted upon the genital organs of either sex, the fact of their existence in such a situation is strongly presumptive of wilful and deliberate malice on the part of an assailant. Such wounds require to be carefully and minutely examined; for the proof of this kind of wound, when fatal, may be tantamount to a proof of murder. A contused wound of the genitals may cause death by hæmorrhage. A case is reported in which a woman, in the eighth month of pregnancy, fell from a chair, which also fell with her. There was hæmorrhage, and she died in a quarter of an hour. The blood had flowed from a wound an inch and a half long, situated between the right labium and the urethra. The edges appeared to be cleanly divided, and the wound penetrated into the cellular tissue. ('Dub. Quart. Jour.' 1870.) In the case of *Reg.* v. *Ling* ('Lancet,' 1870, II. 268), the medical evidence for the prosecution went to show that a wound in the vulva of a female, found dead from hæmorrhage, had been produced by a stick on which blood and hair were found. A medical man who appeared for the defence thought that a varicose vein had burst and caused the bleeding, and that the injury had

not been produced by the violent use of a stick. The jury acquitted the prisoner.

A practitioner may be sometimes required to determine whether wounds affecting the female organs have resulted from accident, have been self-inflicted, or inflicted by others with homicidal intention. In 1842, a woman received a longitudinal wound in the genitals on the left side by a cutting instrument, to the extent of an inch and a half. There was a smaller wound on the right side. The accused alleged that the woman had inflicted the injury on herself; and Easton, on being required to state his opinion on the question at issue, came to the conclusion:—1. From the regular edges of the wounds, that they had been produced by a clean cutting instrument, and therefore could not have been caused by a fall, excepting the person had fallen upon some sharply cutting projection. 2. If the woman had injured herself by thrusting a knife into the private parts, the situation and direction of the wounds would have been different. There was a want of proof to connect the prisoner with the act, and he was discharged. This is an improbable situation for the self-infliction of wounds with a view to suicide. Accidental wounds of the genitals, unless all the circumstances are known, may sometimes resemble those produced by design. A girl, æt. 6, fell from a tree with her legs apart upon one of the sharp-pointed shoots below, about half an inch thick. This entered the vagina, and passing through its posterior wall, broke off. A woman removed the wood with some difficulty. The child died in twenty-eight hours from peritonitis. ('Lancet.' 1871, II. 74.) Had this child been found dead with the wood in her body, there might have been some difficulty in assigning an accidental origin to such an injury. (For remarks on wounds of the male genital organs, see 'Ann. d'Hyg.' 1868, 2, 110. Toulmouche.) Some rules which have been elsewhere given (p. 498 *et seq.*) may enable a witness to form an opinion when a question of this kind is involved in doubt. (For cases in which such wounds were homicidally inflicted upon males, see 'Ann. d'Hyg.' 1848, 1, 443; also 1865, 1, 156; and for a case, which led to a trial for the murder of a woman, see 'Med. Gaz.' vol. 44, p. 813.)

Contused wounds on the female genitals sometimes prove fatal, by the laceration of parts leading to great loss of blood. Several trials for manslaughter have taken place in which this was proved to have been the cause of death. (*Reg.* v. *Cawley*, Liverpool Wint. Ass. 1847; 'Assoc. Med. Jour.' June 28, 1856, p. 538.) There may be such a loss of blood in these cases as to destroy life, although no large blood-vessel is implicated in the injury. A contused wound on the vulva may occasionally present an ambiguous appearance, and be mistaken for an incised wound. When the soft parts of the body are struck by a blow or kick, if there is a bony surface beneath, a longitudinal rent may appear as a result of the force being received by the bone. A blow on the cranium with the fist produced in one instance a rent which was at first mistaken for a cut. A kick on the vulva, or a fall on this part, may produce a similar injury, and, unless carefully examined, may lead to the inference that a weapon has been used for its production. A contused wound of the clitoris proved fatal. ('Lancet,' Oct. 31, 1846, p. 478.) A woman, æt. 36, received a kick from her husband in the lower part of the abdomen while she was in a stooping posture. When seen in about three-quarters of an hour, she had lost from three to four pounds of blood. She was sinking, and expired a few minutes afterwards. On inspection, there was no injury to the uterus or vagina; the wound was situated at the edge of the vulva, extending from the pubes along the ramus of that bone. It was about an inch long and three-quarters of an inch deep. The left crus

clitoridis was crushed throughout its length, so as to exhibit its cavernous structure. From this the fatal bleeding had proceeded. The heart and great vessels contained no blood. The bleeding from such injuries is always likely to be more profuse, but is not always fatal, when the woman is pregnant. ('Med. Times,' May 15, 1847, p. 233.) Some women are subject to frequent discharges of blood from the genital organs from natural causes. When the bleeding immediately follows a blow, and the woman has not been subject to such a discharge, the fair presumption is that violence was the cause; but when the flow of blood appears only a long time after the alleged violence, of which no traces can be seen, it is most probably due to natural causes. In one case of this kind there was no difficulty in giving an opinion that the flow of blood was *not* due to violence.

It may be alleged in defence that the injuries found on the body were inflicted *after death*, and not while the deceased was living. Kicks or blows on the vulva, if they destroy life at all, cause death by copious effusion of blood. Violence to this part after death would not produce such an effusion as would account for death. There are also other distinguishing characters which have been elsewhere pointed out (see p. 487). A case was tried in Edinburgh, in which this defence was set up; but Simpson was enabled to say, from his observation of the effects of such violence to a dead body, that the injuries in question could not have been produced after death.

CHAPTER 49.

FRACTURES—PRODUCED BY A BLOW WITH A WEAPON OR BY A FALL—OCCUR IN THE AGED—BRITTLENESS OF THE BONES—FRACTURE CAUSED BY SLIGHT MUSCULAR EXERTION—IN THE LIVING AND DEAD BODY—HAS A BONE EVER BEEN FRACTURED?—LOCOMOTION—DISLOCATIONS FROM VIOLENCE OR NATURAL CAUSES—MEDICAL OPINIONS—ACTIONS FOR MALAPRAXIS.

FRACTURES.

FRACTURES of the bones have some important bearings in relation to medical jurisprudence. They may result from falls, blows, or the spontaneous action of the muscles.

Causes.—Questions are sometimes put as to whether a particular fracture was caused by an accidental fall or a blow; and if by a blow, whether by the use of a weapon or not. It is obvious that the answers must be regulated by the circumstances of each case. In examining a fracture, it is important to determine, if possible, whether a *weapon* has or has not been used, and this may be sometimes ascertained by the state of the parts. It is a common defence on these occasions, to attribute the fracture to an accidental fall. Fractures more readily occur from equal degrees of force in the old than in the young, and in the young rather than in the adult; because it is at the adult period of life that the bones possess their maximum degree of firmness and solidity. The bones of aged persons are sometimes very *brittle*, and slight violence will then produce fracture. This has been regarded as an extenuating circumstance, when the fracture produced by a slight blow was followed by death. Certain diseases, such as syphilis, arthritis, cancer, scurvy, and rickets, render bones more fragile; but they are sometimes preternaturally brittle in apparently healthy persons, and this brittleness appears to be hereditary.

('Dub. Hosp. Gaz.' Feb. 1846, p. 186.) In such cases, a defence might fairly rest upon an abnormal condition of the bones, providing the violence producing the fracture was slight. Several trials have taken place in which this brittleness of the bones became a subject of inquiry. In a case of fractured skull leading to death from inflammation of the brain, it was proved that the bones of the skull were occasionally thin and brittle, and this led to a mitigation of punishment. (*Reg.* v. *Kennedy*, Gloucester Wint. Ass. 1855.) The orbital plate of the frontal bone is very thin, and it may be fractured by a blow on the eye. (*Reg.* v. *Wilson*, Oxford Lent Ass. 1859.) Death was here caused by inflammation of the brain as the result of such a fracture. There is occasionally another condition of the skull, namely, a congenital depression or thinning of the outer table, which may be mistaken for fracture. In *Barnett* v. *Roberts* (Court of Exch. Nov. 1867), an action was brought by plaintiff, a surgeon, for injury resulting from an assault by the defendant. It appeared from the evidence that the defendant struck the plaintiff two violent blows on the head with the handle of his umbrella. It was alleged that this had caused a fracture of the skull, and had produced a long and painful illness. Erichsen, and Forbes Winslow, gave evidence for the plaintiff to the effect that in their judgment the skull was fractured, the brain organically injured, and the plaintiff's recovery rendered practically hopeless. For the defence, Partridge, Wood, and other witnesses, deposed that the skull was not fractured—that the depression supposed to indicate the fracture was congenital and not the result of a blow or accident. A skull with a natural depression in it was produced and shown to the jury. The plaintiff's head was examined in court by Partridge. He could feel no cicatrix in the alleged seat of injury, but there was a thickening over the depression. On this evidence the jury could not agree. Even if there had been a cicatrix on this occasion, this would not have proved that the skull had been fractured. The injury to the brain might well have been a result of the violence, although there had been no fracture.

Spontaneous Fractures.—In a case in which there is no appearance of disease, a fracture may be ascribed to spontaneous causes. Thus bones have been fractured by moderate muscular exertion. The elbow (olecranon), heel-bone (os calcis), and knee-pan (patella), are particularly exposed to this accident. The long bones are seldom the subject of an accident of this kind; but the arm (humerus) in a healthy man has been broken by the simple muscular exertion of throwing a cricket-ball. ('Med. Gaz.' vol. 16, p. 659.) A young lady fractured the neck of the scapula by suddenly throwing a necklace round her neck. ('Med. Gaz.' Oct. 1842.) In 1858, a man, æt. 40, was in the act of bowling at cricket, when on delivering the ball he and some bystanders heard distinctly a sharp crack, like the breaking of a dry piece of wood. He fell to the ground as if he had been shot. The thigh-bone was found to be fractured, evidently from muscular exertion only. In 1871, while a strong young member of the Scottish volunteers was in the act of 'putting' a sixteen-pound shot, making at the time a violent effort, he felt something snap in his arm and instantly lost all power over it. It was found on examination that the humerus had been broken by muscular force. No person can meet with an accident of this kind without being instantly conscious of it. It is probable that in these instances, if there were an opportunity of examining the bone, it would be found to have undergone some change in its composition, which had rendered it brittle. A case of spontaneous fracture of the femur was brought into Guy's Hospital, in 1846. A healthy man, temperate, æt. 33, was in the act of placing one leg over the other to look at the sole of his foot, when he heard something give way, and the right leg imme-

diately hung down. It was found that the right thigh-bone had been transversely fractured at the junction of its middle with the lower third. This case is remarkable, inasmuch as spontaneous fractures of the thigh-bones are very rare, as the man had not suffered from any of those diseases which cause preternatural fragility, and the fracture was not caused by violent muscular exertion. The actual condition of the bone was of course unknown; but it healed readily, and the man left the hospital at the usual period. In fractures arising from this cause there will be no abrasion of the skin, nor any appearance to indicate that a blow has been struck; while the marks of a blow would, of course, remove all idea of the fracture having had a spontaneous origin. It is most unusual that the ribs should be fractured from muscular exertion; but a case occurred which shows that this accident may readily occur. The patient was a strong healthy labourer, æt. 45, who, slipping while walking, only saved his footing by the exertion of considerable strength. While recovering his balance he felt a sharp pain on his right side, which was aggravated by inspiration and by exertion, so that he reached home with difficulty. On examination a tender spot of about half a hand's breadth was found in the axillary region over the seventh and eighth ribs. Crepitation was not distinct, and emphysema was not present. As the pain occurred so suddenly, and was limited to so small a space, it was supposed that a rupture of the muscular fibres had taken place, although the absence of all swelling and effusion, as well as of any depression amidst the fibres, rendered this not very probable. Pleurisy was set up, and the patient was confined to bed for a fortnight; when all traces of pain had left the part, the deposition of callus (new bone) plainly showed that there had been fractures of the seventh and eighth ribs. ('Archiv. der Heilk.' vol. 1, p. 473; also 'Med. Times and Gaz.' Ap. 1861, p. 450.)

Fractures are not *dangerous to life*, unless, when of a compound nature, they occur in old persons, or in those who are debilitated by disease or dissipated habits. They may then cause death by inducing irritative fever, erysipelas, gangrene, tetanus, pyæmia, or delirium tremens.

Fractures in the living and dead body.—It is not always easy to say whether a fracture has been produced *before or after death*. A fracture produced shortly after death, while the body is warm, and another produced shortly before death, will present similar characters, except that in the former case there might be less blood effused. A fracture caused ten or twelve hours before death would be indicated by a copious effusion of blood into the surrounding parts and between the fractured edges of the bones, as well as by laceration of the muscles; or if for a longer period before death, there may be the marks of inflammation. Fractures caused several hours after death are not accompanied by an effusion of blood. A medical witness may be asked,—How long did the deceased survive after receiving the fracture? This is a question which can be decided only by an examination of the fractured part. Unless the person has survived eighteen or twenty-four hours, there are commonly no appreciable changes. After this time, lymph is poured out from the surrounding structures. This slowly becomes hard from the deposition of calcium phosphate, and forms what is called a 'callus' (new bone). In the process of time, the callus acquires all the hardness of the original bone. The death of a person may take place during these changes, and a medical man may then have to state the period at which the fracture probably happened, in order to connect the violence with the act of a particular person. Unfortunately, we have no satisfactory data, if we except the extreme stages of this process of repair, upon which to ground an opinion. We can say whether a person lived for a long or a short time after receiving a fracture, but to specify the exact time

is clearly impossible; since this process of restoration in bone varies according to age, constitution, and many other circumstances. In young persons, bones unite rapidly, in the old slowly; in the diseased and unhealthy the process of union is slow, and sometimes does not take place at all. In those who are at the time affected with a mortal disease there is usually no attempt at reparation. (Astley Cooper.) According to Villermé, the callus assumes a cartilaginous structure in from sixteen to twenty-five days; and it becomes ossified in a period varying from three weeks to three months. It requires, however, a period of from six to eight months for the callus to acquire all the hardness, firmness, and power of resisting shocks possessed by the original bone. A force applied to a recently united bone will break it through the callus or bond of union, while after the period stated the bone will break as readily through any other part. It is generally assumed that the period required for the union of a simple fracture in a healthy person, is, for the thigh-bone, six weeks; for the tibia (leg), five weeks; for the humerus (arm), four weeks; and for the ulna and radius (fore-arm), three weeks; for the ribs, about the same period: but cases have been known in which the ribs had not perfectly united in two months, and in some fractures of the other bones it was found that union had not taken place in four months. In a case which occurred to Reid (*ante*, p. 648), a fracture of the tibia, the principal bone of the leg, had healed in thirty-one days.

Has a bone ever been fractured?—This question is sometimes put in reference to the *living* body. It is well known that a bone seldom unites so evenly that the point of bony union is not indicated by a node or projection. Some bones are so exposed as to be well placed for this examination, as the radius, the collar-bone, and tibia—these being but little covered with skin; in others the detection is difficult. It is impossible for us to say when the fracture took place; it may have been for six months or six years—as, after the former period, the bone undergoes no perceptible change. These facts are of importance in relation to the *dead* as well as to the living; since they will enable us to answer questions respecting the identity of skeletons found under suspicious circumstances: and here medical evidence may take a wider range, for a fracture in any bone may be discovered, if not by external examination, at least by sawing the bone longitudinally through the suspected broken part, when, should the suspicion be correct, the bony shell will be found thicker and less regular in the situation of the united fracture than in the other parts. So, in such cases, it will be easy to say whether a fracture is recent or of old standing. (See p. 159.)

Locomotion.—With respect to the power of *locomotion* after a fracture, it may be observed, that when the injury is in the arm or in the ribs—unless many of them are broken or the fractures are on both sides—a person may be able to move about, although unfitted for struggling or making great exertion. Fractures of the leg generally incapacitate persons from moving except to short distances. See case, 'Ed. Med. and Surg. Jour.' Oct. 1836; also another in which one bone of the leg was fractured, and a power of walking some miles was retained. ('Amer. Jour. Med. Sci.' Oct. 1845, p. 484.) The reader will find additional information on this subject in the 'Ann. d'Hyg.' 1839, 2, 241 [illegible] 2, 146; and in Friedreich 'Ueber die Knochen in forens. Bezie[illegible] 1853.

DISLOCAT[illegible]

Dislocations are not frequent in the [illegible] whose bones are brittle. They rarely form a subj[illegible] vestigation. A witness is liable to [illegible]

direction, would produce a dislocation—questions not difficult to answer. They are not dangerous to life, unless of a compound nature, when death may take place from secondary causes. A dislocation which has occurred in the *living body* may be known after death by a laceration of the soft parts in the neighbourhood of the joint, and by the copious effusion and coagulation of blood. For an account of the appearances presented by a dislocation of the shoulder four days after death, see 'Med. Gaz.' vol. 31, p. 266. If of old standing, a dislocation would be identified by the cicatrices in surrounding structures. Dislocations may occur from *natural causes*, as from disease and destruction of the ligaments in a joint; also from violent muscular spasm during an epileptic convulsion. Dymock met with an instance of dislocation of the shoulder forwards during puerperal convulsions. ('Ed. Med. and Surg. Jour.' Ap. 1843; see also 'Lancet,' Ap. 1845, p. 440.) A power of *locomotion* may exist, except when the injury is in the lower limbs: but it has been observed that, for some time after a dislocation of the hip-joint, considerable power over the limb remains; it is only after a few hours that the limb becomes fixed in one position. Exertion with the dislocated member is in all cases out of the question.

Detection of fractures. (*Malapraxis.*)—There are certain fractures of an obscure kind which closely resemble dislocations. This has been pointed out by Astley Cooper, in relation to fractures of the anatomical neck of the os humeri (arm-bone). ('Guy's Hosp. Rep.' vol. 9, p. 272.) This accident might easily be mistaken for a dislocation of the shoulder. ('Med. Gaz.' vol. 36, p. 38.) In attempting to reduce the bone, the head continually falls back into the axilla. In such a case an action for malapraxis might be brought against a surgeon. It could only be by a dissection of the part after death that the real nature of the case would be ascertained. It is requisite, therefore, that great caution should be used in giving an opinion. The same observations apply, although with less force, to fractures of the neck of the thigh-bone, because this is a more common accident. It is well known that fractures and dislocations, when cured, are often attended with some slight *deformity* of the limb, or with some impairment of its functions. This result is occasionally inevitable under the best treatment; but it is commonly set down as a sign of unskilfulness in the medical attendant. An action for malapraxis is instituted, and the surgeon is sometimes heavily fined for a result which could not be avoided.

CHAPTER 50.

GUNSHOT WOUNDS—THEIR DANGER—IN THE LIVING AND DEAD BODY—WAS THE PIECE FIRED NEAR OR FROM A DISTANCE?—EVIDENCE FROM SEVERAL WOUNDS—THE PROJECTILE NOT DISCOVERED—DEFLECTION OF BALLS—ACCIDENTAL, SUICIDAL, AND HOMICIDAL WOUNDS—POSITION OF THE WOUNDED PERSON WHEN SHOT—WOUNDS FROM SMALL-SHOT—WOUNDS FROM WADDING AND GUNPOWDER—IDENTITY FROM THE FLASH OF POWDER—EXAMINATION OF THE WEAPON.

GUNSHOT wounds are of the contused kind, but they differ from other wounds in the fact that the vitality of the part struck by the projectile is destroyed, and this leads ultimately to a process of sloughing. The legal definition of a wound applies here as in other cases, so that in order to constitute a *gunshot* wound in a legal sense, the cutis or true skin, must

be injured. In *Reg.* v. *Mortlock* (Cambridge Lent Ass. 1843), the surgeon deposed that there was a circular wound on the skin, by which it had been deprived of its cuticle, but the true skin was not penetrated. The bullet had struck obliquely at a considerable angle; had it been otherwise, it must have entered the abdomen. The judge said that, as the true skin was not penetrated, there was no wounding within the meaning of the statute.

Their danger.—The medico-legal questions which arise out of gunshot wounds, are similar to those which have been examined in relation to other wounds. They are *dangerous to life*, especially when they penetrate or traverse any of the great cavities of the body. Death may take place directly, either from loss of blood or from shock; although immediate or copious bleeding is not a common character of these injuries, except when some large vessel is injured. Death from shock is occasionally witnessed. In the case of *Daly*, who was killed by a pistol bullet, it was found, on inspection, that the bullet had traversed the distended stomach at the greater end from behind forwards. The two apertures were about the size of a shilling, and the edges black. There was but little blood effused, and the other viscera were uninjured. The deceased died in a few seconds after receiving the wound, apparently from shock. ('Lancet,' May, 1842.) Indirectly, these wounds are attended with much danger; sloughing generally takes place uniformly throughout the whole of the parts perforated, and inflammation or fatal bleeding may cut short life. If the person survives the first effects, he may die at almost any period from suppurative fever, erysipelas, gangrene, or from the results of operations absolutely required for his treatment. Gunshot wounds may thus destroy life after long periods of time. A man was shot in the right loin. He died from the effects of the wound three years and ten months after the injury. ('Guy's Hosp. Rep.' 1859, p. 173.) Marshal Maison died in Paris in 1840, as it is reported, from the effects of a gunshot wound received forty years before. Instances of gunshot wounds proving fatal after a year and a day are not unfrequent, and they show the inconsistency of limiting the legal responsibility of an assailant by the period at which death takes place. (See p. 595.) In gunshot wounds of a severe kind, the first symptoms by no means indicate the degree of mischief. In the case of *Mr. Drummond*, who was shot by *M'Naughten*, in 1843, the symptoms were in the first instance so slight, that the bullet was supposed not to have penetrated the cavity of the abdomen, but to have coursed round the skin. Death took place in a few days, and it was then found that the bullet had completely traversed the abdomen, perforating the diaphragm. Army-surgeons have also remarked that slight wounds of the coverings of the abdomen, are often insidiously attended with deep-seated injury. (See cases, 'Med. Gaz.' vol. 24, p. 850.) It is not easy to mistake a gunshot wound for any other injury. If the circumstances under which it is produced do not satisfactorily account for its origin, a simple examination will generally suffice to show its true nature. Sometimes the projectile, or part of the dress, is found lodged in the wound. A perforating wound of the skull, inflicted with a red-hot poker, produced in the bones a small sharply-defined circular opening nearly half an inch in diameter. It bore a close resemblance to a bullet wound. The absence of a bullet showed that it had not been produced by any projectile. ('Med. Gaz.' vol. 44, p. 767.)

In the living and dead body.—A medical witness may be asked whether the wound was inflicted *before or after death*. It is by no means easy to answer this question, unless the bullet has injured some vessel, when the effusion of blood, and the formation of coagula, will indicate that the person

was living when it was received. If a gunshot wound has been produced in a dead body, no blood will be effused, unless the bullet strikes a large blood-vessel.

Was the piece fired near or from a distance?—A gunshot wound produced by the muzzle of a piece being placed near to the surface of the body, has the following characters:—There may be two apertures, the one of *entrance* and the other of *exit;* but it sometimes happens that the bullet lodges and does not pass out. The edges of the aperture of entrance are generally torn and lacerated, and appear blackened, as if they had been burnt; this arises from the flame of the gunpowder at the moment of explosion. The skin is often ecchymosed, and is much discoloured by the powder; the clothes covering the body are blackened by the discharge, and sometimes ignited by the flame. If the muzzle of the piece was not in immediate contact with the part struck, the wound is rounded; but if there has been direct contact, the skin, besides being burnt, is torn and much lacerated. The bleeding is usually slight, and when it occurs it is more commonly observed from the orifice of exit than from that of entrance. The aperture of entrance is round only when the bullet strikes point-blank, or nearly so. If it should strike obliquely, the orifice will have more or less of an oval or valvular form; and by an observation of this kind we may sometimes determine the relative position of the assailant with respect to a wounded person. Supposing the bullet to have been fired from a moderate distance, but so near as to have sufficient momentum to traverse the body, then the appearance of the wound will be different. The *orifice of entrance* will be well defined, and round or oval, according to circumstances; the skin slightly depressed; the edges presenting a faintly bruised appearance; but the surrounding parts are neither blackened nor burnt, and they do not present any marks of bleeding. In these cases the *orifice of exit* is large, irregular, the edges somewhat everted, and the skin lacerated, but free from any appearances of blackness or burning: it is generally three or four times as large as the entrance-aperture. This is not universally admitted. ('Ann. d'Hyg.' 1840, 1, 458.) The orifice of entrance is generally large and irregular when the bullet strikes near the extremity of its range. Under common circumstances, the entrance-aperture may have the appearance of being smaller than the projectile, owing to the elasticity of the skin. ('Ann. d'Hyg.' 1839, 2, 319.) It is the same with the aperture in the dress, when this is formed of an elastic material. According to Dupuytren, the hole in the dress is always smaller than that made by a bullet in the skin. These points should be remembered in fitting projectiles to wounds which they are supposed to have produced.

Useful evidence may be sometimes obtained by a careful examination of the projectile, which, if found, should be preserved. When the projectile cannot be found, and there are no marks of burning, or other signs of a near wound on the skin, we must be cautious in expressing an opinion. In the case of *The King* v. *Howe and Wood* (Stafford Lent Ass. 1813), it was proved that the deceased had died from a gunshot wound in the back. The bullet extracted from the wound was found to have been discharged from a pistol with a screw-barrel. A weapon of this kind was found on the prisoner, as well as a bullet which had evidently been cast in the same mould as that taken from the body of the deceased. (Wills's 'Circ. Evidence,' 264.) On these occasions, the medical attendant should either keep possession of any of the projectiles which he may remove from a wound, or deliver them only into the hands of responsible persons. An examination of the *dress* alone will sometimes enable us to give an opinion as to where the bullet had passed in, and to form a judgment of the direction in which

the shot was fired. If a ball strikes at a moderate distance, the aperture in the dress where it enters is round, and the margin is regularly defined; but the aperture by which it passes out is irregularly torn. In one case the ball traversed the left arm: it had taken out a circular piece of the coat, shirt, and undershirt, where it had entered; but it produced a large irregular opening where it had passed out. Sometimes portions of the dress are carried into the wound; or, if the ball is nearly spent, the dress is elongated like a pouch into the wound. By putting the edges of the cloth together where the bullet has passed in, it may be seen whether any of the cloth has been carried before it. The holes are generally ragged, but the nearer the wounded person is to the assailant, the more perfect is the hole in the dress—provided the piece be not discharged in immediate contact. The bruised and dark appearance which a gunshot wound sometimes presents, even when the piece is discharged at a distance from the body, has led to the supposition that this effect was due to a burn, and that the bullet burnt the parts which it touched; but this idea is exploded. The projectile never becomes sufficiently heated to acquire the least power of burning.

The question whether a piece was fired *near to, or at a distance from*, the wounded person, may be of some importance, either on a charge of homicide or of alleged suicide. Two persons may quarrel, one having a loaded weapon in his hand, which he may allege to have been accidentally discharged, and to have killed the deceased. A tithe-collector was tried for the murder of a man by shooting him. It appeared in evidence that the prisoner, while on duty, was attacked by the deceased and two of his sons, and he drew a pistol to intimidate them. He was dragged off his horse by these persons, and during the scuffle, it is supposed, the pistol was discharged accidentally and inflicted a wound on the deceased, of which he died shortly afterwards. The sons of the deceased swore that the prisoner took a deliberate aim, and fired the pistol at their father when at some distance; and a priest deposed that such was the dying declaration of the deceased. From some doubt of the truth of this story, the body, which had been carelessly inspected in the first instance, was disinterred. It was again examined by a surgeon, who was enabled to swear positively that the pistol must have been fired close to the body of the deceased, and not at a distance, since there were the marks of powder and burning on the wrist. Hence it followed that the pistol had not been discharged at a distance, but during the scuffle, either by accident or in self-defence. The prisoner was acquitted, and the parties who had appeared as witnesses against him were convicted of perjury.

In the case of *Pearce*, who was tried (C. C. C. 1840) for shooting at his wife, it appeared from the medical evidence that the pistol had been fired so near to the person of the prosecutrix, that her dress was burnt and the skin blistered. A man was placed as sentry in a position where he was occasionally fired at by the enemy. The man was one day found severely wounded; the calf of his leg was greatly torn, the whole charge of a musket having passed through it. He attributed the wound to a shot from the enemy: but from the skin of the leg having been completely blackened by charcoal, it was clear that it must have arisen from the discharge of his own musket. He had inflicted this wound upon himself in order to obtain a discharge from the regiment. Both the dress and skin of a person who has received a gun or pistol-shot wound should be closely examined. The result may be, that the statement given of the mode in which a wound was received will be entirely disproved. The case of *Peytel* furnishes an illustration. This man was travelling in a carriage, in company with his wife, and attended by a man-servant. The

wife and the man-servant were found dead on the road, and the account given by Peytel was, that the servant had discharged a pistol into the carriage and shot his wife, and he had afterwards pursued and killed him. The facts, however, were so suspicious against Peytel, that he was charged with the double murder. From an examination of the body of the wife, it appeared that there were two pistol-wounds in the face, which had most probably been produced by two separate pistols. The prisoner alleged that about nine o'clock at night, when it was dark, he desired the servant to get down and walk in order to relieve the horses. Two minutes afterwards, some man, whom he found to be the servant, approached the carriage-door, discharged a pistol at him, and wounded his wife; but the evidence showed that two weapons must have been used, or at least two different discharges made by a person sitting very near to the deceased, so that the muzzles must have almost touched her face—the eye-lashes and skin having been much burnt by the powder. These facts, together with other strong circumstances against him, led to the prisoner's conviction. Ollivier considered that the deceased might have been shot by the servant, and that the two wounds might have been produced by one pistol loaded with two bullets; also, that the marks of burning about the face of the deceased might be attributed to the wadding, and, therefore, they afforded no proof that the muzzle of the pistol had, at the time of its discharge, been close to her person. He further contended that the deceased had not died from the wounds. Notwithstanding these suggestions the prisoner was convicted. ('Ann. d'Hyg.' 1839, 2, 339; 1842, 1, 368.) The amount or degree to which the clothes and body of a person may be burnt by the near discharge of fire-arms has given rise to a medico-legal inquiry. A fact of this kind can only be determined by the circumstances of each case. ('Ann. d'Hyg.' 1860, 1, 125.)

It has been said that when a bullet is fired near, it commonly traverses the body; and therefore it has been rather hastily assumed that, when there is only one external wound, and the bullet has lodged in the body, this is a proof that the piece has been fired from a distance. This inference is, however, erroneous. A bullet may be fired close to a person and yet not traverse the body. Many cases might be cited to show that, in the near wounds produced by suicides and murderers, the bullets have not always traversed the body. In suicide, when the piece is discharged into the mouth, the projectile often lodges in some part of the head.

Evidence from several wounds.—When several wounds are found on a body, can we determine whether they were produced by one or several different discharges? This question was raised in *Peytel's* case (*supra*), as there were two wounds on the deceased, and the prisoner alleged that the servant had fired but one pistol. Ollivier thought that this might be explained by supposing that there had been two bullets in the pistol:—it was, however, affirmed by some military officers and other witnesses, that these wounds had been produced by separate pistols—a fact which overthrew the defence of the prisoner. ('Ann. d'Hyg.' 1843, 1, 368.) One ball may sometimes produce several wounds on the body; and then there will be only one orifice of entrance, but, owing to the ball occasionally splitting within the body, and dividing itself into three or four pieces, there may be several orifices of exit. This splitting of a ball has repeatedly occurred when the projectile in its course has encountered an angular surface, or a projecting ridge of bone. Dupuytren met with an instance, in which a ball, after having struck the ridge of the bone of the leg (tibia), divided into two parts, which traversed the calf of that leg, and penetrated into the calf of the opposite leg. Thus no fewer than five wounds were produced in one instance by a single ball—three of entrance and two of

exit. A similar effect was observed in a case in which the bullet struck the parietal bone of the head and divided into two portions:—one passed out superficially through the skin, the other penetrated into the brain, and lodged on the tentorium. This fact shows that the discovery of an exit-aperture does not always prove that the whole of a projectile has passed out—a matter which may influence a medical opinion as to the result.

In the case of *Mr. Drummond*, who was shot by *M'Naughten*, the pistol was discharged close to the back of the deceased. The ball, however, had not traversed the body, but had lodged beneath the skin in the forepart of the abdomen. In the case of *Latham*, shot by *Buranelli*, although the pistol was discharged close to the deceased, the bullet lodged in the second vertebra of the neck, where it was found after death. It is then out of the power of a witness to say from the mere fact of a bullet lodging or traversing, whether the assassin was far off or near at the time the deceased was wounded. The latter point may be sometimes readily determined by the marks of injury and burning about the skin and dress. When a gun or pistol is discharged at the distance of three or four yards from the person, it will not, of course, produce those marks of blackening, burning, and bruising on the skin which are found when the muzzle is within a few inches of the body. Such a wound may remove a suspicion of suicide, and create a strong presumption of homicide. Lachèse found that in firing a gun at the distance of four feet, the skin was only partially blackened. It would be very important in a case of this kind to notice the direction of the wound as well as the relative position of the assailant and assailed, as stated by witnesses or deduced from circumstances. In this respect the facts connected with the death of *Charles XII. of Sweden* are of some interest. On the night of Dec. 11th, 1718, the king, who was besieging the fortress of Frederickshall, during an examination of the works, clambered up a mound facing the enemy's batteries and within reach of their fire. There were with him, but at different distances from him, several noblemen. Suddenly the king gave a deep sigh, and fell dead on the parapet, with his face towards the fortress. A ball had struck him on the right temple, traversed the brain from right to left, and forced the left eye from its socket. The direction of the wound tended clearly to prove that the king was not struck by a ball from the battery which he was facing, but that this had come from his right hand. Suspicion fell upon a M. Siquier, who was at that time in attendance on the king: whether this was well founded or not, it is generally supposed the king was assassinated.

The projectile not discovered.—It is not absolutely necessary for the conviction of a person on a criminal charge of maliciously shooting at another, that the bullets or shot should be produced, or that they should even have been found on a post-mortem examination of the body. In the case of *Reg. v. Cottrell*, tried in 1839, the deceased was seen to drop, and his face was covered with blood. On persons going up to him he was found dead. The medical evidence established that there was a gunshot wound in the left eye, leading to the brain, and that this had caused death. The shot could not be found. The prisoner's counsel objected, on this ground, that there was no proof of a gunshot wound having been inflicted; but the judge held that the circumstances were sufficient to warrant the jury in inferring that the deceased had been struck by some substance from the gun, which had caused his death; and it was not necessary to prove whether this had been done by leaden shot or pellets. If, however, it should happen that no wound was produced by the discharge, there would be a want of evidence as to whether the piece was loaded or not. This subject gave rise to much discussion in the case of *Reg. v. Oxford*, in 1840. By this case it seems to

have been decided that the proof of a piece being loaded with ball or shot is not necessary, provided the prisoner were so near to the party when he fired it, that mischief might be done by the wadding or gunpowder only. This becomes occasionally a medical question.

Was the piece loaded with ball?—At one of the trials which took place for an attempt on the life of the Queen, it was asked whether it were possible to determine if a recently discharged gun or pistol had been loaded with ball or not. It is impossible to give an answer to this question, merely by an examination of the weapon. The report is said to be louder, and sharper in the case of a piece loaded with ball, than when it is charged with gunpowder and wadding only. If a piece were fired in a direction so that the projectile met with any hard or resisting object, the fact of a bullet having been used would be proved, if not by the discovery of a flattened projectile, by the trace of a deep leaden mark in the situation of the part struck.

Deflection of balls.—When a ball traverses the body, it sometimes happens that the two apertures are opposite to each other, although the ball may not have taken a rectilinear course between them, but have been variously deflected by the subjacent soft parts. This deflection of a ball from a rectilinear course is met with in those cases in which it strikes obliquely a curved surface, and it is found that when the ball enters and does not pass out, its course is often circuitous, so that it is not always easy to say in what part of the body it will be found. In 1830, the author saw a boy who had received a gunshot wound in the upper part of the abdomen: the entrance-orifice was plainly situated there, but there was an opening at the back, nearly diametrically opposite, out of which the ball had passed, so that it conveyed the impression that the ball had completely traversed the abdominal cavity. There was, however, no sign of collapse or depression, nor any indication of serious injury; and Dupuytren gave an opinion, which was afterwards verified, that the ball had not penetrated, but had been deflected beneath the skin, and had taken a circuitous course through the cellular tissue to the back. Many similar facts are recorded. The same deflection may occur even when the piece is discharged close to the body, as in cases of suicide. Abernethy was called to examine a man, who had shot himself, as it was supposed, through the head. He found two openings in the scalp, nearly opposite to each other. It was soon perceived that the ball had not penetrated the bone, but had followed the curve of the exterior of the skull to its point of exit. The deflection of projectiles may occur not merely when they come in contact with bone, but when they meet skin, muscles, tendons, or membranes; the ball then takes its course in the spaces between these different structures. A ball which entered at the ankle has been known to make its exit at the knee; and another, which entered at the back of the left shoulder, passed down on the inside of the scapula, and was found below the right ear. This deflection of a ball by slight obstacles has been ascribed, partly to the obliquity with which it strikes, and partly to the rotary motion on its axis, which every spherical projectile is considered to have. It does not appear to be much connected with the degree of velocity, for the same deviation has been found to occur when the bullet was fired near or at a distance.

If we can at any time discover two fixed points where a ball has touched a building without being deflected, it will be easy to determine the *direction* from which the piece was discharged. An illustration of this is given by Watson. The case occurred at Ayr, in 1831. Several shots had been maliciously fired into a church. Some of the bullets traversed a window, making holes in the glass, and struck against a wall on the other side of

the church—a fact plainly indicated by the marks which they left. A straight line carried from these two points reached a window on the opposite side of the street, from which it was afterwards ascertained the bullets had been fired. In a case tried at the Kingston Lent Assizes, 1862, a similar piece of evidence clearly showed that a gun loaded with a bullet had been maliciously discharged with a design to kill one of two persons. The prosecutrix and her mother were sitting by candle-light one evening near a window in their house, so that their shadows were projected on the blind: a bullet passed through the window and struck the wall of the house inside. A line drawn between these points was about half an inch over the head of the prosecutrix, and about one inch below the level of her mother's head. Neither was hurt. The prisoner was connected with the act by his having been seen near the spot, and by a variety of circumstances. It was alleged in defence that the prisoner had gone out with his gun in the evening to shoot birds with bullets, and that the piece had been discharged by some accident. The judge directed the jury to consider with what intent a shot could have been fired so as to come within half an inch of the head of a person. The prisoner was convicted.

Survival after Gunshot wounds.—A witness may be asked,—When was the gunshot wound inflicted, and how long did the wounded person *survive* after receiving it? Like other wounds, a gunshot wound undergoes no change for eight or ten hours after its infliction. Our judgment in reference to these questions may be assisted by observing the parts which are involved, although we cannot always infer from the quantity of blood found near to a body, that the bleeding was an immediate consequence of the wound, or that the whole of the blood was effused at once. We cannot, then, always affirm that the deceased could not have moved or exerted himself in some degree after receiving it. The exertion thus made subsequently to his being wounded may have actually caused the fatal bleeding.

Suicidal and Homicidal Gunshot wounds.—When it is doubtful whether the wound was the result of suicide or homicide, the point may be sometimes determined by paying attention to its situation and direction. *Suicidal* gunshot wounds are almost always directed to a vital part—to the heart or to the brain: they possess those characters which belong to wounds inflicted near to the body. The skin is discoloured or burnt, the wound wide and lacerated, the hand which discharged the weapon often blackened, and sometimes still grasping the pistol. The ball may or may not have traversed, as this will depend on the momentum which it derived from the charge, and the resistance which it experienced. (See *Reg.* v. *Thomas*, Brecon Lent Ass. 1845.) The situation in this instance negatived the supposition of suicide. Suicidal gunshot wounds are seldom situated at the back of the body; therefore the determination of the point of entrance, if the ball has traversed, is of some importance. The direction of these wounds is probably of less moment than their situation, because the projectile is liable to be deflected in the body. In a duel, one of the parties, a tall man, was killed by a ball which was found to have entered below the right shoulder, and to have taken a direction downwards. In consequence of this, it was thought that he had been shot unfairly by his antagonist, who was short in stature. Breschet and others explained the suspicious course of the wound by assuming that the ball had struck the under part of the clavicle, and had thence probably been deflected downwards. This question excited considerable interest at the trial of a *Dr. Smith* for the murder of a *William Macdonald* (High Court of Just. Edin. Ap. 1854). It appeared that the deceased was found dead in a field belonging to the prisoner, on the morning of Nov. 20th. The body, according to the testimony of eye-witnesses, was lying at full length on its left side in

a ditch. The left arm was partly beneath, and the right partly across the body. There was a blackened wound or hole in, and a little blood on, the cheek. A pistol was lying on the ground, according to one witness, about four feet from the head of the deceased. The time at which the deceased died was fixed with tolerable precision at twenty-five minutes before eight o'clock on the evening of Nov. 19th; and although the prisoner was not seen near the spot, there was evidence that he had made an appointment to meet the deceased that evening, and the testimony of many witnesses showed that he had had an opportunity of being on the spot at the time when the discharge of a pistol was heard. The defence was, that this was an act of suicide. The pistol could not be identified as belonging to the prisoner; and one witness for the defence positively swore that, six years before, he had sold to the deceased a pistol resembling that found near his body. Upon this statement, and upon the failure of the medical evidence to throw any light upon the important question of homicide or suicide, the prisoner was discharged on a verdict of Not Proven. ('Med. Times and Gaz.' Ap. 22 and May 20, 1854.)

It was proved by the two medical witnesses who gave evidence at this trial, that deceased had died from a pistol-shot, the bullet having penetrated the brain. From the characters of the wound, one witness thought that the muzzle of the pistol, when discharged, must have been within from three to twelve inches of the face. He admitted that, as an act of suicide, the body might have assumed the position in which it was found, but that the probabilities were against it. The other witnesses thought that the pistol, when discharged, might have been twelve or thirteen inches from the face; and although a person standing could, in his opinion, have made the wound that appeared on the cheek, yet a suicide would probably have made more sure of his aim, by selecting another position. The only information regarding the wound was, that it was in the right cheek, below the malar prominence; that the opening was blackened, and the nose scorched with gunpowder. It appears that the medical witnesses did not see the body until after the lapse of *two days*. It had in fact been removed from the spot, washed, dressed in grave-clothes, and put into a coffin, before they saw it. ('Med. Times and Gaz.' May 20, 1854, p. 525.) Thus the marks of gunpowder on one of the hands, generally found in suicide by pistols, were not seen here; and the removal of the body from the spot placed the medical men in a difficulty, since they could base their opinion only on the statement of ignorant witnesses. There were marks of blood on the ground; but these, it was suggested, might have been accidentally caused during the removal of the body. The situation of the wound, *i.e.* below the malar prominence in the cheek, is rather unusual for an act of suicide, but it was such as a murderer walking by the side of the deceased could have easily selected. The distance at which the pistol was held appears to have been greater than we usually find in cases of suicide; for had it been close, as it usually is in suicide, there would have been marks of extensive burning and laceration of the soft parts about the wound. The position of the pistol with respect to the dead body, as described by the witnesses who found it, is inconsistent with the supposition that deceased had thus fallen accidentally after having himself discharged the pistol. There was no motive for suicide, and no reason why, had suicide been contemplated, the deceased should have selected the prisoner's field for perpetrating the act. The deceased had been seen transacting business within half an hour of the time at which he must have died; and it was stated by his friends that they had never seen him with a gun or pistol in his possession, and had never known him to use fire-arms. Every fact tended to prove that this was an act of homicide and not of suicide: further, there was no mark of

struggling or scuffling, and no robbery had been perpetrated. The accused had the motive, means, and opportunity of committing the crime, but there were no circumstances which could directly connect him with it. The early interference with the body, and the neglect to call for a medical investigation, probably led to the obliteration of parts of the evidence which would have clearly satisfied the jury that this could not have been an act of suicide.

Accidental gunshot wounds bear the characters of near wounds: they may touch vital parts, but, if the body has not been disturbed, the presence or absence of design in the infliction of a wound is commonly made apparent by the relative position of the body and the weapon. They frequently arise from persons drawing the charges of guns or pistols with the muzzles pointed towards them, and they are then situated in front: at other times they are produced by persons pulling towards them through a hedge, or dragging after them, a loaded gun. In the latter case the wound is behind, and it may strongly resemble a homicidal wound, although the circumstances under which the body is found generally suffice to explain the matter. ('Ann. d'Hyg.' 1860, 1, 443.) In the following case of attempted suicide, the characters of the wound somewhat resembled those which are commonly imputed to homicide. In 1844, a man was brought to Guy's Hospital, with a large ragged gunshot wound on the right side of the head, behind the angle of the jaw, and between it and the ear. No slugs or bullet could be found; the direction was from behind forwards and from above downwards. According to this man's statement, the pistol missed fire three times, but he succeeded in discharging it into his mouth at the fourth attempt. He lost a large quantity of blood, but after some time he walked to a table at the distance of five yards, reloaded the pistol, and discharged it at the back of his head in the situation described. Thus, then, there were in this case two wounds, one of them being apparently homicidal in its characters; and there was a power of locomotion after the first wound, in spite of great loss of blood. A gunshot wound in the mouth or temple would seldom be set down to accident, and yet attempts are occasionally made to ascribe to such wounds an accidental origin. The admission of a near wound in the temple occurring from accident, must depend entirely upon the circumstances proved. (See *Reg.* v. *Tottenham*, Norwich Lent Ass. 1845.)

In suicide there is commonly strong evidence of design; in accident all evidence of design is wanting. Suicides sometimes make use of unusual weapons, or use weapons in an extraordinary manner. In a case that was brought into St. Thomas' Hospital, a young man employed, for the purpose of shooting himself, the case of an Italian iron, in which he had filed a touch-hole. He used a marble for a bullet, and discharged the piece into his mouth. Guns are rarely used by suicides, and when they are employed, the marks of design are commonly evident: thus the gun is perhaps found to have been discharged by a piece of string attached to the trigger and connected with the deceased's foot. In one instance a man loaded a gun, and placed the stock and breech in a grate. He then deliberately lighted a fire in the grate, and sat opposite to the muzzle. When suicides destroy themselves by guns, the wounds are never situated behind. A wound in the back from a gun, indicates either accident or homicide. Important medical questions sometimes arise out of a case of this kind, for the circumstances under which a dead body so wounded is found, may entirely forbid the supposition of accident. In one case (*Rex* v. *Adams*, Berkshire Ass. 1836), in which the prisoner was charged with the murder of his father, the gunshot wound which had caused death was situated at the back of the head. No weapon was found

near; hence there could be no doubt that this was an act of murder. The prisoner was acquitted, since, although he was seen running from the spot at or about the time of the murder, another gun was heard to be discharged from the same spot about an hour afterwards; and it was impossible, from a medical examination of the wound, to say at what particular time it had been caused. A somewhat similar case occurred subsequently (*Reg.* v. *Richards*, Warwick Lent Ass. 1843). The deceased was found dead, lying on his back, with his gun placed on the front of his body, reaching from his thigh to some inches above his head. On inspection, it was ascertained that death had been caused by a gunshot wound at the back of the right ear. Two surgeons gave it as their opinion, that, from the position of the wound, the body, and the weapon, death could not have occurred from design or accident on the part of the deceased, but might have taken place from the accident of another. The prisoner was acquitted, as there was insufficient proof to connect him with the act.

There is one circumstance to be noticed in reference to suicide by fire-arms. If a man has really discharged the piece at himself, whether it be a gun or a pistol, the injury should present the characters of a near wound —indicated by blackening and lividity of the skin, with a bruising and laceration or burning of the soft parts. A case was tried (*Reg.* v. *Wilson*, Shrewsbury Aut. Ass. 1870) in which a medical student was charged with shooting at his father, a medical man, with intent to murder him. The prosecutor was lying asleep on a sofa in the evening, when he was suddenly awakened by a report of fire-arms, and the sensation of an acute burning pain in the eye. This was followed by another report. He was unable to see for the moment, but fancied he heard the sound of foot-steps between the two reports. A bullet was subsequently extracted from the eye and another from the head. He fell off the sofa, and in raising himself up found a revolver on the floor at a short distance in advance of him. This was proved to be his own revolver. The prisoner had shortly before this gone downstairs in the direction of the room where his father was lying asleep. The prisoner called to his sister, saying that his father had shot himself. The medical evidence clearly showed that this was not such a wound as would have been produced by an attempt at suicide. It had none of the characters of a near wound. The prisoner had had some disputes with his father, but there did not appear to be a sufficient motive for such an act, although he had the means and opportunity. He was acquitted of the charge. It was suggested that some person might have entered the house and fired twice at the prosecutor while he was asleep, although there was no motive for shooting a sleeping man. The statement made by the son, that his father had shot himself, was proved to be untrue by the nature of the wounds.

Evidence from the position of the body and the weapon.—Due allowance must be made for the unusual conditions under which the bodies of persons who have committed suicide by fire-arms may be found, or erroneous suspicions of murderous interference may be formed. In 1868, a man was found dead on the floor of his bedroom, his body stretched out at full length, and both arms lying straight close to the sides of the body. A pistol-case was at a short distance from his right hand, and the left was gently closed on a piece of burnt paper without any blood on it, and the insides of the fingers were blackened. The pistol was lying near the *left* hand. On the right temple there was a deep wound, completely traversing the head, and having the characters of an entrance wound. Portions of brain and blood had been carried to the left side, covering some of the furniture beyond the body. On this side, too, a conical bullet was found within the fender, resembling those in the pistol-case. This was, it is

believed, an act of suicide. The discharge of the pistol was heard in an adjoining room by a servant, who stated that she heard the man speak immediately after the discharge of the pistol. The position of the pistol and the laid-out attitude of the body, the arms and hands close to the sides, might have fairly given rise to a suspicion of murder. The fingers of the left hand were blackened, but it is impossible to conceive that such a wound could have been inflicted on the right temple with the left hand, and then the question arose, how came the burnt paper (wadding) in this hand? If the pistol was discharged with the right hand, then how did it happen that the pistol was lying near to the left hand on the left side of the body, while the right arm was stretched at full length on the right side of the body. It is probable that the man shot himself with his right hand while sitting on the floor; that the pistol dropped on his left side, and that he fell flat on his back, retaining sufficient power to place his arms by the sides of his body. The burnt paper and the blackening of the fingers remain to be explained. The left hand must have been held near the pistol when it was discharged.

In these cases, as in cases of actual murder, there are many mysteries which can only be unravelled by the person committing the crime. Such a case as the above might have easily given rise to a charge of murder.

The case of *Risk Allah*, will furnish an additional illustration. A young man named *Readly*, to whom the accused was related by marriage, and by whose death he would inherit some property, was found dead in his bed at an hotel in Antwerp, in 1865. Readly was subject to epileptic fits; and he had recently had a disappointment in reference to marriage. Risk Allah had insured the deceased's life for 1000*l*., but that was in order to cover a loan which he had made to him. The facts, as they transpired from an official inquiry at Antwerp, were these:—One morning the deceased had an epileptic fit, and his companion, Risk Allah, a medical man, having attended to him, left him to sleep—he himself sleeping in a corridor at some distance from the deceased's bedroom. At 7 o'clock on that morning the chambermaid had gone into the deceased's room and had seen him asleep. At 7.30 Risk Allah was seen to come downstairs and to go out of the house, to which he did not return until just before 9 o'clock, when the landlord said that as they had neither seen nor heard anything of Readly since his fit, Risk Allah had better go and see how he was. The bedroom door was found fastened on the inside, and there was a strong smell of gunpowder-smoke issuing from the keyhole. He immediately called for assistance. The door was broken open, and it was found, on entering, that furniture had been placed against it, and the room was full of smoke. A table and chair were found overturned. The deceased was lying on the bed, shot through the head. The body was naked, the night-dress which he had worn being in another part of the room, without any stains of blood upon it. Blood was still flowing from the wound, and one of the hands was warm. The right arm was across his stomach, and his left arm was lying by the side of his body. The left hand was almost out of the bed. A recently discharged gun and a ramrod were on the floor by the side of the bed, and there was a chair close by, which had been overturned. Some shots were also found. On a table in the room was a piece of paper on which was written, in the handwriting of the deceased, the words 'I have done it,' the ink being still *wet*. A trial took place, and the question was raised, whether this was an act of murder or suicide? Risk Allah was discharged, and the act was pronounced to be one of suicide. Three years afterwards the whole case was gone into again in this country, on the occasion of an action for libel, in which the writer substantially charged Risk Allah with the murder of his companion (*Risk Allah* v. *Whitchurch*, Q. B. June, 1868), and a verdict with

heavy damages was returned for the plaintiff. Apart from the fact that the accused was not proved to have been on the spot when the deceased received his death-wound—that the doors of the room were fastened on the inside—that the body when found was warm, and that coagulated blood was still oozing from the wound—that the ink on the paper with the words 'I have done it' was still wet, and proved to be in the handwriting of the deceased, there was another circumstance pointed out on the trial for libel. The body was found naked on the bed, the night-dress being in another part of the room, not stained with blood. This seemed only consistent with suicide. The deceased slept in a night-dress, and was seen with one on that night. If shot by the hand of another, it cannot be supposed that the murderer would have taken off the night-dress and stripped the deceased naked before firing the gun. Had it been possible to do this without causing a struggle and raising an alarm, there could be no conceivable motive for such an act. On the other hand, the deceased might have removed it to prevent its catching fire; but whether this was or was not the motive, the deceased himself must have taken it off and placed it where it was subsequently found.

The position and attitude of the dead body were considered by some medical men to be inconsistent with suicide. One said that after a severe gunshot wound like this, involving the brain, it would be impossible for a person to place his arms by the sides of the body or to put his hands under the bedclothes. Another contended that a man could not possibly shoot himself with a gun while lying down in bed; but both of these propositions are contrary to fact. In a case of probable suicide related at p. 693, the arms were found straight down on each side of the body, the wound in that case traversing the brain and causing almost instantaneous death. In reference to the second point there have been instances of soldiers destroying themselves by firing the gun while lying down, by means of the ramrod, which appears to have been used for this purpose by Readly; and in order to satisfy the jury, one of the military experts for the defence, at the Antwerp trial, lay down on a bed in court and fired a gun by means of a ramrod. It was also proved that the wound in the body had the usual appearances of a near wound which would be the result of a gun so fired. In short, there was nothing in the *medical* circumstances of this case which justified the charge of murder.

In relying upon the relative position to the deceased of a discharged gun or pistol, an expert, unless he has had a large experience in such subjects, may be easily deceived, and draw a false conclusion. In 1869, a gentleman was out shooting with a double-barrelled gun. He had just put on the percussion-cap, and was holding the gun loosely in his hands, when the right barrel went off. From the recoil, with nothing behind the butt, the gun flew back a yard or two behind him, and the cap of the left barrel came so sharply in contact with the hard ground, that it also exploded, sending the charge into the outside of the sportman's thigh. The shot passed through the right-hand pocket of his shooting-jacket, striking his shot-bag, and driving the brass-top into the muscles behind the hip-joint. The metal head of the shot-bag deflected the charge, so that it passed round outside the thigh and lodged in the muscles. This deflection probably saved his life, as no great vessel was wounded. Assuming that the man had been found dead under these circumstances, it might have been said that suicide and accident were impossible, that no man could have shot himself with a gun from behind in the manner described, and that the position of the gun, one or two yards behind the body, could only be explained on the supposition that some one had shot the deceased from behind.

A case of some interest in reference to the attitude of the body and position of the weapon, in death from a pistol-shot wound, is reported in the 'Ann. d'Hyg.' 1868, 2, 445. Toulmouche has also contributed several cases illustrating the effects produced by bullets and small-shot under different conditions. ('Ann. d'Hyg.' 1867, 1, 403.)

Position of the wounded person when shot.—Did the deceased receive the shot while standing, falling, or lying down? Was the piece, when discharged, pointed from the shoulder?—These questions can only be answered by reference to the particular circumstances of each case. In general, when a person is shot while standing, and the piece is pointed from the shoulder, the wound is more or less transverse; but due allowance must be made for the deflection of balls after penetration. (*Reg.* v. *Magarity*, C. C. C. July, 1841.) Was the deceased shot while running away, or when approaching the person who fired?—This question is answered by observing, in the case of a traversing wound, in which alone any difficulty can arise, whether the entrance-orifice be situated in front or behind.

An officer was charged with having caused the death of a man, by shooting him. The deceased was in company with a strong party of smugglers, whom the prisoner and his men were pursuing. During their retreat, the companions of the deceased fired on their pursuers, and there seemed great reason to believe that he was accidentally killed by one of the shots so fired, as he was at that time between the pursuers and pursued. If, however, this had been the case, it was clear that he must have received the gunshot wound in front, as he himself was in the act of retreating. On the other hand, it was uncertain, from the general evidence, whether he had not been shot by the prisoner; because, although it did not appear that shots had been fired by him or any of his party, yet it was proved that in running he tripped and fell, and his gun went off at the same instant, so that it was not impossible the deceased might have received the mortal wound in this manner. The whole case, therefore, rested on the evidence of two surgeons, one for the prosecution, and the other for the defence. The surgeon who appeared for the prosecution deposed that he found the body of the deceased traversed by a gunshot wound, which had caused death from the laceration of an artery, and the consequent hæmorrhage. One of the orifices of the wound was situated in the lower part of the buttock, and the other in the upper part of the groin, so that the latter was higher up than the former. In his judgment the ball had passed through the bones of the pelvis, from behind. According to the opinion of this witness, therefore, the prisoner must have caused the death of the deceased. For the defence, a surgeon in the navy—who, it appeared, had had considerable experience relative to gunshot wounds—was called. He stated that he examined the body of the deceased in the presence of the first witness, but he was of opinion that the ball had entered in front, and passed out behind the body. The reasons which he assigned for this opinion were, that the wound in front was much smaller than that situated behind, and its edges were smooth and depressed, or turned inwards; while the opening behind was twice or three times the size of that before, and was ragged and uneven—the fragments of bone lying about the opening, and being partly lodged in the muscles of the buttock. These facts proved to him, most unequivocally, that the ball had entered in front, having, with diminished impetus, torn itself out posteriorly. If the ball had entered from behind, he should have expected that the fragments of bone would have been carried upwards and inwards into the pelvis, and would not have been lodged about the buttock. The value of this witness's evidence was most

materially affected by the cross-examination which he underwent. He then stated that he did not make an inspection of the body until after it had been already inspected, and sewn up. He did not see the state of the bone itself, and his examination of it was but slight. He admitted that the openings of the wound afforded better evidence than the state of the bone, as also that the bone would certainly be shattered where the ball had entered. They had both agreed, in the first instance, that the ball had entered in front. It is most probable that the ball had entered in front, and that the deceased was shot by his own party. The direction of the wound—its passing from above downwards, and from before backwards—throws a shade of doubt upon the correctness of this view, since, for the shot to have been fired in front, the individual who fired it must have been much elevated above the deceased (a circumstance which did not appear from the evidence), or a ball could not have taken such a course; while, on the other hand, its direction was precisely such as it would have taken if it had been discharged from the prisoner's gun, since it was established by the evidence that the accused had fallen while pursuing, and his gun had become then accidentally discharged. (Smith's 'For. Med.' p. 290.)

In 1882, whilst the preceding pages were passing through the press, the celebrated *trial of the brothers Peltzer* took place, for the murder in Brussels of *M. Bernays*. At this trial several important questions relative to hæmorrhage from gunshot wounds, the position of the assailant, and the production of cadaveric lividities, were raised, which may here be noticed, since they could not be referred to in their proper places. M. Bernays was a well-known barrister in Antwerp, and was on very intimate terms with Armand, the elder of the two brothers Peltzer, and was also known to the younger brother, Léon. Either on account of a *liaison* between Armand and Madame Bernays, or because M. Bernays was in the possession of a secret affecting the character of Armand, the latter resolved to get rid of Bernays, and employed for this purpose his brother Léon. Bernays was accordingly inveigled into a room in a house in Brussels, specially prepared for the purpose; and as he crossed the threshold it is supposed that the disguised Léon presented a pistol near the nape of the neck, and shot his victim dead. The body was no doubt subsequently disposed of by the brothers in the following manner. All traces of blood were removed from the room except in one spot, where there was a pool of blood weighing about nine ounces; and the body was placed in an arm-chair so that it might be supposed that death was the result of either suicide or accident. About a week later information was conveyed to the authorities, by letter, that Bernays had been shot accidentally by one Vaughan—an assumed name of Léon—during an altercation; and this letter led to the discovery of the deceased's body. A judicial and medical examination of the body was made on the 18th, eleven days after the death on January 7th, 1881. Stienon, who made the medical examination, said there were two wounds, one on the right temple, of a simple nature, the other in the nape of the neck, which had been the cause of death. This was a perfectly clean wound, without any burn. The ball had gone through the neck from left to right, slightly ascending and perforating the skull. The principal part of the projectile was found in the right temporal (middle) lobe of the brain. On the body were stains of blood and cadaveric lividities. The blood stains were in the nape of the neck, and on the right side of the head. On the nostrils and moustache were streaks of blood. There were lividities on the right leg and forearm. No blood was found in the pharynx. The wound in the nape of the neck could not have bled much externally. The bleeding had been *internal, and through the nose*. There was little blood on the

clothes of the deceased. A spot on the carpet contained nine ounces of blood. There was a footprint, as he alleged, in this spot, not produced by the deceased. Experiments made for the purpose showed that the footprints could not have been produced earlier than two hours and a half after the blood had flowed on to the carpet, and probably it was twenty or twenty-five hours afterwards. It was certain that the footprint was not produced on January 18th, the day of the first investigation at the house, and eleven days after the death. Experiments showed that cadaveric lividities could no longer be displaced when the body had remained in the same position for twenty-eight or thirty hours: therefore the body could not have become cold in the same position as that in which it was found. It might have been moved after twenty-eight or thirty hours, but the cadaveric rigidity must be taken into consideration. The body must have been rigid after twenty-four hours. Destruction of this rigidity was possible only by tearing the muscles, and no muscles were torn: therefore it was probable that the moving of the body had been effected after cadaveric rigidity had disappeared, which usually happened after sixty or seventy hours. It followed that the body must have been moved some days after the crime. The blood-clot on the carpet was irregular in shape, there being no blood in the centre; and the footprint was at the side. Death had doubtless been instantaneous; and experiments showed that the shot had been fired at a distance of four inches from the wound, though there was no blackening. The clothes of the deceased were in perfect order, and there was no evidence of a struggle having taken place. Léon had indicated a spot where the shot was fired; but it was impossible that his victim could have been on that spot, as in that case the blood would have flowed all over his clothes, which was not the case. Bernays had evidently fallen against the corner of a writing table, as was indicated by the wound on the temple, and had then rolled on to the floor. Probably the deceased was shot whilst stooping his head, as many people do instinctively on entering a room. Inside on the door were some drops of blood, spurted on it when the wound was inflicted. The victim had bled through the nose for five or ten minutes after death. If the assassin had raised the head of Bernays, the blood would have flowed on to the clothes, which were free from blood. The footprint on the blood-clot on the carpet had probably been made by a boot of Armand's, with which the mark corresponded. The body had not been moved sooner than from forty to sixty hours after death. This was the summary of Stienon's evidence; and he was confirmed by Vleminckx. For the defence, Guillery stated that what had been described as a footprint on the blood on the carpet, had been produced by a knee, not a boot; and the impress might have been made ten or fifteen minutes after the blood had flowed. Hence it might have been produced, as Léon stated, when he knelt to raise the head of the deceased, and to render him assistance. Cadaveric lividities, he asserted, permitted no conclusions to be drawn, as twelve days after death they were accompanied by putrefaction. The blood, he contended, had flowed from the nape, not from the nose. Schönfield confirmed this evidence. The brothers Peltzer were both convicted. ('Br. Med. Jour.' 1883, I., p. 23).

Wounds from small-shot.—Death is sometimes occasioned by small-shot, and here several medico-legal questions present themselves. Small-shot may act in two ways:—1. It either strikes without spreading, in which case the discharge is always near the person, and its action is much more dangerous than that of a single ball, because it produces extensive lacerations; or 2. It strikes after it has spread, and here the discharge must have been distant, and comparatively little mischief is done. Lachèse found, by many experiments on dead bodies, that in order to produce with

small-shot a round opening, somewhat resembling that produced by a bullet, the discharge should take place point-blank at the distance of not more than ten or twelve inches from the surface of the body. When the distance was from twelve to eighteen inches, the opening made was irregular, and the borders were much lacerated; at thirty-six inches, a central opening was entirely lost, and the surface of the body was covered by the scattered shot. The effect after this was found to depend on the distance, the goodness of the gun, and the strength of the charge ('Ann. d'Hyg.' 1836); but the shot is, in general, much scattered over the surface of the body. A witness may be required to form an opinion of the distance at which a gun was fired. In *Reg.* v. *Chapman* (Oxford Lent Ass. 1839), it was proved that the deceased had been killed by small-shot fired from a gun; that the discharge must have taken place very near, as the shot had not been scattered, and the point of the gun must have been below the level of the wound, as the direction was rather upwards. Two medical witnesses were examined, and both agreed that, judging from the direction of the wound, the gun when fired could not have been pointed from the shoulder. A similar question was raised in *Reg.* v. *Hull* (Oxford Sum. Ass. 1846), and it was decided that the discharge of the gun took place accidentally during a struggle. In the case of *Reg.* v. *Kendrew* (York Wint. Ass. 1844), the medical evidence was very satisfactory. It was shown to be highly improbable that deceased could have shot himself with small-shot from a gun, as the shot were scattered, and there was no round opening or mark of burning. It is difficult to conceive that small-shot could produce a single entrance-wound, having an appearance of circularity about it, without at the same time singeing or burning the skin or dress.

The difficulty of laying down any general rules respecting the wounds produced by small-shot at their entrance and exit, will be apparent from the following facts:—A boy was shot in the neck by the accidental discharge of his gun, loaded with an ounce of No. 8 shot. He died instantly. He was leaning forwards on the muzzle, so that it was nearly in contact with the skin of the neck. A large round hole was produced, one inch and a half in diameter, the edges of which were slightly blackened with powder. The exit-aperture, which was at the back of the neck, a little to the left of the third cervical vertebra, was a mere slit in the skin, scarcely an inch long, with the long diameter placed vertically. The smallness of this aperture may have been owing to the greater part of the charge being lodged in the body. The entrance-aperture, although rounded, was too large to be mistaken for a bullet-wound: it was evidently a near wound, from the blackening of the edges. On the other hand, it has been found that a round aperture may be produced by the discharge of small-shot at a much greater distance from the object than that assigned by Lachèse. A new gun was fired with the usual charge at a sheet of paper placed at sixty paces' distance. A circular hole was produced in the centre of the sheet, through which apparently every shot had passed. The hole was slightly jagged at the edge, but otherwise resembled that made by a bullet. New guns with highly polished surfaces throw the shot very closely together, and this is the explanation of the difference in the results thus obtained and those described by Lachèse. Admitting such exceptional instances, and assuming the general correctness of the inferences drawn by Lachèse, from the results of his experiments in discharging small-shot at dead bodies placed at different distances, it does not seem probable that a wound from small-shot could, under any circumstances, be mistaken for one produced by a leaden *bullet*. This question arose in a case tried by Parke, B. (*Reg.* v. *Spriggs*, Lewes Lent Ass. 1854), in which the prisoner was charged, upon his own statement, with having caused the death of his

wife by discharging at her a loaded gun. When seen shortly after by the medical witness, the deceased was quite dead. There was a 'jagged' wound upon her forehead, about an inch above the right eyebrow. The witness described it as a wound which, from its appearance, might have been produced by any blunt instrument, or by a gun fired from a short distance. On further examination it was found that the back part of the head been driven in, and it appeared as though the shot had passed completely through the head and brain, passing out behind in a direction slanting downwards, the wound behind being three inches lower than that in front. He did not see any shot, nor did he open the head to endeavour to find any; but a portion of the skull and hair had been driven into the wound. The judge properly suggested that the brain should have been examined, as some shot might have remained there, and this would have shown exactly how the mortal injury had been produced. The witness was strongly pressed to say whether he was certain the injury had been caused by shot and not by a bullet. He said he was certain it was by shot, as he had had much experience of bullet-wounds. Fortunately, there was good evidence to show that one barrel only of the prisoner's gun had been discharged, and the undischarged barrel was found loaded with shot. The prisoner was convicted. There appears to have been no mark of burning or singeing of the hair or dress in this case, or the witness would not have suggested that the wound might have been occasioned by a blunt instrument. Considering that there were two penetrating wounds on opposite sides of the head, this was a singular part of the evidence. It was clear that there was one great central wound (the entrance-wound), which, although described as 'jagged,' appeared difficult to be accounted for, as no shot were scattered, or could be found in the skin. Yet this single wound was obviously caused by small-shot. In all similar cases, it would be proper to examine the track of a wound throughout. According to Lachèse's experiments, it is probable that the piece was in this case discharged within twelve to eighteen inches from the surface of the skin.

A discharge of small-shot, in contact with the skin or close to it, generally produces, not a round opening, but a severe lacerated wound. A man lay down on the grass and fell asleep, the muzzle of his gun being close to the back of the calf of his left leg, and pointing in a slanting direction downwards. By some accident the gun went off, and the shot produced a laceration of the whole of the fleshy part of the leg, with no appearance of a round perforation. As might be expected from the closeness of the discharge, the leg of his trousers was much burnt as well as cut and torn. Although, according to Lachèse's experiments, a round opening may be produced by small-shot when the piece is fired at the distance of a foot from the body, the above case proves that the shot may be scattered, and an extensively lacerated wound caused, when the muzzle is close to the skin, and the piece is not discharged point-blank. The scattering of the shot, however, in such a case, could not lead to the inference that the discharge had taken place from a distance, because the skin and dress would always present distinct marks of burning. When a piece is fired near, the shot may be carried into the wound without scattering, and it may be found lying like a solid mass in the wound. This was proved to have been the case in *Reg.* v. *Evans* (Swansea Lent Ass. 1869). In 1869, a gentleman was accidentally shot by the discharge of his gun from behind. The entire shot were found lodged, as in a purse, in the muscles behind the thigh-bone.

The course taken by small-shot, when discharged at short distances, may indicate the direction in which the discharge took place, and thus aid in the identification of the assailant. In *Reg.* v. *Marris* (Lincoln Lent Ass.

1870), it was a question whether the wound indicated the direction in which the gun was fired. The deceased was shot while passing along a public path. If the prisoner were guilty, he must have fired the gun from a window more than twelve feet above the ground. According to the evidence, the shot must have been fired downwards. It had blown away the upper lip, the teeth, and lower jaw. The prisoner was convicted.

Small-shot is rarely observed to traverse the body entirely, unless discharged so near as to make a clean round opening; but a single pellet reaching the body may destroy life. There may be no exit-aperture, or it may be smaller than that of entrance. Two cases have already been mentioned: one (p. 664) in which a young man was killed by a single pellet wounding the sixth intercostal artery; the other (p. 652), in which a girl was killed by a pellet traversing the orbital plate and wounding the brain. Such minute wounds might be easily overlooked in the examination of a dead body. Small-shot, even when wounding only the skin of the back superficially, has been known to cause death by tetanus. In the post-mortem examination of the body of a person who has been killed by a discharge of small-shot, the pellets do not always present a rounded appearance. By the force of the discharge, especially when near to the body, or when any bony surface has been struck, the spherical form of the shot may be almost entirely lost. In *Reg.* v. *Evans* (Swansea Lent Ass. 1869), it was attempted to connect the prisoner with an act of murder by the appearance of the shot removed from the dead body. Some slips of lead, with small cut portions of the metal of a rough cubic form, were found in prisoner's possession. A portion of the shot removed from the body of deceased, who was found dead, had a similar cubical form. They consisted only of lead, but it was impossible to say that the lead was the same as that found in the possession of the prisoner. The evidence failed to connect the prisoner with the act. Cut lead, in the form of slugs, may be mixed with shot, and it appeared to be so in this case. In all manufactured shot there is arsenic. If this is found, it would tend to show that ordinary shot had been used.

When in an act of suicide a pistol is discharged close to the chest, the amount of injury done cannot be measured by the size of the bullet. In a case of suicide in which a man discharged a pistol pressed closely to his chest, loaded with a bullet three-eighths of an inch in diameter, the whole of the clothes were torn through, and portions of them, with parts of the ribs, were carried deeply into the chest. The opening in the chest was circular, and three inches in diameter. The margin was burnt and ragged. The heart was intact, but the left lung was completely shattered The small bullet was found firmly impacted in the fourth dorsal vertebra, on the left side. The explosion of the gunpowder close to the body sufficiently accounted for this large wound.

A single bullet of no great dimensions, fired from a gun at a distance of from four to six yards from the person, has been known to produce an extensive wound. In the case of *Mr. Walshe*, who was shot by a man named Wells, in 1868, the bullet had traversed the head, destroying the nose entirely. The entrance-aperture at this point was so large as to admit three or four fingers. The bullet had passed out behind, splitting the occipital bone, and it was found in the room with a stain of blood upon it, and some hair resembling that of the deceased. In this case the bullet, of the Minié pattern, weighed only 250 grains, but it produced a very large wound.

Wounds from wadding and gunpowder.—A gun loaded with wadding, or even with gunpowder only, may cause death. In these cases, an impulsive force is given by the explosion, and the substance becomes a dangerous projectile. The lighter the projectile, the shorter the distance

to which it is carried; but when discharged near to the body, it may produce a fatal penetrating wound. A portion of the dress may be carried into the wound, and lead to death from bleeding; or if the wounded person recover from the first effects, he may subsequently sink under an attack of tetanus or erysipelas. Fatal accidents frequently occur from persons discharging guns or pistols at others in sport—an act which they think they may perform without danger, because the pieces are not loaded with ball or shot. In *Reg.* v. *Race* (Bury Lent. Ass. March, 1840), it was proved that the prisoner had killed the deceased by discharging at him, within a few feet, a gun loaded with powder and paper-wadding. The deceased fell and died in a few minutes. It was found that the chest was penetrated, and that the wadding had wounded the left auricle of the heart. ('Ann d'Hyg.' 1859, 1, 421.) In 1838, a girl was killed by a boy, who discharged at her a gun loaded with paper pellets. Some of these penetrated the body, and lodged in the lungs and liver. Dupuytren mentions an instance, where, during a quarrel between two men, one discharged at the other a gun loaded with powder and wadding only, at a distance of about eighteen inches. The man instantly fell dead. On inspection, his clothes were found torn, the intestines were lacerated, blood was effused, and the wadding was lodged in the abdomen.

In 1881, a man sitting in the gallery of a theatre at Brighton, had the upper half of the hand completely blown away by a piece of greased newspaper, tightly rammed, discharged from a small cannon on the stage of the theatre.

It has been observed that persons in attempting to commit suicide have occasionally forgotten to put a bullet into the pistol; nevertheless, the discharge of a piece into the mouth has sufficed, from the effect of the wadding only, to produce considerable destruction of parts, and to cause serious loss of blood. Fatal accidents have frequently taken place from the discharge of wadding from cannon during reviews. It is not easy to say at what distance a weapon charged with wadding and gunpowder would cease to produce mischief, since this must depend on the impulsive force given by the charge of powder, and on the size of the piece. Lachèse found that a piece charged with gunpowder only, is capable of producing a penetrating wound somewhat resembling that caused by small-shot, when the piece is large, strongly charged, and fired within six inches of the surface of the body. ('Ann. d'Hyg.' 1836, p. 368.) This arises from a portion of the powder always escaping combustion at the time of discharge, and each grain then acts like a pellet of small-shot. Under any circumstances, a discharge of powder contuses the skin, producing ecchymosis, and often lacerating it, if the piece is fired near. The dress is burnt and the skin scorched from the flame formed by the combustion of the powder; many particles of gunpowder may be actually driven into the true skin. All the substances here spoken of are considered to be projectiles; and the weapons are held in law to be loaded arms, so long as they are capable of producing bodily injury at the distance from which the piece containing them is discharged. It may therefore become a question as to the distance at which these light projectiles cease to be harmless. The answer must be governed by circumstances; but it will in all cases materially depend on the strength of the charge. In *Reg.* v. *Collier* (Abingdon Lent Ass. 1844) the prisoner was charged with firing a gun loaded with small-shot at the prosecutor, with intent to do grievous bodily harm. It appeared that the gun was deliberately pointed at the prosecutor, who was then at a distance of from seventy to eighty yards from the prisoner. The shot, which was very small, had marked the clothes, but had not penetrated the skin or inflicted any wound. The defence was, that, from the slight injury done,

the prisoner merely intended to frighten the prosecutor, and not to do him any bodily harm. He was found guilty of a common assault. The question was here a delicate one, for had the prosecutor been a few yards nearer, and the pellets touched an exposed part of his body, the result might have been serious. One pellet has destroyed life (pp. 652, 664). A case occurred, in the United States, involving the question as to the distance at which a pistol *not* loaded with ball would suffice to produce a serious wound. A boy, in play, discharged a pistol at a companion, producing on the fleshy part of the left hip a wound one inch in diameter and four inches in depth. The skin was destroyed, and the muscles were a blackened lacerated mass. There was no ball in the pistol; but it is not certain whether there was wadding. Death took place from tetanus on the seventh day; and on examination no wadding was found in the wound. There were, however, grains of gunpowder, with which the wound was blackened throughout its whole extent. At the inquest the witnesses differed respecting the distance at which the pistol was held when the wound was inflicted. Some said one foot; others two or three yards. The deceased had stated his belief that the pistol had almost touched him, and, judging by the state of the wounded parts, this was probably the truth. Swift contended that the wound had been produced by gunpowder only, without wadding. He performed some experiments with the pistol used by the prisoner, but loaded with gunpowder and *wadding*, in order to determine the effect of the discharges at different distances. At twelve inches distance from a body, he found that the clothes were lacerated and the skin abraded, but the wadding did not penetrate; at six inches, the clothes were lacerated, and the wadding penetrated to the depth of half an inch; at two inches, the wound produced, which was two inches deep, was ragged and blackened; at one and a half inch from the chest, the wadding passed into the cavity between the ribs, and in a second experiment it carried away a portion of a rib. ('Med. Gaz.' vol. 40, p. 734.) This subject was investigated by Mackintosh, and he found, in reference to the wounds produced by wadding, that the amount of injury done is in proportion to the amount of powder in the gun, the hardness and compactness of the wadding or substance used in place of shot or bullet, and the distance of the object from the point of firing. A case occurred in his practice which was the subject of a trial for unlawful wounding: *Reg.* v. *Isgute* (Norwich Lent Ass. 1867.) The prisoner fired at a boy with a gun loaded with brown paper, pressed together. He was then at a distance of two or three yards from the boy. There was a wound in the chest about the size of a shilling. The margin of the wound was jagged, had a blueish-black or mottled appearance, and the edges of one of the ribs was laid bare. The paper pellet took a course downwards, as a result of a deflection of the projectile by the rib. A quantity of brown paper was removed from the wound, and the boy ultimately recovered. The question which Mackintosh proposed to consider was whether paper-wadding could really produce such a wound as was here found, when the gun was fired from a distance of *two or three yards*. Without going into details, it may be stated, that when the gun was charged with a small quantity of powder and brown-paper wadding, there was indentation, but no penetration at a distance of two yards. With one-third more powder and a brown-paper pellet closely compressed, there was penetration through the boy's jacket to an inch and a half beyond. These facts bear out the conclusion already given, and confirmed the boy's account of the distance from which the gun was fired at him by the prisoner. Swift had inferred from his experiments that a penetrating wound from wadding was not produced unless the piece was discharged within a distance of six inches; but Mackintosh's results clearly show that this

must depend on the quantity of powder used and the loose or compact nature of the substance employed as a projectile.

Identity from the flash of gunpowder.—Among the singular questions which have arisen out of this subject is the following:—Whether the person who fires a gun or pistol at another during a dark night can be identified by means of the light produced in the discharge? This question was first referred to the class of Physical Sciences in France, in 1809, and they answered it in the negative. A case tending to show that their decision was erroneous was subsequently reported by Fodéré. A woman positively swore that she saw the face of a person, who fired at another during the night, surrounded by a kind of glory, and that she was thereby enabled to identify the prisoner. This statement was confirmed by the deposition of the wounded person. Desgranges performed many experiments on this subject, and he concluded that on a dark night, and away from every source of light, the person who fired the gun might be identified within a moderate distance. If the flash was very strong, the smoke very dense, and the distance great, the person firing the piece could not be identified. The question was raised in this country, in the case of *Reg.* v. *White* (Croydon Aut. Ass. 1839.) A gentleman was shot at while driving home during a dark night; and he was wounded in the elbow. When he observed the flash of the gun, he saw that the piece was levelled towards him, and the light of the flash enabled him to recognize at once the features of the accused. In cross-examination he said he was quite sure he could see the prisoner, and that he was not mistaken as to his identity. The accused was skilfully defended, and he was acquitted. Evidence of this kind has, however, been received in an English Court of Law. A similar case was tried at the Lewes Lent Assizes, 1862 (*Reg.* v. *Stapley*). The prisoner shot at the prosecutor, a gamekeeper, on a dark evening in December, and the latter swore that he distinctly saw the prisoner by the flash of the gun, and could identify him by the light on his features. His evidence was corroborated by three other witnesses, who saw him not far from the spot, and by one who saw him in the act of running away. He was convicted. A case is quoted by Paris and Fonblanque (*Rex* v. *Haines*), in which some police-officers were shot at by a highwayman during a dark night. One of the officers stated that he could distinctly see, from the flash of the pistol, that the robber rode a dark-brown horse of a remarkable shape in the head and shoulders, and that he had since identified the horse at a stable in London. He also perceived, by the same flash of light, that the person had on a rough brown great-coat. This evidence was considered to be satisfactory.

From the information which the author has been able to collect on this point, there appears to be no doubt that an assailant may be thus occasionally identified.

For a description of the chemical examination of fire-arms, to determine whether they have been recently discharged or not, the reader is referred to p. 544.

CHAPTER 51.

DEATH FROM BURNS AND SCALDS—SYMPTOMS—STUPOR—CAUSE OF DEATH—POST-MORTEM APPEARANCES—BURNS ON THE DEAD BODY—ACCIDENT, HOMICIDE, OR SUICIDE—WOUNDS CAUSED BY FIRE—SCALDING—BURNS BY CORROSIVE LIQUIDS.

Burns and scalds.—A *burn* is an injury produced by the application of a flame or heated substance to the surface of the body; while a *scald* results from the application of a liquid at or near its boiling point, under the same circumstances. There seems to be no real distinction between a burn and a scald as to the effects produced on the body: the injury resulting from boiling mercury or melted lead might receive either appellation. Nevertheless, as a matter of medical evidence, it may be important to state whether the injury found on a body was caused by such a liquid as boiling water, or by a heated solid. If the former, the injury might be ascribed to accident; if the latter, to criminal design. A scald produced by boiling water would be indicated by a sodden state of the skin and flesh, but there would be no destruction of substance. In a burn by a heated solid, the parts may be more or less destroyed, or even charred; the cuticle may be found blackened, dry, almost of a horny consistency, and presenting a shrivelled appearance. This distinction would only apply to scalds from water. A scald from melted lead could not be distinguished from a burn produced by a solid heated to the same temperature. Some of the oils boil at 500° F., and they produce by contact with the skin burns as severe as those caused by melted metals. Burns from flame, such as that of gas, are indicated by extensive scorching of the skin, while burns from gunpowder are known not only by the scorching, but by the small particles of unburnt carbon which are imbedded in the skin.

Action of melted metals.—A singular case occurred, in which an attempt on life was made by pouring a melted metal into the ear. The mother of an idiot, wishing to get rid of him, adopted the plan of pouring melted pewter into his right ear while he was lying asleep. Great pain and violent inflammation followed, but the man, æt. 25, recovered. The mother then alleged that he had himself poured the melted metal into his own ear. At a judicial investigation, Boys de Loury was required to say whether such an act was likely to occasion death, and, if so, how it happened that the party had in this instance recovered. The alloy was formed of seven parts of tin and three of lead, and the melting point of such an alloy would be about 340° F. De Loury stated that such an act might lead to death, by causing inflammation and disease of the bones of the internal ear extending to the brain. The recovery of the youth was owing to the mischief which followed having been comparatively slight. In performing some experiments on the dead body, he found that it was difficult to fill the ear-passage with such an alloy, in consequence of the sudden expansion of the air caused by the high temperature. ('Ann. d'Hyg.' 1847, 2, 424.)

Various degrees of burns.—Dupuytren has divided burns into six degrees, which are commonly recognized by medical jurists:—

1. The heat produces a simple inflammation of the skin without vesication. The skin is red, but the redness disappears on pressure: there is slight and superficial swelling, with severe pain, relieved by the contact of cold substances. The inflammation subsides after a few hours, and the skin resumes its natural condition; or it may continue for several days, and the cuticle then peels off.

2. There is severe inflammation of the skin, and the cuticle is raised into blisters containing a yellow-coloured serum. This kind of injury is generally the result of the action of boiling liquids. Some blisters are formed *immediately;* others are produced within twenty-four hours, and those which are already formed become enlarged. Suppuration takes place if the cuticle is removed, and the person survives sufficiently long. As the cutis or true skin is not destroyed by this degree of burn, there is no mark or cicatrix left on healing, to indicate its past existence.

3. The superficial part of the cutis is destroyed. The burn appears in the form of yellow or brown patches, insensible when gently touched, but giving pain when strongly pressed. An inflammatory redness, accompanied by vesication or blistering, is perceived in the healthy portion of skin around the eschars. A white and shining cicatrix without contraction of parts, remains after healing. This degree of injury is commonly observed in burns from gunpowder, and the part which was the seat of the burn is frequently stained black, when the particles of gunpowder have not been removed soon after the accident.

4. The skin is destroyed as far as the subjacent cellular tissue. There are firm and thick eschars (dead portions of skin), which are quite insensible. If the burn has arisen from a boiling liquid, the eschars are soft and of a yellowish colour; if from a red-hot solid, they are firm, hard, and of a brown colour—sometimes black. The skin appears shrivelled and puckered towards the eschar, which is depressed below the surface. The surrounding skin presents a high degree of inflammation, and vesications appear. From the fourth to the sixth day the eschar falls off, leaving an ulcerated surface, which heals slowly and is always indicated by a cicatrix.

5. In the fifth degree, the whole of the layers of the skin, the cellular membrane, and a portion of the muscles beneath, are converted into a general eschar. The appearances are similar to those of the fourth degree, but in a more aggravated form.

6. The burnt part is completely charred. If the person survives, violent inflammation is set up in the subjacent tissues and organs.

Neither a burn nor a scald appears to be considered as a *wound* in law; but in the statute on wounding they are included among bodily injuries dangerous to life. Burns and scalds may be regarded as dangerous in proportion to the extent of surface (of skin) which they cover, as well as the depth to which they extend. The extent of skin involved in a superficial burn, as a result of exposure to flame, is of greater importance than the entire destruction of a small part of the body through an intensely heated solid. When the burn is extensive, death may ensue either from the intensity of the pain produced, or from a sympathetic shock to the nervous system. Death rapidly takes place from burns in children and nervous females; but in adults and old persons there is a better chance of recovery. From a statistical report published in 1875 by the Registrar-General, it appears that in twenty-five years (1848–72) 68,785 persons died in England and Wales from the effects of burns and scalds. Of this number 34,854 were children under five years of age. In 1880, there were 2,061 deaths from burns and scalds.

Symptoms. Stupor from burns.—In some instances, especially in children, stupor and insensibility have supervened; and these symptoms have been followed by coma and death. If, under these circumstances, opium has been given to the patient as a sedative, the stupor resulting from a burn may be attributed to the effects of the drug; and should the person die, the practitioner may find himself involved in a charge of malapraxis. It may be alleged, as in the following case, that the person was poisoned by opium. A medical man was charged with the manslaughter

of a child by giving to it an overdose of opium, while it was labouring under the effects of a severe scald. Abernethy stated in his evidence, which was given in favour of the practitioner, that he thought the exhibition of opium very proper: that the quantity given, eight drops of tincture of opium immediately after the accident, and ten drops two hours afterwards, was not an overdose for a child (the age is not stated). The circumstance of the child continuing to sleep until it died, after the exhibition of the opium, was, in his judgment, no proof that it had been poisoned. This sleep was nothing more than the torpor into which it had been plunged by the accident. The surgeon was acquitted. Notwithstanding the very favourable opinion expressed of this plan of treatment, it would be advisable to avoid the use of opium on these occasions in respect to infants and children. Life is readily destroyed in young subjects by the smallest dose of this drug (see p. 364): and there are no sure means of distinguishing the comatose symptoms produced by a burn or a scald from those produced by an overdose of opium.

Cause of death.—Of the cause of death in persons exposed to fire but little need be said. In large conflagrations persons are frequently simply suffocated, from the want of proper air, or the respiration of the products of combustion—carbonic acid and carbonic oxide. The former darkens the blood; the latter renders it lighter in colour. In other cases, where a large volume of flame suddenly falls upon the body and the person is still able to breathe, the fatal effect may be due to shock; *i.e.* a sudden and violent impression on the nervous system. A person may recover from the first effects of severe burns, but ultimately sink from exhaustion or from an attack of tetanus. ('Med. Times and Gaz.' Ap. 26, 1854, p. 406.) The cause of death from extensive burns of the skin and the appearances presented by the internal organs, have been investigated and described by Mendel, in Horn's 'Vierteljahrsschr.' 1870, 2, 93. See also 'Wiener Med. Blätter,' 1881, p. 1538; 'Vierteljahrsschr. f. Gerichtl. Med.' xxxvii. pp. 65, 237.

As a result of burns from explosions, a person either dies speedily or he recovers. In a case tried at the Swansea Lent Assizes, 1869, it was proved that a man had sustained severe burns from an explosion of fire-damp in a coal mine. He partially recovered from the first effects, but lingered for nearly three months, when he died, according to the medical evidence, from inflammation and ulceration of the bowels. There was no other apparent cause for this inflammation but the burns, and death was referred to the burning as the primary cause. There was no actual recovery from the time of the occurrence until death. In the coal-mining districts, inflammation and ulceration of the bowels is not an unusual result of burns affecting a large surface of skin, when the person lingers for some time after the accident.

The observations made by Wilks confirm these views. He has found that, in reference to burns, death has been in some cases immediately due to bronchitis, pneumonia, or pleuro-pneumonia. If the patient survive but a short time, the fatal result is put down to shock; if, also, he lives for a few days and no marked appearances are found in the viscera, death is attributed to the same cause. He describes a case, in which a boy, æt. 2, was scalded in the face, neck, and chest with hot water, and he died in eight days. The body was carefully examined, and no morbid changes could be found to which to attribute death. ('Guy's Hosp. Rep.' 1860, p. 146.) A girl, æt. 9, died nine days after her clothes had caught fire. Twenty-four hours before death she became very restless, and subsequently all her limbs and body were stiffened as in tetanus. There were no convulsions. There were burns on the upper part of the chest and both arms, with

granulating and suppurating sores. The brain appeared quite healthy, also the spinal cord. All the organs throughout the body were healthy. (Ibid.)

Post-mortem appearances.—In examining the body of a person found burnt, all matters connected with sex and identity should be duly observed. The burning of the Ring Theatre at Vienna, in 1881, gave rise to many important medico-legal investigations respecting the sex and identity of charred remains, of which Hoffmann and Schutze have given a description ('Wiener Med. Blätter,' 1881, p. 1538), to which the reader is referred. (See also Horn's 'Vierteljahrsschr.' Oct. 1864, p. 303.) The presence of a large quantity of calcium phosphate in the ashes would indicate animal remains; but the bones are never completely destroyed. They become white, and portions of them retain their form under the action of a most intense heat. When death has been caused by severe pain, no changes have been detected in the dead body; but, under other circumstances, it has been found on inspection that there were patches of redness on the bronchial mucous membrane, as well as on that of the alimentary canal. The brain has been found gorged, and the ventricles have contained an abundance of serum. The serous liquids of the pericardium and pleura have also been in larger quantity than natural. In short, besides congestion, there is generally abundant serous effusion in one of the three great cavities, especially in the head. (See cases, 'Med. Gaz.' vol. 25, p. 743; vol. 31, p. 551.) In deaths from fires in houses the persons are usually suffocated, and there are the appearances of this kind of death (see SUFFOCATION). In a case in which a woman died on the thirteenth day from a superficial burn involving the skin of the lower part of her body, the stomach was found inflamed at its greater extremity, and the duodenum at its lower portion—the mucous folds of the intestines having a scarlet colour. The other intestines as far as the cæcum were also more or less inflamed. ('Amer. Jour. Med. Sci.' Jan. 1861, p. 137.) If the person survives the first effects, he may die from inflammation, suppuration, gangrene, irritation, or fever, or he may be worn out and die from exhaustion. In this respect, burns of the fourth, fifth, and sixth degrees are especially dangerous to life; and it would be unsafe to give a premature opinion of the probable result, as inflammation of deep-seated viscera only appears after several days. In the case of six children burnt to death, the following observations were made. The eyelids were firmly closed; the limbs were contracted, and the hands clenched. The burns on the bodies of these children were of great superficial extent, but not deep. Nearly three-fourths of the surface of the body had suffered from the effects of fire, and in all, the hands were very much burnt. In one of the bodies least injured by the fire the skin and covering of the chest were injected with bright red blood. The lungs were much congested, and of a bright red colour. The cavities of the heart were empty. The brain was congested with red blood. No blood in the body presented the usual characters of venous blood. Death was attributed to the shock from sudden and extensive burns, and not to suffocation. ('Lancet,' 1863, 1, p. 60.) In a case of death from burning, the lungs were congested, and the cavities of the heart were empty. No particular observation was made as to the colour of the blood. [redacted] was swollen, and there were some other appearances indic[redacted]ngulation; so that the burning had probably been resor[redacted] conceal the mode of death. There was a blister o[redacted]p of the chest, showing that when the body was b[redacted] degree of vitality. The eyes were much suffused. [redacted] account of the appearances presented by the [redacted]m burns in Horn's 'Vierteljahr[redacted] pearances vary

according to the seat and extent of the burns, and the time at which they prove fatal. In protracted cases the organs of the chest and abdomen frequently present marks of inflammation and its consequences. (See also 'Guy's Hosp. Rep.' 1860, p. 146.)

The principal subject on which medical evidence is required on these occasions is in reference to the question whether, in a dead body found burnt, the burning took place during life or after death. As bodies are sometimes burnt in order to conceal other acts of violence, a careful inspection should be made to determine whether there are indications of any other kind of violence. The power to answer these questions must depend on the degree to which the action of the fire has been carried. The remains may be so charred as to render all such inquiries nugatory.

Did the burning take place before or after death? Vesication.—The production of *vesication*, *i.e.* of *blisters containing serum*, is commonly regarded as an essential character of a burn which has been produced during life, but it is not a necessary or invariable effect of a burn on the living body. Vesication is especially observed in scalds, or in those cases in which the skin has been burnt by flame or by the ignition of the clothes, provided the cuticle has not been destroyed. It is not so commonly observed in burns produced by intensely heated solids. In vesication, the cuticle is raised from the true skin beneath, and is converted into one or more blisters containing serum, while the skin around is of a deep red colour. It is uncertain as to the time at which it appears; it may be produced in a *few minutes*, or sometimes not for several hours; hence death may take place before vesication occurs, and the non-discovery of this condition does not warrant the opinion that the burn could not have taken place during life. If the cuticle is removed from a vesicated part of the living body, the skin beneath will become intensely reddened; but if the cuticle is stripped off a dead body, the skin will become hard, dry, and of a horny-yellow colour; it does not acquire the intense scarlet injection which is acquired by the living skin when vesicated and exposed.

There have been conflicting opinions whether the presence of blisters on a dead body should be received as absolute proof of burning during life. The following may be taken as a summary of the ascertained facts. Christison had an opportunity of trying experiments on the effects of dry heat on the same body before and after death, in the case of a young man who had poisoned himself with opium. While he was lying in a hopeless state of coma, four hours before death, a hot iron was held on the outside of the hip-joint; and half an hour after death, a red-hot poker was applied to three places on the inside of the arm. Vesication followed the burns in both instances; but those caused during life contained serum, and those which were formed after death, *air*. In a second experiment, a cauterizing iron produced no blisters on a leg, half an hour after amputation; but vesications containing air were formed when the iron was applied ten minutes after amputation. On the whole, Christison thought that a vesication containing serum indicates a burn during life, and one containing air, a burn after death. The author performed some experiments on the bodies of infants eighteen and twenty hours after death, both with boiling water and heated solids; but in no case did he observe any kind of vesication to follow at that period. The skin was shrivelled, and was partly destroyed by the heat, but there were no blisters produced. (See 'Ann. d'Hyg.' 1843, 1, 383.) Under certain morbid states, blisters containing serum may be produced in the dead body, even twenty-four hours after death. Leuret observed that this took place in a dropsical subject, in the vicinity of which a heated brazier had been placed. The cuticle was hardened, then raised and blistered; and the *blister* contained an abundance of reddish-coloured serum. In

repeating this experiment on other dead bodies not infiltrated, it was observed that no vesications containing serum were produced. ('Ann. d'Hyg.' 1835, 2, 387.) Champouillon has repeated the experiments on bodies affected with general dropsy, and he finds that blisters may be produced in them at almost any period after death. Thus, they occurred when heat was applied to one recently dead, to another when in a state of cadaveric rigidity, and to a third when putrefaction had commenced. The blisters did not appear immediately: the time which he found requisite for their production varied from two to six hours. The serum effused beneath the raised cuticle was rarely tinged with blood. ('Ann. d'Hyg.' 1846, 1, 421.) These experiments confirm the results of Leuret, but add nothing to our knowledge of the subject. The conclusion to be drawn from them is, that in the examination of *burns* on the body of a person affected with general dropsy, it is necessary to be cautious in expressing an opinion. In such cases it would not be possible, from the existence of mere vesication, to say whether the burn took place before or after death.

Wright produced a serous blister in a dead body more than a dozen times—twice within half an hour, and once within fifteen minutes after death; and in amputated limbs he has produced them in from half a minute to four minutes and a half after amputation. The only favourable opportunity which occurred to him for producing a serous blister after death, was in the case of a woman thirty years of age, who died suffocated from acute congestion of the lungs. She was slightly dropsical. *Three hours and a half* after death, when the body was quite warm and the joints flexible, a spirit-lamp flame was applied to the lower and back part of the left leg. After the lapse of an hour, blisters had formed, and were filled with serum of a pale straw-colour: one contained two and the other three drachms of fluid. Ten and fifteen hours after death, when the body had become cold and rigid, the flame produced only *gaseous* blisters. ('Path. Researches on Vital and Post-mort. Burning,' 1850.) The results obtained by Liman in performing similar experiments on five dead bodies, in from one to two hours after death, are not in accordance with those described by Wright. Liman noticed that by a spirit-flame a blister might be raised, but that it contained nothing more than vapour derived from the fluids of the skin beneath the cuticle. It soon became flat and charred, and there were no changes in the surrounding skin indicative of vital reaction. The temperature (of the bodies) varied from 78° F. to 98° F. No experiments were performed on the bodies of persons dying or just dead. (Casper's 'Vierteljahrsschr.' 1863, 24, 367.) It is, therefore, exceedingly doubtful whether, except under special conditions of the body such as general dropsy, blisters containing serum can be produced by a burn on the skin of a person really dead. Christison found that when boiling water was poured upon a dead body *ten minutes* after death, the skin was simply ruffled and shrivelled; but the cuticle was not raised into a blister. The same effects were produced so long as the body retained its warmth. Accident enabled the author to describe the results within a shorter period than that above mentioned. The body of a drowned man, within a few minutes after the accident, was removed from the water and placed in a hot bath. It was found impossible to resuscitate him, but owing to the heat of the water portions of the cuticle came off, when the body was removed. On inspection, there were several blisters *filled with bloody serum* over a considerable portion of the skin, especially of the extremities. There was no dropsy here to account for their production; and the fact of their occurrence appears to bear out the view of Wright, that the production of a *serous* blister on a dead body depends on the amount of *latent* organic life remaining in it. In this case the man was pulseless,

and to all appearances *dead*, when placed in the hot bath; hence the effects of *hot liquids* on the living and the recently dead body, so far as the production of vesication is concerned, are proved by this case to be similar. Chambert has published the results of numerous experiments on the effects of burns on the living and dead body. These were made on the bodies of persons, from the moment of death until twenty hours after dissolution, and some were performed before death. The general results of his researches are,—that blisters may be produced by burns both on the living and dead body; that they are produced at a lower temperature in the living than in the dead; that in the living a burn produces great capillary congestion, with effusion of serum in the blisters, and that this serum, when heated or treated with nitric acid, sets into a nearly solid coagulum. The blisters produced in a dead body, even a few minutes after death, contain a thin watery serum, which is only rendered opaline or milky by heat or the action of nitric acid. ('Ann d'Hyg.' 1859, 1, 342.)

A line of redness.—In burns, especially in those produced by red-hot solids, other effects besides vesication follow. The edge of the skin immediately around the burnt part is commonly of a dead white line, and close to this is a *deep red line*, gradually shaded off into the surrounding skin, which is reddened. The diffused redness is removable by pressure, and disappears with life; the red line here referred to, however, is not removable by pressure, and is persistent after death. This line of redness is not always met with in severe burns, and when a person survives one or two days, its production appears to depend upon a power of reaction in the system. Thus, then, its absence furnishes no proof of the burn having been produced after death, for it is not a necessary accompaniment of a burn during life. Christison endeavoured to determine by experiment whether this line of redness could be produced by applying a heated iron to a dead body. He found that when the person had been dead only *ten minutes*, no such effect was produced. In repeating his experiments on bodies many hours after death, the author found that no line of redness ever presented itself; so that its discovery in a dead body burnt, would appear to indicate either that the burning took place during life, or within a few minutes after death—most probably the former. Champouillon takes exception to the inference derivable from these experiments. He says that he has caused the production of a line of redness by the application of heat to a dead body, and that it is a uniform accompaniment of the formation of blisters in the dead. He admits that it is in this case a mere capillary infiltration of blood, quite superficial, and surrounding the margin of the blister; while in the red line produced during life the tissues of the skin are deeply injected, and this line is evidently the result of vital reaction. (See 'Ann. d'Hyg.' vol. 1, p. 442.) It would appear that he has only remarked this condition in dead dropsical bodies, in which vesications had been produced, and it is obvious from his description that he is referring to a slight congestion of the vessels, occasioned probably by the stagnation of the fluid portion of the blood in the superficial capillaries. It is altogether distinct from the line of redness described by Christison as a frequent consequence of severe burns. In the case of *Mr. Westwood*, in 1839, the fact of certain burns on the body having been produced during life was determined from an observation of this sign. The deceased was found dead, with his skull extensively fractured, his throat cut, and his body burnt in various places. French remarked that the burns were surrounded by a line of redness —that they were probably produced about the same time as the other injuries, but certainly while there was some vital action in the system. When, however, vesication and a line of redness are absent, we have no medical data on which to found an opinion whether the burn was caused

before or after death. Wright considered that in a low state of vitality a line of redness might not be produced by a severe burn on the living body, and that more reliance might be placed on the red marks found beneath the blisters and crusts of vital burns. These latter were well marked when he found the line of redness itself indistinct. (Op. cit. p. 25.) The researches of Chambert confirm this view. In a burn on a living person, if the skin has not been entirely charred and destroyed, the cutis will present a dotted or pointed redness, these dots or points corresponding to the sudiparous (perspiratory) glands and hair-follicles. After complete death, the burn does not produce any such effect; the cutis is of a dead-white on its surface and in its substance. In one experiment performed ten minutes after death, there was no redness of the skin, either beneath the blisters or in the surrounding parts. ('Ann. d'Hyg.' 1859, 1, 368.) This reddened or congested state of the bare skin is more constant than any other appearance, and forms at present the best criterion of the infliction of a burn on the living body. The facts connected with burns on the living and the dead, underwent a minute scrutiny in a remarkable case of alleged matricide at Bridgenorth. (*Reg.* v. *Newton*, Shrewsbury Lent and Sum. Ass. 1849.)

In 1848, two persons were charged with the murder of a new-born child, which had been secretly buried, and was exhumed for inspection ten days after death. Independently of an incised wound on the arm, the edges of which were everted and retracted like a wound produced on the living body, the right leg presented the marks of burning. The cuticle was entirely destroyed over the greater part of the limb: the surface beneath had an intense scarlet colour and was much injected. There was a red line of inflammation around its edge, particularly in the upper portion, and at the lower part of the scrotum there was a large vesicle filled with serum. From this condition of the parts, Prince properly inferred that the child must have been living when these burns were inflicted. The lungs merely indicated that respiration had been imperfectly performed. It turned out subsequently, by the confession of the mother, that the child had been born alive, and that its body had been deliberately burnt by one of the accused parties. The child probably did not survive its birth a quarter of an hour: a proof that the marks indicative of a vital burn do not require a long period for their production.

When *several burns* are found on a dead body, it may be a question whether they were all produced at the same time. This is a point which can be determined only by observing whether any of them present signs of gangrenous separation, of suppuration, granulation, or other changes that take place in a living body after accidents of this kind. The witness may be asked, how long did the deceased survive the burn? A person may die in a few minutes or live some hours after receiving a most extensive burn; and yet there will be no change in the part burnt, to indicate when death actually took place. There may have been no time for inflammation or its consequences to become established. Suppuration generally follows vesication, and in severe cases it may occur on the second or third day; but often not until a later period. In regard to gangrene, this takes place when the vitality of a part burned is destroyed. The time of its occurrence is uncertain, but it sometimes very speedily follows the accident.

After a murder has been perpetrated, it is not uncommon for a criminal to attempt to dispose of the body by burning it. This occurred in the case of Mr. *Paas* (*Rex* v. *Cook*), likewise in the case of *Reg.* v. *Good*, and in another case at Leeds (Jan. 1843), where a mutilated body was found [illegible] in a river with marks of burning about it. In general, the body is [illegible] until all signs of life have disappeared; we shall therefore meet,

in such cases, with nothing but the charring of dead flesh, so that no difficulty can exist in forming an opinion. When the burning is partial, and has probably taken place from a wilful ignition of the clothes, at or about the time of death, some caution is required in expressing an opinion, since marks of vesication and a line of redness are not always present in burns during life. It is by no means unusual, however, to find it stated in evidence that blisters are a constant accompaniment of a burn in the living body. In *Reg.* v. *Taylor* (York Lent Ass. 1842), the deceased was found dead with marks of strangulation on her neck, and her clothes were much burnt from her waist to the knees. She was lying across the hearth; the body was burnt, as well as the upper and lower limbs and the neck. In the opinion of the medical witness, the burn on the neck could not have been produced by fire extending from the other parts of the body. The burns must have occurred after death; and they could not have taken place before, nor at the time of death, because there was no vesication, and he had never seen a burn on a living person which was not followed by blistering. The prisoner was convicted, his counsel having failed to prove or render it probable that death was caused, as alleged, by accidental burning. (See Rep. by Stone of the trial of Dr. Webster for the murder of Dr. Parkman, Boston, 1850.)

Accident, homicide, or suicide.—It is rare that murder is perpetrated by burning: the dead body is either burnt for the purpose of entirely destroying it, or the clothes are fired soon after a person has been killed, in order to conceal wounds or other violent means of death, and to make it appear as if the deceased had been accidentally destroyed by fire. Death by burning is either the result of accident or homicide, most commonly the former, but medical evidence may give rise to a suspicion of murder, under two conditions:—1. When it is evident that several parts of the body have been fired at the same time, and the burns are such as not readily to be explained by the same accident, or by an accidental ignition of the clothes. 2. When there are marks of homicidal violence on the body; but these marks, if we except fractures of the bones, may be easily effaced when the burn is extensive. *Accidental* deaths from this cause are very frequent among women and children. In investigating a suspicious case, we must remember that the fact of a dead body not being found near a fire or any substance capable of causing ignition, does not justify an imputation of murder; since the deceased, unless disabled by intoxication, infirmity, or disease, has the power of running away from the fire after an accident, and may be found dead at a distance, without having been seen by any person. Homicidal burning cannot be established by medical evidence, so much as by that which is presumptive or circumstantial; but there are many medical questions which arise out of the circumstances under which a dead body is found burnt.

A man named *Gilchrist* was tried at Glasgow, for the murder of his wife. On the evening of the alleged murder, the persons who lived on the floor above them stated that they heard a noise like that of two persons struggling, and afterwards a moaning as of one choking or bleeding to death. A smell of fire now became perceptible in the house, which was soon filled with smoke. The witnesses being alarmed, went down to the prisoner's apartment, and demanded admission. After some delay he admitted them, and in doing so appeared to them to have come out of an inner room, where he said he had been sleeping. On admitting them, he stumbled over the body of his wife, which was lying in the outer apartment quite dead, kneeling before a chair, and very much burnt. The prisoner was accused of having murdered her, and then burnt the body in order to conceal the manner of death. In his defence, he alleged that he had gone to

bed tired, and that he knew nothing of what had happened to his wife until awoke by his neighbours. He presumed that her clothes had caught fire while she was intoxicated, and that she was thus accidentally burnt. The medical witnesses who examined the body reported that they found it so much burnt that they could give no opinion of the cause of death. The prisoner was condemned, the general evidence being against him, although the precise manner of his wife's death was not proved even presumptively.

In another case, the general evidence was similar to that adduced in the case of *Gilchrist*, but stronger against the prisoner. On the night of the alleged murder the prisoner was in bed, when his wife returned home with a lighted candle and some whisky, which she had procured from a neighbour. Some time after, a struggling was heard in the apartment, and when this had subsided a smell of fire was perceived to issue from it. The neighbours now endeavoured to obtain admission by knocking at the prisoner's door, but he either could not, or would not, hear them. At last a man forced his way in, by breaking the window of the outer room. On entering, he found the room full of smoke, and something burning in a corner, over which he instantly threw a pitcher of water: this proved to be the body of the deceased. Several persons now entered the inner room, where they found the prisoner either asleep or feigning to be so. On being roused, and told that his wife was dead, he expressed neither surprise nor sorrow; but coolly demanded by what authority his neighbours had broken into his house, and threatened to send for a constable. On an examination of the body, some parts were found completely carbonized by the action of the fire. On the face and extremities, however, the fire had not acted with such violence, and on these parts were found marks of vital reaction, indicating that the burning had taken place during life. Some spots were merely red and inflamed, others scorched to a hard transparent crust, but surrounded by a distinct redness: there were also many vesications filled with serum. From these appearances, the witnesses gave it as their opinion that the deceased had been burnt to death. The jury, in this case, returned a verdict of 'not proven,' considering probably that the deceased might have been accidentally burnt. Duncan remarks, in regard to these two cases, that the action of the fire was extremely violent and destructive, compared with the small quantity of combustible matter consumed; but by what standard this was measured we have no explanation. As the combustible material was reduced to ashes, and the time occupied in the burning was not known, such an opinion could be little more than a conjecture. In both, the burns must have been entirely produced by the ignition of the clothes, since there was no trace of burning of the house or furniture in either. In the second case the deceased was found on the hearth with part of her clothes unburnt, and a chair from which she had fallen quite entire. She was dead when the neighbours entered, and the body was discovered in the dark by the red light issuing from it. An important question was raised on the second trial, in reference to the opinion of the deceased having been burnt to death, namely, whether the redness and blisters, remarked on the edges of the scorched parts, might not have arisen immediately after strangling or some other cause of death than burning,—during the period when a lingering vitality remains in the body, and when undoubtedly certain phenomena of a vital nature are frequently observed. The medical witnesses felt themselves unable to answer the question decisively, but they stated that they did not consider it at all probable that blisters could be produced on the body even immediately after death. ('Med. Gaz.' vol. 8, p. 170. See 'Ann. d'Hyg.' 1835, 2, 370.)

Suicide by burning rarely presents itself for the consideration of a medical jurist. A case of this kind occurred in the gaol of Newgate, in

1871. A prisoner was found in his cell with his clothes and part of the bed-clothes much burnt, and with some severe burns on his body. The gas-light in the cell was so placed that no accident would account for the fire; but all the facts concurred to show that the man had done the act deliberately. He gave no alarm, but a moaning was heard in his cell, and this caused the warder to enter and make the discovery in time to save him.

Amongst the questions which arise in reference to a body found dead from burns is this—Whether the burns have been caused by gas, by inflammable vapours such as petroleum, or by gunpowder. Petroleum is at once indicated by the peculiar and powerful odour, and sooty blackening of the parts. In *Reg.* v. *Gaitskell* (Carlisle Spring Ass. 1872), the prisoner was convicted of manslaughter under the following circumstances. He poured a quantity of petroleum over the clothes of the deceased, and by accident the vapour caught fire, and the burns produced caused the man's death on the following day. Burns from the flame of gunpowder are generally characterized by the blackening of the skin, and the introduction of some of the grains into the substance of the skin. In the Morfa colliery explosion, in 1870, it was of some importance to determine whether gunpowder or fire-damp had caused the deaths of some colliers. There was a little difficulty in the case because explosions from gas in mines generally cause a blackening of the skin from the coal-dust. The large volume of flame both in gas and gunpowder explosions causes extensive and fatal burns.

Wounds caused by fire.—On the discovery of wounds on a body which has been exposed to fire, it is necessary they should be closely examined, in order that a witness may be enabled to say whether they have been caused by cutting or other instruments *before* death by burning, or whether they are not simple mechanical results of the effects of fire on the skin. A boy, two years of age, was brought to the London Hospital, in 1840, so severely burnt on the face, neck, abdomen, and limbs that he survived the accident only three-quarters of an hour. It appeared that the stepmother, who had charge of the child, left him at home locked up in a room where there was a fire, while she went out. Some of the neighbours shortly afterwards hearing screams proceeding from the room, broke open the door, and discovered the child enveloped in flames, and its clothes on fire. The flames were immediately extinguished, and the boy was brought to the hospital. A suspicion of ill-treatment having been excited by the appearance of wounds about the knees, which were observed as soon as the child was admitted, and by the reported neglect and ill-usage of the child by the stepmother, an inspection was made. The body was plump and well-formed. The skin in the burnt parts was deprived of cuticle, and converted into a dry deep yellowish or blackish mass, which was very tense, hard, and easily torn. There were gaping wounds on both knees. On the right side, a fissure in the skin commenced about the middle of the thigh, and proceeded for two inches and three-quarters to the inside of the knee-pan, where it became somewhat jagged, and making a sudden turn inwards, passed to the extent of two inches towards the back of the joint. A transverse laceration of the skin, three-quarters of an inch in length, was observed on the front of the left thigh a little above the left knee; and another, which was also transverse and measured an inch and a half in length, was situated below, on the inner side of the joint. These fissures in the charred skin were all about three lines in width and two in depth, and exposed the fatty tissue beneath, which was white, and free from any effusion of blood. The edges of these fissures were not uneven, but they did not present the clean and smooth appearance usually observed in incised wounds. The vessels on the surface of the brain were full of blood, and the cortical structure appeared dark-coloured. The lungs were congested, but the heart contained

little blood. The mucous membrane of the stomach presented a slightly pinkish hue, but that of the intestinal canal was nearly white. From the absence of any trace of effusion of blood, the sound condition of the exposed adipose tissue, its exemption from the action of the fire, and the irregular character and appearance of the fissures, Curling concluded that they were not the result of wounds inflicted before the occurrence of the burn; he considered them to have been occasioned by the influence of heat, which had forcibly corrugated the skin and completely destroyed its elasticity, and the superficial layer of fatty tissue being closely adherent to it, necessarily gave way at the same time. In several places some small vessels containing blood were observed running across the fissures; these, being more tenacious than the fatty tissue, had not yielded with it. This appearance alone was sufficient to negative the supposition of the infliction of wounds by cutting instruments. The production of the fissures might have been aided by the child's struggles immediately after the occurrence of the burn, but it did not appear that these were at all violent. This conclusion was justified by the facts; and the case is calculated to throw an important light on the accidental origin of fissures or wounds of the skin in cases of death from burns.

The conclusions which we may draw from the foregoing statements, are:—1. That, as a general rule, when we discover marks of vesication, with effusion of serum, or a line of redness, or both, about a burnt part of the body, we are justified in saying that the burn has occurred during life. 2. That when these appearances are not met with, it by no means follows that the burn has not been produced in the living body; the affirmative evidence derived from such appearances being much stronger than the negative.

The subject of *scalding* scarcely requires a separate notice. A scald from boiling water would, when recent, be indicated by vesication and the sodden state of the skin. The living structures are not charred or destroyed as by the application of a red-hot solid. A woman was convicted of throwing boiling water over her husband, with intent to maim him. (*Reg.* v. *King*, Liverpool Sum. Ass. 1847.) In another case (*Reg.* v. *Blewitt*, Worcester Sum. Ass. 1847), the prisoner was convicted of the manslaughter of his wife by pouring over her the contents of a kettle of boiling water. At the Stafford Winter Assizes, 1859 (*Reg.* v. *Hill*), a man was convicted of feloniously casting boiling water over the prosecutor, with intent to do him grievous bodily harm. The medical evidence was to the effect that the scalds were on the head, cheek, neck, and arm, and were of a dangerous character. A woman at Glasgow attempted to kill her husband by pouring boiling water over his genital organs while he was asleep in bed. He died; but his death could not be clearly traced to this cause.

BURNS BY CORROSIVE LIQUIDS.

Among the cases in which medical evidence is sometimes required, are those of throwing mineral acids, alkalies, or other corrosive liquids on the person. This crime was at one time prevalent, and until the passing of 24 & 25 Vict. c. 100, s. 29, there was no adequate punishment for it. On one occasion, an assailant escaped a charge of felony, because it could not be considered, in law, that sulphuric acid was capable of producing a *wound*—the man having been indicted for wounding. One surgeon considered that the injury produced was a wound, another thought that it was not. The judges decided that it was not a wound within the meaning of the Act. (*Rex* v. *Murrow*, Liverpool Aut. Ass. 1835.) The statute above mentioned, while it punishes the offence, omits all reference to a definition of the word wound. The nature of the liquid

thrown is merely defined, in general terms, to be 'any corrosive fluid or any destructive substance'—a point which will require medical evidence for its elucidation.

In common language, and according to the statute, the injury thus produced by a mineral acid such as oil of vitriol, is called a burn; but it is wholly different in its origin, as well as in its progress. Great deformity and actual blindness have resulted from such an injury. A medical man is sometimes required to distinguish these injuries from burns and scalds; this may be easily done, in the first instance, by the appearance of the part injured, as well as by the description of the first symptoms. The eschar or destroyed part is soft, and not dry as in a burn from a heated solid. The skin touched by a concentrated acid is destroyed and sloughs away, to the extent of the part on which the corrosive liquid was applied, leaving a suppurating and granulating surface. There is no capillary congestion or redness of the skin around the injury, as in a burn; but the colour of the injured part may throw some light upon the nature of the corrosive substance used. Thus, while oil of vitriol (sulphuric acid) produces dark-brown stains, aqua-fortis (nitric acid) produces yellow or yellow-brown stains on the skin. Articles of dress are also differently coloured by these acids. The period at which a person may recover from an injury of this kind depends on the degree and extent of the injury, and the part affected by the corrosive liquid. Although a person may not die from the direct effects of the acid, yet the inflammation which follows in deep-seated parts may prove fatal. In infants, or delicate women, an extensive injury thus produced may readily destroy life. In one instance, sulphuric acid thrown on the face produced inflammation of the eye, for which bleeding was prescribed. The person died of phlebitis (inflammation of the vein), as the result of this bleeding (p. 611). In the case of *Miss Cashin*, for whom an escharotic liniment, containing nitric acid, was prescribed by a quack, there was no doubt that death was caused by the great local mischief produced by the application. The nature of the acid may be determined by applying wetted linen to the part when the injury is recent, and examining the liquid thus absorbed. In general, however, evidence is readily obtained by examining the spots or stains left on articles of clothing or furniture. Sulphuric acid is most commonly used: nitric acid has also been thrown at the person, and has led to the destruction of the sight. The caustic alkalies may also be used under these circumstances, as well as numerous other liquids, on which the only medical opinion required would be, whether the article employed should or should not be considered as a corrosive liquid or a destructive substance. To constitute a felony, it is not now necessary that the *person* should have sustained, from the act of throwing, any bodily injury. Unless vital reaction has taken place, there are no means of distinguishing the effects of a corrosive liquid on the living from those produced on the dead body. ('Ann. d'Hyg.' 1869, 1, 396.)

The mineral acids are sometimes used in other ways for the destruction of life. In 1833, a man poured a quantity of strong nitric acid into the ear of his wife while she was lying asleep. She awoke suddenly with a violent pain in the ear, which continued for three days, whereby she became weak and exhausted. Soon afterwards there was copious bleeding, and a portion of membrane escaped. She lost the use of her right arm, and became completely deaf. Suppuration took place from the ear, and blood escaped daily. She gradually sank, and died six weeks after the injury, the right half of the body being convulsed before death. On inspection, a portion of the external ear was wanting, and the ear-passage was much wider than natural. The brain, near the petrous portion of the temporal bone, was softened, and the bone itself diseased (carious). The injury had

led to death indirectly by producing disease of the brain. ('Med. Gaz.' vol. 17, p. 89.)

In a case tried at Aberdeen, a woman poured oil of vitriol down the throat of her husband, while he was lying asleep with his mouth open. She was tried, and convicted of the murder. In another case, a woman killed her husband, by pouring a solution of corrosive-sublimate down his throat while he was sleeping. These, however, were treated as cases of poisoning, as death did not depend on the local or *external* mischief produced by the corrosive agent employed.

CHAPTER 52.

SPONTANEOUS COMBUSTION—ALLEGED OCCURRENCE OF CASES IN HUMAN BEINGS —IN THE DEAD BODY—ACCIDENTS BY FIRE—SPONTANEOUS COMBUSTION OF MINERAL AND ORGANIC SUBSTANCES—CONDITIONS FOR THE SPONTANEOUS COMBUSTION OF COTTON, HAY, AND OTHER SUBSTANCES—INFLUENCE OF OIL AND WATER—SPONTANEOUS COMBUSTION OF FLAX, HEMP, JUTE, AND SILK—CASES REQUIRING SCIENTIFIC EVIDENCE.

It is nearly a century and a half since the hypothesis of the spontaneous combustion of the human body took its origin. It was readily accepted by those who could not in any other way account for the phenomena, and who were incompetent to reason correctly from recorded facts. At that date the facts connected with combustion had not even been discovered. All bodies were supposed to hold within them a principle of fire (*phlogiston*), which might be eliminated from them under certain conditions. When a person was found burnt, and no cause was apparent, the fire was supposed to have had a spontaneous origin, *i.e.* within the body of the deceased.

In old medico-legal works cases are recorded, in which it was supposed the body had been spontaneously consumed by an inward combustion of the organs. In one of the earliest of these cases, that of a man of the name of *Millet*, of Rheims, who was charged with the murder of his wife by fire, the question of spontaneous combustion was raised in the defence, and led to the acquittal of the accused. This case rests upon the authority of Le Cat, and it is stated to have occurred at Rheims in 1725. It appears that the body of the deceased woman, almost entirely consumed, was found lying in the kitchen of the house at a short distance from the hearth. A part of the head only, with a portion of the legs, and a few of the vertebræ, had escaped combustion. The floor beneath the body was partially burnt. The prisoner, in his defence, stated that he and his wife had retired to rest on the previous evening; that his wife, not being able to sleep, got up and went into the kitchen, as he supposed, to warm herself. He was awakened by the smell of fire, and going down into the kitchen discovered the deceased lying near the hearth in the manner described. An intrigue with a female servant was considered to furnish a sufficient motive for the alleged act of murder, and the man was found guilty. On appeal to a higher Court, the sentence of death was revoked, and the prisoner was discharged on the ground that this was a case of spontaneous combustion. (Taylor's 'Elts. of Med. Jurispr.' 1836, 1, 254. See also Liebig's 'Letters on Chemistry,' 1851, p. 281.) As far as the mode of death was concerned, there was nothing in this case to indicate violence by another. The facts are explicable on the supposition that the clothes of the deceased were accidentally ignited. The almost complete destruction of the body appeared

at that date to be inconsistent with the ordinary effects of fire, but subsequent observations have shown that this is an error. Other cases, in which the details are similar, have been recorded. It does not appear, however, that any one on whose judgment reliance can be placed has ever seen a case or recorded the details from actual observation. The hypothesis of such a mode of destruction of the human body is not only unsupported by any credible facts, but is wholly inconsistent with all that science has revealed. In the instances reported which are worthy of any credit, a candle, a fire, or some other ignited body has been at hand, and the accidental kindling of the clothes of the deceased was highly probable. They who adopt this hypothesis appeal to the electrical state of the atmosphere or of the person, coupled with the impregnation of the tissues with the 'inflammable principles' of alcohol, as condition sufficiently explanatory of their views: such explanations may be reserved until the occurrence of this spontaneous combustion from internal causes is placed beyond any reasonable doubt. (For a minute description of the phenomena which are supposed to accompany this condition, see Casper's 'Wochenschrift,' 1841, Nos. 8, 9, 10; Henke's 'Zeitschrift der S. A.' 1842, 2, 228; 1843, 2, 39; 'Ann. d'Hyg.' 1850, 2, 191 and 363; also 1851, 1, 99; 2, 383.) It need hardly be observed that there is nothing in the structure of the human body which is not equally found in the bodies of all warm-blooded animals. No one has ever recorded a case of the death by spontaneous combustion of any domestic animal; and the cases recorded as having occurred in human beings are explicable as ordinary natural phenomena—the combustion of clothing or furniture, or the result of accident.

Some writers, who have rejected the doctrine of spontaneous combustion, have taken up the view that the human body may in certain cases acquire preternaturally combustible properties. Although they admit that fire is always applied from without, they at the same time contend that from the amount of animal matter found burnt, compared with the clothing or furniture which may have become ignited, the flesh, soft organs, and even bones must have been more combustible than usual. Such a theory as this, however, is not required to explain the facts. Dry animal solids readily burn, but the soft parts, either in the living or recently dead body, contain as much as 72 per cent. of water, which renders them highly incombustible. Until a large proportion of this water is evaporated, the substance does not undergo combustion. In many experiments made on different organs and on different bodies the author has not observed that different parts of the same body or the parts of different bodies have varied in their degree of combustibility. The bones alone have withstood a greater degree of heat, from the large proportion of earthy matter contained in them. The experiments have led to this result—the flesh and the organs generally are very difficult of combustion, and can be completely consumed only in a strong fire and under a powerful current of air. Experiments on the bodies of animals have shown that they possess the same property of difficult combustibility. The presence of alcohol in flesh does not render it combustible. The alcohol will burn, but the flesh can only be burned by removing from it the substance which interferes with its combustibility—namely, water. Tissues which have undergone extensive fatty degeneration may, nevertheless, become unusually combustible, so as to become readily inflamed on the application of the moderate heat of a spirit-lamp.

Liebig correctly observes: 'With respect to the fuel assumed to have been present in insufficient quantity, this is a very insecure supposition; for fire, the cause of death by burning, has this peculiarity—that it consumes the fuel or matter which supports it, so that the fuel does not

remain unaltered, like the knife with which a man has been murdered. It is, therefore, obviously impossible, after a case of burning, for any person to define how much fuel has been present before the burning commenced, That which remains is only a part of the fuel which has acted, and it is precisely that part which has disappeared or has been consumed that produces the effect.' (Op. cit. p. 291.)

In some cases of accidental burning in which *all* the facts were known, the body is stated to have been much destroyed, compared with the injury done to surrounding objects. In 1864, a woman given to habits of intoxication was found dead in her room. Her clothes were on fire, and a chair had been burnt. The room when entered was filled with a thick black offensive smoke. On examination it was found that some of the bones were completely deprived of flesh. In the absence of a fire or candle (which was still burning on the table) this might have been set down as a case of spontaneous combustion, or, by reason of the flesh being burnt from the bones, at least as a case of preternatural combustibility, whereas it was nothing more than a casualty by fire.

Ogston, Senr. and Junr. ('Lect. on Med. Jurispr.' pp. 463, 559), relate the two following cases of preternatural combustibility, which came within their own experience. A woman, aged 66, of intemperate habits, was left in her house alone. An hour later her body was found on the third step of the stair near the kitchen; the step on which the corpse rested, and one of the spokes of the wooden hand-rail, being charred, as were the seat of a chair and a small portion of the front of a straw mattress on a bed, both in a kitchen on the same floor and adjoining the staircase. Contrasted with this moderate amount of combustion exterior to the woman's body, was the extent of its effects on herself. On the front of the head and face, the absence of the soft parts left the exposed bones blackened and calcined. On the back of the neck and chest, patches of a greasy charcoal were found here and there; and, beside them, the spinal column and several of the ribs were exposed and burned black. The abdominal wall was wanting, the intestines a burned and blackened mass, and the surface of the liver calcined. The upper limbs were distorted, the elbows strongly flexed, and everywhere charred to a great depth; the bones, however, even of the fingers, preserving their position. The right thigh had its deeper muscles still uncharred, but presenting the appearance of roast beef, and was very dry. The skin and superficial muscles were completely burnt away. The right leg, only partially attached to the thigh, was entirely converted into a greasy black charred mass, even the bones not escaping. The right foot, totally detached from the leg, had been changed into a soft, black, greasy, and shapeless cinder. The left thigh, leg, and foot were in a condition similar to the right. Not a vestige of clothing remained anywhere. In the second case, a woman, aged 60, was left by her husband in bed, apparently in her usual health. Three hours later smoke was noticed issuing from the room, and the woman was found dead close to the fireplace, in which there were then only a few nearly extinguished embers; her night-dress, her only clothing, was on fire. It was supposed that two hours previously, and an hour after her husband had left her, the deceased had got out of bed to light the fire in her room. The whole of the right side of the body was more or less burned, the burns being in all stages, from mere reddening of the skin to its complete destruction, along with that of the flesh underneath it. The flesh of the right arm was charred down to the bones, and the elbow-joint was laid open. The superficial muscles of the right thigh were burned away, and the deeper muscles roasted. The right side of the face and head were charred. The right breast was roasted. There were burns of the first and second degrees on the left arm and hand. The belly was

much swollen. In both these cases the combustion appears to have originated from the ashes in the fireplaces, but, in the opinion of Ogston, they seemed insufficient to account for the extreme destruction of the bodies, without supposing that they were in a state of unusual readiness to support combustion.

It frequently happens that the skin is much injured by fire, while the muscles and soft parts beneath have suffered but little. There are some circumstances which may occasionally explain the different degrees in which parts of a body are found burnt. An assassin may have employed methylated spirit, naphtha, benzoline, turpentine, or some inflammable liquid, of which no trace can be found; and the great destruction of the body may therefore be due to this extraneous cause, and not to any increased combustibility of its parts. A short exposure to a large volume of flame, owing to its high temperature, will speedily char the flesh and consume it. Articles of female dress, from the quantity of air enclosed between the layers, are capable of producing a considerable volume of flame, and thus the bodies of women are sometimes extensively destroyed, as a result of the accidental burning of the clothes (p. 713). Even allowing that parts of the human body might, in certain cases, acquire increased combustible properties, the medical jurist will perceive that this admission does not involve any difficulty in the judicial determination of a question of murder by burning; since it is contended that the combustion of a body cannot possibly take place except by contact with some substance already in a state of combustion. But whether the ignition of the clothes of a deceased person took place accidentally, or by the criminal act of another, is a totally different question: it can be cleared up only by general and circumstantial evidence. Assuming that the body of one person will burn more rapidly and completely than that of another, this will be no answer to a charge of causing death by fire. The intention which a person may have had in setting fire to the clothes of another, when he could not possibly know to what degree the burning would extend, is a question for a jury, to be decided from the circumstances. The relation of this subject of the alleged spontaneous combustion of the body to medical jurisprudence appears to have been much exaggerated.

Such a defence as spontaneous combustion might afford, would, if admitted, prove most convenient to assassins. In the case of *Mrs. Pulley*, whose body was examined in 1860, the circumstances were such as to require but little ingenuity to transform them into a case of spontaneous combustion, although a proper inquiry showed that it was a deliberate murder by strangulation. There was a subsequent burning of the body by means of the clothes, in order to efface the marks of a violent death. The deceased was found lying on the hearth of her room, about three or four feet from the grate. From the shoulders downwards, the body was lying on a boarded floor of oak. The deceased was fully dressed, and parts of her clothing and body had been destroyed by fire. A brass candlestick was lying between the left arm and the body, the top of the candlestick being inclined towards it. The clothes were wholly burnt off both arms, and partly off the upper portion of the trunk. The legs were not at all burnt. A bonnet which the deceased wore was partly burnt. The right arm was elevated by the side, with the elbow resting on the floor. The fingers were partly burnt off, and the remainder of the hand was charred. The left hand, which was stretched out, was not so much burnt as the right. Some ashes from the clothing lay between the left arm and the body, which was not elevated above the floor. The fire was extinguished, but there was a strong smell of burning in the room when it was entered. There had been no fire in the grate. Under the

body there was a hole in the oak floor, which had been produced by burning. The features were distorted and swollen, and the eyes suffused with blood. Some parts were burnt to a cinder, whilst others were but little affected by the fire. This case is in some respects similar to that of *Millet* (p. 718).

The advice of Liebig, in reference to the duties of medical men in cases of alleged death from burning, is deserving of the notice of medical witnesses:—'In cases of fire, when the investigation is extended to all those who had access to the place where it broke out, it often happens that the incendiary or the actual originator of the fire is discovered. Legal medicine, even if the theory of spontaneous combustion were true, which it is not, ought not to interfere in so simple a proceeding, justified as it is by experience, until all other probable causes of fire have been excluded. . . . The physician who is called in to give evidence in such cases can only say, if he act according to duty and conscience, in what state the body was found; whether the injuries from burning took place before or after death; whether death was caused by fire alone, or before the action of the fire, by other means, such as wounds, strangulation, or a blow on the head, &c. In no case is it permitted to him to explain anything he has not seen, by means which he has also not seen, or by a theory which he cannot understand.' (Op. cit. p. 311.)

Cases of alleged spontaneous combustion dependent on accident or homicide.—The following case occurred in France. The body of a man was found lying in bed, and in a state of combustion, by some persons who entered his bedroom in the morning. The chamber was filled with a dense smoke, and one of the witnesses asserted that he saw a small whitish flame playing around the body of the deceased, which receded from him as he approached. The clothes of the deceased and the coverings of the bed were almost entirely consumed; but the wood was only partially burnt. There were no ashes, and there was but a small quantity of vegetable charcoal: there was, however, a kind of mixed residue, altered by fire, and some pieces of animal charcoal, which had evidently been derived from the joints. The deceased was in the habit of carrying lucifer-matches in his waistcoat-pocket, and, according to his usual practice, he had had a hot brick placed at his feet when he went to bed the preceding evening. Two hours afterwards his son and daughter-in-law passed by the door of his room, but there was nothing which attracted their attention. It was only the following morning, early, that his grandson found his body in the state described. The deceased was 71 years of age. He was not fat, nor was he addicted to drunkenness. The temperature of the air was low; and there were no electrical manifestations. The son and his wife were suspected of having murdered the deceased, and afterwards burnt the body in order to conceal the traces of the crime. The body, which had been buried, was exhumed and examined. The partially burnt cravat was still around the neck, and part of a sleeve of a nightshirt was found. The hands, completely burnt, were also attached to the forearms by some carbonized tendons, which gave way on the slightest touch. The thighs were detached, so as to resemble a wilful mutilation, but for the discovery of animal charcoal about them. From these facts, Masson considered it impossible to ascribe the changes to the effect of accidental burning; and as they could only be produced by violent combustion continuing for some time, he drew the inference that the burning must have resulted from some inherent cause in the person, probably roused into activity by the hot brick placed at the feet of the deceased. The burning once commenced, would be easily supported by the state of the tissues. Hence the case was, in his opinion, to be referred to the class of spontaneous combustions. Orfila is reported to have coincided with Masson in this opinion, and the accused were

acquitted. ('Gaz. Méd.' Sept. 4, 1847.) With respect to the medical opinion, that a long-continued action of a strong heat was necessary in order to produce the effects observed, it may be remarked that it is not possible to assign the degree of the duration of the heat which is required to produce particular effects on the body. It appears probable that Masson had underrated the effects which are liable to follow from an accidental ignition of the clothes.

In 1850 some German physicians advocated, in a case of murder, the hypothesis of spontaneous combustion. A trial took place at Darmstadt in 1850, in which a valet named *John Stauff* was charged with the murder of his mistress, the *Countess of Goerlitz*. This lady was found dead in her apartment; the dress on the upper part of the body was almost wholly consumed; the head exhibited the form of a nearly shapeless black mass, in which the mouth was imperfectly distinguishable, with the charred tongue protruding from it. The skin of the neck, as well as the skin and muscles of the face and upper part of the chest, were much blackened and charred. The joints of both arms were charred on their surfaces, and the blackened ends of the bones protruded. There were no marks of fire anywhere on the clothes beyond the margins of the burns on the body. A writing-desk near the body had been partially burnt, and the floor beneath and in front of the desk, over a space of a foot and a half, had been entirely consumed. The feet of a chair placed near the writing-desk were slightly charred. A folding-board and the drawers were also much burnt. The physician who was consulted could suggest no other explanation of the facts than that the body of the Countess must have taken fire *spontaneously*, while she was engaged in writing at her desk. He could not even admit that her cap or dress might have become, by some not uncommon accident among women, ignited by a candle; because, had this been the case, she would, in his opinion, have had time to escape or call for assistance. The other reasons assigned for the adoption of this hypothesis were, that deceased went to bed in good health, that there was a greasy black or sooty substance found about the room, and that the body exhaled an empyreumatic odour. It may be observed that when the room was first broken into, and the Countess was found dead, flames burst out simultaneously from the hangings, the writing-desk, and the floor beneath it, which required to be extinguished by water. The opinion thus given amounted to this, the Countess's body had undergone slow combustion until it reached a full red-heat; it then ignited the furniture around—the reverse of the process by which, according to experience, persons are usually burnt to death. The Countess was thus found dead in her chamber on June 13th, 1847. On Nov. 26th of that year, it was intimated to the Count that an inquest would be held; and the valet Stauff, having in the meantime made an attempt to poison his master, was then first suspected of having murdered the Countess—the death by burning having up to this time been treated as an accidental occurrence. The body, which had been buried, was not exhumed until Aug. 11th, 1848, *i.e.* fourteen months after death: it was subjected to a special examination, and the Hessian Medical College, to which the case was referred, came to the conclusion that the Countess had not died from spontaneous combustion. The case was subsequently referred to Liebig and Bischoff; and their report was issued in March, 1850, at which date the man Stauff was put on his trial. They found no difficulty in concluding that a murder had been perpetrated, and the body wilfully burnt *after death* for the purpose of concealing the crime. There was some doubt whether the deceased had died from strangulation, or from violence to the head. Stauff was convicted chiefly upon circumstantial evidence. He subsequently confessed that the countess had entered her room as he was in the act of committing

a robbery. A struggle took place; he seized her by the throat, strangled her, and afterwards placed the body in a chair, piling around it combustible articles of furniture. He set fire to these with the view of destroying the proofs of his crime. It will be observed that the tongue was found protruded, as it is in violent strangulation, and that in its charred state it retained the position given to it by the act of murder.

One of the supposed scientific difficulties in this case was, that the body *appeared* to have been so much consumed compared with the amount of combustibles near it. This, however, seems to have been a mere conjecture. Another point which excited notice was, that the clothes were not consumed beyond the margins of the burns on the body—a circumstance which has been regarded as a special characteristic of spontaneous combustion, although it simply shows that when the clothing burns without producing much flame, the burns on the body are defined by the clothing actually consumed. The dark greasy matter on the furniture and the empyreumatic smell are also conditions which in this case were proved to be the results of a homicidal attempt to conceal a murder, and they were not, in any sense, indications of spontaneous combustion. They are always produced when there is a slow or smothered combustion of animal matter. (See, for a further report of this case, a paper by Tardieu, 'Ann. d'Hyg.' 1850, 2, 191, 363; and 1851, 1, 99; also Ogston, in 'Med. Gaz.' vol. 46, pp. 889 and 948.

A recent case of note in reference to this subject is that reported by Bertholle ('L'Union Méd.' Nov. 19, 1870); and by Strohl ('Ann. d'Hyg.' 1871, 1, 228). A woman addicted to drinking alcoholic liquids to excess, including *absinthe*, having drunk largely, went into her bedroom, and two hours afterwards, her husband, in attempting to enter the room, found the door so hot that it gave him the sensation of burning. An alarm of fire was given, and the room was entered by a window. There was a nauseous odour and a sense of suffocation on entering. The dead body of the woman was found on the floor between the bed and the hearth—the head being partly under the bed, and the legs across the hearth. There was no fire in the grate, and the trap was down. The floor on which the body was lying was more carbonized than burnt, and on it were found fragments of bones —some of the ribs, a hand, and incinerated remains. The head, which was swollen and of a violet-red colour, presented no mark of burning. The hair was not burnt. The upper part of the trunk was not burnt, but was covered with a black powder, the residue of the burnt clothing. The left arm had disappeared from the shoulder. The right arm had lost the hand, which was disarticulated at the wrist. The elbow joint was exposed, but the muscles of the arms were not destroyed. The left side and front of the chest were widely open, but there was no trace of the thoracic viscera. The lower ribs were separated. The walls of the abdomen were gone,—its cavity was empty, the viscera being reduced to a greasy black soot adhering to the vertebræ. The bones of the spine and pelvis remained, but the muscles and fasciæ had disappeared. The lower limbs from the thighs downwards were entire, the skin being covered with a black powder—but there were no blisters or vesications on these parts.

It is further stated that, although there was no visible source of fire or ignition in the room—and the bed and its furniture had escaped burning —the floor was still burning, but without flame, when the room was entered. No combustible in the shape of candle, matches, or fuel was found near the body. No noise or cry of alarm was heard, and the people living opposite saw no light or flames in the chamber or smoke issuing from it.

The complete destruction of the clothes by burning in this case shows that the fire was *ab extra*, and although no sources of combustion were found in the room, still this does not preclude the possibility of an accident

from this source. The woman may have had matches about her, and in her intoxicated state an accident may have easily occurred, by which her clothes were ignited and led to the combustion of the body as well as of the matches. This, at any rate, is more probable than the theory that the viscera of her body should have spontaneously acquired such a temperature as to lead to the complete destruction of her clothing. A case like this proves nothing in favour of the theory of spontaneous combustion. It is similar in its details to that of *Mrs. Pulley*, a case of murder with an attempt at concealment (p. 721). The unequal burning of the body was observed in both cases.

It could scarcely be supposed that the question of the spontaneous combustion of the *dead* human body would present itself for consideration, yet the following case bears upon this point. In 1865, a gentleman, æt. 30, died in the south of England of typhoid fever. It was noticed that there was great tympanitis. His remains were taken to Garston and interred in the family vault in the parish church. The body was in a shell, enclosed in a patent metallic coffin and an oaken one. About thirteen months after the burial a foul smell was perceived in the church, and it was found to issue from a crevice in the floor immediately over the vault in which the coffins had been placed. The vault was opened, and it was then found that the coffins in which the body was placed had burst opposite to the breast, and liquid matter was oozing from the body. The coffins were filled with sawdust, and the vault was left exposed for the night. The gas, which had been lighted in the church during the exploration, was turned off at the meter, and, as it was supposed, all was left quite safely. The next morning, when the workmen entered, the vault was found to be on fire, burning, as the sexton said, with a blueish flame and a most offensive smell. By throwing water and earth on the burning mass the flames were extinguished, and it was then found that the wooden coffin of the deceased and his remains were entirely consumed, with the exception of the silver coffin-plate and a portion of the intestines. Another coffin in the same vault, at a short distance from it, was slightly burnt at the side.

For such a complete destruction of the body to have taken place, the fire must have been going on for some hours before discovery. None of the woodwork or any other part of the church was injured, and the place was found secure as on the previous night. Many persons set it down to spontaneous combustion, but it was found that one of the workmen had been smoking in the vault, and might have carelessly thrown down the lighted paper which he used. This may have kindled the cloth covering of the coffin and sawdust, and assuming that the gases issuing from the body were of a combustible nature, like those described as issuing from dead bodies advanced in putrefaction (pp. 111, 112), the results might be accounted for without reference to the theory of spontaneous combustion. The only inexplicable fact of the case is, that the bones are stated to have entirely disappeared, as these are chiefly formed of incombustible mineral matter—calcium phosphate and carbonate. Dead bodies may, as it has been elsewhere stated (pp. 51, 96), emit light and heat, and evolve inflammable gases. But these gases require a full red-heat, in order that they should burn and produce the usual effects of burning. In this case the sawdust no doubt acted as fuel, and thus led to the complete burning of the body.

Time required for the burning of a dead body.—It may be a medico-legal question whether, on discovering a body much burnt, it could be determined from its appearance how long a period it would require to produce the amount of destruction observed. An answer to such a question may be necessary, in order to connect a person with the perpetration of an alleged crime, but the question does not admit of a precise answer. A conjecture

only can be formed from the facts proved in each particular case. The human body contains a large proportion of water (72 per cent.); this gives to the soft structures a power of resisting combustion. At the same time there is a quantity of fat in the body, varying in different parts, but amounting to an average of about five per cent. The fat or oil tends to increase its combustibility, and this is still further increased if it is placed on any combustible article which can imbibe it, such as a rug or a deal floor. The nature of the dress will also make a difference. Under a strong and active flame, which might subsequently burn out before the discovery of the body, there would be a degree of destruction in half-an-hour which a more slow and smothered combustion would not effect in several hours. In the case of the *Countess of Goerlitz* (p. 723), it was proved that she had retired to her room between three and four o'clock in the afternoon: the Count returned at seven o'clock, and knocked at the door of her anteroom, but receiving no answer he again went out. Had the burning of the body already commenced, he would have perceived it by the smell or by the appearance of smoke. He returned again at nine o'clock; and during this second absence, covering an interval of *two hours*, a bright light had been seen at one of the windows, and a thick smoke issued from one of the chimneys. There is a little discrepancy as to the time, but taking the maximum, the amount of destruction described in this case must have occupied less than two hours, and probably not more than one hour.

This question actually arose in *Reg.* v. *Hatto* (Aylesbury Lent Ass. 1854). The deceased, a female, was found dead in her room, and her body much burnt. She was last known to be living at about a quarter-past eight o'clock in the evening, and her body was found, still smouldering with fire, on the floor of the room, at about a quarter-past eleven o'clock. The only persons known to have been in the house were the prisoner and the deceased. The prisoner pretended that he knew nothing of the circumstances attending her death, and endeavoured to make it appear that robbers might have broken into the house and committed the murder at some period of the three hours during which he alleged that he was asleep in bed. It was suggested, in order to exclude this hypothesis—which, however, was sufficiently excluded by other facts—that the act of murder, with the attendant burning, must have occupied the whole of the time intervening between the period at which deceased was last seen living, and the period at which her body was found. The medical man who examined the deceased found that 'both knees were consumed by fire, and the thighs, as well as the private parts, were burnt to a cinder—leaving the shafts of the thigh-bones exposed and charred for several inches. Between the thighs and the feet, the floor underneath had been burnt away, and the leg-bones had fallen through the floor, leaving the feet unburnt on the floor.' He expressed an opinion that it would take from two and a half to three hours in order to consume the body to this degree; thus covering the whole interval during which deceased and prisoner were in the house together. It should be stated that the clothes of the deceased were much burnt, and that beneath the body there was a hempen mat, so combustible, owing to the melted human fat with which it was impregnated, that when ignited it burnt like a link. The guilt of the prisoner was made sufficiently evident from other circumstances proved in the case, which were quite inconsistent with his innocence. It is obvious that an opinion on such a subject must be in all cases conjectural, since the effects, *cæteris paribus*, depend as much on the intensity as on the duration of the heat. It was indeed just as probable, medically speaking, that, with a large body of flame, the amount of injury met with might have been produced in an hour as in three hours. The confession of the prisoner, subse-

quently made, shows that the burning observed must have taken p
less than two hours, and perhaps within an hour and a half. The (
case (p. 723), and some others, prove that a short period may
for a large amount of destruction, and that, judging by what re
the combustible materials consumed appear to bear only a small proj
to the parts of the body burnt. This may be accounted for by the
volume of flame produced during the combustion of articles of
clothing.

END OF VOL. I.

LONDON: PRINTED BY WILLIAM CLOWES AND SONS, LIMITED,
STAMFORD STREET AND CHARING CROSS.







